




DATE: 2024-02-28 1:15 PM




GARBAGE COMPACTOR SLAB DETAIL




TYPICAL DETAIL - CAST-IN-PLACE RETAINING WALL CONNECTION TO HOSPITAL STRUCTURE




TYPICAL OPTIONAL CONSTRUCTION JOINT




JOINT CONTROL DETAIL




SECTION A-A - HEARSE PARKING SLAB




RAILING CONNECTION DETAIL - PRE-CAST BLOCK WALLS




PLAN - HEARSE PARKING SLAB




ELEVATION TYPICAL BARRIER WALL REINFORCEMENT DETAILS




SECTION TYPICAL BARRIER WALL REINFORCEMENT DETAILS




RAILINGS DETAILS - PRE-CAST BLOCK WALLS




RAILINGS DETAILS - PRE-CAST BLOCK WALLS




VERTICAL CONSTRUCTION JOINT DETAIL FOR RETAINING WALLS



VERTICAL EXPANSION JOINT DETAIL FOR RETAINING WALLS



TYPICAL WATERPROOFING FOR CAST-IN-PLACE CONCRETE RETAINING WALLS



RAILINGS DETAILS - CAST-IN-PLACE CONCRETE WALLS

- HEARSE SLAB NOTES:**
- SEE MECHANICAL DRAWINGS FOR SLAB HEATING ELEMENT DETAILS.
 - CONCRETE TO CLASS C EXPOSURE, 38MPa @ 28 DAYS.
 - SEE STRUCTURAL BUILDING DRAWINGS FOR CANOPY STRUCTURE DETAILS.
 - INSULATION TO BE EXTRUDED EXPANDED POLYSTYRENE GRADE A GRADE C TO BE USED BELOW THE CONCRETE SLAB.
 - CHAMFER ALL CONCRETE EDGES 30MM.
 - MANHOLE STRUCTURE WILL BE INSTALLED BEFORE CONCRETE SLAB STRUCTURE.
 - CUT FRENCH LONGITUDINAL AND TRANSVERSE REINFORCEMENT 100MM AWAY FROM MANHOLE STRUCTURE AND INSTALL ADDITIONAL REINFORCING STEEL AROUND MANHOLE.
- GENERAL RAILING NOTES:**
- DESIGN LOAD: INTERIOR BUILDING CODE (R90), 2004 AND NATIONAL BUILDING CODE (NBC) 2000.
 - THE SIZES OF MEMBERS TO BE AS SPECIFIED ANY REDUCTION IN MEMBER SIZES WILL NOT BE PERMITTED, REGARDLESS OF WHETHER A REDUCTION IN MEMBER SIZE IS ACCOMPANIED BY ENGINEERED SUBMISSION.
 - PROPRIETARY DESIGN OF RAILINGS WILL BE CONSIDERED, PROVIDED THAT THE MEMBER SIZES DESIGNATED IN CONTRACT ARE MAINTAINED, OR IMPROVED.
 - ALL WELDING WORK SHALL BE CARRIED OUT BY QUALIFIED WELDERS.
- PRE-CAST BLOCK WALL RAILING NOTES:**
- THE RAILING SUPPLIER WILL SET THE SPACING BETWEEN POSTS, WHICH MUST BE SHOWN ON SHOP DRAWINGS AND DETERMINED BY THE SECURITY OF THE PRE-CAST BLOCK WALLS. ENDING POSTS OR CHAMFER ARE POSITIONED AWAY FROM JOINTS BETWEEN PRE-CAST CONCRETE BLOCKS.
 - THE RAILING DETAILERS ARE TO COORDINATE POST SPACING SELECTION WITH THE RETAINING WALL DESIGNER.
 - ALL GRADE 300M STEEL, AS WELL AS ALL RAILING COMPONENTS AND ADAPTERS, SHALL BE HOT-DIP GALVANIZED IN ACCORDANCE WITH THE LATEST EDITION OF ASTM A123 FOLLOWING FABRICATION.
 - ALL HSS MEMBERS TO BE CAPPED AND VENTED.
 - USE STAINLESS STEEL BOLTS TO CONNECT POSTS TO RAILING ADAPTERS.
 - USE SENSITIVE NON-SHRINK GROUT FROM THE MTO DDM LIST OF APPROVED GROUTS FOR BEARINGS TO SECURE THE ADAPTERS IN POSITION.
 - INSTALL ADAPTERS AND RAILING PLUM, LEVEL AND BRACED. RECEIVE CONTRACT ADMINISTRATOR APPROVAL BEFORE GROUTING.
 - KEEP BRACING IN PLACE FOR 48 HOURS AFTER GROUT SETS, THEN REMOVE SUPPORTS CAREFULLY.
 - APPLY DRY PACK, NON-SHRINK GROUT MATERIAL SUITABLE FOR HAND APPLICATION BENEATH THE ADAPTER PLATES.
 - PROVIDE A SAMPLE WITH TWO ADAPTERS AND ONE RAILING PANEL INSTALLED DRY IN A SETUP SIMILAR TO THE DESIGN.
 - RETAINING WALL #14 AT THE LOADING DOCK (A CAST-IN-PLACE WALL) TO HAVE THE SAME RAILING AS OTHER PRE-CAST BLOCK WALLS. THE RAILING WILL BE MOUNTED ON TOP WITH FOUR HSS 16T22 SS STAINLESS STEEL ANCHORS, EMBEDDED 100MM.
- COATING NOTES FOR PRE-CAST BLOCK WALL RAILING:**
- RAILING SECTIONS SHALL BE HOT-DIP GALVANIZED AND COATED IMMEDIATELY FOLLOWING FABRICATION.
 - THE RAILING SUPPLIER TO PROVIDE ALL REQUIRED COMPONENTS FOR SPLICING OF RAILING IN FIELD.
 - THE GALVANIZING TO COMPLY WITH CANADA CAN 11.
 - THE ABRASIVE BLAST MEDIA FOR SWEEP-BLASTING OF GALVANIZED SURFACE FOR COATING SHALL BE OF HARSHNESS THAT THE GALVANIZING IS NOT DAMAGED AND THICKNESS OF GALVANIZING IS NOT REDUCED.
 - ABRASIVE BLAST CLEAN GALVANIZED SURFACE AND PREPARE AND REPAIR GALVANIZED SURFACE FOR COATING AS PER ASTM D668.
 - A COMPLETE, WRITTEN PROCEDURE DETAILED GALVANIZING, PREPARATION FOR COATING, AND COATING APPLICATION SHALL BE SUBMITTED FOR ACCEPTANCE.
 - THE COATING OVER GALVANIZING SHALL BE:
- COATING TABLE:**
- | PRODUCTS LISTED ON USM #9 2016 ARE PRE-APPROVED. ALTERNATIVE PRODUCTS ARE SUBJECT TO APPROVAL. |
|--------------------------------------------------------------------------------------------------------------|
| MODIFIED ALUMINUM EPOXY MASTIC FOLLOWED BY ALPHATIC POLYURETHANE AND CLEAR SEALER. |
| HIGH BUILD EPDM FOLLOWED BY ALPHATIC POLYURETHANE. |
| THICKNESS OF EACH COAT AS PER MTO DSM #9.20.10. |
| THICKNESS OF SEALER AS REQUIRED TO OBTAIN 100% COVERAGE AND AS PER COATING MATERIAL SUPPLIER RECOMMENDATION. |
| THE EXPOSED SECTIONS OF ANCHOR BOLTS TO BE HAND COATED FOLLOWING RAILING INSTALLATION. |
- STAINLESS STEEL RAILING NOTES:**
- STAINLESS STEEL GRADE SHALL BE EITHER 304 OR 316.
 - RAILING APPEARANCE VALUE OF "HIGH" - NO VISIBLE BLEMSHES OR IMPERFECTIONS.
 - STAINLESS STEEL TO HAVE A BRUSHED FINISH.
 - A CONCRETE BACK-UP OF RAILING INSTALLATION IS REQUIRED. MOCK-UP ELEMENTS, ONCE APPROVED, MAY BE INCORPORATED INTO THE WORK.
 - ALL ANCHORS FOR RAILINGS TO BE STAINLESS STEEL.

PROJECT: THE OTTAWA HOSPITAL NEW CAMPUS DEVELOPMENT - PHASE 4 MAIN HOSPITAL BUILDING
900 CARLING AVE, OTTAWA, ONTARIO

CLIENT: The Ottawa Hospital | Hôpital d'Ottawa

CONSTRUCTION: PCL | EllisDon

CLIENT PROJECT NO: 1070002

KEY PLAN: TRUE NORTH | PROJECT NORTH

REVISIONS:

04	SITE PLAN CONTROL RESUBMISSION	2024-01-12
03	90% CD SUBMISSION	2023-09-19
02	SITE PLAN CONTROL RESUBMISSION	2023-06-05
01	65% CD SUBMISSION	2023-06-05
NO	ISSUED	DATE

DRAWING STATUS: NOT FOR CONSTRUCTION

DISCREPANCIES MUST BE REPORTED IMMEDIATELY TO THE ARCHITECT BEFORE PROCEEDING. ONLY FIGURED DIMENSIONS ARE TO BE USED. CONTRACTORS MUST CHECK ALL DIMENSIONS ON SITE. THIS DRAWING IS PROTECTED BY COPYRIGHT. ALL DIMENSIONS ARE SHOWN IN METRIC.

AUTHOR: WSP

PROJECT TEAM: DESIGN BUILDER: POLICED, A JOINT VENTURE
ARCHITECTURAL: PARKIN ARCHITECTS LIMITED, JODAN LAMARIE PRATTE ARCHITECTS, ADAMSON ASSOCIATES ARCHITECTS, 188 ARCHITECTS OTTAWA INC.
STRUCTURAL: STERNECHON ENGINEERING LTD., BOUYALLETTE PARISZAL INC.
MECHANICAL: H1 ANGLUS & ASSOCIATES LTD., CROSSLEY ENGINEERING LTD.
ELECTRICAL: MULVEY & BANANI INTERNATIONAL INC.
CIVIL: WSP CANADA INC.
LANDSCAPE: VERDEDESIGN INC., PFP LANDSCAPE ARCHITECTURE
BUILDING CODE: UMDO BUILDING CODE CONSULTANTS LTD.

AUTHOR PROJECT NO: CA0027758.0-51

STAMP: [Blank Stamp Area]

DRAWING TITLE: DETAILS CAST-IN-PLACE WALLS

DRAWN: K. MARTIN | **CHECKED:** M. THOM
SCALE: 47' x 67' AS SHOWN | **DATE:** 2024-02-28

GRAPHIC SCALE: 1:250

DRAWING NO.: C7-408 | **REV. NO.:** 04