



LRL

ENGINEERING | INGÉNIERIE

**Site Servicing and
Stormwater Management Report
for Site Plan Control Application**

**ESP Pierre-de-Blois
Auditorium Addition
1310 Chapman Mills Dr.,
Ottawa, Ontario**

Prepared for

Conseil des écoles publiques de l'Est de l'Ontario (CEPEO)

LRL File No.: 220512

March 19, 2026



TABLE OF CONTENTS

1	INTRODUCTION	3
2	SITE DESCRIPTION	3
3	SCOPE OF WORK.....	4
4	WATER SUPPLY AND FIRE PROTECTION.....	5
4.1	Existing Water Supply Services	5
4.2	Water Supply Demand	5
4.3	Fire Flow Requirements	6
4.4	Fire Hydrant Coverage & Aggregate Flow.....	7
4.5	Boundary Conditions	6
5	SANITARY DRAINAGE	8
5.1	Existing Sanitary Sewer Services	8
5.2	Sanitary Sewer Servicing Design	8
6	STORMWATER MANAGEMENT	9
6.1	Existing Stormwater Infrastructure	9
6.2	Proposed Management Concept	9
6.3	Design Criteria – Water Quantity	9
6.4	Stormwater Quantity Controls	10
6.4.1	<i>Rooftop Stormwater Management</i>	<i>10</i>
6.4.2	<i>Surface Stormwater Management.....</i>	<i>11</i>
7	EROSION AND SEDIMENT CONTROL	12
8	CONCLUSIONS	12
9	LIMITATIONS AND USE OF REPORT	13



LIST OF FIGURES

Figure 1 - Aerial view of the location of the proposed development (Google Earth).....4

APPENDICES

Appendix A	Domestic Water Demand and Fire Flow Calculations
Appendix B	Sanitary Sewer Calculation Sheet
Appendix C	Stormwater Management Design Sheets
Appendix D	Supporting Documents
Appendix E	Engineering Drawings



1 INTRODUCTION

LRL Associates Ltd. (LRL) has been retained by the Conseil des écoles publiques de L'Est de l'Ontario (CEPEO) to prepare a site servicing and stormwater management report in support of their site plan control application for a proposed new auditorium addition & site alterations to the existing Public High School, ESP Pierre-de-Blois, in Barrhaven.

This report aims to review the adequacy of the current site's water, sanitary and stormwater networks, and determine whether any changes / upgrades are required to accommodate the expected increase in demand & flow from the new addition & site changes.

This report is to be read in conjunction with the Site Servicing and Stormwater Management Report prepared for the initial school development, titled "Proposed New Public High School Barrhaven Center" prepared by LRL Engineering dated September 5th, 2019.

This report has been prepared in consideration of the survey carried out by Annis O'Sullivan Vollebakk Ltd. (AOV) in August 2017 and the master servicing study "Harmony Stage 1 Development for Minto Communités" prepared by J.L. Richards & Associates Limited and dated July 2017. Topographical data for the developed high school site has been pulled from high school development site grading as-builts, as prepared by LRL Engineering.

Should there be any discrepancies in the existing infrastructure, which may relate to the site servicing considerations, LRL should be advised in order to review the report recommendations. This report should be read in conjunction with the grading and drainage, site servicing, and stormwater management plans prepared by LRL.

2 SITE DESCRIPTION

The subject property is located within the urban boundary of the City of Ottawa, south of Strandherd Drive and west of Chapman Mills Drive, and has a total area of approximately 4.86 ha.

The site is currently occupied by the recently constructed Pierre-de-Blois High School, a three-storey slab-on-grade institutional building with an approximate footprint of 6,770 m². Site access is provided from Chapman Mills Drive. In addition to the school building, the site includes an internal access roadway, parking areas, playgrounds, a soccer field, and an area reserved for future portable classrooms. Prior to the development of the high school, the property consisted of vacant land.

Any site modifications associated with the proposed auditorium expansion will be designed and constructed by others in accordance with applicable municipal design criteria, while maintaining consistency with the master servicing design for the Harmony Stage 1 development, as



prepared by J.L. Richards & Associates Limited as part of the Harmony Stage 1 Development for Minto Communities, dated July 2017.




Figure 1 - Aerial view of the location of the proposed development (Google Earth)

3 SCOPE OF WORK

As per applicable guidelines, the scope of work includes the following:

Water services

- Calculate the anticipated domestic water demands under average and peak flow conditions, as well as the fire protection requirements, for the existing school and proposed addition.
- Review adequacy of the current on-site water distribution network based on new calculated water demand & fire flow.

Sanitary services

- Calculate the peak flow rates for the existing school and proposed addition.
- Review adequacy of the current on-site sanitary sewer based on new peak flow rates.



Stormwater management

- Calculate roof drain and storage requirements for the new auditorium addition, and determine feasibility of tying them to the existing on-site stormwater network
- Review adequacy of the current on-site stormwater network based on changes, including; pipe sizing, flow control, storage requirements and quality treatment based on new tributary drainage areas.

4 WATER SUPPLY AND FIRE PROTECTION

4.1 Existing Water Supply Services

Based on the civil drawing prepared for the school development, municipal as-builts and sewer and watermain mapping; it can be observed the current school building is serviced by an on-site 200mm dia. watermain. The watermain, branching off the north face of the school, follows the existing site parking lot and driveway to connect to the Chapman Mills Dr. 300mm diameter watermain, approximately 240m southeast of the Strandherd / Chapman Mills intersection.

There are currently four (4) municipal fire hydrants located within proximity to the site, along Chapman Mills Drive and within the residential subdivision east of the institutional lot. Two private fire hydrants have been installed on-site, branching off the private 200mm watermain to ensure compliance with OBC, placing a hydrant within 90m of the principal entrances, and within 45m of the building's Fire Department Connection. The hydrants are located just off the southwest corner, and the southwest corners, of the school.

Refer to C401 – Servicing Plan for the existing municipal infrastructure design.

4.2 Water Supply Demand

With the proposed building expansion comes an expected increase in water demand and fire protection requirements. Domestic water demand and fire protection demand requirements for the proposed building, including the new addition, are to be calculated to ensure adequacy of the existing on-site water distribution network.

The institutional water demand, based on the anticipated population, was determined using Table 4.2 of the City of Ottawa *Water Distribution Design Guidelines*. The water supply requirements for the institutional development have been calculated using the following formulas:



Where:

q = average water consumption (L/capita/day)

P = design population (# of students)

M = Peak factor

The existing building including the auditorium expansion is expected to have a student population of 700. *Table 4.2 of the City of Ottawa Water Distribution Design Guidelines* was used to determine the unit rate and peaking factors of the institutional space. A water consumption rate of **70L/student/day**, a Maximum Daily Demand Factor of **1.5** and a Maximum Hourly Demand Factor of **1.8** were used to perform the water demand calculations.

Using the peak factors, the anticipated institutional demands were calculated as follows:

- Average daily domestic water demand is **0.81 L/s**,
- Maximum daily demand is **1.22 L/s**, and
- Maximum hourly demand is **2.19 L/s**.

Per City of Ottawa Technical Bulletin ISTB-2021-03, 4.3.1 developments with a basic day demand greater than 50 m³/day (0.57L/s) shall be connect with a minimum of two water service connections, separated by an isolation valve to avoid a vulnerable service area. The addition of the auditorium expansion creates daily demand greater than the 0.57L/s requiring the site to install a second watermain connection point with the installation of an isolation valve.

Detailed water demand calculations can be found in Appendix A.

4.3 Fire Flow Requirements

The estimated fire flow for the proposed buildings was calculated in accordance with *ISTB-2018-02*, evaluated in accordance with the Fire Underwriters Survey (FUS) design methodology. The following parameters were provided by the Architect:

- Type of construction – Non-combustible construction (Type II)
- Occupancy type – Limited Combustible
- Sprinkler Protection – None

The estimated fire flow demand was estimated to be **14,000 L/min (233.3 L/s)**, see Appendix A for calculation details.

4.4 Boundary Conditions

The City of Ottawa was contacted to obtain boundary conditions associated with the estimated water demand and fire flow calculations, as indicated in the boundary request correspondence included in **Appendix A**.



Table 1 below summarizes boundary conditions for the proposed development.

Table 1: Summary of Boundary Conditions

Design Parameter	Anticipated Demand (L/s)	Boundary Conditions @ Chapman Mills Dr	*Residual Pressure
		(m H2O)	(psi)
Average Daily Demand	0.81	153.7	84.7
Max Day + Fire Flow (per FUS)	1.22 + 233.3	141.7	67.6
Peak Hour	2.19	144.9	72.2
*Ground elevation assumed at 94.20m for the proposed connection at Chapman Mills Dr WM			

As indicated in red in Table 2, residual pressure within the Maximum HGL / Average Daily Demand scenario will exceed the required pressure range stated in the City of Ottawa Design Guidelines – Water Distribution (Section 4.2.2). Refer to **Appendix C** for Boundary Conditions.

As on-site pipe pressure losses do not reduce pressure sufficiently to fall within the acceptable range, a pressure reducing valve will need to be installed immediately downstream of the isolation valve in the building. The design and implementation of the pressure reducing valve to be performed by the mechanical engineer, and included within the buildings plumbing design.

Considering the calculated peak water demands and fire flow of the existing building & auditorium, with the addition of the pressure reducing valve, the existing private watermain is considered adequate to accommodate both existing and proposed water and fire flow demands.

4.5 Fire Hydrant Coverage & Aggregate Flow

There are four (4) existing fire hydrants in proximity to the proposed lot, and two (2) private hydrants within the site, that are available to contribute to the required fire flow demands.

Table 2 below summarizes the aggregate fire flow of the contributing hydrants in proximity to the proposed development, and private hydrants based on Table 18.5.4.3 of *ISTB-2018-02*.

Table 2: Fire Protection Summary Table

	Max. Fire Flow Demand (L/min)	Fire Hydrants(s) within 76m	Fire Hydrant(s) within 152m	Fire Hydrant(s) within 305m	Available Combined Fire Flow* (L/min)
Existing Development + Addition	13,000	3	3	0	(3 x 5678) + (3 x 3785) = 28,389



*assuming residual pressure of minimum 20 psi (139.9 kPa)

The total available fire flow from contributing hydrants is equal to **28,389 L/min**, which is sufficient to provide adequate fire flow for the proposed development.

As the previously installed southwest fire hydrant falls within a 45m radius of the new auditorium entrance, and sufficient aggregate flow is provided by nearby fire hydrants, and the proposed southwest private fire hydrant, no changes are required to the existing fire protection network.

5 SANITARY DRAINAGE

5.1 Existing Sanitary Sewer Services

Based on the civil drawing prepared for the school development, municipal as-builts and sewer and watermain mapping; it can be observed the current school building is serviced by an on-site 250mm dia. sanitary sewer. The sanitary sewer, branching off the east face of the school, follows the existing site parking lot and driveway to connect to a sanitary manhole within the 900mm diameter sanitary sewer located on Chapman Mills Dr., approximately 240m southeast of the Strandherd / Chapman Mills intersection.

5.2 Sanitary Sewer Servicing Design

The peak design sanitary flow for the existing building and the proposed addition was calculated in accordance with Sections 4.4.1.2 (Institutional Flows), 4.4.1.4 (Extraneous Flows), and Appendix 4-A of the City of Ottawa Sewer Design Guidelines. The parameters used to estimate the anticipated institutional sanitary flows include a total site area of 4.86 ha, an institutional peak flow rate of 28,000 L/day, an institutional peak factor of 1.5, and an extraneous flow allowance of 0.33 L/s/ha. Based on these parameters, the total anticipated wet weather sanitary flow was estimated to be **3.96 L/s**.

Table 2: Sanitary Sewer Design Criteria

Design Parameter	Value
Manning roughness coefficient (n)	0.013
Minimum velocity (full)	0.6 m/s
Maximum velocity (full)	3.0 m/s

The existing on-site sanitary sewer consists of a 250 mm diameter pipe with an approximate total length of 120 m and a minimum longitudinal slope of 1.0%. The flow capacity of the existing sewer was calculated to be **59.47 L/s**, with a corresponding flow velocity of **1.21 m/s**. As the anticipated sanitary flow is well below the calculated pipe capacity and the flow velocity falls within the allowable range specified in the City of Ottawa Sewer Design Guidelines, the existing private sanitary sewer is considered adequate to accommodate both existing and proposed sanitary design flows.



Refer to Appendix B for the site sanitary sewer design calculations.

6 STORMWATER MANAGEMENT

6.1 Existing Stormwater Infrastructure

Based on the 2019 civil drawing prepared for the school development, municipal as-builts and sewer and watermain mapping; it can be observed that a private stormwater network had been developed to services the current school building and site. Drainage from the site is captured by a series of roof drains, catch basins, catch basin manholes and perforated subdrains which conveys the stormwater to the existing 1,350mm diameter storm sewer on Chapman Mills Drive.

Stormwater quantity flow control is provided via flow-control roof drains on the existing school rooftop, an undersized 900mm diameter pipe at the site stormwater network outlet, and storage requirements are accommodated via an on-site infiltration gallery.

A Stormwater Management Facility Pond design by J.L. Richards & Associates Limited is located southeast of the subject site at the downstream end of Minto Harmony Community and provides enhanced protection, 80% Total Suspended Solids removal. Hence, no stormwater quality management is required on the site for the addition.

6.2 Proposed Management Concept

The proposed scope of work includes the addition of an auditorium to the existing school, along with several minor modifications to site grading and drainage to accommodate the addition and associated site improvements. Five new roof drains and corresponding roof ponding areas are proposed for the new addition.

Stormwater tributary and catchment areas will be revised to reflect the proposed site changes. As a result of these modifications, the site stormwater management design—including the storm sewer network sizing, quantity control measures, and storage requirements—will be reviewed to confirm its adequacy under the proposed conditions.

6.3 Design Criteria – Water Quantity

Proposed development stormwater management quantity control will remain as constructed following the same criteria as the previous development. All storm events up to and including the 100-year event will continue to be controlled to the 5-year pre-development level. The site major overland flow route has been designed to ensure that storm events beyond the 100-year design storm can be safely conveyed overland towards the Chapman Mills Drive right-of-way. The minor system (storm sewer) within the site is sized to convey the 5-year storm event flows from the site to the municipal storm sewer on Chapman Mills Drive.



The Rational Method was used to calculate the runoff from the development. The Intensity-Duration-Frequency (IDF) curve formulas for the MacDonald-Cartier International Airport, in the city of Ottawa, were used to calculate the peak storm flows for the site.

This site is subject to stormwater management control where the allowable flow for the 5 and 100-year storm events are estimated at 1,055.8 L/s as per the design prepared by J.L. Richards & Associates Limited. The total allowable release rate will be restricted with an undersized pipe at the outlet that will throttle the total allowable release rate to **884L/s** as per J.L. Richards & Associates Limited design sheet. Refer to Appendix D - Supporting Documents.

6.4 Stormwater Quantity Controls

The existing stormwater management quantity control for this development have been accomplished through the use of:

- Existing undersized piping to throttle the flow rate,
- existing Zurn Control-Flo roof drains & roof top water storage,
- existing pipe, maintenance hole and infiltration gallery storage

The existing site storm sewer and stormwater management system are shown on drawing C401 – Servicing Plan within Appendix E of the report.

6.4.1 Rooftop Stormwater Management

In current conditions, the collected stormwater from the previously proposed catchment area WS-15 was regulated using thirty-five (35) one notch Zurn Control-Flo roof drains with a total maximum release rate of **15.11 L/s*m**. With the thirty-five (35) roof drains, the total anticipated flow from the roof drains was **63.47 L/s**, and rooftop ponding could reach a maximum volume of **213 m³** during the 100-year storm event. The controlled roof water was conveyed to storm manhole MH02 before outletting to Chapman Mills Drive.

The rooftop catchment area WS-15 was originally calculated using conservative assumptions to account for potential future additions to the school. With the footprint of the proposed auditorium now confirmed, the calculation has been revisited to reflect the actual footprint of the east addition rather than the previously assumed conservative area. As a result, the WS-15 catchment area has been reduced to 0.677 ha.

The addition of the auditorium necessitates new roof drains to adequately control and manage rooftop stormwater. The proposed rooftop drainage system includes five (5) additional one-notch Zurn Control-Flo roof drains, providing a combined maximum release rate of **15.11 L/s*m**. With a revised total of forty (40) roof drains across the site, the total anticipated discharge from the roof drainage system is **70.72 L/s**. Under the 100-year storm event, rooftop ponding is anticipated to reach a maximum storage volume of **186.04 m³**.



Controlled roof runoff is conveyed to storm manhole MH02, downstream of the flow control structure, prior to discharging to Chapman Mills Drive.

Detailed rooftop calculations can be found in Appendix C.

6.4.2 Surface Stormwater Management

With the proposed changes to the addition footprint and site, some minor changes have been made to the previous site design’s catchment area’s / watershed. Table 3, included below, provides a summary of the new catchment areas to be used for the purposes of this report.

Table 3: Post-Development Estimated Areas & Runoff Coefficients

WATERSHED	Total Area (ha)	Weighted Runoff Coefficient (C)
RWS-01 (controlled)	0.074	0.90
WS-02 (controlled)	0.104	0.28
WS-03 (controlled)	0.284	0.76
WS-04 (controlled)	0.228	0.90
RWS-05 (controlled)	0.133	0.36
RWS-06 (controlled)	0.111	0.30
RWS-07 (controlled)	0.175	0.26
WS-08 (controlled)	0.186	0.75
WS-09 (controlled)	0.130	0.88
RWS-10 (controlled)	1.001	0.25
RWS-11 (controlled)	0.942	0.31
WS-12 (controlled)	0.333	0.50
RWS-13 (controlled)	0.325	0.34
WS-14 (controlled)	0.147	0.76
CA-15 (uncontrolled)	0.677	0.90
TOTAL	4.850	0.50

The surface currently consists of parking and driving area, landscaped area and playground area. Runoff from these catchment areas will be captured through a number of catchbasins and subdrains before being directed to the existing 825mm outlet on Chapman Mills Drive and controlled with the undersized 825mm diameter reinforced concrete pipe. The 825mm pipe is installed at a 0.29% slope, with a full capacity / allowable release rate of **769 L/s**.

In order to control the 100-year storm event with the new catchment areas, while still utilizing the existing flow control system, **253.20m³** of on-site storage will be required.

Storage is currently being provided by the underground pipes, structures and infiltration gallery. With the revisions to the catchment areas, the existing stormwater network systems will provide the following storage volumes;

- **115.84 m³** from on-site pipes and maintenance structures and



- **180.31** m³ from the infiltration gallery.

As the available storage greatly exceeds the required, the existing stormwater management network is sufficient to accommodate the proposed changes in surface runoff, and will not require any modifications for the proposed works.

Refer to C401 – Servicing Plan and Appendix C for stormwater management design details.

7 EROSION AND SEDIMENT CONTROL

During the construction, erosion and sediment controls will be required primarily via a sediment control fence to be erected along the perimeter of the site where runoff has the potential of leaving the site. Inlet sediment control devices are also to be provided in any catchbasin and/or manholes on and around the site that may be impacted by the site construction activities. Construction and maintenance requirements for erosion and sediment controls are to comply with Ontario Provincial Standard Specification OPSS 577. Refer to LRL drawing C101 – Erosion and Sediment Control Plan for details.

8 CONCLUSIONS

In accordance with this report objectives, the analyses for the proposed development can be summarized as follows:

Water Service

- The anticipated average daily domestic water demand is **0.81 L/s**, maximum daily demand is **1.22 L/s**, and maximum hourly demand is **2.19 L/s**. This only represents a minor increase in domestic water demand from the existing school.
- With the expansion the basic day demand is greater than 50m³/day creating a vulnerable service area and therefore requiring a second water service connection.
- The required fire flow was calculated at **233.3 L/s** using the FUS method, same as it was for the existing school.
- Residual site pressures are calculated to be higher than the required 80psi and therefore a pressure reducing valve will be installed.
- Based on the expected water demands, fire flow and fire hydrant layout, it has been concluded the existing on-site watermain is adequate to accommodate the new addition.

Sanitary Service

- The anticipated sanitary flow from the proposed development is **3.96 L/s**.
- Based on the anticipated peak sanitary flow, it has been concluded the existing on-site sanitary sewer will have more than adequate to accommodate the additions flows.

Stormwater Management



- 5 new roof drains will be added to the auditorium rooftop, increasing total rooftop discharge to **70.72 L/s**, and providing a maximum rooftop storage of **186.04 m³**.
- Some watersheds / catchment areas have been revised to accommodate the new building addition and minor site changes. It has been determined that the current stormwater network has adequate storage & pipe capacity to accommodate the change in catchment runoffs and rooftop discharge, all while keeping the existing flow control system.

9 LIMITATIONS AND USE OF REPORT

The report conclusions are applicable only to this project described in this report. Any changes may require a review by LRL Associates Ltd. to insure compatibility with the recommendations contained in this report. We trust the information presented meets your current requirements. Please do not hesitate to contact us should you have any questions or concerns.

Prepared by:

LRL Associates Ltd.



Kyle Herold
Civil Project Manager

Kelly Paradis, PEng, PMP
Senior Manager of Civil Engineering



APPENDIX A

Domestic Water Demand and Fire Flow Calculations & Boundary Conditions



Water Supply Calculations

LRL File No. : 220512-03

Project: Auditorium Addition - ESP Pierre-de-Blois

Location: 1310 Chapman Mills Dr, Ottawa

Date: 2026-03-19

Designed: K. Herold

Checked: K. Paradis

Dwg Reference: C401

Water Demand based on the City of Ottawa Design Guidelines-Water Distribution, 2010

Institutional / Commercial / Industrial Demand

Property Type	Unit Rate (L/student/d)	Student Capacity	Demand (L/d)
Institutional	70	1000	70000

Average Day Demand	70,000 L/d	0.810 L/s
Maximum Day Factor	1.5	(Design Guidelines-Water Distribution Table 4.2)
Maximum Daily Demand	105,000 L/d	1.215 L/s
Peak Hour Factor	1.8	(Design Guidelines-Water Distribution Table 4.2)
Maximum Hour Demand	189,000 L/d	2.188 L/s

TOTAL DEMAND			
Average Day Demand	70,000 L/d	0.81 L/s	
Maximum Daily Demand	105,000 L/d	1.22 L/s	
Maximum Hour Demand	189,000 L/d	2.19 L/s	

Water Service Pipe Sizing

$$Q = VA$$

Where: V = velocity (m/s)

A = area of pipe (m²)

Q = flow rate (L/s)

Assuming a maximum velocity of 1.8m/s, the diameter of pipe is calculated as:

$$\begin{aligned} \text{Minimum pipe diameter (d)} &= (4Q/\pi V)^{1/2} \\ &= 0.039 \text{ m} \\ &= 39 \text{ mm} \end{aligned}$$

$$\begin{aligned} \text{Proposed pipe diameter (d)} &= 50 \text{ mm} \\ &= 2 \text{ Inches} \end{aligned}$$



Fire Flow Calculations

LRL File No. 220512-03

Project: Auditorium Addition - ESP Pierre-de-Blois

Location: 1310 Chapman Mills Dr, Ottawa

Date: March 19, 2026

Method: Fire Underwriter's Survey (FUS)

Prepared by: K. Herold

Step	Task	Term	Options	Multiplier	Choose:	Value	Unit	Fire Flow
Construction Coefficient (C)								
1	Choose frame used for building	Coefficient C related to the type of construction	Wood Frame Construction (Type V)	1.5	Noncombustible Construction (Type II)	0.8		
			Mass Timber Construction (Type IV-A)	0.8				
			Mass Timber Construction (Type IV-B)	0.9				
			Mass Timber Construction (Type IV-C)	1.0				
			Mass Timber Construction (Type IV-D)	1.5				
			Ordinary Construction (Type III)	1.0				
			Noncombustible Construction (Type II)	0.8				
			Fire Resistive Construction (Type I)	0.6				
Floor Area (A)								
2	Total Effective Floor Area					10,089	m ²	
3	Obtain fire flow before reductions	Required fire flow (rounded to nearest 1000)	Fire Flow = 220 x C x A ^{0.5}				L/min	18,000
Occupancy and Contents Adjustment								
4	Choose combustibility of contents	Occupancy hazard reduction or surcharge	Noncombustible	-25%	Limited combustible	-15%	L/min	15,300
			Limited combustible	-15%				
			Combustible	0%				
			Free burning	15%				
			Rapid burning	25%				
Sprinkler Protection								
5	Choose reduction for sprinklers	Sprinkler reduction	Automatic sprinkler protection designed & installed in accordance with NFPA 13	-30%	False	0%	L/min	13,770
			Water supply is standard for both the system and fire department hose lines	-10%	True	-10%		
			Fully supervised system	-10%	False	0%		
Exposure Adjustment								
6	Choose separation	Exposure distance	North side	>30m	0%	0%	L/min	13,770
			East side	>30m	0%			
			South side	>30m	0%			
			West side	>30m	0%			
Net Required Fire Flow								
7	Obtain fire flow and duration	Minimum required fire flow (rounded to nearest 1000)					L/min	14,000
		Minimum required fire flow					L/s	233.3
		Required duration of fire flow					hr	3.0



Pipe Pressure Losses Calculations

LRL File No. 220512-03

Project Auditorium Addition - ESP Pierre-de-Blois

Location: 1310 Chapman Mills Dr, Ottawa

Date 2026-03-19

Designed: K. Herold

Piezometric Head Equation (Derived from Bernoulli's Equation)

$$h = \frac{p}{\gamma} + z$$

Where:

h = HGL (m)

p = Pressure (Pa)

γ = Specific weight (N/m³) =

9810

z = Ground Elevation (m) =

94.2

Water Pressure on Huron Street			
HGL (m)		Pressure	
		kPa	psi
Minimum =	144.9	497.37	72.14
Maximum =	153.7	583.70	84.66
Max. Day + Fire =	141.7	465.98	67.58

Hazen Williams Equation

$$h_f = \frac{10.67 \times Q^{1.85} \times L}{C^{1.85} \times d^{4.87}}$$

Where:

h_f = Head loss over the length of pipe (m)

Q = Volumetric flow rate (m³/s)

L = Length of pipe (m)

C = Pipe roughness coefficient

d = Pipe diameter (m)

Scenario 1: maximum daily demand

Q (L/s)	1.215
C	110
L (m.)	153.1

I.D. (mm)	250	
V (m/s)	0.02	
h_f (m)	0.00	
Head Loss (psi)	0.00	
Min. Pressure (psi)	72.14	
Max. Pressure (psi)	84.66	
Service Obv. @ Street Connection (m)	91.70	
Service Obv. @ Building Connection (m)	92.00	
Pressure Adjustment (psi)	-0.43	(due to service elev. Diff. from street to building)
Adjusted Min. Pressure (psi)	71.71	(must not be less than 50psi)
Adjusted Max. Pressure (psi)	84.23	(must not be more than 80psi)

Scenario 2: maximum hourly demand

Q (L/s)	2.188	
C	110	
L (m.)	153.1	
I.D. (mm)	200	
V (m/s)	0.07	
h_f (m)	0.01	
Head Loss (psi)	0.01	
Min. Pressure (psi)	72.13	
Max. Pressure (psi)	84.65	
Service Obv. @ Street Connection (m)	91.70	
Service Obv. @ Building Connection (m)	92.00	
Pressure Adjustment (psi)	-0.43	(due to service elev. Diff. from street to building)
Adjusted Min. Pressure (psi)	71.70	(must not be less than 40psi)
Adjusted Max. Pressure (psi)	84.22	(must not be more than 80psi)

APPENDIX B
Sanitary Servicing Calculation Sheet

LRL Associates Ltd.
Sanitary Sewer Design Sheet



LRL File No.: 220512-01
Project: Auditorium Addition - ESP Pierre-de-Blois
Location: 1310 Chapman Mills Dr., Ottawa
Designed: K. Herold
Checked: K. Paradis
Date: 2026-01-16
DWG. Reference: C401

Sanitary Design Parameters

Commercial & Institutional Flow = 28000 L/ha/day
 Light Industrial Flow = 35000 L/ha/day
 Heavy Industrial Flow = 55000 L/ha/day
 Maximum Residential Peak Factor = 4.0
 Commercial & Institutional Peak Factor = 1.5

Average Daily Flow = 280 L/p/day
 Industrial Peak Factor = as per Appendix 4-B
 Extraneous Flow = 0.33 L/s/ha

Pipe Design Parameters

Maximum Velocity = 3.00 m/s
 Minimum Velocity = 0.60 m/s
 Manning's n = 0.013

LOCATION			RESIDENTIAL						COMMERCIAL		INDUSTRIAL			INSTITUTIONAL		C+I+I	INFILTRATION			TOTAL FLOW, Q	PIPE						
STREET	FROM	TO	AREA	POP.	ACCU.		PEAK FACT.	PEAK FLOW	AREA	ACCU. AREA	AREA	ACCU. AREA	PEAK FACT.	AREA	ACCU. AREA	PEAK FLOW	TOTAL AREA	ACCU. AREA	INFILT. FLOW		LENGTH	DIA.	SLOPE	MATERIAL	CAP. Q(FULL)	VEL. V(FULL)	RATIO Q/QFULL
					AREA	POP.														(Ha)							
	BLDG	Ex. SAN												4.858		2.36	4.858	4.858	1.60	3.96		250	1.00%	PVC	59.47	1.21	0.07

Notes: Existing inverts and slopes are estimated. They are to be confirmed on-site.

APPENDIX C
Stormwater Management Design Sheets



LRL File No. 220512-01
Project: Auditorium Addition - ESP Paul-de-Blois
Location: 1310 Chapman Mills Dr, Ottawa
Date: January 16, 2026
Designed: K. Herold
Checked: K. Paradis
Drawing Reference: C701, C703

Post-Development Catchments

WATERSHED	C = 0.20	C = 0.80	C = 0.90	Total Area (ha)	Combined C
EWS-01	4.850	0.000	0.000	4.850	0.20

Post-Development Catchments (Post-Addition)

WATERSHED	C = 0.20	C = 0.80	C = 0.90	Total Area (ha)	Combined C
RWS-01	0.000	0.000	0.074	0.074	0.90
WS-02	0.092	0.000	0.012	0.104	0.28
WS-03	0.056	0.000	0.228	0.284	0.76
WS-04	0.000	0.000	0.228	0.228	0.90
RWS-05	0.103	0.000	0.030	0.133	0.36
RWS-06	0.095	0.000	0.016	0.111	0.30
RWS-07	0.160	0.000	0.015	0.175	0.26
WS-08	0.041	0.000	0.145	0.186	0.75
WS-09	0.003	0.000	0.127	0.130	0.88
RWS-10	0.934	0.000	0.067	1.001	0.25
RWS-11	0.796	0.000	0.146	0.942	0.31
WS-12	0.190	0.000	0.143	0.333	0.50
RWS-13	0.260	0.000	0.065	0.325	0.34
WS-14	0.030	0.000	0.117	0.147	0.76
RWS-15	0.000	0.000	0.677	0.677	0.90
TOTAL	2.760	0.000	2.090	4.850	0.50

*WS-XX (SAME AS PRE-ADDITION), RWS-XX (REVISED TO ACCOMODATE PROPOSED AUDITORIUM ADDITION + SITE CHANGES)



LRL File No. 220512-01
Project: Auditorium Addition - ESP Paul-de-Blois
Location: 1310 Chapman Mills Dr, Ottawa
Date: January 16, 2026
Designed: K. Herold
Checked: K. Paradis
Drawing Ref.: C401

**Stormwater Management
Design Sheet**

STORM - 5 YEAR

Runoff Equation

$Q = 2.78CIA$ (L/s)
 C = Runoff coefficient
 I = Rainfall intensity (mm/hr) = $A / (Td + C)^B$
 A = Area (ha)
 T_c = Time of concentration (min)

Pre-Development Catchments within Development Area

Allowable Release Rate

5 Year Pre-Development Flow Rate

$I_5 = 998.071 / (Td + 6.053)^{0.814}$ **a = 998.071** **b = 0.814** **C = 6.053**

Allowable Release Rate = 884.00 L/s As Per JL Richards, Harmony Stage 1 Report Dated July 2017

Post-development Stormwater Management

		Total Site Area =	4.850	ha	ΣR=	0.50	ΣR ₅	ΣR ₁₀₀
Controlled	WS-01	0.074	ha	R=	0.90	1.00		
	WS-02	0.104	ha	R=	0.28	0.35		
	WS-03	0.284	ha	R=	0.76	0.95		
	WS-04	0.228	ha	R=	0.90	1.00		
	WS-05	0.133	ha	R=	0.36	0.45		
	WS-06	0.111	ha	R=	0.30	0.38		
	WS-07	0.175	ha	R=	0.26	0.33		
	WS-08	0.186	ha	R=	0.75	0.93		
	WS-09	0.130	ha	R=	0.88	1.00		
	WS-10	1.001	ha	R=	0.25	0.31		
	WS-11	0.942	ha	R=	0.31	0.39		
	WS-12	0.333	ha	R=	0.50	0.63		
	WS-13	0.325	ha	R=	0.34	0.43		
	WS-14	0.147	ha	R=	0.76	0.95		
	Total Flow to Storm Stub =	4.173	ha	ΣR=	0.44	0.55		
Roof Top	WS-15 (Controlled Rooftop Area)	0.677	ha	R=	0.90	1.00		
	Total Flow to Storm Stub =	0.677	ha	ΣR=	0.90	1.00		

Post-development Stormwater Management

$I_{100} = 1735.688 / (Td + 6.014)^{0.820}$ **a = 1735.688** **b = 0.82** **C = 6.014**

Time (min)	Intensity (mm/hr)	Rooftop Storage		Overland Storage			Uncontrolled Runoff (L/s)	Total Release Rate (L/s)	Height on Roof (m)	
		Controlled Runoff (L/s)	Storage Volume (m³)	Controlled Release Rate (L/s)	Controlled Runoff** (L/s)	Storage Volume (m³)				Controlled Release Rate (L/s)
10	178.6	336.06	165	60.44	1192.00	253	770.0	0.00	830	0.098
20	120.0	225.75	186	70.72	830.86	73	770.0	0.00	841	0.110
30	91.9	172.90	181	72.53	654.72	0	770.0	0.00	843	0.107
40	75.1	141.43	167	71.93	548.14	0	770.0	0.00	842	0.099
50	64.0	120.37	151	70.12	475.40	0	770.0	0.00	840	0.089
60	55.9	105.20	139	66.49	420.70	0	770.0	0.00	836	0.082
70	49.8	93.71	127	63.47	378.99	0	770.0	0.00	833	0.075
80	45.0	84.68	116	60.44	345.56	0	770.0	0.00	830	0.069
90	41.1	77.37	108	57.42	317.95	0	770.0	0.00	827	0.064
100	37.9	71.34	102	54.40	294.60	0	770.0	0.00	824	0.060
110	35.2	66.25	86	53.19	276.27	0	770.0	0.00	823	0.051
120	32.9	61.91	80	50.77	259.23	0	770.0	0.00	821	0.047
130	30.9	58.15	105	44.73	240.54	0	770.0	0.00	815	0.062

Infiltration Gallery - 280m

Pipe Storage 13.74 m³
 Granular Storage 166.6 m³
Total Available Storage = 180.31 m³

40% Void
 refer to Drawing C401 for detail

Rooftop Controls

Control-Flo Roof Drain Rate = 136 L/min
 Max HWL = 0.150 m
 Control-Flo Roof Drain Rate = 15.11 L/s-m
 # of roof drains = 40
 Max Roof Storage = 186.0 m³
 Height = 0.110 m
 Max Roof Rel. Rate = 70.72 L/s

Onsite Stormwater Retention

Total Storage Required = 253.20 m³
 Pipe Storage = 101.37 m³ refer to Storm Sewer Design Sheet
 CB/MH Storage = 14.47 m³ refer to Storm Sewer Design Sheet
 Infiltration Gallery = 180.00 m³ refer to Drawing C401
Total Available Storage = 295.84 m³



LRL File No. 220512-01
Project: Auditorium Addition - ESP Paul-de-Bois
Location: 1310 Chapman Mills Dr, Ottawa
Date: January 16, 2026
Designed: K. Herold
Checked: K. Paradis
Drawing Ref.: C401

**Stormwater Management
Design Sheet**

STORM - 5 YEAR

Runoff Equation

Q = 2.78CIA (L/s)
 C = Runoff coefficient
 I = Rainfall intensity (mm/hr) = $A / (T_d + C)^B$
 A = Area (ha)
 T_c = Time of concentration (min)

Pre-Development Catchments within Development Area

Allowable Release Rate

5 Year Pre-Development Flow Rate

$I_s = 998.071 / (T_d + 6.053)^{0.814}$
a = 998.071
b = 0.814
C = 6.053

Allowable Release Rate = 884.00 L/s

As Per J.L. Richards, Harmony Stage 1 Report Dated July 2017

Post-development Stormwater Management

		Total Site Area =	4.850	ha	ΣR=	0.50	ΣR ₁₀₀	0.63
Controlled	RWS-01	0.074	ha	R=	0.90	1.00		
	WS-02	0.104	ha	R=	0.28	0.35		
	WS-03	0.284	ha	R=	0.76	0.95		
	WS-04	0.228	ha	R=	0.90	1.00		
	RWS-05	0.133	ha	R=	0.36	0.45		
	RWS-06	0.111	ha	R=	0.30	0.38		
	RWS-07	0.175	ha	R=	0.26	0.33		
	WS-08	0.186	ha	R=	0.75	0.93		
	WS-09	0.130	ha	R=	0.88	1.00		
	RWS-10	1.001	ha	R=	0.25	0.31		
	RWS-11	0.942	ha	R=	0.31	0.39		
	WS-12	0.333	ha	R=	0.50	0.63		
	RWS-13	0.325	ha	R=	0.34	0.43		
	WS-14	0.147	ha	R=	0.76	0.95		
Total Flow to Storm Stub =		4.173	ha	ΣR=	0.44	0.55		
Roof Top	RWS-15 (Controlled Rooftop Area)	0.677	ha	R=	0.90	1.00		
	Total Flow to Storm Stub =	0.677	ha	ΣR=	0.90	1.00		

5 Year Stormwater Management Calculations

$I_s = 998.071 / (T_d + 6.053)^{0.814}$
a = 998.071
b = 0.814
C = 6.053

Time (min)	Intensity (mm/hr)	Rooftop Storage			Overland Storage			Uncontrolled Runoff (L/s)	Total Release Rate (L/s)	Height on Roof (m)
		Controlled Runoff (L/s)	Storage Volume (m ³)	Controlled Release Rate (L/s)	Controlled Runoff (L/s)	Storage Volume (m ³)	Controlled Release Rate (L/s)			
10	104.2	176.49	87	31.43	559.66	0	770.00	0.00	801.43	0.051
20	70.3	119.00	98	37.48	393.63	0	770.00	0.00	807.48	0.058
30	53.9	91.35	96	38.08	311.48	0	770.00	0.00	808.08	0.057
40	44.2	74.84	90	37.48	261.48	0	770.00	0.00	807.48	0.053
50	37.7	63.78	83	36.27	227.16	0	770.00	0.00	806.27	0.049
60	32.9	55.80	75	35.06	202.07	0	770.00	0.00	805.06	0.044
70	29.4	49.75	67	33.85	182.76	0	770.00	0.00	803.85	0.039
80	26.6	44.99	62	32.04	166.70	0	770.00	0.00	802.04	0.037
90	24.3	41.14	56	30.83	153.96	0	770.00	0.00	800.83	0.033
100	22.4	37.95	50	29.62	143.22	0	770.00	0.00	799.62	0.030
110	20.8	35.27	45	28.41	133.97	0	770.00	0.00	798.41	0.027
120	19.5	32.98	42	27.20	125.89	0	770.00	0.00	797.20	0.025
130	18.3	30.99	39	25.99	118.74	0	770.00	0.00	795.99	0.023
260	10.6	17.95	0	22.97	76.70	0	770.00	0.00	792.97	0.000

Onsite Stormwater Retention


Total Storage Required = 0.00 m³
 Pipe Storage = 101.37 m³
 CB/MH Storage = 14.47 m³
 Infiltration Gallery = 180.00 m³
Total Available Storage = 295.84 m³

refer to Storm Sewer Design Sheet
 refer to Storm Sewer Design Sheet
 refer to Drawing C401

Rooftop Controls

Control-Flo Roof Drain Rate = 136 L/min
 Max HWL = 0.15 m
 Control-Flo Roof Drain Rate = 15.11 L/s·m
 # of roof drains = 40
 Max Roof Storage = 97.8 m³
 Height = 0.058 m
 Max Roof Rel. Rate = 37.48 L/s

LRL Associates Ltd.
5 year Storm Design Sheet

	LRL File No.	220512-01	Rational Method Q = 2.78CIA Q = Peak flow in litres per second (L/s) A = Drainage area in hectares (ha) C = Runoff coefficient I = Rainfall intensity (mm/hr)	Storm Design Parameters			
	Project:	Auditorium Addition - ESP Paul-de-Blois		Runoff Coefficient (C)			
	Location:	1310 Chapman Mills Dr, Ottawa		Grass	0.20		
	Date:	January 16, 2026		Gravel	0.85		
Designed:	K. Herold	Asphalt / rooftop	0.90				
Verified:	K. Paradis						

LOCATION			AREA (ha)			FLOW					STORM SEWER							MANHOLE						STORAGE					
WATERSHED / STREET	From MH	To MH	C = 0.20	C = 0.80	C = 0.90	Indiv. 2.78AC	Accum. 2.78AC	Time of Conc. (min.)	Rainfall Intensity (mm/hr)	Peak Flow Q (l/s)	Pipe Diameter (mm)	Type	Slope (%)	Length (m)	Capacity Full (L/s)	Velocity Full (m/s)	Time of Flow (min.)	Ratio (Q/Q _{FULL})	Up Invert (m)	Down Invert (m)	T/G Up Stream (m)	T/G Down Stream	Up Depth obv (m)	Down Depth obv (m)	Up Depth inv (m)	Pipe Storage 100 year (m ³)	Upstream CB/MH Size (m)	Water Depth 100 year (m)	CB/MH Storage 100 year (m ³)
WS-14	CB08	CB07	0.030	0.000	0.117	0.31	0.31	10.00	104.19	32.24	250	PVC	0.50%	66.3	42.0	0.86	1.29	0.77	92.50	92.17	94.00	93.60	1.25	1.18	1.25	3.26	0.60	0.50	0.18
WS-13	CB07	CB06	0.260	0.000	0.065	0.31	0.62	11.29	97.84	60.33	250	PVC	0.50%	54.9	42.0	0.86	1.07	1.43	92.10	91.83	93.60	93.28	1.25	1.20	1.25	2.70	0.60	0.90	0.32
WS-13	CB06	CB05	0.000	0.000	0.000	0.00	0.62	12.36	93.19	57.46	250	PVC	0.50%	59.8	42.0	0.86	1.16	1.37	91.77	91.47	93.28	93.80	1.26	2.08	1.26	2.94	0.60	1.23	0.44
WS-05	CB05	CBMH04	0.103	0.000	0.030	0.13	0.75	13.52	88.66	66.40	300	PVC	0.35%	44.9	57.2	0.81	0.92	1.16	91.44	91.28	93.80	93.50	2.06	1.92	2.06	3.18	1.20	1.56	2.25
WS-02 WS-06	LCB19	CBMH09	0.187	0.000	0.028	0.17	0.17	10.00	104.19	18.16	300	PVC	0.85%	23.6	89.2	1.26	0.31	0.20	92.20	92.00	93.85	93.50	1.35	1.20	1.35	1.67	0.60	0.80	0.29
WS-03	CBMH09	CBMH04	0.056	0.000	0.228	0.60	0.78	10.31	102.57	79.55	375	PVC	0.30%	34.6	96.0	0.87	0.66	0.83	92.00	91.90	93.50	93.50	1.12	1.22	1.12	3.82	1.20	1.00	1.43
WS-04	CBMH04	MH03	0.000	0.000	0.228	0.57	2.09	14.45	85.39	258.38	600	CONC	0.15%	27.3	237.8	0.84	0.54	1.09	91.23	91.19	93.50	93.15	1.67	1.36	1.67	7.72	1.20	1.67	2.40
WS-01	CB26	MH03	0.000	0.000	0.074	0.19	0.19	10.00	104.19	19.29	250	PVC	0.75%	13.9	51.5	1.05	0.22	0.37	91.28	91.18	93.30	93.50	1.77	2.07	1.77	0.68	0.60	1.72	0.62
WS-12	LCB18	LCB17	0.190	0.000	0.143	0.46	0.46	10.00	104.19	48.29	250	SUB PVC	0.35%	86.8	35.2	0.72	2.02	1.37	93.00	92.70	93.75	93.30	0.50	0.35	0.50	0.76	0.60	0.00	0.00
WS-11	LCB17	LCB15	0.796	0.000	0.146	0.81	1.27	12.02	94.62	120.31	300	SUB PVC	0.35%	145.4	57.2	0.81	2.99	2.10	92.67	92.16	93.30	93.30	0.33	0.84	0.33	10.28	0.60	0.33	0.12
WS-10	LCB15	CBMH12	0.934	0.000	0.067	0.69	1.96	15.01	83.52	163.57	300	SUB PVC	0.35%	173.0	57.2	0.81	3.56	2.86	92.13	91.52	93.30	93.50	0.87	1.68	0.87	12.23	0.60	0.87	0.31
	CBMH12	CBMH11	0.000	0.000	0.000	0.00	1.96	18.57	73.54	144.03	450	PVC	0.35%	34.8	168.7	1.06	0.55	0.85	91.52	91.40	93.50	93.00	1.53	1.15	1.53	5.54	0.60	1.48	0.53
WS-09	CBMH11	CBMH10	0.003	0.000	0.127	0.32	2.28	19.12	72.24	164.60	450	PVC	0.35%	21.7	168.7	1.06	0.34	0.98	91.37	91.29	93.00	93.00	1.18	1.26	1.18	3.45	0.60	1.18	0.42
WS-08 WS-07	CBMH10	MH03	0.200	0.000	0.160	0.51	2.79	19.46	71.45	199.38	450	PVC	0.35%	23.8	168.7	1.06	0.37	1.18	91.26	91.18	93.20	93.50	1.49	1.87	1.49	3.79	0.60	1.49	0.53
	MH03	MH02	0.000	0.000	0.015	0.00	5.07	14.99	83.60	423.82	825	CONC	0.29%	23.8	769	1.44	0.28	0.55	91.16	91.09	93.15	93.50	1.16	1.58	1.16	12.73	1.20	1.16	1.68
WS-15	School	MH02	0.000	0.000	0.677	1.69	1.69	10.00	104.19	72.53	375	PVC	0.47%	89.0	120.2	1.09	1.36	0.60	91.51	91.09	94.55	93.49	2.66	2.02	2.66	9.83	0.60	1.49	0.54
	MH02	MH01	0.000	0.000	0.000	0.00	6.76	15.26	82.72	632.00	900	CONC	0.25%	26.4	912.4	1.43	0.31	0.69	91.03	90.97	93.59	94.30	1.66	2.43	1.66	16.80	1.20	1.66	2.39
	MH01	CITY	0.000	0.000	0.000	0.00	6.76	15.57	81.76	625.53	1,050	CONC	0.25%	0.5	884.0	1.02	0.01	0.71	90.94	90.93	94.30	94.30	2.31	2.32	2.31				

Notes: Maximum roof flow rate shown as per SWM design sheet

101.37 14.47

Maximum roof flow rate shown as per SWM design sheet

Peak allowable flow rate as per JL Richards Design

Invert from JL Richards Design

HWL (100 Year)	93.00
Storage(100 year)	115.84




Z105
CONTROL-FLO ROOF DRAIN
W/ PARABOLIC WEIR

SPECIFICATION SHEET

TAG _____

Dimensional Data (inches and [mm]) are Subject to Manufacturing Tolerances and Change Without Notice



Specify Number of Notches in Weir	
___-N1	One Notch
___-N2	Two Notches
___-N3	Three Notches
___-N4	Four Notches
___-N5	Five Notches
___-N6	Six Notches

A- Pipe Size In.[mm]	Approx. Wt. Lbs. [kg]	Dome Open Area Sq. In. [cm ²]
2,3,4 [51,76,102]	34 [15]	103 [665]

ENGINEERING SPECIFICATION: ZURN Z105

15" [381mm] Diameter Control-Flo roof drain for dead-level roof construction, Dura-Coated cast iron body, Control-Flo weir shall be linear functioning with integral membrane flashing clamp/gravel guard and Poly-Dome. All data shall be verified proportional to flow rates. Each notch will allow 10 GPM [LPM] of flow per 1" [25mm] of rain water build up above the drain.

OPTIONS (Check/specify appropriate options)

PIPE SIZE

- 3, 4 [76, 102]
- 2, 3, 4 [51, 76, 102]
- 2, 3, 4 [51, 76, 102]

(Specify size/type) **OUTLET**

- ___ IC Inside Caulk
- ___ NH No-Hub
- ___ NL Neo-Loc

E BODY HT. DIM.

- 5-1/4 [133]
- 5-1/4 [133]
- 4-9/16 [116]

PREFIXES

- ___ Z D.C.C.I. Body with Poly-Dome*
- ___ ZA D.C.C.I. Body with Aluminum Dome
- ___ ZC D.C.C.I. Body with Cast Iron Dome

SUFFIXES

- ___ -C Underdeck Clamp
- ___ -DP Top-Set® Deck Plate (Replaces both -C & -R)
- ___ -E Static Extension 1 [25] thru 4 [102] (Specify Ht.)
- ___ -EA Adjustable Extension Assembly
2-1/8 [54] thru 3-1/2 [89]
- ___ -G Galvanized Cast Iron
- ___ -R Roof Sump Receiver
- ___ -TC Neo-Loc Test Cap Gasket (2,3,4
[51,76,102] NL Bottom Outlet Only)
- ___ -VP Vandal Proof Secured Top
- ___ -10 6 [152] High Parabolic Weir for
Sloped Roof (ZC or ZA)

* Regularly furnished unless otherwise specified.

APPENDIX D
Supporting Documents



LRL

ENGINEERING | INGÉNIERIE

**Site Servicing and
Stormwater Management Report
for Site Plan Control Application**

**Proposed New Public High School
Barrhaven Centre
4005 Strandherd Drive
Barrhaven, Ontario**

Prepared for

Conseil des écoles publiques de l'Est de l'Ontario

Attention: Mrs Carolyn Jones, MRAIC

LRL File No.: 170364

September 5, 2019
Revision 03



TABLE OF CONTENTS

1	INTRODUCTION	3
2	SITE DESCRIPTION	3
3	SCOPE OF WORK.....	4
4	WATER SUPPLY AND FIRE PROTECTION.....	5
4.1	Existing Water Supply Services.....	5
4.2	Water Supply Demand.....	5
4.3	Water supply servicing design	6
4.4	Boundary Conditions	6
5	SANITARY DRAINAGE.....	7
5.1	Municipal Sanitary Sewer Services	7
5.2	Sanitary Sewer Servicing Design	7
6	STORMWATER MANAGEMENT	7
6.1	Municipal Stormwater Infrastructure.....	7
6.2	Stormwater Management Concept	8
6.3	Design Criteria	8
6.3.1	Water Quality	8
6.3.2	Water Quantity.....	8
6.4	Method of Analysis	8
6.5	Allowable Release Rate.....	8
6.6	Stormwater Quantity Controls	9
6.7	Stormwater Quality Management	10
7	EROSION AND SEDIMENT CONTROL.....	10
8	CONCLUSIONS	10
9	LIMITATIONS AND USE OF REPORT	11



LIST OF FIGURES

Figure 1 - Aerial view of the location of the proposed development (Google Earth)..... 4

APPENDICES

Appendix A	Domestic Water Demand and Fire Flow Calculations & Boundary Conditions
Appendix B	Sanitary Sewer Calculation Sheet
Appendix C	Stormwater Management Design Sheets
Appendix D	Supporting Documents
Appendix E	Engineering Drawings



1 INTRODUCTION

LRL Associates Ltd. (LRL) has been retained by the Conseil des écoles publiques de L'Est de l'Ontario (CEPEO) to prepare a site servicing and stormwater management report in support of their site plan control application for a proposed new Public High School in Barrhaven. This report presents the proposed servicing plan of the new development for water and sanitary services, as well as stormwater management.

This report has been prepared in consideration of the survey carried out by Annis O'Sullivan Vollebakk Ltd. (AOV) in August 2017 and the design brief prepared by J.L. Richards & Associates Limited and dated July 2017. Should there be any discrepancies in the existing infrastructure and/or connections to the existing services, which may relate to the site servicing considerations, LRL should be advised in order to review the report recommendations. This report should be read in conjunction with the grading and drainage, site servicing, and stormwater management plans prepared by LRL.

2 SITE DESCRIPTION

The subject property is currently vacant land and is located within the urban boundary of the City of Ottawa, Ontario. As illustrated in Figure 1, the development is located south on Strandherd Drive. The total area of the property measures approximately 4.86 ha.

Chapman Mills is to be developed and constructed by others in accordance with the design prepared by J.L. Richards & Associates Limited as part of Harmony Stage 1 Development for Minto Communities, dated July 2017.





Figure 1 - Aerial view of the location of the proposed development (Google Earth)

The proposed development is located within the proposed Minto Harmony Community area that has yet to be fully constructed by others. The land surface has a minimal grade change with elevations ranging between 92.09m and 94.57m.

The proposed development consists of a three-storey, slab-on grade, public high school with access roadway, parking areas, playground areas, a soccer field and a future portable classes area. Refer to Appendix D for the proposed site plan (Drawing C401 – Servicing Plan).

3 SCOPE OF WORK

As per applicable guidelines, the scope of work includes the following:

Water services

- Calculate the expected domestic water demands at average and peak flow conditions.
- Calculate the fire flow as per the Fire Underwriters Survey (FUS) method.
- Describe the proposed water distribution network and connection to the existing watermain.

Sanitary services

- Describe the existing sanitary sewers available to receive wastewater from the building.
- Calculate the peak flow rates from the development.
- Describe the proposed sanitary sewer system.



- Verify the available capacity in the downstream sanitary sewer.
- Verify the capacity of the existing lateral sanitary sewer

Stormwater management

- Calculate the allowable stormwater release rate.
- Calculate the anticipated post development stormwater release rates.
- Demonstrate how the target quality and quantity objectives will be achieved.
- Verify the capacity of the existing lateral storm sewer

4 WATER SUPPLY AND FIRE PROTECTION

4.1 Existing Water Supply Services

The 300mm diameter watermain on Chapman Mills Drive will be constructed by others. According to J.L. Richards & Associates Limited design, the site will have a 200mm diameter water service stub provided along Chapman Mills Drive, approximately 240m southeast of Strandherd Drive. There will be four (4) fire hydrants along Chapman Mills Drive on the east side near the proposed site. Refer to C401 – Servicing Plan for the proposed municipal infrastructure design.

4.2 Water Supply Demand

As per the AWWA Standards and the City of Ottawa Design Guidelines, the average domestic water demand was calculated using 850 equivalent fixture units and for daily and hourly peaking factors of **1.5** and **1.8**, respectively. Thus, the average daily domestic water demand for the proposed building is **12.33 L/s**, the maximum daily flow rate is **18.50 L/s** and the maximum hourly flow rate is **22.20 L/s**. Refer to Appendix A for the domestic water demand calculation sheet.

The fire flow requirement was evaluated in accordance with the Fire Underwriters Survey (FUS). This method is based on the floor area of the building to be protected, type and combustibility of the structural frame and the separation distances with adjoining buildings. The fire flow demand was calculated to be **116.7L/s**. Refer to Appendix A – Fire Flow Calculations, for the fire flow

However, to meet the minimum requirement of a 90m radius distance between the fire hydrant and the building, as required by the City of Ottawa, a private fire hydrant on the said property is added to service the building. In addition, a second private hydrant has been proposed south corner of the school for future portable expansion planning. Refer to LRL drawing C401 Rev.01 – *Servicing Plan* for the layout of the proposed water services and connections.



4.3 Water supply servicing design

The proposed building will be serviced by a 200mm dia. water service which will connect to the 200mm diameter stub along Chapman Mills Drive. The proposed service will be located on the east side of the building. Refer to LRL drawing C401 – Servicing Plan for the layout of the proposed water service.

A fire department siamese connection is proposed on the east side near the building main student entrance. The siamese connection is located adjacent to the proposed sidewalk to facilitate the access for the fire department year-round. To meet the minimum requirement of a 45m radius distance between the fire hydrant and the building main entrance, as required by the OBC, a private fire hydrant will be installed at the north-east corner of the building. Refer to LRL drawing C401 Rev.01 – *Servicing Plan* for the layout of the proposed water service connection and the private fire hydrant.

4.4 Boundary Conditions

The existing boundary conditions provided by the City of Ottawa for the site are as follow:

Demand Scenario	Head (m)	Pressure ¹ (psi)
Maximum HGL	156.5	89.5
Peak Hour	144.7	72.7
Max Day Plus Fire (7,000 L/min)	127.8	48.7

As the available fire flow provided by the City of Ottawa is above the minimum fire flow requirement for the proposed development, no supplementary fire protection and storage are required for the site. Refer to Appendix A for the provided city boundary conditions dated 2018-Dec-17.



5 SANITARY DRAINAGE

5.1 Municipal Sanitary Sewer Services

Along Chapman Mills Drive, a 300mm diameter sanitary sewer flowing easterly on Clarity Street will be constructed by others. J.L. Richards & Associates Limited design indicates that a 250mm diameter sanitary service stub will be provided to service this site with a total allowable flow 62.0 L/s. Refer to drawing C401 – Servicing Plan for the layout.

5.2 Sanitary Sewer Servicing Design

The new building will be serviced with a 250mm dia. sanitary service that will be installed south of the new building. A sanitary maintenance manhole, SAN MH01 will be installed just north of the property line before connecting to the 250mm stub and discharging to the municipality sewer system. The proposed 250mm PVC DR35 sanitary service will be installed at a minimum slope of 1.00%. Refer to LRL drawing C401 – Servicing Plan for the proposed sanitary servicing.

The sanitary peak load was calculated using the Ontario Building Code (2012), Part 7 – Plumbing and estimated at **12.33 L/s**.

Also, LRL used the City of Ottawa Sanitary Design Guidelines to estimate the allocated sanitary peak flow to ensure the most conservative demand is used. Using the criteria as shown in Table 1 and the City specific design parameters, the site anticipated sanitary flow was calculated at **5.58 L/s** for the 4.86 ha area. Refer to Appendix B for the site sanitary sewer design sheet. Since this estimate is lower than the total sanitary peak flow estimated using the Ontario Building Code (2012) Part 7, the total sanitary flow for the proposed elementary school was estimated at **12.33 L/s**, as this flow rate is more accurate and conservative.

Table 1 Sanitary Sewer Design Criteria

Design Parameter	Value
Minimum service connection size (diameter)	135 mm
Manning roughness coefficient (n)	0.013
Minimum velocity (full)	0.6 m/s
Maximum velocity (full)	3.0 m/s

6 STORMWATER MANAGEMENT

6.1 Municipal Stormwater Infrastructure

Along Chapman Mills Drive, a 675mm diameter storm sewer flowing easterly and draining into the 1,350mm diameter storm sewer on Clarity Street will be constructed by others. J.L. Richards



& Associates Limited show that a 1,050mm diameter storm service stub will be provided to service the site. Refer to drawing C401 – Servicing Plan for the layout.

6.2 Stormwater Management Concept

Drainage from the site will be captured by a series of roof drains, catchbasins, catchbasin manholes and perforated subdrains which will convey the stormwater to the existing 1,050mm diameter storm sewer stub on Chapman Mills Drive. Refer to LRL drawing C401 for the proposed storm servicing and drawings C301 and C702 for the grading and drainage plan and stormwater management. Refer to Appendix C – Stormwater Management Design Sheets for the proposed site storm sewer design.

6.3 Design Criteria

Stormwater quantity control measures are proposed for this site to reduce the post-development stormwater runoff to allowable levels.

6.3.1 Water Quality

Enhanced (80% Total Suspended Solids removal) quality control is to be provided by others. The stormwater retaining pond has been designed as part of Minto Harmony Community project, Phase 1 which was prepared by J.L. Richards & Associates Limited.

6.3.2 Water Quantity

All storm events up to and including the 100-year event will be controlled to the 5-year pre-development level. The site major overland flow route has been designed to ensure that storm events beyond the 100-year design storm can be safely conveyed overland towards the Chapman Mills Drive right-of-way. The minor system (storm sewer) within the site is sized to convey the 5-year storm event flows from the site to the municipal storm sewer on Chapman Mills Drive.

6.4 Method of Analysis

The Rational Method was used to calculate the runoff from the development. The Intensity-Duration-Frequency (IDF) curve formulas for the MacDonald-Cartier International Airport, in the city of Ottawa, were used to calculate the peak storm flows for the site.

6.5 Allowable Release Rate

This site is subject to stormwater management control where the allowable flow for the 5 and 100-year storm events are estimated at 1,055.8 L/s as per the design prepared by J.L. Richards & Associates Limited. The total allowable release rate will be restricted with an undersized pipe



at the outlet that will throttle the total allowable release rate to **884L/s** as per J.L. Richards & Associates Limited design sheet. Refer to Appendix D - Supporting Documents.

6.6 Stormwater Quantity Controls

The proposed stormwater management quantity control for this development will be accomplished through the use of: undersized piping to throttle the flow rate, Zurn Control-Flo roof drains, roof top water storage, pipe and maintenance holes structure underground. The proposed site storm sewer and stormwater management system are shown on drawing C401 – Servicing Plan and detailed calculations including the design sheet are attached in Appendix C.

The collected stormwater from catchment area WS-15 (0.711ha), will first be regulated using thirty-five (35) one notch Zurn Control-Flo roof drains with a total maximum release rate of **14.91 L/s*m**. With the thirty-five (35) roof drains, a maximum ponding volume of **213 m³** of water will be stored on the roof during the 100-year storm event to minimize the water directed to MH02. The controlled roof water will be captured by the proposed storm manhole MH02 before outletting to Chapman Mills Drive. The two future expansions have been added to the design calculations in order to obtain the maximum value for the roof top ponding and flow generated by the hard surface. The roof drains will be connected downstream of the controlled manhole (MH03) to prevent a double control measurement as per the City of Ottawa guidelines. The total anticipated flow of the roof drains is **63.47L/s**.

WS-01, WS-02, WS-03, WS-04, WS-05, WS-06, WS-07, WS-08, WS-09, WS-10, WS-11, WS-12, WS-13 and WS-14 areas, (0.059ha, 0.105ha, 0.281ha, 0.221ha, 0.161ha, 0.095ha, 0.169ha, 0.201ha, 0.130ha, 1.033ha, 0.929ha, 0.333ha, 0.285ha and 0.147ha respectively) consist of parking and driving area, landscaped area and playground area. These catchments area will be captured through a number of catchbasins and subdrains before being directed to the proposed 825mm outlet on Chapman Mills Drive and controlled using an undersized 825mm diameter reinforced concrete pipe. The 825mm pipe will be installed at a 0.29% slope that has a full capacity of **769 L/s**.

In order to control the 100-year storm event, **224.25m³** of on-site storage will be required. This storage will be provided with the use of some pipe/structure storage and an infiltration gallery up to the expected high water level of 93.00m MASL. The stormwater storage will be provided as follows: **115.84 m³** from on-site pipes and maintenance structures and **180.31 m³** from the infiltration gallery. Refer to C401 – Servicing Plan and Appendix C for stormwater management design details. Thus, the outlet to Chapman Mills Drive is able of achieving the required stormwater quantity control of **884L/s**.



6.7 Stormwater Quality Management

A Stormwater Management Facility Pond design by J.L. Richards & Associates Limited is located southeast of the subject site at the downstream end of Minto Harmony Community and will provide enhanced protection, 80% Total Suspended Solids removal. Hence, no stormwater quality management is required on the site. Refer to Appendix D – Supporting Documents for the location of the proposed stormwater management pond.

7 EROSION AND SEDIMENT CONTROL

During the construction, erosion and sediment controls will be required primarily via a sediment control fence to be erected along the perimeter of the site where runoff has the potential of leaving the site. Inlet sediment control devices are also to be provided in any catchbasin and/or manholes on and around the site that may be impacted by the site construction activities. Construction and maintenance requirements for erosion and sediment controls are to comply with Ontario Provincial Standard Specification OPSS 577. Refer to LRL drawing C101 – Erosion and Sediment Control Plan for details.

8 CONCLUSIONS

In accordance with this report objectives, the analyses for the proposed development can be summarized as follows:

Water Service

- The anticipated maximum domestic water demand for the site is 22.20 L/s.
- The required fire flow was calculated at 116.7 L/s using the FUS method.
- A new fire hydrant will be installed on-site within the m radius from the siamese connection.
- The new development will be serviced with a 200mm dia. watermain connected to the proposed 300mm dia. watermain on Chapman Mills Drive.

Sanitary Service

- The anticipated sanitary flow from the proposed development is 12.33 L/s.
- The proposed building will be serviced by a 250mm sanitary service connection to the existing 900mm dia. sanitary sewer on Chapman Mills Drive.
- A new monitoring manhole will be installed on the new 250mm sanitary service that is connected to the proposed 900mm dia. sanitary sewer on Chapman Mills Drive.

Stormwater Management

- The stormwater release rates from the proposed development will meet the pre-development allowable release rate of 884 L/s onto Chapman Mills Drive.




- Stormwater quantity control objectives will be achieved through on-site storage.
- Stormwater quality control objectives will be achieved off-site through the future Stormwater Management Pond designed by J.L. Richards & Associates Limited.

9 LIMITATIONS AND USE OF REPORT

The report conclusions are applicable only to this project described in this report. Any changes may require a review by LRL Associates Ltd. to insure compatibility with the recommendations contained in this report. We trust the information presented meets your current requirements. Please do not hesitate to contact us should you have any questions or concerns.

Prepared by:

LRL Associates Ltd.



Virginia Johnson, P.Eng

Civil Engineer



APPENDIX A

Domestic Water Demand and Fire Flow Calculations & Boundary Conditions



Domestic Water Supply Calculations

LRL File No. 170364
Project: Public High School Barrhaven Centre
Location: 4005 Strandherd Drive, Barrhaven, Ottawa
Date: January 16, 2019
Designed: G. Brunet
Verified: J.C. Lalonde

Domestic Commercial Flow Demand

Total Building Floor Area =	5,956	m ²	(includes existing and proposed building)
Site Total Area =	4.86	ha	
Total Proposed Fixture Unit =	850		
Average Demand Per Fixture Unit =	<u>0.8704</u>	L/min	As per AWWA Standard
Average Commercial Water Demand =	740	L/min	12.33 L/s
Maximum Daily Peak Factor =	1.5	* As per City of Ottawa	
Maximum Daily Commercial =	1,110	L/min	18.50 L/s
Maximum Hourly Peak Factor =	1.8	* As per City of Ottawa	
Maximum Hourly Commercial =	1,332	L/min	22.20 L/s
Therefore,			
Domestic Peak Hourly Flow Rate	22.20	L/s	
Required Fire Flow rate=	116.7	L/s	



Fire Flow Calculations

LRL File No. 170364
 Project Public High School Barrhaven Centre
 Date January 16, 2019
 Method Fire Underwriters Survey (FUS)
 Designed by G. Brunet

Multi-level Development	9281	
	9,281	m ²

Step	Task	Term	Options	Multiplier	Choose:	Value	unit	Fire Flow	
Structural Framing Material									
1	Choose frame used for building	Coefficient C related to the type of construction	Wood Frame	1.5	Non-combustible construction	0.8			
			Ordinary Construction	1.0					
			Non-combustible construction	0.8					
			Fire resistive construction <2 hrs	0.7					
			Fire resistive construction >2 hrs	0.6					
Floor Space Area									
2	Choose type of housing	Type of housing	Single family dwelling	0	Building - no. of units per floor	1	units		
			Townhouse - no. of units	0					
			Building - no. of units per floor	1					
	Enter no. of storeys	Number of floors/storeys for the building (excluding the basement)				3	floors		
3	Enter area	Enter floor space area		1		9,281	sq.m.		
4	Obtain fire flow before reductions	Required fire flow	Fire Flow = 220 x C x Area^{0.5}					L/min	16,955
								L/s	282.6
Reductions or surcharge due to factors affecting burning									
5	Choose combustibility of contents	Occupancy hazard reduction or surcharge	Non-combustible	-0.25	Limited combustible	-0.15			
			Limited combustible	-0.15					
			Combustible	0					
			Free burning	0.15					
			Rapid burning	0.25					
6	Choose reduction for sprinklers	Sprinkler reduction	Sprinklers (NFPA13)	-0.30	True	-0.3			
			Water supply is standard for both the system and fire department hose lines	-0.10	True	-0.1	L/min	7,206	
			Fully supervised system	-0.10	True	-0.1	L/s	120.1	
7	Choose separation	Exposure distance between units	North side	Over 45m	0				
			East side	Over 45m	0				
			South side	Over 45m	0		L/min	7,206	
			West side	Over 45m	0		L/s	120.1	
Net required fire flow									
8	Obtain fire flow, duration, and volume	Minimum required fire flow rate (rounded to nearest 1000 as per City of Ottawa)					L/min	7,000	
		Minimum required fire flow rate					L/s	116.7	
		Required duration of fire flow					hr	2	

BOUNDARY CONDITIONS



Boundary Conditions For: 4005 Strandherd Dr.

Date of Boundary Conditions: 2018-Dec-17

Provided Information:

Scenario	Demand	
	L/min	L/s
Average Daily Demand	739.8	12.3
Maximum Daily Demand	1,110	18.5
Peak Hour	1332	22.2
Fire Flow #1 Demand	7,000	116.7

Number of Connections: 1

Location:



BOUNDARY CONDITIONS



Results:

Pre-Configuration

Connection #: 1

Demand Scenario	Head (m)	Pressure ¹ (psi)
Maximum HGL	156.5	89.5
Peak Hour	144.7	72.7
Max Day Plus Fire (7,000) L/min	127.8	48.7

¹Elevation: **94.640 m**

Notes:

1) As per the Ontario Building Code in areas that may be occupied, the static pressure at any fixture shall not exceed 552 kPa (80 psi.) Pressure control measures to be considered are as follows, in order of preference:


- a) If possible, systems to be designed to residual pressures of 345 to 552 kPa (50 to 80 psi) in all occupied areas outside of the public right-of-way without special pressure control equipment.
 - b) Pressure reducing valves to be installed immediately downstream of the isolation valve in the home/ building, located downstream of the meter so it is owner maintained.
- 2) Both HGL and Pressures at Junction reflect the interm condition of watermain connections and not the ultimate condition of watermain connections which involves a 400 mm diameter main at Strandherd Dr. that will connect the network providing higher HGL at near by connections.

Disclaimer

The boundary condition information is based on current operation of the city water distribution system. The computer model simulation is based on the best information available at the time. The operation of the water distribution system can change on a regular basis, resulting in a variation in boundary conditions. The physical properties of watermains deteriorate over time, as such must be assumed in the absence of actual field test data. The variation in physical watermain properties can therefore alter the results of the computer model simulation. Fire Flow analysis is a reflection of available flow in the watermain; there may be additional restrictions that occur between the watermain and the hydrant that the model cannot take into account.

APPENDIX B
Sanitary Servicing Calculation Sheet


LRL Associates Ltd.
Storm Design Sheet

 <p>LRL File No. 170364 Project: Public High School Barrhaven Centre Location: 4005 Strandherd Drive, Barrhaven, Ottawa Date: January 16, 2019 Designed: G. Brunet Verified: J.C. Lalonde</p>	<p style="text-align: center;">Sanitary Design Parameters</p> <p>Average Daily Flow = 350 L/p/day Commercial & Institutional Flow = 50000 L/ha/day Light Industrial Flow = 35000 L/ha/day Heavy Industrial Flow = 55000 L/ha/day Maximum Residential Peak Factor = 4.0 Commercial & Institutional Peak Factor = 1.5</p>	<p style="text-align: center;">Pipe Design Parameters</p> <p>Minimum Velocity = 0.60 m/s Manning's n = 0.013</p>
---	---	--

LOCATION			RESIDENTIAL AREA AND POPULATION						COMMERCIAL		INDUSTRIAL		INSTITUTIONAL		C+I	INFILTRATION			TOTAL FLOW	PIPE					MANHOLE				
STREET	FROM MH	TO MH	AREA (Ha)	POP.	CUMMULATIVE		PEAK FACT.	PEAK FLOW (l/s)	AREA (Ha)	ACCU. AREA (Ha)	ACCU. AREA (Ha)	PEAK FACT.	AREA (Ha)	ACCU. AREA (Ha)	PEAK FLOW (l/s)	TOTAL AREA (Ha)	ACCU. AREA (Ha)	INFILT. FLOW (l/s)	TOTAL FLOW (l/s)	LENGTH (m)	DIA. (mm)	SLOPE (%)	MATERIA L	CAP. (FULL) (l/s)	VEL. (FULL) (m/s)	UP INVERT (m)	DOWN INVERT (m)		
					AREA (Ha)	POP.																							
SITE	PROP. BLDG	MH01	0.000	0.0	0.00	0.0	0.0	0.00	0.000	0.000	0.00	7.0	4.9	4.9	4.22	4.86	4.86	1.36	5.58	91.3	250	1.00%	PVC	59.47	1.21	91.43	90.52		
SITE	MH01	STUB	0.000	0.0	0.0	0.0	4.0	0.00	0.000	0.000	0.00	7.0	0.0	4.9	4.22	0.00	4.86	1.36	5.58	26.8	250	1.00%	PVC	59.47	1.21	90.46	90.19		
SITE	STUB	CITY	0.000	0.0	0.0	0.0	4.0	0.00	0.000	0.000	0.00	7.0	0.0	4.9	4.22	0.00	4.86	1.36	5.58	1.0	250	1.00%	PVC	59.47	1.21	90.19	90.18		
NOTES															(use 12.33 L/s)														
Existing inverts and slopes are estimated. They are to be confirmed on-site. Inverts provided by J.L. Richards & Associates Ltd * Use average flow rate of 12.33 L/s for design															Designed: G.B.					PROJECT: Public High School Barrhaven Centre									
															Checked: J.C.L.					LOCATION: 4005 Standherd Drive, Ottawa									
															Dwg. Reference: C401 - Servicing Plan					File Ref.: 170364					Date: September-14-18				
																									Sheet No. 1 of 1				

APPENDIX C
Stormwater Management Design Sheets

LRL Associates Ltd.
Storm Design Sheet

 <p>LRL File No. 170364 Project: Public High School Barrhaven Centre Location: 4005 Strandherd Drive, Barrhaven, Ottawa Date: January 16, 2019 Designed: G. Brunet Verified: J.C. Lalonde</p>	<p style="text-align: center;">Sanitary Design Parameters</p> <p>Average Daily Flow = 350 L/p/day Commercial & Institutional Flow = 50000 L/ha/day Light Industrial Flow = 35000 L/ha/day Heavy Industrial Flow = 55000 L/ha/day Maximum Residential Peak Factor = 4.0 Commercial & Institutional Peak Factor = 1.5</p>	<p style="text-align: center;">Pipe Design Parameters</p> <p>Minimum Velocity = 0.60 m/s Manning's n = 0.013</p>
---	---	--

LOCATION			RESIDENTIAL AREA AND POPULATION						COMMERCIAL		INDUSTRIAL		INSTITUTIONAL		C+I	INFILTRATION			TOTAL FLOW	PIPE					MANHOLE				
STREET	FROM MH	TO MH	AREA (Ha)	POP.	CUMMULATIVE		PEAK FACT.	PEAK FLOW (l/s)	AREA (Ha)	ACCU. AREA (Ha)	ACCU. AREA (Ha)	PEAK FACT.	AREA (Ha)	ACCU. AREA (Ha)	PEAK FLOW (l/s)	TOTAL AREA (Ha)	ACCU. AREA (Ha)	INFILT. FLOW (l/s)	TOTAL FLOW (l/s)	LENGTH (m)	DIA. (mm)	SLOPE (%)	MATERIA IL	CAP. (FULL) (l/s)	VEL. (FULL) (m/s)	UP INVERT (m)	DOWN INVERT (m)		
					AREA (Ha)	POP.																							
SITE	PROP. BLDG	MH01	0.000	0.0	0.00	0.0	0.0	0.00	0.000	0.000	0.00	7.0	4.9	4.9	4.22	4.86	4.86	1.36	5.58	91.3	250	1.00%	PVC	59.47	1.21	91.43	90.52		
SITE	MH01	STUB	0.000	0.0	0.0	0.0	4.0	0.00	0.000	0.000	0.00	7.0	0.0	4.9	4.22	0.00	4.86	1.36	5.58	26.8	250	1.00%	PVC	59.47	1.21	90.46	90.19		
SITE	STUB	CITY	0.000	0.0	0.0	0.0	4.0	0.00	0.000	0.000	0.00	7.0	0.0	4.9	4.22	0.00	4.86	1.36	5.58	1.0	250	1.00%	PVC	59.47	1.21	90.19	90.18		
NOTES															(use 12.33 L/s)														
Existing inverts and slopes are estimated. They are to be confirmed on-site. Inverts provided by J.L. Richards & Associates Ltd * Use average flow rate of 12.33 L/s for design															Designed: G.B.					PROJECT: Public High School Barrhaven Centre									
															Checked: J.C.L.					LOCATION: 4005 Standherd Drive, Ottawa									
															Dwg. Reference: C401 - Servicing Plan					File Ref.: 170364					Date: September-14-18				
																									Sheet No. 1 of 1				



LRL File No. 170364
Project: Public High School Barrhaven Centre
Location: 4005 Strandherd Drive, Barrhaven, Ottawa
Date: January 16, 2019
Designed: G. Brunet
Verified: J.C. Lalonde
Drawing Reference: C701 and C702

Post-Development Catchments

WATERSHED	C = 0.20	C = 0.80	C = 0.90	Total Area (ha)	Combined C
EWS-01	0.00	0.00	0.06	0.059	0.90
EWS-02	0.10	0.00	0.00	0.105	0.23
EWS-03	0.07	0.00	0.21	0.281	0.73
EWS-04	0.00	0.00	0.22	0.221	0.90
EWS-05	0.15	0.01	0.00	0.161	0.24
EWS-06	0.10	0.00	0.00	0.095	0.20
EWS-07	0.15	0.02	0.00	0.169	0.27
EWS-08	0.03	0.00	0.17	0.201	0.80
EWS-09	0.01	0.00	0.12	0.130	0.86
EWS-10	0.94	0.00	0.10	1.033	0.27
EWS-11	0.80	0.00	0.13	0.929	0.30
EWS-12	0.19	0.00	0.14	0.333	0.50
EWS-13	0.26	0.00	0.03	0.285	0.26
EWS-14	0.03	0.00	0.12	0.147	0.76
EWS-15 (ROOF)	0.00	0.00	0.71	0.711	0.90
TOTAL	2.819	0.030	2.011	4.860	0.49



LRL File No. 170364
Project: Public High School Barrhaven Centre
Location: 4005 Strandherd Drive, Barrhaven, Ottawa
Date: January 16, 2019
Designed: G. Brunet
Checked: J.C. Lalonde
Drawing Ref.: C401

**Stormwater Management
Design Sheet**

STORM - 5 YEAR

Runoff Equation

$Q = 2.78CIA$ (L/s)
 C = Runoff coefficient
 $I = \text{Rainfall intensity (mm/hr)} = A / (T_d + C)^B$
 A = Area (ha)
 $T_c = \text{Time of concentration (min)}$

Pre-Development Catchments within Development Area

Allowable Release Rate

5 Year Pre-Development Flow Rate

$I_5 = 998.071 / (T_d + 6.053)^{0.814}$
a = 998.071
b = 0.814
C = 6.053

Allowable Release Rate = 884.00 L/s
As Per JL Richards, Harmony Stage 1 Report Dated July 2017

Post-development Stormwater Management

				$\sum R_5$	$\sum R_{100}$
Total Site Area =		4.860	ha	$\sum R = 0.49$	0.62
Controlled	WS-01	0.059	ha	R= 0.90	1.00
	WS-02	0.105	ha	R= 0.23	0.28
	WS-03	0.281	ha	R= 0.73	0.91
	WS-04	0.221	ha	R= 0.90	1.00
	WS-05	0.161	ha	R= 0.24	0.30
	WS-06	0.095	ha	R= 0.20	0.25
	WS-07	0.169	ha	R= 0.27	0.34
	WS-08	0.201	ha	R= 0.80	0.99
	WS-09	0.130	ha	R= 0.86	1.00
	WS-10	1.033	ha	R= 0.27	0.33
	WS-11	0.929	ha	R= 0.30	0.37
	WS-12	0.333	ha	R= 0.50	0.63
	WS-13	0.285	ha	R= 0.26	0.33
	WS-14	0.147	ha	R= 0.76	0.95
Total Flow to Storm Stub =		4.149	ha	$\sum R = 0.42$	0.53
Roof Top	WS-15 (Controlled Rooftop Area)	0.711	ha	R= 0.90	1.00
	Total Un-Contolled =	0.711	ha	$\sum R = 0.90$	1.00

Post-development Stormwater Management

$I_{100} = 1735.688 / (T_d + 6.014)^{0.820}$
a = 1735.688
b = 0.82
C = 6.014

Time (min)	Intensity (mm/hr)	Rooftop Storage			Overland Storage			Uncontrolled Runoff (L/s)	Total Release Rate (L/s)	Height on Roof (m)
		Controlled Runoff (L/s)	Storage Volume (m ³)	Controlled Release Rate (L/s)	Controlled Runoff** (L/s)	Storage Volume (m ³)	Controlled Release Rate (L/s)			
10	178.6	352.94	180	52.89	1143.76	224	770.0	0.00	823	0.101
20	120.0	237.09	210	61.88	794.69	30	770.0	0.00	832	0.118
30	91.9	181.58	213	63.47	624.72	0	770.0	0.00	833	0.120
40	75.1	148.53	205	62.94	522.02	0	770.0	0.00	833	0.116
50	64.0	126.41	195	61.35	452.07	0	770.0	0.00	831	0.110
60	55.9	110.48	188	58.18	399.65	0	770.0	0.00	828	0.106
70	49.8	98.41	180	55.53	359.71	0	770.0	0.00	826	0.101
80	45.0	88.93	173	52.89	327.75	0	770.0	0.00	823	0.097
90	41.1	81.26	167	50.24	301.40	0	770.0	0.00	820	0.094
100	37.9	74.92	164	47.60	279.16	0	770.0	0.00	818	0.092
110	35.2	69.58	152	46.54	261.60	0	770.0	0.00	817	0.086
120	32.9	65.02	148	44.43	245.39	0	770.0	0.00	814	0.083
130	30.9	61.07	171	39.14	227.90	0	770.0	0.00	809	0.096

Infiltration Gallery - 280m

Pipe Storage 13.74 m³
 Granular Storage 166.6 m³
Total Available Storage = 180.31 m³

40% Void
refer to Drawing C401 for detail

Rooftop Controls

Control-Flo Roof Drain Rate = 136 L/min
 Max HWL = 0.150 m
 Control-Flo Roof Drain Rate = 15.11 L/s-m
 # of roof drains = 35
 Max Roof Storage = 212.6 m³
 Height = 0.120 m
 Max Roof Rate = 63.47 L/s

Onsite Stormwater Retention

Total Storage Required = 224.25 m³
 Rooftop Ponding = 212.61 m³
 Pipe Storage = 104.88 m³
 CB/MH Storage = 16.55 m³
 Infiltration Gallery = 180.00 m³
Total Available Storage = 301.42 m³

refer to Storm Sewer Design Sheet
refer to Storm Sewer Design Sheet
refer to Drawing C401



LRL File No. 170364
Project: Public High School Barrhaven Centre
Location: 4005 Strandherd Drive, Barrhaven, Ottawa
Date: January 16, 2019
Designed: G. Brunet
Checked: J.C. Lalonde
Drawing Ref.: C401

**Stormwater Management
Design Sheet**

STORM - 5 YEAR

Runoff Equation

$Q = 2.78CIA \text{ (L/s)}$
 C = Runoff coefficient
 I = Rainfall intensity (mm/hr) = $A / (Td + C)^B$
 A = Area (ha)
 T_c = Time of concentration (min)

Pre-Development Catchments within Development Area

Allowable Release Rate

5 Year Pre-Development Flow Rate

$I_s = 998.071 / (Td + 6.053)^{0.814}$ **a = 998.071** **b = 0.814** **C = 6.053**
Allowable Release Rate = 884.00 L/s As Per JL Richards, Harmony Stage 1 Report Dated July 2017

Post-development Stormwater Management

				ΣR_5	ΣR_{100}
Total Site Area =		4.860	ha	$\Sigma R =$	0.49
Controlled	WS-01	0.059	ha	R=	0.90
	WS-02	0.105	ha	R=	0.23
	WS-03	0.281	ha	R=	0.73
	WS-04	0.221	ha	R=	0.90
	WS-05	0.161	ha	R=	0.24
	WS-06	0.095	ha	R=	0.20
	WS-07	0.169	ha	R=	0.27
	WS-08	0.201	ha	R=	0.80
	WS-09	0.130	ha	R=	0.86
	WS-10	1.033	ha	R=	0.27
	WS-11	0.929	ha	R=	0.30
	WS-12	0.333	ha	R=	0.50
	WS-13	0.285	ha	R=	0.26
	WS-14	0.147	ha	R=	0.76
Total Flow to Storm Stub =		4.149	ha	$\Sigma R =$	0.42
Roof Top	WS-15 (Controlled Rooftop Area)	0.711	ha	R=	0.90
	Total Un-Controlled =	0.711	ha	$\Sigma R =$	0.90

5 Year Stormwater Management Calculations

$I_s = 998.071 / (Td + 6.053)^{0.814}$ **a = 998.071** **b = 0.814** **C = 6.053**

Time (min)	Intensity (mm/hr)	Rooftop Storage			Overland Storage			Uncontrolled Runoff (L/s)	Total Release Rate (L/s)	Height on Roof (m)
		Controlled Runoff (L/s)	Storage Volume (m ³)	Controlled Release Rate (L/s)	Controlled Runoff** (L/s)	Storage Volume (m ³)	Controlled Release Rate (L/s)			
10	104.2	185.35	95	27.14	536.38	0	770.00	0.00	797.14	0.053
20	70.3	124.97	111	32.36	375.71	0	770.00	0.00	802.36	0.063
30	53.9	95.93	113	32.88	296.45	0	770.00	0.00	802.88	0.064
40	44.2	78.60	111	32.36	248.31	0	770.00	0.00	802.36	0.062
50	37.7	66.98	107	31.32	215.34	0	770.00	0.00	801.32	0.060
60	32.9	58.60	102	30.27	191.28	0	770.00	0.00	800.27	0.057
70	29.4	52.25	97	29.23	172.78	0	770.00	0.00	799.23	0.054
80	26.6	47.25	94	27.66	157.48	0	770.00	0.00	797.66	0.053
90	24.3	43.21	90	26.62	145.33	0	770.00	0.00	796.62	0.050
100	22.4	39.86	86	25.57	135.09	0	770.00	0.00	795.57	0.048
110	20.8	37.04	83	24.53	126.30	0	770.00	0.00	794.53	0.046
120	19.5	34.63	80	23.49	118.63	0	770.00	0.00	793.49	0.045
130	18.3	32.54	79	22.44	111.86	0	770.00	0.00	792.44	0.044
260	10.6	18.85	0	19.83	71.63	0	770.00	0.00	789.83	0.000

Onsite Stormwater Retention

Total Storage Required = 0.00 m³
 Rooftop Ponding = 113.49 m³
 Pipe Storage = 104.88 m³ refer to Storm Sewer Design Sheet
 CB/MH Storage = 16.55 m³ refer to Storm Sewer Design Sheet
 Infiltration Gallery = 180.00 m³ refer to Drawing C401
Total Available Storage = 301.42 m³

Rooftop Controls

Control-Flo Roof Drain Rate = 136 L/min
 Max HWL = 0.152 m
 Control-Flo Roof Drain Rate = 14.91 L/s-m
 # of roof drains = 35
 Max Roof Storage = 113.5 m³
 Height = 0.064 m
 Max Roof Rate = 32.88 L/s

APPENDIX D
Supporting Documents



HARMONY STAGE 1
4005 STRANDHERD DRIVE
CITY OF OTTAWA
MINTO COMMUNITIES INC.
JLR NO. 24051-01

STORM SEWER DESIGN SHEET

Designed by: J.W.

Checked by: K.F.

Date: July 2017

Manning's Coefficient, n =	0.013
IDF CURVE =	2 Year

Denotes Existing Storm Sewer (Mattamy Barrhaven Mews) - Per IBI As-Constructed Drawings dated February 2010

STREET	Maintenance Hole Number FROM TO		DRAINAGE AREAS											In Pipe		2 YR PEAK FLOW				5 YR PEAK FLOW				TOTAL		PLUG FLOW		SEWER DATA											Residual Capacity Q ₃₀ , Q ₅₀ (L/s)	UPSTREAM				DOWNSTREAM			
			0.30	0.53	0.72	0.75	0.76	0.80	0.90	Total Area	Cum. Area 2 YR (ha)	Cum. Area 5 YR (ha)	Inlet Time (min.)	Flow Time (min.)	2.78AR	Cum. 2.78AR	2 Yr Intensity (mm/hr)	Peak Flow (L/s)	2.78AR	Cum. 2.78AR	5 Yr Intensity (mm/hr)	Peak Flow (L/s)	Peak Design Flow (L/s)	Peak ICD Flow (L/s)	Dia (mm)	H (mm)	W (mm)	Slope (%)	Q full (L/s)	V full (m/s)	Length (m)	Center Line	Obvert	Invert	Cover	Center Line	Drop	Obvert		Invert	Cover						
			2 Yr	5 Yr	2.78AR	Cum. 2.78AR	2 Yr Intensity (mm/hr)	Peak Flow (L/s)	2.78AR	Cum. 2.78AR	5 Yr Intensity (mm/hr)	Peak Flow (L/s)	Peak Design Flow (L/s)	Peak ICD Flow (L/s)	Dia (mm)	H (mm)	W (mm)	Slope (%)	Q full (L/s)	V full (m/s)	Length (m)	Center Line	Obvert	Invert	Cover	Center Line	Drop	Obvert	Invert	Cover																	
Commercial (Block 105)	Stub	MH120						0.76		0.76	0.00	0.76	10.00	0.42					1.90	1.90	104.19	198.13	198.13	235.0	600			0.15	248.09	0.85	21.6	50.0	94.34	91.835	91.225	2.51	94.24	0.00	91.803	91.193	2.44						
Chapman Mills Drive	MH120	MH121			0.55				0.55	0.00	1.31	10.42	2.16					1.10	3.00	102.01	306.28	306.28	135.0	675			0.15	339.63	0.92	119.2	33.4	94.24	91.803	91.117	2.44	94.41	-0.34	91.624	90.938	2.79							
Future Institutional Block	Stub	MH121			4.86				4.86	0.00	4.86	10.00	0.14					10.13	10.13	104.19	1055.80	1055.80	884.0	950			0.25	1424.40	1.59	13.8	368.6	94.41	92.001	90.934	2.41	94.32	0.00	91.967	90.900	2.35							
Chapman Mills Drive	MH123	MH124			0.34				0.34	0.00	0.34	10.00	1.69					0.68	0.68	104.19	70.91	70.91	30.0	450			0.20	133.02	0.81	82.2	62.1	94.30	91.406	90.949	2.89	93.45	0.00	91.242	90.785	2.21							
High Density (Block 118) Chakra (Street No. 6)	Stub	MH125			0.10		0.32		0.10	0.32	0.00	0.32	10.00	0.19				0.71	0.71	104.19	74.15	74.15	89.0	375			0.35	108.21	0.95	10.6	34.1	94.40	91.588	91.207	2.81	94.28	0.06	91.551	91.170	2.73							
Chapman Mills Drive	MH123	MH122			0.19				0.19	0.10	0.51	11.06	0.82		0.20	72.95	14.60	0.38	1.09	98.89	107.98	122.59	48.0	600			0.15	248.09	0.85	41.8	125.5	94.30	91.316	90.706	2.98	94.18	0.00	91.253	90.644	2.93							
Chapman Mills Drive	MH122	MH121								0.10	0.51	11.88	0.63		0.20	70.26	14.06	1.09	95.20	103.95	118.02	0.0	600			0.15	248.09	0.85	32.3	130.1	94.18	91.253	90.644	2.93	94.32	-0.76	91.205	90.595	3.12								
Clarity (Street No. 5)	MH121	MH115			0.34				0.34	0.44	6.68	12.58	1.22	0.68	0.88	68.13	60.00		14.23	92.28	1312.88	1372.88	54.0	1350			0.15	2156.55	1.46	106.5	783.7	94.32	91.967	90.595	2.35	94.22	0.00	91.807	90.435	2.41							
Park (Block 117)	Stub	MH115	1.53						1.53	0.00	1.53	10.00	0.27					1.28	1.28	104.19	132.95	132.95	84.0	450			0.25	148.72	0.91	14.8	15.8	94.33	91.387	90.929	2.94	94.21	-0.46	91.350	90.893	2.86							
Clarity (Street No. 5)	MH115	MH115A	0.42	0.41					0.83	1.27	8.21	13.80	0.88	1.44	2.32	64.76	150.24		15.50	87.65	1358.87	1509.12	66.0	1350			0.15	2156.55	1.46	77.3	647.4	94.22	91.807	90.435	2.41	94.10	-0.08	91.691	90.319	2.41							
Waterlilly Way	MH118	MH117	0.17	0.39					0.56	0.56	0.00	10.00	1.49	1.03	1.03	76.81	79.19				79.19	62.0	600			0.20	286.47	0.98	87.5	207.3	94.50	92.214	91.604	2.29	94.30	0.00	92.039	91.429	2.26								
Waterlilly Way	MH117	MH116		0.34					0.34	0.90	0.00	11.49	1.21	0.68	1.71	71.54	122.44				122.44	52.0	675			0.20	392.18	1.06	77.3	269.7	94.40	92.039	91.353	2.36	94.30	0.00	91.884	91.198	2.42								
Easement (Block 110)	MH116	MH115A								0.90	0.00	12.70	1.41		1.71	67.79	116.03				116.03	0.0	675			0.15	339.63	0.92	77.9	223.6	94.16	91.884	91.198	2.28	94.32	0.00	91.767	91.081	2.55								
Clarity (Street No. 5)	MH115A	MH113	0.46						0.46	2.63	8.21	14.68	0.43	0.68	4.71	62.53	294.48		15.50	84.60	1311.58	1606.07	0.0	1500			0.15	2856.14	1.57	40.4	1250.1	94.22	91.767	90.243	2.45	94.10	0.00	91.707	90.183	2.39							
Namaste (Street No. 4)	MH114	MH113	0.11	0.42					0.53	0.53	0.00	10.00	1.65	1.00	1.00	76.81	77.02				77.02	66.0	600			0.20	286.47	0.98	96.9	209.5	94.17	91.603	90.994	2.57	94.10	-0.30	91.409	90.800	2.69								
Clarity (Street No. 5)	MH113	MH110		0.24					0.24	3.40	8.21	15.11	0.84	0.48	6.19	61.51	380.89		15.50	83.20	1289.87	1670.76	36.0	1500			0.15	2856.14	1.57	78.9	1185.4	94.10	91.707	90.183	2.39	94.02	0.00	91.588	90.064	2.43							
Waterlilly Way	MH109A	EX. 21		0.13					0.13	0.13	0.00	10.00	1.65	0.26	0.26	76.81	19.99				19.99	18.0	300			0.35	59.68	0.82	80.8	39.7	94.60	92.393	92.088	2.21	94.77	0.00	92.110	91.805	2.66								
Waterlilly Way	EX. 21	MH109		0.17		0.18			0.35	0.48	0.00	11.65	0.96	0.72	0.98	71.01	69.65				69.65	--	300			0.33	57.95	0.80	45.9	-11.7	94.77	92.110	91.805	2.66	95.00	0.45	91.959	91.654	3.04								
Lilthe (Street No. 3)	MH109	MH110		0.22					0.22	0.70	0.00	12.60	1.27	0.44	1.42	68.07	96.74				96.74	34.0	450			0.35	175.96	1.07	81.7	79.2	95.00	91.508	91.051	3.49	94.02	-0.37	91.222	90.765	2.80								
Lilthe (Street No. 3)	MH112	MH111								0.00	0.00	10.00	1.30								0.00	0.0	375			0.25	91.46	0.80	62.7		94.14	91.545	91.164	2.59	93.80	0.00	91.388	91.007	2.41								
Lilthe (Street No. 3)	MH111	MH110		0.27	0.53				0.80	0.80	0.00	11.30	1.16	1.46	1.46	72.14	105.23				105.23	84.0	600			0.16	256.22	0.88	60.9	151.0	93.80	91.388	90.779	2.41	94.02	-0.30	91.291	90.681	2.73								
Clarity (Street No. 5)	MH110	MH110A							4.90	8.21	15.95	0.34		9.07	59.61	540.82		15.50	80.61	1249.67	1790.49	0.0	1500			0.15	2856.14	1.57	31.6	1065.6	94.02	91.588	90.064	2.43	93.68	0.00	91.541	90.017	2.14								
Clarity (Street No. 5)	MH110A	MH106		0.23					5.13	8.21	16.29	0.47	0.46	9.53	58.89	561.37		15.50	79.62	1234.34	1795.71	34.0	1500			0.15	2856.14	1.57	44.0	1060.4	93.68	91.541	90.017	2.14	93.94	-0.04	91.475	89.951	2.46								
Octave (Street No. 2)	MH108	MH107		0.33					0.33	0.33	0.00	10.00	1.30	0.49	0.49	76.81	37.34				37.34	0.0	375			0.25	91.46	0.80	62.7	54.1	94.02	91.789	91.388	2.25	93.75	0.00	91.612	91.231	2.14								
Octave (Street No. 2)	MH107	MH106		0.56					0.56	0.89	0.00	11.30	1.33	1.12	1.61	72.14	115.94				115.94	90.0	525			0.16	179.46	0.80	64.3	63.5	93.75	91.612	91.079	2.14	93.94	0.00	91.510	90.976	2.43								
Clarity (Street No. 5)	MH106	MH102		0.40	0.24				0.64	6.66	8.21	16.75	0.73	1.07	12.21	57.91	707.11		15.50	78.29	1213.69	1920.81	36.0	1585	2495	0.15	5749.47	1.87	82.2	3828.7	93.94	91.513	89.913	2.43	93.86	0.00	91.390	89.790	2.47								
Waterlilly Way	MH109	EX. 20								0.00	0.00	10.00	0.16								0.00	--	300			0.33	57.95	0.80	7.7		95.00	91.960	91.656	3.04	94.96	-0.03	91.935	91.630	3.03								
Waterlilly Way	EX. 20	EX. 19		0.16		0.17			0.33	0.33	0.00	10.16	1.40	0.68	0.68	76.19	51.77				51.77	--	375			0.24	89.05	0.80	67.4	37.3	94.96	91.961	91.580	3.00	94.68	0.04	91.801	91.420	2.88								
Waterlilly Way	EX. 19	MH101							0.33	0.00	11.57	1.59		0.68	71.27	48.43				48.43	--	375			0.28	96.96	0.85	81.2	48.5	94.68	91.761	91.380	2.92	93.94	0.36	91.533	91.152	2.41									
Hamsa (Street No. 1)	MH101	MH102		0.19					0.19	0.52	0.00	13.16	1.42	0.38	1.06	66.49	70.46				70.46	28.0	450			0.25	148.72	0.91	77.2	78.3	94.00	91.171	90.714	2.83	93.86	-0.41	90.978	90.521	2.88								
Hamsa (Street No. 1)	MH102	MH103		0.22					0.22	7.40	8.21	17.49	0.33	0.44	13.71	56.46	774.00		15.50	76.29	1182.80	1956.79	32.0	1585	2495	0.15	5749.47	1.87	36.6	3792.7	93.86	91.390	89.790	2.47	93.37	-0.38	91.335	89.735	2.04								
Hamsa (Street No. 1)	MH105	MH103		0.32	0.25				0.57	0.57	0.00	10.00	1.89	0.97	0.97	76.81	74.65				74.65	40.0	525			0.16	179.46																				

APPENDIX E
Engineering Drawings

EROSION AND SEDIMENT CONTROL MEASURES
 ** CONTRACTOR IS RESPONSIBLE FOR ALL INSTALLATION, MONITORING, REPAIR AND REMOVAL OF ALL EROSION AND SEDIMENT CONTROL FEATURES **

1. PRIOR TO START OF CONSTRUCTION:




- PRIOR TO THE REMOVAL OF ANY VEGETATIVE COVER, MOVING OF SOIL, AND CONSTRUCTION
- INSTALL SILT FENCE IMMEDIATELY DOWNSTREAM FROM AREAS TO BE DISTURBED (SEE PLAN FOR LOCATION)
- INSTALL GEOTEXTILE INSERTS WITH AN OVERFLOW WALL, THE DOWNSTREAM CATCH BASINS AND MANHOLES
- INSTALL SILTSTACK FILTERS IN ALL CONCRETE CATCH BASIN STRUCTURES
- INSPECT MEASURES IMMEDIATELY AFTER INSTALLATION.

2. DURING CONSTRUCTION:

- WORK TO BE DONE IN THE VICINITY OF MAJOR WATERWAYS TO BE CARRIED OUT FROM JULY TO SEPTEMBER ONLY.
- MINIMIZE THE EXTENT OF DISTURBED AREAS AND THE DURATION OF EXPOSURE.
- PROTECT DISTURBED AREAS FROM RUNOFF.
- PROVIDE TEMPORARY COVER SUCH AS SEEDING OR MULCHING IF DISTURBED AREA WILL NOT BE REHABILITATED WITHIN 30 DAYS.
- INSPECT SILT FENCES, FILTER CLOTHS AND CATCH BASIN SLUMPS WEEKLY AND AFTER EVERY MAJOR STORM EVENT. CLEAN AND REPAIR WHEN NECESSARY.
- CONSTRUCT SWALES AS PER DETAIL.
- PLAN TO BE REVIEWED AND REVISED AS REQUIRED DURING CONSTRUCTION.
- EROSION CONTROL FENCING TO BE ALSO INSTALLED AROUND THE BASE OF ALL STOCKPILES.
- DO NOT LOCATE TOPSOIL PILES AND EXCAVATION MATERIAL CLOSER THAN 2.5M FROM ANY PAVED SURFACE, OR ONE WHICH IS TO BE PAVED BEFORE THE PILE IS REMOVED. ALL TOPSOIL PILES ARE TO BE SEEDED IF THEY ARE TO REMAIN ON SITE LONG ENOUGH FOR SEEDS TO GROW (LONGER THAN 30 DAYS).
- CONTROL WIND BLOWN DUST OR SOIL TO ACCEPTABLE LEVELS BY SEEDING TOPSOIL PILES AND OTHER AREAS TEMPORARILY PROVIDE WATERING AS REQUIRED.
- ALL EROSION CONTROL STRUCTURE TO REMAIN IN PLACE UNTIL ALL DISTURBED GROUND SURFACES HAVE BEEN STABILIZED EITHER BY PAVING OR RESTORATION OF VEGETATIVE GROUND COVER.
- NO ALTERNATE METHODS OF EROSION PROTECTION SHALL BE PERMITTED UNLESS APPROVED BY THIS CONSULTING ENGINEER AND THE CITY DEPARTMENT OF PUBLIC WORKS.
- CONTRACTOR RESPONSIBLE FOR CITY ROADWAY AND SIDEWALK TO BE CLEANED OF ALL SEDIMENT FROM VEHICULAR TRACKING ETC. AT THE END OF EACH WORK DAY.
- PROVIDE GRAVEL ENTRANCE WHEREVER EQUIPMENT LEAVES THE SITE TO PREVENT MUD TRACKING ONTO PAVED SURFACES. GRAVEL BED SHALL BE A MINIMUM OF 15m LONG, 4M WIDE AND 0.5M DEEP AND SHALL CONSIST OF COARSE 50mm CRUSHER RUN LIMESTONE MATERIAL. MAINTAIN GRAVEL ENTRANCE IN CLEAN CONDITION.
- DURING WET CONDITIONS, TIRES OF ALL VEHICLES/QUIPMENT LEAVING THE SITE ARE TO BE SCRAPED.
- ANY MUD/MATERIAL TRACKED ONTO THE ROAD SHALL BE REMOVED IMMEDIATELY BY HAND OR RUBBER TIRE LOADER. TAKE ALL NECESSARY STEPS TO PREVENT BUILDING MATERIAL, CONSTRUCTION DEBRIS OR WASTE BEING SPILLED OR TRACKED ONTO ADJACENT PROPERTIES OR PUBLIC STREETS DURING CONSTRUCTION AND PROCEED IMMEDIATELY TO CLEAN UP ANY AREAS SO AFFECTED.
- THE CONTRACTOR SHALL IMPLEMENT BEST MANAGEMENT PRACTICES TO PROVIDE PROTECTION OF THE AREA DRAINAGE SYSTEM AND THE RECEIVING WATER COURSE. DURING CONSTRUCTION ACTIVITIES, THE CONTRACTOR ACKNOWLEDGES THAT FAILURE TO IMPLEMENT APPROPRIATE EROSION AND SEDIMENT CONTROL MEASURES MAY BE SUBJECT TO PENALTIES IMPOSED BY ANY APPLICABLE REGULATORY AGENCY.


3. AFTER CONSTRUCTION:

- PROVIDE PERMANENT COVER CONSISTING OF TOPSOIL AND SEED TO DISTURBED AREAS
- REMOVE STORM DRAIN FLOW CHECK DAMS, SILT FENCES AND FILTER CLOTHS ON CATCH BASINS AND MANHOLE COVERS AFTER DISTURBED AREAS HAVE BEEN REHABILITATED AND STABILIZED.
- INSPECT AND CLEAN CATCH BASIN SLUMPS AND STORM SEWERS



LEGEND:

	EXISTING PROPERTY LINE TO REMAIN
	PROPOSED CURB
	PROPOSED DEPRESSED CURB
	PROPOSED TERRACING (3.1 MRL)
	PROPOSED DOOR ENTRANCE/EXIT
	PROPOSED GRASS AS PER L-001
	PROPOSED CONCRETE FEATURES/SLAB
	PROPOSED SILT FENCE AS PER OPSD 219.110
	PROPOSED CHAIN LINK FENCE
	PROPOSED HEAVY DUTY ASPHALT
	PROPOSED LIGHT DUTY ASPHALT
	PROPOSED GRASS AS PER L-001 (FUTURE PARKING LOT AREA)
	PROPOSED INFILTRATION GALLERY
	PROPOSED ELEVATION
	PROPOSED HIGH POINT ELEVATION
	PROPOSED ELEVATION
	PROPOSED BOTTOM OF CURB ELEVATION
	PROPOSED TOP OF CURB ELEVATION
	PROPOSED TOP OF SIDEWALK ELEVATION
	PROPOSED BOTTOM OF SIDEWALK ELEVATION
	PROPOSED STRAIGHTENING ELEVATION TO BE COMPLETE BY 2022
	MATCH INTO EXISTING ELEVATION
	EXISTING ELEVATION
	PROPOSED OVERLAND MAJOR FLOW ROUTE
	PROPOSED 100mm PERFORATED SUBDRAIN
	PROPOSED STORM SEWER
	PROPOSED SANITARY SEWER
	PROPOSED WATERMAIN
	PROPOSED HYDRANT LEAD
	EXISTING STORM SEWER
	EXISTING SANITARY SEWER
	EXISTING WATERMAIN
	EXISTING MANHOLE
	EXISTING CATCHBASIN
	PROPOSED CATCHBASIN-MANHOLE/CATCHBASIN
	PROPOSED STC300
	PROPOSED CURB STOP
	PROPOSED FIRE HYDRANT
	PROPOSED PIPE INSULATION
	PROPOSED 100 YEAR HIGH WATER LEVEL
	STORM WATERSHED EXTENT
	WATERSHED NAME
	RUNOFF COEFFICIENT
	AREA IN HECTARES



no.	date	revision / issue	by
09	2018/09/05	ISSUED AS PER ADDENDUM NO.02	M.L.
08	2018/09/29	ISSUED AS PER ADDENDUM NO.01	M.L.
07	2018/07/24	ISSUED TENDER	G.B.
06	2018/07/03	ISSUED AS PER CITY COMMENTS	G.B.
05	2018/05/28	ISSUED AS PER COMMENTS	G.B.
04	2018/05/13	ISSUED FOR PERMIT	G.B.
03	2018/02/21	RE-ISSUED FOR SPA	G.B.
02	2018/10/01	RE-ISSUED FOR SPA	G.B.
01	2018/09/29	ISSUE FOR SPA	G.B.

grc architects
 47 Clarence Street, Suite 401,
 Ottawa, Ontario K1R 0R1
 613.241.8203, 613.241.4180
 info@grcarchitects.com www.grcarchitects.com

consultant
LRJ
 ENGINEERING | INFRASTRUCTURE
 5430 Carleton Road | Ottawa, ON, K1J 9G2
 www.lrj.ca (613) 842-3434

professional stamp

project title
NOUVELLE ÉCOLE SECONDAIRE BARRHAVEN
 Barrhaven, Ontario

drawing title
EROSION AND SEDIMENT CONTROL PLAN

date	25/01/2018	job no.	1817
scales	1:400	drawing no.	C101
drawn	M.L.	approved	J.C.L.
plot date	25/01/2018		

1. DO NOT SCALE THIS DRAWING.
 2. CONTRACTOR TO VERIFY ALL DIMENSIONS AND NOTIFY THE ARCHITECT OF ANY DISCREPANCIES BEFORE WORK COMMENCES.
 3. THIS DRAWING TO BE READ IN CONJUNCTION WITH THE FOLLOWING DRAWINGS: STRUCTURAL, MECHANICAL, ELECTRICAL.

NOTES: GENERAL


- CONTRACTOR IS RESPONSIBLE FOR ALL LAYOUT FOR CONSTRUCTION PURPOSES.
- ALL ELEVATIONS ARE GEODETIC AND UTILIZE METRIC UNITS.
- JOB BENCH MARK - CONFIRM WITH L.R. PRIOR TO UTILIZATION.
- ALL GROUND SURFACES SHALL BE EVENLY GRADED WITHOUT FONDING AREAS AND WITHOUT LOW POINTS EXCEPT WHERE APPROVED WORK CATCH BASIN OUTLETS AND/OR STORM DETENTION AREAS ARE PROVIDED.
- STRIP AND REMOVE ALL TOPSOIL FROM IMPROVED AREAS.
- COORDINATE AND SCHEDULE ALL WORK WITH OTHER TRADES AND CONTRACTORS.
- ALL EDGES OF DISTURBED PAVEMENT SHALL BE SAW CUT TO FORM A CLEAN STRAIGHT LINE PRIOR TO PLACING NEW PAVEMENT. PAVEMENT REINSTATEMENT SHALL BE WITH STEP JOINTS OF 500mm WIDTH MINIMUM.
- CURBS TO BE BARRIER, CONSTRUCTED AS PER OPSD 600.116.
- ALL MATERIAL SUPPLIED AND PLACED FOR PARKING LOT AND ACCESS ROAD CONSTRUCTION SHALL BE TO OPSD STANDARDS AND SPECIFICATIONS UNLESS OTHERWISE NOTED. CONSTRUCTION TO OPSD 206.10 & 214. MATERIALS TO OPSD 100.1, 100.3 & 100.5.
- ABUTTING PROPERTY GRADE TO BE MATCHED.
- OBTAIN AND PAY FOR ALL NECESSARY PERMITS AND APPROVALS FROM THE MUNICIPAL AUTHORITIES PRIOR TO COMMENCING CONSTRUCTION.
- MINIMIZE DISTURBANCE TO EXISTING VEGETATION DURING THE EXECUTION OF ALL WORKS.
- FILTER FABRIC TO BE INSTALLED AND MAINTAINED BETWEEN THE FRAME AND COVER OF ALL CATCHBASINS, CATCHBASIN MANHOLES AND MANHOLES DURING THE CONSTRUCTION PERIOD TO MINIMIZE SEDIMENTS ENTERING THE STORM SEWER SYSTEM. ALL GRASSED AREAS MUST BE COMPLETED PRIOR TO THE REMOVAL OF THE FILTER FABRIC IN THE DRAINAGE STRUCTURES.
- REMOVE FROM SITE ALL EXCESS EXCAVATED MATERIAL UNLESS OTHERWISE DIRECTED FROM THE ENGINEER. EXCAVATE AND REMOVE ALL ORGANIC MATERIAL AND DEBRIS IF ANY LOCATED WITHIN THE PROPOSED BUILDING, PARKING AND ROADWAY LOCATIONS.
- THE APPROVAL OF THIS PLAN DOES NOT EXEMPT THE CONTRACTOR FROM THE REQUIREMENTS TO OBTAIN THE VARIOUS PERMITS/APPROVALS REQUIRED TO COMPLETE A CONSTRUCTION PROJECT, SUCH AS BUT NOT LIMITED TO: ROAD CUT PERMITS, SEWER PERMITS, WATER PERMIT, ETC.
- AT PROPOSED UTILITY CONNECTION POINTS AND CROSSINGS (I.E. STORM SEWER, SANITARY SEWER, WATER, ETC.) THE CONTRACTOR SHALL DETERMINE THE PRECISE LOCATION AND DEPTH OF EXISTING UTILITIES AND REPORT ANY DISCREPANCIES OR CONFLICTS TO THE ENGINEER BEFORE COMMENCING WORK.
- ALL SIDEWALK CONSTRUCTION TO BE AS PER OPSD 310.010 & OPSD 310.050.

NOTES: SEWERS

- SEWER BEDDING AS PER TRENCH DETAIL WITH GRANULAR 'A' BEDDING COMPACTED TO 90% OF ITS SPREAD.
- ALL WORK SHALL BE PERFORMED AS APPLICABLE IN ACCORDANCE WITH OPSD 407 AND 410.
- CONTRACTOR TO CONFIRM ELEVATION OF EXISTING SEWERS AT PROPOSED CONNECTION POINTS AND REPORT ANY DISCREPANCIES TO THE ENGINEER BEFORE COMMENCING ANY WORK.
- ALL SEWERS WITH LESS THAN 20m OF COVER ARE SUBJECT TO INSULATION DETAIL.

LEGEND:

- EXISTING PROPERTY LINE TO REMAIN
- PROPOSED CURB
- PROPOSED DEPRESSIONED CURB
- PROPOSED TERRACING (3.1M)
- PROPOSED DOOR ENTRANCE EXIT
- PROPOSED CONCRETE FEATURES/SLAB
- PROPOSED SBT FENCE AS PER OPSD 216.110
- PROPOSED CHAIN LINK FENCE
- PROPOSED HEAVY DUTY ASPHALT
- PROPOSED LIGHT DUTY ASPHALT
- PROPOSED GRASS AS PER L-01 (FUTURE PARKING LOT AREA)
- PROPOSED INFILTRATION GALLERY
- PROPOSED ELEVATION
- PROPOSED HIGH POINT ELEVATION
- PROPOSED ELEVATION
- PROPOSED BOTTOM OF CURB ELEVATION
- PROPOSED TOP OF CURB ELEVATION
- PROPOSED TOP OF SIDEWALK ELEVATION
- PROPOSED BOTTOM OF SIDEWALK ELEVATION
- PROPOSED STRAIGHTED ELEVATION TO BE COMPLETED BY 2022
- MATCH INTO EXISTING ELEVATION
- EXISTING ELEVATION
- PROPOSED OVERLAND MAJOR FLOW ROUTE
- PROPOSED 100mm PERFORATED SUBRAIN
- PROPOSED STORM SEWER
- PROPOSED SANITARY SEWER
- PROPOSED WATERMAIN
- PROPOSED HYDRANT LEAD
- EXISTING STORM SEWER
- EXISTING SANITARY SEWER
- EXISTING WATERMAIN
- EXISTING MANHOLE
- EXISTING CATCHBASIN
- PROPOSED CATCHBASIN-MANHOLE/CATCHBASIN
- PROPOSED STC300
- PROPOSED CURB STOP
- PROPOSED FIRE HYDRANT
- PROPOSED PIPE INSULATION
- PROPOSED 100 YEAR HIGH WATER LEVEL
- STORM WATERHEED EXIST
- WATERSHED NAME
- RUNOFF COEFFICIENT
- AREA IN HECTARES



no.	date	revision / issue	by
09	2018/09/05	ISSUED AS PER ADDENDUM NO.02	M.L.
08	2018/06/29	ISSUED AS PER ADDENDUM NO.01	M.L.
07	2018/07/24	ISSUED TENDER	G.B.
06	2018/07/03	ISSUED AS PER CITY COMMENTS	G.B.
05	2018/05/28	ISSUED AS PER COMMENTS	G.B.
04	2018/05/13	ISSUED FOR PERMIT	G.B.
03	2018/12/21	RE-ISSUED FOR SPA	G.B.
02	2018/10/01	RE-ISSUED FOR SPA	G.B.
01	2018/09/28	ISSUE FOR SPA	G.B.

grc architects
 47 Clarence Street, Suite 401,
 Ottawa, Ontario K1M 0K1
 613.241.8203, 613.241.4180
 info@grcarchitects.com www.grcarchitects.com

LRJ
 ENGINEERING | INSPECTION
 5400 Carleton Road | Ottawa, ON, K1J 9G2
 www.lrj.ca 1(877)842-3434

Professional stamp of J.C.L., Professional Engineer, No. 10108, Ontario.


project title
NOUVELLE ÉCOLE SECONDAIRE BARRHAVEN
 Barrhaven, Ontario

drawing title
SERVICING PLAN

date	25/01/2018	job no.	1817
scales	1:400	drawing no.	C401
drawn	M.L.	approved	J.C.L.
plot date	25/01/2018		

CROSSING TABLE

Crossing #	WM (obv.)	STM (inv.)	STM (inv.)	SAN (obv.)	Depth Separation (m)
CR-01	91.45	92.10			0.45
CR-02		91.93	91.22	90.80	0.44
CR-03			91.09	90.55	0.54
CR-04	92.20		91.00	90.22	0.53



DETAIL 01 - INFILTRATION GALLERY DETAIL



LEGEND:

- EXISTING PROPERTY LINE TO REMAIN
- PROPOSED CURB
- PROPOSED DEPRESSION CURB
- PROPOSED TERRACING (3:1 MIN.)
- PROPOSED DOOR ENTRANCE/EXIT
- PROPOSED GRASS AS PER L-001
- PROPOSED CONCRETE FEATURES/SLAB
- PROPOSED SILT FENCE AS PER OPSD 210.1.10
- PROPOSED CHAIN LINK FENCE
- PROPOSED HEAVY DUTY ASPHALT
- PROPOSED LIGHT DUTY ASPHALT
- PROPOSED GRASS AS PER L-001 (FUTURE PARKING LOT AREA)
- PROPOSED INFILTRATION GALLERY
- PROPOSED ELEVATION
- PROPOSED HIGH POINT ELEVATION
- PROPOSED ELEVATION
- PROPOSED BOTTOM OF CURB ELEVATION
- PROPOSED TOP OF CURB ELEVATION
- PROPOSED TOP OF SIDEWALK ELEVATION
- PROPOSED BOTTOM OF SIDEWALK ELEVATION
- PROPOSED STRANDHERD ELEVATION TO BE COMPLETE BY 2022
- MATCH INTO EXISTING ELEVATION
- EXISTING ELEVATION
- PROPOSED OVERLAND MAJOR FLOW ROUTE
- PROPOSED 100mmØ PERFORATED SUBDRAIN
- PROPOSED STORM SEWER
- PROPOSED SANITARY SEWER
- PROPOSED WATERMAIN
- PROPOSED HYDRANT LEAD
- EXISTING STORM SEWER
- EXISTING SANITARY SEWER
- EXISTING WATERMAIN
- EXISTING MANHOLE
- EXISTING CATCHBASIN
- PROPOSED CATCHBASIN-MANHOLE/CATCHBASIN
- PROPOSED STC300
- PROPOSED CURB STOP
- PROPOSED FIRE HYDRANT
- PROPOSED PIPE INSULATION
- PROPOSED 100 YEAR HIGH WATER LEVEL
- STORM WATERSHED EXTENT
- WATERSHED NAME
- RUNOFF COEFFICIENT
- AREA IN HECTARES

09	2019/09/05	ISSUED AS PER ADDENDUM NO.02	M.L.
08	2019/06/29	ISSUED AS PER ADDENDUM NO.01	M.L.
07	2019/07/24	ISSUED TENDER	G.B.
06	2019/07/03	ISSUED AS PER CITY COMMENTS	G.B.
05	2019/05/28	ISSUED AS PER COMMENTS	G.B.
04	2019/05/13	ISSUED FOR PERMIT	G.B.
03	2018/12/21	RE-ISSUED FOR SPA	G.B.
02	2018/10/01	RE-ISSUED FOR SPA	G.B.
01	2018/09/25	ISSUE FOR SPA	G.B.
no.	date	revision / issue	by

grc architects
 47 Clarence Street, Suite 401,
 Ottawa, Ontario K1R 0R1
 613.241.8203, 613.241.4180
 info@grcarchitects.com www.grcarchitects.com

LRJ
 ENGINEERING | INSPECTION
 5430 Carleton Road | Ottawa, ON, K1J 9J2
 www.lrj.ca (613) 942-3434


Professional stamp

project title
NOUVELLE ÉCOLE SECONDAIRE BARRHAVEN
 Barrhaven, Ontario

drawing title
PRE-DEVELOPMENT WATERSHED PLAN

date	25/01/2018	job no.	1817
scales	1:400	drawing no.	C701
drawn	M.L.	approved	J.C.L.
plot date	25/01/2018		

1 DO NOT SCALE THIS DRAWING.
 2 CONTRACTOR TO VERIFY ALL DIMENSIONS AND NOTIFY THE ARCHITECT OF ANY DISCREPANCIES BEFORE WORK COMMENCES.
 3 THIS DRAWING TO BE READ IN CONJUNCTION WITH THE FOLLOWING DRAWINGS: STRUCTURAL, MECHANICAL, ELECTRICAL.



LEGEND:

- EXISTING PROPERTY LINE TO REMAIN
- PROPOSED CURB
- PROPOSED DEPRESSED CURB
- PROPOSED TERRACING (3.1 MIN.)
- PROPOSED DOOR ENTRANCE/EXIT
- PROPOSED GRASS AS PER L-001
- PROPOSED CONCRETE FEATURES/SLAB
- PROPOSED SILT FENCE AS PER OPSD 218.110
- PROPOSED CHAIN LINK FENCE
- PROPOSED HEAVY DUTY ASPHALT
- PROPOSED LIGHT DUTY ASPHALT
- PROPOSED GRASS AS PER L-001 (FUTURE PARKING LOT AREA)
- PROPOSED INFILTRATION GALLERY
- 50.00 PROPOSED ELEVATION
- 50.00P PROPOSED HIGH POINT ELEVATION
- 50.00 PROPOSED ELEVATION
- 50.00BC PROPOSED BOTTOM OF CURB ELEVATION
- 50.00TC PROPOSED TOP OF CURB ELEVATION
- 50.00TS PROPOSED TOP OF SIDEWALK ELEVATION
- 50.00BS PROPOSED BOTTOM OF SIDEWALK ELEVATION
- 50.00ST PROPOSED STRANDHERD ELEVATION TO BE COMPLETE BY 2022
- 50.00EX MATCH INTO EXISTING ELEVATION
- 50.00E EXISTING ELEVATION
- ➔ PROPOSED OVERLAND MAJOR FLOW ROUTE
- SUB SUB PROPOSED 100mmØ PERFORATED SUBDRAIN
- STM STM PROPOSED STORM SEWER
- SAN SAN PROPOSED SANITARY SEWER
- WTR WTR PROPOSED WATERMAIN
- HYD HYD PROPOSED HYDRANT LEAD
- STM STM EXISTING STORM SEWER
- SAN SAN EXISTING SANITARY SEWER
- WTR WTR EXISTING WATERMAIN
- EXISTING MANHOLE
- EXISTING CATCHBASIN
- PROPOSED CATCHBASIN-MANHOLE/CATCHBASIN
- PROPOSED STC300
- PROPOSED CURB STOP
- PROPOSED FIRE HYDRANT
- PROPOSED PIPE INSULATION
- PROPOSED 100 YEAR HIGH WATER LEVEL
- STORM WATERSHED EXTENT
- WS-XX WATERSHED NAME
- WS-XX RUNOFF COEFFICIENT
- WS-XX AREA IN HECTARES

09	2018/09/05	ISSUED AS PER ADDENDUM NO.02	M.L.
08	2018/06/29	ISSUED AS PER ADDENDUM NO.01	M.L.
07	2018/07/24	ISSUED TENDER	G.B.
06	2018/07/03	ISSUED AS PER CITY COMMENTS	G.B.
05	2018/05/28	ISSUED AS PER COMMENTS	G.B.
04	2018/05/13	ISSUED FOR PERMIT	G.B.
03	2018/02/21	RE-ISSUED FOR SPA	G.B.
02	2018/10/01	RE-ISSUED FOR SPA	G.B.
01	2018/09/25	ISSUE FOR SPA	G.B.
no.	date	revision / issue	by

grc architects
 47 Clarence Street, Suite 401,
 Ottawa, Ontario K1R 0K1
 613.241.8203, 613.241.4180
 info@grcarchitects.com www.grcarchitects.com

consultant
LRJ
 ENGINEERING | INFRASTRUCTURE
 5430 Carleton Road | Ottawa, ON, K1J 9G2
 www.lrj.ca 613.942.9434


professional stamp

project title
NOUVELLE ÉCOLE SECONDAIRE BARRHAVEN
 Barrhaven, Ontario

drawing title
POST-DEVELOPMENT WATERSHED PLAN

date	25/01/2018	job no.	1817
scales	1:400	drawing no.	C702
drawn	M.L.	approved	J.C.L.
plot date	25/01/2018		

1 DO NOT SCALE THIS DRAWING.
 2 CONTRACTOR TO VERIFY ALL DIMENSIONS AND NOTIFY THE ARCHITECT OF ANY DISCREPANCIES BEFORE WORK COMMENCES.
 3 THIS DRAWING TO BE READ IN CONJUNCTION WITH THE FOLLOWING DRAWINGS: STRUCTURAL, MECHANICAL, ELECTRICAL.



LEGEND:

- EXISTING PROPERTY LINE TO REMAIN
- PROPOSED CURB
- PROPOSED DEPRESSED CURB
- PROPOSED TERRACING (3.1 MIN.)
- PROPOSED DOOR ENTRANCE/EXIT
- PROPOSED CONCRETE FEATURES/SLAB
- PROPOSED SILT FENCE AS PER OPSD 210.110
- PROPOSED CHAIN LINK FENCE
- PROPOSED HEAVY DUTY ASPHALT
- PROPOSED LIGHT DUTY ASPHALT
- PROPOSED GRASS AS PER L-001 (FUTURE PARKING LOT AREA)
- PROPOSED INFILTRATION GALLERY
- 50.00 PROPOSED ELEVATION
- 50.00HP PROPOSED HIGH POINT ELEVATION
- 50.00 PROPOSED ELEVATION
- 50.00BC PROPOSED BOTTOM OF CURB ELEVATION
- 50.00TC PROPOSED TOP OF CURB ELEVATION
- 50.00TS PROPOSED TOP OF SIDEWALK ELEVATION
- 50.00BS PROPOSED BOTTOM OF SIDEWALK ELEVATION
- 50.00ST PROPOSED STRANDHERD ELEVATION TO BE COMPLETE BY 2022
- 50.00EX MATCH INTO EXISTING ELEVATION
- PROPOSED OVERLAND MAJOR FLOW ROUTE
- SUB — PROPOSED 100mmØ PERFORATED SUBDRAIN
- STM — PROPOSED STORM SEWER
- SAN — PROPOSED SANITARY SEWER
- WTR — PROPOSED WATERMAIN
- HYD — PROPOSED HYDRANT LEAD
- STM — EXISTING STORM SEWER
- SAN — EXISTING SANITARY SEWER
- WTR — EXISTING WATERMAIN
- EXISTING MANHOLE
- EXISTING CATCHBASIN
- PROPOSED CATCHBASIN-MANHOLE/CATCHBASIN
- PROPOSED STC300
- PROPOSED CURB STOP
- PROPOSED FIRE HYDRANT
- PROPOSED PIPE INSULATION
- PROPOSED 100 YEAR HIGH WATER LEVEL
- STORM WATERSHED EXTENT
- WS-XX WATERSHED NAME
- RUNOFF COEFFICIENT
- AREA IN HECTARES

CUP LEGEND:

- BELL — BELL PROPOSED UNDERGROUND BELL CABLE
- GAS — GAS PROPOSED UNDERGROUND GAS CABLE
- HYD — HYDRO PROPOSED UNDERGROUND HIGH VOLTAGE
- PROPOSED GAS METER LOCATION
- PROPOSED BELL PEDESTAL LOCATION

no.	date	revision / issue	by
09	2018/09/05	ISSUED AS PER ADDENDUM NO.02	M.L.
08	2018/06/29	ISSUED AS PER ADDENDUM NO.01	M.L.
07	2018/07/24	ISSUED TENDER	G.B.
06	2018/07/03	ISSUED AS PER CITY COMMENTS	G.B.
05	2018/05/28	ISSUED AS PER CITY COMMENTS	G.B.
04	2018/05/13	ISSUED FOR PERMIT	G.B.
03	2018/12/21	RE-ISSUED FOR SPA	G.B.
02	2018/10/01	RE-ISSUED FOR SPA	G.B.
01	2018/09/25	ISSUE FOR SPA	G.B.

grc architects
 47 Clarence Street, Suite 401,
 Ottawa, Ontario K1M 0K1
 (613) 241-1800, (613) 241-1180
 info@grcarchitects.com www.grcarchitects.com

consultant
LRJ
 ENGINEERING | INFRASTRUCTURE
 5430 Carleton Road | Ottawa, ON, K1J 9G2
 www.lrj.ca (613) 942-3434















professional stamp

project title
NOUVELLE ÉCOLE SECONDAIRE BARRHAVEN
 Barrhaven, Ontario

drawing title
COMPOSITE UTILITY PLAN

date	25/01/2018	job no.	1817
scales	1:400	drawing no.	C801
drawn	M.L.	approved	J.C.L.
plot date	25/01/2018		

1 DO NOT SCALE THIS DRAWING.
 2 CONTRACTOR TO VERIFY ALL DIMENSIONS AND NOTIFY THE ARCHITECT OF ANY DISCREPANCIES BEFORE WORK COMMENCES.
 3 THIS DRAWING TO BE READ IN CONJUNCTION WITH THE FOLLOWING DRAWINGS: STRUCTURAL, MECHANICAL, ELECTRICAL.



no.	date	revision / issue	by
09	2010/09/05	ISSUED AS PER ADDENDUM NO.02	M.L.
08	2010/06/29	ISSUED AS PER ADDENDUM NO.01	M.L.
07	2010/07/24	ISSUED TENDER	G.B.
06	2010/07/03	ISSUED AS PER CITY COMMENTS	G.B.
05	2010/05/28	ISSUED AS PER CITY COMMENTS	G.B.
04	2010/05/13	ISSUED FOR PERMIT	G.B.
03	2010/12/21	RE-ISSUED FOR SPA	G.B.
02	2010/10/01	RE-ISSUED FOR SPA	G.B.
01	2010/09/29	ISSUE FOR SPA	G.B.

grc architects
 47 Clarence Street, Suite 401,
 Ottawa, Ontario K1R 0R1
 (613) 241-8203, (613) 241-4180
 info@grcarchitects.com www.grcarchitects.com

consultant
LRJ
 ENGINEERING | INSURERS
 5430 Carleton Road | Ottawa, ON, K1J 9G2
 www.lrj.ca | (613) 942-3434

professional stamp


project title
NOUVELLE ÉCOLE SECONDAIRE BARRHAVEN
 Barrhaven Ontario

drawing title
CONSTRUCTION DETAILS PLAN

date	25/01/2018	job no.	1817
scales	1:400	drawing no.	C901
drawn	M.L.	approved	J.C.L.
plot date	25/01/2018		

1 DO NOT SCALE THIS DRAWING.
 2 CONTRACTOR TO VERIFY ALL DIMENSIONS AND NOTIFY THE ARCHITECT OF ANY DISCREPANCIES BEFORE WORK COMMENCES.
 3 THIS DRAWING TO BE READ IN CONJUNCTION WITH THE FOLLOWING DRAWINGS: STRUCTURAL, MECHANICAL, ELECTRICAL.

APPENDIX E
Engineering Drawings



LEGEND:

- EXISTING PROPERTY LINE TO REMAIN
- PROPOSED CURB
- PROPOSED SILT FENCE AS PER OPSD 219.110
- PROPOSED DOOR ENTRANCE/EXIT
- PROPOSED GRASS AREA (100mm TOP SOIL & SOD)
- PROPOSED CONCRETE FEATURES/SLAB
- PROPOSED HEAVY DUTY ASPHALT
- *50.00 PROPOSED ELEVATION
- *50.00BC PROPOSED BOTTOM OF CURB / ASPHALT ELEVATION
- *50.00TC PROPOSED TOP OF CURB ELEVATION
- *50.00BW PROPOSED EXPOSED BOTTOM OF RETAINING WALL
- *50.00TW PROPOSED TOP OF RETAINING WALL
- *50.00EX MATCH INTO EXISTING ELEVATION
- *70.19 EXISTING ELEVATION
- WTR - WATER SERVICE
- STM - EXISTING STORM SEWER
- SAN - EXISTING SANITARY SEWER
- WTR - EXISTING WATERMAIN
- SUB - EXISTING SUBDRAIN
- EXISTING MANHOLE
- EXISTING CATCHBASIN
- PROPOSED MANHOLE
- PROPOSED PIPE INSULATION
- PROPOSED 100 YEAR HIGH WATER LEVEL
- STORM WATERSHED EXTENT
- WS-XX WATERSHED NAME
- CONTROLLED RUNOFF COEFFICIENT
- AREA RUNOFF AREA IN HECTARES

Conseil des écoles publiques de l'Est de l'Ontario
Conseil des écoles publiques de l'Est de l'Ontario

key plan

EXISTING SCHOOL
NEW AUDITORIUM

3	2026.03.19	ISSUED FOR SPC	K.H.
2	2026.01.16	ISSUED FOR SPC	K.H.
1	2025.12.19	33% COORDINATION	K.H.
no.	date	revision/issue	by

architecture

PROVENCHER ROY

PROVENCHER ROY ASSOCIATES ARCHITECTS INC. T 613 886 6339
47 Rue Clarence, Suite 440 T 613 886 6339
OTTAWA, ONTARIO, CANADA K1N 9K1 PROVENCHERROY.CA

consultants

JAMES B. LENNOX & ASSOCIATES
LANDSCAPE ARCHITECTS

CUNLIFFE & ASSOCIATES
CONSULTING STRUCTURAL ENGINEERS

LRJ
LANDSCAPE ARCHITECTURE

northpoint

professional stamp

project title

AUDITORIUM ADDITION


ESP PAUL-DE-BLOIS - 1310 CHAPMAN MILLS DR., OTTAWA, ON K2J 3T9

drawing title

EROSION & SEDIMENT CONTROL PLAN

date	Issue Date	job no.
scale	1 : 500	220512
drawn	K.H.	drawing no.
approved	M.B.	C101
plot date	2025-12-19 12:30 PM	

1. DO NOT SCALE FROM THIS DRAWING
2. CONTRACTOR TO VERIFY ALL DIMENSIONS AND NOTIFY THE ARCHITECT OF ANY DISCREPANCIES BEFORE WORK COMMENCES
3. THIS DRAWING TO BE READ IN CONJUNCTION WITH THE FOLLOWING DRAWINGS: STRUCTURAL, MECHANICAL, ELECTRICAL




PAVEMENT STRUCTURE

COURSE	MATERIAL	THICKNESS (mm)	
		AUTOMOBILE PARKING	TRUCK ROUTE (HEAVY TRAFFIC)
SURFACE	HL 3 A/C (PG 58-34)	50	40
BINDER	HL 8 A/C (PG 58-34)	-	50
BASECOURSE	OPSS GRANULAR 'A'	150	150
SUBBASE	OPSS GRANULAR 'B' TYPE II	300	350

NOTE:
 IN PREPARATION FOR PAVEMENT CONSTRUCTION AT THIS SITE, ANY SURFICIAL OR NEAR SURFACE/SUBGRADE LEVEL TOPSOIL AND ANY SOFT, WET OR DELETERIOUS MATERIALS SHOULD BE REMOVED FROM THE PROPOSED PAVED AREAS. THE EXPOSED SUBGRADE SHOULD BE INSPECTED AND APPROVED BY GEOTECHNICAL PERSONNEL AND ANY SOFT AREAS EVIDENT SHOULD BE SUBEXCAVATED AND REPLACED WITH SUITABLE EARTH BORROW APPROVED BY THE GEOTECHNICAL ENGINEER. THE SUBGRADE SHOULD BE SHAPED AND CROWNED TO PROMOTE DRAINAGE OF THE SITE DRAINAGE STRUCTURES. FOLLOWING APPROVAL OF THE PREPARATION OF THE SUBGRADE, THE PAVEMENT GRANULARS MAY BE PLACED.

LEGEND:

- EXISTING PROPERTY LINE TO REMAIN
- PROPOSED CURB
- PROPOSED SILT FENCE AS PER OPSD 219.110
- PROPOSED DOOR ENTRANCE/EXIT
- PROPOSED GRASS AREA (100mm TOP SOIL & SOD)
- PROPOSED CONCRETE FEATURES/SLAB
- PROPOSED HEAVY DUTY ASPHALT
- *50.00 PROPOSED ELEVATION
- *50.00BC PROPOSED BOTTOM OF CURB / ASPHALT ELEVATION
- *50.00TC PROPOSED TOP OF CURB ELEVATION
- *50.00BW PROPOSED EXPOSED BOTTOM OF RETAINING WALL
- *50.00TW PROPOSED TOP OF RETAINING WALL
- *50.00EX MATCH INTO EXISTING ELEVATION
- *70.19 EXISTING ELEVATION
- WTR PROP. WATER SERVICE
- STM EXISTING STORM SEWER
- SAN EXISTING SANITARY SEWER
- WTR EXISTING WATERMAIN
- SUB EXISTING SUBDRAIN
- EXISTING MANHOLE
- EXISTING CATCHBASIN
- PROPOSED MANHOLE
- PROPOSED PIPE INSULATION
- PROPOSED 100 YEAR HIGH WATER LEVEL
- STORM WATERSHED EXTENT
- WS-XX WATERSHED NAME
- CONTROLLED RUNOFF COEFFICIENT
- AREA IN HECTARES



no.	date	revision/issue	by
3	2026.03.19	ISSUED FOR SPC	K.H.
2	2026.01.16	ISSUED FOR SPC	K.H.
1	2025.12.19	33% COORDINATION	K.H.

no.	date	revision/issue	by
3	2026.03.19	ISSUED FOR SPC	K.H.
2	2026.01.16	ISSUED FOR SPC	K.H.
1	2025.12.19	33% COORDINATION	K.H.

architecture

PROVENCHER ROY

PROVENCHER ROY ASSOCIÉS ARCHITECTES INC. T 613 686 6339
 47 Rue Clarence, Suite 440 T 613 686 6339
 OTTAWA, ONTARIO, CANADA K1N 5K1 PROVENCHERROY.CA

consultants

JAMES B. LENNOX & ASSOCIATES
 LANDSCAPE ARCHITECTS

CUNLIFFE & ASSOCIATES
 CONSULTING STRUCTURAL ENGINEERS

LRJ
 ENGINEERS & LANDSCAPERS

northpoint

professional stamp

project title

AUDITORIUM ADDITION

ESP PAUL-DE-BLOIS - 1310 CHAPMAN MILLS DR., OTTAWA, ON K2J 3T9

drawing title

GRADING & DRAINAGE PLAN

date	Issue Date	job no.
scale	1 : 500	220512
drawn	K.H.	drawing no.
approved	M.B.	C301
plot date	2025-12-19 12:30 PM	


1. DO NOT SCALE FROM THIS DRAWING
 2. CONTRACTOR TO VERIFY ALL DIMENSIONS AND NOTIFY THE ARCHITECT OF ANY DISCREPANCIES BEFORE WORK COMMENCES
 3. THIS DRAWING TO BE READ IN CONJUNCTION WITH THE FOLLOWING DRAWINGS: STRUCTURAL, MECHANICAL, ELECTRICAL

Proposed Watermain Schedule				
Location	Station	Min. Obv	Grade	Notes
North WM Connection Line				
Connection to City WM	0+000.0	Match Ex WM OBV	93.55	
SAN Crossing	0.003.2	90.45	93.58	SAN OBV = ±86.75
STM Crossing	0.004.4	90.30	93.57	STM INV = ±90.88
Valve	0+020.6	90.95	93.35	
Elbow Fitting 1	0+021.7	91.00	93.40	
Elbow Fitting 2	0+022.7	91.00	93.40	
Tee Fitting	0+024.7	91.03	93.43	*branches into existing watermain line, approx STA 0+022.6

JOB BENCHMARK
MAG NAIL IN UTILITY POLE
ELEV = 93.92

WATER, SANITARY AND STORM SERVING FOR THE PROPOSED ADDITION ARE TO BE ROUTED THROUGH THE EXISTING SCHOOL BUILDING. PLEASE REFER TO THE MECHANICAL ENGINEERING PLANS FOR GREATER DETAIL.

INSTALL FIVE (5) ZURN FLOW CONTROL ROOF DRAINS WITHIN THE NEW AUDITORIUM ADDITION.
SINGLE NOTCH SETTING @ 15.11 L/s/m
TOTAL ROOFTOP PROVIDED 100yr STORAGE = 186.0 m³
TOTAL ROOFTOP 100yr ROOF DRAIN REL. RATE = 70.72 L/s



no.	date	revision/issue	by
3	2026.03.19	ISSUED FOR SPC	K.H.
2	2026.01.16	ISSUED FOR SPC	K.H.
1	2025.12.19	33% COORDINATION	K.H.

architecture


PROVENCHER ROY

PROVENCHER ROY ASSOCIÉS ARCHITECTES INC. T 613 886 6339
47 Rue Clarence, Suite 440 T 613 886 6339
OTTAWA, ONTARIO, CANADA K1N 9K1 PROVENCHEROY.CA

consultants

JAMES B. LENNOX & ASSOCIATES
LANDSCAPE ARCHITECTS

CUNLIFFE & ASSOCIATES
CONSULTING STRUCTURAL ENGINEERS



northpoint

professional stamp

project title

AUDITORIUM ADDITION


ESP PAUL-DE-BLOIS - 1310 CHAPMAN MILLS DR., OTTAWA, ON K2J 3T9

drawing title

SERVICING PLAN


date	Issue Date	job no.
scale	1 : 400	220512
drawn	K.H.	drawing no.
approved	M.B.	C401
plot date	2025-12-19 12:30 PM	

1. DO NOT SCALE FROM THIS DRAWING
2. CONTRACTOR TO VERIFY ALL DIMENSIONS AND NOTIFY THE ARCHITECT OF ANY DISCREPANCIES BEFORE WORK COMMENCES
3. THIS DRAWING TO BE READ IN CONJUNCTION WITH THE FOLLOWING DRAWINGS: STRUCTURAL, MECHANICAL, ELECTRICAL



LEGEND:

- EXISTING PROPERTY LINE TO REMAIN
- PROPOSED CURB
- PROPOSED SILT FENCE AS PER OPSD 219.110
- PROPOSED DOOR ENTRANCE/EXIT
- PROPOSED GRASS AREA (100mm TOP SOIL & SOD)
- PROPOSED CONCRETE FEATURES/SLAB
- PROPOSED HEAVY DUTY ASPHALT
- PROPOSED ELEVATION
- PROPOSED BOTTOM OF CURB / ASPHALT ELEVATION
- PROPOSED TOP OF CURB ELEVATION
- PROPOSED EXPOSED BOTTOM OF RETAINING WALL
- PROPOSED TOP OF RETAINING WALL
- MATCH INTO EXISTING ELEVATION
- EXISTING ELEVATION
- PROP. WATER SERVICE
- EXISTING STORM SEWER
- EXISTING SANITARY SEWER
- EXISTING WATERMAIN
- EXISTING SUBMAIN
- EXISTING MANHOLE
- EXISTING CATCHBASIN
- PROPOSED MANHOLE
- PROPOSED PIPE INSULATION
- PROPOSED 100 YEAR HIGH WATER LEVEL
- STORM WATERSHED EXTENT
- WATER NAME
- RUNOFF COEFFICIENT
- AREA IN HECTARES



LEGEND:

- EXISTING PROPERTY LINE TO REMAIN
- PROPOSED CURB
- PROPOSED SILT FENCE AS PER OPSD 219.110
- PROPOSED DOOR ENTRANCE/EXIT
- PROPOSED GRASS AREA (100mm TOP SOIL & SOD)
- PROPOSED CONCRETE FEATURES/SLAB
- PROPOSED HEAVY DUTY ASPHALT
- PROPOSED ELEVATION
- PROPOSED BOTTOM OF CURB / ASPHALT ELEVATION
- PROPOSED TOP OF CURB ELEVATION
- PROPOSED EXPOSED BOTTOM OF RETAINING WALL
- PROPOSED TOP OF RETAINING WALL
- MATCH INTO EXISTING ELEVATION
- EXISTING ELEVATION
- PROP. WATER SERVICE
- EXISTING STORM SEWER
- EXISTING SANITARY SEWER
- EXISTING WATERMAIN
- EXISTING SUBDRAIN
- EXISTING MANHOLE
- EXISTING CATCHBASIN
- PROPOSED MANHOLE
- PROPOSED PIPE INSULATION
- PROPOSED 100 YEAR HIGH WATER LEVEL
- STORM WATERSHED EXTENT
- WATERSHED NAME
- RUNOFF COEFFICIENT
- AREA IN HECTARES

Conseil des écoles publiques de l'Est de l'Ontario

Conseil des écoles publiques de l'Est de l'Ontario

key plan

no.	date	revision/issue	by
3	2026.03.19	ISSUED FOR SPC	K.H.
2	2026.01.16	ISSUED FOR SPC	K.H.
1	2025.12.19	33% COORDINATION	K.H.

architecture

PROVENCHER ROY

PROVENCHER ROY ASSOCIÉS ARCHITECTES INC. T 613 686 6339
47 Rue Clarendon, Suite 440 T 613 686 6339
OTTAWA, ONTARIO, CANADA K1N 9K1 PROVENCHERROY.CA

consultants

JAMES B. LENNOX & ASSOCIATES
LANDSCAPE ARCHITECTS

CUNLIFFE & ASSOCIATES
CONSULTING STRUCTURAL ENGINEERS

LRJ
PROFESSIONAL ENGINEER

northpoint

professional stamp

project title

AUDITORIUM ADDITION


ESP PAUL-DE-BLOIS - 1310 CHAPMAN MILLS DR., OTTAWA, ON K2J 3T9

drawing title

PRE-DEVELOPMENT WATERSHED PLAN


date	Issue Date	job no.
scale	1 : 500	220512
drawn	K.H.	drawing no.
approved	M.B.	C701
plot date	2025-12-19 12:30 PM	

1. DO NOT SCALE FROM THIS DRAWING
2. CONTRACTOR TO VERIFY ALL DIMENSIONS AND NOTIFY THE ARCHITECT OF ANY DISCREPANCIES BEFORE WORK COMMENCES
3. THIS DRAWING TO BE READ IN CONJUNCTION WITH THE FOLLOWING DRAWINGS: STRUCTURAL, MECHANICAL, ELECTRICAL



LEGEND:

- EXISTING PROPERTY LINE TO REMAIN
- PROPOSED CURB
- PROPOSED SILT FENCE AS PER OPSD 219.110
- PROPOSED DOOR ENTRANCE/EXIT
- PROPOSED GRASS AREA (100mm TOP SOIL & SOD)
- PROPOSED CONCRETE FEATURES/SLAB
- PROPOSED HEAVY DUTY ASPHALT
- PROPOSED ELEVATION
- PROPOSED BOTTOM OF CURB / ASPHALT ELEVATION
- PROPOSED TOP OF CURB ELEVATION
- PROPOSED EXPOSED BOTTOM OF RETAINING WALL
- PROPOSED TOP OF RETAINING WALL
- MATCH INTO EXISTING ELEVATION
- EXISTING ELEVATION
- PROP. WATER SERVICE
- EXISTING STORM SEWER
- EXISTING SANITARY SEWER
- EXISTING WATERMAIN
- EXISTING SUBDRAIN
- EXISTING MANHOLE
- EXISTING CATCHBASIN
- PROPOSED MANHOLE
- PROPOSED PIPE INSULATION
- PROPOSED 100 YEAR HIGH WATER LEVEL STORM WATERSHED EXTENT
- WATERSHED NAME
- RUNOFF COEFFICIENT
- AREA IN HECTARES



3	2026.03.19	ISSUED FOR SPC	K.H.
2	2026.01.16	ISSUED FOR SPC	K.H.
1	2025.12.19	33% COORDINATION	K.H.
no.	date	revision/issue	by

architecture

PROVENCHER ROY

PROVENCHER ROY ASSOCIÉS ARCHITECTES INC. 1 613 686 6339
47 Rue Clarence, Suite 440 OTTAWA, ONTARIO, CANADA K1N 9K1 T 613 686 6339 PROVENCHERROY.CA

consultants

JAMES B. LENNOX & ASSOCIATES
LANDSCAPE ARCHITECTS

CUNLIFFE & ASSOCIATES
CONSULTING STRUCTURAL ENGINEERS

LRJ
PROFESSIONAL ENGINEER

northpoint

professional stamp

project title

AUDITORIUM ADDITION

ESP PAUL-DE-BLOIS - 1310 CHAPMAN MILLS DR., OTTAWA, ON K2J 3T9


drawing title

POST-DEVELOPMENT WATERSHED PLAN (PRE-ADDITION)

date	Issue Date	job no.
scale	1 : 500	220512
drawn	K.H.	drawing no.
approved	M.B.	C702
plot date	2025-12-19 12:30 PM	

1. DO NOT SCALE FROM THIS DRAWING
2. CONTRACTOR TO VERIFY ALL DIMENSIONS AND NOTIFY THE ARCHITECT OF ANY DISCREPANCIES BEFORE WORK COMMENCES
3. THIS DRAWING TO BE READ IN CONJUNCTION WITH THE FOLLOWING DRAWINGS: STRUCTURAL, MECHANICAL, ELECTRICAL

key plan



no.	date	revision/issue	by
3	2026.03.19	ISSUED FOR SPC	K.H.
2	2026.01.16	ISSUED FOR SPC	K.H.
1	2025.12.19	33% COORDINATION	K.H.

architecture


PROVENCHER ROY

PROVENCHER ROY ASSOCIATES ARCHITECTES INC. T 613 686 6339
47 Rue Cavendish, Suite 400 OTTAWA, ONTARIO, CANADA K1N 9K1 PROVENCHERROY.CA

consultants

JAMES B. LENNOX & ASSOCIATES
LANDSCAPE ARCHITECTS

CUNLIFFE & ASSOCIATES
CONSULTING STRUCTURAL ENGINEERS



northpoint

professional stamp

project title

AUDITORIUM ADDITION

ESP PAUL-DE-BLOIS - 1310 CHAPMAN MILLS DR., OTTAWA, ON K2J 3T9

drawing title

CONSTRUCTION DETAILS PLAN

date	Issue Date	job. no.
scale		220512
drawn	K.H.	drawing no.
approved	M.B.	C901
plot date	2025-12-19 12:30 PM	

1. DO NOT SCALE FROM THIS DRAWING
2. CONTRACTOR TO VERIFY ALL DIMENSIONS AND NOTIFY THE ARCHITECT OF ANY DISCREPANCIES BEFORE WORK COMMENCES
3. THIS DRAWING TO BE READ IN CONJUNCTION WITH THE FOLLOWING DRAWINGS: STRUCTURAL, MECHANICAL, ELECTRICAL

