

UNDERSTORY PLANTING SCHEDULE - GROUND COVER

KEY	QTY	BOTANICAL NAME	COMMON NAME	DECIDUOUS/ EVERGREEN	NATIVE/NON NATIVE	SUN EXPOSURE	SALT TOLERANCE	MOISTURE	DROUGHT TOLERANT	POLLINATOR	ROOT CONDITION	SPACING
		ACANTHUS SPINOSUS	SPINY BEAR'S BREECHES	DECIDUOUS	N	F.SUN/P.SHADE	MODERATE	DRY-MOIST	Y	N	1 gallon pot	450mm
		ACHILLEA MILLEFOLIUM	COMMON YARROW	SEMI-EVERGREEN	Y	F.SUN/P.SHADE	MODERATE	LOW	Y	Y	1 gallon pot	450mm
		ADANTUM PEDATUM	NORTHERN MAIDENHAIR FERN	DECIDUOUS	Y	P.SHADE/SHADE	LOW	MOIST	N	N	1 gallon pot	300mm
		AGASTACHE FOENICULUM	ANISE HYSSOP	EVERGREEN	Y	F.SUN/P.SHADE	MODERATE	DRY-MEDIUM	Y	Y	1 gallon pot	900mm
		AMSONIA HUBRICHTII	BLUESTAR	DECIDUOUS	N	F.SUN/P.SHADE	LOW	MEDIUM	Y	Y	1 gallon pot	300mm
		ANAPHALIS MARGARITACEA	PEARLY EVERLASTING	DECIDUOUS	Y	F.SUN/P.SHADE	HIGH	LOW	Y	Y	1 gallon pot	450mm
		ANEMONE CANADENSE	CANADA ANEMONE	DECIDUOUS	Y	F.SUN/P.SHADE	MODERATE	MOIST-WET	N	N	1 gallon pot	300mm
		ANDROPOGON GERARDII	BIG BLUESTEM	PERENNIAL GRASS	Y	F.SUN/P.SHADE	MODERATE	DRY-MOIST	Y	N	1 gallon pot	300mm
		AQUILEGIA CANADENSIS	EASTERN COLUMBINE	SEMI-EVERGREEN	Y	P.SHADE/SHADE	MODERATE	DRY-MOIST	N	Y	4" pot	450mm
		ARALIA NUDICAULIS	WILD SARSAPARILLA	DECIDUOUS	Y	P.SHADE/SHADE	MODERATE	AVERAGE-MOIST	Y	Y	seed	n/a
		ARALIA RACEMOSA	AMERICAN SPIKENARD	DECIDUOUS	Y	P.SHADE/SHADE	MODERATE	MOIST-WET	Y	N	1 gallon pot	450mm
		ARCTOSTAPHYLOS UVA-URSI	KINKKINICK	EVERGREEN	Y	F.SUN/P.SHADE/SHADE	HIGH	DRY-MOIST	Y	N	1 gallon pot	450mm
		ARTEMISIA LUDOVICIANA	WHITE SAGE	SEMI-EVERGREEN	Y	F.SUN	HIGH	DRY	Y	N	1 gallon pot	200mm
		ASARUM CANADENSE	WILD GINGER	DECIDUOUS	Y	P.SHADE/SHADE	LOW	MOIST	N	N	plug (zone 1)	200mm
		ASARUM CANADENSE	WILD GINGER	DECIDUOUS	Y	P.SHADE/SHADE	LOW	MOIST	N	N	1 gallon pot (zone 18)	300mm
		ASARUM CANADENSE	WILD GINGER	DECIDUOUS	Y	P.SHADE/SHADE	LOW	MOIST	N	N	4" pot (zone 20)	300mm
		ASCLEPIAS SYRIACA	COMMON MILKWEED	DECIDUOUS	Y	F.SUN	MODERATE	DRY-MEDIUM	Y	Y	1 gallon pot	300mm
		ASCLEPIAS TUBEROSA	BUTTERFLY MILKWEED	DECIDUOUS	Y	FULL SUN	MODERATE	LOW	Y	Y	1 gallon pot	300mm
		ASPLENUM SCOLOPENDRIUM	HART'S-TONGUE FERN	EVERGREEN	Y	P.SHADE/F.SHADE	LOW	MEDIUM	N	N	1 gallon pot	300mm
		ASTER ALPINUS	ALPINE ASTER	DECIDUOUS	Y	F.SUN	HIGH	MOIST	Y	Y	seed	n/a
		ASTILBOIDES TABULARIS	SHIELD-LEAF RODGERGIA	DECIDUOUS	N	P.SHADE/SHADE	MODERATE	MOIST-WET	N	N	1 gallon pot	450mm
		ATHYRIUM FILIX-FEMINA	LADY FERN	DECIDUOUS	Y	P.SHADE/SHADE	LOW	MOIST	N	N	1 gallon pot	450mm
		BAPTISIA 'BLUEBERRY SUNDAY'	FALSE INDIGO	DECIDUOUS	CULTVAR	FULL SUN	MODERATE	DRY-MOIST	Y	Y	1 gallon pot	450mm
		BOUTELLOUA CURTIPENDULA	SIDE-OATS GRAMA	PERENNIAL GRASS	Y	F.SUN/P.SHADE	MODERATE	DRY-MOIST	Y	N	seed (zone 10)	n/a
		BOUTELLOUA CURTIPENDULA	SIDE-OATS GRAMA	PERENNIAL GRASS	Y	F.SUN/P.SHADE	MODERATE	DRY-MOIST	Y	N	4" pot (zone 11)	300mm
		BOUTELLOUA GRACILIS	BLUE GRAMA	SEMI-EVERGREEN	Y	F.SUN	MODERATE	DRY	Y	N	4" pot	300mm
		CALAMAGROSTIS CANADENSIS	BLUE-JOINT GRASS	PERENNIAL GRASS	Y	F.SUN/P.SHADE	MODERATE	MOIST-WET	Y	N	plug	300mm
		CAREX ALBURSINA	WHITE BEAR SEDGE	SEMI-EVERGREEN	Y	P.SHADE/SHADE	MODERATE	DRY-MOIST	Y	N	seed (zone 4)	n/a
		CAREX ALBURSINA	WHITE BEAR SEDGE	SEMI-EVERGREEN	Y	P.SHADE/SHADE	MODERATE	DRY-MOIST	Y	N	plug (zone 4)	200mm
		CAREX BREVIOR	SHORT SEDGE	EVERGREEN	Y	P.SHADE/SHADE	MODERATE	MEDIUM-WET	Y	N	seed	n/a
		CAREX DIVULSA	GREY SEDGE	EVERGREEN	N	F.SUN/P.SHADE/SHADE	MODERATE	DRY-MOIST	Y	N	4" pot	300mm
		CAREX EBURNEA	BRISTLELEAF SEDGE	EVERGREEN	Y	F.SUN/P.SUN/SHADE	MODERATE	DRY	Y	N	plug (zone 1, zone 7)	200mm
		CAREX PENNSYLVANICA	PENNSYLVANIA SEDGE	SEMI-EVERGREEN	Y	P.SHADE/SHADE	MODERATE	DRY-MOIST	Y	N	plug (zone 1)	200mm
		CAREX PENNSYLVANICA	PENNSYLVANIA SEDGE	SEMI-EVERGREEN	Y	P.SHADE/SHADE	MODERATE	DRY-MOIST	Y	N	4" pot (zone 2)	300mm
		CAREX PENNSYLVANICA	PENNSYLVANIA SEDGE	SEMI-EVERGREEN	Y	P.SHADE/SHADE	MODERATE	DRY-MOIST	Y	N	1 gal (zone 20)	300mm
		CAREX PLATYPHYLLA	BROADLEAF SEDGE	EVERGREEN	Y	P.SHADE/SHADE	MODERATE	DRY-MEDIUM	N	N	plug	200mm
		CAREX VULPINOIDEA	FOX SEDGE	DECIDUOUS	Y	F.SUN/P.SHADE	MODERATE	MEDIUM-WET	N	N	plug	200mm
		CHASMANTHIUM LATIFOLIUM	NORTHERN SEA OATS	DECIDUOUS	N	P.SHADE/SHADE	HIGH	MEDIUM-WET	N	N	plug	300mm
		CHELONE GLABRA	WHITE TURTLEHEAD	DECIDUOUS	Y	F.SUN/P.SHADE/SHADE	LOW	MOIST-WET	N	Y	plug (zone 8)	300mm
		CHELONE GLABRA	WHITE TURTLEHEAD	DECIDUOUS	Y	F.SUN/P.SHADE/SHADE	LOW	MOIST-WET	N	Y	1 gallon pot (zone 21E)	300mm
		CHRYSOGONUM VIRGINIANUM	GREEN AND GOLD	SEMI-EVERGREEN	N	F.SUN/P.SHADE	MODERATE	MOIST-MEDIUM	N	Y	4" pot	300mm
		COREOPSIS LANCEOLATA	LANCELEAF COREOPSIS	DECIDUOUS	Y	F.SUN	MODERATE	DRY-MEDIUM	Y	Y	seed	n/a
		CORNUS CANADENSIS	BUNCHBERRY DOGWOOD	DECIDUOUS	Y	P.SHADE	MODERATE	MOIST	N	Y	4" pot	300mm
		DENNSTAEDIA PUNCTILOBLA	HAY-SCENTED FERN	DECIDUOUS	Y	P.SHADE/SHADE	MODERATE	MEDIUM	N	N	1 gallon pot	450mm
		DESCHAMPSIA CESPITOSA	TUFTED HAIR GRASS	SEMI-EVERGREEN	Y	SUN/P.SHADE	HIGH	MEDIUM-MOIST	Y	N	seed	n/a
		DOELLINGERIA UMBELLATA	FLAT-TOPPED ASTER	DECIDUOUS	Y	SUN/P.SHADE	MODERATE	MEDIUM-WET	N	Y	seed	n/a
		DICENTRA EXIMA 'SNOWDRIFT'	FRINGED BLEEDING	DECIDUOUS	CULTVAR	P.SHADE/SHADE	LOW	MOIST	N	Y	1 gallon pot	900mm
		DIPHYLLIA CYMOSA	UMBRELLA LEAF	DECIDUOUS	N	F.SUN/P.SHADE	LOW	MOIST-WET	N	N	1 gallon pot	900mm
		DRYAS OCTOPETALA	MOUNTAIN-AVENS	EVERGREEN	Y	F.SUN	MODERATE	MOIST	Y	Y	4" pot	300mm
		DRYOPTERIS GOLDIANA	GOLDIE'S FERN	DECIDUOUS	Y	P.SHADE/SHADE	LOW	MOIST	N	N	1 gallon pot (zone 1, zone 20)	450mm
		DRYOPTERIS INTERMEDIA	INTERMEDIATE WOOD FERN	SEMI-EVERGREEN	Y	P.SHADE/SHADE	LOW	MOIST	N	N	1 gallon pot	600mm
		DRYOPTERIS MARGINALIS	MARGINAL WOOD FERN	EVERGREEN	Y	P.SHADE/SHADE	LOW	MOIST	N	N	1 gallon pot	450mm
		ECHINACEA PURPUREA	PURPLE CONEFLOWER	DECIDUOUS	N	F.SUN/P.SHADE	HIGH	DRY-MEDIUM	Y	Y	seed	n/a
		ELYMUS HYSTRIX	BOTTLEBRUSH GRASS	SEMI-EVERGREEN	N	P.SUN/SHADE	MODERATE	DRY-MEDIUM	Y	Y	seed	n/a
		ERIOPHORUM CALLITRIX	ARCTIC COTTONGRASS	HERBACIOUS PERENNIAL	Y	F.SUN/P.SHADE	MODERATE	MOIST	N	N	1 gallon pot	300mm
		ERYTHRONIUM AMERICANUM	YELLOW TROUT LILY	DECIDUOUS	Y	P.SHADE/SHADE	MODERATE	MEDIUM	N	N	4" pot	200mm
		EURYBIA MACROPHYLLA	BIGLEAF ASTER	DECIDUOUS	Y	F.SUN/P.SHADE	MODERATE	DRY-MOIST	Y	Y	1 gallon pot	450mm
		EUTROCIUM MACULATUM	SPOTTED JOE-PYE WEED	DECIDUOUS	Y	F.SUN/P.SHADE	MODERATE	MEDIUM-WET	Y	Y	plug	300mm
		FESTUCA BREVIPLA TRACEY	HARD FESCUE	EVERGREEN	N	F.SUN/P.SHADE	MODERATE	DRY-MOIST	Y	N	n/a	n/a
		FESTUCA RUBRA SSP. COMMUTATA	CHEWINGS FESCUE	EVERGREEN	N	F.SUN/P.SHADE	MODERATE	DRY-MOIST	Y	N	n/a	n/a
		FESTUCA RUBRA SSP. RUBRA GAUDIN	CREeping RED FESCUE	EVERGREEN	Y	F.SUN/P.SHADE	MODERATE	MOIST	Y	N	n/a	n/a
		FRAGARIA VESCA	WOODLAND STRAWBERRY	DECIDUOUS	Y	F.SUN/P.SHADE	MODERATE	MEDIUM-MOIST	Y	N	1 gallon pot	300mm
		GALIUM BOREALE	NORTHERN BEDSTRAW	HERBACIOUS PERENNIAL	Y	P.SHADE	MODERATE	MEDIUM	N	Y	seed	n/a
		GAULTHERIA PROCUMBENS	WINTERGRASS	EVERGREEN	Y	P.SHADE/F.SHADE	LOW	MOIST-WET	N	N	1 gallon pot	300mm
		GERANIUM MACULATUM	WILD GERANIUM	DECIDUOUS	Y	F.SUN/P.SHADE	LOW	DRY-MOIST	N	N	4" pot (zone 2)	300mm
		GERANIUM MACULATUM	WILD GERANIUM	DECIDUOUS	Y	F.SUN/P.SHADE	LOW	DRY-MOIST	N	N	seed (zone 4)	n/a
		GERANIUM MACULATUM	WILD GERANIUM	DECIDUOUS	Y	F.SUN/P.SHADE	LOW	DRY-MOIST	N	N	1 gallon (zone 16, zone 19)	450mm
		HEUCHERA VILLOSA	HAIRY ALUMROOT	SEMI-EVERGREEN	N	P.SHADE/SHADE	HIGH	LOW	Y	Y	1 gallon pot	450mm
		HEROCHLOE ODORATA	SWEETGRASS	DECIDUOUS	Y	F.SUN/P.SHADE	MODERATE	MOIST-WET	N	N	1 gallon pot	450mm
		HOSTA 'HALCYON'	HALCYON' HOSTA	DECIDUOUS	CULTVAR	P.SHADE/SHADE	MODERATE	MOIST	Y	N	1 gallon pot	450mm
		HYSSOPUS OFFICINALIS	HYSSOP	HERBACIOUS PERENNIAL	N	F.SUN/P.SHADE	MODERATE	DRY-MEDIUM	Y	Y	4" pot	300mm
		JUNCUS EFFUSUS PYLAEI	SOFT RUSH	EVERGREEN	Y	F.SUN/P.SHADE	MODERATE	MOIST-WET	N	N	plug	200mm
		LINNAEA BOREALIS	TWINFLOWER	EVERGREEN	Y	F.SUN/P.SHADE/SHADE	HIGH	MEDIUM	Y	N	1 gallon pot	450mm
		MAIANTHEMUM CANADENSE	CANADA MAYFLOWER	DECIDUOUS	Y	P.SHADE/SHADE	MODERATE	DRY-MOIST	N	N	Plug (zone 1)	200mm
		MAIANTHEMUM CANADENSE	CANADA MAYFLOWER	DECIDUOUS	Y	P.SHADE/SHADE	MODERATE	DRY-MOIST	N	N	1 gallon pot (zone 21E)	300mm
		MAIANTHEMUM RACEMOSUM	FALSE SOLOMON'S SEAL	DECIDUOUS	Y	P.SHADE/SHADE	MODERATE	MEDIUM	Y	N	4" pot	300mm
		MENTHA CANADENSIS	WILD MINT	HERBACIOUS PERENNIAL	Y	F.SUN/P.SHADE	MODERATE	WET-MEDIUM	N	N	1 gallon pot	450mm
		MERTENSIA VIRGINICA	VIRGINIA BLUEBELLS	DECIDUOUS	Y	P.SHADE/SHADE	LOW	MOIST	N	Y	4" pot (zone 20)	300mm
		MERTENSIA VIRGINICA	VIRGINIA BLUEBELLS	DECIDUOUS	Y	P.SHADE/SHADE	LOW	MOIST	N	Y	1 gallon (zone 21E)	300mm
		MIMULUS RINGENS	MONKEY FLOWER	HERBACIOUS PERENNIAL	Y	F.SUN/P.SHADE	HIGH	MEDIUM-WET	N	Y	plug	200mm
		MONARDA DIDYMA	OSWEGO TEA	HERBACIOUS PERENNIAL	Y	F.SUN/P.SHADE	MODERATE	MOIST-WET	N	Y	1 gallon pot	450mm
		MONARDA FISTULOSA	WILD BERGAMOT	HERBACIOUS PERENNIAL	Y	F.SUN/P.SHADE	MODERATE	DRY-MOIST	Y	Y	1 gallon pot	300mm
		MONARDA PUNCTATA	SPOTTED BEEBALM	DECIDUOUS	Y	F.SUN/P.SHADE	MODERATE	DRY-MEDIUM	Y	Y	seed	n/a

UNDERSTORY PLANTING SCHEDULE - GROUND COVER

KEY	QTY	BOTANICAL NAME	COMMON NAME	DECIDUOUS/ EVERGREEN	NATIVE/NON NATIVE	SUN EXPOSURE	SALT TOLERANCE	MOISTURE	DROUGHT TOLERANT	POLLINATOR	ROOT CONDITION	SPACING
		ONOCLEA SENSIBILIS	SENSITIVE FERN	DECIDUOUS	Y	P.SHADE/SHADE	LOW	MOIST-WET	N	N	1 gallon pot	450mm
		PACKERA AUREA	GOLDEN GROUNDSEL	DECIDUOUS	Y	F.SUN/P.SHADE	LOW	MEDIUM-WET	N	Y	seed	n/a
		PANICUM VIRGATUM	SWITCH GRASS	DECIDUOUS	Y	F.SUN/P.SHADE	MODERATE	DRY-MOIST	Y	N	plug	300mm
		PENSTEMON DIGITALIS	FOXGLOVE BEARDTONGUE	DECIDUOUS	N	F.SUN/P.SHADE	MODERATE	DRY-MEDIUM	Y	Y	seed	n/a
		PHLOX DIVARICATA	WOODLAND PHLOX	SEMI-EVERGREEN	Y	P.SHADE/F.SHADE	LOW	MOIST-MEDIUM	N	Y	4" pot	300mm
		POLYSTICHUM ACROSTICHOIDES	CHRISTMAS FERN	EVERGREEN	Y	P.SHADE/SHADE	LOW	MOIST	N	N	1 gallon pot	450mm
		POTENTILLA ANSERINA	SILKWEED	HERBACIOUS PERENNIAL	Y	F.SUN	HIGH	MEDIUM	Y	Y	1 gallon pot	300mm
		RUBRICKIA HIRTA	BLACK EYES SUSAN	HERBACIOUS PERENNIAL	Y	F.SUN	MODERATE	DRY-MOIST	Y	Y	1 gallon pot	300mm
		SALVIA MEMOROSA	WOODLAND SAGE	HERBACIOUS PERENNIAL	N	F.SUN	MODERATE	MEDIUM	Y	Y	4" pot	300mm
		SAXIFRAGA OPOSITIFOLIA	PURPLE SAXIFRAGE	EVERGREEN	Y	P.SHADE	MODERATE	DRY	Y	N	1 gallon pot	300mm
		SCHIZACHYRIUM SCOPARIUM	LITTLE BLUESTEM	DECIDUOUS	Y	F.SUN	HIGH	DRY-MOIST	Y	N	1 gallon pot	300mm
		SISYRINCHIUM MONTANUM	BLUE EYED GRASS	HERBACIOUS PERENNIAL	Y	F.SUN/P.SHADE/SHADE	MODERATE	DRY-MOIST	Y	N	1 gallon pot	300mm
		SOLIDAGO CAESIA	BLUE-STEMMED GOLDENROD	DECIDUOUS	Y	F.SUN/P.SHADE	MODERATE	DRY	Y	N	1 gallon pot	450mm
		SOLIDAGO CANADENSIS	GOLDENROD	DECIDUOUS	Y	F.SUN/P.SHADE	HIGH	MOIST-WET	Y	Y	seed	n/a
		SOLIDAGO MEMORIALIS	OLD FIELD GOLDENROD	DECIDUOUS	Y	F.SUN/P.SHADE/SHADE	MODERATE	DRY	Y	Y	4" pot	300mm
		SORGHASTRUM NUTANS	INDIAN GRASS	DECIDUOUS	Y	F.SUN	MODERATE	DRY-MOIST	Y	N	1 gallon pot	450mm
		SPARTINA PECTINATA	PRAIRIE CORN GRASS	DECIDUOUS	Y	F.SUN/P.SHADE	MODERATE	MOIST-WET	N	N	plug	300mm
		SPOROBOLEUS HETEROLEPIS	PRAIRIE DROPSEED	DECIDUOUS	Y	F.SUN	HIGH	DRY-MOIST	Y	N	seed	n/a
		STYLOPHORUM DIPHYLLUM	CELANDINE POPPY	HERBACIOUS PERENNIAL	Y	P.SHADE/SHADE	LOW	MEDIUM-WET	N	N	4" pot	300mm
		THELYPTERIS NOVEBORACENSIS	NEW YORK FERN	DECIDUOUS	Y	P.SHADE/SHADE	MODERATE	MOIST	Y	N	1 gallon pot	450mm
		TIARELLA CORDIFOLIA	FOAM FLOWER	DECIDUOUS	Y	P.SHADE/SHADE	LOW	MOIST	N	N	1 gallon pot	450mm
		TRADESCANTIA VIRGINIANA	VIRGINIA SPIDERWORT	DECIDUOUS	N	F.SUN/P.SHADE	MODERATE	MOIST-MEDIUM	Y	Y	4" pot	300mm
		TRICENTIS FLAVUS	PURPLETOP	DECIDUOUS	N	F.SUN/P.SHADE/SHADE	HIGH	DRY-MOIST	Y	Y	seed	n/a
		VERBENA SIMPLEX	NARROW-LEAVED VERVAIN	HERBACIOUS PERENNIAL	Y	F.SUN	MODERATE	DRY-MEDIUM	Y	Y	1 gallon pot	450mm
		VIOLA LABRADORICA	ALPINE VIOLET	SEMI-EVERGREEN	Y	F.SUN/P.SHADE	HIGH	MEDIUM	N	N	4" pot	300mm
		VIOLA SORORIA	COMMON BLUE VIOLET	SEMI-EVERGREEN	Y	F.SUN/P.SHADE	LOW	MOIST	N	N	4" pot	200mm
		ZIZIA AUREA	GOLDEN ALEXANDER	DECIDUOUS	Y	F.SUN/P.SHADE	MODERATE	MEDIUM-WET	N	Y	plug	300mm

UNDERSTORY PLANTING SCHEDULE - SHRUB

KEY	QTY	BOTANICAL NAME	COMMON NAME	DECIDUOUS/ EVERGREEN	NATIVE/NON NATIVE	SUN EXPOSURE	SALT TOLERANCE	MOISTURE	DROUGHT TOLERANT	POLLINATOR	ROOT CONDITION	SPACING
		AESCULUS PARVIFLORA	BOTTLEBRUSH BUCKEYE	DECIDUOUS	N	F.SUN/P.SHADE	LOW	MEDIUM-WET	Y	Y	1 gallon	1800mm
		ARONIA ARBUTIFOLIA	RED CHOKEBERRY	DECIDUOUS</								