9216 (40") x 1651 (65") CUSTOM SHEET SIZE

SEE SHEET L07-101
SEE SHEET L07-103

SEE SHEET L07-103
SEE SHEET L07-102

SOIL VOLUME: 21m³
SOIL DEPTH: 1m
1 TREE
21m³ SV PER TREE

SOIL VOLUME: 45 m³
SOIL DEPTH: 1m
3 TREES
15m³ SV PER TREE

SOIL VOLUME: 18m³
SOIL DEPTH: 1m
1 TREE
18m³ SV PER TREE

SOIL VOLUME: 357 m³
SOIL DEPTH: 1m
8 TREES
44m³ SV PER TREE

SOIL VOLUME: 160m³
SOIL DEPTH: 1m STRUCTURAL SOIL, 1m FOR TREE PLANTING; 450mm FOR OTHER PA
5 TREES
32m³ SV PER TREE

SOIL VOLUME: 80m³
SOIL DEPTH: 1m
4 TREES
20m³ SV PER TREE

SOIL VOLUME: 224m³
SOIL DEPTH: 1m FOR TREE PLANTING; 450mm FOR OTHER PA
6 TREES
37m³ SV PER TREE

SOIL VOLUME: 45m³
SOIL DEPTH: 1m FOR TREE PLANTING; 450mm FOR OTHER PA
3 TREES
15m³ SV PER TREE

SOIL VOLUME: 788m³
SOIL DEPTH: 1m FOR TREE PLANTING; 450mm FOR OTHER PA
7 TREES
112m³ SV PER TREE

SOIL VOLUME: 56 m³
SOIL DEPTH: 1m
2 TREES
28m³ SV PER TREE

SOIL VOLUME: 87m³
SOIL DEPTH: 300mm IN PA; 1m IN TREE PLANTING AREA; 700mm STRUCTURAL SOIL
5 TREES
17.4m³ SV PER TREE

SOIL VOLUME: 136 m³
SOIL DEPTH: 1m
5 TREES
27m³ SV PER TREE

SOIL VOLUME: 105 m³
SOIL DEPTH: 1m
3 TREES
35m³ SV PER TREE

SOIL VOLUME: 605m³
SOIL DEPTH: 1m
25 TREES
24m³ SV PER TREE

SOIL VOLUME: 45m³
SOIL DEPTH: 1m
3 TREES
15m³ SV PER TREE

SOIL VOLUME: 336m³
SOIL DEPTH: 1m
15 TREES
22m³ SV PER TREE

SOIL VOLUME: 45m³
SOIL DEPTH: 1m
3 TREES
15m³ SV PER TREE

SOIL VOLUME: 328m³
SOIL DEPTH: 1m
15 TREES
21m³ SV PER TREE

SOIL VOLUME: 87m³
SOIL DEPTH: 300mm IN PA; 1m IN TREE PLANTING AREA; 700mm STRUCTURAL SOIL
17.4m³ SV PER TREE

SOIL VOLUME: 56 m³
SOIL DEPTH: 1m
2 TREES
28m³ SV PER TREE

SOIL VOLUME: 198 m³
SOIL DEPTH: 1m
9 TREES
22m³ SV PER TREE

SOIL VOLUME: 487 m³
SOIL DEPTH: 1m
12 TREES
40m³ SV PER TREE

SOIL VOLUME: 375m³
SOIL DEPTH: 1m
17 TREES
22m³ SV PER TREE

SOIL VOLUME: 258 m³
SOIL DEPTH: 1m
5 TREES
52m³ SV PER TREE

SOIL VOLUME: 250 m³
SOIL DEPTH: 1m
6 TREES
42m³ SV PER TREE

SOIL VOLUME: 117m³
SOIL DEPTH: 1m
2 TREES
58.5m³ SV PER TREE

SOIL VOLUME: 295 m³
SOIL DEPTH: 1m FOR PA; 600mm STRUCTURAL SOIL
6 TREES
49m³ SV PER TREE

SOIL VOLUME: 150m³
SOIL DEPTH:
600mm STRUCTURAL SOIL; 1m FOR TREE PLANTING; 450mm FOR OTHER PA
37.5m³ SV PER TREE

SOIL VOLUME: 454 m³
SOIL DEPTH: 1m
18 TREES
25m³ SV PER TREE

SOIL VOLUME: 60 m³
SOIL DEPTH: 1m
1 TREE
60m³ SV PER TREE

SOIL VOLUME: 288m³
SOIL DEPTH: 1m FOR TREE PLANTING; 450mm FOR OTHER PA
15 TREES
19m³ SV PER TREE

SOIL VOLUME: 76 m³
SOIL DEPTH: 1m
1 TREE
76m³ SV PER TREE

SOIL VOLUME: 1686m³
SOIL DEPTH: 1m FOR TREE PLANTING; 450mm FOR OTHER PA
60 TREES
28m³ SV PER TREE

ROAD A

ROAD B

CARLING AVENUE

PHASE 2
PARKING GARAGE
NOT IN SCOPE

SEE SHEET L07-103
SEE SHEET L07-105

SEE SHEET L07-103
SEE SHEET L07-105

REFER TO L00-001-L00-005 FOR NOTES AND LEGENDS

PLOT DATE

PROJECT
THE OTTAWA HOSPITAL NEW CAMPUS DEVELOPMENT - PHASE 4 MAIN HOSPITAL BUILDING
900 CARLING AVE, OTTAWA, ONTARIO

CLIENT
The Ottawa Hospital | L'Hôpital d'Ottawa
Infrastructure Ontario
PCL CONSTRUCTION | EllisDon

CLIENT PROJECT NO.
1070002

KEY PLAN
TRUE NORTH | PROJECT NORTH

THIS DRAWING TO BE PRINTED IN COLOUR

| NO | ISSUED | DATE |
|---|---|---|
| 09 | SITE PLAN CONTROL RESUBMISSION R2 | 2026-03-27 |
| 08 | DESIGN-BUILD BASELINE SUBMISSION | 2026-03-02 |
| 07 | SITE PLAN CONTROL RESUBMISSION | 2026-01-12 |
| 06 | 95% DD SUBMISSION | 2025-09-19 |
| 05 | SITE PLAN CONTROL RESUBMISSION | 2025-06-02 |
| 04 | 65% DD SUBMISSION | 2025-04-03 |
| 03 | 35% DD SUBMISSION | 2025-01-20 |
| 02 | ACPOR READINESS | 2025-01-09 |
| 01 | 80% SD SUBMISSION | 2024-08-15 |

REVISIONS

DRAWING STATUS
NOT FOR CONSTRUCTION

DISCREPANCIES MUST BE REPORTED IMMEDIATELY TO THE ARCHITECT BEFORE PROCEEDING.
ONLY FIGURED DIMENSIONS ARE TO BE USED. CONTRACTORS MUST CHECK ALL DIMENSIONS ON SITE. THIS DRAWING IS PROTECTED BY COPYRIGHT.

ALL DIMENSIONS ARE SHOWN IN METRIC.

AUTHOR
PWP
VERTECHS DESIGN
landscape architects

PROJECT TEAM

| | |
|---|---|
| DESIGN-BUILDER | PCL/ED, A JOINT VENTURE |
| ARCHITECTURAL | PARKIN ARCHITECTS LIMITED<br>JODOIN LAMARRE PRATTE ARCHITECTES<br>ADAMSON ASSOCIATE ARCHITECTS<br>fabARCHITECTS INC. |
| STRUCTURAL | STEPHENSON ENGINEERING LTD.<br>BOUTHILLETTE PARIZEAU INC. |
| MECHANICAL | HH ANGUS & ASSOCIATES LTD.<br>CROSSEY ENGINEERING LTD. |
| ELECTRICAL | MULVEY & BANANI INTERNATIONAL INC. |
| CIVIL | WSP CANADA INC. |
| LANDSCAPE | VERTECHS DESIGN INC.<br>PWP LANDSCAPE ARCHITECTURE |
| BUILDING CODE | LMDG BUILDING CODE CONSULTANTS LTD. |

AUTHOR PROJECT NO.
PCL2301_C

STAMP | STAMP

DRAWING TITLE
SOILS PLAN

| DRAWN | CHECKED |
|---|---|
| - | - |
| SCALE AT 40" x 66" | DATE |
| 1:250 | 15-AUG-2024 |

File Number:
D07-12-26-0008 (Revision)
D07-12-22-0168 (Original)
Plan Number: 19424

GRAPHIC SCALE: 0 2.5 5 10 15
SCALE IN METRIC

DRAWING NO. L07-103
REV NO. 09