









Stantec Consulting Ltd. 400 - 1331 Clyde Avenue Ottawa ON Tel. 613.722.4420 www.stantec.com

## Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay. The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

Legend





### - SANITARY DRAINAGE AREA ID#

INFILTRATION RATE OF 0.28 L/s/Ha APPLIED

#### SANITARY DRAINAGE AREA ID#

FLOW RATE IN (L/s) BASED ON MOTEL / HOTEL RATES USED FROM APPENDIX 4-A.4 OF THE OSDG, RESIDENTIAL PORTION WITH FULL HOUSEKEEPING FACILITIES @ 225L/day/p (ASSUMING DOUBLE OCCUPANCY PER ROOM) AND 125L/day/p FOR DINNING ROOM.

NUMBER OF ROOMS (ASSUME DOUBLE OCCUPANCY)

SANITARY DRAINAGE AREA

## Notes

# SANITARY STATS POPULATION COUNT - PHASE 1, 2 AND 3 63 STUDIO APTS @ 1.4PPU = 89 PEOPLE 190 - 1 BEDROOM APTS @ 1.4PPU = 266 PEOPLE 113 - 2 BEDROOM APTS @ 2.1PPU = 238 PEOPLE 8 - 3 BEDROOM APTS @ 3.1PPU = 25 PEOPLE 28 CARE UNITS @ 1.0 PPU = 28 PEOPLE TOTAL POPULATION = 644

COMMERCIAL AREA

TOTAL COMMERCIAL SPACE = 548m<sup>2</sup> (0.0548ha) @ 28,000 L/ha/day

INFILTRATION AREA

TOTAL SITE AREA = 0.912 Ha.

0 ISSUED TO CITY FOR SPA		SLW	DT	20.01.09
Revision		Ву	Appd.	YY.MM.DD
File Name: 160401510-DB	NJS	KS	SLM	19.09.23
	Dwn.	Chkd.	Dsgn.	YY.MM.DD

Permit-Seal

Client/Project SELECTION GROUP INTERNATIONAL INC. 2400 BOUL. DANIEL JOHNSON LAVAL, QUEBEC H7T 3A4 1357 BASELINE ROAD OTTAWA, ON, CANADA Title SANITARY DRAINAGE PLAN Project No. Scale 0 2.5 7.5 160401510 1:250 Drawing No. Sheet Revision

SA-1

7 of 8

0