



Engineers, Planners & Landscape Architects

Engineering

Land / Site
Development
Municipal
Infrastructure
Environmental /
Water Resources
Traffic /
Transportation
Structural
Recreational

Planning

Land/Site
Development
Planning
Application
Management
Municipal
Planning
Documents &
Studies
Expert Witness
(OMB)
Wireless Industry

Landscape Architecture

Urban Design &
Streetscapes
Recreation & Parks
Planning
Environmental
Restoration
Sustainable Design

Abbott-Fernbank Holdings Inc. Fernbank Crossing – Phase 5

Stormwater Management Report

Engineering excellence. Planning precision. Inspired landscapes.



**ABBOTT-FERNBANK HOLDINGS INC.
FERNBANK CROSSING**

**STORMWATER MANAGEMENT REPORT
(PHASE 5)**



Prepared By:

NOVATECH

Suite 200, 240 Michael Cowpland Drive
Ottawa, Ontario
K2M 1P6

December 7, 2018

Novatech File: 108180-19
Ref: R-2018-112

December 7, 2018

City of Ottawa
Infrastructure Services and Community Sustainability
110 Laurier Avenue West
Ottawa, ON K1P 1J1

Attention: Mr. Eric Surprenant

Dear Mr. Surprenant

**Reference: Stormwater Management Report
Fernbank Crossing, Phase 4
Our File No.: 108180-17**

Please find enclosed the Stormwater Management Report for Phase 5 of the Abbott-Fernbank Holdings Inc. lands within the Fernbank Community – Fernbank Crossing. This report outlines the storm drainage and stormwater management strategy for Phase 5 of the Fernbank Crossing development. The stormwater management design has been developed based on the requirements of the City of Ottawa and Rideau Valley Conservation Authority.

If you have any questions or comments, please do not hesitate to contact us.

Sincerely,

NOVATECH



Kallie Auld, P.Eng.
Project Coordinator

TABLE OF CONTENTS

| | | |
|------------|---|-----------|
| 1.0 | INTRODUCTION | 1 |
| 1.1 | Background | 1 |
| 1.2 | Land Use | 2 |
| 1.3 | Phase 5..... | 3 |
| 1.4 | Changes from Fernbank Community Design Plan | 4 |
| 1.5 | Additional Reports..... | 7 |
| 2.0 | EXISTING CONDITIONS | 7 |
| 2.1 | Topography..... | 7 |
| 2.2 | Subsurface Conditions | 7 |
| 2.3 | Drainage Outlet..... | 7 |
| 3.0 | STORMWATER MANAGEMENT CRITERIA..... | 9 |
| 3.1 | Quality & Quantity Control | 9 |
| 3.2 | Storm Drainage / Conveyance | 9 |
| 3.3 | Erosion and Sediment Control | 10 |
| 4.0 | PROPOSED DEVELOPMENT | 10 |
| 4.1 | Storm Sewer Design (Minor System) | 10 |
| 4.1.1 | Inlet Control Devices..... | 12 |
| 4.2 | Overland Flow Path (Major System)..... | 12 |
| 4.3 | Infiltration Best Management Practices and Low Impact Development | 12 |
| 5.0 | HYDROLOGIC & HYDRAULIC MODELING | 12 |
| 5.1 | Design Storms | 12 |
| 5.2 | Model Development..... | 13 |
| 5.2.1 | Storm Drainage Area Plan | 13 |
| 5.2.2 | Subcatchment Model Parameters..... | 13 |
| 5.2.3 | Minor System..... | 15 |
| 5.2.4 | Major System..... | 15 |
| 5.2.5 | Park & Ride Facility | 15 |
| 5.2.6 | Modeling Files / Schematic | 16 |
| 5.3 | Results of Hydrologic Analysis | 16 |
| 5.3.1 | Minor System..... | 16 |
| 5.3.2 | Major System..... | 17 |
| 5.3.3 | Hydraulic Grade Line | 17 |
| 6.0 | EROSION AND SEDIMENT CONTROL | 19 |
| 7.0 | CONCLUSIONS AND RECOMMENDATIONS | 20 |

List of Tables

Table 4.1: Storm Sewer Design Parameters
Table 4.2: Runoff Coefficients
Table 5.1: Hydrologic Modeling Parameters (Phase 5)
Table 5.2: Inlet Control Device Sizes and Design Flows
Table 5.3: Overland Flow Results (100-year Event)
Table 5.4: 100-year HGL Elevations

List of Figures

Figure 1: Key Plan
Figure 2: Conceptual Land Use Plan
Figure 3: Phasing Plan
Figure 4: Existing Watershed Boundaries
Figure 5: Storm Sewer Network

Appendices

Appendix A Draft Conditions (SWM)
Appendix B SWM Calculations and Design Sheets
Appendix C Autodesk Storm and Sanitary Analysis Model
Appendix D Drawings

List of Drawings

General Plan (108180-19-GP)
Grading Plan (108180-19-GR)
Storm Drainage Area Plans (108180-19-STM)
Erosion and Sediment Control Plan (108180-19-ESC)

1.0 INTRODUCTION

1.1 Background

Novatech has been retained to prepare a stormwater management report for the proposed Phase 5 development of the Abbott-Fernbank Lands (hereafter referred to as Fernbank Crossing). The subject site is located within the new Fernbank Community on the North side of Fernbank Road and west of Terry Fox Drive as shown in **Figure 1**. The lands will be developed as a low to medium density residential subdivision.




Figure 1: Key Plan

1.2 Land Use

The Fernbank Crossing subdivision (67.30 ha) is comprised primarily of low and medium density residential dwellings with a total of 506 singles, 244 towns and 76 stacked units proposed. Medium density residential (6.81ha) and a Community Core Area (7.11ha) are proposed adjacent Robert Grant Way and the hydro corridor. The Community Core is comprised of Mixed-Use land and a Village Green which is a public green space. Two schools (4.95ha) will front onto Cope Drive which divides the site (North/South). A Park n' Ride facility (1.79ha) is proposed along Fernbank Road. A Transit Station (1.02ha), Hydro Corridor (3.37ha), a SWM facility (0.93ha) and a Park (1.00ha) make up the remainder of the site. The proposed Land Use Plan is shown in **Figure 2**.

Stormwater Management Draft Conditions are provided in **Appendix A**. The Draft Plan of Subdivision is included in **Appendix D**.

1.3 Phase 5

Fernbank Crossing Subdivision will be developed in phases as shown in




Figure 3. This report includes details for the servicing design and construction of the Phase 5 lands that includes 59 townhouse units.

1.4 Changes from Fernbank Community Design Plan

Initially, a paramedic post was proposed in the Fernbank Community Design Plan for the lands comprising Phase 5. Coordination with the City of Ottawa concluded that a paramedic post is no longer required at this location. The proposed boundary of Phase 5 lands and the adjacent Park N' Ride has been circulated and approved by the City.

**Figure 2: Conceptual Land Use Plan**




Figure 3: Phasing Plan

1.5 Additional Reports

This Stormwater Management Report provides information on the considerations and approach by which Novatech has designed and evaluated the proposed storm drainage system for the Phase 5 lands and builds upon the Fernbank Community Design Plan [1] prepared by Walker, Nott, Dragicevic Associates Limited, the Fernbank Master Servicing Study [2] prepared by Novatech, and the Fernbank Environmental Management Plan also prepared by Novatech [3].

This report should be read in conjunction with the following:

- *Abbott-Fernbank Holdings Inc. Fernbank Crossing Stormwater Management Report (Phases 1&2)* prepared by Novatech, dated August 17, 2012. [8]
- *Abbott-Fernbank Holdings Inc. Fernbank Crossing – Phase 3 Stormwater Management Report* prepared by Novatech, July 15, 2015. [9]
- *Abbott-Fernbank Holdings Inc. Fernbank Crossing – Phase 4 Stormwater Management Report* prepared by Novatech, February 8, 2018. [10]
- *Geotechnical Investigation, Fernbank Crossing Residential Subdivision Phase 4, Ottawa, Ontario* prepared by Houle Chevrier Engineering, dated March 13, 2017. [5]
- *Servicing Design Brief (Phase 5) – Abbott-Fernbank Holdings Inc. Fernbank Crossing* prepared by Novatech, dated December 7, 2018 (R-2017-035). [12]

2.0 EXISTING CONDITIONS

2.1 Topography

The site generally slopes to the east with an average slope of approximately 3.0%. The maximum grade of approximately 106.00 metres in the middle of the site and a minimum elevation of approximately 103.00 metres near the southeast corner give a total elevation differential of approximately 3.0 metres across the site.

2.2 Subsurface Conditions

Geotechnical investigations were carried out by Houle Chevrier Engineering [4][5], and bedrock was encountered between 2.0 and 5.0 metres below the existing ground surface (approximate value only – refer to geotechnical report for details).

2.3 Drainage Outlet

The Fernbank Crossing development is located at the headwaters of the Monahan Drain Subwatershed (part of the Jock River Watershed). **Figure 4** shows the location of the Fernbank Crossing development and the existing watershed boundaries. The Phase 5 development drains through Phases 3 and 4, which outlet to the existing Pond 6.

The Monahan Drain is a municipal drain flowing eastwards towards Terry Fox Drive, with several lateral branches on the north and south sides that connect with the main branch. As specified in the Fernbank Environmental Management Plan, the Monahan Drain upstream of Terry Fox Drive has been classified as an intermittent watercourse that provides indirect habitat supporting tolerant warm/cool water fish communities.

The Monahan Drain has been abandoned upstream of Pond 6, along with the various branch drains within the limits of the Fernbank Community. The branch drains will be filled in as new development within the Fernbank Community proceeds. The main branch between Terry Fox Drive and Pond 6 has been lowered and enhanced using natural channel design techniques to mitigate against the loss of habitat associated with abandoning the various branch drains.




Figure 4: Pre-Development Watershed Boundaries

A minimum 40m wide riparian corridor has been designated for the section of the drain to be retained downstream of Pond 6 to protect aquatic habitat and stream function.

3.0 STORMWATER MANAGEMENT CRITERIA

The stormwater management criteria for the proposed development were established as part of the Fernbank Environmental Management Plan [3] and are based on the recommendations of the Jock River Reach 2 Subwatershed Study and input from Rideau Valley Conservation Authority.

In addition to the SWM criteria outlined in the Fernbank EMP, the proposed stormwater management strategy for Phase 5 will need to adhere to all applicable policies and guidelines of the Rideau Valley Conservation Authority, the City of Ottawa, the Ministry of the Environment, and other approvals agencies.

3.1 Quality & Quantity Control

- Storm runoff from Fernbank Crossing Phase 5 is to be directed to Fernbank Pond 6 for water quality & quantity control;
- Fernbank Pond 6 has been designed to control post-development peak flows in the Monahan Drain to pre-development levels and ensure no adverse impacts on the function of the Monahan Drain Constructed Wetlands SWM Facility.
- Fernbank Pond 6 has been designed to provide an *Enhanced* level of water quality protection (80% long term TSS removal) for the contributing drainage area, including Phase 5 Fernbank Crossing;

3.2 Storm Drainage / Conveyance

Technical Bulletin PIEDTB-2016-01 – Revisions to Ottawa Design Guidelines – Sewer [11] was considered for the design of the minor system. However, as the adjacent phases of development were all designed to the higher previous standard, Phase 5 is proposed to follow the same standard for consistency of performance in the subdivision.

- Storm sewers are to be designed to convey the 5-year post-development peak flow for the proposed development.
- Overland flows are to be confined within the rights-of-way and/or defined drainage easements for all storms up to and including the 100-year event.
- ICD flow rates are to be calculated for each drainage area to ensure that the following stormwater management (SWM) objectives are satisfied:
 - Surface water accumulation at street low points, during a 5-year event, shall follow Section 8.3.8.2 of the City of Ottawa Sewer Design Guidelines.
 - Major system storage in backyards is not to be included / accounted for in design computations.
 - Maximum flow depths and elevations on streets shall not exceed 350 mm and shall be confined to the road right-of-way as well as not be within 300 mm (vertical) to the nearest building opening.
 - The maximum flow depth on streets (both public and private and on parking lots) under either static or dynamic conditions shall be 350 mm.
 - The product of the 100-year flow depth (m) on street and flow velocity (m/s) shall not exceed 0.6.
 - The 100-year hydraulic grade line within the storm sewers shall not be within 30 cm (vertical) to adjacent building underside of footing.

3.3 Erosion and Sediment Control

- A qualified inspector should conduct daily visits during construction to ensure that the contractor is working in accord with the design drawings and that mitigation measures are being implemented as specified.
- Silt fencing is to be installed along the upland edge of all fish habitat corridors.
- Straw bale check dams are to be installed at the outlets to roadside ditches.
- Filter fabric is to be placed under all catchbasins and storm manhole covers.
- After complete build-out, all sewers are to be inspected and cleaned and all sediment and construction fencing is to be removed.

4.0 PROPOSED DEVELOPMENT

When the Stormwater Management report for Phase 4 [10] was submitted, the Phase 5 lands were intended to become a paramedic post, with runoff being directed through the existing Phase 3 lands. The design for the Phase 5 lands has been revised to include 59 townhouse units, with access provided via Slapshot Way within the Phase 4 development. Runoff from Phase 5 will be directed to both Phase 3 and Phase 4 under the revised design.

4.1 Storm Sewer Design (Minor System)

As noted above, runoff from the Phase 5 development will be directed into the existing storm sewer systems servicing Phases 3 and 4, where it will then be directed to the existing stormwater management facility 'Pond 6', which has been designed to provide the required quantity and quality control. The layout of the proposed storm sewer network is shown on **Figure 5**.

The proposed storm sewers have been designed using the Rational Method to convey peak flows associated with a 5-year return period. The storm sewer design sheets are provided in **Appendix B**. The corresponding Storm Drainage Area Plan (**Drawing 108180-19-STM**) is provided in **Appendix D**. The design parameters used in sizing the storm sewers are summarized in **Table 4.1** and **Table 4.2**.

Table 4.1: Storm Sewer Design Parameters

| Parameter | Design Criteria |
|---|--------------------------------|
| Local and Collector Roads | 5-year Return Period |
| Storm Sewer Design | Rational Method/Modeling |
| IDF Rainfall Data | Ottawa Sewer Design Guidelines |
| Initial Time of Concentration (T_c) | 10 minutes |
| Minimum Velocity | 0.8 m/s |
| Maximum Velocity | 3.0 m/s |
| Minimum Diameter | 250 mm |

Table 4.2: Runoff Coefficients

| Land Use | Runoff Coefficient |
|-------------------|--------------------|
| Park N' Ride | 0.80 |
| Towns Front Yards | 0.70 |
| Towns Rear Yards | 0.60 |




Figure 5: Storm Sewer Network

4.1.1 Inlet Control Devices

Inlet control devices (ICDs) will be installed as required to limit inflows to the minor system during large (>5-year) storm events. ICDs will be installed in roadway catchbasins. Rear yard catchbasins will connect to a catchbasin manhole, which will be fitted with an ICD. ICDs shall be slide-in orifice plate ICDs.

4.2 Overland Flow Path (Major System)

The rights-of-way have been designed to convey major system overland flow from the Phase 5 lands through Phase 4 via Slapshot Way to Pond 6. The road profiles have been graded to ensure that the 100-year peak overland flows are confined within the right-of-way at a maximum dynamic flow depth of 0.35 m. The major system has been designed to ensure that the product of velocity x depth does not exceed 0.60 during the 100-year event.

4.3 Infiltration Best Management Practices and Low Impact Development

The Fernbank EMP recommends lot level and infiltration best management practices (BMPs) and Low Impact Development (LIDs) to mitigate against the potential reduction in infiltration resulting from development. Phase 5 of the Fernbank Crossing subdivision will consist primarily of residential lots. Proposed BMPs and LIDs for groundwater infiltration include:

- Pipes connecting rear yard CBs will be perforated to promote infiltration of runoff from rear yard areas (as per City of Ottawa Standard Detail S29).
- Roof leaders will be directed to rear yard areas.

By implementing infiltration BMPs as part of the storm drainage design, the impacts of development on the hydrologic cycle can be considerably reduced. Infiltration of clean runoff will have additional benefits for stormwater management. By reducing the volume of “clean” water conveyed to the SWM facility, the end-of-pipe storage requirements can be reduced.

5.0 HYDROLOGIC & HYDRAULIC MODELING

The performance of the proposed storm drainage system for the site was evaluated using the ‘Autodesk Storm and Sanitary Analysis’ (SSA) hydrologic / hydraulic model. To maintain compatibility with the previously developed Phase 1-4 models (each of which built in SSA), the Phase 5 model was also developed in SSA.

5.1 Design Storms

The hydrologic analysis was completed using the following synthetic design storms and historical storms. The IDF parameters used to generate the design storms were taken from the Ottawa Design Guidelines - Sewer (October 2012).

3 Hour Chicago Storms:

5-year 3hr Chicago storm
100-year 3hr Chicago storm
100-year 3hr +20% Chicago storm

12 Hour SCS Type II Storms:

5-year 12 hour SCS Type II storm
100-year 12 hour SCS Type II storm
100-year 12 hour +20% SCS Type II storm

The 3-hour Chicago distribution generates the highest peak flows for both the minor and major systems and was determined to be the critical storm distribution for the design of the storm drainage system. The proposed drainage system has also been stress tested using a 3-hour Chicago design storm that has a 20% higher intensity and total volume compared to the 100-year event.

Model results from all storm distributions are provided on the enclosed CD.

5.2 Model Development

The SSA model accounts for both minor and major system flows (*dual drainage*), including the routing of flows through the storm sewer network (*minor system*), and overland along the road network (*major system*). The results of the analysis were used to:

- Ensure no ponding in the rights-of-way following a 5-year event;
- Calculate the storm sewer hydraulic grade line for the 100-year storm event;
- Evaluate overland flow depths and ponding volumes in the right-of-way during the 100-year event; and
- Determine the total major and minor system runoff from the site to Pond 6.

The model uses ‘conveyance links’ to model all minor and major systems during analysis. The conveyance links allow you to input the appropriate road cross sections in the open channel option so during the analysis the major system is modelled correctly. The conveyance links are connected to ‘junctions’ and ‘storm inlets’ which represent the gutter grades at selected points, catchbasins in sags (*low points*) and overtopping points (*high points*). The major system (*road network*) corresponds to the grading plan of the proposed site. The junctions, inlets and conveyance links are used to determine the flows, velocities and ponding depths at specific points on the road. The road networks on the plan and profile drawings are used to create the major system model using all slopes and grades for the site.

The model is capable of accounting for both static and dynamic storage within the rights-of-way, including the overland flow across all high points and capture/bypass curves for inlets on continuous grade. The 100-year flow depths computed by the model represent the total (static + dynamic) ponding depths at low points for areas in road sags, or the gutter flow depth where the inlets are on a continuous grade.

5.2.1 Storm Drainage Area Plan

The Fernbank Crossing subdivision has been divided into subcatchments based on the drainage areas tributary to each inlet of the proposed storm sewer system. The catchment areas are shown on the Storm Drainage Area Plan provided as **Drawing 108180-19-STM** in **Appendix D**.

Due to the updated design for Fernbank Phase 5, the drainage areas for a portion of Fernbank Phase 4 have been updated. The following areas have changed or moved since the submission of the Fernbank Phase 4 SWM Report [10]: 646 ,647, 648, and 650.

5.2.2 Subcatchment Model Parameters

The hydrologic parameters for each subcatchment were developed based on the Land Use Plan (**Figure 2**) and the Storm Drainage Area Plan specified above. An overview of the modeling parameters is provided in **Table 5.1**. Supporting calculations are provided in **Appendix B**.

Table 5.1: Hydrologic Modeling Parameters (Phase 5)

| Area ID | Catchment Area (ha) | Runoff Coefficient | Percent Impervious (%) | No Depression (%) | Equivalent Width (m) | Average Slope (%) |
|---------|---------------------|--------------------|------------------------|-------------------|----------------------|-------------------|
| 633 | 1.78 | 0.80 | 86% | 10% | 120 | 0.50 |
| 644 | 0.17 | 0.70 | 71% | 50% | 60 | 1.00 |
| 645 | 0.24 | 0.70 | 71% | 40% | 60 | 0.80 |
| 646 | 0.17 | 0.70 | 71% | 40% | 55 | 2.20 |
| 647 | 0.17 | 0.70 | 71% | 20% | 55 | 0.73 |
| 648 | 0.27 | 0.70 | 71% | 30% | 105 | 2.30 |
| 649 | 0.21 | 0.70 | 71% | 40% | 80 | 1.30 |
| 650 | 0.10 | 0.70 | 71% | 30% | 60 | 1.30 |
| 651 | 0.21 | 0.60 | 57% | 100% | 90 | 1.00 |
| 652 | 0.35 | 0.65 | 64% | 50% | 150 | 0.70 |
| 653 | 0.16 | 0.70 | 71% | 50% | 50 | 0.85 |
| 654 | 0.33 | 0.65 | 64% | 50% | 95 | 0.65 |
| 655 | 0.14 | 0.65 | 64% | 50% | 45 | 3.50 |
| 656 | 0.10 | 0.65 | 64% | 50% | 30 | 3.00 |
| 657 | 0.05 | 0.60 | 57% | 100% | 26 | 0.50 |
| 658 | 0.15 | 0.60 | 57% | 100% | 60 | 0.50 |
| 659 | 0.20 | 0.60 | 57% | 100% | 112 | 0.50 |
| 660 | 0.22 | 0.60 | 57% | 100% | 150 | 0.50 |
| 661 | 0.09 | 0.70 | 71% | 0% | 40 | 1.30 |

¹Equivalent widths are calculated using the methods described in the OSDG

Infiltration

Infiltration losses for all catchment areas were modeled using Horton's infiltration equation, which defines the infiltration capacity of the soil over the duration of a precipitation event using a decay function that ranges from an initial maximum infiltration rate to a minimum rate as the storm progresses. The default values for the City of Ottawa [6] were used for all catchments.

Horton's Equation:

$$f(t) = f_c + (f_o - f_c)e^{-k(t)}$$

Initial infiltration rate: $f_o = 76.2$ mm/hr
 Final infiltration rate: $f_c = 13.2$ mm/hr
 Decay Coefficient: $k = 4.14$ /hr

Depression Storage

The default values for depression storage in the City of Ottawa [6] were used for all catchments. Residential rooftops were assumed to provide no depression storage.

- Depression Storage (pervious areas): 4.67 mm
- Depression Storage (impervious areas): 1.57 mm

Equivalent Width

'Equivalent Width' refers to the width of the sub-catchment flow path. This parameter is calculated as described in the *Sewer Design Guidelines, October 2012, Section 5.4.5.6*.

Impervious Values

Impervious (TIMP) values for each subcatchment area were calculated based on the proposed land use plan (Figure 2) and correspond to the Runoff Coefficients used in the Rational Method calculations using the equation:

$$C = 0.90(\% \text{ IMP}) + 0.20(1 - \% \text{ IMP})$$

To check that the impervious values used in the design are appropriate, the impervious value for a typical lot was calculated for each land use and compared to the values used in the design. The results of this analysis indicate that the Runoff Coefficients and impervious values used in the stormwater management design are slightly higher than the calculated values and therefore represent a slightly conservative design. Supporting calculations are provided in **Appendix B**.

5.2.3 Minor System

Inflows to the storm sewer were modeled based on the characteristics of each inlet;

- For areas where catchbasins are located at low points (*represented as junctions*), inflows to the storm sewer are based on the ICD specified for the inlet and the maximum depth of ponding. Storage volumes within the right-of-way are based on the grading design.
- For areas where catchbasins are located on a continuous grade, the capture rate is based on the type of grate, the geometry of the road, and the approach flow. Rating curves for approach flow vs. capture rate were input into the model using the appropriate tables from the *Ottawa Design Guidelines – Sewer*.
 - Design Chart 4.04: Gutter Flow Rate for Barrier Curb with Gutter.
 - Design Chart 4.06: Gutter Flow Rate for Mountable Curb with Gutter.
 - Design Chart 4.14: Inlet Capacity for Barrier Curb.
 - Design Chart 4.15: Inlet Capacity for Mountable Curb.
 - Appendix 7-A. Type S22 Curb Inlet Catchbasin with Cross Fall fixed at 3%

5.2.4 Major System

The proposed road network was input into the SSA model to calculate the total inflow into the storm sewers (minor system), and to calculate the overland flows and flow depths within the rights-of-way (major system).

The roads are represented in the model as open channels. Model input includes:

- Right-of-way cross-sections;
- Length and slope of the road between each high and low point;
- The location of all storm inlets and whether the inlets are in a sag or on-grade.

The elevations used to define the road network are based on the gutter elevations, as opposed to the centerline of road elevations shown on the Grading Plans.

5.2.5 Park & Ride Facility

The model developed for Phases 1-5 of the Fernbank Crossing subdivision must account for inflows from all future phases, as well as inflows from adjacent development. Where detailed information does not exist, the following assumptions were made in developing the model:

- The maximum release rate for the proposed park and ride facility was established as 150L/s/ha as per the community design plan.

5.2.6 Modeling Files / Schematic

The modeling files and model schematics are provided in **Appendix C**. Individual model files for each storm event have been included. Digital copies of the modeling files and model output for all storm events are provided on the enclosed CD.

5.3 Results of Hydrologic Analysis

The model was used to evaluate the performance of the proposed storm drainage system for the Phase 5 lands and specifically to determine the 100-year hydraulic grade line.

5.3.1 Minor System

The proposed inlet control devices (ICDs) have been sized to capture the approximate 5-year peak flow at each inlet to the storm sewer, as well as to reduce the 100-year HGL elevation in the storm sewers. Consequently, there will be little to no ponding within the rights-of-way during the 5-year event. The selection of ICDs takes into account the overland flow that bypasses catchbasins on-grade by providing additional capacity at the downstream inlets. The list of ICD sizes and performance is provided in **Table 5.2**.

Table 5.2: Inlet Control Device Sizes and Design Flows

| Structure | ICD Size & Inlet Rate | | | | | | 5-year Peak Flow to CB** (L/s) |
|-----------------|---------------------------|----------------------------|----------------|-------------------|------------------------|---|---|
| | Diameter 1 (mm) | Diameter 2* (mm) | T/G (m) | Invert (m) | Max Head (m) | Calculated 5-yr Capture Rate (L/s) | |
| ROW CBs | | | | | | | |
| CB187-188 | 83 | 83 | 104.59 | 103.19 | 1.36 | 35 | 38 |
| CB189-190 | 94 | 94 | 105.54 | 104.14 | 1.35 | 44 | 49 |
| CB191-192 | 83 | 83 | 105.51 | 104.11 | 1.36 | 35 | 35 |
| CB193-194 | 102 | 102 | 104.37 | 102.97 | 1.35 | 52 | 60 |
| CB195 | 83 | 0 | 103.82 | 102.42 | 1.36 | 17 | 27 |
| Rear Yard CBMHs | | | | | | | |
| RYCB09 | 83 | 0 | 105.96 | 103.32 | 2.60 | 24 | 8 |
| RYCB11 | 108 | 0 | 105.17 | 103.51 | 1.61 | 32 | 46 |
| CBMH16 | 83 | 0 | 104.28 | 102.53 | 1.71 | 19 | 25 |

*Diameter 2 only specified where catchbasins are not interconnected

**From SSA Model, 5-year 3-hour Chicago storm distribution

The Rational Method design sheets (**Appendix B**) were used to calculate the required storm sewer sizes based on capturing the peak flow at each inlet to the storm sewer for a 5-year design return period.

5.3.2 Major System

During the 100-year event, stormwater runoff that exceeds the available static storage within road sags will flow overland within the rights-of-way and/or defined drainage easements to Pond 6 as described in **Table 5.3**. The major system network was evaluated using the model to ensure that the flow depths and velocities conform to City standards. The results of the 100-year modelling indicate that the overland flow depths on all streets will be less than 0.30m, the product of depth x velocity will be less than 0.60, and major system flows will be confined to the rights-of-way with no encroachment onto private property.

Table 5.3 also provides the model results for a 20% increase in the 100-year design event. Based on these results, the proposed storm drainage system will not experience any adverse flooding even with a 20% increase to the 100-year event. An expanded table of the ponding depths at low points in the roadway (including the stress-test event) is provided in **Appendix B**.

Table 5.3: Overland Flow Results (100-year Event)

| Location/ Structure ID | T/G (m) | Max. Static Ponding (Spill Depth) | | 100-yr Event (3hr) | | | |
|------------------------------|------------|--------------------------------------|--------------|-------------------------------|-----------------------|-------------------|--|
| | | Elev. (m) | Depth (m) | Total Dynamic Depth (m) | Peak Flow (cms) | Velocity (m/s) | Velocity * Depth (m ² /s) |
| CB187-188 | 104.59 | N/A | N/A | 0.06 | 0.08 | 0.55 | 0.03 |
| CB189-190 | 105.54 | 105.70 | 0.16 | 0.15 | 0.10 | 0.00 | 0.00 |
| CB191-192 | 105.51 | 105.58 | 0.07 | 0.15 | 0.07 | 0.14 | 0.02 |
| CB193-194 | 104.37 | 104.50 | 0.13 | 0.17 | 0.13 | 0.19 | 0.03 |
| CB195 | 103.82 | N/A | N/A | 0.06 | 0.08 | 0.55 | 0.03 |
| 26+077 | N/A | N/A | N/A | 0.02 | 0.02 | 0.19 | 0.00 |
| 26+115 | N/A | N/A | N/A | 0.00 | 0.00 | 0.00 | 0.00 |
| 26+185 | N/A | N/A | N/A | 0.00 | 0.00 | 0.00 | 0.00 |

(1) N/A denotes catchbasin pairs on a continuous grade that do not have a static ponding depth.

5.3.3 Hydraulic Grade Line

The Phase 5 model has been integrated with the existing Fernbank Phase 1-4 SSA model. By integrating the models, the HGL elevations within the proposed Phase 5 development and downstream in Phase 3 and 4 can be accurately determined.

The results of the HGL analysis were used to ensure that a minimum freeboard of 0.30m is provided between the 100-year HGL and the designed underside of footing elevations. The 100-year HGL is indicated on the Plan and Profile Drawings (submitted separately). The 100-year HGL elevations at each storm manhole with the respected underside of footing are provided in **Table 5.4**.

An expanded table showing the results of the stress test (100-year +20% event) and the HGL elevations for Phases 3 and 4 is provided in **Appendix C**. The stress test indicates that the HGL elevations will be below the USF elevations for this event.

Table 5.4: 100-year HGL Elevations

| Manhole ID | MH Invert Elevation (m) | T/G Elevation (m) | 100yr-3hr HGL Elevation (m) | Design USF (m) | Clearance (100yr) (m) |
|----------------------|----------------------------|----------------------|--------------------------------|-------------------|--------------------------|
| HGL - Phase 5 | | | | | |
| 501 | 100.81 | 104.24 | 101.32 | 102.87 | 1.55 |
| 503 | 102.36 | 105.84 | 102.68 | 103.90 | 1.22 |
| 505 | 102.58 | 105.79 | 102.98 | 103.90 | 0.92 |
| 507 | 102.43 | 105.69 | 102.32 | 103.78 | 1.46 |
| 509 | 101.97 | 105.63 | 103.17 | 104.03 | 0.86 |
| HGL - Phase 4 | | | | | |
| 301 | 96.64 | 101.51 | 98.86 | 99.86 | 1.00 |
| 303 | 97.86 | 101.65 | 99.04 | 100.06 | 1.02 |
| 305 | 98.10 | 101.88 | 99.39 | 100.16 | 0.77 |
| 307 | 98.29 | 102.09 | 99.66 | 100.26 | 0.60 |
| 309 | 100.67 | 103.82 | 101.14 | 101.77 | 0.63 |
| 311 | 98.65 | 102.41 | 99.81 | 100.41 | 0.60 |
| 313 | 98.62 | 102.41 | 100.03 | 100.48 | 0.45 |
| 315 | 99.13 | 102.38 | 100.12 | 100.66 | 0.54 |
| 317 | 99.50 | 102.38 | 100.14 | 100.81 | 0.67 |
| 319 | 99.06 | 102.99 | 100.32 | 100.85 | 0.53 |
| 321 | 102.54 | 105.45 | 102.71 | 103.37 | 0.66 |
| 323 | 99.38 | 103.21 | 100.47 | 101.45 | 0.98 |
| 325 | 99.72 | 103.29 | 100.67 | 101.68 | 1.01 |
| 327 | 99.82 | 103.33 | 100.73 | 101.68 | 0.95 |
| 329 | 100.39 | 103.84 | 101.12 | 102.10 | 0.98 |
| 333 | 101.67 | 105.03 | 101.67 | 102.90 | 1.23 |

6.0 EROSION AND SEDIMENT CONTROL

Erosion and sediment control measures will be implemented during construction in accordance with the “Guidelines on Erosion and Sediment Control for Urban Construction Sites” (Government of Ontario, May 1987). Details are provided on the Erosion and Sediment Control Plan (108180-15-ESC) provided in **Appendix D**.

- All erosion and sediment control measures are to be installed to the satisfaction of the engineer, the municipality and the conservation authority prior to undertaking any site alterations (filling, grading, removal of vegetation, etc.) and remain present during all phases of site preparation and construction.
- A qualified inspector should conduct daily visits during construction to ensure that the contractor is working in accord with the design drawings and that mitigation measures are being implemented as specified.
 - A light duty silt fence barrier is to be installed in the locations shown on the Erosion and Sediment Control Plan.
 - Filter cloth bags/ inserts are to be placed in all catchbasins and structures within the construction area.
 - After complete build-out, all sewers are to be inspected and cleaned and all sediment and construction fencing is to be removed.
- The contractor shall ensure that proper dust control is provided with the application of water (and if required, calcium chloride) during dry periods.
- The contractor shall immediately report to the engineer or inspector any accidental discharges of sediment material into any ditch or sewer system. Appropriate response measures shall be carried out by the contractor without delay.
- The contractor acknowledges that failure to implement erosion and sediment control measures may result in penalties imposed by any applicable regulatory agency.

7.0 CONCLUSIONS AND RECOMMENDATIONS

The servicing design generally conforms to the conclusions and recommendations outlined in the Fernbank Master Servicing Study and the Fernbank Environmental Management Plan both of which were approved by Ottawa City Council on June 24, 2009.

The conclusions based on the results of the stormwater management analysis are as follows:

Storm Drainage / Conveyance

- Storm sewers (minor system) have been designed to convey the 5-year post-development peak flow for the proposed development.
- Inflows to the minor system will be controlled using inlet control devices (ICDs).
- The site has been graded to provide an overland flow route along the road network.
- Overland flows during the 100-year event will not exceed a maximum flow depth of 0.35m within the right-of-way. The product of depth x velocity will be less than 0.6.
- A minimum clearance of 0.30m will be provided between the 100-year hydraulic grade line (HGL) and the designed underside of footing elevations.

Stormwater Management

- Water quality and quantity control for the Fernbank Crossing subdivision (including the Phase 5 lands) will be provided by Fernbank Pond 6 located at the headwaters of the Monahan Drain.
- Pond 6 will control post-development flows to the Monahan Drain to pre-development levels for all storms up to and including the 100-year event.
- Pipes connecting rear yard catchbasins will be perforated to promote infiltration and reduce the volume of storm runoff to Pond 6.

The preceding report is respectfully submitted for review and approval. Please contact the undersigned should you have questions or require additional information.

NOVATECH

Prepared by

Reviewed by



A handwritten signature in blue ink, appearing to read "Michael Petepiece", with a long horizontal line extending to the right.

Kallie Auld, P.Eng.
Project Coordinator | Water Resources

Michael Petepiece, P.Eng.
Senior Project Manager | Water Resources

References

1. “Fernbank Community Design Plan, Walker, Nott, Dragicevic Associates Ltd. [June 24, 2009]
2. “Fernbank Master Servicing Study”, Novatech Engineering Consultants Ltd. [June 24, 2009]
3. “Fernbank Environmental Management Plan”, Novatech Engineering Consultants Ltd. [June 24, 2009]
4. “Additional Test Pits East Portion of Brookfield Property, Fernbank Community Design, Ottawa, Ontario” Houle Chevrier Engineering Ltd. [Report No. 08-601, December 2008]
5. “Geotechnical Investigation, Fernbank Crossing Residential Subdivision Phase 3 and 4, Ottawa, Ontario” Houle Chevrier Engineering Ltd. [Report No. 14-482, December 2014]
6. “Sewer Design Guidelines”, Department of Public Works and Services, City of Ottawa [October 2012]
7. “Standard Tender Documents, Material Specifications and Standard Detail Drawings” City of Ottawa, Department of Infrastructure Services and Community Sustainability [March 31, 2009]
8. “Fernbank Crossing Stormwater Management Report (Phases 1&2)”, Novatech Engineering Consultants Ltd. [August 17, 2012]
9. “Fernbank Crossing – Phase 3 Stormwater Management Report”, Novatech [July 13, 2015]
10. “Fernbank Crossing – Phase 4 Stormwater Management Report”, Novatech [February 8, 2018]
11. “Technical Bulletin PIEDTB-2016-01 Revisions to Ottawa Design Guidelines – Sewer”, City of Ottawa [September 6, 2016]
12. “Servicing Design Brief (Phase 5) – Abbott-Fernbank Holdings Inc. Fernbank Crossing”, Novatech [December 7, 2018]

Appendix A Draft Conditions (SWM)

MENU OF CONDITIONS
FOR DRAFT APPROVAL
Abbott-Fernbank CORPORATION
Fernbank Road

DRAFT APPROVED 24/02/2012
REVISED 11/06/2013
REVISED AND EXTENDED 30/10/ 2015

INDEX

| | |
|--|----|
| General..... | 2 |
| Zoning | 4 |
| Roadway Modifications..... | 4 |
| Highways/Roads..... | 5 |
| Public Transit..... | 7 |
| Geotechnical | 9 |
| Sidewalks, Walkways, Fencing, and Noise Barriers | 10 |
| Landscaping/Streetscaping | 12 |
| Gateway Features | 13 |
| Fernbank Crossing Park Condition Updates | 15 |
| Environmental Constraints | 19 |
| Schools..... | 20 |
| Archaeology..... | 21 |
| Stormwater Management..... | 21 |
| Sanitary Services..... | 24 |
| Water Services..... | 25 |
| Serviced Lands..... | 26 |
| Unserviced Lands..... | 27 |
| Hydro..... | 27 |
| Fire Services | 30 |
| Utilities..... | 30 |
| Noise Attenuation | 30 |
| Land Transfers | 31 |
| Development Charges By-law..... | 31 |
| Survey Requirements..... | 33 |
| Closing Conditions | 33 |

Manager, Planning and Growth Management.

- | | | |
|-------------|---|-------------------------------------|
| 106. | The Owner agrees to enter into an agreement with the Ottawa Catholic School Board for the reservation of the designated school site known as Block 533 on the draft plan of subdivision for a period of up to seven years from the date of registration of the plan which contains the school site. The agreement shall address matters such as use of the site for construction by the Owner, and the condition the site must be in at the time of transfer. | Ottawa Catholic School Board |
| 107. | The Owner acknowledges and agrees to erect a 1.8 metres chain link fence along the property line between the Ottawa Catholic School Board's designated elementary school site and any adjacent residential or non-residential properties. The fences will not contain any gated access to the school site. | Ottawa Catholic School Board |

Archaeology

- | | | |
|-----------------------|---|--|
| 108. ARC 1 | <ul style="list-style-type: none">(i) The Owner acknowledges having been required to retain a licensed consultant archaeologist to undertake an archaeological assessment of the entire property, including 1:10,000 scale mapping, "Archaeological Site Record" and report(s);(ii) The Owner agrees to implement the recommendations of the approved assessment, including mitigation, through preservation or removal and documentation of archaeological resources; and(iii) The Owner agrees that no site works shall take place until any archaeological resource conservation concerns have been addressed. | OTTAWA Planning MTCS (Ministry provides written clearance to the City prior to registration, usually at the request of the applicant.) |
|-----------------------|---|--|

All of the above noted conditions shall be to the satisfaction of the Ministry of Culture and the General Manager, Planning and Growth Management.

Stormwater Management

- | | | |
|-----------------|--|-----------------------------|
| 109. SW1 | The Owner shall provide to the General Manager, Planning and Growth Management any and all stormwater reports that may be required by the City for approval prior to the commencement of any works in any phase of the Plan of Subdivision. Such reports shall be in accordance with any watershed or subwatershed studies, conceptual stormwater reports, City or Provincial standards, specifications and guidelines. The reports shall include, but not be limited to, the provision of erosion and sedimentation control measures, implementation or phasing requirements of interim or permanent measures, and all stormwater monitoring and testing requirements. All reports shall be to the satisfaction of the General Manager, Planning and Growth Management. | OTTAWA Planning RVCA |
| 110. SW2 | <ul style="list-style-type: none">(a) Prior to the commencement of construction of any phase of this Subdivision (roads, utilities, any off site work, etc.) the Owner shall:<ul style="list-style-type: none">i. have a Stormwater Management Plan and an Erosion and Sediment Control Plan prepared by a Professional Engineer in accordance with Current Best Management Practices, | OTTAWA Planning |

- ii. have said plans approved by the General Manager, Planning and Growth Management, and
- iii. provide certification to the General Manager, Planning and Growth Management through a Professional Engineer that the plans has been implemented.

(b) Any changes made to the Plan shall be submitted to the satisfaction to the City of Ottawa and the Conservation Authority.

(c) The Owner shall implement an inspection and monitoring plan to maintain erosion control measures.

- | | | |
|-----------------|---|---------------------------------------|
| 111. SW3 | On completion of all stormwater works, the Owner shall provide certification to the General Manager, Planning and Growth Management through a Professional Engineer that all measures have been implemented in conformity with the approved Stormwater Site Management Plan. | OTTAWA Planning |
| 112. SW4 | Prior to the registration, or the making of an application for a Ministry of Environment Certificate of Approval for any stormwater works, whichever event first occurs, the Owner shall prepare a Stormwater Site Management Plan in accordance with a Conceptual Stormwater Site Management Plan (specified by title of plan, date). The Stormwater Site Management Plan shall identify the sequence of its implementation in relation to the construction of the subdivision and shall be to the satisfaction of the General Manager, Planning and Growth Management and the (Specify) Conservation Authority. | OTTAWA Planning and CA |
| 113. SW5 | The Owner shall maintain the stormwater management pond in accordance with the recommendations of the Stormwater Management Plan and to the satisfaction of the General Manager, Planning and Growth Management until such time as the stormwater management pond has been given Final Acceptance and assumed by the City of Ottawa. | OTTAWA Planning |
| 114. SW6 | The Owner shall design and construct, as part of the stormwater management infrastructure, at no cost to the City, a monitoring facility or facilities and vehicular access to the satisfaction of the General Manager, Planning and Growth Management. | OTTAWA Planning |
| 115. SW7 | The Owner agrees that the development of the Subdivision shall be undertaken in such a manner as to prevent any adverse effects, and to protect, enhance or restore any of the existing or natural environment, through the preparation of any storm water management reports, as required by the City. All reports are to be approved by the General Manager, Planning and Growth Management prior to the commencement of any Works. | OTTAWA Planning |
| 116. SW8 | The Owner covenants and agrees that the following clause shall be incorporated into all agreements of purchase and sale for the whole or any part of a lot or block on the Plan of Subdivision, and registered separately against the title: | OTTAWA Legal |

"The Owner acknowledges that some of the rear yards within this subdivision

are used for on-site storage of infrequent storm events. Pool installation and/or grading alterations on some of the lots may not be permitted and/or revisions to the approved Subdivision Stormwater Management Plan Report may be required to study the possibility of pool installation on any individual lot. The Owner must obtain approval of the General Manager, Planning and Growth Management of the City of Ottawa prior to undertaking any grading alterations.”

- 117.** The Owner shall acknowledge and agree in the subdivision agreement that the agricultural tile drains encountered during construction shall be decommissioned/removed in accordance with the direction provided in the Fernbank Community Design Plan Environmental Management Plan, as approved by Council June 24, 2009. **OTTAWA Planning**
- 118.** The Owner acknowledges and agrees that prior to early servicing and prior to final approval and registration, a detailed stormwater site management plan in accordance with the Fernbank Community Design Plan, Master Servicing Study and Environmental Management Plan, as approved by Council June 24, 2009 shall be prepared and accepted by the City of Ottawa and Rideau Valley Conservation Authority. The final design shall satisfy the requirements for the receiving stream flow quantity and quality as they relate to natural channel design and the protection of fish habitat and maintenance of the existing hydrological characteristics. The final design shall also account for upstream drainage, including areas serviced by agricultural tiles drains in accordance with the Fernbank Community Design Plan, Master Servicing Study and Environmental Management Plan, as approved by Council June 24, 2009. **OTTAWA Planning**
- 119.** Prior to early servicing and final approval and registration, the Owner shall provide an implementation/staging plan that clearly describes the coordination between the construction of the Pond 6 stormwater management facility and its outlet, related stormwater infrastructure and the undertaking of modifications and improvement works to the Monahan Drain as described in Section 11.9, 11.9.1 & 11.9.2 of the Fernbank Community Design Plan Environmental Management Plan, as approved by Council June 24, 2009. **OTTAWA Planning**
- 120.** The Owner acknowledges and agrees that the proposed stormwater Pond identified as Pond 6 and the outlet to the downstream Monahan Drain shall require an application and approval under Ontario Regulation 174/06 under Section 28 of the Conservation Authorities Act “Development, Interference with Wetlands and Alterations to Shorelines and Watercourses Regulation” prior to undertaking said works. Any applications received in this regard would be assessed within the context of approved policies for the administration of the regulation, including those for the protection of fish habitat. **OTTAWA Planning RVCA**
- 121.** The Owner acknowledges and agrees that the design and construction of the stormwater management facility identified as Pond 6 requires the concurrence and coordination with the adjacent landowner to the west. The **OTTAWA Planning**

Owner shall provide the General Manager, Planning and Growth Management written verification from the abutting owner that there is an agreement with respect to design and construction of Pond 6.

- 122.** Prior to early servicing and final approval and registration, a report documenting the process for undertaking the construction of the stormwater management facility identified as Pond 6 in coordination with the adjacent landowner to the west shall be prepared to the satisfaction of the Rideau Valley Conservation Authority and the City of Ottawa. **OTTAWA Planning RVCA**
- 123.** The Owner acknowledges and agrees that the stormwater management facility identified as Pond 6 is constructed and operational prior to the commissioning of the stormsewers within the plan of subdivision. **OTTAWA Planning**

Sanitary Services

- 124. SS1** The Owner shall submit detailed municipal servicing plans, prepared by a Civil Engineer licensed in the Province of Ontario, to the General Manager, Planning and Growth Management. **OTTAWA Planning**
- 125. SS2** Where the Owner is required under this Agreement to provide and install sanitary sewers of a diameter larger and/or at a greater depth than would be required to service the area to be developed, as detailed in the approved plans of this agreement, the Owner shall convey to the City such 0.3m reserves as may be necessary to prevent the owners and developers of adjacent lands from making connections to the sanitary sewers installed by the Owner. Insofar as it legally may, the City will require other persons connecting to the sewer to pay an equitable share of the cost thereof to the Owner, the amount of which payment shall be determined by the General Manager, Planning and Growth Management. **OTTAWA Planning**
- 126. SS3** Where the Owner is required under this Agreement to provide the oversize and/or over-depth storm sewers or open drains in order to make provisions for later development of upstream lands not owned by the Owner herein, as referred to in the approved plans, the City shall, insofar as it legally may, require that payment shall be made by the Owner of such upstream undeveloped land which will utilize the said storm sewers as an outlet(s), prior to the approval of a Plan of Subdivision for such land by the City, the amount of which shall be determined by the General Manager, Planning and Growth Management. **OTTAWA Planning**
- 127. SS4** As the Owner proposes a road allowance(s) of less than 20 meters, and if the Owner also proposed boulevards between 4.0 and 5.0 meters wide, the Owner shall meet the following requirements: **OTTAWA Planning**
- a) extend water, sanitary, and storm services a minimum of 2.0 meters onto private property during installation before being capped;
 - b) install hydro high voltage cable through the transformer foundations to maintain adequate clearance from the gas main;

Appendix B

SWM Calculations & Design Sheets

- *Storm Sewer Design Sheet*
- *Typical Lot Impervious Calculations*

Fernbank Crossing (Phase 5 and Phase 4) - Storm Sewer Design Sheet (Rational Method)

| LOCATION | | | AREA | | | | | | | FLOW | | | | | Total Peak Flow (Q) (L/s) | PROPOSED SEWER | | | | | | | | |
|--------------------------------------|-----------|---------|-------------------------------------|---------------------|-------------------|------------------|-----------------|------------|-----------------------------|----------------|---------------|--|------------------------|------|------------------------------|--|------|------|-------|--------|----------|--------------------|--------------|---------|
| Location | From node | To node | Parks | Singles Front Yards | Singles Rear Yard | Towns Front Yard | Towns Rear Yard | Total Area | Weighted Runoff Coefficient | Indivi 2.78 AR | Accum 2.78 AR | Time of Concentration | Rain Intensity (mm/hr) | | | Peak Flow | Pipe | Size | Grade | Length | Capacity | Full Flow Velocity | Time of Flow | Q/Qfull |
| | | | | | | | | | | | | | 5yr | 10yr | | | | | | | | | | |
| | | | 0.40 | 0.65 | 0.55 | 0.70 | 0.60 | (ha) | | | | | | | (L/s) | | | | | | | | | |
| Phase 5 (Outletting through Phase 4) | | | | | | | | | | | | | | | | | | | | | | | | |
| 647 | 333 | 331 | | | | 0.16 | | 0.16 | 0.70 | 0.31 | 0.31 | 10.00 | 104.2 | | 32.4 | 32.4 | PVC | 375 | 1.00 | 36.4 | 182.9 | 1.60 | 0.38 | 17.7% |
| | | | | | | | | 0.00 | | 0.00 | 0.00 | 10.00 | | | 0.0 | | | | | | | | | |
| 648, 657 | 507 | 331 | | | | 0.27 | 0.05 | 0.32 | 0.68 | 0.61 | 0.61 | 10.00 | 104.2 | | 63.4 | 63.4 | PVC | 300 | 1.00 | 69.6 | 100.9 | 1.38 | 0.84 | 62.9% |
| | | | | | | | | 0.00 | | 0.00 | 0.00 | 10.00 | | | 0.0 | | | | | | | | | |
| 649, 650, 660 | 331 | 329 | | | | 0.31 | 0.22 | 0.53 | 0.66 | 0.97 | 1.89 | 10.84 | 100.0 | | 189.0 | 189.0 | PVC | 450 | 0.75 | 78.0 | 257.6 | 1.57 | 0.83 | 73.4% |
| | | | | | | | | 0.00 | | 0.00 | 0.00 | 10.84 | | | 0.0 | | | | | | | | | |
| | 505 | 503 | | | | | | 0.00 | 0.00 | 0.00 | 0.00 | 10.00 | | | 0.0 | 0.0 | PVC | 250 | 2.00 | 12.4 | 87.7 | 1.73 | 0.12 | 0.0% |
| | | | | | | | | 0.00 | | 0.00 | 0.00 | 10.00 | | | 0.0 | | | | | | | | | |
| 646 | 503 | 501 | | | | 0.17 | | 0.17 | 0.70 | 0.33 | 0.33 | 10.12 | 103.6 | | 34.3 | 34.3 | PVC | 300 | 2.00 | 70.8 | 142.7 | 1.96 | 0.60 | 24.0% |
| | | | | | | | | 0.00 | | 0.00 | 0.00 | 10.12 | | | 0.0 | | | | | | | | | |
| | 501 | 329 | | | | | | 0.00 | 0.00 | 0.00 | 0.33 | 10.72 | 100.5 | | 33.3 | 33.3 | PVC | 375 | 1.00 | 20.5 | 182.9 | 1.60 | 0.21 | 18.2% |
| | | | | | | | | 0.00 | | 0.00 | 0.00 | 10.72 | | | 0.0 | | | | | | | | | |
| 653, 661 | 329 | 327 | | | | 0.25 | | 0.25 | 0.70 | 0.49 | 2.71 | 11.67 | 96.1 | | 260.3 | 260.3 | CONC | 525 | 0.80 | 76.9 | 401.3 | 1.80 | 0.71 | 64.9% |
| | | | | | | | | 0.00 | | 0.00 | 0.00 | 11.67 | | | 0.0 | | | | | | | | | |
| | 327 | 325 | | | | | | 0.00 | 0.00 | 0.00 | 2.71 | 12.38 | 93.1 | | 252.1 | 252.1 | CONC | 600 | 0.35 | 8.6 | 379.0 | 1.30 | 0.11 | 66.5% |
| | | | | | | | | 0.00 | | 0.00 | 0.00 | 12.38 | | | 0.0 | | | | | | | | | |
| 651, 654 | 325 | 323 | | | | 0.33 | 0.21 | 0.54 | 0.66 | 0.99 | 3.70 | 12.49 | 92.6 | | 342.8 | 342.8 | CONC | 675 | 0.35 | 75.6 | 518.8 | 1.40 | 0.90 | 66.1% |
| | | | | | | | | 0.00 | | 0.00 | 0.00 | 12.49 | | | 0.0 | | | | | | | | | |
| 652, 677 | 323 | 319 | | | | 0.35 | 0.22 | 0.57 | 0.66 | 1.05 | 4.75 | 13.39 | 89.2 | | 423.3 | 423.3 | CONC | 750 | 0.35 | 72.6 | 687.1 | 1.51 | 0.80 | 61.6% |
| | | | | | | | | 0.00 | | 0.00 | 0.00 | 13.39 | | | 0.0 | | | | | | | | | |
| 693 | 321 | 319 | | 0.16 | | | | 0.16 | 0.65 | 0.29 | 0.29 | 10.00 | 104.2 | | 30.1 | 30.1 | PVC | 300 | 4.00 | 69.1 | 201.8 | 2.77 | 0.42 | 14.9% |
| | | | | | | | | 0.00 | | 0.00 | 0.00 | 10.00 | | | 0.0 | | | | | | | | | |
| 655, 692 | 319 | 313 | | 0.47 | | | | 0.47 | 0.65 | 0.85 | 5.89 | 14.19 | 86.3 | | 507.8 | 507.8 | CONC | 750 | 0.35 | 81.2 | 687.1 | 1.51 | 0.90 | 73.9% |
| | | | | | | | | 0.00 | | 0.00 | 0.00 | 14.19 | | | 0.0 | | | | | | | | | |
| 656 | 317 | 315 | | 0.10 | | | | 0.10 | 0.65 | 0.18 | 0.18 | 10.00 | 104.2 | | 18.8 | 18.8 | PVC | 375 | 0.30 | 75.4 | 100.2 | 0.88 | 1.43 | 18.8% |
| | | | | | | | | 0.00 | | 0.00 | 0.00 | 10.00 | | | 0.0 | | | | | | | | | |
| 681, 687, 682, 688 | 315 | 313 | | 0.61 | 1.07 | | | 1.68 | 0.59 | 2.74 | 2.92 | 11.43 | 97.2 | | 283.7 | 283.7 | CONC | 600 | 0.30 | 80.5 | 350.8 | 1.20 | 1.12 | 80.9% |
| | | | | | | | | 0.00 | | 0.00 | 0.00 | 11.43 | | | 0.0 | | | | | | | | | |
| 694, 696 | 313 | 311 | | 0.46 | 0.27 | | | 0.73 | 0.61 | 1.24 | 10.05 | 15.09 | 83.3 | | 836.8 | 836.8 | CONC | 975 | 0.25 | 83.5 | 1169.0 | 1.52 | 0.92 | 71.6% |
| | | | | | | | | 0.00 | | 0.00 | 0.00 | 15.09 | | | 0.0 | | | | | | | | | |
| 703 | 311 | 307 | | 0.39 | | | | 0.39 | 0.65 | 0.70 | 10.75 | 16.01 | 80.4 | | 865.1 | 865.1 | CONC | 1050 | 0.25 | 81.9 | 1424.4 | 1.59 | 0.86 | 60.7% |
| | | | | | | | | 0.00 | | 0.00 | 0.00 | 16.01 | | | 0.0 | | | | | | | | | |
| 695, 699, 707, 709, 714 | 309 | 307 | 1.28 | 0.40 | 0.27 | | | 1.95 | 0.47 | 2.56 | 2.56 | 10.00 | 104.2 | | 266.6 | 266.6 | PVC | 450 | 1.64 | 119.0 | 380.9 | 2.32 | 0.85 | 70.0% |
| | | | | | | | | 0.00 | | 0.00 | 0.00 | 10.00 | | | 0.0 | | | | | | | | | |
| 698, 702, 724 | 433 | 307 | | 0.12 | 0.58 | | | 0.70 | 0.57 | 1.10 | 1.10 | 10.00 | 104.2 | | 115.0 | 115.0 | PVC | 375 | 0.50 | 45.8 | 129.3 | 1.13 | 0.67 | 88.9% |
| | | | | | | | | 0.00 | | 0.00 | 0.00 | 10.00 | | | 0.0 | | | | | | | | | |
| 701 | 307 | 305 | | | 0.14 | | | 0.14 | 0.55 | 0.21 | 14.63 | 16.86 | 78.0 | | 1141.0 | 1141.0 | CONC | 1050 | 0.25 | 78.8 | 1424.4 | 1.59 | 0.82 | 80.1% |
| | | | | | | | | 0.00 | | 0.00 | 0.00 | 16.86 | | | 0.0 | | | | | | | | | |
| 715 | 305 | 303 | | 0.44 | | | | 0.44 | 0.65 | 0.80 | 15.43 | 17.69 | 75.8 | | 1168.9 | 1168.9 | CONC | 1050 | 0.25 | 84.8 | 1424.4 | 1.59 | 0.89 | 82.1% |
| | | | | | | | | 0.00 | | 0.00 | 0.00 | 17.69 | | | 0.0 | | | | | | | | | |
| 725, 726 | 303 | 301 | | 0.32 | 0.32 | | | 0.64 | 0.60 | 1.07 | 16.49 | 18.58 | 73.5 | | 1213.0 | 1213.0 | CONC | 1200 | 0.25 | 54.7 | 2033.7 | 1.74 | 0.52 | 59.6% |
| | | | | | | | | 0.00 | | 0.00 | 0.00 | 18.58 | | | 0.0 | | | | | | | | | |
| Q = 2.78 AIR | | | WHERE : Q = (1/n) A R^(2/3)So^(1/2) | | | | | | | WHERE : | | Q = CAPACITY (L/s) n = MANNING COEFFICIENT OF ROUGHNESS (0.013) A = FLOW AREA (m2) | | | | Project: Fernbank Crossing, Phase 5 (108180-19) Designed: LRW Checked: MAB Date: December 7, 2018 | | | | | | | | |



LIVERY STREET

BLOCK 497A

FRONTYARD AREA = 207.151 m²
 AREA OF IMPERVIOUSNESS = 141.718 m²
 TOTAL IMPERVIOUSNESS = 68.4 %

REARYARD AREA = 144.070 m²
 AREA OF IMPERVIOUSNESS = 69.418 m²
 TOTAL IMPERVIOUSNESS = 48.2 %

NOVATECH
 ENGINEERING
 CONSULTANTS LTD.

ENGINEERS & PLANNERS

Suite 200, 240 Michael Cowpland Drive
 Ottawa, Ontario, Canada
 K2M 1P6

Telephone (613) 254-9643
 Facsimile (613) 254-5867
 Email: novainfo@novatech-eng.com

FERNBANK LANDS

EXAMPLE LOT 1 - TOWNS

JULY 2012

108180

TOWN 1

Appendix C

Autodesk Storm and Sanitary Analysis Model

- *HGL Elevations*
- *Ponding Depths*
- *ICD Chart*
- *Catchbasin Inlet Curves*

Schematics:

- *SSA Legend*
- *Overall Model Schematic*

Design Storms:

- *Chicago 3-hour Events*
- *SCS 12-hour Events*

Fernbank Crossing - Phase 5

Inlet Control Device Parameters


| Structure | ICD Size & Inlet Rate | | | | | | 5-year Peak Flow to CB** (L/s) |
|-----------------|-----------------------|---------------------|------------|---------------|-----------------|---------------------------------------|-----------------------------------|
| | Diameter 1 (mm) | Diameter 2* (mm) | T/G (m) | Invert (m) | Max Head (m) | Calculated 5-yr Capture Rate (L/s) | |
| ROW CBs | | | | | | | |
| CB187-188 | 83 | 83 | 104.59 | 103.19 | 1.36 | 35 | 38 |
| CB189-190 | 94 | 94 | 105.54 | 104.14 | 1.35 | 44 | 49 |
| CB191-192 | 83 | 83 | 105.51 | 104.11 | 1.36 | 35 | 35 |
| CB193-194 | 102 | 102 | 104.37 | 102.97 | 1.35 | 52 | 60 |
| CB195 | 83 | 0 | 103.82 | 102.42 | 1.36 | 17 | 27 |
| Rear Yard CBMHs | | | | | | | |
| RYCB09 | 83 | 0 | 105.96 | 103.32 | 2.60 | 24 | 8 |
| RYCB11 | 108 | 0 | 105.17 | 103.51 | 1.61 | 32 | 46 |
| CBMH16 | 83 | 0 | 104.28 | 102.53 | 1.71 | 19 | 25 |

*Diameter 2 only specified where catchbasins are not interconnected

**From SSA Model, 5-year 3-hour Chicago storm distribution

Fernbank Corssing - Phase 5

ICD Rating Curves



Fernbank Crossing - Phase 5
Ponding in Road Calculations



| Structure | T/G (m) | Max. Static Ponding (Spill Depth) | | 5-yr Event (3hr) | | | | 100-yr Event (3hr) | | | | 100-yr Event (+20%) (3hr) | | | |
|-----------|------------|--------------------------------------|--------------|------------------|--------------|--------------------|--------------------|--------------------|--------------|--------------------|----------------------|---------------------------|--------------|--------------------|--------------------|
| | | Elev. (m) | Depth (m) | Elev. (m) | Depth (m) | Cascading Flow? | Cascade Depth m | Elev. (m) | Depth (m) | Cascading Flow? | Cascade Depth (m) | Elev. (m) | Depth (m) | Cascading Flow? | Cascade Depth m |
| CB189-190 | 105.54 | 105.70 | 0.16 | 105.57 | 0.03 | N | 0.00 | 105.69 | 0.15 | N | 0.00 | 105.71 | 0.17 | Y | 0.01 |
| CB191-192 | 105.51 | 105.58 | 0.07 | 105.49 | 0.00 | N | 0.00 | 105.66 | 0.15 | Y | 0.08 | 105.68 | 0.17 | Y | 0.10 |
| CB193-194 | 104.37 | 104.50 | 0.13 | 104.41 | 0.04 | N | 0.00 | 104.54 | 0.17 | Y | 0.04 | 104.56 | 0.19 | Y | 0.06 |

Fernbank Crossing - Phase 5

HGL Elevations

| Manhole ID | MH Invert Elevation (m) | T/G Elevation (m) | 100yr-3hr HGL Elevation (m) | 100yr-3hr+20% HGL Elevation (m) | Design USF (m) | Clearance (100yr) (m) | Clearance (100yr+20%) (m) |
|----------------------|----------------------------|----------------------|-----------------------------------|---------------------------------------|----------------------|-----------------------------|---------------------------------|
| HGL - Phase 5 | | | | | | | |
| 501 | 100.81 | 104.24 | 101.32 | 101.32 | 102.87 | 1.55 | 1.55 |
| 503 | 102.36 | 105.84 | 102.68 | 102.68 | 103.90 | 1.22 | 1.22 |
| 505 | 102.58 | 105.79 | 102.98 | 102.99 | 103.90 | 0.92 | 0.91 |
| 507 | 102.43 | 105.69 | 102.32 | 102.33 | 103.78 | 1.46 | 1.45 |
| 509 | 101.97 | 105.63 | 103.17 | 103.18 | 104.03 | 0.86 | 0.85 |
| HGL - Phase 4 | | | | | | | |
| 301 | 96.64 | 101.51 | 98.86 | 98.91 | 99.86 | 1.00 | 0.95 |
| 303 | 97.86 | 101.65 | 99.04 | 99.12 | 100.06 | 1.02 | 0.94 |
| 305 | 98.10 | 101.88 | 99.39 | 99.52 | 100.16 | 0.77 | 0.64 |
| 307 | 98.29 | 102.09 | 99.66 | 99.83 | 100.26 | 0.60 | 0.43 |
| 309 | 100.67 | 103.82 | 101.14 | 101.16 | 101.77 | 0.63 | 0.61 |
| 311 | 98.65 | 102.41 | 99.81 | 100.02 | 100.41 | 0.60 | 0.39 |
| 313 | 98.62 | 102.41 | 100.03 | 100.26 | 100.48 | 0.45 | 0.22 |
| 315 | 99.13 | 102.38 | 100.12 | 100.37 | 100.66 | 0.54 | 0.29 |
| 317 | 99.50 | 102.38 | 100.14 | 100.40 | 100.81 | 0.67 | 0.41 |
| 319 | 99.06 | 102.99 | 100.32 | 100.56 | 100.85 | 0.53 | 0.29 |
| 321 | 102.54 | 105.45 | 102.71 | 102.71 | 103.37 | 0.66 | 0.66 |
| 323 | 99.38 | 103.21 | 100.47 | 100.73 | 101.45 | 0.98 | 0.72 |
| 325 | 99.72 | 103.29 | 100.67 | 100.94 | 101.68 | 1.01 | 0.74 |
| 327 | 99.82 | 103.33 | 100.73 | 101.01 | 101.68 | 0.95 | 0.67 |
| 329 | 100.39 | 103.84 | 101.12 | 101.27 | 102.10 | 0.98 | 0.83 |
| 331 | 101.16 | 104.66 | 101.67 | 101.69 | 102.90 | 1.23 | 1.21 |
| 333 | 101.67 | 105.03 | 102.05 | 102.05 | 103.20 | 1.15 | 1.15 |
| HGL - Phase 3 | | | | | | | |
| 343 | 98.71 | 103.09 | 100.52 | 100.65 | 101.36 | 0.84 | 0.71 |
| 345 | 101.15 | 104.26 | 101.47 | 101.47 | 102.24 | 0.77 | 0.77 |
| 347 | 98.78 | 103.46 | 100.98 | 101.15 | 101.68 | 0.70 | 0.53 |
| 349 | 100.46 | 104.47 | 101.28 | 101.46 | 102.47 | 1.19 | 1.01 |
| 351 | 99.23 | 104.05 | 101.22 | 101.40 | 102.05 | 0.83 | 0.65 |
| 353 | 101.12 | 104.86 | 101.42 | 101.55 | 102.71 | 1.29 | 1.16 |
| 357 | 101.60 | 104.65 | 102.27 | 102.29 | 102.85 | 0.58 | 0.56 |
| 359 | 102.24 | 105.24 | 102.80 | 102.80 | 103.25 | 0.45 | 0.45 |
| 373 | 101.88 | 104.40 | 102.01 | 102.03 | 102.75 | 0.74 | 0.72 |
| 375 | 101.22 | 104.76 | 102.18 | 102.21 | 103.04 | 0.86 | 0.83 |
| 377 | 101.37 | 104.98 | 102.31 | 102.34 | 103.17 | 0.86 | 0.83 |
| 379 | 101.66 | 104.99 | 102.50 | 102.52 | 103.07 | 0.57 | 0.55 |
| 381 | 101.80 | 105.14 | 102.60 | 102.62 | 103.18 | 0.58 | 0.56 |
| 383 | 102.06 | 105.23 | 102.85 | 102.87 | 103.61 | 0.76 | 0.74 |
| 385 | 102.08 | 105.26 | 102.92 | 102.94 | 103.61 | 0.69 | 0.67 |
| 387 | 102.19 | 105.17 | 103.02 | 103.04 | 103.44 | 0.42 | 0.40 |
| 389 | 102.87 | 105.46 | 103.15 | 103.17 | 103.64 | 0.49 | 0.47 |
| 391 | 100.71 | 103.19 | 102.44 | 102.45 | - | - | - |
| 393 | 101.13 | 103.91 | 101.47 | 101.47 | 101.88 | 0.41 | 0.41 |
| 395 | 98.90 | 103.18 | 100.66 | 100.80 | 101.44 | 0.78 | 0.64 |
| 397 | 100.09 | 103.94 | 101.29 | 101.46 | 102.05 | 0.76 | 0.59 |
| 399 | 100.71 | 104.22 | 101.36 | 101.55 | 102.34 | 0.98 | 0.79 |
| 417 | 99.89 | 103.87 | 101.31 | 101.47 | 102.12 | 0.81 | 0.65 |
| 419 | 102.04 | 104.86 | 102.77 | 102.79 | 103.30 | 0.53 | 0.51 |


Fernbank Crossing - Phase 5


HGL Elevations

| Manhole ID | MH Invert Elevation (m) | T/G Elevation (m) | 100yr-3hr HGL Elevation (m) | 100yr-3hr+20% HGL Elevation (m) | Design USF (m) | Clearance (100yr) (m) | Clearance (100yr+20%) (m) |
|-------------------------|-------------------------------|----------------------|-----------------------------------|---------------------------------------|----------------------|-----------------------------|---------------------------------|
| HGL - Cope Drive | | | | | | | |
| 301 | 96.94 | 101.51 | 98.86 | 98.91 | 99.86 | 1.00 | 0.95 |
| 335 | 96.66 | 101.86 | 99.21 | 99.28 | 100.05 | 0.84 | 0.77 |
| 337 | 96.79 | 102.14 | 99.47 | 99.55 | 100.30 | 0.83 | 0.75 |
| 339 | 96.90 | 102.43 | 99.68 | 99.77 | 100.55 | 0.87 | 0.78 |
| 341 | 97.32 | 102.85 | 100.09 | 100.21 | 101.23 | 1.14 | 1.02 |
| 361 | 99.03 | 103.65 | 100.83 | 100.99 | 101.87 | 1.04 | 0.88 |
| 363 | 100.40 | 104.46 | 101.51 | 101.59 | 102.41 | 0.90 | 0.82 |
| 365 | 101.02 | 104.46 | 101.95 | 101.95 | 102.50 | 0.55 | 0.55 |
| 367 | 101.34 | 104.59 | 102.08 | 102.08 | 102.67 | 0.59 | 0.59 |
| 369 | 101.59 | 104.55 | 102.18 | 102.19 | 102.77 | 0.59 | 0.58 |
| 371 | 102.04 | 104.86 | 102.54 | 102.54 | 102.95 | 0.41 | 0.41 |
| 391 | 100.71 | 104.40 | 102.44 | 102.45 | - | - | - |
| M97 | 96.25 | 101.00 | 98.44 | 98.47 | 99.86 | 1.42 | 1.39 |
| M98 | 95.80 | 100.75 | 98.15 | 98.16 | 99.86 | 1.71 | 1.70 |

Fernbank Crossing - Phase 5

SSA Legend





Fernbank Crossing - Phase 5
Design Storm Time Series Data
3-hour Chicago Design Storms



| C25mm-3.stm | | C2-3.stm | | C5-3.stm | |
|-------------|-----------|----------|-----------|----------|-----------|
| Duration | Intensity | Duration | Intensity | Duration | Intensity |
| min | mm/hr | min | mm/hr | min | mm/hr |
| 0:00 | 0 | 0:00 | 0 | 0:00 | 0 |
| 0:10 | 2.21 | 0:10 | 2.81 | 0:10 | 3.68 |
| 0:20 | 2.75 | 0:20 | 3.5 | 0:20 | 4.58 |
| 0:30 | 3.68 | 0:30 | 4.69 | 0:30 | 6.15 |
| 0:40 | 5.73 | 0:40 | 7.3 | 0:40 | 9.61 |
| 0:50 | 14.29 | 0:50 | 18.21 | 0:50 | 24.17 |
| 1:00 | 60.28 | 1:00 | 76.81 | 1:00 | 104.19 |
| 1:10 | 18.9 | 1:10 | 24.08 | 1:10 | 32.04 |
| 1:20 | 9.7 | 1:20 | 12.36 | 1:20 | 16.34 |
| 1:30 | 6.53 | 1:30 | 8.32 | 1:30 | 10.96 |
| 1:40 | 4.94 | 1:40 | 6.3 | 1:40 | 8.29 |
| 1:50 | 3.99 | 1:50 | 5.09 | 1:50 | 6.69 |
| 2:00 | 3.37 | 2:00 | 4.29 | 2:00 | 5.63 |
| 2:10 | 2.92 | 2:10 | 3.72 | 2:10 | 4.87 |
| 2:20 | 2.58 | 2:20 | 3.29 | 2:20 | 4.3 |
| 2:30 | 2.32 | 2:30 | 2.95 | 2:30 | 3.86 |
| 2:40 | 2.1 | 2:40 | 2.68 | 2:40 | 3.51 |
| 2:50 | 1.93 | 2:50 | 2.46 | 2:50 | 3.22 |
| 3:00 | 1.79 | 3:00 | 2.28 | 3:00 | 2.98 |

Fernbank Crossing - Phase 5
Design Storm Time Series Data
3-hour Chicago Design Storms



| C100-3.stm | | C100-3+20%.stm | |
|------------|-----------|----------------|-----------|
| Duration | Intensity | Duration | Intensity |
| min | mm/hr | min | mm/hr |
| 0:00 | 0 | 0:00 | 0 |
| 0:10 | 6.05 | 0:10 | 6.14 |
| 0:20 | 7.54 | 0:20 | 9.05 |
| 0:30 | 10.16 | 0:30 | 12.19 |
| 0:40 | 15.97 | 0:40 | 19.16 |
| 0:50 | 40.65 | 0:50 | 48.78 |
| 1:00 | 178.56 | 1:00 | 214.27 |
| 1:10 | 54.05 | 1:10 | 64.86 |
| 1:20 | 27.32 | 1:20 | 32.78 |
| 1:30 | 18.24 | 1:30 | 21.89 |
| 1:40 | 13.74 | 1:40 | 16.49 |
| 1:50 | 11.06 | 1:50 | 13.27 |
| 2:00 | 9.29 | 2:00 | 11.15 |
| 2:10 | 8.02 | 2:10 | 9.62 |
| 2:20 | 7.08 | 2:20 | 8.5 |
| 2:30 | 6.35 | 2:30 | 7.62 |
| 2:40 | 5.76 | 2:40 | 6.91 |
| 2:50 | 5.28 | 2:50 | 6.34 |
| 3:00 | 4.88 | 3:00 | 5.86 |

Fernbank Crossing - Phase 5
Design Storm Time Series Data
SCS Design Storms



| S2-12.stm | | S5-12.stm | | S100-12.stm | |
|-----------|-----------|-----------|-----------|-------------|-----------|
| Duration | Intensity | Duration | Intensity | Duration | Intensity |
| min | mm/hr | min | mm/hr | min | mm/hr |
| 0:00 | 0.00 | 0:00 | 0 | 0:00 | 0 |
| 0:30 | 1.27 | 0:30 | 1.69 | 0:30 | 2.82 |
| 1:00 | 0.59 | 1:00 | 0.79 | 1:00 | 1.31 |
| 1:30 | 1.10 | 1:30 | 1.46 | 1:30 | 2.44 |
| 2:00 | 1.10 | 2:00 | 1.46 | 2:00 | 2.44 |
| 2:30 | 1.44 | 2:30 | 1.91 | 2:30 | 3.19 |
| 3:00 | 1.27 | 3:00 | 1.69 | 3:00 | 2.82 |
| 3:30 | 1.69 | 3:30 | 2.25 | 3:30 | 3.76 |
| 4:00 | 1.69 | 4:00 | 2.25 | 4:00 | 3.76 |
| 4:30 | 2.29 | 4:30 | 3.03 | 4:30 | 5.07 |
| 5:00 | 2.88 | 5:00 | 3.82 | 5:00 | 6.39 |
| 5:30 | 4.57 | 5:30 | 6.07 | 5:30 | 10.14 |
| 6:00 | 36.24 | 6:00 | 48.08 | 6:00 | 80.38 |
| 6:30 | 9.23 | 6:30 | 12.25 | 6:30 | 20.47 |
| 7:00 | 4.06 | 7:00 | 5.39 | 7:00 | 9.01 |
| 7:30 | 2.71 | 7:30 | 3.59 | 7:30 | 6.01 |
| 8:00 | 2.37 | 8:00 | 3.15 | 8:00 | 5.26 |
| 8:30 | 1.86 | 8:30 | 2.47 | 8:30 | 4.13 |
| 9:00 | 1.95 | 9:00 | 2.58 | 9:00 | 4.32 |
| 9:30 | 1.27 | 9:30 | 1.69 | 9:30 | 2.82 |
| 10:00 | 1.02 | 10:00 | 1.35 | 10:00 | 2.25 |
| 10:30 | 1.44 | 10:30 | 1.91 | 10:30 | 3.19 |
| 11:00 | 0.93 | 11:00 | 1.24 | 11:00 | 2.07 |
| 11:30 | 0.85 | 11:30 | 1.12 | 11:30 | 1.88 |
| 12:00 | 0.85 | 12:00 | 1.12 | 12:00 | 1.88 |

Appendix D Drawings

- *Draft Plan of Subdivision* (Annis, O'Sullivan, Vollebekk)
- *General Plan* 108180-19-GP
- *Grading Plan* 108180-19-GR
- *Storm Drainage Area Plans* 108180-19-STM
- *Erosion and Sediment Control Plan* 108180-19-ESC

ROBERT GRANT AVENUE

BLOCK 129

FUTURE PARK N' RIDE
(BY OTHERS)

PHASE 3

PHASE 5

TIM SHEEHAN PLACE

FERNBANK ROAD

5572 FERNBANK ROAD

NORTH

KEY PLAN

N.T.S.

LEGEND

- SANITARY MANHOLE, SEWER & DIRECTION OF FLOW
○ STORM MANHOLE, SEWER & DIRECTION OF FLOW
— WATERMAIN AND DIAMETER
V VALVE & VALVE BOX
VC VALVE & VALVE CHAMBER
B BEND AND THRUST BLOCK
HYD HYDRANT C/W VALVE & LEAD
CAP
REDUCER
PRV PRESSURE REDUCING VALVE
- ROAD CATCHBASIN
ROAD CATCHBASIN WITH ICD
LANDSCAPE TYPE CATCHBASIN
REAR YARD CATCH BASIN
CATCH BASIN MANHOLE
SINGLE SERVICE LOCATION
DOUBLE SERVICE LOCATION
PHASING BOUNDARY

GENERAL NOTES:

- DIMENSIONS AND LAYOUT INFORMATION SHALL BE CONFIRMED PRIOR TO COMMENCEMENT OF CONSTRUCTION.
- THE ORIGINAL TOPOGRAPHY AND GROUND ELEVATIONS, SERVICING AND SURVEY INFORMATION SHOWN ON THIS PLAN ARE SUPPLIED FOR INFORMATION PURPOSES ONLY. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY THE ACCURACY OF ALL INFORMATION OBTAINED FROM THIS PLAN.
- CO-ORDINATE AND SCHEDULE ALL WORK WITH OTHER TRADES AND CONTRACTORS.
- BEFORE COMMENCING CONSTRUCTION, PROVIDE PROOF OF COMPREHENSIVE ALL RISK AND OPERATIONAL LIABILITY INSURANCE INCLUDING BLASTING, INSURANCE POLICY TO NAME THE OWNER, ENGINEER AND THE CITY AS CO-INSURED.
- CONNECT TO EXISTING SYSTEMS AS DETAILED, INCLUDING ALL RESTORATION WORK NECESSARY TO REINSTATE SURFACES TO EXISTING CONDITIONS OR BETTER.
- DETERMINE THE EXACT LOCATION, SIZE, MATERIAL AND ELEVATION OF ALL EXISTING UTILITIES PRIOR TO COMMENCING CONSTRUCTION. PROTECT AND ASSUME RESPONSIBILITY FOR ALL EXISTING UTILITIES WHETHER OR NOT SHOWN ON THESE DRAWINGS.
- OBTAIN AND PAY FOR ALL NECESSARY PERMITS AND APPROVALS BEFORE COMMENCING CONSTRUCTION.
- RESTORE ALL TRENCHES AND SURFACE FEATURES TO EXISTING CONDITIONS OR BETTER AND TO THE SATISFACTION OF MUNICIPAL AUTHORITIES.
- REMOVE FROM SITE ALL EXCESS EXCAVATED MATERIAL UNLESS OTHERWISE INSTRUCTED BY THE ENGINEER. EXCAVATE AND REMOVE FROM SITE ALL ORGANIC MATERIAL AND DEBRIS UNLESS OTHERWISE INSTRUCTED BY THE ENGINEER.
- ALL ELEVATIONS ARE GEODETIC AND UTILIZE METRIC UNITS.
- REFER TO GEOTECHNICAL INVESTIGATION (DATED NOVEMBER 19, 2018), PREPARED BY GEMTEC FOR SUBSURFACE CONDITIONS AND CONSTRUCTION RECOMMENDATIONS.
- PERFORATED PIPE SUB-DRAINS TO BE PROVIDED AT SUBGRADE LEVEL EXTENDING FROM THE ROADSIDE CATCHBASIN FOR A DISTANCE OF 3.0m, PARALLEL TO THE CURB IN TWO DIRECTIONS.

SEWER NOTES:

- SPECIFICATIONS:

| ITEM | SPEC. No. | REFERENCE |
|-----------------------------------|--------------------|---------------------------------------|
| CATCH-BASIN (600x600mm) | 705.010 | OPSD |
| CATCH-BASIN MANHOLE (12000) | 701.010 | OPSD |
| STORM / SANITARY MANHOLE (12000) | 701.010 | OPSD |
| ROADSIDE CB, FRAME & COVER | S2 & S19 | CITY OF OTTAWA |
| CBMH FRAME & COVER | S25 & S24.1 | CITY OF OTTAWA |
| STORM / SANITARY MH FRAME & COVER | S24.1 / S24 & S25 | CITY OF OTTAWA |
| STORM SEWER | PVC DR 35 OR CONC. | (CLASS SPECIFIED ON PROFILE DRAWINGS) |
| SANITARY SEWER | PVC DR 35 | |
| CATCH-BASIN LEAD | PVC DR 35 | |
- INSULATE ALL PIPES (SAN/STM) THAT HAVE LESS THAN 1.5m COVER WITH 50mmX1200mm H-40 INSULATION. PROVIDE 150mm CLEARANCE BETWEEN PIPE AND INSULATION.
- SERVICES ARE TO BE CONSTRUCTED TO PROPERTY LINE AT MINIMUM SLOPE OF 1.0% (2.0% IS PREFERRED).
- PIPE BEDDING, COVER AND BACKFILL ARE TO BE COMPACTED TO AT LEAST 95% OF THE STANDARD PROCTOR MAXIMUM DRY DENSITY. THE USE OF CLEAR CRUSHED STONE AS A BEDDING LAYER SHALL NOT BE PERMITTED.
- SEWER SERVICE CONNECTIONS PER CITY OF OTTAWA DETAILS S11 AND S11.1.
- THE SITE SERVICING CONTRACTOR SHALL PERFORM FIELD TESTS FOR QUALITY CONTROL OF ALL SANITARY SEWERS. LEAKAGE TESTING SHALL BE COMPLETED IN ACCORDANCE WITH OPS3 410.07.16 AND 407.07.24. DYE TESTING IS TO BE COMPLETED ON ALL SANITARY SERVICES TO CONFIRM PROPER CONNECTION TO THE SANITARY SEWER MAIN. THE FIELD TESTS SHALL BE PERFORMED IN THE PRESENCE OF THE ENGINEER.
- STORM MANHOLES AND CBMHs SHALL HAVE 300mm SLUMPS UNLESS OTHERWISE INDICATED.
- CONTRACTOR TO TELE-TEST (CCTV) ALL PROPOSED SEWERS, 200mm OR GREATER PRIOR TO BASE COURSE ASPHALT, UPON COMPLETION OF CONTRACT, THE CONTRACTOR IS RESPONSIBLE TO FLUSH AND CLEAN ALL SEWERS & APPURTENANCES.

WATERMAIN NOTES:

- GENERAL:

| ITEM | DETAIL No. | REFERENCE |
|---|-------------|----------------|
| WATERMAIN TRENCHING | W17 | CITY OF OTTAWA |
| THERMAL INSULATION IN SHALLOW TRENCHES | W22 | CITY OF OTTAWA |
| WATERMAIN CROSSING BELOW SEWER / OVER SEWER | W25 / W25.2 | CITY OF OTTAWA |
- THE WATERMAIN SHALL BE PVC DR 18 IN ACCORDANCE WITH MATERIAL SPECIFICATION MW-18.1, UNLESS OTHERWISE INDICATED.
- SUPPLY AND CONSTRUCT ALL WATERMANS AND APPURTENANCES IN ACCORDANCE WITH THE CITY OF OTTAWA STANDARDS AND SPECIFICATIONS. EXCAVATION, INSTALLATION, BACKFILL AND RESTORATION OF ALL WATERMANS BY THE CONTRACTOR. CONNECTIONS AND SHUT-OFFS AT THE MAIN AND CHLORINATION OF THE WATER SYSTEM SHALL BE PERFORMED BY CITY OFFICIALS.
- WATERMAIN SHALL BE MINIMUM 2.4m DEPTH BELOW GRADE UNLESS OTHERWISE INDICATED.
- PROVIDE MINIMUM 0.50m CLEARANCE BETWEEN OUTSIDE OF PIPES AT ALL CROSSINGS.
- WATER SERVICE IS TO BE CONSTRUCTED TO PROPERTY LINE AND CAPPED, UNLESS OTHERWISE INDICATED.
- PRESSURE REDUCING VALVES ARE TO BE INSTALLED AT ALL UNITS.

| STM MANHOLE TABLE | | | | |
|-------------------|-----------|--------------|--|------------------------------------|
| MANHOLE ID | SIZE (mm) | T/G ELEV (m) | INVERT (m) | PIPE DIAMETER (mm) |
| 501 | 12000 | 104.30 | SW=101.22 NE=101.15 | SW=300 NE=375 |
| 503 | 12000 | 105.84 | W=102.69 NE=102.64 | W=250 NE=300 |
| 505 | 12000 | 105.78 | NW=103.15 E=102.94 | NW=375 E=250 |
| 507 | 12000 | 105.66 | SW=103.14 NE=102.30 | SW=300 NE=300 |
| 509 | 12000 | 105.67 | W=102.87 SE=102.94 NE=103.02 | W=450 SE=375 NE=300 |
| CBMH15 | 18000 | 105.34 | E=102.78 S=103.43 SW=102.48 NW=102.33 | E=450 S=300 SW=750 NW=900 |

| SAN MANHOLE TABLE | | | | |
|-------------------|-----------|--------------|------------------------|--------------------|
| MANHOLE ID | SIZE (mm) | T/G ELEV (m) | INVERT (m) | PIPE DIAMETER (mm) |
| 778 | 12000 | 105.46 | NW=101.91 SW=101.97 | NW=200 SW=200 |
| 852 | 12000 | 105.90 | NE=102.01 W=102.04 | NE=200 W=200 |
| 954 | 12000 | 105.86 | E=102.30 NW=102.65 | E=200 NW=200 |
| 956 | 12000 | 105.76 | SE=102.07 N=102.04 | SE=200 N=200 |
| 958 | 12000 | 105.64 | S=101.95 NE=101.92 | S=200 NE=200 |

| REAR YARD CATCHBASIN TABLE | | | |
|----------------------------|---------------|------------------------|----------|
| RYCB No. | T/G ELEVATION | INVERT | ICD DIA. |
| LCB30 | 105.55 | NW=104.05 SE=104.05 | |
| LCB31 | 105.73 | NW=104.33 | |
| RYCB10 | 104.29 | NE=102.89 | |
| RYCB11 | 105.17 | N=103.51 SE=103.54 | 108mm |
| RYCB9 | 104.37 | SE=103.42 | 83mm |
| CBMH16 | 104.28 | SE=102.56 NE=102.56 | 83mm |

| CATCHBASIN TABLE | | | |
|------------------|---------------|--------|----------|
| CB No. | T/G ELEVATION | INVERT | ICD DIA. |
| 187 | 104.57 | 103.17 | 83mm |
| 188 | 104.57 | 103.17 | 83mm |
| 189 | 105.54 | 104.14 | 94mm |
| 190 | 105.54 | 104.14 | 94mm |
| 191 | 105.51 | 104.11 | 83mm |
| 192 | 105.51 | 104.11 | 83mm |
| 193 | 104.37 | 102.97 | 102mm |
| 194 | 104.37 | 102.97 | 102mm |
| 195 | 103.82 | 102.42 | 83mm |

| PRESSURE REDUCING VALVE TABLE PHASE 5 | |
|---------------------------------------|-------------------------|
| LOT / BLOCK | PRESSURE REDUCING VALVE |
| T1 - T47 | YES |

NOTE:
THE POSITION OF ALL POLE LINES, CONDUITS, WATERMANS, SEWERS AND OTHER UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED. BEFORE STARTING WORK, DETERMINE THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES AND ASSUME ALL LIABILITY FOR DAMAGE TO THEM.

| SCALE | |
|------------------------|--------------|
| 1:500 | |
| 0 5 10 15 20 | |
| 1. ISSUED FOR APPROVAL | DEC 7/18 MAB |
| No. | REVISION |
| | DATE |
| | BY |


| FOR REVIEW ONLY | |
|-------------------------|--------------------------|
| DESIGN | LRW |
| CHECKED | MAB |
| DRAWN | DTD |
| CHECKED | MAB |
| APPROVED | JGR |
| L.R. WILSON 10016005 | M.A. BISSETT 10016005 |



NOVATECH
Engineers, Planners & Landscape Architects
Suite 200, 240 Michael Cowpland Drive
Ottawa, Ontario, Canada K2M 1P6
Telephone (613) 254-9643
Facsimile (613) 254-5867
Website www.novatech-eng.com

CITY OF OTTAWA
FERNBANK CROSSING - PHASE 5

GENERAL PLAN OF SERVICES

| | |
|-------------|--------------|
| PROJECT No. | 108180-19 |
| REV | REV # 1 |
| DRAWING No. | 108180-19-GP |





LEGEND


- PHASE 5 AREA (hectares)
- PHASE 5 AREA ID
- PHASE 5 RUN-OFF COEFFICIENT
- EXISTING DRAINAGE AREA (hectares)
- EXISTING AREA ID
- EXISTING RUN-OFF COEFFICIENT
- PROPOSED STORM DRAINAGE AREA BOUNDARY
- EXISTING STORM DRAINAGE AREA BOUNDARY
- PROPOSED STORM MANHOLE / SEWER AND FLOW DIRECTION
- PROPOSED ROAD CATCHBASIN
- MAJOR SYSTEM FLOW ROUTE
- 100 YEAR PONDING LIMIT
- 100 YEAR + 20% PONDING LIMIT

| 100 YEAR PONDING | | | |
|------------------|-----------|-----------------------|---------------------------|
| PONDING ID | STRUCTURE | MAX PONDING DEPTH (m) | MAX PONDING ELEVATION (m) |
| P1 | 189-190 | 0.16 | 105.70 |
| P2 | 191-192 | 0.07 | 105.58 |
| P3 | 192-193 | 0.13 | 104.50 |
| P4 | 195 | 0.11 | 103.93 |

| 100 YEAR PONDING + 20% | | | |
|------------------------|-----------|-----------------------|---------------------------|
| PONDING ID | STRUCTURE | MAX PONDING DEPTH (m) | MAX PONDING ELEVATION (m) |
| P1 | 189-190 | 0.17 | 105.71 |
| P2 | 191-192 | 0.17 | 105.68 |
| P3 | 193-194 | 0.19 | 104.56 |
| P4 | 195 | 0.12 | 103.94 |


| REAR YARD PONDING | | | | |
|-------------------|-----------|--------------------------------|------------------------------------|--------------------------------------|
| PONDING ID | STRUCTURE | MAX 100 YEAR PONDING DEPTH (m) | MAX 100 YEAR PONDING ELEVATION (m) | MAX 100 YEAR + 20% PONDING DEPTH (m) |
| P5 | LCB31 | 0.30 | 105.92 | 0.30 |
| P6 | LCB30 | 0.30 | 105.83 | 0.30 |
| P7 | RYCB11 | 0.30 | 105.47 | 0.30 |
| P8 | LCB25 | 0.30 | 105.12 | 0.30 |
| P9 | LCB34 | 0.20 | 104.47 | 0.20 |
| P10 | LCB35 | 0.20 | 104.36 | 0.20 |

PHASE 5
1:750



NOTE:
THE POSITION OF ALL POLE LINES, CONDUITS,
WATERMANS, SEWERS AND OTHER
UNDERGROUND AND OVERGROUND UTILITIES AND
STRUCTURES IS NOT NECESSARILY SHOWN ON
THE CONTRACT DRAWINGS, AND WHERE SHOWN,
THE ACCURACY OF THE POSITION OF SUCH
UTILITIES AND STRUCTURES IS NOT GUARANTEED.
BEFORE STARTING WORK, DETERMINE THE EXACT
LOCATION OF ALL SUCH UTILITIES AND
STRUCTURES AND ASSUME ALL LIABILITY FOR
DAMAGE TO THEM.

| 1. ISSUED FOR APPROVAL | | | |
|------------------------|----------|----------|-----|
| No. | REVISION | DATE | BY |
| | | DEC 7/18 | MAB |



FOR CONSTRUCTION

DESIGN: LRW
CHECKED: MAB
DRAWN: DTD
CHECKED: MAB
APPROVED: JGR

PROFESSIONAL ENGINEER
L.R. WILSON
100160065
PROVINCE OF ONTARIO



PROFESSIONAL ENGINEER
M.A. BISSETT
100160065
PROVINCE OF ONTARIO

CITY OF OTTAWA
FERNBANK CROSSING - PHASE 5

STORM DRAINAGE AREA PLAN

NOVATECH
Engineers, Planners & Landscape Architects
Suite 200, 240 Michael Cowpland Drive
Ottawa, Ontario, Canada K2M 1P6
Telephone: (613) 254-9643
Facsimile: (613) 254-5867
Website: www.novatech-eng.com


PROJECT No.: 108180-19
REV: 1
DRAWING No.: 108180-19-STM



- LEGEND**
- PHASING BOUNDARY
 - SILT FENCE PER OPSD 219.110
 - STRAW BALE FLOW CHECK PER OPSD 219.180
 - CLEARING, GRUBBING AND VEGETATION REMOVAL
 - REMOVE EXISTING ACCESS ROAD
 - REMOVALS
 - TERRAFIX SILT/XXX INSTALLED AT CB

- EROSION AND SEDIMENT CONTROL NOTES :**
1. ALL EROSION AND SEDIMENT CONTROLS ARE TO BE INSTALLED TO THE SATISFACTION OF THE ENGINEER, THE MUNICIPALITY AND THE CONSERVATION AUTHORITY. THEY ARE TO BE APPROPRIATE TO THE SITE CONDITIONS. PRIOR TO UNDERTAKING ANY SITE ALTERATIONS (FILLING, GRADING, REMOVAL OF VEGETATION, ETC.) AND DURING ALL PHASES OF SITE PREPARATION AND CONSTRUCTION, THESE PRACTICES ARE TO BE IMPLEMENTED IN ACCORDANCE WITH THE CURRENT BEST MANAGEMENT PRACTICES FOR EROSION AND SEDIMENT CONTROL AND SHOULD INCLUDE AS A MINIMUM THOSE MEASURES INDICATED ON THE PLAN.
 2. TO PREVENT SURFACE EROSION FROM ENTERING THE DITCH OR STORM SYSTEM DURING CONSTRUCTION, FILTER SOCKS WILL BE PLACED UNDER GRATES OF ALL PROPOSED AND EXISTING CATCHBASINS AND STRUCTURES. A LIGHT DUTY SILT FENCE BARRIER WILL ALSO BE INSTALLED IN SELECTED LOCATIONS SHOWN ON THIS PLAN, AND STRAW BALE BARRIERS WILL BE INSTALLED WITHIN THE OUTLET DITCHES. THESE CONTROL MEASURES WILL REMAIN IN PLACE UNTIL VEGETATION HAS BEEN ESTABLISHED AND CONSTRUCTION COMPLETE.
 3. THE SEDIMENT CONTROL MEASURES SHALL ONLY BE REMOVED WHEN, IN THE OPINION OF THE ENGINEER, THE MEASURES ARE NO LONGER REQUIRED. NO CONTROL MEASURES MAY BE PERMANENTLY REMOVED WITHOUT PRIOR AUTHORIZATION FROM THE ENGINEER.
 4. THE CONTRACTOR SHALL IMMEDIATELY REPORT TO THE ENGINEER ANY ACCIDENTAL DISCHARGES OF SEDIMENT MATERIAL INTO ANY DITCH OR STORM SEWER SYSTEM. APPROPRIATE RESPONSE MEASURES, INCLUDING ANY REPAIRS TO EXISTING CONTROL MEASURES OR THE IMPLEMENTATION OF ADDITIONAL CONTROL MEASURES, SHALL BE CARRIED OUT BY THE CONTRACTOR WITHOUT DELAY.
 5. THE CONTRACTOR ACKNOWLEDGES THAT FAILURE TO IMPLEMENT EROSION AND SEDIMENT CONTROL MEASURES MAY BE SUBJECT TO PENALTIES IMPOSED BY ANY APPLICABLE REGULATORY AGENCY.
 6. THE CONTRACTOR SHALL ENSURE PROPER DUST CONTROL IS PROVIDED WITH THE APPLICATION OF WATER (AND IF REQUIRED, CALCIUM CHLORIDE) DURING DRY PERIODS.

- REMOVALS NOTES :**
1. ALL HYDRANTS, VALVES AND OTHER APPURTENANCES TO BE REMOVED SHALL BE SALVAGED AND DELIVERED TO CITY OF OTTAWA MAINTENANCE YARD AT CLYDE AVENUE.
 2. THE CONTRACTOR SHALL PROTECT ALL SURVEY MONUMENTS.
 3. REMOVAL OF ALL ABOVE GROUND TRAFFIC PLANT AND STREETLIGHTING TO BE DONE BY OTHERS. CONTRACTOR SHALL PROTECT AND MAINTAIN EXISTING STREETLIGHTING, HYDRO POLES AND OVERHEAD LINES DURING CONSTRUCTION.
 4. ALL BELL AND HYDRO OTTAWA MAINTENANCE HOLE ADJUSTMENTS SHALL BE PERFORMED BY AN APPROVED CONTRACTOR ONLY.
 5. ALL TOPSOIL AND ANY SOFT, WET OR DELETERIOUS MATERIAL SHALL BE REMOVED FROM IMPROVED AREAS UNLESS OTHERWISE DIRECTED BY THE ENGINEER.
 6. FORESTRY TO BE CONTACTED PRIOR TO ANY SELECTIVE PRUNING OR REMOVALS WITHIN THE AREAS OF TREES SURROUNDING THE TRANS CANADA TRAIL AND TREES THAT ARE TO REMAIN ARE TO HAVE PROPER TREE PROTECTION FENCING.



NOTE:
THE POSITION OF ALL POLE LINES, CONDUITS, WATERMANS, SEWERS AND OTHER UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED. BEFORE STARTING WORK, DETERMINE THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES AND ASSUME ALL LIABILITY FOR DAMAGE TO THEM.

SCALE
1:500
0 5 10 15 20

FOR REVIEW ONLY
L.R. WILSON
M.A. BISSETT
PROVINCE OF ONTARIO

**CITY OF OTTAWA
FERNBANK CROSSING - PHASE 5**
REMOVALS & EROSION AND SEDIMENT CONTROL PLAN
108180-ESC

NOVATECH
Engineers, Planners & Landscape Architects
Suite 200, 240 Michael Cowpland Drive
Ottawa, Ontario, Canada K2M 1P6
Telephone: (613) 254-9643
Facsimile: (613) 254-5867
Website: www.novatech-eng.com

PROJECT NO: 108180-19
REV # 1
DRAWING NO: 108180-ESC