Appendix A : Hydraulic Analysis Excerpts
February 15, 2019

# APPENDICES

# Appendix A : HYDRAULIC ANALYSIS EXCERPTS

residential units be completed with mitigation measures. The extent of this area should, however, be finalized pending the final grading plan and a more detailed analysis at detailed design. Although the minimum pressure constraint will not be achieved, the recommended measures are appropriate to reduce the inconvenience of low pressures. Hence, it is recommended that this deviation to the Guidelines be accepted.

### 7.4.2 Maximum Day plus Fire Flow Conditions


To ensure adequate fire protection, a maximum day demand was simultaneously simulated with a fire flow along the proposed watermains within the BSUEA. As per Section 7.2.4, a system level fire flow of 13,000 L/min (217 L/s) was used in this analysis with the static elevations reported in Table 7-5 under existing (2016) and build-out conditions (2031).

#### 7.4.2.1 Existing Condition (2016 Scenario)

The watermain layout as depicted on Drawing MWM was found, in general, to be capable of delivering fire flows in excess of 13,000 L/min (217 L/s) within the BSUEA during a maximum day demand as shown on Figure 7-11. However, there are two (2) nodes located within the Mattamy Lands East that do not meet the system level fire flow of 13,000 L/min (217 L/s). Those nodes, located next to New Greenbank Road, have a fire flow availability that exceeds the cap fire flow of 10,000 L/min (167 L/s) as per Technical Bulletin ISDTB-2014-02; the two (2) nodes show fire flows of 190.3 L/s and 199.4 L/s. Given that fire flow at the boundary of the property of the Mattamy Lands East exceed 21,300 L/min (356 L/s), it is recommended that hydrant spacing within the Mattamy Lands East be developed by locating proposed hydrants closest to existing Half Moon Bay rather than New Greenbank Road. This servicing approach would increase fire flow availability within the Mattamy Lands East and potentially meet the system fire flow of 13,000 L/min (217 L/s). It is therefore recommended, that hydrant spacing be reviewed closely at detailed design of the Mattamy Lands East to maximize fire flow availability. It should also be noted that since the previous submission, the City has issued a Technical Bulletin (ISTB-2018-02) on water distribution, particularly in regard to hydrant capacity requirements and required fire flow (RFF). This Bulletin allows that the aggregate fire flow capacity of all contributing fire hydrants within 150 m of a building/structure be used against the RFF. Contributing hydrant flow should reflect those in Table 1 of Appendix I of the Technical Bulletin.

#### 7.4.2.2 Build-out Condition (2031 Scenario)

The watermain layout as depicted on Drawing MWM was found, in general, to be capable of delivering fire flows in excess of 13,000 L/min (217 L/s) within the BSUEA during a maximum day demand as shown on Figure 7-12. However, there are two (2) nodes located within the Mattamy Lands East that do not meet the fire flow of 13,000 L/min (217 L/s). Those nodes, located next to New Greenbank Road, have a fire flow availability that exceeds the cap fire flow of 10,000 L/min (167 L/s) as per Technical Bulletin ISDTB-2014-02. Given that fire flow at the boundary of the property exceed 22,000 L/min (368 L/s), it is recommended that




## Legend

**Water Junction**

**Available fire flow**

- < 217 L/s
- > 217 L/s

**Watermain**

**Study Area**

PROJECT:

# BARRHAVEN SOUTH URBAN EXPANSION AREA

OTTAWA, ONTARIO

DRAWING:

## MAX DAY PLUS FIRE CONDITION (2016)

J.L.Richards
ENGINEERS · ARCHITECTS · PLANNERS
www.jlrichards.ca

This drawing is copyright protected and may not be reproduced or used for purposes other than execution of the described work without the express written consent of J.L. Richards & Associates Limited.


| | |
|---|---|
| DESIGN: | ID |
| DRAWN: | KTK |
| CHECKED: | GF |
| JLR #: | 26610 |

DRAWING #:

FIGURE 7-11

File Location: R:\26000\26610 - Barrhaven Expansion - Minto Brazeau Mattamy\JLR DWG\GIS\26610 C MaxDayFire_2016.mxd

Plot Date: May 2, 2018 10:41:23 AM




## Legend

**Water Junction**

**Available fire flow**

- < 217 L/s
- > 217 L/s

**Watermain**

**Study Area**

PROJECT:

# BARRHAVEN SOUTH URBAN EXPANSION AREA

OTTAWA, ONTARIO

DRAWING:

## MAX DAY PLUS FIRE CONDITION (2031)

J.L.Richards
ENGINEERS · ARCHITECTS · PLANNERS
www.jlrichards.ca

This drawing is copyright protected and may not be reproduced or used for purposes other than execution of the described work without the express written consent of J.L. Richards & Associates Limited.

| | |
|---|---|
| DESIGN: | ID |
| DRAWN: | KTK |
| CHECKED: | GF |
| JLR #: | 26610 |

DRAWING #:

# FIGURE 7-12

File Location: R:\26000\26610 - Barrhaven Expansion - Minto Brazeau Mattamy\JLR DWG\GIS\26610 C MaxDayFire_2031.mxd

Plot Date: May 2, 2018 10:54:12 AM

# Appendix B : SANITARY SEWER CALCULATIONS & REPORT EXCERPTS

SCHOOL
OCSB – Secondary
14.42ac
5.84ha

EXT-1
5.84 INS

COMMUNITY PARK
7.91ac
3.20ha

207
2.66

28
0.23

98
1.34

118
1.37

SCHOOL
OCSB – Elementary
6.85ac
2.77ha

NEIGHBOURHOOD PARK
2.25ac
0.91ha

BLOCK 125
SCHOOL
AREA = 2.07 ha.
RELEASE RATE = 120L/s/ha.

BLOCK 124
PARK
AREA = 0.56 ha.

PARK
AREA = 0.40 GRN

BY OTHERS
INS
2.83

BY OTHERS
1.617
7.88

Widened Area Not Dedicated by BY-Law

MAYFLY CRESCENT
SONG SPARROW STREET
DUTCHMANS WAY
WHITE ARCTIC AVENUE
SNOW GOOSE STREET
BLUEGILL AVENUE
DUNDONALD DRIVE
MEADOWHAWK CRESCENT
SWEET GRASS CIRCLE
SWITCH GRASS CRESCENT
PONCHAIK WAY
DEVARO CRES.
RUE DES SOLDATS RIENDEAU STREET
REMORA WAY
BUFFALOGRASS CRES.
MHIMBEL WAY
DAMSELFLY WAY
KILBIRNIE DRIVE
WALKWAY
MARK AUDET AVENUE
RIVER MIST ROAD
CHILLOW WAY
EGRET WAY
CHAMP CANAL STREET


Stantec

Stantec Consulting Ltd.
400 - 1331 Clyde Avenue
Ottawa ON
Tel. 613.722.4420
www.stantec.com



Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.


Legend

- SA101A / 0.50 / 12 — SANITARY DRAINAGE AREA ID#, POPULATION, SANITARY DRAINAGE AREA ha.
- SANITARY DRAINAGE AREA
- PROPOSED SANITARY SEWER
- EXISTING PHASE
- FUTURE STUB
- EX101A / 0.50 / 12 — FUTURE SANITARY DRAINAGE AREA
- 891 / 12.72 — OFF-SITE OVERALL CONTRIBUTING POPULATION, OFF-SITE OVERALL CONTRIBUTING AREA (ha.)

Notes

| | | | | |
|---|---|---|---|---|
| 5 | ISSUED FOR CONSTRUCTION | DT | DT | 15.10.20 |
| 4 | REVISED INTERIM DRAINAGE | DT | DT | 15.09.02 |
| 3 | REVISED PER CITY COMMENTS | DT | DT | 15.08.26 |
| 2 | REVISED PER CITY COMMENTS | WJ | DT | 15.07.30 |
| 1 | ISSUED FOR REVIEW | MS | DT | 15.05.27 |
| Revision | | By | Appd. | YY.MM.DD |

| | | | | |
|---|---|---|---|---|
| File Name: 160400743-D8 | DT | PM | DT | 15.05.19 |
| | Dwn. | Chkd. | Dsgn. | YY.MM.DD |

Permit-Seal

LICENSED PROFESSIONAL ENGINEER
D. C. THIFFAULT
100186107
20/10/2015
PROVINCE OF ONTARIO

Client/Project
MATTAMY HOMES LTD.

HALF MOON BAY SOUTH
PHASE 4
Ottawa, ON

Title
SANITARY DRAINAGE PLAN

| | | | |
|---|---|---|---|
| Project No. 160400743 | Scale 1:1500 (0, 15, 45, 75m) | | |
| Drawing No. SA-1 | Sheet 28 of 28 | Revision 5 | |


ORIGINAL SHEET - ARCH D

Stantec

SUBDIVISION:

**HALF MOON BAY SOUTH SUBDIVISION - PHASE 4**

DATE: 26/8/2015
REVISION: 2
DESIGNED BY: DT
CHECKED BY:

# SANITARY SEWER DESIGN SHEET
**(City of Ottawa)**

**FILE NUMBER:** 160400743

**DESIGN PARAMETERS**

| | | | | | |
|---|---|---|---|---|---|
| MAX PEAK FACTOR (RES.)= | 4.0 | AVG. DAILY FLOW / PERSON | 350 l/p/day | MINIMUM VELOCITY | 0.60 m/s |
| MIN PEAK FACTOR (RES.)= | 2.0 | COMMERCIAL | 50,000 l/ha/day | MAXIMUM VELOCITY | 3.00 m/s |
| PEAKING FACTOR (INDUSTRIAL): | 2.4 | INDUSTRIAL (HEAVY) | 55,000 l/ha/day | MANNINGS n | 0.013 |
| PEAKING FACTOR (COMM., INST.): | 1.5 | INDUSTRIAL (LIGHT) | 35,000 l/ha/day | BEDDING CLASS | B |
| PERSONS / SINGLE UNIT | 3.4 | INSTITUTIONAL | 50,000 l/ha/day | MINIMUM COVER | 2.50 m |
| PERSONS / TOWNHOME | 2.7 | INFILTRATION | 0.28 l/s/Ha | | |
| PERSONS / APARTMENT | 2.3 | | | | |

| LOCATION | | | RESIDENTIAL AREA AND POPULATION | | | | | | | | | COMMERCIAL | | INDUSTRIAL (L) | | INDUSTRIAL (H) | | INSTITUTIONAL | | GREEN / UNUSED | | C+I+I | INFILTRATION | | | TOTAL | PIPE | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| AREA ID NUMBER | FROM M.H. | TO M.H. | AREA | UNITS SINGLE | UNITS TOWN | UNITS APT. | POP. | CUMULATIVE AREA | CUMULATIVE POP. | PEAK FACT. | PEAK FLOW | AREA | ACCU. AREA | AREA | ACCU. AREA | AREA | ACCU. AREA | AREA | ACCU. AREA | AREA | ACCU. AREA | PEAK FLOW | TOTAL AREA | ACCU. AREA | INFILT. FLOW | FLOW | LENGTH | DIA | MATERIAL | CLASS | SLOPE | CAP. (FULL) | CAP. V PEAK FLOW | VEL. (FULL) | VEL. (ACT.) |
| | | | (ha) | | | | | (ha) | | | (l/s) | (ha) | (ha) | (ha) | (ha) | (ha) | (ha) | (ha) | (ha) | (ha) | (ha) | (l/s) | (ha) | (ha) | (l/s) | (l/s) | (m) | (mm) | | | (%) | (l/s) | (%) | (m/s) | (m/s) |
| EX103A | EX103 | EX102 | 0.80 | 18 | 0 | 0 | 61 | 0.80 | 61 | 4.00 | 1.0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.80 | 0.80 | 0.2 | 1.2 | 120.0 | 200 | PVC | SDR 35 | 2.02 | 47.5 | **2.56%** | 1.49 | 0.54 |
| EX123AA | EX123A | EX123 | 0.00 | 0 | 0 | 0 | 0 | 0.00 | 0 | 4.00 | 0.0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 2.06 | 2.06 | 0.00 | 0.00 | 1.8 | 2.06 | 2.06 | 0.6 | 2.4 | 15.8 | 250 | PVC | SDR 35 | 0.89 | 57.1 | **4.14%** | 1.15 | 0.47 |
| EX23AA | EX23A | EX23 | 0.67 | 15 | 0 | 0 | 51 | 0.67 | 51 | 4.00 | 0.8 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.67 | 0.67 | 0.2 | 1.0 | 105.0 | 200 | PVC | SDR 35 | 0.37 | 20.4 | **4.97%** | 0.64 | 0.28 |
| EX23A | EX23 | EX126 | 0.40 | 6 | 0 | 0 | 20 | 1.06 | 71 | 4.00 | 1.2 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.40 | 1.06 | 0.3 | 1.5 | 89.3 | 200 | PVC | SDR 35 | 1.47 | 40.5 | **3.59%** | 1.27 | 0.50 |
| EX131A | EX131 | EX130 | 0.80 | 19 | 0 | 0 | 65 | 0.80 | 65 | 4.00 | 1.0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.80 | 0.80 | 0.2 | 1.3 | 112.3 | 200 | PVC | SDR 35 | 1.00 | 33.4 | **3.80%** | 1.05 | 0.42 |
| EX130B, EX130A | EX130 | EX128 | 0.36 | 6 | 0 | 0 | 20 | 1.16 | 85 | 4.00 | 1.4 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.40 | 0.40 | 0.0 | 0.76 | 1.56 | 0.4 | 1.8 | 96.5 | 200 | PVC | SDR 35 | 0.50 | 23.6 | **7.68%** | 0.74 | 0.37 |
| SA202A | 202 | 201 | 0.53 | 4 | 0 | 0 | 14 | 0.53 | 14 | 4.00 | 0.2 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.53 | 0.53 | 0.1 | 0.4 | 50.0 | 200 | PVC | SDR 35 | 3.25 | 60.3 | **0.61%** | 1.90 | 0.46 |
| SA213A | 213 | 212 | 0.93 | 21 | 0 | 0 | 71 | 0.93 | 71 | 4.00 | 1.2 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.93 | 0.93 | 0.3 | 1.4 | 120.0 | 200 | PVC | SDR 35 | 0.65 | 27.0 | **5.26%** | 0.85 | 0.37 |
| SA212A | 212 | 211 | 0.20 | 3 | 0 | 0 | 10 | 1.13 | 82 | 4.00 | 1.3 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.20 | 1.13 | 0.3 | 1.6 | 12.8 | 200 | PVC | SDR 35 | 0.40 | 21.1 | **7.75%** | 0.67 | 0.33 |
| SA211A | 211 | 210 | 0.27 | 5 | 0 | 0 | 17 | 1.40 | 99 | 4.00 | 1.6 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.27 | 1.40 | 0.4 | 2.0 | 59.5 | 200 | PVC | SDR 35 | 0.40 | 21.1 | **9.41%** | 0.67 | 0.35 |
| SA210A | 210 | 209 | 0.06 | 1 | 0 | 0 | 3 | 1.46 | 102 | 4.00 | 1.7 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.06 | 1.46 | 0.4 | 2.1 | 11.0 | 200 | PVC | SDR 35 | 0.40 | 21.1 | **9.75%** | 0.67 | 0.35 |
| SA209A | 209 | 208 | 0.29 | 7 | 0 | 0 | 24 | 1.75 | 126 | 4.00 | 2.0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.29 | 1.75 | 0.5 | 2.5 | 40.6 | 200 | PVC | SDR 35 | 0.40 | 21.1 | **11.95%** | 0.67 | 0.37 |
| SA208A | 208 | 203 | 0.75 | 18 | 0 | 0 | 61 | 2.50 | 187 | 4.00 | 3.0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.75 | 2.50 | 0.7 | 3.7 | 120.0 | 200 | PVC | SDR 35 | 0.40 | 21.1 | **17.63%** | 0.67 | 0.42 |
| SA207A | 207 | 206 | 0.18 | 0 | 9 | 0 | 24 | 0.18 | 24 | 4.00 | 0.4 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.18 | 0.18 | 0.0 | 0.4 | 63.7 | 200 | PVC | SDR 35 | 1.75 | 44.2 | **1.00%** | 1.39 | 0.37 |
| SA206A | 206 | 205 | 0.17 | 0 | 9 | 0 | 24 | 0.35 | 49 | 4.00 | 0.8 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.17 | 0.35 | 0.1 | 0.9 | 63.7 | 200 | PVC | SDR 35 | 1.75 | 44.2 | **2.00%** | 1.39 | 0.46 |
| SA205AA | 205A | 205 | 0.00 | 0 | 0 | 0 | 0 | 0.00 | 0 | 4.00 | 0.0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 3.10 | 3.10 | 0.0 | 3.10 | 3.10 | 0.9 | 0.9 | 7.7 | 150 | PVC | DR 28 | 1.00 | 15.3 | **5.66%** | 0.86 | 0.39 |
| SA205A | 205 | 204 | 0.04 | 0 | 1 | 0 | 3 | 0.40 | 51 | 4.00 | 0.8 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 3.10 | 0.0 | 0.04 | 3.50 | 1.0 | 1.8 | 11.0 | 200 | PVC | SDR 35 | 1.50 | 41.0 | **4.42%** | 1.29 | 0.55 |
| SA204A | 204 | 203 | 0.14 | 0 | 4 | 0 | 11 | 0.54 | 62 | 4.00 | 1.0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 3.10 | 0.0 | 0.14 | 3.64 | 1.0 | 2.0 | 36.5 | 200 | PVC | SDR 35 | 1.50 | 41.0 | **4.94%** | 1.29 | 0.55 |
| SA216A | 216 | 215 | 0.19 | 0 | 5 | 0 | 14 | 0.19 | 14 | 4.00 | 0.2 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.19 | 0.19 | 0.1 | 0.3 | 45.2 | 200 | PVC | SDR 35 | 0.65 | 27.0 | **1.01%** | 0.85 | 0.23 |
| SA217A, External | 217 | 215 | 2.72 | 61 | 0 | 0 | 207 | 2.72 | 207 | 4.00 | 3.4 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 2.72 | 2.72 | 0.8 | 4.1 | 34.5 | 200 | PVC | SDR 35 | 2.00 | 47.3 | **8.72%** | 1.49 | 0.76 |
| SA215A | 215 | 214 | 0.34 | 0 | 15 | 0 | 41 | 3.25 | 261 | 4.00 | 4.2 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.34 | 3.25 | 0.9 | 5.1 | 72.0 | 200 | PVC | SDR 35 | 2.00 | 47.3 | **10.88%** | 1.49 | 0.81 |
| SA214A | 214 | 203 | 0.35 | 0 | 15 | 0 | 41 | 3.60 | 302 | 4.00 | 4.9 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.35 | 3.60 | 1.0 | 5.9 | 73.5 | 200 | PVC | SDR 35 | 2.00 | 47.3 | **12.48%** | 1.49 | 0.85 |
| SA203A | 203 | 201 | 0.12 | 0 | 0 | 0 | 0 | 6.75 | 551 | 3.95 | 8.8 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 3.10 | 0.0 | 0.12 | 9.85 | 2.8 | 11.6 | 73.7 | 200 | PVC | SDR 35 | 0.40 | 21.1 | **54.76%** | 0.67 | 0.58 |
| SA201A | 201 | EX129A | 0.21 | 3 | 0 | 0 | 10 | 7.49 | 575 | 3.94 | 9.2 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 3.10 | 0.0 | 0.21 | 10.59 | 3.0 | 12.1 | 47.8 | 200 | PVC | SDR 35 | 0.40 | 21.1 | **57.43%** | 0.67 | 0.59 |
| EX129AA | EX129A | EX129 | 0.75 | 18 | 0 | 0 | 61 | 8.24 | 636 | 3.92 | 10.1 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 3.10 | 0.0 | 0.75 | 11.34 | 3.2 | 13.3 | 100.9 | 200 | PVC | SDR 35 | 0.40 | 21.1 | **62.76%** | 0.67 | 0.61 |
| EX129A | EX129 | EX128 | 0.58 | 11 | 0 | 0 | 37 | 8.82 | 673 | 3.90 | 10.7 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 3.10 | 0.0 | 0.58 | 11.92 | 3.3 | 14.0 | 91.7 | 200 | PVC | SDR 35 | 0.40 | 21.1 | **66.15%** | 0.67 | 0.62 |
| EX128A | EX128 | EX127 | 0.37 | 9 | 0 | 0 | 31 | 10.35 | 789 | 3.86 | 12.4 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 3.50 | 0.0 | 0.37 | 13.85 | 3.9 | 16.2 | 49.8 | 200 | PVC | SDR 35 | 0.50 | 23.6 | **68.64%** | 0.74 | 0.70 |
| EX127A | EX127 | EX126 | 0.66 | 13 | 0 | 0 | 44 | 11.01 | 833 | 3.85 | 13.0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 3.50 | 0.0 | 0.66 | 14.51 | 4.1 | 17.1 | 97.8 | 200 | PVC | SDR 35 | 0.32 | 19.0 | **89.70%** | 0.60 | 0.61 |
| SA163A | 163 | 162 | 7.96 | 118 | 43 | 0 | 517 | 7.96 | 517 | 3.97 | 8.3 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 2.83 | 2.83 | 0.00 | 0.00 | 2.5 | 10.79 | 10.79 | 3.0 | 13.8 | 36.3 | 250 | PVC | SDR 35 | 0.85 | 55.9 | **24.67%** | 1.13 | 0.78 |
| SA162A | 162 | 161 | 0.20 | 0 | 0 | 0 | 0 | 8.16 | 517 | 3.97 | 8.3 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 2.83 | 0.00 | 0.00 | 2.5 | 0.20 | 10.99 | 3.1 | 13.8 | 87.2 | 250 | PVC | SDR 35 | 1.15 | 65.0 | **21.29%** | 1.31 | 0.86 |
| SA161AA | 161A | 161 | 0.00 | 0 | 0 | 0 | 0 | 0.00 | 0 | 4.00 | 0.0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.91 | 0.91 | 0.0 | 0.91 | 0.91 | 0.3 | 0.3 | 14.0 | 150 | PVC | DR 28 | 1.00 | 15.3 | **1.66%** | 0.86 | 0.27 |
| SA161A | 161 | 151 | 0.19 | 0 | 0 | 0 | 0 | 8.35 | 517 | 3.97 | 8.3 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 2.83 | 0.00 | 0.91 | 2.5 | 0.19 | 12.09 | 3.4 | 14.2 | 57.7 | 250 | PVC | SDR 35 | 1.15 | 65.0 | **21.77%** | 1.31 | 0.88 |
| SA151AA | 151A | 151 | 0.00 | 0 | 0 | 0 | 0 | 0.00 | 0 | 4.00 | 0.0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 2.77 | 2.77 | 0.00 | 0.00 | 2.4 | 2.77 | 2.77 | 0.8 | 3.2 | 12.7 | 150 | PVC | DR 28 | 1.00 | 15.3 | **20.77%** | 0.86 | 0.57 |
| EX151A | 151 | EX151 | 0.09 | 0 | 0 | 0 | 0 | 8.44 | 517 | 3.97 | 8.3 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 5.60 | 0.00 | 0.91 | 4.9 | 0.09 | 14.95 | 4.2 | 17.4 | 17.9 | 300 | PVC | SDR 35 | 1.40 | 113.6 | **15.28%** | 1.61 | 0.98 |
| | EX151 | EX142 | 0.00 | 0 | 0 | 0 | 0 | 8.44 | 517 | 3.97 | 8.3 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 5.60 | 0.00 | 0.91 | 4.9 | 0.00 | 14.95 | 4.2 | 17.4 | 44.4 | 300 | PVC | SDR 35 | 1.40 | 113.6 | **15.28%** | 1.61 | 0.98 |
| SA165A | 165 | 150 | 0.67 | 17 | 0 | 0 | 58 | 0.67 | 58 | 4.00 | 0.9 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.67 | 0.67 | 0.2 | 1.1 | 101.2 | 200 | PVC | SDR 35 | 1.50 | 41.0 | **2.75%** | 1.29 | 0.47 |
| SA155A | 155 | 154 | 0.10 | 0 | 2 | 0 | 5 | 0.10 | 5 | 4.00 | 0.1 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.10 | 0.10 | 0.0 | 0.1 | 10.6 | 200 | PVC | SDR 35 | 0.65 | 27.0 | **0.43%** | 0.85 | 0.18 |
| SA154A | 154 | 153 | 0.48 | 0 | 22 | 0 | 59 | 0.59 | 65 | 4.00 | 1.1 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.48 | 0.59 | 0.2 | 1.2 | 95.5 | 200 | PVC | SDR 35 | 0.40 | 21.1 | **5.74%** | 0.67 | 0.30 |
| SA160A | 160 | 159 | 0.04 | 0 | 1 | 0 | 3 | 0.04 | 3 | 4.00 | 0.0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.04 | 0.04 | 0.0 | 0.1 | 10.6 | 200 | PVC | SDR 35 | 0.65 | 27.0 | **0.21%** | 0.85 | 0.13 |
| SA159A | 159 | 158 | 0.51 | 0 | 23 | 0 | 62 | 0.56 | 65 | 4.00 | 1.1 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.51 | 0.56 | 0.2 | 1.2 | 95.5 | 200 | PVC | SDR 35 | 0.40 | 21.1 | **5.70%** | 0.67 | 0.30 |
| SA158A, External | 158 | 153 | 1.50 | 14 | 50 | 0 | 118 | 2.06 | 183 | 4.00 | 3.0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 1.50 | 2.06 | 0.6 | 3.5 | 45.0 | 200 | PVC | SDR 35 | 0.40 | 21.1 | **16.73%** | 0.67 | 0.41 |
| SA153A, External | 153 | 152 | 1.46 | 12 | 21 | 0 | 98 | 4.10 | 345 | 4.00 | 5.6 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 1.46 | 4.10 | 1.1 | 6.7 | 70.0 | 200 | PVC | SDR 35 | 0.80 | 29.9 | **22.53%** | 0.94 | 0.63 |
| SA152A, External | 152 | 150 | 0.56 | 14 | 0 | 0 | 48 | 4.66 | 393 | 4.00 | 6.4 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.56 | 4.66 | 1.3 | 7.7 | 85.7 | 200 | PVC | SDR 35 | 0.80 | 29.9 | **25.64%** | 0.94 | 0.66 |
| SA150A | 150 | 146 | 0.30 | 6 | 0 | 0 | 20 | 5.63 | 471 | 3.99 | 7.6 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.30 | 5.63 | 1.6 | 9.2 | 72.0 | 200 | PVC | SDR 35 | 0.80 | 29.9 | **30.71%** | 0.94 | 0.70 |
| SA149A | 149 | 148 | 0.27 | 5 | 0 | 0 | 17 | 0.27 | 17 | 4.00 | 0.3 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.27 | 0.27 | 0.1 | 0.4 | 51.2 | 200 | PVC | SDR 35 | 1.00 | 33.4 | **1.05%** | 1.05 | 0.28 |
| SA148A | 148 | 147 | 0.15 | 2 | 0 | 0 | 7 | 0.42 | 24 | 4.00 | 0.4 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.15 | 0.42 | 0.1 | 0.5 | 10.5 | 200 | PVC | SDR 35 | 1.00 | 33.4 | **1.51%** | 1.05 | 0.32 |
| SA147A | 147 | 146 | 0.52 | 13 | 0 | 0 | 44 | 0.95 | 68 | 4.00 | 1.1 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.52 | 0.95 | 0.3 | 1.4 | 78.2 | 200 | PVC | SDR 35 | 1.00 | 33.4 | **4.09%** | 1.05 | 0.43 |
| SA146A | 146 | EX145 | 0.08 | 2 | 0 | 0 | 7 | 6.66 | 546 | 3.95 | 8.7 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.08 | 6.66 | 1.9 | 10.6 | 19.3 | 200 | PVC | SDR 35 | 0.50 | 23.6 | **44.87%** | 0.74 | 0.62 |

Stantec

SUBDIVISION:

**HALF MOON BAY SOUTH SUBDIVISION - PHASE 4**

DATE: 26/8/2015
REVISION: 2
DESIGNED BY: DT
CHECKED BY:

# SANITARY SEWER DESIGN SHEET
**(City of Ottawa)**

**FILE NUMBER:** 160400743

**DESIGN PARAMETERS**

| | | | | | |
|---|---|---|---|---|---|
| MAX PEAK FACTOR (RES.)= | 4.0 | AVG. DAILY FLOW / PERSON | 350 l/p/day | MINIMUM VELOCITY | 0.60 m/s |
| MIN PEAK FACTOR (RES.)= | 2.0 | COMMERCIAL | 50,000 l/ha/day | MAXIMUM VELOCITY | 3.00 m/s |
| PEAKING FACTOR (INDUSTRIAL): | 2.4 | INDUSTRIAL (HEAVY) | 55,000 l/ha/day | MANNINGS n | 0.013 |
| PEAKING FACTOR (COMM., INST.): | 1.5 | INDUSTRIAL (LIGHT) | 35,000 l/ha/day | BEDDING CLASS | B |
| PERSONS / SINGLE UNIT | 3.4 | INSTITUTIONAL | 50,000 l/ha/day | MINIMUM COVER | 2.50 m |
| PERSONS / TOWNHOME | 2.7 | INFILTRATION | 0.28 l/s/Ha | | |
| PERSONS / APARTMENT | 2.3 | | | | |

| LOCATION | | | RESIDENTIAL AREA AND POPULATION | | | | | | | | | COMMERCIAL | | INDUSTRIAL (L) | | INDUSTRIAL (H) | | INSTITUTIONAL | | GREEN / UNUSED | | C+I+I | INFILTRATION | | | TOTAL | PIPE | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| AREA ID NUMBER | FROM M.H. | TO M.H. | AREA | SINGLE | UNITS TOWN | APT. | POP. | CUMULATIVE AREA | CUMULATIVE POP. | PEAK FACT. | PEAK FLOW | AREA | ACCU. AREA | AREA | ACCU. AREA | AREA | ACCU. AREA | AREA | ACCU. AREA | AREA | ACCU. AREA | PEAK FLOW | TOTAL AREA | ACCU. AREA | INFILT. FLOW | FLOW | LENGTH | DIA | MATERIAL | CLASS | SLOPE | CAP. (FULL) | CAP. V PEAK FLOW | VEL. (FULL) | VEL. (ACT.) |
| | | | (ha) | | | | | (ha) | | | (l/s) | (ha) | (ha) | (ha) | (ha) | (ha) | (ha) | (ha) | (ha) | (ha) | (ha) | (l/s) | (ha) | (ha) | (l/s) | (l/s) | (m) | (mm) | | | (%) | (l/s) | (%) | (m/s) | (m/s) |
| EX145A | EX145 | EX144 | 0.07 | 0 | 0 | 0 | 0 | 6.73 | 546 | 3.95 | 8.7 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.07 | 6.73 | 1.9 | 10.6 | 35.9 | 200 | PVC | SDR 35 | 0.50 | 23.6 | **44.94%** | 0.74 | 0.62 |
| EX144A | EX144 | EX143 | 0.54 | 9 | 0 | 0 | 31 | 7.27 | 576 | 3.94 | 9.2 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.54 | 7.27 | 2.0 | 11.2 | 114.9 | 200 | PVC | SDR 35 | 0.50 | 23.6 | **47.53%** | 0.74 | 0.62 |
| | EX143 | EX142 | 0.00 | 0 | 0 | 0 | 0 | 7.27 | 576 | 3.94 | 9.2 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.00 | 7.27 | 2.0 | 11.2 | 21.5 | 200 | PVC | SDR 35 | 0.40 | 21.1 | **53.14%** | 0.67 | 0.58 |
| EX142A | EX142 | EX139 | 0.26 | 3 | 0 | 0 | 10 | 15.97 | 1104 | 3.77 | 16.9 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 5.60 | 0.00 | 0.91 | 4.9 | 0.26 | 22.48 | 6.3 | 28.0 | 74.8 | 300 | PVC | SDR 35 | 0.40 | 60.7 | **46.15%** | 0.86 | 0.72 |
| EX141B | EX141 | EX140 | 0.16 | 2 | 0 | 0 | 7 | 0.16 | 7 | 4.00 | 0.1 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.16 | 0.16 | 0.0 | 0.2 | 10.6 | 200 | PVC | SDR 35 | 0.65 | 27.0 | **0.58%** | 0.85 | 0.18 |
| EX140A | EX140 | EX139 | 0.24 | 5 | 0 | 0 | 17 | 0.40 | 24 | 4.00 | 0.4 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.24 | 0.40 | 0.1 | 0.5 | 67.7 | 200 | PVC | SDR 35 | 0.65 | 27.0 | **1.85%** | 0.85 | 0.28 |
| EX139A | EX139 | EX136 | 0.47 | 10 | 0 | 0 | 34 | 16.84 | 1162 | 3.76 | 17.7 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 5.60 | 0.00 | 0.91 | 4.9 | 0.47 | 23.35 | 6.5 | 29.1 | 64.7 | 300 | PVC | SDR 35 | 0.40 | 60.7 | **47.89%** | 0.86 | 0.73 |
| EX141A | EX141 | EX138 | 0.38 | 8 | 0 | 0 | 27 | 0.38 | 27 | 4.00 | 0.4 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.38 | 0.38 | 0.1 | 0.5 | 49.7 | 200 | PVC | SDR 35 | 0.65 | 27.0 | **2.03%** | 0.85 | 0.28 |
| EX138A | EX138 | EX137 | 0.18 | 2 | 0 | 0 | 7 | 0.56 | 34 | 4.00 | 0.6 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.18 | 0.56 | 0.2 | 0.7 | 10.6 | 200 | PVC | SDR 35 | 0.65 | 27.0 | **2.62%** | 0.85 | 0.31 |
| EX137A | EX137 | EX136 | 0.28 | 5 | 0 | 0 | 17 | 0.84 | 51 | 4.00 | 0.8 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.28 | 0.84 | 0.2 | 1.1 | 67.8 | 200 | PVC | SDR 35 | 0.65 | 27.0 | **3.94%** | 0.85 | 0.35 |
| EX136A | EX136 | EX126 | 0.29 | 4 | 0 | 0 | 14 | 17.96 | 1226 | 3.74 | 18.6 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 5.60 | 0.00 | 0.91 | 4.9 | 0.29 | 24.48 | 6.9 | 30.3 | 78.9 | 300 | PVC | SDR 35 | 0.41 | 61.7 | **49.10%** | 0.88 | 0.74 |
| EX126A | EX126 | EX123 | 0.29 | 0 | 5 | 0 | 14 | 30.32 | 2144 | 3.56 | 30.9 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 5.60 | 0.00 | 4.41 | 4.9 | 0.29 | 40.34 | 11.3 | 47.1 | 71.3 | 375 | PVC | SDR 35 | 0.45 | 117.4 | **40.10%** | 1.06 | 0.85 |
| EX123A | EX123 | EX112 | 0.34 | 0 | 7 | 0 | 19 | 30.66 | 2163 | 3.56 | 31.2 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 7.66 | 0.00 | 4.41 | 6.7 | 0.34 | 42.73 | 12.0 | 49.8 | 90.3 | 375 | PVC | SDR 35 | 0.42 | 113.8 | **43.78%** | 1.03 | 0.85 |
| EX117A | EX117 | EX113 | 0.15 | 0 | 0 | 0 | 0 | 0.15 | 0 | 4.00 | 0.0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.15 | 0.15 | 0.0 | 0.0 | 90.0 | 200 | PVC | SDR 35 | 0.65 | 27.0 | **0.15%** | 0.85 | 0.13 |
| EX116A | EX116 | EX113 | 0.50 | 0 | 21 | 0 | 57 | 0.50 | 57 | 4.00 | 0.9 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.50 | 0.50 | 0.1 | 1.1 | 90.6 | 200 | PVC | SDR 35 | 0.50 | 23.6 | **4.48%** | 0.74 | 0.32 |
| EX113A | EX113 | EX112B | 0.25 | 0 | 10 | 0 | 27 | 0.90 | 84 | 4.00 | 1.4 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.25 | 0.90 | 0.3 | 1.6 | 47.0 | 200 | PVC | SDR 35 | 0.65 | 27.0 | **5.96%** | 0.85 | 0.39 |
| EX112BA | EX112B | EX111 | 0.46 | 0 | 22 | 0 | 59 | 1.36 | 143 | 4.00 | 2.3 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.46 | 1.36 | 0.4 | 2.7 | 81.5 | 200 | PVC | SDR 35 | 0.65 | 27.0 | **10.01%** | 0.85 | 0.45 |
| EX119A | EX119 | EX118 | 0.51 | 0 | 30 | 0 | 81 | 0.51 | 81 | 4.00 | 1.3 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.51 | 0.51 | 0.1 | 1.5 | 116.9 | 200 | PVC | SDR 35 | 0.50 | 23.6 | **6.15%** | 0.74 | 0.34 |
| EX122A | EX122 | EX121 | 0.69 | 0 | 31 | 0 | 84 | 0.69 | 84 | 4.00 | 1.4 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.69 | 0.69 | 0.2 | 1.5 | 112.0 | 200 | PVC | SDR 35 | 0.40 | 21.1 | **7.33%** | 0.67 | 0.32 |
| EX121A | EX121 | EX120 | 0.16 | 0 | 4 | 0 | 11 | 0.85 | 95 | 4.00 | 1.5 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.16 | 0.85 | 0.2 | 1.8 | 8.5 | 200 | PVC | SDR 35 | 0.40 | 21.1 | **8.37%** | 0.67 | 0.34 |
| EX120A | EX120 | EX118 | 0.17 | 0 | 6 | 0 | 16 | 1.02 | 111 | 4.00 | 1.8 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.17 | 1.02 | 0.3 | 2.1 | 39.0 | 200 | PVC | SDR 35 | 0.40 | 21.1 | **9.84%** | 0.67 | 0.35 |
| EX118A | EX118 | EX111 | 0.09 | 0 | 1 | 0 | 3 | 1.62 | 194 | 4.00 | 3.2 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.09 | 1.62 | 0.5 | 3.6 | 46.5 | 200 | PVC | SDR 35 | 0.40 | 21.1 | **17.04%** | 0.67 | 0.41 |
| EX111A | EX111 | EX112 | 0.42 | 0 | 15 | 0 | 41 | 3.39 | 378 | 4.00 | 6.1 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.42 | 3.39 | 0.9 | 7.1 | 74.8 | 200 | PVC | SDR 35 | 0.32 | 18.9 | **37.43%** | 0.59 | 0.47 |
| EX112A | EX112 | EX102 | 0.14 | 0 | 0 | 0 | 0 | 34.19 | 2541 | 3.50 | 36.1 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 7.66 | 0.00 | 4.41 | 6.7 | 0.14 | 46.26 | 13.0 | 55.7 | 68.0 | 375 | PVC | SDR 35 | 0.31 | 97.4 | **57.13%** | 0.88 | 0.79 |
| EX115A | EX115 | EX114 | 0.51 | 0 | 22 | 0 | 59 | 0.51 | 59 | 4.00 | 1.0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.51 | 0.51 | 0.1 | 1.1 | 81.6 | 200 | PVC | SDR 35 | 0.40 | 21.1 | **5.22%** | 0.67 | 0.29 |
| EX114A | EX114 | EX110 | 0.16 | 0 | 3 | 0 | 8 | 0.67 | 68 | 4.00 | 1.1 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.16 | 0.67 | 0.2 | 1.3 | 10.6 | 200 | PVC | SDR 35 | 0.40 | 21.1 | **6.05%** | 0.67 | 0.30 |
| EX110A | EX110 | EX108 | 0.17 | 0 | 6 | 0 | 16 | 0.83 | 84 | 4.00 | 1.4 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.17 | 0.83 | 0.2 | 1.6 | 37.5 | 200 | PVC | SDR 35 | 0.40 | 21.1 | **7.51%** | 0.67 | 0.32 |
| EX109A | EX109 | EX108 | 0.38 | 0 | 22 | 0 | 59 | 0.38 | 59 | 4.00 | 1.0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.38 | 0.38 | 0.1 | 1.1 | 85.6 | 200 | PVC | SDR 35 | 0.65 | 27.0 | **3.96%** | 0.85 | 0.35 |
| EX108A | EX108 | EX107 | 0.48 | 0 | 15 | 0 | 41 | 1.69 | 184 | 4.00 | 3.0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.48 | 1.69 | 0.5 | 3.4 | 106.8 | 200 | PVC | SDR 35 | 0.40 | 21.1 | **16.30%** | 0.67 | 0.41 |
| EX107A | EX107 | EX106 | 0.15 | 0 | 3 | 0 | 8 | 1.84 | 192 | 4.00 | 3.1 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.15 | 1.84 | 0.5 | 3.6 | 10.4 | 200 | PVC | SDR 35 | 0.40 | 21.1 | **17.13%** | 0.67 | 0.41 |
| EX106A | EX106 | EX105 | 0.65 | 0 | 22 | 0 | 59 | 2.49 | 251 | 4.00 | 4.1 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.65 | 2.49 | 0.7 | 4.8 | 92.1 | 200 | PVC | SDR 35 | 0.40 | 21.1 | **22.54%** | 0.67 | 0.45 |
| EX105A | EX105 | EX104 | 0.61 | 0 | 22 | 0 | 59 | 3.11 | 311 | 4.00 | 5.0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.61 | 3.11 | 0.9 | 5.9 | 88.7 | 200 | PVC | SDR 35 | 0.40 | 21.1 | **27.90%** | 0.67 | 0.48 |
| EX104A | EX104 | EX102 | 0.73 | 0 | 28 | 0 | 76 | 3.83 | 386 | 4.00 | 6.3 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.73 | 3.83 | 1.1 | 7.3 | 114.6 | 200 | PVC | SDR 35 | 0.44 | 22.2 | **33.05%** | 0.70 | 0.52 |
| EX102A | EX102 | EX101 | 0.07 | 0 | 0 | 0 | 0 | 38.89 | 2989 | 3.44 | 41.7 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 7.66 | 0.00 | 4.41 | 6.7 | 0.07 | 50.96 | 14.3 | 62.6 | 34.0 | 375<br>375 | PVC | SDR 35 | 0.29 | 95.1 | **65.84%** | 0.86 | 0.80 |
| EX7A | EX7 | EX6 | 0.10 | 0 | 2 | 0 | 5 | 0.10 | 5 | 4.00 | 0.1 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.10 | 0.10 | 0.0 | 0.1 | 11.1 | 200 | PVC | SDR 35 | 0.63 | 26.5 | **0.44%** | 0.83 | 0.18 |
| EX6A | EX6 | EX5 | 0.66 | 0 | 31 | 0 | 84 | 0.76 | 89 | 4.00 | 1.4 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.66 | 0.76 | 0.2 | 1.7 | 117.0 | 200 | PVC | SDR 35 | 0.65 | 26.9 | **6.15%** | 0.85 | 0.39 |
| EX5A | EX5 | EX4 | 0.07 | 0 | 2 | 0 | 5 | 0.83 | 95 | 4.00 | 1.5 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.07 | 0.83 | 0.2 | 1.8 | 8.5 | 200 | PVC | SDR 35 | 1.18 | 36.3 | **4.86%** | 1.14 | 0.49 |
| EX4A | EX4 | EX3 | 0.05 | 0 | 0 | 0 | 0 | 0.88 | 95 | 4.00 | 1.5 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.05 | 0.88 | 0.2 | 1.8 | 39.0 | 200 | PVC | SDR 35 | 1.08 | 34.7 | **5.12%** | 1.09 | 0.48 |
| EX10A, EX10B | EX10 | EX9 | 0.33 | 5 | 0 | 0 | 17 | 0.33 | 17 | 4.00 | 0.3 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.56 | 0.56 | 0.0 | 0.89 | 0.89 | 0.2 | 0.5 | 75.3 | 200 | PVC | SDR 35 | 0.92 | 32.0 | **1.64%** | 1.01 | 0.31 |
| EX18A | EX18 | EX19 | 0.14 | 2 | 0 | 0 | 7 | 0.14 | 7 | 4.00 | 0.1 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.14 | 0.14 | 0.0 | 0.1 | 8.5 | 200 | PVC | SDR 35 | 0.83 | 30.4 | **0.49%** | 0.96 | 0.21 |
| EX19A | EX19 | EX9 | 0.62 | 11 | 12 | 0 | 70 | 0.76 | 77 | 4.00 | 1.2 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.62 | 0.76 | 0.2 | 1.5 | 107.0 | 200 | PVC | SDR 35 | 0.63 | 26.5 | **5.50%** | 0.83 | 0.37 |
| EX9A | EX9 | EX8 | 0.07 | 0 | 0 | 0 | 0 | 1.16 | 94 | 4.00 | 1.5 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.56 | 0.0 | 0.07 | 1.72 | 0.5 | 2.0 | 48.0 | 200 | PVC | SDR 35 | 0.96 | 32.7 | **6.11%** | 1.03 | 0.47 |
| EX14A | EX14 | EX13 | 0.13 | 0 | 2 | 0 | 5 | 0.13 | 5 | 4.00 | 0.1 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.13 | 0.13 | 0.0 | 0.1 | 9.5 | 200 | PVC | SDR 35 | 0.74 | 28.7 | **0.43%** | 0.90 | 0.20 |
| EX13A | EX13 | EX12 | 0.43 | 0 | 20 | 0 | 54 | 0.57 | 59 | 4.00 | 1.0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.43 | 0.57 | 0.2 | 1.1 | 82.1 | 200 | PVC | SDR 35 | 0.65 | 26.9 | **4.17%** | 0.85 | 0.35 |
| EX12A | EX12 | EX11 | 0.44 | 0 | 21 | 0 | 57 | 1.01 | 116 | 4.00 | 1.9 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.44 | 1.01 | 0.3 | 2.2 | 82.1 | 200 | PVC | SDR 35 | 0.41 | 21.5 | **10.06%** | 0.68 | 0.36 |
| EX18B | EX18 | EX15 | 0.15 | 3 | 0 | 0 | 10 | 0.15 | 10 | 4.00 | 0.2 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.15 | 0.15 | 0.0 | 0.2 | 42.0 | 200 | PVC | SDR 35 | 2.38 | 51.6 | **0.40%** | 1.62 | 0.31 |
| EX17A | EX17 | EX16 | 0.67 | 9 | 10 | 0 | 58 | 0.67 | 58 | 4.00 | 0.9 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.67 | 0.67 | 0.2 | 1.1 | 84.1 | 200 | PVC | SDR 35 | 0.44 | 22.2 | **5.05%** | 0.70 | 0.31 |
| EX16A | EX16 | EX15 | 0.49 | 7 | 9 | 0 | 48 | 1.16 | 106 | 4.00 | 1.7 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.49 | 1.16 | 0.3 | 2.0 | 79.0 | 200 | PVC | SDR 35 | 0.34 | 19.5 | **10.42%** | 0.62 | 0.33 |

Stantec

SUBDIVISION:
**HALF MOON BAY SOUTH SUBDIVISION - PHASE 4**

DATE: 26/8/2015
REVISION: 2
DESIGNED BY: DT
CHECKED BY:

# SANITARY SEWER DESIGN SHEET
**(City of Ottawa)**

**FILE NUMBER:** 160400743

**DESIGN PARAMETERS**

| | | | | | |
|---|---|---|---|---|---|
| MAX PEAK FACTOR (RES.)= | 4.0 | AVG. DAILY FLOW / PERSON | 350 l/p/day | MINIMUM VELOCITY | 0.60 m/s |
| MIN PEAK FACTOR (RES.)= | 2.0 | COMMERCIAL | 50,000 l/ha/day | MAXIMUM VELOCITY | 3.00 m/s |
| PEAKING FACTOR (INDUSTRIAL): | 2.4 | INDUSTRIAL (HEAVY) | 55,000 l/ha/day | MANNINGS n | 0.013 |
| PEAKING FACTOR (COMM., INST.): | 1.5 | INDUSTRIAL (LIGHT) | 35,000 l/ha/day | BEDDING CLASS | B |
| PERSONS / SINGLE UNIT | 3.4 | INSTITUTIONAL | 50,000 l/ha/day | MINIMUM COVER | 2.50 m |
| PERSONS / TOWNHOME | 2.7 | INFILTRATION | 0.28 l/s/Ha | | |
| PERSONS / APARTMENT | 2.3 | | | | |

| LOCATION | | | RESIDENTIAL AREA AND POPULATION | | | | | | | | | COMMERCIAL | | INDUSTRIAL (L) | | INDUSTRIAL (H) | | INSTITUTIONAL | | GREEN / UNUSED | | C+I+I | INFILTRATION | | | TOTAL | PIPE | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| AREA ID NUMBER | FROM M.H. | TO M.H. | AREA (ha) | SINGLE | UNITS TOWN | APT. | POP. | CUMULATIVE AREA (ha) | CUMULATIVE POP. | PEAK FACT. | PEAK FLOW (l/s) | AREA (ha) | ACCU. AREA (ha) | AREA (ha) | ACCU. AREA (ha) | AREA (ha) | ACCU. AREA (ha) | AREA (ha) | ACCU. AREA (ha) | AREA (ha) | ACCU. AREA (ha) | PEAK FLOW (l/s) | TOTAL AREA (ha) | ACCU. AREA (ha) | INFILT. FLOW (l/s) | FLOW (l/s) | LENGTH (m) | DIA (mm) | MATERIAL | CLASS | SLOPE (%) | CAP. (FULL) (l/s) | CAP. V PEAK FLOW (%) | VEL. (FULL) (m/s) | VEL. (ACT.) (m/s) |
| EX22A | EX22 | EX21 | 0.51 | 11 | 0 | 0 | 37 | 0.51 | 37 | 4.00 | 0.6 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.51 | 0.51 | 0.1 | 0.8 | 55.9 | 200 | PVC | SDR 35 | 0.72 | 28.3 | 2.65% | 0.89 | 0.32 |
| EX21A | EX21 | EX20 | 0.63 | 16 | 0 | 0 | 54 | 1.14 | 92 | 4.00 | 1.5 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.63 | 1.14 | 0.3 | 1.8 | 97.5 | 200 | PVC | SDR 35 | 0.60 | 26.0 | 6.95% | 0.82 | 0.39 |
| EX33A | EX33 | EX32 | 0.68 | 14 | 0 | 0 | 48 | 0.68 | 48 | 4.00 | 0.8 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.68 | 0.68 | 0.2 | 1.0 | 90.6 | 200 | PVC | SDR 35 | 0.40 | 21.1 | 4.54% | 0.67 | 0.28 |
| EX32A | EX32 | EX31 | 0.11 | 1 | 0 | 0 | 3 | 0.78 | 51 | 4.00 | 0.8 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.11 | 0.78 | 0.2 | 1.0 | 10.6 | 200 | PVC | SDR 35 | 0.40 | 21.1 | 4.94% | 0.67 | 0.28 |
| EX31A | EX31 | EX30 | 0.46 | 10 | 0 | 0 | 34 | 1.25 | 85 | 4.00 | 1.4 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.46 | 1.25 | 0.3 | 1.7 | 57.5 | 200 | PVC | SDR 35 | 0.40 | 21.1 | 8.16% | 0.67 | 0.33 |
| EX30A | EX30 | EX29 | 0.15 | 2 | 0 | 0 | 7 | 1.40 | 92 | 4.00 | 1.5 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.15 | 1.40 | 0.4 | 1.9 | 10.6 | 200 | PVC | SDR 35 | 0.40 | 21.1 | 8.89% | 0.67 | 0.34 |
| EX29A | EX29 | EX28 | 0.44 | 10 | 0 | 0 | 34 | 1.84 | 126 | 4.00 | 2.0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.44 | 1.84 | 0.5 | 2.6 | 71.7 | 200 | PVC | SDR 35 | 0.40 | 21.1 | 12.08% | 0.67 | 0.37 |
| EX28A | EX28 | EX24 | 0.21 | 4 | 0 | 0 | 14 | 2.05 | 139 | 4.00 | 2.3 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.21 | 2.05 | 0.6 | 2.8 | 54.6 | 200 | PVC | SDR 35 | 0.80 | 29.9 | 9.47% | 0.94 | 0.49 |
| EX27A | EX27 | EX26 | 0.16 | 2 | 0 | 0 | 7 | 0.16 | 7 | 4.00 | 0.1 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.16 | 0.16 | 0.0 | 0.2 | 11.2 | 200 | PVC | SDR 35 | 0.65 | 27.0 | 0.57% | 0.85 | 0.18 |
| EX26A | EX26 | EX25 | 0.31 | 8 | 0 | 0 | 27 | 0.47 | 34 | 4.00 | 0.6 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.31 | 0.47 | 0.1 | 0.7 | 48.8 | 200 | PVC | SDR 35 | 0.40 | 21.1 | 3.22% | 0.67 | 0.25 |
| EX25A | EX25 | EX24 | 0.48 | 10 | 0 | 0 | 34 | 0.95 | 68 | 4.00 | 1.1 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.48 | 0.95 | 0.3 | 1.4 | 91.3 | 200 | PVC | SDR 35 | 0.60 | 25.9 | 5.28% | 0.81 | 0.36 |
| EX36A | EX36 | EX35 | 0.76 | 19 | 0 | 0 | 65 | 0.76 | 65 | 4.00 | 1.0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.76 | 0.76 | 0.2 | 1.3 | 91.7 | 200 | PVC | SDR 35 | 0.50 | 23.6 | 5.32% | 0.74 | 0.33 |
| EX35A | EX35 | EX34 | 0.12 | 2 | 0 | 0 | 7 | 0.88 | 71 | 4.00 | 1.2 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.12 | 0.88 | 0.2 | 1.4 | 43.9 | 200 | PVC | SDR 35 | 0.60 | 25.9 | 5.42% | 0.81 | 0.36 |
| EX40A | EX40 | EX39 | 0.50 | 12 | 0 | 0 | 41 | 0.50 | 41 | 4.00 | 0.7 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.50 | 0.50 | 0.1 | 0.8 | 65.7 | 200 | PVC | SDR 35 | 1.60 | 42.3 | 1.90% | 1.33 | 0.44 |
| EX45A | EX45 | EX44 | 0.67 | 16 | 0 | 0 | 54 | 0.67 | 54 | 4.00 | 0.9 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.67 | 0.67 | 0.2 | 1.1 | 112.3 | 200 | PVC | SDR 35 | 1.20 | 36.6 | 2.92% | 1.15 | 0.44 |
| EX44A | EX44 | EX43 | 0.17 | 2 | 0 | 0 | 7 | 0.84 | 61 | 4.00 | 1.0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.17 | 0.84 | 0.2 | 1.2 | 10.6 | 200 | PVC | SDR 35 | 0.80 | 29.9 | 4.10% | 0.94 | 0.39 |
| EX43A | EX43 | EX42 | 0.78 | 18 | 0 | 0 | 61 | 1.63 | 122 | 4.00 | 2.0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.78 | 1.63 | 0.5 | 2.4 | 103.5 | 200 | PVC | SDR 35 | 0.80 | 29.9 | 8.15% | 0.94 | 0.47 |
| EX42A | EX42 | EX41 | 0.06 | 1 | 0 | 0 | 3 | 1.68 | 126 | 4.00 | 2.0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.06 | 1.68 | 0.5 | 2.5 | 10.6 | 200 | PVC | SDR 35 | 0.80 | 29.9 | 8.39% | 0.94 | 0.48 |
| EX41A | EX41 | EX39 | 0.10 | 0 | 0 | 0 | 0 | 1.79 | 126 | 4.00 | 2.0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.10 | 1.79 | 0.5 | 2.5 | 64.5 | 200 | PVC | SDR 35 | 0.40 | 21.1 | 12.02% | 0.66 | 0.37 |
| EX39A | EX39 | EX38 | 0.67 | 17 | 0 | 0 | 58 | 2.96 | 224 | 4.00 | 3.6 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.67 | 2.96 | 0.8 | 4.5 | 94.6 | 200 | PVC | SDR 35 | 0.40 | 21.1 | 21.11% | 0.67 | 0.44 |
| EX38A | EX38 | EX37 | 0.21 | 5 | 0 | 0 | 17 | 3.16 | 241 | 4.00 | 3.9 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.21 | 3.16 | 0.9 | 4.8 | 46.8 | 200 | PVC | SDR 35 | 0.40 | 21.1 | 22.69% | 0.67 | 0.45 |
| EX52A | EX52 | EX51 | 0.16 | 2 | 0 | 0 | 7 | 0.16 | 7 | 4.00 | 0.1 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.16 | 0.16 | 0.0 | 0.2 | 11.6 | 200 | PVC | SDR 35 | 0.75 | 29.0 | 0.54% | 0.91 | 0.20 |
| EX51A | EX51 | EX50 | 0.43 | 11 | 0 | 0 | 37 | 0.59 | 44 | 4.00 | 0.7 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.43 | 0.59 | 0.2 | 0.9 | 71.7 | 200 | PVC | SDR 35 | 0.75 | 29.0 | 3.05% | 0.91 | 0.35 |
| EX54A | EX54 | EX53 | 0.45 | 9 | 0 | 0 | 31 | 0.45 | 31 | 4.00 | 0.5 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.45 | 0.45 | 0.1 | 0.6 | 71.2 | 200 | PVC | SDR 35 | 0.45 | 22.4 | 2.77% | 0.71 | 0.26 |
| SA62A | 62 | 61 | 0.24 | 4 | 0 | 0 | 14 | 0.24 | 14 | 4.00 | 0.2 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.24 | 0.24 | 0.1 | 0.3 | 46.2 | 200 | PVC | SDR 35 | 0.65 | 27.0 | 1.07% | 0.85 | 0.23 |
| SA61A | 61 | 60 | 0.22 | 3 | 0 | 0 | 10 | 0.46 | 24 | 4.00 | 0.4 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.22 | 0.46 | 0.1 | 0.5 | 11.0 | 200 | PVC | SDR 35 | 0.65 | 27.0 | 1.91% | 0.85 | 0.28 |
| SA60A | 60 | 59 | 0.31 | 8 | 0 | 0 | 27 | 0.77 | 51 | 4.00 | 0.8 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.31 | 0.77 | 0.2 | 1.0 | 53.3 | 200 | PVC | SDR 35 | 0.50 | 23.6 | 4.40% | 0.74 | 0.32 |
| SA64A | 64 | 63 | 0.19 | 4 | 0 | 0 | 14 | 0.19 | 14 | 4.00 | 0.2 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.19 | 0.19 | 0.1 | 0.3 | 48.9 | 200 | PVC | SDR 35 | 2.00 | 47.3 | 0.58% | 1.49 | 0.32 |
| SA65A | 65 | 63 | 0.54 | 12 | 0 | 0 | 41 | 0.54 | 41 | 4.00 | 0.7 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.54 | 0.54 | 0.2 | 0.8 | 72.4 | 200 | PVC | SDR 35 | 0.65 | 27.0 | 3.01% | 0.85 | 0.32 |
| SA63A | 63 | 59 | 0.32 | 7 | 0 | 0 | 24 | 1.05 | 78 | 4.00 | 1.3 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.32 | 1.05 | 0.3 | 1.6 | 70.6 | 200 | PVC | SDR 35 | 0.75 | 29.0 | 5.39% | 0.91 | 0.40 |
| SA59A | 59 | EX58A | 0.30 | 6 | 0 | 0 | 20 | 2.12 | 150 | 4.00 | 2.4 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.30 | 2.12 | 0.6 | 3.0 | 59.3 | 200 | PVC | SDR 35 | 0.75 | 29.0 | 10.42% | 0.91 | 0.49 |
| | EX58A | EX58 | 0.00 | 0 | 0 | 0 | 0 | 2.12 | 150 | 4.00 | 2.4 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.00 | 2.12 | 0.6 | 3.0 | 12.6 | 200 | PVC | SDR 35 | 0.75 | 29.0 | 10.42% | 0.91 | 0.49 |
| EX58A | EX58 | EX57 | 0.47 | 12 | 0 | 0 | 41 | 2.59 | 190 | 4.00 | 3.1 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.47 | 2.59 | 0.7 | 3.8 | 64.5 | 200 | PVC | SDR 35 | 0.75 | 29.0 | 13.16% | 0.91 | 0.52 |
| EX57A | EX57 | EX56 | 0.12 | 2 | 0 | 0 | 7 | 2.70 | 197 | 4.00 | 3.2 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.12 | 2.70 | 0.8 | 4.0 | 10.6 | 200 | PVC | SDR 35 | 0.75 | 29.0 | 13.65% | 0.91 | 0.53 |
| EX56A | EX56 | EX55 | 0.34 | 7 | 0 | 0 | 24 | 3.05 | 221 | 4.00 | 3.6 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.34 | 3.05 | 0.9 | 4.4 | 65.6 | 200 | PVC | SDR 35 | 0.75 | 29.0 | 15.31% | 0.91 | 0.55 |
| EX55A | EX55 | EX53 | 0.38 | 8 | 0 | 0 | 27 | 3.43 | 248 | 4.00 | 4.0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.38 | 3.43 | 1.0 | 5.0 | 65.5 | 200 | PVC | SDR 35 | 0.50 | 23.6 | 21.07% | 0.74 | 0.49 |
| EX53A | EX53 | EX50 | 0.19 | 3 | 0 | 0 | 10 | 4.07 | 289 | 4.00 | 4.7 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.19 | 4.07 | 1.1 | 5.8 | 68.5 | 200 | PVC | SDR 35 | 0.40 | 21.1 | 27.53% | 0.67 | 0.47 |
| EX50A | EX50 | EX37 | 0.26 | 6 | 0 | 0 | 20 | 4.92 | 354 | 4.00 | 5.7 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.26 | 4.92 | 1.4 | 7.1 | 49.1 | 200 | PVC | SDR 35 | 0.40 | 21.0 | 33.77% | 0.66 | 0.50 |
| EX37A | EX37 | EX34 | 0.41 | 10 | 0 | 0 | 34 | 8.49 | 629 | 3.92 | 10.0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.41 | 8.49 | 2.4 | 12.4 | 72.0 | 200 | PVC | SDR 35 | 0.40 | 21.1 | 58.49% | 0.67 | 0.59 |
| EX34A | EX34 | EX24 | 0.41 | 10 | 0 | 0 | 34 | 9.79 | 734 | 3.88 | 11.6 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.41 | 9.79 | 2.7 | 14.3 | 72.5 | 200 | PVC | SDR 35 | 0.40 | 21.1 | 67.57% | 0.67 | 0.62 |
| EX24A | EX24 | EX20 | 0.38 | 10 | 0 | 0 | 34 | 13.16 | 976 | 3.81 | 15.0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.38 | 13.16 | 3.7 | 18.7 | 73.0 | 200 | PVC | SDR 35 | 0.42 | 21.7 | 86.43% | 0.68 | 0.69 |
| EX20A | EX20 | EX15 | 0.10 | 0 | 0 | 0 | 0 | 14.40 | 1068 | 3.78 | 16.4 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.10 | 14.40 | 4.0 | 20.4 | 71.0 | 250 | PVC | SDR 35 | 0.37 | 36.7 | 55.56% | 0.74 | 0.65 |
| EX15A | EX15 | EX11 | 0.20 | 0 | 8 | 0 | 22 | 15.92 | 1205 | 3.75 | 18.3 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.20 | 15.92 | 4.5 | 22.7 | 68.0 | 300 | PVC | SDR 35 | 0.34 | 55.8 | 40.73% | 0.79 | 0.64 |
| EX11A | EX11 | EX8 | 0.11 | 0 | 4 | 0 | 11 | 17.05 | 1332 | 3.72 | 20.1 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.11 | 17.05 | 4.8 | 24.8 | 45.0 | 300 | PVC | SDR 35 | 0.98 | 94.9 | 26.15% | 1.35 | 0.95 |
| EX8A | EX8 | EX3 | 0.15 | 0 | 6 | 0 | 16 | 18.35 | 1442 | 3.69 | 21.6 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.56 | 0.0 | 0.15 | 18.91 | 5.3 | 26.9 | 50.3 | 300 | PVC | SDR 35 | 0.38 | 59.0 | 45.49% | 0.84 | 0.70 |
| EX3A | EX3 | EX2 | 0.30 | 0 | 18 | 0 | 49 | 19.53 | 1585 | 3.66 | 23.5 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.56 | 0.0 | 0.30 | 20.09 | 5.6 | 29.1 | 68.1 | 300 | PVC | SDR 35 | 0.37 | 58.2 | 50.08% | 0.83 | 0.71 |
| EX2A | EX2 | EX1 | 0.36 | 0 | 15 | 0 | 41 | 19.89 | 1625 | 3.65 | 24.1 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.56 | 0.0 | 0.36 | 20.45 | 5.7 | 29.8 | 68.1 | 300 | PVC | SDR 35 | 0.35 | 57.0 | 52.25% | 0.81 | 0.70 |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | 300 | | | | | | | |

Stantec

SUBDIVISION:

**Half Moon Bay South Phase 5**

DATE: 15/2/2019
REVISION: 1
DESIGNED BY: DT
CHECKED BY: KS

# SANITARY SEWER DESIGN SHEET
(City of Ottawa)

**FILE NUMBER:** 160401476

**DESIGN PARAMETERS**


| | | | | | |
|---|---|---|---|---|---|
| MAX PEAK FACTOR (RES.)= | 4.0 | AVG. DAILY FLOW / PERSON | 280 l/p/day | MINIMUM VELOCITY | 0.60 m/s |
| MIN PEAK FACTOR (RES.)= | 2.0 | COMMERCIAL | 28,000 l/ha/day | MAXIMUM VELOCITY | 3.00 m/s |
| PEAKING FACTOR (INDUSTRIAL): | 2.4 | INDUSTRIAL (HEAVY) | 55,000 l/ha/day | MANNINGS n | 0.013 |
| PEAKING FACTOR (ICI >20%): | 1.5 | INDUSTRIAL (LIGHT) | 35,000 l/ha/day | BEDDING CLASS | B |
| PERSONS / SINGLE | 3.4 | INSTITUTIONAL | 28,000 l/ha/day | MINIMUM COVER | 2.50 m |
| PERSONS / TOWNHOME | 2.7 | INFILTRATION | 0.33 l/s/Ha | HARMON CORRECTION FACTOR | 0.8 |
| PERSONS / APARTMENT | 1.8 | | | | |

| LOCATION | | | RESIDENTIAL AREA AND POPULATION | | | | | | | | | COMMERCIAL | | INDUSTRIAL (L) | | INDUSTRIAL (H) | | INSTITUTIONAL | | GREEN / UNUSED | | C+I+I | INFILTRATION | | | TOTAL | PIPE | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| AREA ID NUMBER | FROM M.H. | TO M.H. | AREA | SINGLE | UNITS TOWN | APT | POP. | CUMULATIVE AREA | CUMULATIVE POP. | PEAK FACT. | PEAK FLOW | AREA | ACCU. AREA | AREA | ACCU. AREA | AREA | ACCU. AREA | AREA | ACCU. AREA | AREA | ACCU. AREA | PEAK FLOW | TOTAL AREA | ACCU. AREA | INFILT. FLOW | FLOW | LENGTH | DIA | MATERIAL | CLASS | SLOPE | CAP. (FULL) | CAP. V PEAK FLOW | VEL. (FULL) | VEL. (ACT.) |
| | | | (ha) | | | | | (ha) | | | (l/s) | (ha) | (ha) | (ha) | (ha) | (ha) | (ha) | (ha) | (ha) | (ha) | (ha) | (l/s) | (ha) | (ha) | (l/s) | (l/s) | (m) | (mm) | | | (%) | (l/s) | (%) | (m/s) | (m/s) |
| 1/4 R227A | 227 | 226 | 0.83 | 17 | 0 | 0 | 58 | 0.83 | 58 | 3.64 | 0.7 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.83 | 0.83 | 0.3 | 1.0 | 111.2 | 200 | PVC | SDR 35 | 0.65 | 27.0 | **3.55%** | 0.85 | 0.34 |
| C230A | 230 | 226 | 0.00 | 0 | 0 | 0 | 0 | 0.00 | 0 | 3.80 | 0.0 | 2.13 | 2.13 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 1.0 | 2.13 | 2.13 | 0.7 | 1.7 | 7.8 | 200 | PVC | SDR 35 | 0.65 | 27.0 | **6.45%** | 0.85 | 0.40 |
| | 226 | 225 | 0.00 | 0 | 0 | 0 | 0 | 0.83 | 58 | 3.64 | 0.7 | 0.00 | 2.13 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 1.0 | 0.00 | 2.96 | 1.0 | 2.7 | 12.7 | 200 | PVC | SDR 35 | 0.50 | 23.6 | **11.40%** | 0.74 | 0.41 |
| | 225 | 222 | 0.00 | 0 | 0 | 0 | 0 | 0.83 | 58 | 3.64 | 0.7 | 0.00 | 2.13 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 1.0 | 0.00 | 2.96 | 1.0 | 2.7 | 63.0 | 200 | PVC | SDR 35 | 2.30 | 50.7 | **5.32%** | 1.60 | 0.70 |
| 1/4 R227A | 224 | 223 | 0.83 | 30 | 0 | 0 | 102 | 0.83 | 102 | 3.59 | 1.2 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.83 | 0.83 | 0.3 | 1.5 | 55.6 | 200 | PVC | SDR 35 | 0.40 | 21.1 | **6.92%** | 0.67 | 0.32 |
| | 223 | 222 | 0.00 | 0 | 0 | 0 | 0 | 0.83 | 102 | 3.59 | 1.2 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.00 | 0.83 | 0.3 | 1.5 | 64.6 | 200 | PVC | SDR 35 | 0.40 | 21.1 | **6.92%** | 0.67 | 0.32 |
| | 222 | 219 | 0.00 | 0 | 0 | 0 | 0 | 1.67 | 160 | 3.55 | 1.8 | 0.00 | 2.13 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 1.0 | 0.00 | 3.80 | 1.3 | 4.1 | 95.3 | 200 | PVC | SDR 35 | 2.30 | 50.7 | **8.13%** | 1.60 | 0.79 |
| 1/4 R227A | 165 | 229 | 0.83 | 3 | 11 | 0 | 40 | 0.83 | 40 | 3.67 | 0.5 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.83 | 0.83 | 0.3 | 0.7 | 58.1 | 200 | PVC | SDR 35 | 0.65 | 27.0 | **2.78%** | 0.85 | 0.31 |
| | 229 | 228 | 0.00 | 0 | 0 | 0 | 0 | 0.83 | 40 | 3.67 | 0.5 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.00 | 0.83 | 0.3 | 0.7 | 28.2 | 200 | PVC | SDR 35 | 0.40 | 21.1 | **3.54%** | 0.67 | 0.26 |
| | 228 | 219 | 0.00 | 0 | 0 | 0 | 0 | 0.83 | 40 | 3.67 | 0.5 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.00 | 0.83 | 0.3 | 0.7 | 48.1 | 200 | PVC | SDR 35 | 0.40 | 21.1 | **3.54%** | 0.67 | 0.26 |
| 1/4 R227A | 221 | 220 | 0.83 | 9 | 0 | 0 | 31 | 0.83 | 31 | 3.68 | 0.4 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.83 | 0.83 | 0.3 | 0.6 | 18.9 | 200 | PVC | SDR 35 | 0.65 | 27.0 | **2.37%** | 0.85 | 0.29 |
| | 220 | 219 | 0.00 | 0 | 0 | 0 | 0 | 0.83 | 31 | 3.68 | 0.4 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.00 | 0.83 | 0.3 | 0.6 | 29.5 | 200 | PVC | SDR 35 | 0.40 | 21.1 | **3.03%** | 0.67 | 0.25 |
| | 219 | 218 | 0.00 | 0 | 0 | 0 | 0 | 3.33 | 230 | 3.50 | 2.6 | 0.00 | 2.13 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 1.0 | 0.00 | 5.46 | 1.8 | 5.5 | 21.7 | 200 | PVC | SDR 35 | 0.40 | 21.1 | **25.77%** | 0.67 | 0.47 |
| | 218 | 217 | 0.00 | 0 | 0 | 0 | 0 | 3.33 | 230 | 3.50 | 2.6 | 0.00 | 2.13 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 1.0 | 0.00 | 5.46 | 1.8 | 5.5 | 16.4 | 200 | PVC | SDR 35 | 0.40 | 21.1 | **25.77%** | 0.67 | 0.47 |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | 200 | | | | | | | |
| R167A | 167 | 166 | 1.35 | 0 | 54 | 0 | 146 | 1.35 | 146 | 3.56 | 1.7 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 1.35 | 1.35 | 0.4 | 2.1 | 63.0 | 200 | PVC | SDR 35 | 3.00 | 57.9 | **3.67%** | 1.82 | 0.72 |
| | 166 | 165 | 0.00 | 0 | 0 | 0 | 0 | 1.35 | 146 | 3.56 | 1.7 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.00 | 1.35 | 0.4 | 2.1 | 70.0 | 200 | PVC | SDR 35 | 3.00 | 57.9 | **3.67%** | 1.82 | 0.72 |
| | 165 | 164 | 0.00 | 0 | 0 | 0 | 0 | 1.35 | 146 | 3.56 | 1.7 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.00 | 1.35 | 0.4 | 2.1 | 71.9 | 200 | PVC | SDR 35 | 1.00 | 33.4 | **6.36%** | 1.05 | 0.49 |
| | 164 | 158 | 0.00 | 0 | 0 | 0 | 0 | 1.35 | 146 | 3.56 | 1.7 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.00 | 1.35 | 0.4 | 2.1 | 71.9 | 200 | PVC | SDR 35 | 1.00 | 33.4 | **6.36%** | 1.05 | 0.49 |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | 200 | | | | | | | |
| R157A | 157 | 156 | 0.74 | 0 | 32 | 0 | 86 | 0.74 | 86 | 3.61 | 1.0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.74 | 0.74 | 0.2 | 1.3 | 62.8 | 200 | PVC | SDR 35 | 1.10 | 35.1 | **3.57%** | 1.10 | 0.44 |
| | 156 | 153 | 0.00 | 0 | 0 | 0 | 0 | 0.74 | 86 | 3.61 | 1.0 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 0.00 | 0.74 | 0.2 | 1.3 | 71.8 | 200 | PVC | SDR 35 | 1.10 | 35.1 | **3.57%** | 1.10 | 0.44 |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | 200 | | | | | | | |
| EX Phase 4 | 152 | 150 | 1.93 | 14 | 48 | 0 | 177 | 4.01 | 409 | 3.41 | 4.5 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.0 | 1.93 | 4.01 | 1.3 | 5.9 | 85.7 | 200 | PVC | SDR 35 | 0.80 | 29.9 | **19.57%** | 0.94 | 0.61 |

# Appendix C : STORM SEWER CALCULATIONS & REPORT EXCERPTS

## ICD Schedule

| Catchment ID | ICD Type / Size (mm) | Max. Release Rate (L/s) | # of CBs and Interconnection |
|---|---|---|---|
| **Proposed Draft Plan 3 Areas with Minor System to the Corrigan Pond** | | | |
| ST546B | 1 x IPEX B | 32 | One rear yard CB |
| ST560A | 1 x IPEX C | 42 | Two CBs Interconnected |
| ST560B | 1 x IPEX B | 32 | One rear yard CB |
| ST561A | 1 x IPEX B | 32 | Two CBs Interconnected |
| ST563A | 1 x IPEX C | 42 | Two CBs Interconnected |
| ST564A | 1 x IPEX C | 42 | Two CBs Interconnected |
| ST564B | 1 x IPEX B | 32 | One rear yard CB |
| ST566A | 1 x IPEX B | 32 | Two CBs Interconnected |
| **Proposed Draft Plan 3 Areas with Minor System to the Todd Pond** | | | |
| ST648A | 1 x IPEX A | 22 | One rear yard CB |
| ST649A | 1 x IPEX C, 1 x IPEX D | 109 | Three CBs - One Interconnected |
| ST650A | 2 x IPEX C | 84 | Two CBs |
| ST650B | 1 x IPEX C | 42 | One rear yard CB |
| ST652A | 3 x IPEX B | 96 | Three CBs |
| ST652AA | 120 L/s/ha | 339 | School CB |
| ST654A | 1 x IPEX B | 32 | One rear yard CB |
| ST655A | 1 x IPEX A, 1 x IPEX B | 54 | Two CBs |
| ST655B | 1 x IPEX D | 67 | One rear yard CB |
| ST656A | 1 x IPEX A, 1 x IPEX B | 54 | Two CBs |
| ST657A | 2 x IPEX B | 64 | Two CBs |
| ST659A | 2 x IPEX B | 64 | Three CBs - One Interconnected |
| ST660A | 1 x IPEX C, 1 x IPEX D | 109 | Two CBs |
| ST660B | 1 x IPEX A | 22 | One rear yard CB |
| ST662A | 60 L/s/ha | 55.2 | Park CB |
| ST662A | 2 x IPEX B | 64 | Two CBs |
| ST663A | 2 x IPEX B | 64 | Three CBs - One Interconnected |
| ST664A | 2 x IPEX C | 84 | Two CBs |
| ST703A | 1 x IPEX B, 2 x IPEX C | 116 | Three CBs |
| ST703B | 1 x IPEX B | 32 | Two CBs Interconnected |
| EXT-6 | 120 L/s/ha | 699.6 | School CB |
| ST704A | 1 x IPEX A, 1 x IPEX B | 55 | Park CB |
| ST705A | 2 x IPEX A, 2 x IPEX D | 178 | Four CBs |
| ST707AA | 60 L/s/ha | 186 | Park CB |
| ST709A | 2 x IPEX B | 64 | Two CBs |
| ST710A | 2 x IPEX C | 84 | Two CBs |
| ST710B | 1 x IPEX D | 67 | One rear yard CB |
| ST711A | 2 x IPEX B | 64 | Two CBs |
| ST713A | 2 x IPEX C | 84 | Two CBs |
| ST714A | 1 x IPEX C | 42 | One rear yard CB |
| ST715A | 1 x IPEX C, 1 x IPEX D | 109 | Two CBs |
| ST715B | 1 x IPEX C | 42 | One rear yard CB |
| ST717A | 2 x IPEX C | 84 | Two CBs |
| ST719A | 2 x IPEX A | 44 | Two CBs |
| ST719B | 1 x IPEX C | 42 | One rear yard CB |




Stantec


Stantec Consulting Ltd.
400 - 1331 Clyde Avenue
Ottawa ON
Tel. 613.722.4420
www.stantec.com



### Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.


### Legend

- PROPOSED STORM SEWER
- AREA ID
- RUNOFF COEFFICIENT
- STORM DRAINAGE AREA ha.
- STORM DRAINAGE BOUNDARY
- EXISTING/FUTURE STORM DRAINAGE BOUNDARY
- FUTURE MINOR DRAINAGE AREA
- TYPICAL SERVICE LATERAL LOCATION
- MAXIMUM PONDING LIMITS
- EXISTING STORM SEWER
- DIRECTION OF OVERLAND FLOW
- OVERLAND FLOW FROM EXTERNAL AREA
- CATCHBASIN TO BE INSTALLED WITH IPEX TYPE A OR EQUIVALENT 22.0L/S.
- CATCHBASIN TO BE INSTALLED WITH IPEX TYPE B OR EQUIVALENT 32.0L/S.
- CATCHBASIN TO BE INSTALLED WITH IPEX TYPE C OR EQUIVALENT 42.0L/S.
- CATCHBASIN TO BE INSTALLED WITH IPEX TYPE D OR EQUIVALENT 67.0L/S AND 250mmØ CB LEAD.
- CATCHBASIN TO BE INSTALLED WITH CIRCULAR ORIFICE (SEE ICD TABLE)
- CATCHBASINS TO BE INTERCONNECTED

1. AREAS ST5XX REPRESENT MINOR SYSTEM DRAINAGE AREAS TRIBUTARY TO THE STORM SEWER ON GREENBANK ROAD TO THE CORRIGAN POND, AREAS ST6XX AND ST7XX REPRESENT MINOR SYSTEM DRAINAGE AREAS TRIBUTARY TO THE STORM SEWER ON RIVER MIST ROAD TO THE TODD POND.

### Notes

| | | | | |
|---|---|---|---|---|
| 5 | ISSUED FOR CONSTRUCTION | DT | DT | 15.10.20 |
| 4 | REVISED INTERIM DRAINAGE | DT | DT | 15.09.02 |
| 3 | REVISED PER CITY COMMENTS | DT | DT | 15.08.26 |
| 2 | REVISED PER CITY COMMENTS | WJ | DT | 15.07.30 |
| 1 | ISSUED FOR REVIEW | MS | DT | 15.05.27 |
| Revision | | By | Appd. | YY.MM.DD |

| | | | | |
|---|---|---|---|---|
| File Name: 160400743-08 | DT | PM | DT | 15.05.19 |
| | Dwn. | Chkd. | Dsgn. | YY.MM.DD |

Permit-Seal

LICENSED PROFESSIONAL ENGINEER
D. C. THIFFAULT
100186107
20/10/2015
PROVINCE OF ONTARIO

Client/Project

MATTAMY HOMES LTD.

HALF MOON BAY SOUTH
PHASE 4
Ottawa, ON

Title

STORM DRAINAGE PLAN

| Project No. | Scale | Revision |
|---|---|---|
| 160400743 | 1:1500 (0, 15, 45, 75m) | |
| Drawing No. | Sheet | |
| SD-1 | 27 of 28 | 5 |


ORIGINAL SHEET - ARCH D

Stantec

**HALF MOON BAY SOUTH SUBDIVISION - PHASE 4**

DATE: 26-Aug-2015
REVISION: 2
DESIGNED BY: DT
CHECKED BY:

**FILE NUMBER: 1604-00743**

# STORM SEWER DESIGN SHEET
**(City of Ottawa)**

DESIGN PARAMETERS
$I = a / (t+b)^c$ (As per City of Ottawa Guidelines, 2012)

| | 1:5 yr | 1:100 yr |
|---|---|---|
| a = | 998.071 | 1735.688 |
| b = | 6.053 | 6.014 |
| c = | 0.814 | 0.820 |

MANNING'S n = 0.013 BEDDING CLASS = B
MINIMUM COVER: 2.00 m
TIME OF ENTRY 10 min

| LOCATION | | | DRAINAGE AREA | | | | | | | | | | | | | | | PIPE SELECTION | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| AREA ID NUMBER | FROM M.H. | TO M.H. | AREA (5-YEAR) (ha) | AREA (100-YEAR) (ha) | AREA (ROOF) (ha) | C (-) | ACCUM. AREA (5YR) (ha) | A x C (5-YEAR) (ha) | ACCUM. AxC (5YR) (ha) | ACCUM. AREA (100YR (ha) | A x C (100-YEAR) (ha) | ACCUM. AxC (100YR) (ha) | T of C (min) | $I_{5\text{-YEAR}}$ (mm/h) | $I_{10\text{-YEAR}}$ (mm/h) | $Q_{CONTROL}$ (NOTE 1) (L/s) | ACCUM. $Q_{CONTROL}$ (L/s) | $Q_{ACT}$ (CIA/360) (L/s) | LENGTH (m) | PIPE WIDTH OR DIAMETEI (mm) | PIPE HEIGHT (mm) | PIPE SHAPE (-) | MATERIAL (-) | CLASS (-) | SLOPE % | $Q_{CAP}$ (FULL) (L/s) | % FULL (-) | VEL. (FULL) (m/s) | VEL. (ACT) (m/s) | TIME OF FLOW (min) |
| ST510A | EX510 | EX509A | 0.56 | 0.00 | 0.00 | 0.20 | 0.56 | 0.112 | 0.112 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 32.4 | 32.9 | 450 | 450 | CIRCULAR | CONCRETE | - | 0.43 | 194.1 | **16.68%** | 1.18 | 0.73 | 0.75 |
| ST509AA, ST509AB | EX509A | EX603 | 0.93 | 0.00 | 0.00 | 0.65 | 1.49 | 0.608 | 0.720 | 0.00 | 0.000 | 0.000 | 10.75 | 100.38 | 171.96 | 0.0 | 0.0 | 200.7 | 37.3 | 750 | 750 | CIRCULAR | CONCRETE | - | 0.30 | 630.9 | **31.81%** | 1.38 | 1.04 | 0.60 |
| | EX603 | EX602 | 0.00 | 0.00 | 0.00 | 0.00 | 1.49 | 0.000 | 0.720 | 0.00 | 0.000 | 0.000 | 11.35 | 97.56 | 167.08 | 0.0 | 0.0 | 195.1 | 120.0 | 750 | 750 | CIRCULAR | CONCRETE | - | 0.11 | 382.3 | **51.03%** | 0.84 | 0.72 | 2.76 |
| | | | | | | | | | | | | | **14.12** | | | | | | | | | | | | | | | | | |
| ST521D, ST521E | EX521 | EX524 | 0.79 | 0.00 | 0.00 | 0.64 | 0.79 | 0.503 | 0.503 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 145.5 | 117.0 | 450 | 450 | CIRCULAR | CONCRETE | - | 0.21 | 134.7 | **108.02%** | 0.82 | 0.82 | 2.38 |
| ST524A | EX524 | EX627 | 0.26 | 0.00 | 0.00 | 0.70 | 1.04 | 0.179 | 0.682 | 0.00 | 0.000 | 0.000 | 12.38 | 93.12 | 159.40 | 0.0 | 0.0 | 176.3 | 84.9 | 525 | 525 | CIRCULAR | CONCRETE | - | 0.33 | 257.7 | **68.43%** | 1.15 | 1.09 | 1.30 |
| | | | | | | | | | | | | | **13.68** | | | | | | | | | | | | | | | | | |
| ST632A | EX632 | EX631 | 0.39 | 0.00 | 0.00 | 0.75 | 0.39 | 0.291 | 0.291 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 84.1 | 89.3 | 375 | 375 | CIRCULAR | PVC | - | 1.00 | 175.3 | **47.97%** | 1.59 | 1.34 | 1.11 |
| 631A, ST631B, ST631D, ST63 | EX631 | EX629A | 1.47 | 0.00 | 0.00 | 0.42 | 1.86 | 0.618 | 0.908 | 0.00 | 0.000 | 0.000 | 11.11 | 98.69 | 169.04 | 0.0 | 0.0 | 249.0 | 106.5 | 600 | 600 | CIRCULAR | CONCRETE | - | 0.25 | 320.2 | **77.76%** | 1.10 | 1.07 | 1.65 |
| | EX629A | EX629 | 0.00 | 0.00 | 0.00 | 0.00 | 1.86 | 0.000 | 0.908 | 0.00 | 0.000 | 0.000 | 12.76 | 91.58 | 156.75 | 0.0 | 0.0 | 231.1 | 17.5 | 750 | 750 | CIRCULAR | CONCRETE | - | 0.23 | 555.3 | **41.62%** | 1.22 | 0.98 | 0.30 |
| | | | | | | | | | | | | | **13.06** | | | | | | | | | | | | | | | | | |
| ST719B, ST719A, FUT-1 | 719 | 717 | 3.02 | 0.00 | 0.00 | 0.66 | 3.02 | 1.983 | 1.983 | 0.00 | 0.000 | 0.000 | 13.77 | 87.75 | 150.14 | 0.0 | 0.0 | 483.4 | 37.6 | 600 | 600 | CIRCULAR | CONCRETE | - | 1.75 | 847.4 | **57.05%** | 2.90 | 2.57 | 0.24 |
| | | | | | | | | | | | | | **14.01** | | | | | | | | | | | | | | | | | |
| | 718 | 717 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.000 | 0.000 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 0.0 | 44.6 | 300 | 300 | CIRCULAR | PVC | - | 0.65 | 77.5 | **0.00%** | 1.10 | 0.00 | 0.00 |
| | | | | | | | | | | | | | **10.00** | | | | | | | | | | | | | | | | | |
| ST717A | 717 | 716 | 0.33 | 0.00 | 0.00 | 0.73 | 3.35 | 0.238 | 2.221 | 0.00 | 0.000 | 0.000 | 14.01 | 86.89 | 148.64 | 0.0 | 0.0 | 536.0 | 69.0 | 825 | 825 | CIRCULAR | CONCRETE | - | 0.20 | 669.7 | **80.04%** | 1.21 | 1.20 | 0.96 |
| | 716 | 705 | 0.00 | 0.00 | 0.00 | 0.00 | 3.35 | 0.000 | 2.221 | 0.00 | 0.000 | 0.000 | 14.97 | 83.64 | 143.04 | 0.0 | 0.0 | 516.0 | 76.5 | 825 | 825 | CIRCULAR | CONCRETE | - | 0.20 | 669.7 | **77.05%** | 1.21 | 1.18 | 1.08 |
| | | | | | | | | | | | | | **16.05** | | | | | | | | | | | | | | | | | |
| ST709A | 709 | 708 | 0.22 | 0.00 | 0.00 | 0.75 | 0.22 | 0.163 | 0.163 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 47.3 | 66.7 | 300 | 300 | CIRCULAR | PVC | - | 1.75 | 127.2 | **37.15%** | 1.81 | 1.41 | 0.79 |
| | 708 | 707 | 0.00 | 0.00 | 0.00 | 0.00 | 0.22 | 0.000 | 0.163 | 0.00 | 0.000 | 0.000 | 10.79 | 100.19 | 171.64 | 0.0 | 0.0 | 45.4 | 63.7 | 300 | 300 | CIRCULAR | CONCRETE | - | 1.75 | 127.2 | **35.73%** | 1.81 | 1.39 | 0.76 |
| | | | | | | | | | | | | | **11.55** | | | | | | | | | | | | | | | | | |
| ST707AA | 707A | 707 | 3.10 | 0.00 | 0.00 | 0.20 | 3.10 | 0.620 | 0.620 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 179.5 | 6.2 | 450 | 450 | CIRCULAR | CONCRETE | - | 0.60 | 230.4 | **77.89%** | 1.40 | 1.37 | 0.08 |
| | | | | | | | | | | | | | **10.08** | | | | | | | | | | | | | | | | | |
| | 707 | 706 | 0.00 | 0.00 | 0.00 | 0.00 | 3.32 | 0.000 | 0.783 | 0.00 | 0.000 | 0.000 | 11.55 | 96.64 | 165.49 | 0.0 | 0.0 | 210.3 | 11.0 | 450 | 450 | CIRCULAR | CONCRETE | - | 1.50 | 364.3 | **57.73%** | 2.22 | 1.98 | 0.09 |
| | 706 | 705 | 0.00 | 0.00 | 0.00 | 0.00 | 3.32 | 0.000 | 0.783 | 0.00 | 0.000 | 0.000 | 11.65 | 96.23 | 164.79 | 0.0 | 0.0 | 209.4 | 35.5 | 450 | 450 | CIRCULAR | CONCRETE | - | 1.50 | 364.3 | **57.48%** | 2.22 | 1.98 | 0.30 |
| | | | | | | | | | | | | | **11.95** | | | | | | | | | | | | | | | | | |
| ST715B, ST715A | 715 | 714 | 0.74 | 0.00 | 0.00 | 0.61 | 0.74 | 0.453 | 0.453 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 131.1 | 120.0 | 375 | 375 | CIRCULAR | PVC | - | 0.75 | 151.8 | **86.37%** | 1.37 | 1.38 | 1.45 |
| ST714A | 714 | 713 | 0.29 | 0.00 | 0.00 | 0.47 | 1.02 | 0.134 | 0.587 | 0.00 | 0.000 | 0.000 | 11.45 | 97.13 | 166.34 | 0.0 | 0.0 | 158.5 | 12.8 | 525 | 525 | CIRCULAR | CONCRETE | - | 0.20 | 200.6 | **79.00%** | 0.90 | 0.88 | 0.24 |
| ST713A | 713 | 712 | 0.32 | 0.00 | 0.00 | 0.71 | 1.34 | 0.226 | 0.813 | 0.00 | 0.000 | 0.000 | 11.69 | 96.05 | 164.48 | 0.0 | 0.0 | 217.0 | 62.5 | 600 | 600 | CIRCULAR | CONCRETE | - | 0.20 | 286.5 | **75.74%** | 0.98 | 0.95 | 1.10 |
| | 712 | 711 | 0.00 | 0.00 | 0.00 | 0.00 | 1.34 | 0.000 | 0.813 | 0.00 | 0.000 | 0.000 | 12.78 | 91.48 | 156.57 | 0.0 | 0.0 | 206.6 | 11.0 | 600 | 600 | CIRCULAR | CONCRETE | - | 0.20 | 286.5 | **72.13%** | 0.98 | 0.94 | 0.20 |
| ST711A | 711 | 710 | 0.28 | 0.00 | 0.00 | 0.71 | 1.62 | 0.200 | 1.013 | 0.00 | 0.000 | 0.000 | 12.98 | 90.71 | 155.25 | 0.0 | 0.0 | 255.3 | 44.6 | 675 | 675 | CIRCULAR | CONCRETE | - | 0.20 | 392.2 | **65.11%** | 1.06 | 0.99 | 0.75 |
| ST710A, ST710B | 710 | 705 | 0.77 | 0.00 | 0.00 | 0.61 | 2.40 | 0.470 | 1.483 | 0.00 | 0.000 | 0.000 | 13.73 | 87.89 | 150.37 | 0.0 | 0.0 | 362.2 | 120.0 | 825 | 825 | CIRCULAR | CONCRETE | - | 0.20 | 669.7 | **54.08%** | 1.21 | 1.07 | 1.88 |
| | | | | | | | | | | | | | **15.61** | | | | | | | | | | | | | | | | | |
| ST705A | 705 | 703 | 0.70 | 0.00 | 0.00 | 0.74 | 9.77 | 0.520 | 5.007 | 0.00 | 0.000 | 0.000 | 16.05 | 80.30 | 137.28 | 0.0 | 0.0 | 1116.9 | 75.2 | 1050 | 1050 | CIRCULAR | CONCRETE | - | 0.25 | 1424.4 | **78.41%** | 1.59 | 1.56 | 0.80 |
| | | | | | | | | | | | | | **16.86** | | | | | | | | | | | | | | | | | |
| ST704A | 704 | 703 | 0.22 | 0.00 | 0.00 | 0.67 | 0.22 | 0.149 | 0.149 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 43.2 | 96.2 | 300 | 300 | CIRCULAR | PVC | - | 1.60 | 121.6 | **35.49%** | 1.73 | 1.33 | 1.21 |
| | | | | | | | | | | | | | **11.21** | | | | | | | | | | | | | | | | | |
| ST703B, ST703A | 703 | EX630A | 0.69 | 0.00 | 0.00 | 0.64 | 10.68 | 0.442 | 5.598 | 0.00 | 0.000 | 0.000 | 16.86 | 78.00 | 133.31 | 0.0 | 0.0 | 1212.9 | 53.1 | 1200 | 1200 | CIRCULAR | CONCRETE | - | 0.15 | 1560.4 | **77.73%** | 1.34 | 1.31 | 0.68 |
| ST630AA, ST630AB | EX630A | EX630 | 1.07 | 0.00 | 0.00 | 0.64 | 11.76 | 0.690 | 6.288 | 0.00 | 0.000 | 0.000 | 17.53 | 76.18 | 130.17 | 0.0 | 0.0 | 1330.6 | 96.7 | 1200 | 1200 | CIRCULAR | CONCRETE | - | 0.15 | 1575.2 | **84.47%** | 1.35 | 1.35 | 1.19 |
| ST630A | EX630 | EX629 | 0.16 | 0.00 | 0.00 | 0.72 | 11.92 | 0.119 | 6.407 | 0.00 | 0.000 | 0.000 | 18.72 | 73.18 | 125.00 | 0.0 | 0.0 | 1302.4 | 91.7 | 1200 | 1200 | CIRCULAR | CONCRETE | - | 0.15 | 1572.3 | **82.84%** | 1.35 | 1.34 | 1.14 |
| | | | | | | | | | | | | | **19.86** | | | | | | | | | | | | | | | | | |
| ST629A | EX629 | EX628 | 0.36 | 0.00 | 0.00 | 0.70 | 14.13 | 0.251 | 7.567 | 0.00 | 0.000 | 0.000 | 19.86 | 70.55 | 120.47 | 0.0 | 0.0 | 1482.9 | 52.7 | 1350 | 1350 | CIRCULAR | CONCRETE | - | 0.15 | 2157.3 | **68.74%** | 1.46 | 1.38 | 0.64 |
| ST628A | EX628 | EX627 | 0.64 | 0.00 | 0.00 | 0.72 | 14.78 | 0.462 | 8.029 | 0.00 | 0.000 | 0.000 | 20.50 | 69.17 | 118.08 | 0.0 | 0.0 | 1542.6 | 99.9 | 1350 | 1350 | CIRCULAR | CONCRETE | - | 0.15 | 2188.4 | **70.49%** | 1.48 | 1.41 | 1.18 |
| | | | | | | | | | | | | | **21.69** | | | | | | | | | | | | | | | | | |
| ST663A | 663 | 662 | 0.24 | 0.00 | 0.00 | 0.69 | 0.24 | 0.163 | 0.163 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 47.2 | 84.0 | 300 | 300 | CIRCULAR | PVC | - | 1.10 | 100.8 | **46.85%** | 1.43 | 1.20 | 1.17 |
| | | | | | | | | | | | | | **11.17** | | | | | | | | | | | | | | | | | |
| ST662AA | 662A | 662 | 0.91 | 0.00 | 0.00 | 0.20 | 0.91 | 0.182 | 0.182 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 52.7 | 12.5 | 375 | 375 | CIRCULAR | PVC | - | 0.25 | 87.8 | **60.05%** | 0.80 | 0.72 | 0.29 |
| | | | | | | | | | | | | | **10.29** | | | | | | | | | | | | | | | | | |
| ST662A | 662 | 652 | 0.26 | 0.00 | 0.00 | 0.62 | 1.41 | 0.163 | 0.508 | 0.00 | 0.000 | 0.000 | 11.17 | 98.42 | 168.56 | 0.0 | 0.0 | 139.0 | 62.0 | 450 | 450 | CIRCULAR | CONCRETE | - | 1.10 | 311.9 | **44.56%** | 1.90 | 1.56 | 0.66 |
| | | | | | | | | | | | | | **11.83** | | | | | | | | | | | | | | | | | |
| ST652AA | 652A | 652 | 2.77 | 0.00 | 0.00 | 0.50 | 2.77 | 1.386 | 1.386 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 401.1 | 17.6 | 600 | 600 | CIRCULAR | CONCRETE | - | 0.50 | 452.9 | **88.54%** | 1.55 | 1.58 | 0.19 |
| | | | | | | | | | | | | | **10.19** | | | | | | | | | | | | | | | | | |

Stantec

**HALF MOON BAY SOUTH SUBDIVISION - PHASE 4**

DATE: 26-Aug-2015
REVISION: 2
DESIGNED BY: DT
CHECKED BY:

**FILE NUMBER: 1604-00743**

# STORM SEWER DESIGN SHEET
**(City of Ottawa)**

DESIGN PARAMETERS
$I = a / (t+b)^c$ (As per City of Ottawa Guidelines, 2012)

| | 1:5 yr | 1:100 yr |
|---|---|---|
| a = | 998.071 | 1735.688 |
| b = | 6.053 | 6.014 |
| c = | 0.814 | 0.820 |

MANNING'S n = 0.013 BEDDING CLASS = B
MINIMUM COVER: 2.00 m
TIME OF ENTRY 10 min

| LOCATION | | | DRAINAGE AREA | | | | | | | | | | | | | | | PIPE SELECTION | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| AREA ID NUMBER | FROM M.H. | TO M.H. | AREA (5-YEAR) (ha) | AREA (100-YEAR) (ha) | AREA (ROOF) (ha) | C (-) | ACCUM. AREA (5YR) (ha) | A x C (5-YEAR) (ha) | ACCUM. AxC (5YR) (ha) | ACCUM. AREA (100YR (ha) | A x C (100-YEAR) (ha) | ACCUM. AxC (100YR) (ha) | T of C (min) | $I_{5\text{-YEAR}}$ (mm/h) | $I_{10\text{-YEAR}}$ (mm/h) | $Q_{CONTROL}$ (NOTE 1) (L/s) | ACCUM. $Q_{CONTROL}$ (L/s) | $Q_{ACT}$ (CIA/360) (L/s) | LENGTH (m) | PIPE WIDTH OR DIAMETEI (mm) | PIPE HEIGHT (mm) | PIPE SHAPE (-) | MATERIAL (-) | CLASS (-) | SLOPE % | $Q_{CAP}$ (FULL) (L/s) | % FULL (-) | VEL. (FULL) (m/s) | VEL. (ACT) (m/s) | TIME OF FLOW (min) |
| ST652A, ST652B | 652 | EX652A | 0.47 | 0.00 | 0.00 | 0.63 | 4.65 | 0.296 | 2.191 | 0.00 | 0.000 | 0.000 | 11.83 | 95.44 | 163.42 | 0.0 | 0.0 | 580.7 | 14.9 | 675 | 675 | CIRCULAR | CONCRETE | - | 1.40 | 1037.6 | **55.97%** | 2.81 | 2.49 | 0.10 |
| | EX652A | EX643 | 0.00 | 0.00 | 0.00 | 0.00 | 4.65 | 0.000 | 2.191 | 0.00 | 0.000 | 0.000 | 11.93 | 95.01 | 162.67 | 0.0 | 0.0 | 578.1 | 46.6 | 675 | 675 | CIRCULAR | CONCRETE | - | 1.40 | 1037.6 | **55.72%** | 2.81 | 2.49 | 0.31 |
| | | | | | | | | | | | | | **12.24** | | | | | | | | | | | | | | | | | |
| | 661 | 660 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.000 | 0.000 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 0.0 | 10.6 | 300 | 300 | CIRCULAR | PVC | - | 0.65 | 77.5 | **0.00%** | 1.10 | 0.00 | 0.00 |
| ST660B, ST660A | 660 | 659 | 0.60 | 0.00 | 0.00 | 0.68 | 0.60 | 0.404 | 0.404 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 116.9 | 98.5 | 525 | 525 | CIRCULAR | CONCRETE | - | 0.20 | 200.6 | **58.25%** | 0.90 | 0.80 | 2.05 |
| ST659A, FUT-3 | 659 | 656 | 1.48 | 0.00 | 0.00 | 0.65 | 2.07 | 0.961 | 1.365 | 0.00 | 0.000 | 0.000 | 12.05 | 94.50 | 161.80 | 0.0 | 0.0 | 358.3 | 48.0 | 750 | 750 | CIRCULAR | CONCRETE | - | 0.20 | 519.4 | **68.98%** | 1.14 | 1.07 | 0.75 |
| | | | | | | | | | | | | | **12.79** | | | | | | | | | | | | | | | | |
| | 658 | 657 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.000 | 0.000 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 0.0 | 10.6 | 300 | 300 | CIRCULAR | PVC | - | 0.65 | 77.5 | **0.00%** | 1.10 | 0.00 | 0.00 |
| ST657A | 657 | 656 | 0.26 | 0.00 | 0.00 | 0.72 | 0.26 | 0.185 | 0.185 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 53.4 | 98.5 | 375 | 375 | CIRCULAR | PVC | - | 0.25 | 87.8 | **60.80%** | 0.80 | 0.72 | 2.27 |
| | | | | | | | | | | | | | **12.27** | | | | | | | | | | | | | | | | |
| ST656A, FUT-2 | 656 | 655 | 1.37 | 0.00 | 0.00 | 0.72 | 3.70 | 0.981 | 2.530 | 0.00 | 0.000 | 0.000 | 12.79 | 91.45 | 156.52 | 0.0 | 0.0 | 642.7 | 67.0 | 825 | 825 | CIRCULAR | CONCRETE | - | 0.80 | 1339.4 | **47.99%** | 2.43 | 2.06 | 0.54 |
| ST655B, ST655A | 655 | 654 | 0.72 | 0.00 | 0.00 | 0.55 | 4.41 | 0.395 | 2.926 | 0.00 | 0.000 | 0.000 | 13.33 | 89.36 | 152.91 | 0.0 | 0.0 | 726.2 | 88.7 | 825 | 825 | CIRCULAR | CONCRETE | - | 0.80 | 1339.7 | **54.21%** | 2.43 | 2.13 | 0.69 |
| | | | | | | | | | | | | | **14.03** | | | | | | | | | | | | | | | | |
| ST664A | 664 | 654 | 0.32 | 0.00 | 0.00 | 0.73 | 0.32 | 0.233 | 0.233 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 67.5 | 98.2 | 300 | 300 | CIRCULAR | PVC | - | 1.50 | 117.8 | **57.35%** | 1.67 | 1.50 | 1.09 |
| | | | | | | | | | | | | | **11.09** | | | | | | | | | | | | | | | | |
| ST654A | 654 | 649 | 0.19 | 0.00 | 0.00 | 0.52 | 4.93 | 0.101 | 3.260 | 0.00 | 0.000 | 0.000 | 14.03 | 86.84 | 148.56 | 0.0 | 0.0 | 786.3 | 75.0 | 825 | 825 | CIRCULAR | CONCRETE | - | 0.80 | 1339.4 | **58.71%** | 2.43 | 2.19 | 0.57 |
| | | | | | | | | | | | | | **14.60** | | | | | | | | | | | | | | | | |
| | 653 | 651 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.000 | 0.000 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 0.0 | 53.8 | 300 | 300 | CIRCULAR | PVC | - | 1.00 | 96.2 | **0.00%** | 1.37 | 0.00 | 0.00 |
| | 651 | 650 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.000 | 0.000 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 0.0 | 11.0 | 300 | 300 | CIRCULAR | PVC | - | 1.00 | 96.2 | **0.00%** | 1.37 | 0.00 | 0.00 |
| ST650A, ST650B | 650 | 649 | 0.70 | 0.00 | 0.00 | 0.58 | 0.70 | 0.403 | 0.403 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 116.6 | 80.9 | 450 | 450 | CIRCULAR | CONCRETE | - | 1.00 | 297.4 | **39.20%** | 1.81 | 1.44 | 0.94 |
| | | | | | | | | | | | | | **10.94** | | | | | | | | | | | | | | | | |
| ST649A | 649 | EX648 | 0.47 | 0.00 | 0.00 | 0.68 | 6.09 | 0.320 | 3.982 | 0.00 | 0.000 | 0.000 | 14.60 | 84.88 | 145.17 | 0.0 | 0.0 | 938.9 | 16.3 | 900 | 900 | CIRCULAR | CONCRETE | - | 0.75 | 1635.6 | **57.41%** | 2.49 | 2.23 | 0.12 |
| ST648A | EX648 | EX647 | 0.10 | 0.00 | 0.00 | 0.52 | 6.19 | 0.050 | 4.032 | 0.00 | 0.000 | 0.000 | 14.72 | 84.47 | 144.47 | 0.0 | 0.0 | 946.1 | 35.9 | 900 | 900 | CIRCULAR | CONCRETE | - | 0.75 | 1635.6 | **57.85%** | 2.49 | 2.23 | 0.27 |
| ST647A | EX647 | EX646 | 0.10 | 0.00 | 0.00 | 0.68 | 6.29 | 0.071 | 4.103 | 0.00 | 0.000 | 0.000 | 14.99 | 83.59 | 142.96 | 0.0 | 0.0 | 952.7 | 114.8 | 975 | 975 | CIRCULAR | CONCRETE | - | 0.75 | 2024.7 | **47.05%** | 2.63 | 2.20 | 0.87 |
| ST646A | EX646 | EX643 | 0.33 | 0.00 | 0.00 | 0.69 | 6.63 | 0.230 | 4.333 | 0.00 | 0.000 | 0.000 | 15.86 | 80.89 | 138.29 | 0.0 | 0.0 | 973.5 | 26.4 | 975 | 975 | CIRCULAR | CONCRETE | - | 0.45 | 1568.3 | **62.07%** | 2.03 | 1.86 | 0.24 |
| | | | | | | | | | | | | | **16.09** | | | | | | | | | | | | | | | | |
| ST643A | EX643 | EX640 | 0.17 | 0.00 | 0.00 | 0.72 | 11.44 | 0.119 | 6.643 | 0.00 | 0.000 | 0.000 | 16.09 | 80.18 | 137.07 | 0.0 | 0.0 | 1479.5 | 71.8 | 975 | 975 | CIRCULAR | CONCRETE | - | 0.50 | 1653.2 | **89.49%** | 2.15 | 2.18 | 0.55 |
| | | | | | | | | | | | | | **16.64** | | | | | | | | | | | | | | | | |
| | EX642 | EX641 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.000 | 0.000 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 0.0 | 10.6 | 300 | 300 | CIRCULAR | PVC | - | 0.65 | 77.5 | **0.00%** | 1.10 | 0.00 | 0.00 |
| ST641A | EX641 | EX640 | 0.27 | 0.00 | 0.00 | 0.69 | 0.27 | 0.186 | 0.186 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 53.9 | 72.2 | 300 | 300 | CIRCULAR | PVC | - | 0.65 | 77.5 | **69.52%** | 1.10 | 1.04 | 1.16 |
| | | | | | | | | | | | | | **11.16** | | | | | | | | | | | | | | | | |
| ST640A | EX640 | EX637 | 0.40 | 0.00 | 0.00 | 0.72 | 12.11 | 0.286 | 7.114 | 0.00 | 0.000 | 0.000 | 16.64 | 78.60 | 134.34 | 0.0 | 0.0 | 1553.3 | 67.7 | 1350 | 1350 | CIRCULAR | CONCRETE | - | 0.10 | 1760.8 | **88.22%** | 1.19 | 1.21 | 0.93 |
| | | | | | | | | | | | | | **17.57** | | | | | | | | | | | | | | | | |
| | EX642 | EX639 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.000 | 0.000 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 0.0 | 52.7 | 300 | 300 | CIRCULAR | PVC | - | 0.65 | 77.5 | **0.00%** | 1.10 | 0.00 | 0.00 |
| | EX639 | EX638 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.000 | 0.000 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 0.0 | 10.6 | 300 | 300 | CIRCULAR | PVC | - | 0.65 | 77.5 | **0.00%** | 1.10 | 0.00 | 0.00 |
| ST638B, ST638A | EX638 | EX637 | 0.51 | 0.00 | 0.00 | 0.70 | 0.51 | 0.357 | 0.357 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 103.3 | 72.3 | 450 | 450 | CIRCULAR | CONCRETE | - | 0.30 | 162.6 | **63.55%** | 0.99 | 0.91 | 1.32 |
| | | | | | | | | | | | | | **11.32** | | | | | | | | | | | | | | | | |
| ST637B, ST637A, ST637C | EX637 | EX627 | 0.79 | 0.00 | 0.00 | 0.58 | 13.42 | 0.457 | 7.928 | 0.00 | 0.000 | 0.000 | 17.57 | 76.07 | 129.98 | 0.0 | 0.0 | 1675.2 | 79.4 | 1500 | 1500 | CIRCULAR | CONCRETE | - | 0.17 | 2996.1 | **55.91%** | 1.64 | 1.46 | 0.91 |
| | | | | | | | | | | | | | **18.48** | | | | | | | | | | | | | | | | |
| ST627A | EX627 | EX624 | 0.24 | 0.00 | 0.00 | 0.71 | 29.47 | 0.168 | 16.806 | 0.00 | 0.000 | 0.000 | 21.69 | 66.75 | 113.93 | 0.0 | 0.0 | 3116.4 | 66.8 | 1650 | 1650 | CIRCULAR | CONCRETE | - | 0.15 | 3679.0 | **84.71%** | 1.67 | 1.67 | 0.67 |
| | | | | | | | | | | | | | **22.35** | | | | | | | | | | | | | | | | |
| ST624AA | EX624A | EX624 | 2.07 | 0.00 | 0.00 | 0.70 | 2.07 | 1.452 | 1.452 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 420.3 | 9.2 | 600 | 600 | CIRCULAR | CONCRETE | - | 1.96 | 896.0 | **46.91%** | 3.07 | 2.57 | 0.06 |
| | | | | | | | | | | | | | **10.06** | | | | | | | | | | | | | | | | |
| ST624A | EX624 | EX613 | 0.31 | 0.00 | 0.00 | 0.67 | 31.86 | 0.207 | 18.466 | 0.00 | 0.000 | 0.000 | 22.35 | 65.48 | 111.73 | 0.0 | 0.0 | 3358.5 | 95.3 | 1650 | 1650 | CIRCULAR | CONCRETE | - | 0.26 | 4870.9 | **68.95%** | 2.21 | 2.08 | 0.76 |
| | | | | | | | | | | | | | **23.12** | | | | | | | | | | | | | | | | |
| | EX617 | EX616 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.000 | 0.000 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 0.0 | 74.7 | 375 | 375 | CIRCULAR | PVC | - | 0.25 | 87.7 | **0.00%** | 0.79 | 0.00 | 0.00 |
| ST616A | EX616 | EX615 | 0.51 | 0.00 | 0.00 | 0.76 | 0.51 | 0.386 | 0.386 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 111.9 | 58.4 | 525 | 525 | CIRCULAR | CONCRETE | - | 0.25 | 224.3 | **49.86%** | 1.00 | 0.86 | 1.13 |
| ST615A | EX615 | EX614 | 0.25 | 0.00 | 0.00 | 0.75 | 0.76 | 0.191 | 0.577 | 0.00 | 0.000 | 0.000 | 11.13 | 98.57 | 168.82 | 0.0 | 0.0 | 158.0 | 84.5 | 525 | 525 | CIRCULAR | CONCRETE | - | 0.30 | 245.7 | **64.29%** | 1.10 | 1.01 | 1.39 |
| | | | | | | | | | | | | | **12.52** | | | | | | | | | | | | | | | | |
| ST620A, ST620B | EX620 | EX619 | 0.39 | 0.00 | 0.00 | 0.76 | 0.39 | 0.300 | 0.300 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 86.8 | 117.2 | 375 | 375 | CIRCULAR | PVC | - | 0.50 | 124.0 | **69.99%** | 1.12 | 1.07 | 1.83 |
| | | | | | | | | | | | | | **11.83** | | | | | | | | | | | | | | | | |

Stantec

**HALF MOON BAY SOUTH SUBDIVISION - PHASE 4**

DATE: 26-Aug-2015
REVISION: 2
DESIGNED BY: DT
CHECKED BY:

**FILE NUMBER: 1604-00743**

# STORM SEWER DESIGN SHEET
**(City of Ottawa)**

DESIGN PARAMETERS

$I = a / (t+b)^c$ (As per City of Ottawa Guidelines, 2012)

| | 1:5 yr | 1:100 yr |
|---|---|---|
| a = | 998.071 | 1735.688 |
| b = | 6.053 | 6.014 |
| c = | 0.814 | 0.820 |

MANNING'S n = 0.013 BEDDING CLASS = B
MINIMUM COVER: 2.00 m
TIME OF ENTRY 10 min

| LOCATION | | | DRAINAGE AREA | | | | | | | | | | | | | | | PIPE SELECTION | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| AREA ID NUMBER | FROM M.H. | TO M.H. | AREA (5-YEAR) (ha) | AREA (100-YEAR) (ha) | AREA (ROOF) (ha) | C (-) | ACCUM. AREA (5YR) (ha) | A x C (5-YEAR) (ha) | ACCUM. AxC (5YR) (ha) | ACCUM. AREA (100YR (ha) | A x C (100-YEAR) (ha) | ACCUM. AxC (100YR) (ha) | T of C (min) | $I_{5\text{-YEAR}}$ (mm/h) | $I_{10\text{-YEAR}}$ (mm/h) | $Q_{CONTROL}$ (NOTE 1) (L/s) | ACCUM. $Q_{CONTROL}$ (L/s) | $Q_{ACT}$ (CIA/360) (L/s) | LENGTH (m) | PIPE WIDTH OR DIAMETEI (mm) | PIPE HEIGHT (mm) | PIPE SHAPE (-) | MATERIAL (-) | CLASS (-) | SLOPE % | $Q_{CAP}$ (FULL) (L/s) | % FULL (-) | VEL. (FULL) (m/s) | VEL. (ACT) (m/s) | TIME OF FLOW (min) |
| ST623A, ST623B | EX623 | EX622 | 1.10 | 0.00 | 0.00 | 0.66 | 1.10 | 0.729 | 0.729 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 210.9 | 116.2 | 525 | 525 | CIRCULAR | CONCRETE | - | 0.35 | 265.4 | **79.46%** | 1.19 | 1.17 | 1.66 |
| | EX622 | EX621 | 0.00 | 0.00 | 0.00 | 0.00 | 1.10 | 0.000 | 0.729 | 0.00 | 0.000 | 0.000 | 11.66 | 96.19 | 164.72 | 0.0 | 0.0 | 194.7 | 8.5 | 525 | 525 | CIRCULAR | CONCRETE | - | 0.30 | 245.7 | **79.23%** | 1.10 | 1.08 | 0.13 |
| ST621A | EX621 | EX619 | 0.36 | 0.00 | 0.00 | 0.75 | 1.47 | 0.273 | 1.002 | 0.00 | 0.000 | 0.000 | 11.79 | 95.62 | 163.73 | 0.0 | 0.0 | 266.1 | 42.0 | 675 | 675 | CIRCULAR | CONCRETE | - | 0.20 | 392.2 | **67.85%** | 1.06 | 0.99 | 0.70 |
| | | | | | | | | | | | | | **12.49** | | | | | | | | | | | | | | | | | |
| ST619A, ST619B | EX619 | EX614 | 0.49 | 0.00 | 0.00 | 0.57 | 2.35 | 0.279 | 1.581 | 0.00 | 0.000 | 0.000 | 12.49 | 92.65 | 158.60 | 0.0 | 0.0 | 406.9 | 46.5 | 750 | 750 | CIRCULAR | CONCRETE | - | 0.20 | 519.4 | **78.34%** | 1.14 | 1.12 | 0.69 |
| | | | | | | | | | | | | | **13.19** | | | | | | | | | | | | | | | | | |
| ST614B, ST614C, ST614A | EX614 | EX613 | 0.39 | 0.00 | 0.00 | 0.74 | 3.50 | 0.287 | 2.445 | 0.00 | 0.000 | 0.000 | 13.19 | 89.92 | 153.88 | 0.0 | 0.0 | 610.7 | 76.9 | 900 | 900 | CIRCULAR | CONCRETE | - | 0.20 | 848.6 | **71.96%** | 1.29 | 1.23 | 1.04 |
| | | | | | | | | | | | | | **14.22** | | | | | | | | | | | | | | | | | |
| ST613A, ST613B | EX613 | EX602 | 1.01 | 0.00 | 0.00 | 0.62 | 36.37 | 0.630 | 21.541 | 0.00 | 0.000 | 0.000 | 23.12 | 64.08 | 109.32 | 0.0 | 0.0 | 3834.2 | 68.0 | 1800 | 1800 | CIRCULAR | CONCRETE | - | 0.32 | 6820.9 | **56.21%** | 2.60 | 2.30 | 0.49 |
| | | | | | | | | | | | | | **23.61** | | | | | | | | | | | | | | | | | |
| ST611A | EX611 | EX610 | 0.38 | 0.00 | 0.00 | 0.50 | 0.38 | 0.189 | 0.189 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 54.6 | 81.6 | 450 | 450 | CIRCULAR | CONCRETE | - | 0.20 | 133.3 | **40.95%** | 0.81 | 0.65 | 2.08 |
| | EX610 | EX609 | 0.00 | 0.00 | 0.00 | 0.00 | 0.38 | 0.000 | 0.189 | 0.00 | 0.000 | 0.000 | 12.08 | 94.35 | 161.53 | 0.0 | 0.0 | 49.4 | 10.6 | 525 | 525 | CIRCULAR | CONCRETE | - | 0.20 | 199.6 | **24.77%** | 0.89 | 0.62 | 0.29 |
| ST609A, ST609B | EX609 | EX608 | 0.42 | 0.00 | 0.00 | 0.63 | 0.79 | 0.263 | 0.452 | 0.00 | 0.000 | 0.000 | 12.37 | 93.15 | 159.46 | 0.0 | 0.0 | 116.9 | 40.5 | 525 | 525 | CIRCULAR | CONCRETE | - | 0.20 | 200.6 | **58.24%** | 0.90 | 0.80 | 0.84 |
| | | | | | | | | | | | | | **13.21** | | | | | | | | | | | | | | | | | |
| ST612A | EX612 | EX608 | 0.26 | 0.00 | 0.00 | 0.77 | 0.26 | 0.201 | 0.201 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 58.2 | 90.6 | 300 | 300 | CIRCULAR | PVC | - | 0.65 | 77.5 | **75.03%** | 1.10 | 1.07 | 1.42 |
| | | | | | | | | | | | | | **11.42** | | | | | | | | | | | | | | | | | |
| 608D, ST608B, ST608C, ST60 | EX608 | EX607 | 0.91 | 0.00 | 0.00 | 0.64 | 1.96 | 0.583 | 1.236 | 0.00 | 0.000 | 0.000 | 13.21 | 89.83 | 153.72 | 0.0 | 0.0 | 308.3 | 106.8 | 675 | 675 | CIRCULAR | CONCRETE | - | 0.20 | 391.7 | **78.72%** | 1.06 | 1.04 | 1.71 |
| | EX607 | EX606 | 0.00 | 0.00 | 0.00 | 0.00 | 1.96 | 0.000 | 1.236 | 0.00 | 0.000 | 0.000 | 14.92 | 83.81 | 143.32 | 0.0 | 0.0 | 287.6 | 10.4 | 675 | 675 | CIRCULAR | CONCRETE | - | 0.20 | 392.1 | **73.35%** | 1.06 | 1.02 | 0.17 |
| ST606A, ST606B | EX606 | EX605 | 0.47 | 0.00 | 0.00 | 0.63 | 2.43 | 0.293 | 1.529 | 0.00 | 0.000 | 0.000 | 15.09 | 83.26 | 142.38 | 0.0 | 0.0 | 353.5 | 92.1 | 825 | 825 | CIRCULAR | CONCRETE | - | 0.20 | 672.2 | **52.60%** | 1.22 | 1.06 | 1.45 |
| ST605A | EX605 | EX604 | 0.50 | 0.00 | 0.00 | 0.75 | 2.93 | 0.376 | 1.905 | 0.00 | 0.000 | 0.000 | 16.54 | 78.89 | 134.84 | 0.0 | 0.0 | 417.5 | 88.7 | 825 | 825 | CIRCULAR | CONCRETE | - | 0.20 | 669.7 | **62.33%** | 1.21 | 1.11 | 1.33 |
| ST604A | EX604 | EX602 | 0.42 | 0.00 | 0.00 | 0.75 | 3.35 | 0.312 | 2.217 | 0.00 | 0.000 | 0.000 | 17.87 | 75.30 | 128.65 | 0.0 | 0.0 | 463.7 | 119.6 | 825 | 825 | CIRCULAR | CONCRETE | - | 0.20 | 670.8 | **69.13%** | 1.22 | 1.15 | 1.74 |
| | | | | | | | | | | | | | **19.61** | | | | | | | | | | | | | | | | | |
| ST602A | EX602 | EX601 | 0.26 | 0.00 | 0.00 | 0.51 | 41.46 | 0.134 | 24.612 | 0.00 | 0.000 | 0.000 | 23.61 | 63.21 | 107.83 | 0.0 | 0.0 | 4321.5 | 31.5 | 1800 | 1800 | CIRCULAR | CONCRETE | - | 0.16 | 4778.3 | **90.44%** | 1.82 | 1.86 | 0.28 |
| | | | | | | | | | | | | | **23.89** | | | | | | | 1800 | 1800 | | | | | | | | | |
| | EX509B | EX509 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.000 | 0.000 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 0.0 | 28.3 | 300 | 300 | CIRCULAR | PVC | - | 0.18 | 40.4 | **0.00%** | 0.57 | 0.00 | 0.00 |
| | | | | | | | | | | | | | **10.00** | | | | | | | | | | | | | | | | | |
| ST520A | EX520 | EX509 | 0.62 | 0.00 | 0.00 | 0.75 | 0.62 | 0.463 | 0.463 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 134.1 | 108.6 | 450 | 450 | CIRCULAR | CONCRETE | - | 0.32 | 168.8 | **79.40%** | 1.03 | 1.01 | 1.79 |
| | | | | | | | | | | | | | **11.79** | | | | | | | | | | | | | | | | | |
| ST509A | EX509 | EX508 | 0.47 | 0.00 | 0.00 | 0.73 | 1.09 | 0.343 | 0.807 | 0.00 | 0.000 | 0.000 | 11.79 | 95.62 | 163.73 | 0.0 | 0.0 | 214.2 | 43.4 | 750 | 750 | CIRCULAR | CONCRETE | - | 0.44 | 768.5 | **27.88%** | 1.69 | 1.21 | 0.60 |
| | | | | | | | | | | | | | **12.38** | | | | | | | | | | | | | | | | | |
| ST514A | EX514 | EX513 | 0.21 | 0.00 | 0.00 | 0.67 | 0.21 | 0.142 | 0.142 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 41.0 | 9.3 | 450 | 450 | CIRCULAR | CONCRETE | - | 0.22 | 138.3 | **29.63%** | 0.84 | 0.62 | 0.25 |
| ST513A | EX513 | EX512 | 0.31 | 0.00 | 0.00 | 0.78 | 0.52 | 0.244 | 0.385 | 0.00 | 0.000 | 0.000 | 10.25 | 102.89 | 176.30 | 0.0 | 0.0 | 110.1 | 82.9 | 450 | 450 | CIRCULAR | CONCRETE | - | 0.24 | 146.1 | **75.38%** | 0.89 | 0.86 | 1.61 |
| ST512A | EX512 | EX511 | 0.40 | 0.00 | 0.00 | 0.78 | 0.92 | 0.311 | 0.696 | 0.00 | 0.000 | 0.000 | 11.86 | 95.32 | 163.21 | 0.0 | 0.0 | 184.3 | 82.9 | 525 | 525 | CIRCULAR | CONCRETE | - | 0.37 | 274.3 | **67.17%** | 1.23 | 1.15 | 1.20 |
| | | | | | | | | | | | | | **13.06** | | | | | | | | | | | | | | | | | |
| | EX520 | EX519 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.000 | 0.000 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 0.0 | 8.5 | 300 | 300 | CIRCULAR | PVC | - | 0.35 | 57.2 | **0.00%** | 0.81 | 0.00 | 0.00 |
| | EX519 | EX516 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.000 | 0.000 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 0.0 | 37.4 | 300 | 300 | CIRCULAR | PVC | - | 0.21 | 44.5 | **0.00%** | 0.63 | 0.00 | 0.00 |
| | | | | | | | | | | | | | **10.00** | | | | | | | | | | | | | | | | | |
| ST518A | EX518 | EX517 | 0.36 | 0.00 | 0.00 | 0.75 | 0.36 | 0.269 | 0.269 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 77.9 | 88.0 | 375 | 375 | CIRCULAR | PVC | - | 0.30 | 95.3 | **81.72%** | 0.86 | 0.86 | 1.71 |
| ST517A | EX517 | EX516 | 0.22 | 0.00 | 0.00 | 0.75 | 0.57 | 0.162 | 0.431 | 0.00 | 0.000 | 0.000 | 11.71 | 95.93 | 164.27 | 0.0 | 0.0 | 114.8 | 79.8 | 375 | 375 | CIRCULAR | PVC | - | 0.45 | 117.8 | **97.52%** | 1.07 | 1.11 | 1.19 |
| | | | | | | | | | | | | | **12.91** | | | | | | | | | | | | | | | | | |
| ST523A | EX523 | EX522 | 0.28 | 0.00 | 0.00 | 0.70 | 0.28 | 0.194 | 0.194 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 56.2 | 55.3 | 300 | 300 | CIRCULAR | PVC | - | 0.45 | 64.6 | **86.98%** | 0.92 | 0.93 | 0.99 |
| ST522A, ST522B | EX522 | EX521 | 0.75 | 0.00 | 0.00 | 0.63 | 1.03 | 0.472 | 0.667 | 0.00 | 0.000 | 0.000 | 10.99 | 99.23 | 169.97 | 0.0 | 0.0 | 183.8 | 102.2 | 450 | 450 | CIRCULAR | CONCRETE | - | 0.43 | 195.2 | **94.14%** | 1.19 | 1.23 | 1.39 |
| | | | | | | | | | | | | | **12.38** | | | | | | | | | | | | | | | | | |
| ST534B, ST534A | EX534 | EX533 | 0.74 | 0.00 | 0.00 | 0.58 | 0.74 | 0.430 | 0.430 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 124.5 | 95.1 | 450 | 450 | CIRCULAR | CONCRETE | - | 0.40 | 188.1 | **66.18%** | 1.15 | 1.06 | 1.49 |
| | EX533 | EX532 | 0.00 | 0.00 | 0.00 | 0.00 | 0.74 | 0.000 | 0.430 | 0.00 | 0.000 | 0.000 | 11.49 | 96.94 | 166.01 | 0.0 | 0.0 | 115.8 | 10.6 | 525 | 525 | CIRCULAR | CONCRETE | - | 0.20 | 200.6 | **57.73%** | 0.90 | 0.80 | 0.22 |
| ST532B, ST532A | EX532 | EX531 | 0.77 | 0.00 | 0.00 | 0.59 | 1.51 | 0.457 | 0.887 | 0.00 | 0.000 | 0.000 | 11.71 | 95.96 | 164.31 | 0.0 | 0.0 | 236.4 | 60.5 | 600 | 600 | CIRCULAR | CONCRETE | - | 0.20 | 286.5 | **82.51%** | 0.98 | 0.98 | 1.03 |
| | EX531 | EX530 | 0.00 | 0.00 | 0.00 | 0.00 | 1.51 | 0.000 | 0.887 | 0.00 | 0.000 | 0.000 | 12.74 | 91.65 | 156.86 | 0.0 | 0.0 | 225.7 | 10.6 | 675 | 675 | CIRCULAR | CONCRETE | - | 0.15 | 339.6 | **66.47%** | 0.92 | 0.85 | 0.21 |
| ST530A | EX530 | EX529 | 0.37 | 0.00 | 0.00 | 0.72 | 1.89 | 0.270 | 1.156 | 0.00 | 0.000 | 0.000 | 12.95 | 90.84 | 155.46 | 0.0 | 0.0 | 291.8 | 71.7 | 750 | 750 | CIRCULAR | CONCRETE | - | 0.15 | 449.8 | **64.87%** | 0.99 | 0.91 | 1.31 |
| ST529A | EX529 | EX525 | 0.32 | 0.00 | 0.00 | 0.51 | 2.21 | 0.163 | 1.319 | 0.00 | 0.000 | 0.000 | 14.26 | 86.02 | 147.15 | 0.0 | 0.0 | 315.3 | 52.8 | 750 | 750 | CIRCULAR | CONCRETE | - | 0.15 | 449.8 | **70.09%** | 0.99 | 0.94 | 0.94 |
| | | | | | | | | | | | | | **15.20** | | | | | | | | | | | | | | | | | |
| ST528A | EX528 | EX527 | 0.22 | 0.00 | 0.00 | 0.70 | 0.22 | 0.156 | 0.156 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 45.2 | 11.4 | 300 | 300 | CIRCULAR | PVC | - | 0.65 | 77.5 | **58.36%** | 1.10 | 0.98 | 0.19 |
| | EX527 | EX526 | 0.00 | 0.00 | 0.00 | 0.00 | 0.22 | 0.000 | 0.156 | 0.00 | 0.000 | 0.000 | 10.19 | 103.19 | 176.82 | 0.0 | 0.0 | 44.8 | 48.9 | 300 | 300 | CIRCULAR | PVC | - | 0.40 | 60.8 | **73.68%** | 0.86 | 0.83 | 0.98 |
| ST526A, ST526B | EX526 | EX525 | 0.69 | 0.00 | 0.00 | 0.61 | 0.91 | 0.417 | 0.574 | 0.00 | 0.000 | 0.000 | 11.17 | 98.38 | 168.50 | 0.0 | 0.0 | 156.7 | 96.1 | 450 | 450 | CIRCULAR | CONCRETE | - | 0.40 | 188.1 | **83.32%** | 1.15 | 1.14 | 1.40 |
| | | | | | | | | | | | | | **12.58** | | | | | | | | | | | | | | | | | |

Stantec

**HALF MOON BAY SOUTH SUBDIVISION - PHASE 4**

DATE: 26-Aug-2015
REVISION: 2
DESIGNED BY: DT
CHECKED BY:

**FILE NUMBER: 1604-00743**

# STORM SEWER DESIGN SHEET
**(City of Ottawa)**

DESIGN PARAMETERS

$I = a / (t+b)^c$ (As per City of Ottawa Guidelines, 2012)

| | 1:5 yr | 1:100 yr |
|---|---|---|
| a = | 998.071 | 1735.688 |
| b = | 6.053 | 6.014 |
| c = | 0.814 | 0.820 |

MANNING'S n = 0.013 BEDDING CLASS = B
MINIMUM COVER: 2.00 m
TIME OF ENTRY 10 min

| LOCATION | | | DRAINAGE AREA | | | | | | | | | | | | | | | PIPE SELECTION | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| AREA ID NUMBER | FROM M.H. | TO M.H. | AREA (5-YEAR) (ha) | AREA (100-YEAR) (ha) | AREA (ROOF) (ha) | C (-) | ACCUM. AREA (5YR) (ha) | A x C (5-YEAR) (ha) | ACCUM. AxC (5YR) (ha) | ACCUM. AREA (100YR (ha) | A x C (100-YEAR) (ha) | ACCUM. AxC (100YR) (ha) | T of C (min) | $I_{5\text{-YEAR}}$ (mm/h) | $I_{10\text{-YEAR}}$ (mm/h) | $Q_{CONTROL}$ (NOTE 1) (L/s) | ACCUM. $Q_{CONTROL}$ (L/s) | $Q_{ACT}$ (CIA/360) (L/s) | LENGTH (m) | PIPE WIDTH OR DIAMETEI (mm) | PIPE HEIGHT (mm) | PIPE SHAPE (-) | MATERIAL (-) | CLASS (-) | SLOPE % | $Q_{CAP}$ (FULL) (L/s) | % FULL (-) | VEL. (FULL) (m/s) | VEL. (ACT) (m/s) | TIME OF FLOW (min) |
| ST537A | EX537 | EX536 | 0.26 | 0.00 | 0.00 | 0.72 | 0.26 | 0.186 | 0.186 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 54.0 | 91.2 | 300 | 300 | CIRCULAR | PVC | - | 0.50 | 68.0 | **79.36%** | 0.97 | 0.95 | 1.60 |
| ST536A | EX536 | EX535 | 0.38 | 0.00 | 0.00 | 0.51 | 0.64 | 0.195 | 0.381 | 0.00 | 0.000 | 0.000 | 11.60 | 96.45 | 165.17 | 0.0 | 0.0 | 102.1 | 48.4 | 450 | 450 | CIRCULAR | CONCRETE | - | 0.50 | 210.3 | **48.57%** | 1.28 | 1.08 | 0.74 |
| | | | | | | | | | | | | | **12.34** | | | | | | | | | | | | | | | | |
| ST541A | EX541 | EX540 | 0.22 | 0.00 | 0.00 | 0.71 | 0.22 | 0.159 | 0.159 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 45.9 | 63.2 | 300 | 300 | CIRCULAR | PVC | - | 1.50 | 117.8 | **38.99%** | 1.67 | 1.33 | 0.79 |
| | | | | | | | | | | | | | **10.79** | | | | | | | | | | | | | | | | |
| ST546B, ST546A | EX546 | EX545 | 0.74 | 0.00 | 0.00 | 0.54 | 0.74 | 0.399 | 0.399 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 115.5 | 112.3 | 375 | 375 | CIRCULAR | PVC | - | 1.20 | 192.0 | **60.17%** | 1.74 | 1.57 | 1.19 |
| | EX545 | EX544 | 0.00 | 0.00 | 0.00 | 0.00 | 0.74 | 0.000 | 0.399 | 0.00 | 0.000 | 0.000 | 11.19 | 98.28 | 168.33 | 0.0 | 0.0 | 109.0 | 10.6 | 375 | 375 | CIRCULAR | PVC | - | 0.80 | 156.8 | **69.51%** | 1.42 | 1.34 | 0.13 |
| ST544A, ST544B | EX544 | EX543 | 0.65 | 0.00 | 0.00 | 0.71 | 1.39 | 0.464 | 0.864 | 0.00 | 0.000 | 0.000 | 11.33 | 97.67 | 167.28 | 0.0 | 0.0 | 234.3 | 103.5 | 525 | 525 | CIRCULAR | CONCRETE | - | 0.80 | 401.3 | **58.38%** | 1.80 | 1.61 | 1.07 |
| | EX543 | EX542 | 0.00 | 0.00 | 0.00 | 0.00 | 1.39 | 0.000 | 0.864 | 0.00 | 0.000 | 0.000 | 12.40 | 93.02 | 159.23 | 0.0 | 0.0 | 223.1 | 10.6 | 525 | 525 | CIRCULAR | CONCRETE | - | 0.80 | 401.3 | **55.60%** | 1.80 | 1.59 | 0.11 |
| ST542A | EX542 | EX540 | 0.23 | 0.00 | 0.00 | 0.70 | 1.62 | 0.162 | 1.026 | 0.00 | 0.000 | 0.000 | 12.51 | 92.56 | 158.45 | 0.0 | 0.0 | 263.8 | 67.5 | 675 | 675 | CIRCULAR | CONCRETE | - | 0.55 | 651.5 | **40.48%** | 1.76 | 1.42 | 0.79 |
| | | | | | | | | | | | | | **13.30** | | | | | | | | | | | | | | | | |
| ST540A | EX540 | EX539 | 0.18 | 0.00 | 0.00 | 0.72 | 2.03 | 0.131 | 1.316 | 0.00 | 0.000 | 0.000 | 13.30 | 89.47 | 153.10 | 0.0 | 0.0 | 326.9 | 97.6 | 750 | 750 | CIRCULAR | CONCRETE | - | 0.30 | 636.1 | **51.39%** | 1.39 | 1.20 | 1.35 |
| | EX539 | EX538 | 0.00 | 0.00 | 0.00 | 0.00 | 2.03 | 0.000 | 1.316 | 0.00 | 0.000 | 0.000 | 14.66 | 84.68 | 144.84 | 0.0 | 0.0 | 309.5 | 42.3 | 750 | 750 | CIRCULAR | CONCRETE | - | 0.30 | 636.1 | **48.65%** | 1.39 | 1.18 | 0.60 |
| | | | | | | | | | | | | | **15.25** | | | | | | | | | | | | | | | | |
| | EX553 | EX552 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.000 | 0.000 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 0.0 | 11.8 | 300 | 300 | CIRCULAR | PVC | - | 0.75 | 83.3 | **0.00%** | 1.18 | 0.00 | 0.00 |
| ST552A | EX552 | EX551 | 0.25 | 0.00 | 0.00 | 0.71 | 0.25 | 0.176 | 0.176 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 50.9 | 74.7 | 300 | 300 | CIRCULAR | PVC | - | 0.75 | 83.3 | **61.08%** | 1.18 | 1.07 | 1.16 |
| | | | | | | | | | | | | | **11.16** | | | | | | | | | | | | | | | | |
| ST555B, ST555A | EX555 | EX554 | 0.21 | 0.00 | 0.00 | 0.62 | 0.21 | 0.131 | 0.131 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 38.0 | 71.2 | 300 | 300 | CIRCULAR | PVC | - | 0.45 | 64.5 | **58.90%** | 0.92 | 0.83 | 1.44 |
| | | | | | | | | | | | | | **11.44** | | | | | | | | | | | | | | | | |
| ST563A | 563 | 562 | 0.39 | 0.00 | 0.00 | 0.65 | 0.39 | 0.251 | 0.251 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 72.6 | 49.2 | 375 | 375 | CIRCULAR | PVC | - | 0.65 | 141.4 | **51.39%** | 1.28 | 1.10 | 0.74 |
| | 562 | 561 | 0.00 | 0.00 | 0.00 | 0.00 | 0.39 | 0.000 | 0.251 | 0.00 | 0.000 | 0.000 | 10.74 | 100.43 | 172.04 | 0.0 | 0.0 | 70.0 | 11.0 | 375 | 375 | CIRCULAR | PVC | - | 0.65 | 140.9 | **49.69%** | 1.28 | 1.09 | 0.17 |
| ST561A | 561 | 560 | 0.13 | 0.00 | 0.00 | 0.71 | 0.52 | 0.094 | 0.345 | 0.00 | 0.000 | 0.000 | 10.91 | 99.62 | 170.64 | 0.0 | 0.0 | 95.6 | 53.3 | 375 | 375 | CIRCULAR | PVC | - | 0.50 | 123.9 | **77.13%** | 1.12 | 1.09 | 0.81 |
| | | | | | | | | | | | | | **11.72** | | | | | | | | | | | | | | | | |
| | 565 | 564 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.000 | 0.000 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 0.0 | 48.9 | 300 | 300 | CIRCULAR | PVC | - | 0.65 | 77.5 | **0.00%** | 1.10 | 0.00 | 0.00 |
| | | | | | | | | | | | | | **10.00** | | | | | | | | | | | | | | | | |
| ST566A | 566 | 564 | 0.30 | 0.00 | 0.00 | 0.70 | 0.30 | 0.208 | 0.208 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 60.2 | 69.0 | 300 | 300 | CIRCULAR | PVC | - | 0.65 | 77.5 | **77.60%** | 1.10 | 1.07 | 1.07 |
| | | | | | | | | | | | | | **11.07** | | | | | | | | | | | | | | | | |
| ST564A, ST564B | 564 | 560 | 0.51 | 0.00 | 0.00 | 0.59 | 0.81 | 0.301 | 0.509 | 0.00 | 0.000 | 0.000 | 11.07 | 98.85 | 169.31 | 0.0 | 0.0 | 139.7 | 73.6 | 450 | 450 | CIRCULAR | CONCRETE | - | 0.65 | 239.8 | **58.26%** | 1.46 | 1.31 | 0.94 |
| | | | | | | | | | | | | | **12.01** | | | | | | | | | | | | | | | | |
| ST560B, ST560A | 560 | EX559A | 0.31 | 0.00 | 0.00 | 0.62 | 1.64 | 0.190 | 1.045 | 0.00 | 0.000 | 0.000 | 12.01 | 94.64 | 162.04 | 0.0 | 0.0 | 274.6 | 57.8 | 525 | 525 | CIRCULAR | CONCRETE | - | 0.75 | 388.5 | **70.68%** | 1.74 | 1.65 | 0.58 |
| | EX559A | EX559 | 0.00 | 0.00 | 0.00 | 0.00 | 1.64 | 0.000 | 1.045 | 0.00 | 0.000 | 0.000 | 12.60 | 92.22 | 157.86 | 0.0 | 0.0 | 267.6 | 11.1 | 525 | 525 | CIRCULAR | CONCRETE | - | 0.75 | 388.5 | **68.87%** | 1.74 | 1.64 | 0.11 |
| ST559B, ST559C, ST559A | EX559 | EX558 | 0.40 | 0.00 | 0.00 | 0.61 | 2.04 | 0.249 | 1.293 | 0.00 | 0.000 | 0.000 | 12.71 | 91.77 | 157.08 | 0.0 | 0.0 | 329.7 | 64.5 | 600 | 600 | CIRCULAR | CONCRETE | - | 0.75 | 554.7 | **59.43%** | 1.90 | 1.71 | 0.63 |
| | EX558 | EX557 | 0.00 | 0.00 | 0.00 | 0.00 | 2.04 | 0.000 | 1.293 | 0.00 | 0.000 | 0.000 | 13.34 | 89.35 | 152.89 | 0.0 | 0.0 | 321.0 | 10.6 | 600 | 600 | CIRCULAR | CONCRETE | - | 0.75 | 554.8 | **57.86%** | 1.90 | 1.70 | 0.10 |
| ST557B, ST557A | EX557 | EX556 | 0.43 | 0.00 | 0.00 | 0.65 | 2.47 | 0.277 | 1.571 | 0.00 | 0.000 | 0.000 | 13.44 | 88.96 | 152.22 | 0.0 | 0.0 | 388.1 | 65.6 | 600 | 600 | CIRCULAR | CONCRETE | - | 0.75 | 554.7 | **69.96%** | 1.90 | 1.80 | 0.61 |
| ST556A | EX556 | EX554 | 0.49 | 0.00 | 0.00 | 0.69 | 2.96 | 0.339 | 1.910 | 0.00 | 0.000 | 0.000 | 14.05 | 86.77 | 148.44 | 0.0 | 0.0 | 460.4 | 62.5 | 675 | 675 | CIRCULAR | CONCRETE | - | 0.50 | 620.3 | **74.21%** | 1.68 | 1.62 | 0.65 |
| | | | | | | | | | | | | | **14.69** | | | | | | | | | | | | | | | | |
| ST554A, ST554B, ST554C | EX554 | EX551 | 1.27 | 0.00 | 0.00 | 0.54 | 4.45 | 0.691 | 2.733 | 0.00 | 0.000 | 0.000 | 14.69 | 84.57 | 144.64 | 0.0 | 0.0 | 641.9 | 71.9 | 750 | 750 | CIRCULAR | CONCRETE | - | 0.55 | 861.3 | **74.52%** | 1.89 | 1.82 | 0.66 |
| | | | | | | | | | | | | | **15.35** | | | | | | | | | | | | | | | | |
| ST551A | EX551 | EX538 | 0.34 | 0.00 | 0.00 | 0.72 | 5.04 | 0.246 | 3.154 | 0.00 | 0.000 | 0.000 | 15.35 | 82.44 | 140.96 | 0.0 | 0.0 | 722.3 | 50.6 | 975 | 975 | CIRCULAR | CONCRETE | - | 0.15 | 905.5 | **79.77%** | 1.17 | 1.16 | 0.73 |
| | | | | | | | | | | | | | **16.08** | | | | | | | | | | | | | | | | |
| ST538A | EX538 | EX535 | 0.24 | 0.00 | 0.00 | 0.72 | 7.30 | 0.171 | 4.641 | 0.00 | 0.000 | 0.000 | 16.08 | 80.22 | 137.14 | 0.0 | 0.0 | 1034.1 | 68.6 | 1200 | 1200 | CIRCULAR | CONCRETE | - | 0.10 | 1286.2 | **80.40%** | 1.10 | 1.09 | 1.05 |
| | | | | | | | | | | | | | **17.13** | | | | | | | | | | | | | | | | |
| ST535A | EX535 | EX525 | 0.66 | 0.00 | 0.00 | 0.72 | 8.61 | 0.478 | 5.500 | 0.00 | 0.000 | 0.000 | 17.13 | 77.24 | 132.00 | 0.0 | 0.0 | 1180.0 | 75.6 | 1200 | 1200 | CIRCULAR | CONCRETE | - | 0.13 | 1466.5 | **80.46%** | 1.26 | 1.24 | 1.02 |
| | | | | | | | | | | | | | **18.15** | | | | | | | | | | | | | | | | |
| ST525A | EX525 | EX521 | 0.55 | 0.00 | 0.00 | 0.72 | 12.27 | 0.395 | 7.787 | 0.00 | 0.000 | 0.000 | 18.15 | 74.59 | 127.42 | 0.0 | 0.0 | 1613.5 | 73.0 | 1200 | 1200 | CIRCULAR | CONCRETE | - | 0.22 | 1893.0 | **85.23%** | 1.62 | 1.62 | 0.75 |
| | | | | | | | | | | | | | **18.90** | | | | | | | | | | | | | | | | |
| ST521A, ST521B, ST521C | EX521 | EX516 | 0.82 | 0.00 | 0.00 | 0.54 | 14.12 | 0.444 | 8.898 | 0.00 | 0.000 | 0.000 | 18.90 | 72.76 | 124.27 | 0.0 | 0.0 | 1798.4 | 71.0 | 1350 | 1350 | CIRCULAR | CONCRETE | - | 0.13 | 1982.4 | **90.72%** | 1.34 | 1.37 | 0.86 |
| | | | | | | | | | | | | | **19.76** | | | | | | | | | | | | | | | | |
| ST516A | EX516 | EX511 | 0.42 | 0.00 | 0.00 | 0.49 | 15.11 | 0.206 | 9.535 | 0.00 | 0.000 | 0.000 | 19.76 | 70.77 | 120.85 | 0.0 | 0.0 | 1874.6 | 65.0 | 1350 | 1350 | CIRCULAR | CONCRETE | - | 0.12 | 1953.4 | **95.97%** | 1.32 | 1.37 | 0.79 |
| | | | | | | | | | | | | | **20.55** | | | | | | | | | | | | | | | | |
| | EX511 | EX508 | 0.00 | 0.00 | 0.00 | 0.00 | 16.04 | 0.000 | 10.231 | 0.00 | 0.000 | 0.000 | 20.55 | 69.06 | 117.89 | 0.0 | 0.0 | 1962.6 | 49.6 | 1350 | 1350 | CIRCULAR | CONCRETE | - | 0.18 | 2371.8 | **82.75%** | 1.61 | 1.60 | 0.52 |

Stantec

**HALF MOON BAY SOUTH SUBDIVISION - PHASE 4**

DATE: 26-Aug-2015
REVISION: 2
DESIGNED BY: DT
**FILE NUMBER: 1604-00743**
CHECKED BY:

# STORM SEWER DESIGN SHEET
**(City of Ottawa)**

DESIGN PARAMETERS

$I = a / (t+b)^c$ (As per City of Ottawa Guidelines, 2012)

| | 1:5 yr | 1:100 yr |
|---|---|---|
| a = | 998.071 | 1735.688 |
| b = | 6.053 | 6.014 |
| c = | 0.814 | 0.820 |

MANNING'S n = 0.013 BEDDING CLASS = B
MINIMUM COVER: 2.00 m
TIME OF ENTRY 10 min

| LOCATION | | | DRAINAGE AREA | | | | | | | | | | | | | | | PIPE SELECTION | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| AREA ID NUMBER | FROM M.H. | TO M.H. | AREA (5-YEAR) (ha) | AREA (100-YEAR) (ha) | AREA (ROOF) (ha) | C (-) | ACCUM. AREA (5YR) (ha) | A x C (5-YEAR) (ha) | ACCUM. AxC (5YR) (ha) | ACCUM. AREA (100YR (ha) | A x C (100-YEAR) (ha) | ACCUM. AxC (100YR) (ha) | T of C (min) | $I_{5\text{-YEAR}}$ (mm/h) | $I_{10\text{-YEAR}}$ (mm/h) | $Q_{CONTROL}$ (NOTE 1) (L/s) | ACCUM. $Q_{CONTROL}$ (L/s) | $Q_{ACT}$ (CIA/360) (L/s) | LENGTH (m) | PIPE WIDTH OR DIAMETEI (mm) | PIPE HEIGHT (mm) | PIPE SHAPE (-) | MATERIAL (-) | CLASS (-) | SLOPE % | $Q_{CAP}$ (FULL) (L/s) | % FULL (-) | VEL. (FULL) (m/s) | VEL. (ACT) (m/s) | TIME OF FLOW (min) |
| | | | | | | | | | | | | | **21.07** | | | | | | | | | | | | | | | | |
| | EX508 | EX503 | 0.00 | 0.00 | 0.00 | 0.00 | 17.12 | 0.000 | 11.038 | 0.00 | 0.000 | 0.000 | 21.07 | 67.98 | 116.04 | 0.0 | 0.0 | 2084.4 | 51.9 | 1500 | 1500 | CIRCULAR | CONCRETE | - | 0.21 | 3396.7 | **61.37%** | 1.86 | 1.69 | 0.51 |
| | | | | | | | | | | | | | **21.58** | | | | | | | | | | | | | | | | |
| | EX507 | EX506 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.000 | 0.000 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 0.0 | 11.4 | 300 | 300 | CIRCULAR | PVC | - | 0.26 | 49.4 | **0.00%** | 0.70 | 0.00 | 0.00 |
| ST506A | EX506 | EX505 | 0.28 | 0.00 | 0.00 | 0.74 | 0.28 | 0.207 | 0.207 | 0.00 | 0.000 | 0.000 | 10.00 | 104.19 | 178.56 | 0.0 | 0.0 | 60.0 | 120.0 | 300 | 300 | CIRCULAR | PVC | - | 0.39 | 60.2 | **99.66%** | 0.85 | 0.90 | 2.23 |
| | EX505 | EX504 | 0.00 | 0.00 | 0.00 | 0.00 | 0.28 | 0.000 | 0.207 | 0.00 | 0.000 | 0.000 | 12.23 | 93.73 | 160.46 | 0.0 | 0.0 | 53.9 | 8.5 | 300 | 300 | CIRCULAR | PVC | - | 0.24 | 46.6 | **115.66%** | 0.66 | 0.66 | 0.21 |
| ST504A | EX504 | EX503 | 0.40 | 0.00 | 0.00 | 0.74 | 0.68 | 0.293 | 0.500 | 0.00 | 0.000 | 0.000 | 12.44 | 92.85 | 158.94 | 0.0 | 0.0 | 128.9 | 37.4 | 450 | 450 | CIRCULAR | CONCRETE | - | 0.45 | 200.6 | **64.26%** | 1.22 | 1.13 | 0.55 |
| | | | | | | | | | | | | | **13.00** | | | | | | | | | | | | | | | | |
| ST503A | EX503 | EX502 | 0.32 | 0.00 | 0.00 | 0.76 | 18.12 | 0.245 | 11.782 | 0.00 | 0.000 | 0.000 | 21.58 | 66.96 | 114.28 | 0.0 | 0.0 | 2191.5 | 60.5 | 1500 | 1500 | CIRCULAR | CONCRETE | - | 0.21 | 3418.2 | **64.11%** | 1.87 | 1.73 | 0.58 |
| ST502A | EX502 | EX501 | 0.26 | 0.00 | 0.00 | 0.76 | 18.39 | 0.201 | 11.983 | 0.00 | 0.000 | 0.000 | 22.17 | 65.83 | 112.34 | 0.0 | 0.0 | 2191.2 | 77.6 | 1500 | 1500 | CIRCULAR | CONCRETE | - | 0.10 | 2368.4 | **92.52%** | 1.30 | 1.34 | 0.97 |
| | | | | | | | | | | | | | **23.13** | | | | | | | 1500 | 1500 | | | | | | | | |

depths and capture rates for areas tributary to the Corrigan system remain unchanged from that of the interim scenario.

**Table 13: HMBS - Phase 4 - Major and Minor System 5 Year Storm Results**

| Segment Type | Segment ID | Peak Flow ($m^3/s$) | Depth on Segment (cm) | Max. Capture (L/s) | Storage Used ($m^3$) | Static Ponding Depth (cm) | Total Flow Depth (cm) |
|---|---|---|---|---|---|---|---|
| Minor System To Todd Pond | | | | | | | |
| Road | ST604A | 0.111 | 6.31 | 64.0 | 11.5 | 15.0 | 21.3 |
| RY | ST602A | 0.033 | 11.82 | 22.0 | 0.0 | 0.0 | N/A |
| RY | ST613B | 0.065 | 15.58 | 32.0 | 0.0 | 0.0 | N/A |
| Road | ST614A | 0.018 | 3.08 | 18.4 | 0.2 | 12.0 | 3.1 |
| Road | ST616A | 0.144 | 6.66 | 64.0 | 33.1 | 19.0 | 6.7 |
| Road | ST606A | 0.075 | 6.00 | 64.0 | 1.2 | 15.0 | 6.0 |
| Road | ST605A | 0.134 | 7.45 | 86.0 | 19.5 | 24.0 | 7.5 |
| RY | ST606B | 0.019 | 9.78 | 18.7 | 0.0 | 0.0 | N/A |
| RY | ST608C | 0.033 | 11.80 | 32.0 | 0.0 | 0.0 | N/A |
| Road | ST620A | 0.030 | 3.75 | 22.0 | 0.0 | 4.0 | 3.8 |
| Road | ST623A | 0.190 | 7.74 | 140.0 | 18.2 | 22.0 | 7.7 |
| Road | ST614B | 0.053 | 5.18 | 32.0 | 9.6 | 12.0 | 5.2 |
| Road | ST615A | 0.066 | 5.66 | 44.0 | 7.1 | 15.0 | 5.7 |
| Road | ST614C | 0.066 | 5.67 | 32.0 | 0.0 | 5.0 | 5.7 |
| Road | ST619B | 0.032 | 4.33 | 22.0 | 0.0 | 0.0 | 4.3 |
| Road | ST620B | 0.074 | 5.97 | 44.0 | 10.7 | 15.0 | 6.0 |
| Road | ST621A | 0.095 | 6.50 | 64.0 | 9.5 | 15.0 | 6.5 |
| RY | ST619A | 0.060 | 15.16 | 32.0 | 0.0 | 0.0 | N/A |
| RY | ST623B | 0.053 | 14.32 | 32.0 | 0.0 | 0.0 | N/A |
| Road | ST628A | 0.158 | 7.90 | 150.0 | 3.0 | 16.0 | 7.9 |
| Road | ST637A | 0.086 | 5.48 | 85.9 | 0.4 | 30.0 | 5.5 |
| Road | ST640A | 0.106 | 6.22 | 105.5 | 0.4 | 10.0 | 6.2 |
| Road | ST612A | 0.070 | 5.82 | 64.0 | 0.3 | 5.0 | 5.8 |
| Road | ST643A | 0.054 | 4.80 | 32.0 | 0.0 | 0.0 | 4.8 |
| Park | ST662AA | 0.015 | 0.46 | 8.7 | 0.0 | - | - |
| Road | ST662A | 0.052 | 4.42 | 52.0 | 0.0 | 0.0 | 4.4 |
| Road | ST663A | 0.058 | 4.59 | 57.3 | 0.2 | 5.0 | 4.6 |
| RY | ST637B | 0.053 | 14.34 | 42.0 | 0.0 | 0.0 | 14.3 |
| Road | ST609A | 0.065 | 5.63 | 54.0 | 2.0 | 15.0 | 5.6 |
| RY | ST652B | 0.017 | 9.26 | 17.0 | 0.0 | 0.0 | 9.3 |
| Road | ST652A | 0.084 | 5.22 | 83.6 | 0.1 | 3.0 | 5.2 |
| Road | ST638A | 0.024 | 3.82 | 22.0 | 0.0 | 9.0 | 3.8 |

| Segment Type | Segment ID | Peak Flow ($m^3/s$) | Depth on Segment (cm) | Max. Capture (L/s) | Storage Used ($m^3$) | Static Ponding Depth (cm) | Total Flow Depth (cm) |
|---|---|---|---|---|---|---|---|
| Road | ST608A | 0.098 | 6.06 | 76.0 | 4.8 | 19.0 | 6.1 |
| RY | ST608D | 0.033 | 4.41 | 32.0 | 0.1 | 5.0 | 4.4 |
| RY | ST608B | 0.020 | 10.06 | 19.9 | 0.0 | 0.0 | 10.1 |
| RY | ST609B | 0.017 | 9.34 | 17.3 | 0.0 | 0.0 | 9.3 |
| Road | ST647A | 0.024 | 3.14 | 24.1 | 0.0 | 9.0 | 3.1 |
| School | ST652AA | 0.397 | 6.64 | 318.7 | 32.9 | - | - |
| Road | ST630A | 0.052 | 5.13 | 32.0 | 1.0 | 19.0 | 24.1 |
| Park | ST631B | 0.042 | 1.29 | 22.0 | 0.0 | - | - |
| Road | ST630AB | 0.159 | 6.68 | 134.0 | 2.9 | 19.0 | 6.7 |
| RY | ST630AA | 0.071 | 15.97 | 32.0 | 0.0 | 0.0 | 16.0 |
| Road | ST629A | 0.089 | 6.36 | 70.9 | 1.8 | 13.0 | 6.4 |
| RY | ST631C | 0.049 | 13.88 | 48.9 | 0.0 | 0.0 | 13.9 |
| RY | ST631D | 0.097 | 17.92 | 67.0 | 0.0 | 0.0 | 17.9 |
| Road | ST632A | 0.103 | 6.68 | 84.0 | 0.0 | 0.0 | 6.7 |
| Road | ST638B | 0.096 | 6.51 | 74.0 | 5.1 | 15.0 | 6.5 |
| Road | ST641A | 0.063 | 5.57 | 54.0 | 1.8 | 15.0 | 5.6 |
| Road | ST646A | 0.076 | 6.03 | 54.0 | 1.0 | 5.0 | 11.0 |
| RY | ST611A | 0.044 | 13.18 | 42.0 | 0.0 | 0.0 | 13.2 |
| RY | ST631A | 0.040 | 12.73 | 22.0 | 0.0 | 0.0 | 12.7 |
| RY | EXT-1 | 0.028 | 11.09 | 0.0 | 0.0 | 0.0 | 11.1 |
| Road | ST509AA | 0.213 | 8.07 | 44.0 | 113.3 | 28.0 | 36.1 |
| RY | ST509AB | 0.048 | 13.77 | 22.0 | 0.0 | 0.0 | 13.8 |
| RY | ST521E | 0.048 | 13.74 | 22.0 | 0.0 | 0.0 | 13.7 |
| Road | ST521D | 0.140 | 7.57 | 22.0 | 81.6 | 30.0 | 7.6 |
| Park | ST510A | 0.009 | 0.28 | 2.7 | 0.0 | - | - |
| Road | ST613A | 0.153 | 7.12 | 149.8 | 1.3 | 30.0 | 7.1 |
| School | ST624AA | 0.468 | 10.47 | 232.9 | 117.3 | 0.0 | 10.5 |
| Road | ST624A | 0.068 | 5.21 | 57.5 | 7.5 | 30.0 | 5.2 |
| Road | ST627A | 0.057 | 5.34 | 55.9 | 0.7 | 20.0 | 5.3 |
| Road | ST524A | 0.060 | 4.78 | 44.0 | 8.0 | 30.0 | 4.8 |
| RY | ST637C | 0.053 | 14.37 | 22.0 | 0.0 | 0.0 | 14.4 |
| RY | ST648A | 0.019 | 9.93 | 19.2 | 0.0 | 0.0 | 9.9 |
| RY | ST660B | 0.024 | 10.63 | 22.0 | 0.0 | 0.0 | 10.6 |
| Road | ST660A | 0.113 | 6.95 | 109.0 | 1.4 | 14.0 | 7.0 |
| Road | ST657A | 0.065 | 5.63 | 62.9 | 1.5 | 15.0 | 5.6 |
| Road | ST659A | 0.113 | 6.94 | 64.0 | 0.5 | 5.0 | 11.9 |
| Road | ST656A | 0.057 | 5.32 | 54.0 | 2.2 | 15.0 | 5.3 |
| Road | ST655A | 0.059 | 4.95 | 54.0 | 1.6 | 15.0 | 5.0 |

| Segment Type | Segment ID | Peak Flow ($m^3/s$) | Depth on Segment (cm) | Max. Capture (L/s) | Storage Used ($m^3$) | Static Ponding Depth (cm) | Total Flow Depth (cm) |
|---|---|---|---|---|---|---|---|
| RY | ST655B | 0.067 | 15.67 | 66.2 | 0.0 | 0.0 | 15.7 |
| RY | ST650B | 0.049 | 13.83 | 42.0 | 0.0 | 0.0 | 13.8 |
| Road | ST650A | 0.084 | 5.43 | 84.0 | 0.0 | 0.0 | 5.4 |
| Road | ST649A | 0.110 | 5.57 | 109.0 | 0.1 | 5.0 | 5.6 |
| RY | ST654A | 0.031 | 11.53 | 31.0 | 0.0 | 0.0 | 11.5 |
| Road | ST669A | 0.070 | 4.52 | 67.0 | 0.0 | 5.0 | 4.5 |
| RY | ST665A | 0.070 | 4.51 | 64.0 | 0.5 | 0.0 | 4.5 |
| Road | ST670A | 0.151 | 6.02 | 84.0 | 0.7 | 0.0 | 6.0 |
| RY | ST670B | 0.027 | 10.98 | 26.9 | 0.0 | 0.0 | 11.0 |
| Road | ST728A | 0.076 | 6.02 | 67.0 | 0.0 | 5.0 | 6.0 |
| Road | ST726A | 0.057 | 4.10 | 55.0 | 0.0 | 0.0 | 4.1 |
| Road | ST726B | 0.044 | 13.15 | 42.0 | 0.0 | 5.0 | 13.2 |
| Road | ST725A | 0.098 | 5.32 | 96.0 | 0.2 | 0.0 | 5.3 |
| Road | ST724A | 0.078 | 4.88 | 77.8 | 0.1 | 15.0 | 4.9 |
| Road | ST724B | 0.052 | 14.26 | 42.0 | 0.0 | 14.0 | 14.3 |
| Road | ST722A | 0.079 | 5.29 | 74.0 | 0.3 | 15.0 | 5.3 |
| Road | ST720A | 0.019 | 2.68 | 19.1 | 0.2 | 15.0 | 2.7 |
| Road | ST667A | 0.058 | 4.91 | 54.0 | 0.3 | 0.0 | 4.9 |
| Park | ST666B | 0.029 | 11.23 | 28.8 | 0.0 | - | - |
| School | ST666A | 0.069 | 5.24 | 64.0 | 0.3 | - | - |
| Road | ST673A | 0.058 | 4.13 | 55.0 | 0.0 | 0.0 | 4.1 |
| Road | ST672A | 0.051 | 3.90 | 51.1 | 0.0 | 18.0 | 3.9 |
| Road | ST672B | 0.030 | 11.39 | 30.0 | 0.0 | 0.0 | 11.4 |
| Road | ST723A | 0.027 | 3.11 | 26.7 | 0.1 | 0.0 | 3.1 |
| Road | ST664A | 0.081 | 4.72 | 81.2 | 0.1 | 0.0 | 4.7 |
| Road | ST715B | 0.039 | 12.58 | 39.0 | 0.0 | 0.0 | 12.6 |
| Road | ST714A | 0.041 | 12.79 | 40.6 | 0.0 | 0.0 | 12.8 |
| Road | ST719B | 0.041 | 12.81 | 40.8 | 0.0 | 0.0 | 12.8 |
| Road | ST719A | 0.047 | 3.75 | 44.0 | 0.3 | 0.0 | 3.8 |
| Road | ST717A | 0.083 | 4.76 | 83.4 | 0.0 | 0.0 | 4.8 |
| Road | ST705A | 0.181 | 6.73 | 178.0 | 0.4 | 0.0 | 6.7 |
| Road | ST709A | 0.057 | 4.09 | 56.9 | 0.0 | 0.0 | 4.1 |
| Road | ST715A | 0.112 | 6.90 | 109.0 | 1.2 | 0.0 | 6.9 |
| Road | ST713A | 0.079 | 6.09 | 76.6 | 1.2 | 0.0 | 6.1 |
| Road | ST711A | 0.069 | 5.78 | 64.0 | 1.7 | 0.0 | 5.8 |
| Road | ST710A | 0.081 | 6.16 | 79.4 | 1.2 | 0.0 | 6.2 |
| Road | ST710B | 0.074 | 16.20 | 67.0 | 0.0 | 0.0 | 16.2 |
| Road | ST707AA | 0.052 | 1.58 | 46.0 | 2.5 | 0.0 | 1.6 |

| Segment Type | Segment ID | Peak Flow ($m^3/s$) | Depth on Segment (cm) | Max. Capture (L/s) | Storage Used ($m^3$) | Static Ponding Depth (cm) | Total Flow Depth (cm) |
|---|---|---|---|---|---|---|---|
| Road | EXT-6 | 0.836 | 9.74 | 699.6 | 26.8 | 0.0 | 9.7 |
| Road | ST703B | 0.032 | 3.90 | 32.0 | 0.0 | 0.0 | 3.9 |
| Road | ST703A | 0.118 | 6.02 | 115.1 | 2.1 | 0.0 | 6.0 |
| Road | ST704A | 0.051 | 4.38 | 51.1 | 0.0 | 0.0 | 4.4 |

**Table 14: HMBS - Phase 4 - Major and Minor System 100 Year Storm Results**

| Segment Type | Segment ID | Peak Flow ($m^3/s$) | Depth on Segment (cm) | Max. Capture (L/s) | Storage Used ($m^3$) | Static Ponding Depth (cm) | Total Flow Depth (cm) |
|---|---|---|---|---|---|---|---|
| Minor System To Todd Pond | | | | | | | |
| Road | ST604A | 0.375 | 10.01 | 64.0 | 11.5 | 15.0 | 25.0 |
| RY | ST602A | 0.087 | 17.17 | 22.0 | 0.0 | 0.0 | N/A |
| RY | ST613B | 0.169 | 22.21 | 32.0 | 0.0 | 0.0 | N/A |
| Road | ST614A | 0.293 | 8.75 | 22.0 | 2.3 | 12.0 | 20.8 |
| Road | ST616A | 0.405 | 9.87 | 64.0 | 48.1 | 19.0 | 28.9 |
| Road | ST606A | 0.148 | 7.72 | 64.0 | 14.2 | 15.0 | 22.7 |
| Road | ST605A | 0.479 | 12.03 | 86.0 | 72.7 | 24.0 | 36.0 |
| RY | ST606B | 0.130 | 20.26 | 22.0 | 0.0 | 0.0 | N/A |
| RY | ST608C | 0.082 | 16.83 | 32.0 | 0.0 | 0.0 | N/A |
| Road | ST620A | 0.057 | 4.88 | 22.0 | 0.0 | 4.0 | 4.9 |
| Road | ST623A | 0.573 | 11.76 | 140.0 | 81.3 | 22.0 | 33.8 |
| Road | ST614B | 0.365 | 10.83 | 32.0 | 9.9 | 12.0 | 22.8 |
| Road | ST615A | 0.127 | 7.28 | 44.0 | 12.0 | 15.0 | 22.3 |
| Road | ST614C | 0.387 | 11.06 | 32.0 | 0.0 | 5.0 | 11.1 |
| Road | ST619B | 0.090 | 6.38 | 22.0 | 0.0 | 0.0 | 6.4 |
| Road | ST620B | 0.143 | 7.62 | 44.0 | 13.3 | 15.0 | 22.6 |
| Road | ST621A | 0.185 | 8.36 | 64.0 | 11.5 | 15.0 | 8.4 |
| RY | ST619A | 0.209 | 24.20 | 32.0 | 0.0 | 0.0 | N/A |
| RY | ST623B | 0.135 | 20.52 | 32.0 | 0.0 | 0.0 | N/A |
| Road | ST628A | 0.529 | 12.45 | 150.0 | 26.7 | 16.0 | 28.5 |
| Road | ST637A | 0.683 | 12.06 | 682.5 | 3.0 | 30.0 | 12.1 |
| Road | ST640A | 0.446 | 10.70 | 128.0 | 4.6 | 10.0 | 20.7 |
| Road | ST612A | 0.134 | 7.46 | 64.0 | 0.5 | 5.0 | 12.5 |
| Road | ST643A | 0.162 | 7.30 | 32.0 | 0.0 | 0.0 | 7.3 |
| Park | ST662AA | 0.101 | 3.09 | 55.2 | 0.0 | - | - |
| Road | ST662A | 0.127 | 6.18 | 64.0 | 0.0 | 0.0 | 6.2 |

| Segment Type | Segment ID | Peak Flow ($m^3/s$) | Depth on Segment (cm) | Max. Capture (L/s) | Storage Used ($m^3$) | Static Ponding Depth (cm) | Total Flow Depth (cm) |
|---|---|---|---|---|---|---|---|
| Road | ST663A | 0.118 | 6.03 | 64.0 | 2.0 | 5.0 | 11.0 |
| RY | ST637B | 0.267 | 26.47 | 42.0 | 0.0 | 0.0 | 26.5 |
| Road | ST609A | 0.129 | 7.32 | 54.0 | 14.6 | 15.0 | 22.3 |
| RY | ST652B | 0.049 | 13.80 | 22.0 | 0.0 | 0.0 | 13.8 |
| Road | ST652A | 0.223 | 7.64 | 96.0 | 0.5 | 3.0 | 10.6 |
| Road | ST638A | 0.100 | 6.61 | 22.0 | 0.0 | 9.0 | 6.6 |
| Road | ST608A | 0.228 | 8.28 | 76.0 | 35.3 | 19.0 | 27.3 |
| RY | ST608D | 0.063 | 5.56 | 32.0 | 1.0 | 5.0 | 10.6 |
| RY | ST608B | 0.114 | 19.25 | 22.0 | 0.0 | 0.0 | 19.3 |
| RY | ST609B | 0.093 | 17.67 | 22.0 | 0.0 | 0.0 | 17.7 |
| Road | ST647A | 0.472 | 9.68 | 55.0 | 0.0 | 9.0 | 9.7 |
| School | ST652AA | 0.851 | 9.84 | 339.0 | 274.5 | - | - |
| Road | ST630A | 0.486 | 12.08 | 32.0 | 1.0 | 19.0 | 31.1 |
| Park | ST631B | 0.246 | 5.58 | 22.0 | 0.0 | - | - |
| Road | ST630AB | 0.434 | 9.79 | 134.0 | 32.5 | 19.0 | 28.8 |
| RY | ST630AA | 0.167 | 22.12 | 32.0 | 0.0 | 0.0 | 22.1 |
| Road | ST629A | 0.457 | 11.80 | 70.9 | 1.8 | 13.0 | 11.8 |
| RY | ST631C | 0.199 | 23.69 | 100.5 | 0.0 | 0.0 | 23.7 |
| RY | ST631D | 0.225 | 24.99 | 67.0 | 0.0 | 0.0 | 25.0 |
| Road | ST632A | 0.467 | 11.90 | 84.0 | 0.0 | 0.0 | 11.9 |
| Road | ST638B | 0.198 | 8.60 | 74.0 | 15.1 | 15.0 | 23.6 |
| Road | ST641A | 0.127 | 7.27 | 54.0 | 12.0 | 15.0 | 22.3 |
| Road | ST646A | 0.150 | 7.75 | 54.0 | 1.0 | 5.0 | 12.8 |
| RY | ST611A | 0.095 | 17.79 | 42.0 | 0.0 | 0.0 | 17.8 |
| RY | ST631A | 0.188 | 23.16 | 22.0 | 0.0 | 0.0 | 23.2 |
| RY | EXT-1 | 0.067 | 15.72 | 0.0 | 0.0 | 0.0 | 15.7 |
| Road | ST509AA | 1.221 | 15.68 | 44.0 | 113.3 | 28.0 | 43.7 |
| RY | ST509AB | 0.105 | 18.58 | 22.0 | 0.0 | 0.0 | 18.6 |
| RY | ST521E | 0.117 | 19.42 | 22.0 | 0.0 | 0.0 | 19.4 |
| Road | ST521D | 0.311 | 10.20 | 22.0 | 111.9 | 30.0 | 40.2 |
| Park | ST510A | 0.062 | 1.90 | 33.0 | 0.0 | - | - |
| Road | ST613A | 0.642 | 12.27 | 638.6 | 5.6 | 30.0 | 12.3 |
| School | ST624AA | 0.907 | 13.41 | 242.4 | 407.5 | 0.0 | 13.4 |
| Road | ST624A | 0.135 | 6.77 | 112.0 | 14.6 | 30.0 | 6.8 |
| Road | ST627A | 0.390 | 11.10 | 387.9 | 4.9 | 20.0 | 11.1 |
| Road | ST524A | 0.116 | 6.18 | 44.0 | 37.6 | 30.0 | 6.2 |
| RY | ST637C | 0.162 | 21.86 | 22.0 | 0.0 | 0.0 | 21.9 |
| RY | ST648A | 0.114 | 19.22 | 22.0 | 0.0 | 0.0 | 19.2 |
| RY | ST660B | 0.056 | 14.78 | 22.0 | 0.0 | 0.0 | 14.8 |

| Segment Type | Segment ID | Peak Flow ($m^3/s$) | Depth on Segment (cm) | Max. Capture (L/s) | Storage Used ($m^3$) | Static Ponding Depth (cm) | Total Flow Depth (cm) |
|---|---|---|---|---|---|---|---|
| Road | ST660A | 0.226 | 9.07 | 109.0 | 10.8 | 14.0 | 23.1 |
| Road | ST657A | 0.152 | 7.78 | 64.0 | 14.7 | 15.0 | 22.8 |
| Road | ST659A | 0.472 | 11.96 | 64.0 | 0.5 | 5.0 | 17.0 |
| Road | ST656A | 0.744 | 14.17 | 54.0 | 16.8 | 15.0 | 29.2 |
| Road | ST655A | 0.621 | 12.13 | 54.0 | 13.5 | 15.0 | 27.1 |
| RY | ST655B | 0.166 | 22.07 | 67.0 | 0.0 | 0.0 | 22.1 |
| RY | ST650B | 0.125 | 20.02 | 42.0 | 0.0 | 0.0 | 20.0 |
| Road | ST650A | 0.171 | 7.13 | 84.0 | 0.0 | 0.0 | 7.1 |
| Road | ST649A | 0.567 | 10.42 | 109.0 | 0.7 | 5.0 | 15.4 |
| RY | ST654A | 0.074 | 16.19 | 32.0 | 0.0 | 0.0 | 16.2 |
| Road | ST669A | 0.151 | 6.01 | 67.0 | 0.0 | 5.0 | 6.0 |
| RY | ST665A | 0.442 | 9.00 | 64.0 | 0.5 | 0.0 | 9.0 |
| Road | ST670A | 0.394 | 8.57 | 84.0 | 0.7 | 0.0 | 8.6 |
| RY | ST670B | 0.094 | 17.74 | 32.0 | 0.0 | 0.0 | 17.7 |
| Road | ST728A | 0.147 | 7.69 | 67.0 | 0.0 | 5.0 | 7.7 |
| Road | ST726A | 0.237 | 7.07 | 55.0 | 0.0 | 0.0 | 7.1 |
| Road | ST726B | 0.109 | 18.81 | 42.0 | 0.0 | 5.0 | 18.8 |
| Road | ST725A | 0.195 | 6.92 | 96.0 | 0.5 | 0.0 | 6.9 |
| Road | ST724A | 0.385 | 9.02 | 84.0 | 0.7 | 15.0 | 9.0 |
| Road | ST724B | 0.111 | 19.03 | 42.0 | 0.0 | 14.0 | 19.0 |
| Road | ST722A | 0.206 | 7.67 | 74.0 | 1.0 | 15.0 | 7.7 |
| Road | ST720A | 0.039 | 3.51 | 22.0 | 2.3 | 15.0 | 3.5 |
| Road | ST667A | 0.370 | 9.96 | 54.0 | 1.0 | 0.0 | 10.0 |
| Park | ST666B | 0.061 | 15.27 | 32.0 | 0.0 | - | - |
| School | ST666A | 0.411 | 10.39 | 64.0 | 0.5 | - | - |
| Road | ST673A | 0.124 | 5.51 | 55.0 | 0.0 | 0.0 | 5.5 |
| Road | ST672A | 0.169 | 6.24 | 55.0 | 0.0 | 18.0 | 6.2 |
| Road | ST672B | 0.073 | 16.14 | 32.0 | 0.0 | 0.0 | 16.1 |
| Road | ST723A | 0.055 | 4.01 | 32.0 | 1.0 | 0.0 | 4.0 |
| Road | ST664A | 0.159 | 6.11 | 84.0 | 0.7 | 0.0 | 6.1 |
| Road | ST715B | 0.091 | 17.53 | 42.0 | 0.0 | 0.0 | 17.5 |
| Road | ST714A | 0.141 | 20.84 | 42.0 | 0.0 | 0.0 | 20.8 |
| Road | ST719B | 0.098 | 18.04 | 42.0 | 0.0 | 0.0 | 18.0 |
| Road | ST719A | 0.126 | 5.54 | 44.0 | 1.6 | 0.0 | 5.5 |
| Road | ST717A | 0.210 | 6.74 | 84.0 | 0.0 | 0.0 | 6.7 |
| Road | ST705A | 0.594 | 10.60 | 178.0 | 1.6 | 0.0 | 10.6 |
| Road | ST709A | 0.109 | 5.24 | 64.0 | 0.0 | 0.0 | 5.2 |
| Road | ST715A | 0.227 | 9.08 | 109.0 | 10.8 | 0.0 | 9.1 |
| Road | ST713A | 0.187 | 8.40 | 84.0 | 13.0 | 0.0 | 8.4 |

| Segment Type | Segment ID | Peak Flow ($m^3/s$) | Depth on Segment (cm) | Max. Capture (L/s) | Storage Used ($m^3$) | Static Ponding Depth (cm) | Total Flow Depth (cm) |
|---|---|---|---|---|---|---|---|
| Road | ST711A | 0.164 | 7.99 | 64.0 | 14.7 | 0.0 | 8.0 |
| Road | ST710A | 0.170 | 8.09 | 84.0 | 13.0 | 0.0 | 8.1 |
| Road | ST710B | 0.172 | 22.38 | 67.0 | 0.0 | 0.0 | 22.4 |
| Road | ST707AA | 0.345 | 6.28 | 186.0 | 14.0 | 0.0 | 6.3 |
| Road | EXT-6 | 1.737 | 12.88 | 699.6 | 500.6 | 0.0 | 12.9 |
| Road | ST703B | 0.354 | 9.79 | 32.0 | 0.0 | 0.0 | 9.8 |
| Road | ST703A | 0.532 | 10.61 | 116.0 | 21.3 | 0.0 | 10.6 |
| Road | ST704A | 0.107 | 5.78 | 55.0 | 0.0 | 0.0 | 5.8 |

The results of the hydrologic analyses (DDSWMM input and output files) for the different storm events are summarized in **Appendix A2.**

The following table shows the segments with 100 year total flow depth greater than 30 cm as shown in the above **Table 12 and Table 14**, along with a comparison to the 100 year total flow depth on those segments as per the approved SWM Report for Draft Plan #2 (Stantec, August 2014).

**Table 15: 100 Year Total Flow Depth Comparison**

| Catchment ID | Approved SWM Plan (August 2014) Total Flow Depth (cm) | Interim Phase 4 SWM Plan (July 2015) Total Flow Depth (cm) | Ultimate Phase 4 SWM Plan (July 2015) Total Flow Depth (cm) |
|---|---|---|---|
| **Minor System to Corrigan Pond** | | | |
| '1-1' / ST525A | 34.4 | 31.2 | 31.2 |
| '1-9' / ST535A | 39.3 | 30.7 | 30.7 |
| '1-20' / ST551A | 34.3 | 26.9 | 26.9 |
| **Minor System to Todd Pond** | | | |
| '2-5' / ST616A | 33.4 | 28.9 | 28.9 |
| '2-7' / ST605A | 38.7 | 36.0 | 36.0 |
| '2-11' / ST623A | 33.7 | 33.8 | 33.8 |
| ST630A | <30 | 31.1 | 31.1 |

The above table shows that total flow depths have been reduced in the majority of areas with the exception of area ST630A, which shows a negligible flow depth increase. These areas were previously designed and approved prior to the flow depth requirement and/or are within Draft Plan #2 and were approved with flow depths in excess of the required 30cm. It should be noted that several efforts were made during detailed design of the approved phases in order to reduce the 100 year flow depths on streets as much as possible. The total 100 year flow depth over the proposed Phase 4 segments remains below 30cm.

Stantec

**Half Moon Bay South Phase 5**

DATE: 2019-02-15
REVISION: 1
DESIGNED BY: DT
CHECKED BY: KS

**FILE NUMBER:** **160401476**

# STORM SEWER DESIGN SHEET
**(City of Ottawa)**

DESIGN PARAMETERS

$I = a / (t+b)^c$ (As per City of Ottawa Guidelines, 2012)

| | 1:2 yr | 1:5 yr | 1:10 yr | 1:100 yr |
|---|---|---|---|---|
| a = | 732.951 | 998.071 | 1174.184 | 1735.688 |
| b = | 6.199 | 6.053 | 6.014 | 6.014 |
| c = | 0.810 | 0.814 | 0.816 | 0.820 |

MANNING'S n = 0.013 BEDDING CLASS = B
MINIMUM COVER: 2.00 m
TIME OF ENTRY 10 min

| LOCATION | | | DRAINAGE AREA | | | | | | | | | | | | | | | | | | | | | PIPE SELECTION | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| AREA ID NUMBER | FROM M.H. | TO M.H. | AREA (2-YEAR) (ha) | AREA (5-YEAR) (ha) | AREA (10-YEAR) (ha) | AREA (100-YEAR) (ha) | AREA (ROOF) (ha) | C (2-YEAR) (-) | C (5-YEAR) (-) | C (10-YEAR) (-) | C (100-YEAR) (-) | A x C (2-YEAR) (ha) | ACCUM AxC (2YR) (ha) | A x C (5-YEAR) (ha) | ACCUM. AxC (5YR) (ha) | A x C (10-YEAR) (ha) | ACCUM. AxC (10YR) (ha) | A x C (100-YEAR) (ha) | ACCUM. AxC (100YR) (ha) | T of C (min) | $I_{2\text{-YEAR}}$ (mm/h) | $I_{5\text{-YEAR}}$ (mm/h) | $I_{10\text{-YEAR}}$ (mm/h) | $I_{100\text{-YEAR}}$ (mm/h) | $Q_{CONTROL}$ (L/s) | ACCUM. $Q_{CONTROL}$ (L/s) | $Q_{ACT}$ (CIA/360) (L/s) | LENGTH (m) | PIPE WIDTH OR DIAMETEI (mm) | PIPE HEIGHT (mm) | PIPE SHAPE (-) | MATERIAL (-) | CLASS (-) | SLOPE % | $Q_{CAP}$ (FULL) (L/s) | % FULL (-) | VEL. (FULL) (m/s) |
| C729A | 729 | 728 | 0.00 | 0.34 | 0.00 | 0.00 | 0.00 | 0.00 | 0.70 | 0.00 | 0.00 | 0.000 | 0.000 | 0.241 | 0.241 | 0.000 | 0.000 | 0.000 | 0.000 | 10.00 | 76.81 | 104.19 | 122.14 | 178.56 | 0.0 | 0.0 | 69.7 | 115.2 | 375 | 375 | CIRCULAR | PVC | - | 0.50 | 116.6 | **59.83%** | 1.11 |
| | 728 | 727 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.000 | 0.000 | 0.000 | 0.241 | 0.000 | 0.000 | 0.000 | 0.000 | 11.93 | 70.12 | 95.01 | 111.33 | 162.67 | 0.0 | 0.0 | 63.6 | 11.9 | 375 | 375 | CIRCULAR | PVC | - | 2.30 | 250.0 | **25.44%** | 2.37 |
| C727B, C727A | 727 | 726 | 0.00 | 0.51 | 0.00 | 0.00 | 0.00 | 0.00 | 0.61 | 0.00 | 0.00 | 0.000 | 0.000 | 0.308 | 0.549 | 0.000 | 0.000 | 0.000 | 0.000 | 12.05 | 69.75 | 94.50 | 110.72 | 161.79 | 0.0 | 0.0 | 144.1 | 63.2 | 375 | 375 | CIRCULAR | PVC | - | 2.30 | 250.0 | **57.65%** | 2.37 |
| | | | | | | | | | | | | | | | | | | | | **12.54** | | | | | | | | | | | | | | | | | |
| C731A | 731 | 730 | 0.00 | 0.27 | 0.00 | 0.00 | 0.00 | 0.00 | 0.70 | 0.00 | 0.00 | 0.000 | 0.000 | 0.186 | 0.186 | 0.000 | 0.000 | 0.000 | 0.000 | 10.00 | 76.81 | 104.19 | 122.14 | 178.56 | 0.0 | 0.0 | 53.8 | 54.1 | 300 | 300 | CIRCULAR | PVC | - | 0.50 | 68.0 | **79.09%** | 0.97 |
| C730A | 730 | 726 | 0.00 | 0.23 | 0.00 | 0.00 | 0.00 | 0.00 | 0.70 | 0.00 | 0.00 | 0.000 | 0.000 | 0.162 | 0.348 | 0.000 | 0.000 | 0.000 | 0.000 | 10.95 | 73.33 | 99.41 | 116.51 | 170.29 | 0.0 | 0.0 | 96.0 | 67.6 | 375 | 375 | CIRCULAR | PVC | - | 0.50 | 116.6 | **82.38%** | 1.11 |
| | | | | | | | | | | | | | | | | | | | | **11.98** | | | | | | | | | | | | | | | | | |
| C726B, C726A | 726 | 721 | 0.00 | 0.50 | 0.00 | 0.00 | 0.00 | 0.00 | 0.66 | 0.00 | 0.00 | 0.000 | 0.000 | 0.327 | 1.223 | 0.000 | 0.000 | 0.000 | 0.000 | 12.54 | 68.25 | 92.44 | 108.30 | 158.23 | 0.0 | 0.0 | 314.1 | 96.1 | 450 | 450 | CIRCULAR | CONCRETE | - | 2.30 | 451.1 | **69.64%** | 2.75 |
| | | | | | | | | | | | | | | | | | | | | **13.16** | | | | | | | | | | | | | | | | | |
| C667B | 667 | 725 | 0.00 | 0.12 | 0.00 | 0.00 | 0.00 | 0.00 | 0.70 | 0.00 | 0.00 | 0.000 | 0.000 | 0.083 | 0.083 | 0.000 | 0.000 | 0.000 | 0.000 | 0.00 | 167.22 | 230.48 | 271.61 | 398.62 | 0.0 | 0.0 | 53.0 | 61.1 | 300 | 300 | CIRCULAR | PVC | - | 0.50 | 68.0 | **77.94%** | 0.97 |
| | 725 | 724 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.000 | 0.000 | 0.000 | 0.083 | 0.000 | 0.000 | 0.000 | 0.000 | 1.08 | 146.90 | 201.75 | 237.48 | 348.31 | 0.0 | 0.0 | 46.4 | 25.9 | 300 | 300 | CIRCULAR | PVC | - | 0.50 | 68.0 | **68.23%** | 0.97 |
| C724A, C724B | 724 | 721 | 0.00 | 0.59 | 0.00 | 0.00 | 0.00 | 0.00 | 0.61 | 0.00 | 0.00 | 0.000 | 0.000 | 0.362 | 0.445 | 0.000 | 0.000 | 0.000 | 0.000 | 1.55 | 139.53 | 191.39 | 225.19 | 330.19 | 0.0 | 0.0 | 236.5 | 50.7 | 525 | 525 | CIRCULAR | CONCRETE | - | 0.50 | 317.2 | **74.55%** | 1.42 |
| | | | | | | | | | | | | | | | | | | | | **2.17** | | | | | | | | | | | | | | | | | |
| C723A | 723 | 722 | 0.00 | 0.31 | 0.00 | 0.00 | 0.00 | 0.00 | 0.70 | 0.00 | 0.00 | 0.000 | 0.000 | 0.218 | 0.218 | 0.000 | 0.000 | 0.000 | 0.000 | 10.00 | 76.81 | 104.19 | 122.14 | 178.56 | 0.0 | 0.0 | 63.2 | 17.4 | 375 | 375 | CIRCULAR | PVC | - | 0.50 | 116.6 | **54.24%** | 1.11 |
| | 722 | 721 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.000 | 0.000 | 0.000 | 0.218 | 0.000 | 0.000 | 0.000 | 0.000 | 10.30 | 75.68 | 102.64 | 120.31 | 175.87 | 0.0 | 0.0 | 62.3 | 31.6 | 375 | 375 | CIRCULAR | PVC | - | 0.50 | 116.6 | **53.43%** | 1.11 |
| | | | | | | | | | | | | | | | | | | | | **10.85** | | | | | | | | | | | | | | | | | |
| | 721 | 720 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.000 | 0.000 | 0.000 | 1.887 | 0.000 | 0.000 | 0.000 | 0.000 | 13.16 | 66.48 | 90.01 | 105.44 | 154.03 | 0.0 | 0.0 | 471.7 | 21.6 | 600 | 600 | CIRCULAR | CONCRETE | - | 0.80 | 572.9 | **82.33%** | 1.96 |
| C720B | 720 | 719 | 0.00 | 0.16 | 0.00 | 0.00 | 0.00 | 0.00 | 0.52 | 0.00 | 0.00 | 0.000 | 0.000 | 0.083 | 1.970 | 0.000 | 0.000 | 0.000 | 0.000 | 13.35 | 65.97 | 89.31 | 104.62 | 152.83 | 0.0 | 0.0 | 488.7 | 13.2 | 600 | 600 | CIRCULAR | CONCRETE | - | 0.80 | 572.9 | **85.29%** | 1.96 |
| | | | | | | | | | | | | | | | | | | | | **13.46** | | | | | | | | | 600 | 600 | | | | | | | |
| C669A | 669 | 668 | 0.00 | 0.22 | 0.00 | 0.00 | 0.00 | 0.00 | 0.70 | 0.00 | 0.00 | 0.000 | 0.000 | 0.154 | 0.154 | 0.000 | 0.000 | 0.000 | 0.000 | 10.00 | 76.81 | 104.19 | 122.14 | 178.56 | 0.0 | 0.0 | 44.6 | 62.6 | 300 | 300 | CIRCULAR | PVC | - | 3.10 | 169.3 | **26.32%** | 2.41 |
| C668A | 668 | 667 | 0.00 | 0.22 | 0.00 | 0.00 | 0.00 | 0.00 | 0.70 | 0.00 | 0.00 | 0.000 | 0.000 | 0.151 | 0.305 | 0.000 | 0.000 | 0.000 | 0.000 | 10.62 | 74.51 | 101.03 | 118.42 | 173.09 | 0.0 | 0.0 | 85.7 | 70.2 | 300 | 300 | CIRCULAR | PVC | - | 3.10 | 169.3 | **50.61%** | 2.41 |
| C667A | 667 | 666 | 0.00 | 0.31 | 0.00 | 0.00 | 0.00 | 0.00 | 0.72 | 0.00 | 0.00 | 0.000 | 0.000 | 0.223 | 0.529 | 0.000 | 0.000 | 0.000 | 0.000 | 11.19 | 72.53 | 98.31 | 115.21 | 168.38 | 0.0 | 0.0 | 144.3 | 72.1 | 450 | 450 | CIRCULAR | CONCRETE | - | 1.00 | 297.4 | **48.53%** | 1.81 |
| C666B, C666A | 666 | 659 | 0.00 | 0.64 | 0.00 | 0.00 | 0.00 | 0.00 | 0.62 | 0.00 | 0.00 | 0.000 | 0.000 | 0.394 | 0.923 | 0.000 | 0.000 | 0.000 | 0.000 | 11.97 | 69.98 | 94.82 | 111.10 | 162.35 | 0.0 | 0.0 | 243.0 | 71.9 | 450 | 450 | CIRCULAR | CONCRETE | - | 1.00 | 297.4 | **81.70%** | 1.81 |
| | | | | | | | | | | | | | | | | | | | | **12.64** | | | | | | | | | 825 | 825 | | | | | | | |
| C665A | 665 | 664 | 0.00 | 0.29 | 0.00 | 0.00 | 0.00 | 0.00 | 0.72 | 0.00 | 0.00 | 0.000 | 0.000 | 0.210 | 0.210 | 0.000 | 0.000 | 0.000 | 0.000 | 10.00 | 76.81 | 104.19 | 122.14 | 178.56 | 0.0 | 0.0 | 60.8 | 58.3 | 300 | 300 | CIRCULAR | PVC | - | 1.10 | 100.8 | **60.27%** | 1.43 |
| C664A | 664 | 656 | 0.00 | 0.33 | 0.00 | 0.00 | 0.00 | 0.00 | 0.72 | 0.00 | 0.00 | 0.000 | 0.000 | 0.237 | 0.447 | 0.000 | 0.000 | 0.000 | 0.000 | 10.75 | 74.03 | 100.38 | 117.65 | 171.96 | 0.0 | 0.0 | 124.8 | 71.9 | 375 | 375 | CIRCULAR | PVC | - | 1.10 | 172.9 | **72.16%** | 1.64 |
| | | | | | | | | | | | | | | | | | | | | **11.52** | | | | | | | | | 750 | 750 | | | | | | | |

Appendix D : Geotechnical Investigation
15/2/2019 12:00:00 AM

# Appendix D : GEOTECHNICAL INVESTIGATION

Geotechnical Engineering

Environmental Engineering

Hydrogeology

Geological Engineering

Materials Testing

Building Science

Archaeological Services

**Paterson Group Inc.**
Consulting Engineers
154 Colonnade Road South
Ottawa, Ontario
Canada K2E 7J5

Tel: (613) 226-7381
Fax: (613) 226-6344
www.patersongroup.ca

**patersongroup**

# Geotechnical Investigation

Proposed Residential Development
Half Moon Bay South (Phase 5)
Greenbank Road
Ottawa, Ontario

Prepared For

Mattamy Homes

February 8, 2019

Report: PG4803-1

# Table of Contents

**Page**

**1.0 Introduction** . . . . . 1

**2.0 Proposed Development** . . . . . 1

**3.0 Method of Investigation**
3.1 Field Investigation . . . . . 2
3.2 Field Survey . . . . . 3
3.3 Laboratory Testing . . . . . 3

**4.0 Observations**
4.1 Surface Conditions . . . . . 4
4.2 Subsurface Profile . . . . . 4
4.3 Groundwater . . . . . 4

**5.0 Discussion**
5.1 Geotechnical Assessment . . . . . 6
5.2 Site Grading and Preparation . . . . . 6
5.3 Foundation Design . . . . . 7
5.4 Design for Earthquakes . . . . . 7
5.5 Basement Slab . . . . . 8
5.6 Pavement Design . . . . . 8

**6.0 Design and Construction Precautions**
6.1 Foundation Drainage and Backfill . . . . . 10
6.2 Protection of Footings . . . . . 10
6.3 Excavation Side Slopes . . . . . 10
6.4 Pipe Bedding and Backfill . . . . . .11
6.5 Groundwater Control . . . . . 12
6.6 Winter Construction . . . . . 12

**7.0 Recommendations** . . . . . 13

**8.0 Statement of Limitations** . . . . . 14

# Appendices

**Appendix 1** Soil Profile and Test Data Sheets
Symbols and Terms

**Appendix 2** Figure 1 - Key Plan
Drawing PG4803-1 - Test Hole Location Plan

# 1.0 Introduction

Paterson Group (Paterson) was commissioned by Mattamy Homes to conduct a geotechnical investigation for the current phase of the proposed residential development to be located within the Half Moon Bay South subdivision in the City of Ottawa (refer to Figure 1 - Key Plan in Appendix 2 of this report).

The objectives of the current investigation were to:

- ❑ Determine the subsoil and groundwater conditions at this site by means of test holes.
- ❑ Provide geotechnical recommendations pertaining to design of the proposed development including construction considerations which may affect the design.

The following report has been prepared specifically and solely for the aforementioned project which is described herein. It contains our findings and includes geotechnical recommendations pertaining to the design and construction of the subject development as they are understood at the time of writing this report.

# 2.0 Proposed Development

Based on the available conceptual drawings, it is our understanding that the proposed development consists of a series of townhomes and/or single family residential houses with associated driveways, access lanes, local roadways and landscaped areas. It is further understood that the proposed development will be serviced by future municipal water, sanitary and storm services.

# 3.0 Method of Investigation

## 3.1 Field Investigation

The field program for the current geotechnical investigation was conducted on February 5, 2019 which consisted of extending a total of 8 test pits (TP1-19 to TP8-19) to a maximum depth of 5.0 m. Previous field programs were conducted in March and December, 2015. During that time, a total of 7 test holes were advanced to a maximum depth of 9.8 m.

The test holes were distributed in a manner to provide general coverage of the proposed development. The locations were determined in the field by Paterson personnel taking into consideration site features and underground services. Approximate locations of the test holes are shown in Drawing PG4803-1 - Test Hole Location Plan included in Appendix 2.

Boreholes were put down using a track-mounted auger drill rig operated by a two-person crew. The test pits were excavated using a hydraulic excavator. All fieldwork was conducted under the full-time supervision of our personnel under the direction of a senior engineer from our geotechnical department. The drilling procedure consisted of augering to the required depths at the selected locations, sampling and testing the overburden. The excavating procedures consisted of advancing each test hole to the required depths at the selected locations and sampling the overburden.

**Sampling and In Situ Testing**

Soil samples were collected from the boreholes using a 50 mm diameter split-spoon (SS) sampler, or from the auger flights. Soil samples from the open test pits were recovered from the excavation side walls. All soil samples were placed in sealed plastic bags and transported to our laboratory. The depths at which the auger, split-spoon and grab samples were recovered from the test holes are shown as AU, SS and G, respectively, on the Soil Profile and Test Data sheets in Appendix 1.

The Standard Penetration Test (SPT) was conducted in conjunction with the recovery of the split spoon samples. The SPT results are recorded as 'N' values on the Soil Profile and Test Data sheets. The 'N' value is the number of blows required to drive the split spoon sampler 300 mm into the soil after a 150 mm initial penetration using a 63.5 kg hammer falling from a height of 760 mm.

Subsurface conditions observed in the test holes were recorded in detail in the field. Reference should be made to the Soil Profile and Test Data sheets presented in Appendix 1 for specific details of the soil profile encountered at the test hole locations.

**Groundwater**

Monitoring wells consisting of 50 mm diameter rigid PVC pipe were installed in 3 borehole locations and flexible standpipe piezometers were installed in 2 borehole locations during the course of the previous field investigations to permit monitoring of the groundwater levels. Groundwater infiltration throught the side walls of the test pits was recorded during the current field program. All groundwater observations are noted on the Soil Profile and Test Data sheets presented in Appendix 1.

**Sample Storage**

All samples will be stored in the laboratory for a period of one month after issuance of this report. They will then be discarded unless we are otherwise directed.

## 3.2 Field Survey

The test hole locations for the current field investigation were selected by Paterson and surveyed in the field by Agrodrain Services Ltd. (ASL). The elevations at the test hole locations are referenced to a geodetic datum. Ground surface elevations at the test hole locations from previous investigations were surveyed by J.D. Barnes Ltd. or were inferred based on available topographic mapping. The ground surface elevations at the test hole locations are presented on Drawing PG4803-1 - Test Hole Location Plan included in Appendix 2.

## 3.3 Laboratory Testing

The soil samples recovered from the subject site were visually examined in our laboratory to review the results of the field logging.

# 4.0 Observations

## 4.1 Surface Conditions

The ground surface across the subject site generally slopes down towards the east and northeast, with a change in elevation of approximately 4 to 5 m. It should be noted that the site is slightly lower than Alex Polowin Avenue towards the northeast portion of the site. The subject site is bordered to the east and northeast by the existing Half Moon Bay subdivision and to the north, west and south by vacant lands. Several fill piles were noted across the subject site due to ongoing construction operations.

## 4.2 Subsurface Profile

### Overburden

Generally, the subsurface profile encountered at the test holes consists of a topsoil or fill layer consisting of silty clay with sand and trace gravel and organics overlying a loose to compact silty sand. A glacial till deposit was encountered below the silty sand layer consisting of silty sand with gravel, cobbles and boulders. Specific details of the soil profile at each test hole location are provided on the Soil Profile and Test Data sheets in Appendix 1.

### Bedrock

Based on available geological mapping, the local bedrock consists of dolomite of the Oxford formation with an anticipated overburden thickness of 15 to 25 m.

## 4.3 Groundwater

Groundwater levels were measured in the monitoring wells and standpipes installed at the borehole locations following completion of the previous investigations. The results are summarized in Table 1 and provided on the Soil Profile and Test Data sheets in Appendix 1.

**Table 1 - Summary of Groundwater Level Readings**

| Test Hole Number | Ground Surface Elevation (m) | Groundwater Depth (m) | Groundwater Elevation (m) | Date |
|---|---|---|---|---|
| BH 5-15 (PG3607) | 108.75 | Dry | - | July 28, 2016 |
| BH 6-15 (PG3607) | 102.59 | Dry | - | July 28, 2016 |
| BH 12-15 (PG3607) | 105.26 | Dry | - | July 28, 2016 |
| BH 5-15 (PG3450) | 103.02 | 7.15<br>6.80<br>6.76 | 95.87<br>96.22<br>96.26 | March 23, 2015<br>April 21, 2015<br>May 12, 2015 |
| BH 6-15 (PG3450) | 101.42 | 2.93<br>0.99<br>1.45 | 98.49<br>100.43<br>99.97 | March 23, 2015<br>April 21, 2015<br>May 12, 2015 |

**Note:** Ground surface elevations at PG3607 test hole locations were inferred based on available topographic mapping. Ground surface elevations at PG3450 test hole locations were provided by J.D. Barnes Ltd. and are understood to be referenced to a geodetic datum.

Based on our observations during the current field program, all test pits were noted to be dry within no infiltration through the side walls of the open test pits. The long-term groundwater level can also be estimated based on the recovered soil samples' moisture levels and consistency at the test hole locations. Based on these observations, the long-term groundwater table is estimated to be between 4 to 5 m below existing ground surface. It should be noted that groundwater levels are subject to seasonal fluctuations. Therefore, the groundwater levels could vary at the time of construction.

# 5.0 Discussion

## 5.1 Geotechnical Assessment

From a geotechnical perspective, the subject site is satisfactory for the proposed development. It is anticipated that the proposed buildings can be constructed using conventional shallow footings placed on an undisturbed, compact silty sand or glacial till bearing surface.

The above and other considerations are discussed in the following paragraphs.

## 5.2 Site Grading and Preparation

### Stripping Depth

Topsoil and any deleterious fill, such as those containing organics, should be stripped from under any buildings and other settlement sensitive structures, such as underground services or paved areas.

### Fill Placement

Fill used for grading beneath the building areas should consist, unless otherwise specified, of clean imported granular fill, such as Ontario Provincial Standard Specifications (OPSS) Granular A or Granular B Type II material. The fill should be placed in lifts no greater than 300 mm thick and compacted using suitable compaction equipment for the lift thickness. Fill placed beneath the buildings should be compacted to at least 98% of its standard Proctor maximum dry density (SPMDD).

Non-specified existing fill along with site-excavated soil could be placed as general landscaping fill where surface settlement is of minor concern. The existing materials should be spread in thin lifts and at least compacted by the tracks of the spreading equipment to minimize voids. If the existing materials are to be placed to increase the subgrade level for areas to be paved, the non-specified existing fill should be compacted in 300 mm lifts and compacted to a minimum density of 95% of the respective SPMDD.

## 5.3 Foundation Design

Footings placed on an undisturbed, compact silty sand bearing surface can be designed using a bearing resistance value at serviceability limit states (SLS) of **100 kPa** and a factored bearing resistance value at ultimate limit states (ULS) of **175 kPa**. A geotechnical resistance factor of 0.5 was applied to the reported bearing resistance value at ULS. If the subgrade medium is noted to be in a loose state of compactness, it is recommended to proof-roll the bearing medium under dry conditions and above freezing temperature using appropriate compaction equipment. The subgrade should be inspected by a Paterson at the time of construction.

Footings placed on an undisturbed, glacial till bearing surface can be designed using a bearing resistance value at serviceability limit states (SLS) of **150 kPa** and a factored bearing resistance value at ultimate limit states (ULS) of **225 kPa**. A geotechnical resistance factor of 0.5 was applied to the reported bearing resistance value at ULS.

An undisturbed soil bearing surface consists of one from which all topsoil and deleterious materials, such as loose, frozen or disturbed soil, have been removed prior to the placement of concrete for footings.

### Settlement

The bearing resistance value given for footings at SLS will be subjected to potential post construction total and differential settlements of 25 and 20 mm, respectively.

### Lateral Support

The bearing medium under footing-supported structures is required to be provided with adequate lateral support with respect to excavations and different foundation levels. Above the groundwater level, adequate lateral support is provided to a compact glacial till, stiff silty clay, or engineered fill when a plane extending down and out from the bottom edge of the footing at a minimum of 1.5H:1V passes only through in situ soil or engineered fill.

## 5.4 Design for Earthquakes

The site class for seismic site response can be taken as **Class D** for the foundations considered at the subject site. Soils underlying the subject site are not susceptible to liquefaction. Reference should be made to the latest revision of the 2012 Ontario Building Code for a full discussion of the earthquake design requirements.

## 5.5 Basement Slab

With the removal of all topsoil and deleterious fill, such as those containing organic materials, from within the footprint of the proposed buildings, the native soil surface or approved engineered fill surface will be considered to be an acceptable subgrade on which to commence backfilling for floor slab construction.

Any soft areas should be removed and backfilled with appropriate backfill material prior to placing any fill. OPSS Granular B Type II, with a maximum particle size of 50 mm, are recommended for backfilling below the floor slab. It is recommended that the upper 200 mm of sub-floor fill consist of 19 mm clear crushed stone. All backfill material within the footprint of the proposed buildings should be placed in maximum 300 mm thick loose layers and compacted to at least 98% of its SPMDD.

## 5.6 Pavement Design

Car only parking and local roadways are anticipated at this site. The proposed pavement structures are shown in Tables 2 and 3.

**Table 2 - Recommended Pavement Structure - Car Only Parking Areas**

| Thickness (mm) | Material Description |
|---|---|
| 50 | **Wear Course -** HL-3 or Superpave 12.5 Asphaltic Concrete |
| 150 | **BASE** - OPSS Granular A Crushed Stone |
| 300 | **SUBBASE** - OPSS Granular B Type II |
| | **SUBGRADE** - Either fill, in situ soil, or OPSS Granular B Type I or II material placed over in situ soil or fill |

**Table 3 - Recommended Pavement Structure - Local Roadways**

| Thickness (mm) | Material Description |
|---|---|
| 40 | **Wear Course -** HL-3 or Superpave 12.5 Asphaltic Concrete |
| 50 | **Binder Course -** HL-8 or Superpave 19.0 Asphaltic Concrete |
| 150 | **BASE** - OPSS Granular A Crushed Stone |
| 400 | **SUBBASE** - OPSS Granular B Type II |
| | **SUBGRADE** - Either fill, in situ soil, or OPSS Granular B Type I or II material placed over in situ soil or fill |

Minimum Performance Graded (PG) 58-34 asphalt cement should be used for this project.

If soft spots develop in the subgrade during compaction or due to construction traffic, the affected areas should be excavated and replaced with OPSS Granular B Type I or Type II material.

The pavement granular base and subbase should be placed in maximum 300 mm thick lifts and compacted to a minimum of 98% of the material's SPMDD using suitable compaction equipment.

# 6.0 Design and Construction Precautions

## 6.1 Foundation Drainage and Backfill

It is recommended that a perimeter foundation drainage system be provided for the proposed structures. The system should consist of a 150 mm diameter perforated corrugated plastic pipe, surrounded on all sides by 150 mm of 19 mm clear crushed stone, placed at the footing level around the exterior perimeter of the structure. The pipe should have a positive outlet, such as a gravity connection to the storm sewer.

Backfill against the exterior sides of the foundation walls should consist of free-draining non frost susceptible granular materials. The site excavated materials will be frost susceptible and, as such, are not recommended for re-use as backfill against the foundation walls unless placed in conjunction with a composite drainage system, such as Delta Drain 6000 or equivalent. Imported granular materials, such as clean sand or OPSS Granular B Type I granular material, should be used for this purpose.

## 6.2 Protection of Footings Against Frost Action

Perimeter footings, of heated structures are required to be insulated against the deleterious effect of frost action. A minimum of 1.5 m thick soil cover, or an equivalent combination of soil cover and foundation insulation should be provided in this regard.

Exterior unheated footings, such as those for isolated exterior piers, are more prone to deleterious movement associated with frost action than the exterior walls of the structure proper and require additional protection, such as soil cover of 2.1 m or an equivalent combination of soil cover and foundation insulation.

## 6.3 Excavation Side Slopes

The side slopes of excavations in the soil and fill overburden materials should be either cut back at acceptable slopes or should be retained by shoring systems from the start of the excavation until the structure is backfilled. It is assumed that sufficient room will be available for the greater part of the excavation to be undertaken by open-cut methods (i.e. unsupported excavations).

The excavation side slopes above the groundwater level extending to a maximum depth of 3 m should be cut back at 1H:1V or flatter. The flatter slope is required for excavation below groundwater level. The subsoil at this site is considered to be mainly a Type 2 and 3 soil according to the Occupational Health and Safety Act and Regulations for Construction Projects.

Excavated soil should not be stockpiled directly at the top of excavations and heavy equipment should be kept at least 3 m away from the excavation sides.

Slopes in excess of 3 m in height should be periodically inspected by the geotechnical consultant in order to detect if the slopes are exhibiting signs of distress.

It is recommended that a trench box be used at all times to protect personnel working in trenches with steep or vertical sides. It is expected that services will be installed by "cut and cover" methods and excavations will not be left open for extended periods of time.

## 6.4 Pipe Bedding and Backfill

At least 150 mm of OPSS Granular A should be used for bedding for sewer pipes when placed on soil subgrade. The bedding should extend to the spring line of the pipe. Cover material, from the spring line to at least 300 mm above the obvert of the pipe should consist of OPSS Granular A (concrete or PSM PVC pipes) or sand (concrete pipe). The bedding and cover materials should be placed in maximum 225 mm thick lifts compacted to a minimum of 95% of the material's standard Proctor maximum dry density (SPMDD).

The cover material, which should consist of OPSS Granular A, should extend from the spring line of the pipe to at least 300 mm above the obvert of the pipe. The material should be placed in maximum 300 mm thick lifts and compacted to a minimum of 95% of its SPMDD.

Generally, it should be possible to re-use the moist (not wet) brown silty sand above the cover material if the excavation and filling operations are carried out in dry weather conditions. Wet silty sand materials will be difficult to re-use, as the high water contents make compacting impractical without an extensive drying period.

Where hard surface areas are considered above the trench backfill, the trench backfill material within the frost zone (about 1.8 m below finished grade) should match the soils exposed at the trench walls to minimize differential frost heaving. The trench backfill should be placed in maximum 300 mm thick loose lifts and compacted to a minimum of 95% of the material's SPMDD.

## 6.5 Groundwater Control

The contractor should be prepared to direct water away from all bearing surfaces and subgrades, regardless of the source, to prevent disturbance to the founding medium. It is anticipated that groundwater infiltration into the excavations should be moderate, if encountered, and controllable using open sumps.

A temporary Ministry of the Environment, Conservation and Parks (MECP) permit to take water (PTTW) may be required for this project if more than 400,000 L/day of ground and/or surface water is to be pumped during the construction phase. A minimum of 4 to 5 months should be allowed for completion of the PTTW application package and issuance of the permit by the MECP.

For typical ground or surface water volumes being pumped during the construction phase, between 50,000 to 400,000 L/day, it is required to register on the Environmental Activity and Sector Registry (EASR). A minimum of two to four weeks should be allotted for completion of the EASR registration and the Water Taking and Discharge Plan to be prepared by a Qualified Person as stipulated under O.Reg. 63/16. If a project qualifies for a PTTW based upon anticipated conditions, an EASR will not be allowed as a temporary dewatering measure while awaiting the MECP review of the PTTW application.

## 6.6 Winter Construction

Precautions must be taken if winter construction is considered for this project.

The subsoil conditions for the silty-clay area of the site consist of frost susceptible materials. In the presence of water and freezing conditions, ice could form within the soil mass. Heaving and settlement upon thawing could occur.

In the event of construction during below zero temperatures, the founding stratum should be protected from freezing temperatures by the use of straw, propane heaters and tarpaulins or other suitable means. In this regard, the base of the excavations should be insulated from sub-zero temperatures immediately upon exposure and until such time as heat is adequately supplied to the building and the footings are protected with sufficient soil cover to prevent freezing at founding level.

Trench excavations and pavement construction are also difficult activities to complete during freezing conditions without introducing frost in the subgrade or in the excavation walls and bottoms. Precautions should be taken if such activities are to be carried out during freezing conditions. Additional information could be provided, if required.

# 7.0 Recommendations

It is a requirement for the foundation design data provided herein to be applicable that the following material testing and observation program be performed by the geotechnical consultant.

- ❑ Review detailed grading plan(s) from a geotechnical perspective.
- ❑ Observation of all bearing surfaces prior to the placement of concrete.
- ❑ Sampling and testing of the concrete and fill materials used.
- ❑ Periodic observation of the condition of unsupported excavation side slopes in excess of 3 m in height, if applicable.
- ❑ Observation of all subgrades prior to backfilling
- ❑ Field density tests to determine the level of compaction achieved.
- ❑ Sampling and testing of the bituminous concrete including mix design reviews.

A report confirming that these works have been conducted in general accordance with our recommendations could be issued upon the completion of a satisfactory inspection program by the geotechnical consultant.

# 8.0 Statement of Limitations

The recommendations made in this report are in accordance with our present understanding of the project. We request that we be permitted to review our recommendations when the grading plan, drawings and specifications are completed.

A geotechnical investigation is a limited sampling of a site. The recommendations are based on information gathered at the specific test locations and can only be extrapolated to an undefined limited area around the test locations. Should any conditions at the site be encountered which differ from those at the test locations, Paterson requests immediate notification in order to permit reassessment of our recommendations.

The present report applies only to the project described in this document. Use of this report for purposes other than those described herein or by person(s) other than Mattamy Homes or their agent(s) is not authorized without review by this firm for the applicability of our recommendations to the altered use of the report.

**Paterson Group Inc.**




Nathan F. S. Christie, P.Eng. Faisal I. Abou-Seido, P.Eng.

**Report Distribution:**

- ❑ Mattamy Homes (3 copies)
- ❑ Paterson Group (1 copy)

# APPENDIX 1

**SOIL PROFILE AND TEST DATA SHEETS**

**SYMBOLS AND TERMS**

# patersongroup Consulting Engineers

154 Colonnade Road South, Ottawa, Ontario K2E 7J5

# SOIL PROFILE AND TEST DATA

**Geotechnical Investigation**
**Half Moon Bay South**
**Ottawa, Ontario**

**DATUM** Ground surface elevations provided by Agrodrain Systems Limited Contractors (ASL)

**FILE NO.** PG4803

**REMARKS**

**HOLE NO.** TP 1-19

**BORINGS BY** Excavator **DATE** 2019 February 5

| SOIL DESCRIPTION | STRATA PLOT | SAMPLE TYPE | SAMPLE NUMBER | SAMPLE % RECOVERY | SAMPLE N VALUE or RQD | DEPTH (m) | ELEV. (m) | Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone ○ Water Content % | Piezometer Construction |
|---|---|---|---|---|---|---|---|---|---|
| **GROUND SURFACE** | | | | | | 0 | 104.31 | | |
| **FILL:** Reddish brown silt and sand, some cobbles, trace topsoil | | | | | | | | | |
| 0.30 | | | | | | | | | |
| Loose to compact, light brown coarse **SILTY SAND** | | G | 1 | | | 1 | 103.31 | | |
| 1.50 | | | | | | | | | |
| | | G | 2 | | | 2 | 102.31 | | |
| Compact, light greyish brown fine **SILTY SAND** | | G | 3 | | | | | | |
| | | G | 4 | | | 3 | 101.31 | | |
| | | G | 5 | | | 4 | 100.31 | | |
| 4.30 | | | | | | | | | |
| Compact, grey **SILTY SAND** | | G | 6 | | | | | | |
| 4.50 | | | | | | | | | |
| End of Test Pit | | | | | | | | | |
| (TP dry upon completion) | | | | | | | | | |

20 40 60 80

20 40 60 80 100

**Shear Strength (kPa)**

▲ Undisturbed △ Remoulded

# patersongroup Consulting Engineers

154 Colonnade Road South, Ottawa, Ontario K2E 7J5

## SOIL PROFILE AND TEST DATA

**Geotechnical Investigation**
**Half Moon Bay South**
**Ottawa, Ontario**

**DATUM** Ground surface elevations provided by Agrodrain Systems Limited Contractors (ASL)

**FILE NO.** PG4803

**REMARKS**

**HOLE NO.** TP 2-19

**BORINGS BY** Excavator **DATE** 2019 February 5

| SOIL DESCRIPTION | STRATA PLOT | SAMPLE TYPE | SAMPLE NUMBER | SAMPLE % RECOVERY | SAMPLE N VALUE or RQD | DEPTH (m) | ELEV. (m) | Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone ○ Water Content % | Piezometer Construction |
|---|---|---|---|---|---|---|---|---|---|
| **GROUND SURFACE** | | | | | | | | | |
| Brown **SILTY SAND**, trace topsoil 0.15 | | G | 1 | | | 0 | 101.36 | | |
| | | G | 2 | | | 1 | 100.36 | | |
| Loose to compact, light brown **SILTY SAND** | | G | 3 | | | 2 | 99.36 | | |
| | | G | 4 | | | | | | |
| | | G | 5 | | | 3 | 98.36 | | |
| 4.10 | | G | 6 | | | 4 | 97.36 | | |
| End of Test Pit | | | | | | | | | |
| (TP dry upon completion) | | | | | | | | | |

Pen. Resist. Blows/0.3m: 20 40 60 80

Water Content %: 20 40 60 80

Shear Strength (kPa): 20 40 60 80 100

▲ Undisturbed △ Remoulded

# patersongroup Consulting Engineers

154 Colonnade Road South, Ottawa, Ontario K2E 7J5

## SOIL PROFILE AND TEST DATA

**Geotechnical Investigation**
**Half Moon Bay South**
**Ottawa, Ontario**

**DATUM** Ground surface elevations provided by Agrodrain Systems Limited Contractors (ASL)

**FILE NO.** PG4803

**REMARKS**

**HOLE NO.** TP 3-19

**BORINGS BY** Excavator **DATE** 2019 February 5

| SOIL DESCRIPTION | STRATA PLOT | SAMPLE TYPE | SAMPLE NUMBER | SAMPLE % RECOVERY | SAMPLE N VALUE or RQD | DEPTH (m) | ELEV. (m) | Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone ○ Water Content % | Piezometer Construction |
|---|---|---|---|---|---|---|---|---|---|
| **GROUND SURFACE** | | | | | | 0 | 101.16 | | |
| **FILL:** Dark brown clayey silt with sand, topsoil and gravel | | G | 1 | | | | | | |
| 0.50 | | | | | | | | | |
| Loose, brown **SILTY SAND** with clay and some gravel | | G | 2 | | | 1 | 100.16 | | |
| 1.50 | | | | | | | | | |
| **GLACIAL TILL:** Coarse, brown to grey sand with gravel, cobbles and boulders | | G | 3 | | | 2 | 99.16 | | |
| | | G | 4 | | | | | | |
| 3.00 | | G | 5 | | | 3 | 98.16 | | |
| End of Borehole | | | | | | | | | |
| Refusal to excavation on boulder @ 3m depth | | | | | | | | | |
| (TP dry upon completion) | | | | | | | | | |

Pen. Resist. Blows/0.3m: 20 40 60 80

Water Content %: 20 40 60 80

Shear Strength (kPa): 20 40 60 80 100

▲ Undisturbed △ Remoulded

# patersongroup Consulting Engineers

154 Colonnade Road South, Ottawa, Ontario K2E 7J5

## SOIL PROFILE AND TEST DATA

**Geotechnical Investigation**
**Half Moon Bay South**
**Ottawa, Ontario**

**DATUM** Ground surface elevations provided by Agrodrain Systems Limited Contractors (ASL)

**FILE NO.** PG4803

**REMARKS**

**HOLE NO.** TP 4-19

**BORINGS BY** Excavator **DATE** 2019 February 5

| SOIL DESCRIPTION | STRATA PLOT | SAMPLE TYPE | SAMPLE NUMBER | SAMPLE % RECOVERY | SAMPLE N VALUE or RQD | DEPTH (m) | ELEV. (m) | Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone ○ Water Content % | Piezometer Construction |
|---|---|---|---|---|---|---|---|---|---|
| **GROUND SURFACE** | | | | | | 0 | 104.60 | | |
| Loose, light brown **SAND**, trace clay and topsoil | | | | | | | | | |
| 0.15 | | | | | | | | | |
| Loose, light brown **SILTY SAND**, trace clay | | G | 1 | | | 1 | 103.60 | | |
| 1.40 | | | | | | | | | |
| Compact, light brown **SILTY SAND** with trace silt | | G | 2 | | | 2 | 102.60 | | |
| | | G | 3 | | | | | | |
| | | G | 4 | | | 3 | 101.60 | | |
| | | G | 5 | | | | | | |
| 4.10 | | G | 6 | | | 4 | 100.60 | | |
| End of Test Pit | | | | | | | | | |
| (TP dry upon completion) | | | | | | | | | |

Pen. Resist. Blows/0.3m: 20 40 60 80

Water Content %: 20 40 60 80

Shear Strength (kPa): 20 40 60 80 100

▲ Undisturbed △ Remoulded

# patersongroup Consulting Engineers

154 Colonnade Road South, Ottawa, Ontario K2E 7J5

## SOIL PROFILE AND TEST DATA

**Geotechnical Investigation**
**Half Moon Bay South**
**Ottawa, Ontario**

**DATUM** Ground surface elevations provided by Agrodrain Systems Limited Contractors (ASL)

**FILE NO.** PG4803

**REMARKS**

**HOLE NO.** TP 5-19

**BORINGS BY** Excavator **DATE** 2019 February 5

| SOIL DESCRIPTION | STRATA PLOT | SAMPLE TYPE | SAMPLE NUMBER | SAMPLE % RECOVERY | SAMPLE N VALUE or RQD | DEPTH (m) | ELEV. (m) | Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone ○ Water Content % | Piezometer Construction |
|---|---|---|---|---|---|---|---|---|---|
| **GROUND SURFACE** | | | | | | 0 | 105.52 | | |
| **FILL:** Silty sand with cobbles, trace clay | | | | | | | | | |
| 0.30 | | | | | | | | | |
| Loose to compact, light brown **SILTY SAND** | | G | 1 | | | 1 | 104.52 | | |
| | | G | 2 | | | 2 | 103.52 | | |
| | | G | 3 | | | | | | |
| | | G | 4 | | | 3 | 102.52 | | |
| | | G | 5 | | | 4 | 101.52 | | |
| 4.50 | | G | 6 | | | | | | |
| End of Test Pit | | | | | | | | | |
| (TP dry upon completion) | | | | | | | | | |

Pen. Resist. Blows/0.3m: 20 40 60 80

Shear Strength (kPa): 20 40 60 80 100

▲ Undisturbed △ Remoulded

# patersongroup Consulting Engineers

154 Colonnade Road South, Ottawa, Ontario K2E 7J5

## SOIL PROFILE AND TEST DATA

**Geotechnical Investigation**
**Half Moon Bay South**
**Ottawa, Ontario**

**DATUM** Ground surface elevations provided by Agrodrain Systems Limited Contractors (ASL)

**FILE NO.** PG4803

**REMARKS**

**HOLE NO.** TP 6-19

**BORINGS BY** Excavator **DATE** 2019 February 5

| SOIL DESCRIPTION | STRATA PLOT | SAMPLE TYPE | SAMPLE NUMBER | SAMPLE % RECOVERY | SAMPLE N VALUE or RQD | DEPTH (m) | ELEV. (m) | Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone ○ Water Content % | Piezometer Construction |
|---|---|---|---|---|---|---|---|---|---|
| **GROUND SURFACE** | | | | | | 0 | 104.12 | 20 40 60 80 | |
| **TOPSOIL** 0.30 | | G | 1 | | | | | | |
| **FILL:** Brown silty sand with clay, gravel and cobbles 0.60 | | G | 2 | | | 1 | 103.12 | | |
| Light brown, loose to compact **SAND**, trace silt | | G | 3 | | | 2 | 102.12 | | |
| | | G | 4 | | | | | | |
| | | G | 5 | | | 3 | 101.12 | | |
| | | G | 6 | | | 4 | 100.12 | | |
| | | G | 7 | | | | | | |
| 5.00 End of Test Pit (TP dry upon completion) | | | | | | 5 | 99.12 | 20 40 60 80 100 **Shear Strength (kPa)** ▲ Undisturbed △ Remoulded | |

# patersongroup Consulting Engineers

154 Colonnade Road South, Ottawa, Ontario K2E 7J5

## SOIL PROFILE AND TEST DATA

**Geotechnical Investigation**
**Half Moon Bay South**
**Ottawa, Ontario**

**DATUM** Ground surface elevations provided by Agrodrain Systems Limited Contractors (ASL)

**FILE NO.** PG4803

**REMARKS**

**HOLE NO.** TP 7-19

**BORINGS BY** Excavator **DATE** 2019 February 5

| SOIL DESCRIPTION | STRATA PLOT | SAMPLE TYPE | SAMPLE NUMBER | SAMPLE % RECOVERY | SAMPLE N VALUE or RQD | DEPTH (m) | ELEV. (m) | Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone ○ Water Content % | Piezometer Construction |
|---|---|---|---|---|---|---|---|---|---|
| **GROUND SURFACE** | | | | | | 0 | 101.50 | | |
| **TOPSOIL** 0.30 | | G | 1 | | | | | | |
| **GLACIAL TILL:** Brown silty sand with cobbles and boulders 0.60 | | G | 2 | | | 1 | 100.50 | | |
| **GLACIAL TILL:** Brown sand with cobbles and boulders 1.80 | | G | 3 | | | | | | |
| **GLACIAL TILL:** Dense silt with gravel, trace sand 2.40 | | G | 4 | | | 2 | 99.50 | | |
| | | G | 5 | | | | | | |
| | | G | 6 | | | | | | |
| **GLACIAL TILL:** Light brown, fine sand with cobbles and boulders | | G | 7 | | | 3 | 98.50 | | |
| 4.00 | | G | 8 | | | 4 | 97.50 | | |
| End of Test Pit | | | | | | | | | |
| (TP dry upon completion) | | | | | | | | | |

Pen. Resist. Blows/0.3m: ○ Water Content % — 20 40 60 80

Shear Strength (kPa): 20 40 60 80 100

▲ Undisturbed △ Remoulded

# patersongroup Consulting Engineers

154 Colonnade Road South, Ottawa, Ontario K2E 7J5

## SOIL PROFILE AND TEST DATA

**Geotechnical Investigation**
**Half Moon Bay South**
**Ottawa, Ontario**

**DATUM** Ground surface elevations provided by Agrodrain Systems Limited Contractors (ASL)

**FILE NO.** PG4803

**REMARKS**

**HOLE NO.** TP 8-19

**BORINGS BY** Excavator **DATE** 2019 February 5

| SOIL DESCRIPTION | STRATA PLOT | SAMPLE TYPE | SAMPLE NUMBER | SAMPLE % RECOVERY | SAMPLE N VALUE or RQD | DEPTH (m) | ELEV. (m) | Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone ○ Water Content % | Piezometer Construction |
|---|---|---|---|---|---|---|---|---|---|
| **GROUND SURFACE** | | | | | | 0 | 102.41 | | |
| **FILL:** Brown silty clay with sand, trace topsoil | | | | | | | | | |
| 0.60 | | | | | | | | | |
| **FILL:** Grey silty clay with sand | | G | 1 | | | | | | |
| 0.90 | | | | | | 1 | 101.41 | | |
| **GLACIAL TILL:** Sand with cobbles and boulders | | G | 2 | | | | | | |
| | | | | | | 2 | 100.41 | | |
| | | G | 3 | | | | | | |
| 2.80 | | | | | | | | | |
| End of Test Pit | | | | | | | | | |
| (TP dry upon completion) | | | | | | | | | |

Pen. Resist. Blows/0.3m: ● 50 mm Dia. Cone; ○ Water Content %
20 40 60 80

20 40 60 80 100
Shear Strength (kPa)
▲ Undisturbed △ Remoulded

# patersongroup Consulting Engineers

154 Colonnade Road South, Ottawa, Ontario K2E 7J5

## SOIL PROFILE AND TEST DATA

**Geotechnical Investigation**
**Barrhaven South Urban Expansion**
**Ottawa, Ontario**

**DATUM** Geodetic elevations interpolated from City of Ottawa basemap.

**FILE NO.** PG3607

**REMARKS**

**HOLE NO.** TP 1-15

**BORINGS BY** Backhoe **DATE** December 2, 2015

| SOIL DESCRIPTION | STRATA PLOT | SAMPLE TYPE | SAMPLE NUMBER | SAMPLE % RECOVERY | SAMPLE N VALUE or RQD | DEPTH (m) | ELEV. (m) | Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone ○ Water Content % | Piezometer Construction |
|---|---|---|---|---|---|---|---|---|---|
| **GROUND SURFACE** | | | | | | | | | |
| **TOPSOIL** 0.10 | | G | 1 | | | 0 | 105.10 | | |
| Compact, brown **SILTY SAND**, trace boulders and cobbles | | G | 2 | | | 1 | 104.10 | | |
| | | | | | | 2 | 103.10 | | |
| 3.00 End of Test Pit | | | | | | 3 | 102.10 | | |
| (TP dry upon completion) | | | | | | | | | |

Pen. Resist. Blows/0.3m: ● 50 mm Dia. Cone; ○ Water Content %; 20 40 60 80

Shear Strength (kPa): 20 40 60 80 100

▲ Undisturbed △ Remoulded

# patersongroup Consulting Engineers

154 Colonnade Road South, Ottawa, Ontario K2E 7J5

## SOIL PROFILE AND TEST DATA

**Geotechnical Investigation**
**Barrhaven South Urban Expansion**
**Ottawa, Ontario**

**DATUM** Geodetic elevations interpolated from City of Ottawa basemap.

**FILE NO.** PG3607

**REMARKS**

**HOLE NO.** TP 2-15

**BORINGS BY** Backhoe **DATE** December 2, 2015

| SOIL DESCRIPTION | STRATA PLOT | SAMPLE TYPE | SAMPLE NUMBER | SAMPLE % RECOVERY | SAMPLE N VALUE or RQD | DEPTH (m) | ELEV. (m) | Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone ○ Water Content % | Piezometer Construction |
|---|---|---|---|---|---|---|---|---|---|
| **GROUND SURFACE** | | | | | | | | | |
| **TOPSOIL** 0.10 | | | | | | 0 | 106.80 | | |
| Compact, brown **SILTY SAND** | | G | 1 | | | 1 | 105.80 | | |
| | | G | 2 | | | 2 | 104.80 | | |
| 3.00 End of Test Pit | | | | | | 3 | 103.80 | | |
| (TP dry upon completion) | | | | | | | | | |

Pen. Resist. Blows/0.3m: 20 40 60 80

Water Content %: 20 40 60 80

Shear Strength (kPa): 20 40 60 80 100

▲ Undisturbed △ Remoulded

# patersongroup Consulting Engineers

154 Colonnade Road South, Ottawa, Ontario K2E 7J5

## SOIL PROFILE AND TEST DATA

**Geotechnical Investigation**
**Barrhaven South Urban Expansion**
**Ottawa, Ontario**

**DATUM** Geodetic elevations interpolated from City of Ottawa basemap.

**FILE NO.** PG3607

**REMARKS**

**HOLE NO.** BH 5-15

**BORINGS BY** CME 75 Power Auger **DATE** December 10, 2015

| SOIL DESCRIPTION | STRATA PLOT | SAMPLE TYPE | SAMPLE NUMBER | SAMPLE % RECOVERY | SAMPLE N VALUE or RQD | DEPTH (m) | ELEV. (m) |
|---|---|---|---|---|---|---|---|
| **GROUND SURFACE** | | | | | | 0 | 108.75 |
| | | SS | 1 | 42 | 13 | 1 | 107.75 |
| | | SS | 2 | 25 | 21 | 2 | 106.75 |
| | | SS | 3 | 33 | 5 | 3 | 105.75 |
| | | SS | 4 | 42 | 4 | 4 | 104.75 |
| **FILL:** Grey silty sand with clay, gravel and wood | | SS | 5 | 42 | 3 | 5 | 103.75 |
| | | SS | 6 | 42 | 3 | 6 | 102.75 |
| | | SS | 7 | 17 | 5 | 7 | 101.75 |
| | | SS | 8 | 25 | 37 | 8 | 100.75 |
| | | SS | 9 | 0 | 50+ | 9 | 99.75 |
| | | SS | 10 | 58 | 9 | | |
| | | SS | 11 | 0 | 1 | | |
| 9.14 | | | | | | | |
| End of Borehole<br><br>(BH dry to 9.14m depth - July 28, 2016) | | | | | | | |

**Pen. Resist. Blows/0.3m**
● 50 mm Dia. Cone
○ Water Content %

20 40 60 80

Monitoring Well Construction

20 40 60 80 100
**Shear Strength (kPa)**
▲ Undisturbed △ Remoulded

# patersongroup Consulting Engineers

154 Colonnade Road South, Ottawa, Ontario K2E 7J5

## SOIL PROFILE AND TEST DATA

**Geotechnical Investigation**
**Barrhaven South Urban Expansion**
**Ottawa, Ontario**

**DATUM** Geodetic elevations interpolated from City of Ottawa basemap.

**FILE NO.** PG3607

**REMARKS**

**HOLE NO.** BH 6-15

**BORINGS BY** CME 75 Power Auger **DATE** December 3, 2015

| SOIL DESCRIPTION | STRATA PLOT | SAMPLE TYPE | SAMPLE NUMBER | SAMPLE % RECOVERY | SAMPLE N VALUE or RQD | DEPTH (m) | ELEV. (m) | Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone ○ Water Content % | Piezometer Construction |
|---|---|---|---|---|---|---|---|---|---|
| **GROUND SURFACE** | | | | | | 0 | 102.59 | | |
| | | AU | 1 | | | | | | |
| Dense to very dense, grey-brown **SILTY SAND** with gravel, cobbles and boulders | | SS | 2 | 75 | 31 | 1 | 101.59 | | |
| | | SS | 3 | 100 | 50+ | 2 | 100.59 | | |
| 2.29 | | | | | | | | | |
| | | SS | 4 | 83 | 27 | 3 | 99.59 | | |
| | | SS | 5 | 58 | 27 | | | | |
| | | SS | 6 | 67 | 26 | 4 | 98.59 | | |
| Compact to dense, grey-brown **SILTY SAND** | | SS | 7 | 71 | 31 | 5 | 97.59 | | |
| | | SS | 8 | 67 | 30 | 6 | 96.59 | | |
| | | SS | 9 | 63 | 30 | | | | |
| | | SS | 10 | 75 | 25 | 7 | 95.59 | | |
| | | SS | 11 | 100 | 19 | 8 | 94.59 | | |
| | | SS | 12 | 100 | 15 | | | | |
| | | SS | 13 | 100 | 15 | 9 | 93.59 | | |
| 9.75 | | | | | | | | | |
| End of Borehole | | | | | | | | | |
| (BH dry to4.40m depth - July 28, 2016) | | | | | | | | | |

Pen. Resist. Blows/0.3m: ● 50 mm Dia. Cone; ○ Water Content %
20 40 60 80

Shear Strength (kPa)
20 40 60 80 100
▲ Undisturbed △ Remoulded

# patersongroup Consulting Engineers

154 Colonnade Road South, Ottawa, Ontario K2E 7J5

# SOIL PROFILE AND TEST DATA

**Geotechnical Investigation**
**Barrhaven South Urban Expansion**
**Ottawa, Ontario**

**DATUM** Geodetic elevations interpolated from City of Ottawa basemap.


**FILE NO.** PG3607

**REMARKS**

**HOLE NO.** BH12-15

**BORINGS BY** CME 75 Power Auger **DATE** December 2, 2015

| SOIL DESCRIPTION | STRATA PLOT | SAMPLE TYPE | SAMPLE NUMBER | SAMPLE % RECOVERY | SAMPLE N VALUE or RQD | DEPTH (m) | ELEV. (m) |
|---|---|---|---|---|---|---|---|
| **GROUND SURFACE** | | | | | | 0 | 105.26 |
| | | AU | 1 | | | | |
| Dense to very dense, brown **SILTY SAND** with gravel, cobbles and boulders | | SS | 2 | 88 | 42 | 1 | 104.26 |
| | | SS | 3 | 33 | 50+ | | |
| - rootlets in upper 100mm | | | | | | 2 | 103.26 |
| | | SS | 4 | 67 | 50+ | | |
| | | | | | | 3 | 102.26 |
| 3.35 | | SS | 5 | 83 | 58 | | |
| | | SS | 6 | 100 | 31 | 4 | 101.26 |
| | | SS | 7 | 75 | 47 | | |
| Dense, brown **SILTY SAND** | | SS | 8 | 92 | 30 | 5 | 100.26 |
| | | SS | 9 | 79 | 31 | | |
| | | SS | 10 | 75 | 35 | 6 | 99.26 |
| - grey by 7.6m depth | | SS | 11 | 92 | 34 | | |
| | | SS | 12 | 100 | 32 | 7 | 98.26 |
| | | SS | 13 | 88 | 37 | | |
| 9.75 | | | | | | 8 | 97.26 |
| End of Borehole | | | | | | | |
| (BH dry to 7.79m depth - July 28, 2016) | | | | | | 9 | 96.26 |



# patersongroup

Consulting Engineers

154 Colonnade Road South, Ottawa, Ontario K2E 7J5

## SOIL PROFILE AND TEST DATA

**Hydrogeological Investigation**
**Residential Development - Half Moon Bay South**
**Ottawa, Ontario**

**DATUM** Ground surface elevations provided by J.D. Barnes Limited.


**FILE NO.** PG3450

**REMARKS**

**HOLE NO.** BH 5-15

**BORINGS BY** CME 55 Power Auger **DATE** March 6, 2015

| SOIL DESCRIPTION | STRATA PLOT | SAMPLE TYPE | SAMPLE NUMBER | SAMPLE % RECOVERY | SAMPLE N VALUE or RQD | DEPTH (m) | ELEV. (m) |
|---|---|---|---|---|---|---|---|
| **GROUND SURFACE** | | | | | | 0 | 103.02 |
| **FILL:** Dark brown silty fine sand with topsoil and gravel | | SS | 1 | 100 | 61 | 1 | 102.02 |
| | | SS | 2 | 42 | 5 | 2 | 101.02 |
| | | SS | 3 | 67 | 3 | 3 | 100.02 |
| 3.50 | | SS | 4 | 67 | 6 | | |
| Dense, brown **SILTY FINE SAND,** with gravel, trace clay | | SS | 5 | 100 | 49 | 4 | 99.02 |
| 4.42 | | SS | 6 | 92 | 46 | 5 | 98.02 |
| Dense to compact, light brown **SILTY FINE SAND** | | SS | 7 | 83 | 38 | 6 | 97.02 |
| - trace to some medium sand by 6.1m depth | | SS | 8 | 67 | 40 | | |
| - running sand by 7.0m depth | | SS | 9 | 83 | 26 | 7 | 96.02 |
| 7.62 | | | | | | | |
| End of Borehole | | | | | | | |
| (GWL @ 7.15m-March 23, 2015) | | | | | | | |
| (GWL @ 6.80m-April 21, 2015) | | | | | | | |
| (GWL @ 6.76m-May 12, 2015) | | | | | | | |
| High groundwater infiltration rate | | | | | | | |



# patersongroup

Consulting Engineers

154 Colonnade Road South, Ottawa, Ontario K2E 7J5

## SOIL PROFILE AND TEST DATA

**Hydrogeological Investigation**
**Residential Development - Half Moon Bay South**
**Ottawa, Ontario**

**DATUM** Ground surface elevations provided by J.D. Barnes Limited.


**FILE NO.** PG3450

**REMARKS**

**HOLE NO.** BH 6-15

**BORINGS BY** CME 55 Power Auger **DATE** March 5, 2015

| SOIL DESCRIPTION | STRATA PLOT | SAMPLE TYPE | SAMPLE NUMBER | SAMPLE % RECOVERY | SAMPLE N VALUE or RQD | DEPTH (m) | ELEV. (m) |
|---|---|---|---|---|---|---|---|
| **GROUND SURFACE** | | | | | | 0 | 101.42 |
| **FILL:** Brown silty clay with sand, trace gravel and topsoil | | | | | | | |
| 0.60 | | | | | | | |
| Very stiff, brown **SILTY CLAY** | | SS | 1 | 42 | 14 | 1 | 100.42 |
| | | SS | 2 | 67 | 12 | 2 | 99.42 |
| - 75mm thick sand seams at 2.1 and 2.7m depths | | SS | 3 | 67 | 7 | | |
| 3.20 | | | | | | 3 | 98.42 |
| Compact to dense, brown **SILTY FINE SAND,** trace gravel | | SS | 4 | 92 | 17 | | |
| - running sand at 3.2 to 4.1m depth | | | | | | | |
| 4.11 | | SS | 5 | 92 | 50 | 4 | 97.42 |
| **GLACIAL TILL:** Very dense, brown to grey silty sand with clay, gravel, trace cobbles | | SS | 6 | 92 | 52 | | |
| 5.18 | | | | | | 5 | 96.42 |
| End of Borehole | | | | | | | |
| (GWL @ 2.93m-March 23, 2015) | | | | | | | |
| (GWL @ 0.99m-April 21, 2015) | | | | | | | |
| (GWL @ 1.45m-May 12, 2015) | | | | | | | |
| High groundwater infiltration rate | | | | | | | |



# SYMBOLS AND TERMS

## SOIL DESCRIPTION

Behavioural properties, such as structure and strength, take precedence over particle gradation in describing soils. Terminology describing soil structure are as follows:

| | | |
|---|---|---|
| Desiccated | - | having visible signs of weathering by oxidation of clay minerals, shrinkage cracks, etc. |
| Fissured | - | having cracks, and hence a blocky structure. |
| Varved | - | composed of regular alternating layers of silt and clay. |
| Stratified | - | composed of alternating layers of different soil types, e.g. silt and sand or silt and clay. |
| Well-Graded | - | Having wide range in grain sizes and substantial amounts of all intermediate particle sizes (see Grain Size Distribution). |
| Uniformly-Graded | - | Predominantly of one grain size (see Grain Size Distribution). |

The standard terminology to describe the strength of cohesionless soils is the relative density, usually inferred from the results of the Standard Penetration Test (SPT) 'N' value. The SPT N value is the number of blows of a 63.5 kg hammer, falling 760 mm, required to drive a 51 mm O.D. split spoon sampler 300 mm into the soil after an initial penetration of 150 mm.

| Relative Density | 'N' Value | Relative Density % |
|---|---|---|
| Very Loose | <4 | <15 |
| Loose | 4-10 | 15-35 |
| Compact | 10-30 | 35-65 |
| Dense | 30-50 | 65-85 |
| Very Dense | >50 | >85 |

The standard terminology to describe the strength of cohesive soils is the consistency, which is based on the undisturbed undrained shear strength as measured by the in situ or laboratory vane tests, penetrometer tests, unconfined compression tests, or occasionally by Standard Penetration Tests.

| Consistency | Undrained Shear Strength (kPa) | 'N' Value |
|---|---|---|
| Very Soft | <12 | <2 |
| Soft | 12-25 | 2-4 |
| Firm | 25-50 | 4-8 |
| Stiff | 50-100 | 8-15 |
| Very Stiff | 100-200 | 15-30 |
| Hard | >200 | >30 |

# SYMBOLS AND TERMS (continued)

## SOIL DESCRIPTION (continued)

Cohesive soils can also be classified according to their “sensitivity”. The sensitivity is the ratio between the undisturbed undrained shear strength and the remoulded undrained shear strength of the soil.

Terminology used for describing soil strata based upon texture, or the proportion of individual particle sizes present is provided on the Textural Soil Classification Chart at the end of this information package.

## ROCK DESCRIPTION

The structural description of the bedrock mass is based on the Rock Quality Designation (RQD).

The RQD classification is based on a modified core recovery percentage in which all pieces of sound core over 100 mm long are counted as recovery. The smaller pieces are considered to be a result of closely-spaced discontinuities (resulting from shearing, jointing, faulting, or weathering) in the rock mass and are not counted. RQD is ideally determined from NXL size core. However, it can be used on smaller core sizes, such as BX, if the bulk of the fractures caused by drilling stresses (called “mechanical breaks”) are easily distinguishable from the normal in situ fractures.

| RQD % | ROCK QUALITY |
|---|---|
| 90-100 | Excellent, intact, very sound |
| 75-90 | Good, massive, moderately jointed or sound |
| 50-75 | Fair, blocky and seamy, fractured |
| 25-50 | Poor, shattered and very seamy or blocky, severely fractured |
| 0-25 | Very poor, crushed, very severely fractured |

## SAMPLE TYPES

| | | |
|---|---|---|
| SS | - | Split spoon sample (obtained in conjunction with the performing of the Standard Penetration Test (SPT)) |
| TW | - | Thin wall tube or Shelby tube |
| PS | - | Piston sample |
| AU | - | Auger sample or bulk sample |
| WS | - | Wash sample |
| RC | - | Rock core sample (Core bit size AXT, BXL, etc.). Rock core samples are obtained with the use of standard diamond drilling bits. |

## SYMBOLS AND TERMS (continued)

### GRAIN SIZE DISTRIBUTION

| | | |
|---|---|---|
| MC% | - | Natural moisture content or water content of sample, % |
| LL | - | Liquid Limit, % (water content above which soil behaves as a liquid) |
| PL | - | Plastic limit, % (water content above which soil behaves plastically) |
| PI | - | Plasticity index, % (difference between LL and PL) |
| Dxx | - | Grain size which xx% of the soil, by weight, is of finer grain sizes<br>These grain size descriptions are not used below 0.075 mm grain size |
| D10 | - | Grain size at which 10% of the soil is finer (effective grain size) |
| D60 | - | Grain size at which 60% of the soil is finer |
| Cc | - | Concavity coefficient = $(D30)^2$ / (D10 x D60) |
| Cu | - | Uniformity coefficient = D60 / D10 |

Cc and Cu are used to assess the grading of sands and gravels:
Well-graded gravels have: $1 < Cc < 3$ and $Cu > 4$
Well-graded sands have: $1 < Cc < 3$ and $Cu > 6$
Sands and gravels not meeting the above requirements are poorly-graded or uniformly-graded.
Cc and Cu are not applicable for the description of soils with more than 10% silt and clay
(more than 10% finer than 0.075 mm or the #200 sieve)

### CONSOLIDATION TEST


| | | |
|---|---|---|
| $p'_o$ | - | Present effective overburden pressure at sample depth |
| $p'_c$ | - | Preconsolidation pressure of (maximum past pressure on) sample |
| Ccr | - | Recompression index (in effect at pressures below $p'_c$) |
| Cc | - | Compression index (in effect at pressures above $p'_c$) |
| OC Ratio | | Overconsolidaton ratio = $p'_c / p'_o$ |
| Void Ratio | | Initial sample void ratio = volume of voids / volume of solids |
| Wo | - | Initial water content (at start of consolidation test) |

### PERMEABILITY TEST

| | | |
|---|---|---|
| k | - | Coefficient of permeability or hydraulic conductivity is a measure of the ability of water to flow through the sample. The value of k is measured at a specified unit weight for (remoulded) cohesionless soil samples, because its value will vary with the unit weight or density of the sample during the test. |


# SYMBOLS AND TERMS (continued)

## STRATA PLOT





## MONITORING WELL AND PIEZOMETER CONSTRUCTION

MONITORING WELL CONSTRUCTION




PIEZOMETER CONSTRUCTION



# APPENDIX 2


**FIGURE 1 - KEY PLAN**

**DRAWING PG4803-1 - TEST HOLE LOCATION PLAN**




# FIGURE 1

## KEY PLAN





**patersongroup**
consulting engineers

154 Colonnade Road South
Ottawa, Ontario K2E 7J5
Tel: (613) 226-7381 Fax: (613) 226-6344


| NO. | REVISIONS | DATE | INITIAL |
|---|---|---|---|
| | | | |

MATTAMY HOMES

GEOTECHNICAL INVESTIGATION
HALF MOON BAY SOUTH - GREENBANK ROAD

OTTAWA, ONTARIO

Title:

# TEST HOLE LOCATION PLAN

| | |
|---|---|
| Scale: 1:1250 | Date: 01/2019 |
| Drawn by: MPG | Report No.: PG4803-1 |
| Checked by: NC | PG4803-1 |
| Approved by: DJG | Revision No.: |

p:\autocad drawings\geotechnical\pg48xx\pg4803\pg4803-1 thlp.dwg

Appendix E : Drawings
15/2/2019 12:00:00 AM

# Appendix E : DRAWINGS

OUTLET TRUNK STORM SEWER TO JOCK RIVER
DISTANCE FROM MH205 TO JOCK RIVER 1:100 YR FLOOD PLAIN LIMIT IS APPROXIMATELY 815 M
INVERT AT MH205 = 93.42 M
INVERT AT JOCK RIVER 100 YR FLOOD PLAIN = APPROXIMATELY 92.0 M
OUTLET SEWER = 825 MM DIA. @ 0.17 %

TO CLARK POND

CAMBRIAN RD

BORRISOKANE RD

FUTURE COLLECTOR RD

HIGHWAY 416

TRAIL RD

BARNSDALE RD

DRUMMOND SWM POND

DRUMMOND AGGREGATE EXTRACTION AREA

BRAZEAU SWM POND

BRAZEAU AGGREGATE EXTRACTION AREA

DRY SWM POND

COMMERCIAL

SCHOOL

PARK

DUNDONALD DR

FAMEFLOWER ST

DES SOLDATS RIENDEAU ST

TODD POND

OUTLET

EX GREENBANK RD

RIVER MIST RD

KILBIRNIE DR

LAURALEAF CR

BREAKSTONE RD

KNOCKADERRY CR

ALEX FOLOWIN AVE

NEW GREENBANK RD

STREET 1

STREET 2

STREET 3

STREET 4

STREET 5

STREET 6

PARK & RIDE

MEDIUM DENSITY

FRENCH PUBLIC ELEMENTARY SCHOOL

FRENCH CATHOLIC ELEMENTARY SCHOOL

NEIGHBOURHOOD PARK

PARKETTE 1

PARKETTE 2

EAST-WEST COLLECTOR

SWM DRY POND

POND 1 (NORTH)

POND 2 (SOUTH)

710 HDS

MA10 GRD 93.5 OBV 91.38

MA11 GRD 96.0 OBV 92.27

MA13 GRD 95.0 OBV 92.27

MA14 GRD 103.0 OBV 96.10

206 OBV 91.61

222 OBV 91.41

223A OBV 91.74

224 OBV 92.31

227 OBV 100.46

228 OBV 102.93

375mmØ @ 0.4%

400mmØ

300mmØ @ 0.75%

300mmØ @ 0.3%

300mmØ

350mmØ @ 1.3%

500mmØ @ 0.25%

750mmØ @ 0.13%

600mmØ @ 0.3%

600mmØ @ 0.13%

750mmØ @ 0.13%

600mmØ

750mmØ

300mmØ

200mmØ

NOTE:
REFER TO DWG SWM-CONV FOR DETAILS

NOTE:

STREETS 1, 2, 3, 4, 5, AND 6 ARE LOCAL ROADS.

LEGEND

- PROPOSED SANITARY, PER 2018 BSUEA MSS
- FUTURE SANITARY, PER 2014 BS MSS
- EXISTING SANITARY
- PROPOSED STORM (CONVENTIONAL SYSTEM), PER 2018 BSUEA MSS
- FUTURE STORM, PER 2014 BS MSS
- EXISTING STORM
- PROPOSED WATERMAIN, PER 2018 BSUEA MSS
- FUTURE WATERMAIN, PER 2014 BS MSS
- EXISTING WATERMAIN
- LIMIT OF STUDY AREA FOR BSUEA
- 710 HDS — HYDROLOGY DYNAMIC SEPARATOR

## SANITARY SEWERS

| M.H. # | | SEWER DATA | | | Upstream | Downstream |
|---|---|---|---|---|---|---|
| | | DIA. | SLOPE | LENGTH | Obvert | Obvert |
| FROM | TO | mm | % | m | | |
| 572 | 511 | 200 | 2.87 | 136.5 | 102.79 | 98.88 |
| 511 | 512 | 200 | 0.80 | 97.5 | 98.88 | 98.10 |
| 514 | 512 | 200 | 0.74 | 212.1 | 99.67 | 98.10 |
| 512 | 10 (ex.) | 200 | 1.60 | 74.4 | 98.10 | 96.91 |
| 514 | 516 | 200 | 0.35 | 127.9 | 102.70 | 102.25 |
| 516 | 554 | 200 | 0.35 | 170.9 | 102.25 | 101.65 |
| 500 | 502 | 200 | 0.35 | 174.0 | 105.03 | 104.42 |
| 502 | 551 | 200 | 0.89 | 163.6 | 104.42 | 102.92 |
| 550 | 551 | 200 | 0.35 | 161.5 | 103.20 | 102.63 |
| 551 | 552 | 200 | 0.35 | 113.6 | 102.63 | 102.24 |
| 552 | 554 | 200 | 0.35 | 173.3 | 102.24 | 101.61 |
| 554 | 556 | 250 | 0.33 | 295.7 | 101.61 | 100.64 |
| 517 | 564 | 200 | 0.58 | 282.4 | 102.10 | 100.45 |
| 13 (ex.) | 14 (ex.) | 200 | 0.67 | 74.6 | 102.55 | 102.05 |
| 14 (ex.) | 90 (ex.) | 200 | 0.94 | 112.1 | 102.00 | 101.95 |
| 90 (ex.) | 5 (ex.) | 200 | 0.35 | 109.2 | 100.95 | 100.57 |
| 5 (ex.) | 564 | 200 | 0.35 | 74.2 | 100.30 | 100.04 |
| 564 | 556 | 200 | 0.35 | 94.6 | 100.04 | 99.71 |
| 556 | 557 | 250 | 1.39 | 44.3 | 99.71 | 99.09 |
| 557 | 558 | 250 | 1.39 | 158.4 | 99.09 | 96.89 |
| 560 | 558 | 200 | 0.35 | 142.3 | 99.32 | 94.82 |
| 558 | 119 | 375 | 0.18 | 150.7 | 93.71 | 93.43 |
| 521 | 522 | 200 | 1.50 | 37.1 | 102.18 | 101.62 |
| 522 | 523 | 200 | 0.80 | 73.3 | 101.82 | 101.04 |
| 523 | 524 | 200 | 0.35 | 164.0 | 101.04 | 100.46 |
| 520 | 524 | 300 | 0.20 | 145.3 | 98.40 | 98.11 |
| 524 | 578 | 300 | 0.20 | 129.9 | 98.11 | 97.85 |
| 578 | 532 | 300 | 0.20 | 173.7 | 97.85 | 97.51 |
| 532 | 534 | 300 | 0.20 | 127.5 | 97.51 | 97.25 |
| 534 | 536 | 450 | 0.20 | 173.3 | 95.50 | 95.15 |
| 536 | 538 | 450 | 0.20 | 309.7 | 95.15 | 94.53 |
| 538 | 119 | 525 | 0.15 | 245.3 | 93.80 | 93.43 |
| 119 | 120 (ex.) | 600 | 0.15 | 168.7 | 93.43 | 93.17 |
| 900 | 158 (ex.) | 200 | 0.35 | 280.0 | 97.23 | 97.13 |
| 910 | 153 (ex.) | 200 | 0.35 | 132.0 | 96.70 | 96.65 |
| 920 | 930 | 200 | 0.35 | 165.0 | 97.42 | 97.36 |
| 930 | 217 (ex.) | 200 | 0.35 | 40.0 | 97.36 | 97.24 |
| 585 | 575 | 250 | 0.24 | 431.0 | 98.56 | 97.52 |
| 575 | 555 | 250 | 0.24 | 228.0 | 97.52 | 96.98 |
| 565 | 555 | 250 | 0.24 | 431.0 | 98.01 | 96.98 |
| 555 | 545 | 250 | 0.24 | 133.0 | 96.98 | 96.66 |
| 545 | 900 | 250 | 0.24 | 72.0 | 96.66 | 96.48 |
| 900 | MA 14 | 250 | 0.24 | 160.0 | 96.48 | 96.10 |
| 900 | MA 14 | 250 | 1.30 | 60.0 | 96.88 | 96.10 |
| MA 14 | MA13 | 250 | 1.30 | 295.0 | 96.10 | 92.27 |
| MA13 | MH57A | 375 | 0.30 | 413.1 | 90.77 | 89.53 |
| 593 | 592 | 200 | 0.35 | 300.0 | 99.19 | 98.14 |
| 592 | 590 | 200 | 0.35 | 220.0 | 98.14 | 97.37 |
| 591 | 590 | 200 | 0.35 | 300.0 | 98.42 | 97.37 |
| 590 | MA 11 | 300 | 0.35 | 80.0 | 97.37 | 97.09 |
| MA 11 | MA 10 | 300 | 0.75 | 482.1 | 95.00 | 91.38 |
| MA 10 | MH57A | 375 | 0.41 | 449.7 | 91.38 | 89.53 |

## CONVENTIONAL STORM SEWERS

| Maintenance Hole Number | | SEWER DATA PIPE | | | Upstream | Downstream |
|---|---|---|---|---|---|---|
| | | Dia | Slope | Length | Obvert | Obvert |
| FROM | TO | (mm) | (%) | (m) | | |
| 110 | 111 | 450 | 2.70 | 69.4 | 102.90 | 100.49 |
| 111 | 112 | 675 | 0.90 | 101.2 | 100.49 | 99.58 |
| 113 | 112 | 525 | 0.74 | 140.0 | 100.60 | 99.56 |
| 112 | 710 (ex) | 675 | 1.30 | 73.3 | 99.56 | 98.61 |
| 112 | 710 | 675 | 1.30 | 73.3 | 99.56 | 98.61 |
| 712 | 711 | 375 | 2.56 | 104.3 | 102.03 | 99.36 |
| 711 | 710 | 450 | 1.32 | 104.4 | 99.41 | 98.03 |
| 710 | 720 | 750 | 0.61 | 115.2 | 98.10 | 97.40 |
| 753 | 754 | 1800 | 0.11 | 54.9 | 95.01 | 94.95 |
| 754 | 755 | 1800 | 0.13 | 76.9 | 94.84 | 94.74 |
| 754 | 190 | 1800 | 0.15 | 15.0 | 94.95 | 94.93 |
| 190 | 190A | 1200 | 0.06 | 30.0 | 94.32 | 94.30 |
| 190A | 190B | 1200 | 0.10 | 52.7 | 94.30 | 94.25 |
| 190B | 755 | 600 | 0.11 | 15.0 | 93.64 | 93.62 |
| 755 | 822 | 1800 | 0.13 | 79.5 | 94.84 | 94.74 |
| 152 | 154 | 525 | 0.35 | 141.1 | 101.47 | 100.98 |
| 114 | 116 | 975 | 0.35 | 170.2 | 102.21 | 101.61 |
| 116 | 154 | 1200 | 0.35 | 171.2 | 101.81 | 101.01 |
| 154 | 156 | 1200 | 0.69 | 311.7 | 100.75 | 98.60 |
| 705(ex.) | 164 | 375 | 0.35 | 65.2 | 99.49 | 99.26 |
| 164 | 156 | 900 | 0.35 | 95.4 | 99.26 | 98.93 |
| 156 | 158 | 1800 | 0.40 | 202.6 | 98.26 | 97.45 |
| 160 | 158 | 1350 | 0.15 | 137.5 | 96.59 | 96.38 |
| 158 | Pl-in | 1800 | 0.15 | 14.5 | 95.84 | 95.82 |
| Diton Inlet | 170 | 900 | 1.05 | 55.9 | 107.04 | 106.45 |
| 170 | 172 | 900 | 1.05 | 188.5 | 106.45 | 104.47 |
| 172 | 174 | 1350 | 0.30 | 184.4 | 104.47 | 103.92 |
| 174 | 176 | 1350 | 0.30 | 166.7 | 103.92 | 103.45 |
| 176 | 179 | 1350 | 0.30 | 161.4 | 103.45 | 102.96 |
| 150 | 151 | 900 | 0.35 | 152.8 | 102.60 | 102.06 |
| Ditch Inlet 2 | 101 | 900 | 0.35 | 131.1 | 104.92 | 104.40 |
| 101 | 102 | 900 | 0.35 | 168.1 | 104.40 | 103.81 |
| 102 | 151 | 900 | 0.96 | 156.9 | 103.81 | 102.30 |
| 151 | 179 | 1200 | 0.35 | 111.8 | 102.06 | 101.67 |
| 120 | 124 | 1200 | 0.15 | 139.2 | 99.10 | 98.69 |
| 121 | 122 | 750 | 0.15 | 64.0 | 101.56 | 101.46 |
| 122 | 123 | 750 | 0.15 | 75.4 | 101.46 | 101.35 |
| 123 | 124 | 750 | 0.15 | 149.9 | 100.68 | 100.51 |
| 124 | 178 | 1200 | 0.15 | 122.1 | 98.89 | 98.71 |
| 178 | 178 | 1800 | 0.15 | 245.7 | 101.46 | 101.09 |
| 178 | 132 | 1950 | 0.15 | 185.6 | 98.71 | 98.43 |
| 132 | 134 | 1950 | 0.20 | 131.1 | 98.43 | 98.17 |
| 134 | 136 | 1950 | 0.20 | 173.3 | 98.17 | 97.82 |
| 136 | 137 | 1950 | 0.16 | 168.8 | 97.82 | 97.55 |
| 137 | P2-IN | 1950 | 0.16 | 38.0 | 97.55 | 97.49 |
| P2-out | HDS825 | 750 | 0.15 | 50.0 | 98.35 | 98.28 |
| HDS825 | EX 822 | 1800 | 0.18 | 160.8 | 97.19 | 96.90 |
| EX 822 | EX 821 | 1800 | 0.14 | 123.1 | 94.07 | 93.90 |
| EX 821 | EX 820 | 1800 | 0.15 | 121.9 | 93.89 | 93.71 |
| EX 748 | EX 747 | 600 | 0.20 | 83.1 | 95.95 | 95.79 |
| EX 747 | EX 746 | 600 | 0.99 | 17.1 | 95.72 | 95.90 |
| EX 746 | EX 744 | 600 | 0.20 | 69.4 | 95.58 | 95.44 |
| EX 743 | EX 744 | 450 | 1.31 | 81.4 | 95.59 | 94.52 |
| EX 744 | EX 820 | 675 | 0.52 | 12.4 | 93.76 | 93.70 |
| EX 820 | EX 102 | 1800 | 0.16 | 121.7 | 93.71 | 93.52 |
| 270 | 265 | 1500 | 0.15 | 100.0 | 99.45 | 99.30 |
| 265 | 260 | 1500 | 0.15 | 367.3 | 98.00 | 97.47 |
| 260 | 245 | 1500 | 0.15 | 227.9 | 97.47 | 97.12 |
| 250 | 245 | 1500 | 0.15 | 345.0 | 97.64 | 97.12 |
| 245 | 240 | 2100 | 0.15 | 84.9 | 97.12 | 97.00 |
| 240 | Brazeau SWM Pond | 2100 | 0.15 | 241.7 | 97.00 | 96.63 |
| 230 | 225 | 1500 | 0.15 | 450.0 | 97.66 | 96.99 |
| 225 | 215 | 1500 | 0.15 | 220.1 | 96.99 | 96.66 |
| 220 | 215 | 1500 | 0.15 | 408.7 | 97.27 | 96.66 |
| 215 | Drummond SWM Pond | 2100 | 0.15 | 350.0 | 96.66 | 96.13 |
| Drummond SWM Pond | 210 | 675 | 0.15 | 25.0 | 94.69 | 94.65 |
| 235 | 210 | 675 | 0.17 | 272.0 | 95.12 | 94.65 |
| 210 | 205 | 825 | 0.17 | 223.0 | 94.65 | 94.26 |
| 205 | Flood Plain | 825 | 0.17 | 817.0 | 94.26 | 92.84 |
| 900 | 227 (ex.) | 975 | 0.15 | 120.0 | 97.93 | 97.75 |

| No. | ISSUE / REVISION | DD/MM/YY |
|---|---|---|
| 4 | ISSUED FOR PLANNING COMMITTEE APPROVAL | 04/05/18 |
| 3 | ADDRESS COMMENTS, RE-ISSUE BSUEA MSS 2ND SUBMISSION | 26/02/18 |
| 2 | ISSUED AS PART OF DRAFT MSS | 20/09/17 |
| 1 | ISSUED FOR PRE-TAC WORKING MEETING | 31/08/17 |

This drawing is copyright protected and may not be reproduced or used for purposes other than execution of the described work without the express written consent of J.L. Richards & Associates Limited.

VERIFY SHEET SIZE AND SCALES. BAR TO THE RIGHT IS 25mm IF THIS IS A FULL SIZE DRAWING. 0 25mm

SCALE: 1:4000

CLIENT:

CONSULTANT: www.jlrichards.ca

J.L.Richards ENGINEERS · ARCHITECTS · PLANNERS

CONSULTANT:

PROFESSIONAL STAMP

LICENSED PROFESSIONAL ENGINEER — N. K. L. DALRYMPLE — May 4/18 — PROVINCE OF ONTARIO

PROJECT NORTH

PROJECT:

BARRHAVEN SOUTH URBAN EXPANSION AREA (BSUEA)

-

DRAWING:

KEY SERVICING PLAN WITH CONVENTIONAL STORM SEWER SYSTEM

| | |
|---|---|
| DESIGN: | JW |
| DRAWN: | CJM |
| CHECKED: | LD |
| JLR #: | 26610 |

DRAWING #: KS1

PLOT DATE: May 3, 2018 4:30:48 PM

File Location: r:\26000\26610 - barrhaven expansion - minto brazeau mattamy\JLR DWG\Civil\26610 C KS1.dwg

BRAZEAU AGGREGATE EXTRACTION AREA

COMMERCIAL

SCHOOL

PARK

KILBIRNIE DR

SCHOOL

PARK

LAURALEAF CR.

BREAKSTONE RD

RIVER MIST RD

ALEX POLOWIN AVE

KNOCKADERRY CR.

STREET 2

PARK & RIDE

FRENCH PUBLIC ELEMENTARY SCHOOL

NEW GREENBANK RD

STREET 1

MEDIUM DENSITY

STREET 3

PARKETTE 2

STREET 4

PARKETTE 1

EAST-WEST COLLECTOR

STREET 5

POND 1 (NORTH)

FRENCH CATHOLIC ELEMENTARY SCHOOL

STREET 6

POND 2 (SOUTH)

EX GREENBANK RD

DRY SWM POND

NEIGHBOURHOOD PARK

BARNSDALE RD

BARNSDALE RD

**LEGEND**

| | |
|---|---|
| 100.95 + | GRADES TAKEN FROM: TODD POND AND CLARK POND MODEL KEEPER ANALYSIS (JFSA) |
| 102.85 + | MINTO LANDS WITHIN BHSUEA |
| 99.75 + | GRADES TAKEN FROM: STANTEC TOPOGRAPHIC SKETCH OCTOBER 2015 |
| 96.13 + | GRADES TAKEN FROM: REALIGNED GREENBANK ROAD AND TRANSITWAY EXTENSION PLANNING AND ENVIRONMENT ASSESSMENT |
| 94.5 + | GRADES TAKEN FROM: BARRHAVEN SOUTH MASTER SERVICING STUDY ADDENDUM (STANTEC) |
| 103.5 + | MINIMUM FILL ELEVATION REQUIREMENT WITHIN PITS |
| | MAJOR OVERLAND FLOW DIRECTION |
| | LIMIT OF STUDY AREA FOR BSUEA |

| No. | ISSUE / REVISION | DD/MM/YY |
|---|---|---|
| 4 | ISSUED FOR PLANNING COMMITTEE APPROVAL | 04/05/18 |
| 3 | ADDRESS COMMENTS, RE-ISSUE BSUEA MSS 2ND SUBMISSION | 26/02/18 |
| 2 | ISSUED AS PART OF DRAFT MSS | 20/09/17 |
| 1 | ISSUED FOR PRE-TAC WORKING MEETING | 31/08/17 |

This drawing is copyright protected and may not be reproduced or used for purposes other than execution of the described work without the express written consent of J.L. Richards & Associates Limited.

VERIFY SHEET SIZE AND SCALES. BAR TO THE RIGHT IS 25mm IF THIS IS A FULL SIZE DRAWING. 0 25mm

SCALE: 1:2000

CLIENT:

CONSULTANT: www.jlrichards.ca

J.L.Richards ENGINEERS · ARCHITECTS · PLANNERS

CONSULTANT:

PROFESSIONAL STAMP

LICENSED PROFESSIONAL ENGINEER M. N. L. DALRYMPLE PROVINCE OF ONTARIO May 4, 2018

PROJECT NORTH

PROJECT:

BARRHAVEN SOUTH URBAN EXPANSION AREA (BSUEA)

-

DRAWING:

MASTER GRADING PLAN (1:2000)

DESIGN:

DRAWN:

CHECKED:

JLR #:

DRAWING #: MG2

File Location: r:\26000\26610 - barrhaven expansion - minto brazeau mattamy\JLR DWG\Civil\26610 C G2.dwg

PLOT DATE: May 3, 2018 4:33:33 PM

OUTLET TRUNK STORM SEWER TO JOCK RIVER
DISTANCE FROM MH205 TO JOCK RIVER 1:100 YR FLOOD PLAIN LIMIT IS APPROXIMATELY 815 M
INVERT AT MH205 = 93.42 M
INVERT AT JOCK RIVER 100 YR FLOOD PLAIN = APPROXIMATELY 92.0 M
OUTLET SEWER = 825 MM DIA. @ 0.17 %

CAMBRIAN RD
TO CLARK POND
TODD POND
OUTLET
FUTURE COLLECTOR RD
BORRISOKANE RD
HIGHWAY 416
TRAIL RD
RIVER MIST RD
EX GREENBANK RD
DUNDONALD DR
KILBIRNIE DR
KILBIRNIE CR
LAURALEAF CR
BREAKSTONE RD
KNOCKADERRY CR
DES SOLDATS RIENDEAU ST
FAMEFLOWER ST
NEW GREENBANK RD
ALEX POLOVIN AVE
STREET 1
STREET 2
STREET 3
STREET 4
STREET 5
EAST WEST COLLECTOR
PARKETTE 1
PARKETTE 2
DRUMMOND SWM POND
DRUMMOND AGGREGATE EXTRACTION AREA
BRAZEAU SWM POND
BRAZEAU AGGREGATE EXTRACTION AREA
SWM DRY POND
DRY SWM POND
POND 1 (NORTH)
POND 2 (SOUTH)
FRENCH PUBLIC ELEMENTARY SCHOOL
FRENCH CATHOLIC ELEMENTARY SCHOOL
NEIGHBOURHOOD PARK
PARK & RIDE
MEDIUM DENSITY
COMMERCIAL
SCHOOL
PARK
BARNSDALE RD
EX GREENBANK RD
373m ST
352m ST
357m ST
161m ST
194m ST
230m ST
233m ST
310m ST
336m ST
270m ST
22m ST
10HDS
680 HDS
750mmØ
825mmØ
1050mmØ
1200mmØ
1500mmØ
1800mmØ
2100mmØ
2400mmØ
2700mmØ
3000mmØ
3300mmØ
3600mmØ
3900mmØ
4200mmØ
4500mmØ
4800mmØ
5100mmØ
5400mmØ
5700mmØ
6000mmØ
6300mmØ
6600mmØ
6900mmØ
7200mmØ
7500mmØ
7800mmØ
8100mmØ
8400mmØ
8700mmØ
9000mmØ
9300mmØ
9600mmØ
9900mmØ
10200mmØ
10500mmØ
10800mmØ
11100mmØ
11400mmØ
11700mmØ
12000mmØ
12300mmØ
12600mmØ
12900mmØ
13200mmØ
13500mmØ
13800mmØ
14100mmØ
14400mmØ
14700mmØ
15000mmØ
15300mmØ
15600mmØ
15900mmØ
16200mmØ
16500mmØ
16800mmØ
17100mmØ
17400mmØ
17700mmØ
18000mmØ
18300mmØ
18600mmØ
18900mmØ
19200mmØ
19500mmØ
19800mmØ
20100mmØ
20400mmØ
20700mmØ
21000mmØ
21300mmØ
21600mmØ
21900mmØ
22200mmØ
22500mmØ
22800mmØ
23100mmØ
23400mmØ
23700mmØ
24000mmØ
24300mmØ
24600mmØ
24900mmØ
25200mmØ
25500mmØ
25800mmØ
26100mmØ
26400mmØ
26700mmØ
27000mmØ
27300mmØ
27600mmØ
27900mmØ
28200mmØ
28500mmØ
28800mmØ
29100mmØ
29400mmØ
29700mmØ
30000mmØ
30300mmØ
30600mmØ
30900mmØ
31200mmØ
31500mmØ
31800mmØ
32100mmØ
32400mmØ
32700mmØ
33000mmØ
33300mmØ
33600mmØ
33900mmØ
34200mmØ
34500mmØ
34800mmØ
35100mmØ
35400mmØ
35700mmØ
36000mmØ
36300mmØ
36600mmØ
36900mmØ
37200mmØ
37500mmØ
37800mmØ
38100mmØ
38400mmØ
38700mmØ
39000mmØ
39300mmØ
39600mmØ
39900mmØ
40200mmØ
40500mmØ
40800mmØ
41100mmØ
41400mmØ
41700mmØ
42000mmØ
42300mmØ
42600mmØ
42900mmØ
43200mmØ
43500mmØ
43800mmØ
44100mmØ
44400mmØ
44700mmØ
45000mmØ
45300mmØ
45600mmØ
45900mmØ
46200mmØ
46500mmØ
46800mmØ
47100mmØ
47400mmØ
47700mmØ
48000mmØ
48300mmØ
48600mmØ
48900mmØ
49200mmØ
49500mmØ
49800mmØ
50100mmØ
50400mmØ
50700mmØ
51000mmØ
51300mmØ
51600mmØ
51900mmØ
52200mmØ
52500mmØ
52800mmØ
53100mmØ
53400mmØ
53700mmØ
54000mmØ
54300mmØ
54600mmØ
54900mmØ
55200mmØ
55500mmØ
55800mmØ
56100mmØ
56400mmØ
56700mmØ
57000mmØ
57300mmØ
57600mmØ
57900mmØ
58200mmØ
58500mmØ
58800mmØ
59100mmØ
59400mmØ
59700mmØ
60000mmØ
60300mmØ
60600mmØ
60900mmØ
61200mmØ
61500mmØ
61800mmØ
62100mmØ
62400mmØ
62700mmØ
63000mmØ
63300mmØ
63600mmØ
63900mmØ
64200mmØ
64500mmØ
64800mmØ
65100mmØ
65400mmØ
65700mmØ
66000mmØ
66300mmØ
66600mmØ
66900mmØ
67200mmØ
67500mmØ
67800mmØ
68100mmØ
68400mmØ
68700mmØ
69000mmØ
69300mmØ
69600mmØ
69900mmØ
70200mmØ
70500mmØ
70800mmØ
71100mmØ
71400mmØ
71700mmØ
72000mmØ
72300mmØ
72600mmØ
72900mmØ
73200mmØ
73500mmØ
73800mmØ
74100mmØ
74400mmØ
74700mmØ
75000mmØ
75300mmØ
75600mmØ
75900mmØ
76200mmØ
76500mmØ
76800mmØ
77100mmØ
77400mmØ
77700mmØ
78000mmØ
78300mmØ
78600mmØ
78900mmØ
79200mmØ
79500mmØ
79800mmØ
80100mmØ
80400mmØ
80700mmØ
81000mmØ
81300mmØ
81600mmØ
81900mmØ
82200mmØ
82500mmØ
82800mmØ
83100mmØ
83400mmØ
83700mmØ
84000mmØ
84300mmØ
84600mmØ
84900mmØ
85200mmØ
85500mmØ
85800mmØ
86100mmØ
86400mmØ
86700mmØ
87000mmØ
87300mmØ
87600mmØ
87900mmØ
88200mmØ
88500mmØ
88800mmØ
89100mmØ
89400mmØ
89700mmØ
90000mmØ
90300mmØ
90600mmØ
90900mmØ
91200mmØ
91500mmØ
91800mmØ
92100mmØ
92400mmØ
92700mmØ
93000mmØ
93300mmØ
93600mmØ
93900mmØ
94200mmØ
94500mmØ
94800mmØ
95100mmØ
95400mmØ
95700mmØ
96000mmØ
96300mmØ
96600mmØ
96900mmØ
97200mmØ
97500mmØ
97800mmØ
98100mmØ
98400mmØ
98700mmØ
99000mmØ
99300mmØ
99600mmØ
99900mmØ
100200mmØ
100500mmØ
100800mmØ
101100mmØ
101400mmØ
101700mmØ
102000mmØ
102300mmØ
102600mmØ
102900mmØ
103200mmØ
103500mmØ
103800mmØ
104100mmØ
104400mmØ
104700mmØ
105000mmØ
105300mmØ
105600mmØ
105900mmØ
106200mmØ
106500mmØ
106800mmØ
107100mmØ
107400mmØ
107700mmØ
108000mmØ
108300mmØ
108600mmØ
108900mmØ
109200mmØ
109500mmØ
109800mmØ
110100mmØ
110400mmØ
110700mmØ
111000mmØ
111300mmØ
111600mmØ
111900mmØ
112200mmØ
112500mmØ
112800mmØ
113100mmØ
113400mmØ
113700mmØ
114000mmØ
114300mmØ
114600mmØ
114900mmØ
115200mmØ
115500mmØ
115800mmØ
116100mmØ
116400mmØ
116700mmØ
117000mmØ
117300mmØ
117600mmØ
117900mmØ
118200mmØ
118500mmØ
118800mmØ
119100mmØ
119400mmØ
119700mmØ
120000mmØ
120300mmØ
120600mmØ
120900mmØ
121200mmØ
121500mmØ
121800mmØ
122100mmØ
122400mmØ
122700mmØ
123000mmØ
123300mmØ
123600mmØ
123900mmØ
124200mmØ
124500mmØ
124800mmØ
125100mmØ
125400mmØ
125700mmØ
126000mmØ
126300mmØ
126600mmØ
126900mmØ
127200mmØ
127500mmØ
127800mmØ
128100mmØ
128400mmØ
128700mmØ
129000mmØ
129300mmØ
129600mmØ
129900mmØ
130200mmØ
130500mmØ
130800mmØ
131100mmØ
131400mmØ
131700mmØ
132000mmØ
132300mmØ
132600mmØ
132900mmØ
133200mmØ
133500mmØ
133800mmØ
134100mmØ
134400mmØ
134700mmØ
135000mmØ
135300mmØ
135600mmØ
135900mmØ
136200mmØ
136500mmØ
136800mmØ
137100mmØ
137400mmØ
137700mmØ
138000mmØ
138300mmØ
138600mmØ
138900mmØ
139200mmØ
139500mmØ
139800mmØ
140100mmØ
140400mmØ
140700mmØ
141000mmØ
141300mmØ
141600mmØ
141900mmØ
142200mmØ
142500mmØ
142800mmØ
143100mmØ
143400mmØ
143700mmØ
144000mmØ
144300mmØ
144600mmØ
144900mmØ
145200mmØ
145500mmØ
145800mmØ
146100mmØ
146400mmØ
146700mmØ
147000mmØ
147300mmØ
147600mmØ
147900mmØ
148200mmØ
148500mmØ
148800mmØ
149100mmØ
149400mmØ
149700mmØ
150000mmØ
150300mmØ
150600mmØ
150900mmØ
151200mmØ
151500mmØ
151800mmØ
152100mmØ
152400mmØ
152700mmØ
153000mmØ
153300mmØ
153600mmØ
153900mmØ
154200mmØ
154500mmØ
154800mmØ
155100mmØ
155400mmØ
155700mmØ
156000mmØ
156300mmØ
156600mmØ
156900mmØ
157200mmØ
157500mmØ
157800mmØ
158100mmØ
158400mmØ
158700mmØ
159000mmØ
159300mmØ
159600mmØ
159900mmØ
160200mmØ
160500mmØ
160800mmØ
161100mmØ
161400mmØ
161700mmØ
162000mmØ
162300mmØ
162600mmØ
162900mmØ
163200mmØ
163500mmØ
163800mmØ
164100mmØ
164400mmØ
164700mmØ
165000mmØ
165300mmØ
165600mmØ
165900mmØ
166200mmØ
166500mmØ
166800mmØ
167100mmØ
167400mmØ
167700mmØ
168000mmØ
168300mmØ
168600mmØ
168900mmØ
169200mmØ
169500mmØ
169800mmØ
170100mmØ
170400mmØ
170700mmØ
171000mmØ
171300mmØ
171600mmØ
171900mmØ
172200mmØ
172500mmØ
172800mmØ
173100mmØ
173400mmØ
173700mmØ
174000mmØ
174300mmØ
174600mmØ
174900mmØ
175200mmØ
175500mmØ
175800mmØ
176100mmØ
176400mmØ
176700mmØ
177000mmØ
177300mmØ
177600mmØ
177900mmØ
178200mmØ
178500mmØ
178800mmØ
179100mmØ
179400mmØ
179700mmØ
180000mmØ
180300mmØ
180600mmØ
180900mmØ
181200mmØ
181500mmØ
181800mmØ
182100mmØ
182400mmØ
182700mmØ
183000mmØ
183300mmØ
183600mmØ
183900mmØ
184200mmØ
184500mmØ
184800mmØ
185100mmØ
185400mmØ
185700mmØ
186000mmØ
186300mmØ
186600mmØ
186900mmØ
187200mmØ
187500mmØ
187800mmØ
188100mmØ
188400mmØ
188700mmØ
189000mmØ
189300mmØ
189600mmØ
189900mmØ
190200mmØ
190500mmØ
190800mmØ
191100mmØ
191400mmØ
191700mmØ
192000mmØ
192300mmØ
192600mmØ
192900mmØ
193200mmØ
193500mmØ
193800mmØ
194100mmØ
194400mmØ
194700mmØ
195000mmØ
195300mmØ
195600mmØ
195900mmØ
196200mmØ
196500mmØ
196800mmØ
197100mmØ
197400mmØ
197700mmØ
198000mmØ
198300mmØ
198600mmØ
198900mmØ
199200mmØ
199500mmØ
199800mmØ
200100mmØ
200400mmØ
200700mmØ
201000mmØ
201300mmØ
201600mmØ
201900mmØ
202200mmØ
202500mmØ
202800mmØ
203100mmØ
203400mmØ
203700mmØ
204000mmØ
204300mmØ
204600mmØ
204900mmØ
205200mmØ
205500mmØ
205800mmØ
206100mmØ
206400mmØ
206700mmØ
207000mmØ
207300mmØ
207600mmØ
207900mmØ
208200mmØ
208500mmØ
208800mmØ
209100mmØ
209400mmØ
209700mmØ
210000mmØ
210300mmØ
210600mmØ
210900mmØ
211200mmØ
211500mmØ
211800mmØ
212100mmØ
212400mmØ
212700mmØ
213000mmØ
213300mmØ
213600mmØ
213900mmØ
214200mmØ
214500mmØ
214800mmØ
215100mmØ
215400mmØ
215700mmØ
216000mmØ
216300mmØ
216600mmØ
216900mmØ
217200mmØ
217500mmØ
217800mmØ
218100mmØ
218400mmØ
218700mmØ
219000mmØ
219300mmØ
219600mmØ
219900mmØ
220200mmØ
220500mmØ
220800mmØ
221100mmØ
221400mmØ
221700mmØ
222000mmØ
222300mmØ
222600mmØ
222900mmØ
223200mmØ
223500mmØ
223800mmØ
224100mmØ
224400mmØ
224700mmØ
225000mmØ
225300mmØ
225600mmØ
225900mmØ
226200mmØ
226500mmØ
226800mmØ
227100mmØ
227400mmØ
227700mmØ
228000mmØ
228300mmØ
228600mmØ
228900mmØ
229200mmØ
229500mmØ
229800mmØ
230100mmØ
230400mmØ
230700mmØ
231000mmØ
231300mmØ
231600mmØ
231900mmØ
232200mmØ
232500mmØ
232800mmØ
233100mmØ
233400mmØ
233700mmØ
234000mmØ
234300mmØ
234600mmØ
234900mmØ
235200mmØ
235500mmØ
235800mmØ
236100mmØ
236400mmØ
236700mmØ
237000mmØ
237300mmØ
237600mmØ
237900mmØ
238200mmØ
238500mmØ
238800mmØ
239100mmØ
239400mmØ
239700mmØ
240000mmØ
240300mmØ
240600mmØ
240900mmØ
241200mmØ
241500mmØ
241800mmØ
242100mmØ
242400mmØ
242700mmØ
243000mmØ
243300mmØ
243600mmØ
243900mmØ
244200mmØ
244500mmØ
244800mmØ
245100mmØ
245400mmØ
245700mmØ
246000mmØ
246300mmØ
246600mmØ
246900mmØ
247200mmØ
247500mmØ
247800mmØ
248100mmØ
248400mmØ
248700mmØ
249000mmØ
249300mmØ
249600mmØ
249900mmØ
250200mmØ
250500mmØ
250800mmØ
251100mmØ
251400mmØ
251700mmØ
252000mmØ
252300mmØ
252600mmØ
252900mmØ
253200mmØ
253500mmØ
253800mmØ
254100mmØ
254400mmØ
254700mmØ
255000mmØ
255300mmØ
255600mmØ
255900mmØ
256200mmØ
256500mmØ
256800mmØ
257100mmØ
257400mmØ
257700mmØ
258000mmØ
258300mmØ
258600mmØ
258900mmØ
259200mmØ
259500mmØ
259800mmØ
260100mmØ
260400mmØ
260700mmØ
261000mmØ
261300mmØ
261600mmØ
261900mmØ
262200mmØ
262500mmØ
262800mmØ
263100mmØ
263400mmØ
263700mmØ
264000mmØ
264300mmØ
264600mmØ
264900mmØ
265200mmØ
265500mmØ
265800mmØ
266100mmØ
266400mmØ
266700mmØ
267000mmØ
267300mmØ
267600mmØ
267900mmØ
268200mmØ
268500mmØ
268800mmØ
269100mmØ
269400mmØ
269700mmØ
270000mmØ
270300mmØ
270600mmØ
270900mmØ
271200mmØ
271500mmØ
271800mmØ
272100mmØ
272400mmØ
272700mmØ
273000mmØ
273300mmØ
273600mmØ
273900mmØ
274200mmØ
274500mmØ
274800mmØ
275100mmØ
275400mmØ
275700mmØ
276000mmØ
276300mmØ
276600mmØ
276900mmØ
277200mmØ
277500mmØ
277800mmØ
278100mmØ
278400mmØ
278700mmØ
279000mmØ
279300mmØ
279600mmØ
279900mmØ
280200mmØ
280500mmØ
280800mmØ
281100mmØ
281400mmØ
281700mmØ
282000mmØ
282300mmØ
282600mmØ
282900mmØ
283200mmØ
283500mmØ
283800mmØ
284100mmØ
284400mmØ
284700mmØ
285000mmØ
285300mmØ
285600mmØ
285900mmØ
286200mmØ
286500mmØ
286800mmØ
287100mmØ
287400mmØ
287700mmØ
288000mmØ
288300mmØ
288600mmØ
288900mmØ
289200mmØ
289500mmØ
289800mmØ
290100mmØ
290400mmØ
290700mmØ
291000mmØ
291300mmØ
291600mmØ
291900mmØ
292200mmØ
292500mmØ
292800mmØ
293100mmØ
293400mmØ
293700mmØ
294000mmØ
294300mmØ
294600mmØ
294900mmØ
295200mmØ
295500mmØ
295800mmØ
296100mmØ
296400mmØ
296700mmØ
297000mmØ
297300mmØ
297600mmØ
297900mmØ
298200mmØ
298500mmØ
298800mmØ
299100mmØ
299400mmØ
299700mmØ
300000mmØ
300300mmØ
300600mmØ
300900mmØ
301200mmØ
301500mmØ
301800mmØ
302100mmØ
302400mmØ
302700mmØ
303000mmØ
303300mmØ
303600mmØ
303900mmØ
304200mmØ
304500mmØ
304800mmØ
305100mmØ
305400mmØ
305700mmØ
306000mmØ
306300mmØ
306600mmØ
306900mmØ
307200mmØ
307500mmØ
307800mmØ
308100mmØ
308400mmØ
308700mmØ
309000mmØ
309300mmØ
309600mmØ
309900mmØ
310200mmØ
310500mmØ
310800mmØ
311100mmØ
311400mmØ
311700mmØ
312000mmØ
312300mmØ
312600mmØ
312900mmØ
313200mmØ
313500mmØ
313800mmØ
314100mmØ
314400mmØ
314700mmØ
315000mmØ
315300mmØ
315600mmØ
315900mmØ
316200mmØ
316500mmØ
316800mmØ
317100mmØ
317400mmØ
317700mmØ
318000mmØ
318300mmØ
318600mmØ
318900mmØ
319200mmØ
319500mmØ
319800mmØ
320100mmØ
320400mmØ
320700mmØ
321000mmØ
321300mmØ
321600mmØ
321900mmØ
322200mmØ
322500mmØ
322800mmØ
323100mmØ
323400mmØ
323700mmØ
324000mmØ
324300mmØ
324600mmØ
324900mmØ
325200mmØ
325500mmØ
325800mmØ
326100mmØ
326400mmØ
326700mmØ
327000mmØ
327300mmØ
327600mmØ
327900mmØ
328200mmØ
328500mmØ
328800mmØ
329100mmØ
329400mmØ
329700mmØ
330000mmØ
330300mmØ
330600mmØ
330900mmØ
331200mmØ
331500mmØ
331800mmØ
332100mmØ
332400mmØ
332700mmØ
333000mmØ
333300mmØ
333600mmØ
333900mmØ
334200mmØ
334500mmØ
334800mmØ
335100mmØ
335400mmØ
335700mmØ
336000mmØ
336300mmØ
336600mmØ
336900mmØ
337200mmØ
337500mmØ
337800mmØ
338100mmØ
338400mmØ
338700mmØ
339000mmØ
339300mmØ
339600mmØ
339900mmØ
340200mmØ
340500mmØ
340800mmØ
341100mmØ
341400mmØ
341700mmØ
342000mmØ
342300mmØ
342600mmØ
342900mmØ
343200mmØ
343500mmØ
343800mmØ
344100mmØ
344400mmØ
344700mmØ
345000mmØ
345300mmØ
345600mmØ
345900mmØ
346200mmØ
346500mmØ
346800mmØ
347100mmØ
347400mmØ
347700mmØ
348000mmØ
348300mmØ
348600mmØ
348900mmØ
349200mmØ
349500mmØ
349800mmØ
350100mmØ
350400mmØ
350700mmØ
351000mmØ
351300mmØ
351600mmØ
351900mmØ
352200mmØ
352500mmØ
352800mmØ
353100mmØ
353400mmØ
353700mmØ
354000mmØ
354300mmØ
354600mmØ
354900mmØ
355200mmØ
355500mmØ
355800mmØ
356100mmØ
356400mmØ
356700mmØ
357000mmØ
357300mmØ
357600mmØ
357900mmØ
358200mmØ
358500mmØ
358800mmØ
359100mmØ
359400mmØ
359700mmØ
360000mmØ
360300mmØ
360600mmØ
360900mmØ
361200mmØ
361500mmØ
361800mmØ
362100mmØ
362400mmØ
362700mmØ
363000mmØ
363300mmØ
363600mmØ
363900mmØ
364200mmØ
364500mmØ
364800mmØ
365100mmØ
365400mmØ
365700mmØ
366000mmØ
366300mmØ
366600mmØ
366900mmØ
367200mmØ
367500mmØ
367800mmØ
368100mmØ
368400mmØ
368700mmØ
369000mmØ
369300mmØ
369600mmØ
369900mmØ
370200mmØ
370500mmØ
370800mmØ
371100mmØ
371400mmØ
371700mmØ
372000mmØ
372300mmØ
372600mmØ
372900mmØ
373200mmØ
373500mmØ
373800mmØ
374100mmØ
374400mmØ
374700mmØ
375000mmØ
375300mmØ
375600mmØ
375900mmØ
376200mmØ
376500mmØ
376800mmØ
377100mmØ
377400mmØ
377700mmØ
378000mmØ
378300mmØ
378600mmØ
378900mmØ
379200mmØ
379500mmØ
379800mmØ
380100mmØ
380400mmØ
380700mmØ
381000mmØ
381300mmØ
381600mmØ
381900mmØ
382200mmØ
382500mmØ
382800mmØ
383100mmØ
383400mmØ
383700mmØ
384000mmØ
384300mmØ
384600mmØ
384900mmØ
385200mmØ
385500mmØ
385800mmØ
386100mmØ
386400mmØ
386700mmØ
387000mmØ
387300mmØ
387600mmØ
387900mmØ
388200mmØ
388500mmØ
388800mmØ
389100mmØ
389400mmØ
389700mmØ
390000mmØ
390300mmØ
390600mmØ
390900mmØ
391200mmØ
391500mmØ
391800mmØ
392100mmØ
392400mmØ
392700mmØ
393000mmØ
393300mmØ
393600mmØ
393900mmØ
394200mmØ
394500mmØ
394800mmØ
395100mmØ
395400mmØ
395700mmØ
396000mmØ
396300mmØ
396600mmØ
396900mmØ
397200mmØ
397500mmØ
397800mmØ
398100mmØ
398400mmØ
398700mmØ
399000mmØ
399300mmØ
399600mmØ
399900mmØ
400200mmØ
400500mmØ
400800mmØ
401100mmØ
401400mmØ
401700mmØ
402000mmØ
402300mmØ
402600mmØ
402900mmØ
403200mmØ
403500mmØ
403800mmØ
404100mmØ
404400mmØ
404700mmØ
405000mmØ
405300mmØ
405600mmØ
405900mmØ
406200mmØ
406500mmØ
406800mmØ
407100mmØ
407400mmØ
407700mmØ
408000mmØ
408300mmØ
408600mmØ
408900mmØ
409200mmØ
409500mmØ
409800mmØ
410100mmØ
410400mmØ
410700mmØ
411000mmØ
411300mmØ
411600mmØ
411900mmØ
412200mmØ
412500mmØ
412800mmØ
413100mmØ
413400mmØ
413700mmØ
414000mmØ
414300mmØ
414600mmØ
414900mmØ
415200mmØ
415500mmØ
415800mmØ
416100mmØ
416400mmØ
416700mmØ
417000mmØ
417300mmØ
417600mmØ
417900mmØ
418200mmØ
418500mmØ
418800mmØ
419100mmØ
419400mmØ
419700mmØ
420000mmØ
420300mmØ
420600mmØ
420900mmØ
421200mmØ
421500mmØ
421800mmØ
422100mmØ
422400mmØ
422700mmØ
423000mmØ
423300mmØ
423600mmØ
423900mmØ
424200mmØ
424500mmØ
424800mmØ
425100mmØ
425400mmØ
425700mmØ
426000mmØ
426300mmØ
426600mmØ
426900mmØ
427200mmØ
427500mmØ
427800mmØ
428100mmØ
428400mmØ
428700mmØ
429000mmØ
429300mmØ
429600mmØ
429900mmØ
430200mmØ
430500mmØ
430800mmØ
431100mmØ
431400mmØ
431700mmØ
432000mmØ
432300mmØ
432600mmØ
432900mmØ
433200mmØ
433500mmØ
433800mmØ
434100mmØ
434400mmØ
434700mmØ
435000mmØ
435300mmØ
435600mmØ
435900mmØ
436200mmØ
436500mmØ
436800mmØ
437100mmØ
437400mmØ
437700mmØ
438000mmØ
438300mmØ
438600mmØ
438900mmØ
439200mmØ
439500mmØ
439800mmØ
440100mmØ
440400mmØ
440700mmØ
441000mmØ
441300mmØ
441600mmØ
441900mmØ
442200mmØ
442500mmØ
442800mmØ
443100mmØ
443400mmØ
443700mmØ
444000mmØ
444300mmØ
444600mmØ
444900mmØ
445200mmØ
445500mmØ
445800mmØ
446100mmØ
446400mmØ
446700mmØ
447000mmØ
447300mmØ
447600mmØ
447900mmØ
448200mmØ
448500mmØ
448800mmØ
449100mmØ
449400mmØ
449700mmØ
450000mmØ
450300mmØ
450600mmØ
450900mmØ
451200mmØ
451500mmØ
451800mmØ
452100mmØ
452400mmØ
452700mmØ
453000mmØ
453300mmØ
453600mmØ
453900mmØ
454200mmØ
454500mmØ
454800mmØ
455100mmØ
455400mmØ
455700mmØ
456000mmØ
456300mmØ
456600mmØ
456900mmØ
457200mmØ
457500mmØ
457800mmØ
458100mmØ
458400mmØ
458700mmØ
459000mmØ
459300mmØ
459600mmØ
459900mmØ
460200mmØ
460500mmØ
460800mmØ
461100mmØ
461400mmØ
461700mmØ
462000mmØ
462300mmØ
462600mmØ
462900mmØ
463200mmØ
463500mmØ
463800mmØ
464100mmØ
464400mmØ
464700mmØ
465000mmØ
465300mmØ
465600mmØ
465900mmØ
466200mmØ
466500mmØ
466800mmØ
467100mmØ
467400mmØ
467700mmØ
468000mmØ
468300mmØ
468600mmØ
468900mmØ
469200mmØ
469500mmØ
469800mmØ
470100mmØ
470400mmØ
470700mmØ
471000mmØ
471300mmØ
471600mmØ
471900mmØ
472200mmØ
472500mmØ
472800mmØ
473100mmØ
473400mmØ
473700mmØ
474000mmØ
474300mmØ
474600mmØ
474900mmØ
475200mmØ
475500mmØ
475800mmØ
476100mmØ
476400mmØ
476700mmØ
477000mmØ
477300mmØ
477600mmØ
477900mmØ
478200mmØ
478500mmØ
478800mmØ
479100mmØ
479400mmØ
479700mmØ
480000mmØ
480300mmØ
480600mmØ
480900mmØ
481200mmØ
481500mmØ
481800mmØ
482100mmØ
482400mmØ
482700mmØ
483000mmØ
483300mmØ
483600mmØ
483900mmØ
484200mmØ
484500mmØ
484800mmØ
485100mmØ
485400mmØ
485700mmØ
486000mmØ
486300mmØ
486600mmØ
486900mmØ
487200mmØ
487500mmØ
487800mmØ
488100mmØ
488400mmØ
488700mmØ
489000mmØ
489300mmØ
489600mmØ
489900mmØ
490200mmØ
490500mmØ
490800mmØ
491100mmØ
491400mmØ
491700mmØ
492000mmØ
492300mmØ
492600mmØ
492900mmØ
493200mmØ
493500mmØ
493800mmØ
494100mmØ
494400mmØ
494700mmØ
495000mmØ
495300mmØ
495600mmØ
495900mmØ
496200mmØ
496500mmØ
496800mmØ
497100mmØ
497400mmØ
497700mmØ
498000mmØ
498300mmØ
498600mmØ
498900mmØ
499200mmØ
499500mmØ
499800mmØ
500100mmØ
500400mmØ
500700mmØ
501000mmØ
501300mmØ
501600mmØ
501900mmØ
502200mmØ
502500mmØ
502800mmØ
503100mmØ
503400mmØ
503700mmØ
504000mmØ
504300mmØ
504600mmØ
504900mmØ
505200mmØ
505500mmØ
505800mmØ
506100mmØ
506400mmØ
506700mmØ
507000mmØ
507300mmØ
507600mmØ
507900mmØ
508200mmØ
508500mmØ
508800mmØ
509100mmØ
509400mmØ
509700mmØ
510000mmØ
510300mmØ
510600mmØ
510900mmØ
511200mmØ
511500mmØ
511800mmØ
512100mmØ
512400mmØ
512700mmØ
513000mmØ
513300mmØ
513600mmØ
513900mmØ
514200mmØ
514500mmØ
514800mmØ
515100mmØ
515400mmØ
515700mmØ
516000mmØ
516300mmØ
516600mmØ
516900mmØ
517200mmØ
517500mmØ
517800mmØ
518100mmØ
518400mmØ
518700mmØ
519000mmØ
519300mmØ
519600mmØ
519900mmØ
520200mmØ
520500mmØ
520800mmØ
521100mmØ
521400mmØ
521700mmØ
522000mmØ
522300mmØ
522600mmØ
522900mmØ
523200mmØ
523500mmØ
523800mmØ
524100mmØ
524400mmØ
524700mmØ
525000mmØ
525300mmØ
525600mmØ
525900mmØ
526200mmØ
526500mmØ
526800mmØ
527100mmØ
527400mmØ
527700mmØ
528000mmØ
528300mmØ
528600mmØ
528900mmØ
529200mmØ
529500mmØ
529800mmØ
530100mmØ
530400mmØ
530700mmØ
531000mmØ
531300mmØ
531600mmØ
531900mmØ
532200mmØ
532500mmØ
532800mmØ
533100mmØ
533400mmØ
533700mmØ
534000mmØ
534300mmØ
534600mmØ
534900mmØ
535200mmØ
535500mmØ
535800mmØ
536100mmØ
536400mmØ
536700mmØ
537000mmØ
537300mmØ
537600mmØ
537900mmØ
538200mmØ
538500mmØ
538800mmØ
539100mmØ
539400mmØ
539700mmØ
540000mmØ
540300mmØ
540600mmØ
540900mmØ
541200mmØ
541500mmØ
541800mmØ
542100mmØ
542400mmØ
542700mmØ
543000mmØ
543300mmØ
543600mmØ
543900mmØ
544200mmØ
544500mmØ
544800mmØ
545100mmØ
545400mmØ
545700mmØ
546000mmØ
546300mmØ
546600mmØ
546900mmØ
547200mmØ
547500mmØ
547800mmØ
548100mmØ
548400mmØ
548700mmØ
549000mmØ
549300mmØ
549600mmØ
549900mmØ
550200mmØ
550500mmØ
550800mmØ
551100mmØ
551400mmØ
551700mmØ
552000mmØ
552300mmØ
552600mmØ
552900mmØ
553200mmØ
553500mmØ
553800mmØ
554100mmØ
554400mmØ
554700mmØ
555000mmØ
555300mmØ
555600mmØ
555900mmØ
556200mmØ
556500mmØ
556800mmØ
557100mmØ
557400mmØ
557700mmØ
558000mmØ
558300mmØ
558600mmØ
558900mmØ
559200mmØ
559500mmØ
559800mmØ
560100mmØ
560400mmØ
560700mmØ
561000mmØ
561300mmØ
561600mmØ
561900mmØ
562200mmØ
562500mmØ
562800mmØ
563100mmØ
563400mmØ
563700mmØ
564000mmØ
564300mmØ
564600mmØ
564900mmØ
565200mmØ
565500mmØ
565800mmØ
566100mmØ
566400mmØ
566700mmØ
567000mmØ
567300mmØ
567600mmØ
567900mmØ
568200mmØ
568500mmØ
568800mmØ
569100mmØ
569400mmØ
569700mmØ
570000mmØ
570300mmØ
570600mmØ
570900mmØ
571200mmØ
571500mmØ
571800mmØ
572100mmØ
572400mmØ
572700mmØ
573000mmØ
573300mmØ
573600mmØ
573900mmØ
574200mmØ
574500mmØ
574800mmØ
575100mmØ
575400mmØ
575700mmØ
576000mmØ
576300mmØ
576600mmØ
576900mmØ
577200mmØ
577500mmØ
577800mmØ
578100mmØ
578400mmØ
578700mmØ
579000mmØ
579300mmØ
579600mmØ
579900mmØ
580200mmØ
580500mmØ
580800mmØ
581100mmØ
581400mmØ
581700mmØ
582000mmØ
582300mmØ
582600mmØ
582900mmØ
583200mmØ
583500mmØ
583800mmØ
584100mmØ
584400mmØ
584700mmØ
585000mmØ
585300mmØ
585600mmØ
585900mmØ
586200mmØ
586500mmØ
586800mmØ
587100mmØ
587400mmØ
587700mmØ
588000mmØ
588300mmØ
588600mmØ
588900mmØ
589200mmØ
589500mmØ
589800mmØ
590100mmØ
590400mmØ
590700mmØ
591000mmØ
591300mmØ
591600mmØ
591900mmØ
592200mmØ
592500mmØ
592800mmØ
593100mmØ
593400mmØ
593700mmØ
594000mmØ
594300mmØ
594600mmØ
594900mmØ
595200mmØ
595500mmØ
595800mmØ
596100mmØ
596400mmØ
596700mmØ
597000mmØ
597300mmØ
597600mmØ
597900mmØ
598200mmØ
598500mmØ
598800mmØ
599100mmØ
599400mmØ
599700mmØ
600000mmØ
600300mmØ
600600mmØ
600900mmØ
601200mmØ
601500mmØ
601800mmØ
602100mmØ
602400mmØ
602700mmØ
603000mmØ
603300mmØ
603600mmØ
603900mmØ
604200mmØ
604500mmØ
604800mmØ
605100mmØ
605400mmØ
605700mmØ
606000mmØ
606300mmØ
606600mmØ
606900mmØ
607200mmØ
607500mmØ
607800mmØ
608100mmØ
608400mmØ
608700mmØ
609000mmØ
609300mmØ
609600mmØ
609900mmØ
610200mmØ
610500mmØ
610800mmØ
611100mmØ
611400mmØ
611700mmØ
612000mmØ
612300mmØ
612600mmØ
612900mmØ
613200mmØ
613500mmØ
613800mmØ
614100mmØ
614400mmØ
614700mmØ
615000mmØ
615300mmØ
615600mmØ
615900mmØ
616200mmØ
616500mmØ
616800mmØ
617100mmØ
617400mmØ
617700mmØ
618000mmØ
618300mmØ
618600mmØ
618900mmØ
619200mmØ
619500mmØ
619800mmØ
620100mmØ
620400mmØ
620700mmØ
621000mmØ
621300mmØ
621600mmØ
621900mmØ
622200mmØ
622500mmØ
622800mmØ
623100mmØ
623400mmØ
623700mmØ
624000mmØ
624300mmØ
624600mmØ
624900mmØ
625200mmØ
625500mmØ
625800mmØ
626100mmØ
626400mmØ
626700mmØ
627000mmØ
627300mmØ
627600mmØ
627900mmØ
628200mmØ
628500mmØ
628800mmØ
629100mmØ
629400mmØ
629700mmØ
630000mmØ
630300mmØ
630600mmØ
630900mmØ
631200mmØ
631500mmØ
631800mmØ
632100mmØ
632400mmØ
632700mmØ
633000mmØ
633300mmØ
633600mmØ
633900mmØ
634200mmØ
634500mmØ
634800mmØ
635100mmØ
635400mmØ
635700mmØ
636000mmØ
636300mmØ
636600mmØ
636900mmØ
637200mmØ
637500mmØ
637800mmØ
638100mmØ
638400mmØ
638700mmØ
639000mmØ
639300mmØ
639600mmØ
639900mmØ
640200mmØ
640500mmØ
640800mmØ
641100mmØ
641400mmØ
641700mmØ
642000mmØ
642300mmØ
642600mmØ
642900mmØ
643200mmØ
643500mmØ
643800mmØ
644100mmØ
644400mmØ
644700mmØ
645000mmØ
645300mmØ
645600mmØ
645900mmØ
646200mmØ
646500mmØ
646800mmØ
647100mmØ
647400mmØ
647700mmØ
648000mmØ
648300mmØ
648600mmØ
648900mmØ
649200mmØ
649500mmØ
649800mmØ
650100mmØ
650400mmØ
650700mmØ
651000mmØ
651300mmØ
651600mmØ
651900mmØ
652200mmØ
652500mmØ