

EXISTING TREE LIST KEY QTY. BOTANICAL NAME CONDITION REMARKS COMMON NAME SIZE **TREES** 150mm DBH To Be Removed Acer negundo Manitoba Maple BP 4 150-250mm DBH Good Betula papyrifera White Birch To Be Removed 250-300mm DBH Good To Be Removed Larix laricina Tamarack MA 2 150-200mm DBH Good To Be Removed Malus sp. Crabapple PA Norway Spruce 200-250mm DBH Good To Be Removed Picea abies PG Picea glauca White Spruce 250mm DBH Poor To Be Removed PP 2 Colorado Spruce 200-300mm DBH Good To Be Removed Picea pungens 200-300mm DBH Fair-Good To Be Removed Scots Pine Pinus sylvestris Eastern White Cedar TO 10 100-500mm DBH Good To Be Removed Thuja occidentalis Ulmus americana American Elm 200-300mm DBH | Dead-Poor To Be Removed WP 2 Pinus strobus 300-450mm DBH Good White Pine To Be Removed

*DENOTES NUMEROUS

GENERAL NOTES:

1. It is the responsibility of the appropriate contractor or official to report any errors, omissions or discrepancies on this plan with actual site conditions to the Landscape Architect before proceeding with construction.

2. The contractor is to notify all utility companies and authorities prior to any excavation and ascertain locations of underground services.

3. The contractor is to reinstate all areas and items damaged as a result of construction activity.

4. The contractor is to comply with all pertinent codes and by-laws.

5. The contractor is to maintain a positive surface run-off throughout the entire construction period.

6. The Landscape Architect is not responsible for subsurface conditions.

7. The contractor is to identify all existing trees to remain on site with the Landscape Architect prior to construction.

8. The contractor is to stake the proposed location of all plant material in conjunction with the Landscape Architect prior to excavation.

9. Minimum distances for selected deciduous trees are as follows: Building Foundations 7.5m Sidewalks 1.5m

Public Streets 2.5m

Underground Infrastructure 2.0m

10. All trees within 1m of underground utility trenches are to be excavated by hand.

11. Remove all protective wrapping from tree trunks after installation.

12. Staking of trees shall only be performed if necessary.

ARCHITECTS:

Roderick Lahey Architect Inc.

Roderick Lahey Architect Inc 56 Beech St, Ottawa, ON K1S 3J6 Tel : (613) 724-9932

SURVEYORS:

ANNIS,O'SULLIVN, VOLLEBEKK LTD.,

ENGINEERS:

EXP Services Inc. 2650 Queensview Drive, Ottawa ON K2B 8H6 Tel: (613) 688-1899

EXISTING TREE TO BE REMOVED

ァノノノ-

GROUP OF EXISTING TREES TO BE REMOVED


2	REVISED PER CITY COMMENTS	10/06/2020	ML	,
1	ISSUED FOR SITE PLAN APPROVAL	04/09/2020	ML	,
No.	Issue	Date MM/DD/YY	DR	(

JAMES B. LENNOX & ASSOCIATES INC. LANDSCAPE **ARCHITECTS** 3332 CARLING AVE. OTTAWA, ONTARIO Tel. (613) 722-5168 Fax. 1(866) 343-3942

1869 MAPLE GROVE

1869 MAPLE GROVE, OTTAWA ON

TREE CONSERVATION REPORT



AS SHOWN

DECEMBER 2019 PROJECT NO.

20MIS2013

DRAWING NO.

