LEGEND:

- 3.0m WIDE ACCESSIBLE STONEDUST TRAIL
- 3.0m WIDE ASPHALT MUP
- CONCRETE SIDEWALK
- ROCK RETAINING WALL
- NATIVE SHRUB PLANTING
- REFORESTATION PLANTING
- DECIDUOUS TREE PLANTING
- CONIFEROUS TREE PLANTING
- APPROXIMATE EXTENT OF SLOPE MODIFICATION
- NATIVE GRASS / WILDFLOWER SEEDING: 'BASE RESTORATION SEED MIX' AS SUPPLIED BY ST.WILLIAMS NURSERY
- SEED / SOD
- PROPERTY LINE
- LIMIT OF APPLICANTS SCOPE OF WORK
- LIMIT OF COMBINED CITY / APPLICANT SCOPE OF WORK
- GUARDRAIL

GENERAL NOTES:
FINAL LAYOUT AND QUANTITIES FOR PLANT MATERIAL WILL BE DETERMINED THROUGH DETAILED DESIGN DEVELOPMENT AND CO-ORDINATION WITH SITE SERVICING AND UTILITIES.

Nursery Stock (Street Trees)

SYM.	BOTANICAL NAME	COMMON NAME	QTY	SIZE	COMMENTS
Deciduous Trees					
AC	Amelanchier canadensis	Serviceberry		50mm Cal.	B.B. / W.B.
AR	Acer rubrum	Red Maple		70mm Cal.	B.B. / W.B.
AS	Acer saccharum	Sugar Maple		70mm Cal.	B.B. / W.B.
CO	Celtis occidentalis	Common Hackberry		70mm Cal.	B.B. / W.B.
PS	Prunus serotina	Black Cherry		50mm Cal.	B.B. / W.B.
QM	Quercus macrocarpa	Bur Oak		70mm Cal.	B.B. / W.B.
QR	Quercus rubra	Red Oak		70mm Cal.	B.B. / W.B.
UM	Ulmus Morton	Accolade Elm		70mm Cal.	B.B. / W.B.
Coniferous Trees					
AB	Abies balsamea	Balsam Fir		1.8m Height	B.B. / W.B.
PG	Picea glauca	White Spruce		1.8m Height	B.B. / W.B.
PR	Pinus resinosa	Red Pine		1.8m Height	B.B. / W.B.
PS	Pinus strobus	White Pine		1.8m Height	B.B. / W.B.

Native Shrub Mix 1

%	SYM.	BOTANICAL NAME	COMMON NAME	QUANTITY PER BED			TOTAL	SIZE	COMMENTS
				BED #	S1	S2			
0	*Native Shrubs @ 600mm o.c*			*AREA m²*	*0*	*0*			
10%	AI	Alnus incana	Speckled Alder		0	0	0	600mm Ht.	Bareroot or Container
10%	AC	Amelanchier canadensis	Serviceberry		0	0	0	600mm Ht.	Bareroot or Container
5%	CR	Cornus racemosa	Gray Dogwood		0	0	0	600mm Ht.	Bareroot or Container
20%	DL	Diervilla lonicera	Bush Honeysuckle		0	0	0	600mm Ht.	Bareroot or Container
10%	PO	Physocarpus opulifolius	Common Ninebark		0	0	0	600mm Ht.	Bareroot or Container
5%	PP	Prunus pensylvanica	Pin Cherry		0	0	0	600mm Ht.	Bareroot or Container
5%	PV	Prunus virginiana	Chokecherry		0	0	0	600mm Ht.	Bareroot or Container
30%	RT	Rhus typhina	Staghorn Sumac		0	0	0	600mm Ht.	Bareroot or Container
5%	VL	Viburnum lentago	Nannyberry		0	0	0	600mm Ht.	Bareroot or Container

Reforestation Mix 1 - (Each area to be 90% Tree Mix and 10% Shrub Mix)

%	SYM.	BOTANICAL NAME	COMMON NAME	QUANTITY PER BED			TOTAL	SIZE	COMMENTS
				BED #	F1	F2			
0	*Reforestation Trees@ 2.0m o.c*		*90%*	*AREA m²*	*0*	*0*			
15%	AR	Acer rubrum	Red Maple		0	0	0	20mm CAL.	Bareroot or Container
20%	AS	Acer saccharum	Sugar Maple		0	0	0	20mm CAL.	Bareroot or Container
10%	BP	Betula papyrifera	White Birch		0	0	0	20mm CAL.	Bareroot or Container
5%	CO	Celtis occidentalis	Common Hackberry		0	0	0	20mm CAL.	Bareroot or Container
5%	PS	Pinus strobus	White Pine		0	0	0	20mm CAL.	Bareroot or Container
5%	PR	Prunus serotina	Black Cherry		0	0	0	20mm CAL.	Bareroot or Container
10%	PT	Populous tremuloides	Trembling Aspen		0	0	0	20mm CAL.	Bareroot or Container
10%	QM	Quercus macrocarpa	Bur Oak		0	0	0	20mm CAL.	Bareroot or Container
15%	TA	Tilia americana	Basswood		0	0	0	20mm CAL.	Bareroot or Container
5%	TO	Thuja occidentalis	Eastern White Cedar		0	0	0	20mm CAL.	Bareroot or Container
0	*Understorey Shrubs@ 1.0m o.c.*		10%						
20%	AI	Alnus incana	Speckled Alder		0	0	0	600mm Ht.	Bareroot or Container
20%	AC	Amelanchier canadensis	Serviceberry		0	0	0	600mm Ht.	Bareroot or Container
20%	DL	Diervilla lonicera	Bush Honeysuckle		0	0	0	600mm Ht.	Bareroot or Container
20%	VL	Viburnum lentago	Nannyberry		0	0	0	600mm Ht.	Bareroot or Container
20%	RT	Rhus typhina	Staghorn Sumac		0	0	0	600mm Ht.	Bareroot or Container

TAGGART REALTY MANAGEMENT

HUNT CLUB RD. - RIVERSIDE DR. LANDSCAPE PLAN

MIXED RESIDENTIAL STUDY

SCALE 1:750

CSW

December 22, 2022