



Kollaard Associates

Engineers

210 Prescott Street, Unit 1  
P.O. Box 189  
Kemptville, Ontario K0G 1J0

Civil • Geotechnical •  
Structural • Environmental •  
Hydrogeology •

**(613) 860-0923**

FAX: (613) 258-0475

REPORT ON

**HYDROGEOLOGICAL INVESTIGATION  
AND TERRAIN EVALUATION  
PROPOSED RESIDENTIAL SUBDIVISION  
3200 REIDS LANE  
OSGOODE WARD, CITY OF OTTAWA  
ONTARIO**

FILE # 210064

Submitted to:

Crestview Innovations Inc.  
12 Escade Drive  
Nepean, ON  
K2G 6R9

REVISION 1                  May 10, 2023

DISTRIBUTION

1 digital copy                  Crestview Innovations Inc.



**Professional Engineers  
Ontario**

Authorized by the Association of Professional Engineers  
of Ontario to offer professional engineering services.



## TABLE OF CONTENTS

<b>TABLE OF CONTENTS .....</b>	<b>ii</b>
<b>1.0 INTRODUCTION .....</b>	<b>1</b>
<b>2.0 FIELD PROCEDURES.....</b>	<b>1</b>
2.1 TERRAIN EVALUATION.....	2
2.2 GROUNDWATER SUPPLY INVESTIGATION.....	3
<b>3.0 TERRAIN EVALUATION.....</b>	<b>4</b>
3.1 SOIL AND GROUNDWATER CONDITIONS .....	4
3.1.1 Shallow Groundwater Sampling.....	7
3.1.2 Discussion of Elevated Nitrates in the Receiving Aquifer .....	8
3.1.3 Land and Water Use Conflicts.....	11
3.2 CLASS IV SEWAGE DISPOSAL SYSTEMS .....	13
3.2.1 Sewage System Envelopes .....	13
3.2.2 Leaching Bed Design Considerations.....	15
3.3 GROUNDWATER IMPACT ASSESSMENT.....	16
3.3.1 Criteria.....	16
3.3.2 Site Conditions Evaluation .....	17
3.3.3 Step 3 Assessment.....	19
<b>4.0 GROUNDWATER SUPPLY INVESTIGATION.....</b>	<b>21</b>
4.1 SUPPLY AQUIFER .....	21
4.2 WATER QUALITY.....	22
4.3 WATER QUANTITY .....	26
4.3.1 Test Well TW1 .....	27
4.3.2 Test Well TW2 .....	27
4.3.3 Test Well TW3 .....	28
4.3.4 Interference Effects .....	28
4.4 GROUNDWATER FLOW DIRECTIONS .....	30
4.5 DEVELOPMENT IMPACTS AND NEIGHBOURING LAND USES.....	32
4.5.1 Impact to Surface Water Quality and Quantity .....	33
4.6 WELL CONSTRUCTION METHODOLOGY .....	33
4.7 POST DEVELOPMENT MONITORING PROGRAM .....	34
<b>5.0 SUMMARY AND CONCLUSIONS.....</b>	<b>35</b>



## TABLE OF CONTENTS continued

### RECORDS OF BOREHOLES BH1, BH2, BH3, BH4, BH5, BH6

TABLE I	– Field Water Quality Measurements for Test Wells
TABLE II	– Summary of Water Chemistry for Test Wells and Sampled Wells
TABLE III	– Summary of Metals for Test Wells
TABLE IV	– Summary of Pumping Test Results and Well Parameters
TABLE V	– Mutual Well Interference Assessment at a Central Well
TABLE VI	– Well Interference Assessment at Property Boundary
TABLE VII	– Measured Drawdown in Observation Wells during Pumping Tests
TABLE VIII	– Storativity Estimate using Observation Well Data
TABLE IX	– Summary of Background Nitrogen Testing

FIGURE 1	– Key Plan
FIGURE 2	– Site Plan
FIGURE 3	– Well Locations
FIGURE 4	– Cross Section East-West
FIGURE 5	– Cross Section North-South
FIGURE 6	– Lot Development Plan

ATTACHMENT A	– Surficial and Bedrock Geology Maps
ATTACHMENT B	– MOE Water Well Records
ATTACHMENT C	– Grain Size Analyses of Soil Samples
ATTACHMENT D	– Results of Laboratory Nitrogen Species Testing of Receiving Aquifer Samples
ATTACHMENT E	– Septic Effluent Dilution Calculations
ATTACHMENT F	– Results of Laboratory Testing of Test Well Water Samples
ATTACHMENT G	– Result of Laboratory Testing of Existing Neighbouring Well Water Samples
ATTACHMENT H	– Pumping Test Data for Test Well TW1
ATTACHMENT I	– Pumping Test Data for Test Well TW2
ATTACHMENT J	– Pumping Test Data for Test Well TW3
ATTACHMENT K	– Observation Well Charts used for Storativity Estimates



## 1.0 INTRODUCTION

Kollaard Associates Inc. was retained by Crestview Innovations Inc. of Ottawa, Ontario to undertake a hydrogeological investigation and terrain evaluation for a site located on Reids Lane. The site is located within Part of Lots 27 & 28, Concession 1, in Osgoode Ward, in the City of Ottawa, Ontario (See Key Plan, Figure 1).

The site consists of an area of approximately 3.5 hectares (8.7 acres) located on the north side of Osgoode Main Street within the village boundary of Osgoode Ward, Ottawa, Ontario. It is proposed to subdivide the site into some 7, average 0.40 hectare lots (minimum 0.4 hectare) for single family dwelling construction purposes. The proposed dwellings will be serviced by private septic systems and wells. The subject site consists mostly of open fields with scattered trees. There are no watercourses on the subject property.

The site is bordered on the west by the Osgoode Link Pathway (a former rail corridor), on the south and north sides by existing residential development and on the east by a municipally-owned woodlot. The existing dwellings to the north and south are serviced by private septic systems and wells.

Based on a review of the surficial geology map for the site area, it is expected that the site is underlain by coarse-textured glaciomarine deposits of sand, gravel, minor silt and clay, predominantly consisting of foreshore and basinal deposits. The bedrock geology map indicates that the bedrock underlying the site consists of dolostone and sandstone of the Beekmantown Group (Attachment A).

## 2.0 FIELD PROCEDURES

The objectives of this study were:

- to determine the shallow subsurface soil and groundwater conditions relative to the design of Class IV septic sewage disposal systems



- to investigate the potential quantity and quality of groundwater available from drilled wells for domestic supply

## 2.1 Terrain Evaluation

The field work for the terrain evaluation was carried out on February 3 and 4, 2021, during which time a total of six boreholes (numbered BH1 to BH6, inclusive) were put down across the site. The boreholes were advanced using a track mounted drill rig equipped with a 200 mm hollow stem auger owned and operated by CCC Drilling of Ottawa, Ontario. The approximate locations of the boreholes are provided in Site Plan, Figure 2.

The boreholes were put down throughout the site. The boreholes were advanced to depths of approximately 4.4 to 9.75 metres below the existing ground surface using 200 mm hollow stem augers. Borehole BH1 was continued to a depth of about 14.52 metres below the existing ground surface as a probe hole until bedrock was encountered. A member of our engineering staff recorded the soils types, depths to strata changes, and groundwater conditions at each borehole location. Groundwater conditions at the boreholes were noted at the time of drilling. Groundwater was also measured at a later date in standpipes installed within three of the boreholes at the time of drilling. The water levels in the standpipes were measured on February 12, 2021, and water samples were obtained from the standpipes for testing of background nitrogen levels. Surficial soil samples were obtained from Boreholes BH1, BH3 and BH5 for laboratory grain size distribution analysis. Two soil samples of underlying soils were also obtained from BH2 and BH4 and underwent hydrometer analysis. All particle analysis results are provided as Attachment C.

To obtain representative samples of the upper groundwater at the site for background testing of nitrogen species, three monitoring wells were installed using the *ASTM Standard D5092-04(2010) Standard Practice for Design and Installation of Groundwater Monitoring Wells*. The monitoring wells installed at BH1, BH3 and BH5 were tested for nitrogen species including nitrites, nitrates, Total Kjeldahl Nitrogen (TKN) and ammonia. The Records of Borehole Logs are provided herein.

### Monitoring Well Sampling Procedure

The sampling procedure was carried out using sampling protocols and methods described in *"Association of Professional Geoscientists of Ontario Guidance for Environmental Site Assessments under 153/04 (as amended), April 2011"*. On February 12, 2021, the static water levels were



measured in each of the standpipes. The standpipes were subsequently purged of approximately three well volumes, and allowed to recover between purgings, prior to water samples being obtained and tested for nitrogen species, including nitrites, nitrates, TKN and ammonia. As no drilling fluids were used during borehole construction, the purging of three well volumes was considered to be sufficient to obtain groundwater samples that were representative of the groundwater in the shallow aquifer. The standing water in the monitoring well was purged using a mechanical displacement pump.

## 2.2 Groundwater Supply Investigation

During the original investigation, to determine the quantity and quality of groundwater available for domestic water supply, three test wells, numbered TW1, TW2 and TW3, were pump tested and sampled. The approximate locations of the test wells are shown on the attached Site Plan, Figure 2. Air Rock Drilling Company Limited of Richmond, Ontario, drilled all three water supply wells on the subject property for the purpose of this hydrogeological investigation on April 26 and 27, 2021. To establish the existing water quality in the area, three offsite neighbouring wells were sampled for water quality. The locations of the test wells, neighbouring sampled wells and other area well records are provided herein as Well Locations, Figure 3. The well records for the wells and the Certificates of Compliance for the test wells are provided herein as Attachment B.

The water well records for the test wells supplied by the well driller indicate that nominal 15 centimetre inside diameter steel casings were installed through the overburden and were set well into the bedrock and grouted in place. The wells were drilled to final depths using a 15 centimetre diameter bit and completed as an open hole in the bedrock. TW1 and TW2 were drilled into the bedrock to final depths of some 76.2 and 74.4 metres, respectively, below the existing ground surface. TW3 was drilled to a depth of 30.5 metres. All three test wells were cased and grouted 3.0 metres into the bedrock with casing lengths of between 18.9 and 20.1 metres.

Pumping tests were conducted on TW1, TW2 and TW3 on May 12, May 10 and May 5, 2021, respectively. The testing consisted of 6 hour duration constant discharge rate pumping tests. During the pumping tests, water level measurements were made on a regular basis to monitor the drawdown of the water level in the wells in response to pumping. After the pumping period, the pump was shut off and the recovery of the water level in the test well was monitored for a period of



time. During the pumping tests, water levels at adjacent test wells were monitored, using pressure transducers, to determine the potential interference effects between the wells.

Groundwater samples were collected from the test wells at about hour 3 and at hour 6 of the pumping tests to characterize groundwater quality. The groundwater samples from the test wells were collected and prepared/preserved in the field using appropriate techniques and submitted to Eurofins Environmental Laboratory in Ottawa, Ontario for the chemical, physical and bacteriological analyses listed in the Ministry of the Environment (MOE) guideline entitled Procedure D-5-5, Technical Guideline for Private Wells: Water Supply Assessment, August 1996 in addition to select heavy metals. The temperature, pH, turbidity, sulphide and residual chlorine levels of the groundwater were measured at periodic intervals during the pumping tests.

Water samples were obtained from three wells servicing existing dwellings located in close proximity to the site at 5560 Lombardy and 5566 Lombardy Drive, located northeast of the site and 5529 Osgoode Main Street, located south of the site. The groundwater samples from the three wells were collected and prepared/preserved in the field using appropriate techniques and submitted to Eurofins Environmental Laboratory in Ottawa, Ontario for the chemical, physical and bacteriological analyses listed in the Ministry of the Environment (MOE) guideline entitled "Technical Guideline for Water Supply Assessment for Subdivision Development on Individual Private Wells," dated July 1992.

### **3.0 TERRAIN EVALUATION**

#### **3.1 Soil and Groundwater Conditions**

This section provides a summarized account of the subsurface soil and groundwater conditions on the subject property based on the information obtained at the borehole locations. Details of the subsurface conditions at the borehole locations are presented in the attached Record of Boreholes. It is noted that in some cases the stratigraphic boundaries within the overburden represent a transition between soil types rather than an exact plane of geologic change. Subsurface conditions differing somewhat from those reported can be expected to exist at the site.

The six borehole locations encountered either fill (consisting of topsoil, sand and gravel), or topsoil. Underlying the surficial organic layers, the engineering staff identified the predominant surficial soil



type at the site as fine to medium sand. Kollaard Associates Inc. (KAI) characterizes soil as fine to medium sand based on textural indicators for grain size. The sand layer was identified to be between 0.7 and 3.0 metres in thickness. The sand layer transitioned from red brown to grey at depths of 0.40 metres below ground surface at BH2 and BH3, and between 0.9 and 1.8 metres at the other borehole locations. BH1 was terminated in sand and continued to presumed bedrock as a probe hole. No soils information below 3.7 metres depth is available from that borehole. Large boulders and/or possible bedrock occur at or below 14.5 metres depth at that location. Below the sand deposit at the other five boreholes (BH2-BH6), a layer of grey sandy silty clay was encountered, of between 0.4 and 1.2 metres in thickness. A silty sand layer of between 0.7 and 1.4 metres in thickness was encountered below the silty sandy clay layer at BH2, BH3, BH4 and BH6. A deposit of grey silty clay was encountered at boreholes BH2, BH4 and BH6. The thickness of this silty clay layer was 2.6 to 3.3 metres at BH2 and BH6. BH4 was terminated within the silty clay layer at a depth of 9.7 metres below existing ground surface. BH2 and BH6 encountered glacial till below the silty clay layer and were terminated on practical refusal on bedrock at depths of 9.0 and 6.7 metres, respectively.

Kollaard Associates Inc. (KAI) characterizes the receiving aquifer at the site as the red to grey fine to medium sand layer and upper portions of the sandy clay or sandy silty clay that was encountered below the sand at five of the borehole locations. The surficial soil is fine to medium sand based on textural indicators for grain size. Three representative samples were obtained from BH1, BH3 and BH5 from depths of 0.8 to 1.4 metres and submitted to a lab for grain size analyses.

The results of a sieve analysis (ASTM C136) on three samples of sand (BH1 - SS2 - 0.76 - 1.37m, BH3 - SS2 - 0.76 - 1.37m and BH5 - SS2 - 0.76 - 1.37m) indicates the samples have the following:

Sample	Depth (metres)	% Gravel	% Sand	% Silt & Clay
BH1	0.76 - 1.37m	0.0	96.5	3.5
BH3	0.76 - 1.37m	0.0	94.9	5.1
BH5	0.76 - 1.37m	0.0	96.7	3.3



The result of a hydrometer test (ASTM D422 and D2216) on one sample of subsurface sandy soil indicates the sample consists of fine sand with some silt and trace clay as follows:

Sample	Depth(metres)	% Gravel	% Sand	% Silt	% Clay
BH4-SS7	4.52 - 5.18m	0.0	85.9	10.1	4.0

The results of a hydrometer test (ASTM D422 and D2216) on a sample of subsurface glacial till soil indicates the sample consists of glacial till as follows:

Sample	Depth(metres)	% Gravel	% Sand	% Silt	% Clay
BH2-SS9	7.62 - 8.22m	17.7	32.1	45.2	5.0

The results of the laboratory testing are located in Attachment C.

The hydraulic conductivity was estimated for the three sand samples using the particle size analyses, as follows.

$$k = 0.35 (D_{15})^2$$

Where  $k$  = hydraulic conductivity, in cm/s

$D_{15}$  = the particle diameter where 15% of soil is passing, in mm

Sample	$D_{15}$ (mm)	K (cm/s)
BH1	0.26	$2.4 \times 10^{-2}$
BH3	0.27	$2.5 \times 10^{-2}$
BH5	0.29	$2.9 \times 10^{-2}$

Based on the above noted information, the hydraulic conductivity of the soil is expected to be  $\sim 2.6 \times 10^{-2}$  cm/s. The soil can be characterized as poorly graded sand. This is considered to be a soil of medium permeability.

The subsurface soils were also sampled. A sample of silty sand from BH4 had 14% fines (silt and clay sized particles) and the underlying glacial till at BH2 contained 50% fines. The silty clay was not sampled, however, it is expected to be of low permeability as it would be considered a fine grained soil. The underlying soils are of medium to low permeability.



The surficial and underlying soils at the site are of medium to low permeability. Based on the soils information, the site is not considered to be hydrogeologically sensitive as there are sufficient soils of medium to low permeability.

Groundwater monitoring wells were installed in three boreholes (BH1, BH3 and BH5). The ground surface and groundwater elevations were subsequently measured on February 12, 2021, as follows.

Monitoring Well	Ground Surface Elevations (masl)	Groundwater Elevations (masl)	
		Feb.12, 2021	March 3, 2022
BH1	92.97	92.50	91.33
BH3	90.53	89.25	90.37
BH5	91.35	89.64	90.13

Water levels in the water supply wells at the site were recorded after the wells were constructed on May 5, 2021, as follows.

Test Well	Top of Casing Elevations (masl)	Ground Surface Elevations (masl)	Groundwater Elevations (masl)	
			May 5, 2021	March 3, 2022
TW1	93.17	92.78	86.45	86.07
TW2	93.08	92.60	86.55	86.09
TW3	91.90	91.34	87.37	87.22

The interpreted groundwater flow directions in the shallow overburden aquifer (sewage effluent receiving aquifer) and the deeper bedrock water supply aquifer are expected to be to the northwest and southeast, respectively, as shown on the attached Figure 2, Site Plan.

### 3.1.1 Shallow Groundwater Sampling

To obtain representative samples of the upper groundwater at the site for background testing of nitrogen species, three monitoring wells were installed using the *ASTM Standard D5092-04(2010) Standard Practice for Design and Installation of Groundwater Monitoring Wells*. The testing includes



nitrogen species nitrates, nitrites, Total Kjeldahl Nitrogen and ammonia. For details on construction and purging procedures see Section 2.1. For borehole locations, see Site Plan, Figure 2.

All of the shallow monitoring wells on the site were sampled on two occasions, February 12, 2021 and March 3 and 11, 2022. Due to the elevated nitrate levels at BH1 (MW1), repeated testing was carried out at that location on June 17, 2022 and February 9, 2023. The laboratory results are provided as Attachment D and a summary of background nitrogen levels is provided as Table IX.

Based on that testing, there has been no increase in nitrates in two of the monitoring wells on site. The level of nitrates in the up gradient well has large fluctuations

### **3.1.2 Discussion of Elevated Nitrates in the Receiving Aquifer**

#### Lateral Migration of Nitrates Across Subject Property

The nitrate levels in the most up gradient monitoring well onsite have fluctuated seasonally from about 5.8 mg/L to 19.7 mg/L. The most recent testing was carried out in February 2023 with a corresponding nitrate level of 19.3 mg/L. The nitrate levels at this location vary from 6 - 8 mg/L up to 19.3 -19.7 mg/L.

In order to evaluate the possible source of the nitrates, several water supply wells located up gradient of the site along Osgoode Main Street were sampled for nitrogen species. The civic addresses where water samples were obtained are provided on Figure 3. These dwellings are indicated to be serviced with driven point (i.e. sand point) wells, based on the information provided by the home owners. A total of four nearby wells were sampled, as follows: 3216 Reids Lane, 5503, 5519 and 5535 Osgoode Main Street. The original laboratory results are provided as Attachment D. The laboratory results indicate the following nitrate levels in three of the four sampled wells; 12.3 mg/L at 5535 Osgoode Main Street, 30.8 mg/L at 3216 Reids Lane and 22.3 mg/L at 5519 Osgoode Main Street. The nitrate level was <0.10 mg/L at 5503 Osgoode Main Street. This well was later confirmed to be a drilled bedrock well (based on a matching well record using the online database which indicates a drilled well was constructed at that address in 2003). As such, the well at 5503 Osgoode Main Street is not obtaining water from the same aquifer as the other properties and that is why the nitrates were not present in that water sample.



The above noted properties that exist along Osgoode Main Street are all undersized with regards to space for sewage systems and potential for sewage impacts. The lot sizes of these properties vary from 0.04 to 0.15 hectares (~0.10 to 0.37 acres). It is considered that these lot sizes are not sufficient to attenuate the nitrates from sewage systems to within acceptable limits. Generally, lot sizes of about 0.4 hectares are necessary to sufficiently dilute sewage effluent, based on the sandy soil conditions in the area. It is understood that some of these properties are not large enough to have sewage systems and at least one of them (3216 Reids Lane) is serviced using a sewage holding tank as the site cannot accommodate a sewage system. These properties have been developed for up to 100 years or more. The source of nitrates in the shallow groundwater at the site is considered to be caused by sewage effluent from the sewage systems servicing properties along Osgoode Main Street and other undersized lots in the older developed parts of the village that are up gradient of the subject property. The source of nitrates is stable and has been present for a long time. There have been no significant changes to development in the area up gradient of the subject site, which has been fully developed dating back to before the earliest available aerial photograph was reviewed for the site (1976 using the City of Ottawa online GeoMaps). As such, it is considered to be a steady state plume, rather than an advancing plume. This is supported by calculating the travel time of groundwater across the site, which provides an indicator of how long the dissolved nitrates in the groundwater up gradient of the site could take to travel across the subject property. This calculation (see below) indicates that it could take from ~1 to ~3 years for sewage effluent from offsite (at or near 3216 Reids Lane) to migrate across the subject property. As the properties have been developed for significantly longer than that, the source of contaminant is considered to be in a steady state (i.e. the contaminant input is not increasing or decreasing).

To determine whether the nitrates measured in BH1 and the up gradient offsite wells are advancing across the site, the following was carried out. The lateral groundwater flow velocity was calculated between BH1 and BH3 using the hydraulic conductivity,  $k$ , of the sandy soils into which these two monitoring wells are screened and water levels measured on two occasions. The calculation is provided (Section 4.4). The resulting lateral groundwater flow across the site is calculated to be about 0.19 to 0.65 m/day (based on groundwater levels at BH1 and BH3 taken on two occasions). The groundwater flow direction is expected to be to the northwest across the site. If the source of nitrates up gradient of the site has been advancing since the first nitrate level was measured at BH1 in 2021, then it could be expected that it would take between 174 days and 597 days for the groundwater plume to travel from BH1 to BH3, using the lateral distance of ~113 metres between those two points. However, based on the nitrate levels at BH3 measured in February 2021 and



March 2022 (some >365 days), there was no increase in nitrates between these two locations over the monitoring interval.

The up gradient concentration at 3216 Reids Lane is some 30.8 mg/L, measured in May 2022. In June 2022, the nitrate level at BH1 was measured to be 8.1 mg/L nitrate. The distance between 3216 Reids Lane and the on site monitoring well at BH1 is some 62 metres. Using the lateral velocity, the plume would take between 97 days and 330 days to reach BH1 and some 272 days to 926 days (~1 to 3 years) to reach BH3 which is also down gradient. So, if the source area is considered as a steady contaminant source (as the properties and septic systems have been in place for upwards of 50 or more years) the groundwater plume should have advanced across the entire subject property. If the nitrate in the plume is conservative (i.e. not degraded) then there should have been a clear increase in the nitrate level at BH1 and nitrate levels at BH3 and/or BH5 should have increased. However, the nitrate concentration at BH3 has been unchanged and BH5 nitrate level is still very low (0.72 mg/L), indicating no anthropogenic impact at either well. This indicates that some other process(es), such as natural attenuation, dilution etc. is causing the nitrate level to decline dramatically between the offsite sources, BH1 and BH3 and BH5.

The background level at BH1 (the most up gradient location on the site) has shown significant seasonal variation (between ~6 mg/l to ~20 mg/L), but the lowest levels of 5.8 and 8.11 mg/L, measured in February 2021 and June 2022, show a steady background level of nitrates over that time with seasonal fluctuations (nitrogen cycle).

It is considered that natural attenuation explains why the nitrate levels have not increased or spread at the site. These processes include denitrification, plant uptake, oxidation/reduction (mineralization), dilution etc. Based on the source of nitrates (i.e. fully developed properties to the south and southeast of the subject property) having been developed for well over fifty years, there are no significant changes to up gradient development, and the lateral gradients indicate that there is no nitrate plume that is advancing on the site.

#### Vertical Migration of Nitrates from Surficial Aquifer to Bedrock Water Supply Aquifer

Based on the sampling of both bedrock water supply wells and driven point wells that exist along there is no indication that nitrates are migrating vertically from the unconfined surficial aquifer to the deeper confined bedrock aquifer at or up gradient of the site.



The concentration of nitrates at the closest bedrock wells (5503 and 5529 Osgoode Main) to the driven point wells (3216 Reids Lane, 5535 Osgoode Main and 5519 Osgoode Main) indicates no detectable nitrates in the bedrock wells despite nitrate levels of 12 to 31 mg/L in the driven point wells. This indicates that the vertical migration of the surficial contaminants is not affecting the bedrock aquifer. Glacial till and silty clay soils underlie the surficial sand aquifer and confining conditions were observed based on the pumping tests carried out at the site. These soil conditions and the presence of the confining unit or aquitard between the aquifers, have demonstrated that the deeper bedrock water supply aquifer is protected from the presence of elevated nitrates in the surficial aquifer.

Based on the above noted information, it is considered that the bedrock water supply aquifer is protected from nitrate impact from the surficial aquifer at the site. This means that the future wells at the site are protected from the increased nitrates that may occur in the surficial aquifer under post development conditions. This has been established by evaluating the conditions on the up gradient lands which have been developed at a much higher density and yet have not affected the target water supply aquifer in the existing development.

It is considered that the existing background nitrate levels in the onsite monitoring wells is acceptable and there is no

### **3.1.3 Land and Water Use Conflicts**

A Phase I Environmental Site Assessment was carried out for the site on October 19, 2022 and a subsequent Phase 2 Environmental Site Assessment was carried out on January 24, 2023. There is no soil or groundwater impact from the previous uses of the site. The following summarizes former uses of the subject property and the current and historical uses of properties within the site vicinity which have been evaluated in terms of the potential for groundwater contamination on the subject property. Dillon Consulting completed a Phase I Environmental Site Assessment (ESA) in November 2016, with subsequent reports regarding debris removal, subsurface investigation, groundwater monitoring and decommissioning of monitoring wells. Based on a review of those reports, the following is noted.



- The Phase I ESA identified a former Imperial Oil fuel depot adjacent to the southwest corner of the site as having been the source for onsite minor soil and groundwater impacts in that portion of the site.
- Fill materials and debris piles across the site represent on site potential sources of contamination.
- Former retail fuel outlets or service garages existed at 5514, 5491, 5543 and 5566 Osgoode Main Street. These are identified as up gradient to the subject property with potential for groundwater contamination (due to PHCs and/or VOCs).
- A soil and groundwater investigation was carried out November 2017 with a total of four soil samples plus one duplicate sample were collected and tested for metals, select VOCs, PAHs and PCBs. Some of the soil samples exceeded the standards for PAHs, lead and arsenic. A total of five groundwater monitoring wells were installed across the site. The overburden groundwater flow direction was estimated to be to the north. Water samples were tested for metals, select VOCs (BTEX), PHCs and PAHs. The only exceedance was vanadium at three locations, which were slightly above the allowable limits for potable water. The source of vanadium was considered to be the silty clay soils which are known to have naturally occurring elevated vanadium levels. The report concludes that the groundwater at the site was not impacted by debris and fill materials that caused soil impacts. The report recommended additional testing of groundwater to confirm the initial testing results.
- In July 2018, the five monitoring wells were retested and the only exceedances were vanadium, at the same three locations. A subsequent review by the MOECC agreed that there was no groundwater impacts from the debris and fill materials at the site and the wells could be abandoned. A subsequent monitoring well decommissioning was carried out and records of well abandonment were provided and registered with the MOECC.

The above noted review of reports indicates that there were no groundwater impacts on the site from gasoline compounds (BTEX), hydrocarbon compounds (PHCs) or metals (with the exception of vanadium which was considered to be due to wells being in contact with silty clay, which is known to contain elevated vanadium). The results of vanadium testing and other metals testing in the groundwater wells indicates that there are no elevated vanadium levels or other metals that exceed the allowable limits for drinking water. The majority of former offsite sources of contamination, namely retail fuel outlets and automotive garages are no longer active, with the exceptions of 5543 Osgoode Main Street and 5566 Osgoode Main Street (Drummond's Gas Bar).



These properties are sufficiently distant, between 40 and 140 metres to the east and southeast of the subject property, such that it is unlikely that there would be any impact on the subject site. The Drummond's gas station had all the previous tanks removed and has been updated with new tanks. Current gas stations are far less likely to cause impacts due to the use of double-walled insulated tanks which are usually constructed using fibreglass that does not degrade and leak, compared to the former use of steel tanks. It should also be noted that many of the existing water supply wells servicing dwellings on Osgoode Main Street are sand point wells. If there were issues with hydrocarbon impacts from nearby commercial development, those wells are much more likely to be impacted. Based on the review of the above noted reports and the current development near the site, there are no concerns with respect to the quality of groundwater supply at the site from the offsite land uses and the historical use of the site.

A review of Permit to Take Water Mapping for a 1 kilometre radius around the site indicates that there are no major water taking activities in the area. The area surrounding the site is mostly developed, with the exception of a vacant parcel to the east. The recent groundwater pumping tests at the site indicate that there is sufficient water supply at the site to support development. As such, there are no concerns with existing development impacting the quantity of water supply at the site.

### **3.2 Class IV Sewage Disposal Systems**

This section discusses the implications of the site-specific terrain conditions in terms of the feasibility of installing Class IV sewage disposal systems within the proposed subdivision.

#### **3.2.1 Sewage System Envelopes**

The septic system envelope area (septic envelope) represents the area on a lot set aside for the construction of the leaching bed and is for the leaching bed only and does not include that area required for the septic tank or the isolation/separation distances required by the Ontario Building Code. The deposit or disposal of any materials or the placement of any structure or the operation of any equipment, other than material, structures or equipment required for the construction of the sewage system within or upon the septic envelope is prohibited.



The size of the septic envelopes are a function of the percolation time of the native soil in the vicinity of the septic envelope and/or the fill used for construction of a septic bed and the daily effluent loading to the septic bed. The native sandy soil at the site is of medium permeability, with an approximate percolation rate of 4 to 6 min/cm (based on Supplementary Guideline Table 2 Approximate Relationships of Soil Types to Permeability and Percolation rate in the Ontario Building Code). The groundwater table at the site is expected to be within 0.9 metres of the ground surface, based on shallow groundwater monitoring wells.

As a conservative approach to determining the expected largest septic system envelope required to service a single family dwelling at this site, a septic system envelope size was calculated assuming a partially raised bed using a percolation rate of 8 minutes per centimetre for the imported sand required and a daily sewage flow of 3000 litres. A design flow of 3000 litres per day is suitable for a five bedroom dwelling with 250 square metres of finished area and 30 fixture units. The following formulae were used to calculate the size of the septic envelope:

The larger of

$$A = \frac{Q}{8} \quad \text{OR} \quad A = \frac{1.6QT}{200} \text{ plus}$$

4:1 Leaching Bed Side Slopes

Where            Q = daily sewage flow for the proposed dwelling (i.e., 3,000 litres per day)

                  T = percolation rate of imported fill material

The size of the septic envelopes, based on the conservative approach described above, is approximately 375 square metres. In view of the minimum proposed lot sizes of about 4055 square metres, and average lot sizes of about 4290 square metres, sufficient area exists at each of the proposed lots for the construction of a conventional septic system that meets the requirements of the Ontario Building Code.

Prior to establishing the actual septic envelope (leaching bed) location on any particular lot, several test holes should be excavated to determine the consistency/variability of the overburden in the vicinity of the proposed septic envelope and percolation rate tests should be carried out to determine the actual envelope area and whether imported mantles are required.



Other site-specific considerations with respect to the locations of the septic envelopes (leaching beds) on the proposed lots are as follows:

- assuming that shallow groundwater flow within the upper overburden is from topographically higher areas to topographically lower areas, the septic envelopes should be situated in the topographically lower areas with the wells on the topographically higher areas
- the separation distances between septic envelopes and properly constructed drilled and cased wells should be at least twice the grade raise plus 15 metres for partially to fully raised beds as required by the Ontario Building Code

### **3.2.2 Leaching Bed Design Considerations**

The design of leaching beds is a combination of a number of interrelated factors including effluent discharge volume, properties of the soil materials in the leaching bed, length of distribution lines and the subsurface conditions. The construction of individual septic disposal systems on the proposed lots should be carried out in accordance with the specifications set out in the Ontario Building Code.

The design must ensure that the bottom of the absorption trenches is at least 0.9 metres above bedrock or soils that are unsuitable for treatment of septic effluent (those with excessively low permeability), and at least 0.9 metres above the seasonally high groundwater table.

Based on the soil and groundwater conditions at the site, partially raised septic system leaching beds are likely to be used. The actual leaching bed type appropriate for each lot will depend on the individual lot specific soil and groundwater conditions.

Any partially raised leaching beds should be constructed of imported sand having a percolation time of between 6 and 8 minutes per centimetre with less than 5 percent passing the #200 (0.074 mm) sieve. It is recommended that gradation analyses be carried out on any potential sand fill prior to leaching bed construction in order to verify that the percolation time of the fill material is acceptable.



### 3.3 Groundwater Impact Assessment

#### 3.3.1 Criteria

The Ministry of the Environment (MOE) Procedure D-5-4 provides guidelines for evaluating "the ability of the lands identified by and restricted to the development document, to treat sewage effluent to meet acceptable limits". The guideline requires that the representative background nitrate levels in the receiving groundwater be determined. Where background levels are greater than 10 milligrams per litre the ministry indicates development of the site should not be supported unless it can be demonstrated that existing levels of nitrates are the results of historical agricultural practices on the site. In addition, the guideline requires demonstration that the site is not obviously hydrogeologically sensitive such as karstic areas, areas of fractured bedrock exposed at the surface, areas of thin soil cover or areas of highly permeable soils.

The guideline indicates that the assessment involves a three step process.

Step 1 regards lot size considerations. Where the lot size for each private residence within the development is an average of one hectare or larger and no lot is smaller than 0.8 hectares, and provided the site is not hydrogeologically sensitive, the risk that impact limits may be exceeded by individual systems is considered acceptable.

Step 2 is in regards to septic system isolation considerations. Developments are considered low risk when it can be demonstrated that sewage effluent is hydrogeologically isolated from existing or potential supply aquifers. For this case the most probable groundwater receiver for sewage is to be defined through information obtained through a test pit or test hole program, and the most probable lower hydraulic or physical boundary of the groundwater receiving sewage effluent is to be defined. The guideline indicates hydrogeologic information concerning lands up to 500 metres beyond the actual development boundary may be required. When it can be demonstrated that the sewage will not enter supply aquifers the lot density of the proposed development is determined based on the space required to install a suitable septic system at each lot in accordance with the Ontario Building Code.

Step 3 is in regards to contaminant attenuation considerations. For this case, it is required to assess the risk that the on-site sewage systems within the proposed development will cause a



concentration of nitrate in groundwater above 10 milligrams per litre at the down gradient boundary of the site.

### 3.3.2 Site Conditions Evaluation

In order to evaluate the background water quality conditions in the receiving aquifer, three shallow monitoring wells were installed at the site and tested for nitrogen species. The construction details are provided in Section 2.1, the Records of Boreholes are appended to the report and groundwater levels are reported in Section 3.1. Background nitrogen concentrations from the shallow groundwater receiving effluent were reported (Section 3.1.1) and the original laboratory testing results are in Attachment D. The Site Plan, Figure 2, shows the locations of the monitoring wells.

The Ministry of the Environment, Conservation and Parks (MECP) Guideline D-5-4 indicates that:

*“.....where nitrate concentrations between 0 and 10 mg/l are found, the MOECC may also decide not to support development if the proponent’s consultant cannot provide a reasonable explanation for the existing levels of nitrate concentrations in the groundwater. However, if it can be demonstrated that existing levels of nitrates are the result of historical agricultural practices on the site (for example farming, feed lot, etc.), the proponent may be able to argue that the nitrate levels will decline after development”*

The results of nitrogen testing (see Table IX) indicate that in two of the three borehole locations, total nitrogen levels were 0.28 to 0.33 mg/l. At BH1 (in the southeast portion of the site) the total nitrate level has been measured from 5.8 and more recently 8.1 mg/l, with seasonal fluctuations of up to 19.3 and 19.7 mg/L. The monitoring of this location indicates that the nitrate levels fluctuate seasonally. On the initial testing, the nitrate level was 5.8 mg/L which increased to 19.7 mg/L (Spring time recharge), then decreased to 8.1 mg/l (Summer, lower recharge) and increased again to 19.3 mg/L.

Further discussion of the background nitrate levels at the site and the likely source of nitrogen is provided (Section 3.1.2).



The site is not obviously hydrogeologically sensitive as no karstic areas, areas of fractured bedrock exposed at the surface or areas of highly permeable soils are indicated to be present at the site. Three soil samples of the surficial sandy soils were obtained and laboratory grain size distribution analysis was carried out. The surficial soils consist mainly of fine sand with low silt/clay content (3 to 5%) which has an average estimated hydraulic conductivity of  $\sim 2.6 \times 10^{-2}$  cm/s (Section 3.1). The soil can be characterized as poorly graded sand. This is considered to be a soil of medium permeability.

The subsurface soils were also sampled. A sample of silty sand from BH4 had 14% fines (silt and clay sized particles) and the underlying glacial till at BH2 contained 50% fines. The silty clay was not sampled, however, it is expected to be of low permeability as it would be considered a fine grained soil. The underlying soils are of medium to low permeability.

The surficial and underlying soils at the site are of medium to low permeability and the overburden thickness at the site is at least 15 metres or more in thickness. Based on the soils information, the site is not considered to be hydrogeologically sensitive.

The water supply aquifer at the site is considered to be confined, based on the following:

- The piezometric surfaces in the three water supply wells (see cross sections, Figures 4 and 5) are above the top of the aquifer (bedrock elevation); and
- the shape of the drawdown response curve observed in the pumping tests closely resembles the ideal response of a confined aquifer; and
- the storativity coefficient calculated using the drawdown response in adjacent wells is  $\sim 2.0 \times 10^{-4}$ , whereas specific yield in an unconfined aquifer is typically orders of magnitude higher; and
- Based on the depth and type of soils onsite, there is a confining unit consisting of silty clay and/or glacial till which are some 9 metres to 15 metres in thickness.

As the water supply aquifer is confined, this is indicative that there is some confining unit that prevents direct vertical migration of surface water into the water supply at depth. This is also indicative that the site is not hydrogeologically sensitive.



The minimum lot size proposed for the development is about 0.40 hectares. Accordingly, the above noted "Step 1" does not apply to this site. Hydrogeological isolation between the receiving and water supply aquifers was not evaluated for this site. Thus, "Step 3" was addressed for this site.

### 3.3.3 Step 3 Assessment

The most probable groundwater receiver for sewage effluent is the red to grey fine to medium sand layer and upper portions of the sandy clay or sandy silty clay that was encountered below the sand at five of the borehole locations. To obtain a general indication as to the potential impact of septic effluent on the properties adjoining the proposed development, a nitrate dilution model was used. A daily effluent loading of 1000 litres per day per septic system was assumed and the expected impact of septic systems at this site was determined by considering the attenuation of nitrate in the effluent from an assumed 40 milligrams per litre (mg/l) ( $\text{NO}_3$  as N) after the septic system treatment to the property boundary by dilution as a result of the infiltration of meteoric water only. The following provides the basis whereby the infiltration reduction factors for the site were chosen for the dilution calculations.

Topographic, soil and land cover infiltration factors were selected from *Table 2* of the MOE *Hydrological Technical Information Requirements for Land Development Applications*. The following is a discussion of each of the infiltration reduction factors chosen for the site.

A soil infiltration factor of 0.40 for open sandy loam is appropriate for the septic effluent dilution calculations, based on the permeability of the soils encountered across the site. Given the continuous nature of the sandy overburden at the site, with between 3 and 5 % silt/clay content in all three sieve analyses, and all six borehole logs describe the surficial soil as fine to medium sand, a terrain map was not considered to be required to delineate the terrain distribution across the property.

The site is characterized by rolling terrain with highest elevations within the southeast portion of the site sloping to the northwest. The steepest slope across the site is to the northwest of about 6 metres over one kilometre and average slope across the site is to the northwest of about 3.0 metres per kilometre. The site is considered to be rolling with a slope infiltration factor of 0.20. Using *Table 10* of the Thorntwaite and Mather *Instructions and Tables for Computing Potential Evapotranspiration and the Water Balance*, a soil water holding capacity of 100 millimetres was



provided for the sandy overburden at the site. The value was chosen based on the combination of mainly pasture (deep-rooted crops) in fine sand. However, post-development, it is expected that the site will be mainly grassed (shallow-rooted crops) and the soil is fine sand. The corresponding soil water holding capacity of the site for post development conditions is expected to be between about 50-75 millimetres. The selection of 100 millimetres is conservative, as it overestimates the applicable soil moisture retention for the soils, which results in underestimating the available moisture for infiltration.

The type of land cover observed at the site at the time of site visits and by use of satellite imagery consists mostly of cultivated lands, although there are scattered trees and shrubs across the site. It is expected that the post-development conditions at the site will consist mainly of grassy areas with few trees and shrubs. The land cover infiltration factor of 0.10 was selected, which corresponds to cultivated lands. This is a conservative prediction as it does not account for the mature trees which may be retained or the landscape trees and shrubs that will likely be cultivated on properties post development.

In order to determine water surplus estimates for the site area, a water surplus model was obtained using published information from Environment Canada (EC) for the City of Ottawa. The water balance model output the average yearly moisture surplus value, based on monthly moisture surplus averages for the period from 1939 to 2021. The expected moisture surplus or net potential infiltration for the site area was estimated at 379 millimetres. The water balance model output data, provided by EC, are provided as Attachment E.

Hard Surfaced Areas post-development were calculated as follows. The total roadway area for the site is 2054 square metres, as provided by Novatech. The other hard surfaced areas are estimated to be 600 m<sup>2</sup> per lot (for each dwelling and driveway). The total hard surfaced areas using these values for post-development conditions are 6254 m<sup>2</sup>.

Post-development conditions include a stormwater management pond, roadside ditches and grassed swales as well as downspouts from the roofs of the dwellings. All of these measures reduce runoff and promote groundwater infiltration on site. The natural background conditions at the site are sandy soil which is expected to readily infiltrate precipitation. The performance of grassed swales in these conditions could be 50%, which reduces the impact of the hard surfaced areas significantly. Even when runoff exceeds the capacity of the swales and roadside ditches, the



stormwater pond is also designed to infiltrate groundwater. Based on this information, it is considered that allotting 600 m<sup>2</sup> per lot is justified, even if actual building footprints are larger or if other structures (pools, other hard landscaped areas etc.) are not accounted for. This is because the effect of stormwater infiltration by the above noted means is not included in the calculation of the sewage effluent dilution calculations and is considered to be conservative (i.e. over estimating expected runoff).

The results of the sewage dilution calculations indicate that the expected concentration of nitrate at the site boundary due to the proposed 7 sewage systems is about 9.9 milligrams per litre (Attachment E). This is within the Ministry of the Environment acceptable nitrate impact limit of 10 milligrams per litre.

Based on the impact assessment, the development of the site on private sewage disposal systems is not expected to have an adverse impact on groundwater resources in the site area.

## 4.0 GROUNDWATER SUPPLY INVESTIGATION

### 4.1 Supply Aquifer

As mentioned above, a bedrock geology map for the site area indicates that dolostone and sandstone of the Beekmantown Group underlie the site. The MOE well records for the test wells indicate the primary material encountered was limestone during drilling for all three test wells. The MOE well records for TW1 and TW2 indicate sandstone was encountered as a secondary material below 49 to 55 metres in depth, while TW3 which was a shallow well at 30 metres depth encountered limestone with no secondary material. A review of the MOE water well records for the test wells, Attachment B, indicate that TW1 and TW2 encountered water fractures during drilling in the bedrock at depths of some 72 to 74 metres. TW3 encountered fractures at depths of about 21 and 28 metres. Geological cross-sections of the site were prepared using soils and bedrock information from the MOE well records for the test wells and the Records of Boreholes. The geological cross sections are provided as Figures 4 and 5.



## 4.2 Water Quality

The results of the chemical, physical and bacteriological analyses of water samples obtained from the test wells are provided as Attachment F and field water quality data is provided in Table I. A summary of the laboratory test results is attached as Tables II and III. The water quality as determined from the results of the analyses is favourable. The water meets all the Ontario Drinking Water Standards (ODWS) health and aesthetic parameters tested for at the test wells except for the following:

- hardness at all of the wells
- total dissolved solids at all of the wells
- hydrogen sulphide at TW1 and TW2
- iron at TW2 and TW3
- organic nitrogen at TW1 and TW3
- sodium above 20 mg/l at all of the wells

### Hardness

The water samples from all of the test wells are considered hard by water treatment standards. Water with hardness above 80 to 100 milligrams per litre as CaCO<sub>3</sub> is often softened for domestic use. The hardness at the test wells ranges from about 211 to 310 milligrams per litre. Water softening by conventional sodium ion exchange will reduce hardness and scaling on fixtures. However, it may also introduce relatively high concentrations of sodium into the drinking water, which may contribute a significant percentage to the daily sodium intake for a consumer on a sodium restricted diet. Where ion exchange water softeners are used, a separate unsoftened water supply could be used for drinking and culinary purposes.

### Total Dissolved Solids

The total dissolved solids (TDS) were measured at 539 to 618 milligrams per litre, the three test wells, above the ODWS of 500 milligrams per litre. The Ryznar Stability Indices (RSI) and Langelier Saturation Indices (LSI) were calculated for the samples and gave RSI values of between 7.1 and 7.5 and LSI values between 0.25 and 0.5. The values of RSI that are close to 7 and slightly above 7, indicate that the formation of calcium carbonate (i.e. scaling) does not lead to a protective corrosion inhibitor film on metal fixtures and pipes. However, there RSI value is less than 8,



indicating that the water is not corrosive either. LSI values are corresponding positive, but close to zero, which indicates that the water has borderline scale potential, such that minor changes in the water quality, temperature could change the scale or corrosive potential of the water. The effect of elevated TDS levels on drinking water depends on the individual components, which are principally chlorides, sulphates, calcium, magnesium and bicarbonates. Depending on which parameters are elevated, TDS exceedances can include hardness, taste, mineral deposition or corrosion. In this case, all the test well water samples have high levels of hardness and elevated chlorides (155 to 180 mg/l) albeit within the operational guideline for hardness and the aesthetic objective (AO) for chlorides. Chloride is less than the AO and consequently the water palatability is still considered to be good. Therefore, the effect of elevated TDS is considered to be mostly associated with elevated hardness, which can cause mineral deposition, due to the potential for scale to form. As hardness is the cause of the elevated TDS, it is considered that treatment to reduce hardness (ion exchange water softeners) will reduce the mineral deposition associated with the TDS levels.

### Hydrogen Sulphide

Hydrogen sulphide levels at TW1 and TW2 are above the aesthetic objective of 0.05 mg/l. TW1 had sulphide levels of 1.10 mg/l and TW2 had lower levels at 0.24 to 0.27 mg/l. Hydrogen sulphide produces an odour and can affect the taste of water. When present in water with iron, it can also cause black staining of laundry items, black deposits on pipes and fixtures. Treatment to reduce sulphide includes aeration. Higher levels of sulphide where iron staining is also an issue (rust staining) may require treatment using chlorination followed by iron filter. Based on the sulphide levels at the site, it is considered that aeration is sufficient to reduce sulphide in the treated water. Well construction recommendations are also made later in this document to ensure that excessive sulphide levels are avoided in future wells at the proposed subdivision.

Three offsite wells were sampled and also had exceedances for hydrogen sulphide. The highest level was at 5560 Lombardy Drive with a hydrogen sulphide level of 8.3 mg/l. The well record for that well indicated that water fractures were encountered at 41 metres depth. In addition, a report for the adjacent subdivision located west of the site entitled "*Report on Site Conditions and Hydrogeology for Top Drawer Holdings Ltd., Proposed Subdivision, Village of Osgoode, March 1978 by Oliver, Mangione, McCalla & Associates Ltd.*" was reviewed with regards to water quality. That report indicated that one of the test wells, drilled to 44 metres depth encountered sulphur water at a depth of about 38 metres depth. Based on this and the occurrence of high levels of hydrogen sulphide at one of the offsite wells (5560 Lombardy Drive), Kollaard Associates Inc. Is



providing well construction recommendations to ensure that the future wells avoid very elevated levels of hydrogen sulphide that are associated with the water fractures encountered at 38 to 41 metres depth.

#### Iron

The level of iron at TW2 and TW3 was elevated for the first water samples obtained after three hours (iron levels of 0.46 and 0.54 mg/l), compared to the AO of 0.3 mg/l. However, by the end of the pumping tests, the iron levels were within aesthetic objectives for all three test wells and ranged from 0.11 to 0.21 mg/l. Three other area wells that were sampled also had iron levels within the acceptable limit of 0.3 mg/l. As a result, iron is considered to be within the aesthetic objective of 0.3 mg/l. It should also be noted that water softening to reduce hardness can also decrease iron.

#### Organic Nitrogen

Organic nitrogen levels at TW1 and TW3 were 0.20 and 0.17 mg/l, respectively, compared to the operational guideline (OG) of 0.15 mg/l. Organic nitrogen is calculated by subtracting the ammonia from the Total Kjeldahl Nitrogen. Organic nitrogen has an OG due to its interaction with chlorine used in water treatment causing taste problems in the treated water. There is a correlation between DOC and organic nitrogen. Organic nitrogen levels above 0.15 mg/l are associated with DOC levels of 0.6 mg/l or greater. As groundwater is typically not treated using chlorine, the potential presence of organic nitrogen in some wells does not require treatment.

#### Sodium

The sodium levels at all three test wells were between 64 and 98 mg/l, above the 20 milligrams per litre advisory level, whereby the local Medical Officer of Health should be notified when the sodium concentration exceeds 20 mg/L so that this information may be communicated to local physicians for their use with patients on sodium restricted diets. The sodium levels were well within the aesthetic objective of 200 mg/l.

#### Sampling of Existing Neighbouring Wells

Neighbours of the site along Lombardy Drive and Osgoode Main Street were canvassed with regards to their servicing. At that time, some of the property owners/tenants along Osgoode Main Street indicated that the wellheads were either below grade or that sand point wells were in use. One property owner indicated that they do not have a sewage system but a holding tank. The



following three wells were sampled as the owners indicated that they had drilled wells and sewage systems.

#### 5529 Osgoode Main Street

- water treatment: iron filter
- water potability: owner drinks water and indicates sulphur odour is present sometimes
- routine bacterial testing: Not since purchase (6 years previous), at which time results were acceptable
- septic system type, age, location and performance: conventional sewage system replaced within last 10 years and no issues
- Well location in east side yard and sewage system in rear yard

#### 5560 Lombardy Drive

- water treatment: aeration, chlorination, iron filter, water softener
- water potability: owner indicates sulphur is a nuisance and treatment equipment maintenance is excessive and problematic. A lot of frustration as adjacent neighbours don't have similar water quality complaints/issues and onerous treatment costs.
- routine bacterial testing: No, but no issues
- septic system type, age, location and performance: original conventional sewage system in front yard, ~5 years old
- Well location in back yard and sewage system in front yard

#### 5566 Lombardy Drive

- water treatment: proprietary filter media, iron filter and water softener
- water potability: Owner indicates sulphur is present.
- routine bacterial testing: No, but no issues
- septic system type, age, location and performance: original conventional sewage system in front yard, ~5 years old
- Well location in back yard and sewage system in front yard



A summary of the water quality obtained from the neighbouring wells and copies of well records (where available) are provided as Table II and Attachment B. The original laboratory test results are provided as Attachment G.

Well records for the wells at 5560 and 5566 Lombardy Drive were available for review. The well records indicate that the well depths are 49 metres and 73 metres, respectively. The well at 5529 Osgoode Main Street is much older and no well record could be confirmed. The well cap could not be removed at the time of the site visit to confirm well depth. However, based on the similarity of water quality in that well to the subject wells, it is considered to be obtaining water from the same formation as other bedrock wells in the area. The test wells on the site are between 30 metres in depth (TW3) and 74 and 76 metres in depth for TW1 and TW2, respectively.

The water quality at the existing wells was generally similar to that of the recently constructed test wells, with exceedances of TDS, hardness and hydrogen sulphide. The exception is the well at 5560 Lombardy Drive, which had very high levels of hydrogen sulphide. That well had a hydrogen sulphide level of 8.3 mg/l in the raw water. At the time of sampling the treated water was also sampled to confirm that hydrogen sulphide could be treated to within the aesthetic objective. The treated water had a hydrogen sulphide level of <0.01 mg/l.

#### **4.3 Water Quantity**

The drawdown and recovery data and plots for TW1, TW2 and TW3 are provided as Attachments H, I and J, respectively. The drawdown and recovery data provided were measured with reference to the top of the well casing at each test well location.

The pumping test data for the test wells were analyzed using the method of Cooper and Jacob (1946). Although the assumptions on which these equations are based are not strictly met, this method provides a reasonable estimate of the aquifer transmissivity. The analysis of the data obtained during the pumping tests is summarized in the attached Table IV. The water levels in observation wells were monitored during the pumping tests at TW1, TW2 and TW3 and the data are provided as Table VII. Where observation well drawdown had occurred, with interference between TW1 and TW2 during the pumping tests at those wells, corresponding curves of that data are provided as Attachment K. TW3 was too distant from TW2 and TW3 for any significant drawdown to be measured.



The following sections discuss the results of the analysis of the data obtained during the pumping tests with respect to test well yields.

#### **4.3.1 Test Well TW1**

The six hour duration pumping test was carried out at a discharge rate of 65 litres per minute. The static water level prior to testing was about 6.86 metres below the top of the well casing and the water level after six hours of pumping was about 8.24 metres below the top of the well casing for a total drawdown at the end of pumping of 1.38 metres. The available drawdown in the well is about 36 metres. The specific capacity of the well at this pumping rate is approximately 68 cubic metres per day per metre of drawdown.

Based on the pumping test drawdown data the transmissivity of the aquifer is estimated to be 288 m<sup>2</sup>/day. Based on the recovery data the aquifer transmissivity is estimated to be 192 m<sup>2</sup>/day. The average transmissivity of the bedrock aquifer in the area of TW1 is estimated to be 240 m<sup>2</sup>/day. At the end of pumping, 95 percent recovery of the total drawdown in the static water level created during pumping occurred in about 14 minutes.

Based on the data obtained during the pumping test, it can be concluded that the well is capable of sustaining a short term yield of at least 65 litres per minute and that during the course of the six hour pumping period about 4 percent of the available drawdown in the test well was utilized.

#### **4.3.2 Test Well TW2**

The six hour duration pumping test was carried out at a discharge rate of 62 litres per minute. The static water level prior to testing was about 6.68 metres below the top of the well casing and the water level after six hours of pumping was about 7.72 metres below the top of the well casing for a total drawdown at the end of pumping of about 1.04 metres. The available drawdown in the well is about 36.6 metres. The specific capacity of the well at this pumping rate is approximately 86 cubic metres per day per metre of drawdown.

Based on the pumping test drawdown data the transmissivity of the aquifer is estimated to be 181 m<sup>2</sup>/day. Based on the pumping test recovery data, the transmissivity of the aquifer is estimated to



be 203 m<sup>2</sup>/day. The average transmissivity of the bedrock aquifer in the vicinity of TW2 is calculated to be about 192 m<sup>2</sup>/day. At the end of pumping 95 percent recovery of the total drawdown in the static water level created during pumping occurred within about 75 minutes.

Based on the data obtained during the pumping test, it can be concluded that the well is capable of sustaining a short term yield of at least 62 litres per minute and that during the course of the six hour pumping period about 3 percent of the available drawdown in the test well was utilized.

#### **4.3.3 Test Well TW3**

The six hour duration pumping test was carried out at a discharge rate of 65 litres per minute. The static water level prior to testing was about 4.53 metres below the top of the well casing and the water level after six hours of pumping was about 4.76 metres below the top of the well casing for a total drawdown at the end of pumping of 0.23 metres. The available drawdown in this well is about 20.5 metres. The specific capacity of the well at this pumping rate is approximately 410 cubic metres per day per metre of drawdown.

Based on the pumping test drawdown data the transmissivity of the aquifer is estimated to be 192 m<sup>2</sup>/day. Based on the pumping test recovery data, the transmissivity of the aquifer is estimated to be 203 m<sup>2</sup>/day. The average transmissivity of the bedrock aquifer in the vicinity of TW3 is calculated to be about 192 m<sup>2</sup>/day. At the end of pumping 90 percent recovery of the total drawdown in the static water level created during pumping occurred after 111 minutes. After 7 hours and 25 minutes, the static water level had recovered 100%.

Based on the data obtained during the pumping test, it can be concluded that the well is capable of sustaining a short term yield of at least 65 litres per minute and that during the course of the six hour pumping period about 1 percent of the available drawdown in the test well was utilized.

#### **4.3.4 Interference Effects**

During pumping of the test wells, observation well drawdown was observed in each of the other test wells to measure interference effects. The data were obtained from pressure transducer loggers and confirmed with manual measurements. The transducer data is provided as Table 7. The mutual interference effects were calculated for a centrally located well (Lot 2) and the well



interference at the property boundary was calculated for the down gradient property line along the north side of the site.

In order to estimate the maximum interference between future wells at the site, calculations were carried out to predict the cumulative thirty year drawdown due to the proposed 7 domestic wells at a central well in the proposed subdivision. The cumulative drawdown at the test wells was calculated for a thirty year pumping rate of 1100 litres per day which allows for four persons per household. The following formula was used for the calculation:

$$s = \frac{2.3Q}{4\pi T} \log\left(\frac{2.25Tt}{r^2 S}\right)$$

where Q = 30 year pumping rate, 1100 L/day

T = average transmissivity, 203 m<sup>2</sup>/day

t = duration, 30 years

S = storativity, 2.4 x 10<sup>-4</sup>

s = expected drawdown due to each of the other 6 wells

r = distance between the observation well and the pumped well, m

The results of the calculations indicate the thirty year drawdown at a centrally located well due to the interference from the other 6 wells in the subdivision is about 0.038 metres. The mutual well interference at the property boundary due to the 7 proposed wells was also estimated to determine the impact of the proposed development on water supply outside of the site. The expected thirty year drawdown at the site boundary was found to be about 0.044 metres.

Attachment B contains MOE Well Records of surrounding existing wells that were available for review. The indicated depths of the existing wells range from about 24 to 73 metres and accordingly are within an aquifer similar to the test wells which range in depth from about 30 to 76 metres. Based on the estimated thirty year drawdown noted above, the expected drawdown is minimal. All wells for which the MOE Well Records were obtained have sufficient available drawdown such that the slight drop in water level that may occur should have no significant impact on water supply at our adjacent to the proposed subdivision. This provides reasonable assurance of adequate water supply in the proposed subdivision as well as at the existing wells.

#### TW1 observation well interference



During the pumping of TW1, pressure transducer logging was carried out at TW2 and TW3, located some 45 metres and 117 metres distance, respectively, from TW1. Total drawdown observed at TW2 and TW3 was about 0.39 metres and 0.00 metres, respectively. There was no drawdown response at TW3, which is considered to be due to the greater distance between that well and the pumped well. In fact, water levels rose slightly in that well during the test and then declined shortly after the test was completed (during recovery interval). It is possible that the water level rose due to the change (i.e. drop) in pressure at the piezometric surface that occurred as a result of the pumping of the adjacent well. The drop in pressure can contribute to a small rise in water levels of adjacent wells, due to the decrease in pressure head. This is indicative that there is a likely connection between the wells, but that the distance between them did not contribute to a drop in water level.

#### TW2 observation well interference

During the pumping of TW2, pressure transducer logging was carried out at TW1 and TW3, located some 45 metres and 117 metres distance, respectively, from TW2. Total drawdown observed at TW1 and TW3 was about 0.42 metres and 0.04 metres, respectively.

#### TW3 observation well interference

During the pumping of TW3, pressure transducer logging was carried out at TW1 and TW2, located some 117 metres and 118 metres distance, respectively, from TW3. There was no measurable drawdown response in either observation well during the pumping test at TW3. This was considered to be due to the distance between this well and the other wells.

Based on the interference observations, especially that between TW1 and TW3, which are constructed on adjacent proposed lots some 45 metres apart, it is considered that the level of interference is acceptable and will not cause unacceptable drawdown in adjacent future wells at the property.

#### **4.4 Groundwater Flow Directions**

The groundwater flow directions and gradients in the receiving and water supply aquifers were determined based on the results of a topographic survey of the site and using the static water levels measured at the standpipes (overburden receiving aquifer) and test wells (bedrock water supply aquifer).



### Receiving Aquifer

The static water level elevations at BH1, BH3 and BH5 were 92.50, 89.25 and 89.64 metres geodetic, respectively, measured on February 12, 2021. Based on that data, the receiving aquifer flow direction is indicated to be northwest across the site (see Figure 2), generally following the topographic slope at the site.

Monitoring Well	Ground Surface Elevations (masl)	Groundwater Elevations (masl)	
		Feb.12, 2021	March 3, 2022
BH1	92.97	92.50	91.33
BH3	90.53	89.25	90.37
BH5	91.35	89.64	90.13

Lateral gradient between BH1 and BH3 (using data from Feb. 12, 2021)

$$i = dh / L = (92.50 - 89.25) / 113.4 = 0.029$$

$$V = K * i$$

$$V = (2.6 \times 10^{-2} \text{ cm/s}) * 0.029$$

$$V = 7.54 \times 10^{-4} \text{ cm/s}$$

V = 0.65 m/day (using data from Feb. 12, 2021)

$$i = (91.33 - 90.37) / 113.4 = 0.0085$$

V = 0.19 m/day (using data from March, 2022)

Based on the gradients and the permeability of the sandy soil (calculated in Section 3.1), groundwater flow across the site migrates in the lateral direction between 0.19 and 0.65 m/day. The groundwater flow direction is expected to be to the northwest across the site.

### Confined Bedrock Water Supply Aquifer

The static water elevations at TW1, TW2 and TW3 are provided below. Based on that data, the supply aquifer groundwater flow direction is indicated to be east-southeast across the site (see Figure 2).

Test Well	Top of Casing Elevations (masl)	Ground Surface Elevations (masl)	Groundwater Elevations (masl)	
			May 5, 2021	March 3, 2022



TW1	93.17	92.78	86.45	86.07
TW2	93.08	92.60	86.55	86.09
TW3	91.90	91.34	87.37	87.22

### Vertical Gradients

Based on elevations in the test wells, compared to the shallow monitoring wells, it is possible that a downward vertical gradient could exist between the receiving aquifer and the bedrock aquifer at the site. However, there is also the presence of a silty clay/glacial till deposit between the two aquifers that is acting as an aquitard to reduce or slow the downward migration of contaminants. This is considered to be a confining unit that is protective of water quality in the bedrock water supply aquifer based on the testing of up gradient wells. The two bedrock wells located along Osgoode Main Street (namely 5503 Osgoode Main and 5529 Osgoode Main) are both drilled bedrock wells with negligible nitrate levels, even though the shallow driven point wells (propagated within the shallow sandy aquifer) have elevated nitrate levels of between 12 and 31 mg/L. Based on the long duration of development in that area, it is considered that there is no hydraulic connection between the surficial aquifer at the site and the deeper bedrock water supply aquifer.

### **4.5 Development Impacts and Neighbouring Land Uses**

A description of existing and historical land uses at and near the site with the potential to impact the water supply at the site was previously noted (Section 3.1.2 Land and Water Use Conflicts). The existing land use up gradient of the site in terms of the deeper bedrock aquifer (i.e west-northwest) consists of scattered single family dwellings and agricultural lands, with the Rideau River some 2.4 kilometres to the west. The results of the water quality testing at the test wells indicate that there is no significant impact on the deeper aquifer at the site due to the surrounding residential and agricultural development.

The topographical slopes and the shallow groundwater flow direction within the overburden at the site are to the northwest, based on the shallow monitoring wells installed as part of the current hydrogeological and terrain investigation. A review of current and historical land uses in the area suggests that the up gradient land (to the south and southeast) is fully developed with residential and commercial development including up gradient potential sources of contamination, especially hydrocarbons, due to current and former automotive garages and service stations. Previous



environmental investigation was carried out by Dillon Consulting which included soil and groundwater testing. In 2017 and 2018, two rounds of groundwater testing were carried out on five shallow monitoring wells installed across the subject property. The overburden groundwater flow direction was estimated to be to the north, based on those monitoring wells. Water samples were tested for metals, select VOCs (BTEX), PHCs and PAHs. The concentrations of the above noted parameters were all within the Table 2 Standards (O. Reg. 153/04 Table 2 Standards 2011, for potable groundwater). Since that time, there has been no new development of properties that could cause hydrocarbon contamination at the subject site. It is considered that there are no current impacts at the site from up gradient sources. All three drilled water supply wells installed at the site were tested on March 4, 2022, for PHCs F1-F4 and VOCs. None of the tested parameters were measured above the method reporting limits, indicating that there was no presence of any of these parameters in the water supply wells.

#### **4.5.1 Impact to Surface Water Quality and Quantity**

There are no surface water bodies at the site or within at least 250 metres or more. The closest water body is an unnamed watercourse that exists some 280 metres east-northeast of the site that is a tributary to the Doyle Creek municipal drain. Since the receiving aquifer at the site flows to the northwest, it is unlikely that the post development site could impact the surface water body that is up gradient of the site.

#### **4.6 Well Construction Methodology**

Future wells drilled on the site should be constructed with a minimum 6 metres length of casing through the overburden and set at least 3 metres into the sound bedrock. The steel casing placed in the auger holes should be pressure grouted or displacement grouted into place. The material used to seal the annular space could consist of either a cement grout or a commercially available bentonite grout product. Cement grout mixtures should be allowed to set for a minimum two day period for normal cement or twelve hours for a high early strength cement prior to advancing the well further into bedrock. If a bentonite grout product is used, drilling need only be suspended for a few hours depending on the product used. Bentonite grout has the additional advantage of remaining flexible when set and therefore will not crack or shrink thereby ensuring as well as possible that surface water or shallow groundwater will not migrate along the annular space and into the well bore.



Once the casing has been sealed, the well should be advanced uncased in the bedrock until a water supply of sufficient quantity and quality is encountered, as per the following Table.

Target Depths (in order of preference)	Bedrock Description	Target Fracture depths (metres)	Target Well Depth (metres)	Well Yields (L/min)	Comments
1	Upper Limestone	20 to 31	30 to 31	60 to 65	If insufficient well yields then proceed to Target Aquifer 2
2	Deeper Limestone with possible secondary sandstone mix	72 to 75	74 to 76	60 to 65	Water quality will yield hydrogen sulphide in the range of 0.3 to 1.2 mg/L, requiring treatment using aeration.

Avoidance Depths	Bedrock Description	Avoidance Fracture depths (metres)	Comments
Between Target Aquifer 1 and 2	Limestone	36 to 41	Proceed to Target Aquifer 2. If water fractures are encountered at these depths, they are likely to encounter hydrogen sulphide levels of 8 mg/L, which requires oxidizing chemicals and/or filtration, possible other pre- treatment, costly and requires significant maintenance.

The completed well should then be developed to maximize the yield. The well casings should be completed at least 400 millimetres above the highest point on the finished ground surface within three metres radially from the well after surface drainage is directed away from the well. The casing should be fitted with a pitless adapter to facilitate below ground plumbing and electrical connections. Surface grading should be completed to direct surface water away from the well in order to ensure that water will not collect or pond in the vicinity of the well.

#### 4.7 Post Development Monitoring Program

The results of this investigation indicate acceptable existing and expected impact on the groundwater quality at this site based on the assessment of existing neighbouring land uses and the proposed development. The existing background nitrate impacts within the receiving aquifer at



the site are generally acceptable for development. The elevated nitrate levels encountered in the up gradient portion of the site are from long time development on undersized properties that have been developed for greater than fifty years. This is considered to be a stable source that is not advancing or increasing on the subject site. There is also no indication of nitrate impacts in the bedrock water supply aquifer in the existing development up gradient of the site, based on the testing of two bedrock wells that are located up gradient of the site. This combined with the soil conditions at the site indicate that a confining unit/aquitard of silty clay and glacial till soils is present at the site. This is reasonable assurance that there is sufficient protection of the water supply at the site from existing and future sewage systems.

The local hydrogeological conditions and existing water quantity and quality all indicate that the impact of the proposed development will not significantly impact the overall groundwater quality and quantity at the site. Septic effluent dilution calculations, which by experience are known to be a conservative estimate of actual impact, indicate that septic system impact at the site is within MECP requirements. There are only seven residential lots proposed for development. Accordingly, a groundwater monitoring program is not considered necessary for this site.

## 5.0 SUMMARY AND CONCLUSIONS

Based on the terrain evaluation and groundwater supply investigation at the proposed residential subdivision and the subsequent analysis of the data collected, the following summary and conclusions are provided:

- 1) Class IV sewage disposal systems with partially raised leaching beds will likely be used at this site depending on the lot specific soil and groundwater conditions. The leaching beds should be constructed to conform to the specifications set out in the Ontario Building Code. Any partially raised leaching beds should be constructed of imported sand having a percolation time of between 6 and 8 minutes per centimetre with less than 5 percent passing the #200 (0.074 mm) sieve. It is recommended that gradation analyses be carried out on any potential sand fill prior to leaching bed construction in order to verify that the percolation time of the fill material is acceptable.



- 2) There is a sufficient groundwater supply of acceptable drinking water quality in the bedrock aquifer system to satisfy the water requirements of the proposed subdivision. It is indicated that most wells will be drilled to depths of about 30 metres to 76 metres and that individual well yields of 62 to 65 litres per minute will be typical. The following Table provides well construction details to be followed for any future wells on the subject property:

Target Depths (in order of preference)	Bedrock Description	Target Fracture depths (metres)	Target Well Depth (metres)	Well Yields (L/min)	Comments
1	Upper Limestone	20 to 31	30 to 31	60 to 65	If insufficient well yields then proceed to Target Aquifer 2
2	Deeper Limestone with possible secondary sandstone mix	72 to 75	74 to 76	60 to 65	Water quality will yield hydrogen sulphide in the range of 0.3 to 1.2 mg/L, requiring treatment using aeration

Avoidance Depths	Bedrock Description	Avoidance Fracture depths (metres)	Comments
Between Target Aquifers 1 and 2	Limestone	36 to 41	If water fractures are encountered at these depths, proceed to drill well deeper to Target Aquifer 2. Wells at this depth may encounter hydrogen sulphide levels of 8 mg/L, treatment requires oxidizing chemicals and/or filtration, possible other pre-treatment, costly and requires significant maintenance

The study findings recommend the following with regards to construction and placement of water supply wells at the site:

- The well water supply at the site is suitable to provide in excess of 3000 litres/day, which is sufficient for a typical single family dwelling. The minimum well yield, as per MOE D-5-5, is 22.7 litres per minute (5 igpm).
- Well Placement: Wells should be located at least twice the grade raise plus 15 metres from the fully raised leaching beds, and at least 15 metres from septic tanks. Clearance distances for treatment units and distribution piping shall conform to OBC Tables 8.2.1.6. A and 8.2.1.6. B. Wells should be located such that surface water will not pool around the



wellhead and the ground surface around the well should be the highest point for at least 3 metres radially outward.

- Well casings should be extended a minimum of 0.4 metres above the final finished ground surface at the well.
- Casing for wells should be minimum 6 metres in length and extend through the overburden and set at least 3.0 metres into the sound bedrock.
- Grouting procedure:
  - the annulus of the casing should be pressure injection grouted from the bottom of the casing up
  - the material used to seal annular space could consist of either a cement grout or a commercially available bentonite grout product and should be allowed to set prior to advancing the well further into bedrock; minimum two day period for normal cement, minimum twelve hours for a high early strength cement, or a few hours for a bentonite grout, depending on the product used
  - the well grouting operation and well casing length should be inspected and approved by an experienced hydrogeologist or geotechnical engineer to ensure that the grouting procedure and casing length are in accordance with the site hydrogeological investigation report and Ont. Reg. 903

3) There is a sufficient groundwater of acceptable drinking water quality in the bedrock aquifer system at this site as it meets all the ODWS concentrations for all health related chemical, physical and bacteriological parameters tested except for the following:

- Hardness:

Future wells at the site are expected to have hardness levels of between about 211 to 310 milligrams per litre. The recommended water treatment consists of ion exchange water softeners and maintaining a separate unsoftened water supply for drinking and culinary purposes.

- Total dissolved solids:

Some future wells at the site may slightly exceed the aesthetic objective of 500 mg/l for TDS at levels of 539 to 618 milligrams per litre. The Ryznar Stability Indices (RSI) and Langelier Saturation Indices (LSI) were calculated for the samples where TDS exceed



with RSI of 7.1 to 7.5, and LSI of 0.25 and 0.50, indicate that the formation of calcium carbonate (i.e. scaling) does not lead to a protective corrosion inhibitor film on metal fixtures and pipes. However, there RSI value is less than 8, indicating that the water is not corrosive either. LSI values are corresponding positive, but close to zero, which indicates that the water has borderline scale potential, such that minor changes in the water quality, temperature could change the scale or corrosive potential of the water. The noted levels of TDS and the individual components that contribute to it include hardness and elevated chlorides (155 to 180 mg/l) albeit within the operational guideline for hardness and the aesthetic objective (AO) for chlorides. Treatment that removes hardness (i.e. water softeners) will reduce the scale potential. The palatability of water with chlorides less than the aesthetic objective of 250 mg/l are considered to be good.

- **Hydrogen Sulphide:**

Future wells constructed to depths of 36 metres and deeper are expected to encounter hydrogen sulphide above the aesthetic objective of 0.05 mg/l, at levels 0.24 to 1.10 mg/l. Hydrogen sulphide produces an odour and can affect the taste of water. When present in water with iron, it can also cause black staining of laundry items, black deposits on pipes and fixtures. Well construction methods are provided to ensure that very high levels of hydrogen sulphide can be avoided. This may require that wells that are deeper than 30.5 metres should be constructed to at least 72 metres to ensure that the water fractures that produce excessive hydrogen sulphide levels (up to 8 mg/l) are avoided. Treatment to reduce sulphide includes aeration. Higher levels of sulphide where iron staining is also an issue (rust staining) may require treatment using chlorination followed by iron filter. Based on the sulphide levels at the site, it is considered that aeration is sufficient to reduce sulphide in the treated water.

- **Organic Nitrogen:**

Organic nitrogen levels may be slightly elevated at 0.17 to 0.20 mg/l, in some future wells, compared to the operational guideline (OG) of 0.15 mg/l. Organic nitrogen is calculated by subtracting the ammonia from the Total Kjeldahl Nitrogen. Organic nitrogen has an OG due to its interaction with chlorine used in water treatment causing taste problems in the treated water. There is a correlation between DOC and organic nitrogen. Organic nitrogen levels above 0.15 mg/l are associated with DOC levels of 0.6



mg/l or greater. As groundwater is typically not treated using chlorine, the potential presence of organic nitrogen in some wells does not require treatment.

- Sodium:

The sodium levels at all three test wells were between 64 and 98 mg/l, above the 20 milligrams per litre advisory level, whereby the local Medical Officer of Health should be notified when the sodium concentration exceeds 20 mg/L so that this information may be communicated to local physicians for their use with patients on sodium restricted diets. The sodium levels were well within the aesthetic objective of 200 mg/l. It is recommended that if water softeners are used to treat hardness and TDS levels, that an untreated drinking water tap is installed in the kitchen to ensure that excessive sodium levels in treated water are not consumed. The City of Ottawa public health should be notified of the sodium exceedance in the raw water supply.

- 4) Mutual water level interference effects between neighbouring wells in the proposed subdivision are expected to be minimal. The impact of future wells at the proposed subdivision on neighbouring existing wells is expected to be minimal.
- 5) Future wells drilled on this property should be constructed with casing through the upper portion of bedrock and set at least 3 metres into the sound bedrock. The annulus of the casing should be grouted using a pressure injection method. Casing and grouting should extend to at least 6 metres below the existing ground surface. Well casings should be extended a minimum of 0.4 metres above the final finished ground surface at the well. Wells should be located at least 18 metres from fully raised septic fields, and up gradient of septic fields.
- 6) It is considered that the type of existing surrounding land use adjacent to the subject property should not impact the subject site from a water supply or water quality point of view.
- 7) Based on the terrain assessment, septic systems impacts from the proposed 7 lots at this site are within acceptable limits established by the MOE.
- 8) The study findings recommend the following with regards to construction of septic systems at the site:



- Partially raised leaching beds will likely be required at this site depending on the lot specific soil and groundwater conditions.
- Leaching beds should be constructed to conform to the specifications set out in the Ontario Building Code.
- Imported sand with a percolation time of between 6 and 8 minutes per centimetre and less than 5 percent passing the #200 (0.074 mm) sieve should be used to construct the raised leaching beds.
- In situ percolation rate tests and/or gradation analyses should be carried out on any potential sand fill or native sand material prior to leaching bed construction in order to verify that the percolation time is acceptable.
- The locations of sewage systems and wells should be placed in accordance with the Lot Development Plan with sewage systems located on the west sides of the lots with wells in the east side of the lots. This will ensure that wells are up gradient of sewage systems on each lot and maximize separation distances between sewage systems and wells on adjacent properties.
- Any change to the placements of the wells and/or sewage systems on any individual lot shall ensure that there is no impairment to the placement of wells and sewage systems on adjacent lots and that the other lots can still follow the Preliminary Grading & Site Servicing Plan.
- The wells must be accessible for servicing in future. This is interpreted as a minimum 3 to 5 metres of space between the front and rear yards where a drill rig could access the rear yard. Based on the side yard setbacks of at least 3 to 5 metres that are provided in the attached Lot Development Plan, it is considered that this is sufficient space to ensure well access.

Test Well Abandonment:

There are currently three test wells that were drilled on the subject site including TW1 (Lot 7), TW2 (Lot 6) and TW3 (Lot 1). These wells can be used as future water supply wells provided that the following is verified and/or carried out:

- wells shall be minimally three metres from the property lines in order to ensure that positive drainage is occurring away from the well head;
- wells shall meet or exceed the minimum separation distances to sewage systems and sewage tanks indicated by the Ontario Building Code; and



- wells should be protected from damage during construction.

Existing on-site monitoring wells, including the boreholes BH1, BH3 and BH5, should be properly decommissioned in accordance with Ontario Well Regulation 903. A record of well abandonment should be produced for each well, prior to any construction at the site.

- 9) The maximum building footprint, based on the Terrain Study, is 600 m<sup>2</sup>, which includes driveways and single family dwellings. Larger building envelopes and/or coach houses and/or ground source heat pumps have not been evaluated as part of the Hydrogeology and Terrain Study. Any proposed use of these systems and/or larger building footprints and coach houses would require a hydrogeological assessment and/or terrain analysis.
- 12) Homeowners should be provided with information regarding well water testing, well maintenance and water and energy conservation. Homeowners should be referred to the MOE publication *Water Supply Wells – Requirements and Best Management Practices* manual, April 2015. Additional information and links on water conservation measures are offered at the [wellaware.ca](http://wellaware.ca) website.

Regards,

Kollaard Associates Inc.



Colleen Vermeersch, P. Eng.

May 2021

210064

TABLE I  
FIELD WATER QUALITY MEASUREMENTS  
FOR TEST WELLS

	Hours Since Pumping Test Started	Temp. (°C)	pH	Conductivity (μs)	TDS (ppm)	Turbidity (NTU)	Free Chlorine (mg/l)
TW 1	1	9.3	7.7	980	497	1.9	0.0
	2	9.3	8.0	990	500	0.6	-
	3	9.5	7.9	988	478	0.8	0.0
	4	9.6	7.7	940	480	0.6	-
	5	9.4	7.8	960	480	0.4	-
	6	9.4	7.7	955	385	0.6	0.0
TW 2	1	9.5	8.3	666	337	1.6	0.0
	2	9.5	7.9	788	395	0.7	-
	3	9.5	7.8	788	400	1.0	0.0
	4	9.5	7.3	840	430	1.0	-
	5	9.5	7.8	775	400	0.6	-
	6	9.5	7.8	850	430	0.6	0.0
TW 3	1	9.4	7.5	832	400	8.1	0.0
	2	9.4	7.3	855	435	4.5	-
	3	9.5	7.8	885	445	1.7	0.0
	4	9.4	7.8	880	447	0.9	-
	5	9.5	7.6	903	463	0.6	-
	6	9.5	7.4	880	445	0.5	0.0

TABLE II

## SUMMARY OF SUBDIVISION WATER CHEMISTRY FOR TEST AND SAMPLED WELLS

Parameter	Guideline	TW1		TW2		TW3		5529 Osgoode Main	5560 Lombardy	5566 Lombardy
		3hr	6hr	3hr	6hr	3hr	6hr			
Alkalinity [mg/l]	OG 500	143	142	139	140	154	157	132	172	178
Chloride [mg/l]	AO/MCCRT 250	178	180	155	165	167	173	163	222	187
Colour [TCU]	AO 5 MCCRT 7	<2	<2	<2	<2	<2	2	2	<2	<2
Conductivity [µS/cm]		951	945	829	879	879	916	862	1160	1050
DOC [mg/l]	AO 5	1.8	2.0	1.8	2.1	1.9	1.9	1.8	1.2	1.5
Fluoride [mg/l]	MAC 1.5	0.83	0.85	0.94	0.89	0.17	0.16	1.19	1.48	0.69
Hydrogen Sulphide [mg/l]	AO 0.05	<b>1.10</b>	<b>1.10</b>	<b>0.27</b>	<b>0.24</b>	<0.01	<0.01	<b>1.22</b>	<b>8.30</b> (raw) <0.01 (treated)	<b>0.30</b>
Ammonia [mg/l]		0.307	0.303	0.290	0.307	0.171	0.168	0.387	0.381	0.320
Nitrite [mg/l]	MAC 1.0	<0.50	<0.50	<0.10	<0.10	<0.10	<0.10	<0.10	<0.50	<0.50
Nitrate [mg/l]	MAC 10.0	<0.50	<0.50	<0.10	<0.10	<0.10	<0.10	<0.10	<0.50	<0.50
pH		8.19	8.20	8.05	8.01	8.01	8.08	8.21	8.35	8.17
Phenols [mg/l]		<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010
Sulphate [mg/l]	AO 500	44	44	47	41	49	50	23	46	60
Tannin & Lignin [mg/l]		0.1	0.1	0.1	0.2	0.7	0.6	<0.10	0.2	0.4
TDS [mg/l]	AO 500	<b>618</b>	<b>614</b>	<b>539</b>	<b>571</b>	<b>571</b>	<b>595</b>	<b>560</b>	<b>754</b>	<b>682</b>
TKN [mg/l]		0.391	0.504	0.272	0.323	0.184	0.337	0.503	0.698	0.505
Organic Nitrogen [mg/l]	AO 0.15	0.08	<b>0.20</b>	0.00	0.02	0.01	<b>0.17</b>	0.12	<b>0.32</b>	<b>0.18</b>
Turbidity [NTU]	AO 5.0	2.2	1.1	<b>5.7</b>	1.2	3.2	1.5	2.4	<b>28.3</b>	1.8
Hardness [mg/l]	OG 100	<b>229</b>	<b>229</b>	<b>211</b>	<b>233</b>	<b>298</b>	<b>310</b>	<b>161</b>	<b>170</b>	<b>234</b>
Ion Balance		1.01	1.01	0.97	1.01	1.00	1.02	0.88	1.03	1.03
Calcium [mg/l]		44	44	40	44	65	68	30	35	46
Magnesium [mg/l]		29	29	27	30	33	34	21	20	29
Potassium [mg/l]		11	11	11	11	4	4	9	9	10
Sodium [mg/l]	AO 200	98	98	78	80	64	67	78	171	126
Iron [mg/l]	A0 0.3	0.16	0.11	<b>0.46</b>	0.14	<b>0.54</b>	0.21	0.20	0.11	0.07
Manganese [mg/l]	AO 0.05	0.01	0.01	0.02	0.01	0.01	0.01	0.01	<0.01	0.01

TABLE III

## SUMMARY OF HEAVY METALS TESTING IN SUBDIVISION TEST WELLS

<b>Parameter</b>	<b>Guideline</b>	<b>TW1</b>		<b>TW2</b>		<b>TW3</b>	
		3hr	6hr	3hr	6hr	3hr	6hr
<b>Aluminum</b> [mg/l]	OG 0.1	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01
<b>Arsenic</b> [mg/l]	IMAC 0.01	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001
<b>Boron</b> [mg/l]	IMAC 5.0	0.53	0.54	0.57	0.58	0.06	0.06
<b>Barium</b> [mg/l]	MAC 1.0	0.08	0.07	0.26	0.20	0.32	0.33
<b>Cadmium</b> [mg/l]	MAC 0.005	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001
<b>Cobalt</b> [mg/l]	*0.0038	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002
<b>Chromium</b> [mg/l]	MAC 0.05	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001
<b>Copper</b> [mg/l]	AO 1.0	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001
<b>Mercury</b> [mg/l]	MAC 0.001	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001
<b>Lead</b> [mg/l]	MAC 0.010	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001
<b>Antimony</b> [mg/l]	IMAC 0.006	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005
<b>Selenium</b> [mg/l]	MAC 0.05	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001
<b>Strontium</b> [mg/l]	** 7.0	3.92	3.87	3.28	3.64	0.662	0.677
<b>Uranium</b> [mg/l]	MAC 0.02	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001
<b>Vanadium</b> [mg/l]	*0.0062	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001
<b>Zinc</b> [mg/l]	AO 5.0	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01

Guideline refers to Ontario Drinking Water Standards, Objectives and Guidelines except where noted

\* O. Reg 153/04 standard Table 2 for potable groundwater

\*\* Health Canada health related maximum

TABLE IV  
SUMMARY OF PUMPING TEST RESULTS AND WELL PARAMETERS

Well	Tp (m <sup>2</sup> /day)	Tr (m <sup>2</sup> /day)	Tav (m <sup>2</sup> /day)	Q (m <sup>3</sup> /day)	SC (m <sup>3</sup> /day/m)	ho m	hf m	Td m	TD m	CS m	AD m
TW1	288	192	240	94.3	68.3	6.86	8.24	1.38	76.20	0.60	36.4
TW2	181	203	192	88.9	85.7	6.68	7.72	1.04	74.37	0.60	36.6
TW3	192	163	177	94.3	409.8	4.53	4.76	0.23	30.48	0.60	20.5

Average Transmissivity: 203 m<sup>2</sup>/day

Well	% Available Drawdown Used
TW1	3.79%
TW2	2.83%
TW3	1.12%

Note:

- Tp: Transmissivity as calculated from pumping data (m<sup>2</sup>/day)
- Tr: Transmissivity as calculated from recovery data (m<sup>2</sup>/day)
- Tav: Average transmissivity (average of pumping and recovery) (m<sup>2</sup>/day)
- Q: Test pumping rate (m<sup>3</sup>/day)
- SC: Specific Capacity (m<sup>3</sup>/day/m)
- ho: Static water level (below top of casing) at beginning of pumping test (metres)
- hf: Water level (below top of casing) at end of 6 hour pumping test (metres)
- Td: Total drawdown (metres)
- TD: Total depth of well (below ground surface) (metres)
- CS: Casing stickup above ground surface (metres)
- AD: Approximate available drawdown (metres)

TABLE V  
MUTUAL WELL INTERFERENCE AT CENTRAL LOT

Storativity	2.4.E-04	based on storativity estimate using drawdown in observation wells (cooper-jacob straight-line)
Transmissivity	203 m <sup>2</sup> /day	average calculated value using cooper-jacob
T	2.E-03 m <sup>2</sup> /s	
Q	1100 L/day	
Q	1.27E-05 m <sup>3</sup> /s	
Duration	30 years	
Duration	946080000 s	
2.3Q/(4piT)	0.0010	

Lot	Distance [m]	30 Year Drawdown [m]
1	47.8	0.007
3	49.5	0.007
4	138	0.006
5	110	0.006
6	108	0.006
7	126	0.006
Cumulative aquifer drawdown at centre well [metres]		0.038

August 2021

210064

TABLE VI  
WELL INTERFERENCE AT PROPERTY BOUNDARY

Storativity	2.4.E-04	based on storativity estimate using drawdown in observation wells (cooper-jacob straight-line)
Transmissivity	203 m <sup>2</sup> /day	average calculated value using cooper-jacob
T	2.E-03 m <sup>2</sup> /s	
Q	1100 L/day	
Q	1.27E-05 m <sup>3</sup> /s	
Duration	30 years	
Duration	946080000 s	
2.3Q/(4piT)	0.0010	

Lot	Distance [m]	30 Year Drawdown [m]
1	29.2	0.007
2	55.7	0.007
3	100	0.006
4	192	0.006
5	158	0.006
6	145	0.006
7	145	0.006
Cumulative aquifer drawdown at north property corner [m]		0.044

August 2021

210064

TABLE VII

DRAWDOWN IN OBSERVATION WELLS  
DURING PUMPING TESTS

DATE 5-May-21  
 PUMPED WELL: TW3  
 OBSERVATION WELL: TW1  
 DISTANCE BETWEEN PUMPED  
 WELL AND OBSERVATION WELL,  $r$ : 117.2 metres  
 PUMPING RATE, Q: 94.3 m<sup>3</sup>/day

Time Lapsed (minutes)	Depth (metres)	$h-h_o$ (metres)
0	-6.73	
15	-6.73	0.00
30	-6.73	0.00
45	-6.74	0.01
60	-6.75	0.02
75	-6.76	0.03
90	-6.74	0.01
105	-6.73	0.00
120	-6.72	0.00
135	-6.72	-0.01
150	-6.72	-0.01
165	-6.74	0.01
180	-6.74	0.02
195	-6.74	0.02
210	-6.74	0.01
225	-6.74	0.01
240	-6.74	0.01
255	-6.74	0.01
270	-6.74	0.01
285	-6.73	0.01
300	-6.73	0.00
315	-6.74	0.01
330	-6.74	0.01
345	-6.73	0.00
360	-6.74	0.02
375	-6.76	0.03
390	-6.73	0.00
405	-6.73	0.00
420	-6.73	0.01

TABLE VII (continued)

DATE 5-May-21

PUMPED WELL: TW3

OBSERVATION WELL: TW2

DISTANCE BETWEEN PUMPED

WELL AND OBSERVATION WELL, r: 117.6 metres

PUMPING RATE, Q: 94.3 m<sup>3</sup>/day

Time Lapsed (minutes)	Depth (metres)	h-ho (metres)
0	-6.63	0
15	-6.63	0.00
30	-6.63	0.00
45	-6.63	0.00
60	-6.64	0.01
75	-6.65	0.03
90	-6.66	0.03
105	-6.64	0.01
120	-6.63	0.00
135	-6.63	0.00
150	-6.62	-0.01
165	-6.62	-0.01
180	-6.64	0.01
195	-6.65	0.02
210	-6.65	0.02
225	-6.64	0.01
240	-6.64	0.01
255	-6.64	0.02
270	-6.64	0.01
285	-6.64	0.01
300	-6.64	0.01
315	-6.63	0.00
330	-6.64	0.01
345	-6.64	0.01
360	-6.63	0.00
375	-6.65	0.02
390	-6.67	0.04
405	-6.63	0.00
420	-6.63	0.01

TABLE VII (continued)

DATE	10-May-21	
PUMPED WELL:	TW2	
OBSERVATION WELL:	TW1	
DISTANCE BETWEEN PUMPED WELL AND OBSERVATION WELL, r:	45 metres	
PUMPING RATE, Q:	88.9 m <sup>3</sup> /day	
Time Lapsed (minutes)	Depth (metres)	h-ho (metres)
0	-7.07	0
15	-7.39	0.32
30	-7.41	0.34
45	-7.43	0.36
60	-7.44	0.37
75	-7.44	0.37
90	-7.44	0.37
105	-7.45	0.38
120	-7.45	0.38
135	-7.46	0.39
150	-7.46	0.39
165	-7.46	0.39
180	-7.47	0.40
195	-7.47	0.40
210	-7.48	0.40
225	-7.49	0.42
240	-7.49	0.42
255	-7.49	0.42
270	-7.49	0.42
285	-7.49	0.42
300	-7.49	0.42
315	-7.50	0.43
330	-7.50	0.43
345	-7.50	0.43
360	-7.50	0.43
375	-7.19	0.12
390	-7.17	0.10
405	-7.17	0.10
420	-7.17	0.10
435	-7.15	0.08
450	-7.14	0.07
465	-7.14	0.07
480	-7.13	0.06
495	-7.15	0.08
510	-7.14	0.07
525	-7.14	0.07
540	-7.14	0.07
555	-7.13	0.06
570	-7.13	0.06
585	-7.13	0.06
600	-7.13	0.05
615	-7.13	0.06
630	-7.12	0.05
645	-7.12	0.04
660	-7.14	0.07
675	-7.11	0.04
690	-7.10	0.03
705	-7.09	0.02
720	-7.09	0.02
735	-7.08	0.01
750	-7.08	0.01

TABLE VII (continued)

DATE 10-May-21

PUMPED WELL: TW2

OBSERVATION WELL: TW3

DISTANCE BETWEEN PUMPED

WELL AND OBSERVATION WELL, r: 117.6 metres

PUMPING RATE, Q: 88.9 m<sup>3</sup>/day

Time Lapsed (minutes)	Depth (metres)	h-ho (metres)
0	-4.61	0
15	-4.61	0.00
30	-4.65	0.03
45	-4.61	0.00
60	-4.60	-0.02
75	-4.61	0.00
90	-4.61	0.00
105	-4.61	-0.01
120	-4.60	-0.01
135	-4.61	-0.01
150	-4.62	0.01
165	-4.62	0.01
180	-4.60	-0.01
195	-4.63	0.02
210	-4.64	0.03
225	-4.63	0.02
240	-4.65	0.04
255	-4.64	0.03
270	-4.62	0.01
285	-4.61	0.00
300	-4.61	0.00
315	-4.61	0.00
330	-4.61	0.00
345	-4.60	-0.02
360	-4.60	-0.02
375	-4.59	-0.02
390	-4.60	-0.02
405	-4.60	-0.02
420	-4.61	0.00
435	-4.62	0.01
450	-4.61	0.00
465	-4.61	0.00
480	-4.62	0.00
495	-4.61	0.00

TABLE VII (continued)

DATE 12-May-21  
 PUMPED WELL: TW1  
 OBSERVATION WELL: TW2  
 DISTANCE BETWEEN PUMPED  
 WELL AND OBSERVATION WELL,  $r$ : 44.6 metres  
 PUMPING RATE,  $Q$ : 94.3 m<sup>3</sup>/day

Time Lapsed (minutes)	Depth (metres)	$h-h_o$ (metres)
0	-6.73	0
15	-7.02	0.29
30	-7.03	0.30
45	-7.04	0.31
60	-7.04	0.31
75	-7.06	0.33
90	-7.06	0.33
105	-7.06	0.33
120	-7.07	0.34
135	-7.07	0.34
150	-7.07	0.34
165	-7.08	0.35
180	-7.09	0.36
195	-7.10	0.37
210	-7.09	0.36
225	-7.09	0.36
240	-7.09	0.36
255	-7.09	0.36
270	-7.11	0.38
285	-7.11	0.38
300	-7.11	0.38
315	-7.11	0.38
330	-7.12	0.39
345	-7.12	0.39
360	-7.12	0.39
375	-6.80	0.07
390	-6.80	0.06
405	-6.78	0.05
420	-6.78	0.05
435	-6.77	0.04
450	-6.77	0.04
465	-6.76	0.03
480	-6.77	0.04
495	-6.75	0.02
510	-6.77	0.04
525	-6.75	0.02
540	-6.74	0.01
555	-6.73	0.00

TABLE VII (continued)

DATE 12-May-21  
 PUMPED WELL: TW1  
 OBSERVATION WELL: TW3  
 DISTANCE BETWEEN PUMPED  
 WELL AND OBSERVATION WELL,  $r$ : 117.2 metres  
 PUMPING RATE,  $Q$ : 94.3 m<sup>3</sup>/day

Time Lapsed (minutes)	Depth (metres)	$h-h_o$ (metres)
0	-4.65	0
15	-4.66	0.00
30	-4.64	-0.02
45	-4.64	-0.01
60	-4.63	-0.02
75	-4.63	-0.02
90	-4.62	-0.03
105	-4.61	-0.04
120	-4.62	-0.03
135	-4.60	-0.05
150	-4.61	-0.05
165	-4.60	-0.05
180	-4.62	-0.04
195	-4.62	-0.04
210	-4.61	-0.04
225	-4.60	-0.05
240	-4.61	-0.04
255	-4.62	-0.04
270	-4.62	-0.03
285	-4.61	-0.04
300	-4.62	-0.04
315	-4.62	-0.04
330	-4.61	-0.04
345	-4.63	-0.03
360	-4.61	-0.04
375	-4.61	-0.04
390	-4.60	-0.06
405	-4.61	-0.04
420	-4.61	-0.04
435	-4.62	-0.04
450	-4.63	-0.03
465	-4.61	-0.04
480	-4.64	-0.01
495	-4.63	-0.02
510	-4.66	0.01
525	-4.65	0.00

August 2021

210064

TABLE VIII  
ESTIMATE OF STORATIVITY BY COOPER-JACOB METHOD

A curve of drawdown versus time was generated for observation wells as an adjacent well was pumped  
(see Table 7 and Attachment K)

Based on the Cooper-Jacob formula, the following values of storativity were calculated.


Pump well	Observation Well	r (m)	Q (m <sup>3</sup> /day)	t <sub>o</sub> (min)	T (m <sup>2</sup> /day)	S
TW2	TW1	44.6	88.9	1.4	180.7	2.0E-04
TW1	TW2	44.6	94.3	1.2	288	2.7E-04
						2.4E-04

TABLE IX - BACKGROUND NITROGEN IN SURFICIAL AQUIFER

<b>LOCATION</b>	<b>Units</b>	<b>MW1</b>	<b>MW3</b>	<b>MW5</b>	<b>MW1</b>	<b>MW3</b>	<b>MW5</b>	<b>MW1</b>	<b>MW1</b>
<b>DATE</b>		12-Feb-21			3-Mar-22	11-Mar-22	3-Mar-22	17-Jun-22	9-Feb-23
N-NH3	mg/L	<0.010	<0.010	0.031	<0.010	0.028	<0.010	0.02	<0.020
TKN	mg/L	0.393	0.331	0.245	0.737	0.397	0.309	0.292	0.572
N-NO2	mg/L	0.17	<0.10	<0.10	0.16	<0.10	<0.10	<0.10	0.14
N-NO3	mg/L	5.8	<0.10	<0.10	19.7	<0.10	0.72	8.11	19.3

# KEY PLAN

FIGURE 1




NOT TO SCALE



Kollaard Associates  
Engineers

Project No. 210064  
Date August 2021



## FIGURE 2

TW1

### Approximate Water Well Location

 Approximate Bore  
Well) Location  
**DW1** (MW1)

 Approximate Borehole (Monitoring Well) Location

BH1 (MW1)

Approximate Receiving Aquifer Flow Direction



## Approximate Water Supply Aquifer Flow Direction

**NOTE:** This drawing to be read in conjunction with accompanying report.




Kollaard Associates  
Engineers

PO. BOX 189, 210 PRESCOTT ST (613) 860-0923  
KEMPTVILLE ONTARIO info@kollaard.ca  
KOG 1J0 FAX (613) 258-0475  
<http://www.kollaard.ca>

**CLIENT:** KILO-XIANG

**PROJECT:** *PROPOSED RESIDENTIAL*

**LOCATION:** 3200 REIDS LANE  
GALT, ONTARIO

**DRAWING:** SITE PLAN


*DESIGNED BY:* **DATE:**  
**AUGUST 2021**

DRAWN BY: CV SCALE: 1:1000

KOLLAARD FILE NUMBER:  
210064

FIGURE 3



**FIGURE 4**

	TOPSOIL
	Yellow brown sand and gravel (FILL)
	Red brown fine to medium SAND, trace silt
	Grey fine to medium SAND
	Grey sandy CLAY, trace silt
	Grey SILTY SAND
	Grey SILTY CLAY
	Grey silty sand, trace to some gravel, cobbles and boulders, trace clay (GLACIAL TILL)
	LIMESTONE BEDROCK

**Kollaard Associates**  
Engineers

210 Prescott Street, Unit 1 613-860-0923  
P.O. Box 189 info@kollaard.ca  
Kemptville, Ontario  
K0G 1J0 Fax: 613-258-0475

**CLIENT:**  
Miles Yang

**PROJECT:**  
Proposed Residential Subdivision


**LOCATION:**  
3200 Reids Lane.  
Osgoode, Ottawa, Ontario

**DRAWING:**  
East-West Cross Section

<b>DESIGNED BY:</b> CV	<b>DATE:</b> July 2021
---------------------------	---------------------------

<b>DRAWN BY:</b> CI	<b>SCALE:</b> 1:100
------------------------	------------------------

**PROJECT NUMBER:**  
210064

**FIGURE 5**

	<b>TOPSOIL</b>
	Yellow brown sand and gravel (FILL)
	Red brown fine to medium SAND, trace silt
	Grey fine to medium SAND
	Grey sandy CLAY, trace silt
	Grey SILTY SAND
	Grey SILTY CLAY
	Grey silty sand, trace to some gravel, cobbles and boulders, trace clay (GLACIAL TILL)
	LIMESTONE BEDROCK

**Kollaard Associates**  
Engineers

210 Prescott Street, Unit 1 613-860-0923  
P.O. Box 189 info@kollaard.ca  
Kemptville, Ontario  
K0G 1J0 Fax: 613-258-0475

**CLIENT:**  
Miles Yang

**PROJECT:**  
Proposed Residential Subdivision

**LOCATION:**  
3200 Reids Lane.  
Osgoode, Ottawa, Ontario



**DRAWING:**  
North-South Cross Section

**DESIGNED BY:** CV      **DATE:** July 2021

**DRAWN BY:** CI      **SCALE:** 1:100

**PROJECT NUMBER:**  
210064

FIGURE 6



NOTE: This drawing to be read in conjunction with accompanying report.

1	CV	02/23	setback distances
REV.	NAME	DATE	DESCRIPTION



**Kollaard Associates**  
Engineers

PO. BOX 189, 210 PRESCOTT ST (613) 860-0923  
KEMPTVILLE ONTARIO info@kollaard.ca  
KOG 1J0 FAX (613) 258-0475  
<http://www.kollaard.ca>

CLIENT: MILES YANG

PROJECT: PROPOSED RESIDENTIAL SUBDIVISION

LOCATION: 3200 REIDS LANE  
OSGOODE, ONTARIO

DRAWING: LOT DEVELOPMENT PLAN

DESIGNED BY: DATE:  
— AUGUST 2021

DRAWN BY: SCALE:  
CV 1:1000

KOLLAARD FILE NUMBER:  
210064



Crestview Innovations Inc.  
May 10, 2023


## Hydrogeological Investigation and Terrain Evaluation

3200 Reids Lane, Ottawa, Ontario  
210064

### ATTACHMENT A

#### SURFICIAL AND BEDROCK GEOLOGY MAPS

# SURFICIAL GEOLOGY MAP



## PLEISTOCENE

12

**Older alluvial deposits:** clay, silt, sand, gravel, may contain organic remains

11

**Coarse-textured glaciomarine deposits:** sand, gravel, minor silt and clay  
11a Deltaic deposits  
11b Littoral deposits  
11c Foreshore and basinal deposits

Ontario Geological Survey of Ontario, issued 2003


Project No. 210064

Date August 2021



Kollaard Associates  
Engineers

# BEDROCK GEOLOGY MAP



1:250,000 scale Bedrock Geology Map MRD 126, issued 2003

## LOWER ORDOVICIAN

53 Dolostone, sandstone: Beekmantown Gp.



Crestview Innovations Inc.  
May 10, 2023

**Hydrogeological Investigation and Terrain Evaluation**

3200 Reids Lane, Ottawa, Ontario  
210064

**ATTACHMENT B**

**CERTIFICATE OF WELL COMPLIANCES AND MOE WATER WELL RECORDS FOR TEST  
WELLS AND AREA WELL RECORDS**

Measurements recorded in:  Metric  Imperial

Page \_\_\_\_\_ of \_\_\_\_\_

## Well Owner's Information

First Name	Last Name/Organization	E-mail Address	<input type="checkbox"/> Well Constructed by Well Owner
Crestview Innovation Inc.			
Mailing Address (Street Number/Name)	Municipality	Province	Postal Code
12 Escade Drive	Ottawa	ON	K2G 6R9

## Well Location

Address of Well Location (Street Number/Name)	Township	Lot	Concession
3200 Reids Lane	Osgoode	P/L 27-28 1	
County/District/Municipality	City/Town/Village	Province	Postal Code
Ottawa Carleton	Osgoode	Ontario	
UTM Coordinates Zone Easting	Municipal Plan and Sublot Number	Other	
NAD 83 18 452113	4R-20040 (Parts 4-5)	TW# 1	

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (m) From	To
	Sand	or Cobble		0'	25'
	Clay			25'	38'
	Gravel		( Packed )	38'	56'
Grey	Limestone			56'	160'
Grey	Limestone	w/ Grey Sandstone Mix		160'	244'
Grey	Limestone	w/ Gray Sandstone Mix		244'	250'

\* Test Well # 1 of 3 \*

## Annular Space

Depth Set at (m) From	To	Type of Sealant Used (Material and Type)	Volume Placed (m³)
66'	56'	Neat cement	9.36
56'	0'	Bentonite slurry	21

## Method of Construction

## Well Use

<input type="checkbox"/> Cable Tool	<input type="checkbox"/> Diamond	<input type="checkbox"/> Public	<input type="checkbox"/> Commercial	<input type="checkbox"/> Not used
<input type="checkbox"/> Rotary (Conventional)	<input type="checkbox"/> Jetting	<input checked="" type="checkbox"/> Domestic	<input type="checkbox"/> Municipal	<input type="checkbox"/> Dewatering
<input checked="" type="checkbox"/> Rotary (Reverse)	<input type="checkbox"/> Driving	<input type="checkbox"/> Livestock	<input type="checkbox"/> Test Hole	<input type="checkbox"/> Monitoring
<input type="checkbox"/> Boring	<input type="checkbox"/> Digging	<input type="checkbox"/> Irrigation	<input type="checkbox"/> Industrial	<input type="checkbox"/> Cooling & Air Conditioning
<input checked="" type="checkbox"/> Air percussion			<input type="checkbox"/> Other, specify	

## Construction Record - Casing

## Status of Well

Inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fiberglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	Depth (m) From	To	
6 1/4"	Steel	.188	+2'	66'	
6"	Open Hole		66'	250'	

X Water Supply

 Replacement Well Test Hole Recharge Well Dewatering Well Observation and/or Monitoring Hole Alteration (Construction) Abandoned, Insufficient Supply Abandoned, Poor Water Quality Abandoned, other, specify Other, specify

Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (m/ft)	From	To

## Results of Well Yield Testing

After test of well yield, water was:	Draw Down		Recovery
Time (min)	Water Level (m/ft)	Time (min)	Water Level (m/ft)
Static Level	22.9"		30.2"
1	21.9	1	25.0
2	28.9	2	23.3
3	29.2	3	22.9
4	29.4	4	22.9"
5	29.5	5	
10	29.8	10	
15	29.9	15	
20	30.0	20	
25	30.0	25	
30	30.1	30	
40	30.1	40	
50	30.2	50	
60	30.2"	60	

X Disinfected?

 Yes  No

## Map of Well Location

Please provide a map below following instructions on the back.



## Water Details

## Hole Diameter

Water found at Depth (m/ft)	Kind of Water: <input type="checkbox"/> Fresh <input type="checkbox"/> Untested <input type="checkbox"/> Gas	Depth (m) From	Diameter (cm/in)
244 (m)	<input type="checkbox"/> Other, specify		
(m/ft)			
Water found at Depth (m/ft)	Kind of Water: <input type="checkbox"/> Fresh <input type="checkbox"/> Untested <input type="checkbox"/> Gas	0' 66"	93/4"

X Gas

 Other, specify

66' 250' 6"

Water found at Depth (m/ft)	Kind of Water: <input type="checkbox"/> Fresh <input type="checkbox"/> Untested <input type="checkbox"/> Gas	Depth (m) From	Diameter (cm/in)

Gas

 Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

 Gas Other, specify

66' 250' 6"

# CERTIFICATE OF WELL COMPLIANCE



I ( Jeremy Hanna ) AIR ROCK DRILLING CO. LTD. - DO HEREBY CERTIFY

that I am licensed to drill water wells in the Province of Ontario, and that I have

supervised the drilling of the water well on the property of :

OWNER: CRESTVIEW INNOVATION INC.

Location: # 3200 REIDS LANE, Osgoode

Part 27 LOT: 428 CON: 1 PLAN # 4R-20040 S# Part 415

Ottawa-Carleton / Geographical Township of Osgoode

I CERTIFY FURTHER that, I am aware of the well drilling requirements, the guidelines, recommendations and regulations of the Ministry of the Environment governing well installations in the Province of Ontario, and the standards specified in any subdivision agreement and hydrogeological report applicable to this site and City Standards.

AND DO HEREBY CERTIFY THAT the said well has been drilled, cased, grouted (cement or bentonite) as applicable and constructed in strict conformity with the standards required.

Signed this 26<sup>th</sup> Day of APRIL, 2021




Jeremy Hanna (T3632)

Air Rock Drilling Co. Ltd. (C-7681)

The Engineer on behalf of the Landowner set out above, Certifies that he/she has inspected the well and it was constructed in accordance with the specifications in O.Reg 903, this report and the Hydrogeological Report with regards to casing length and grouting requirements.

Signed this 11<sup>th</sup> day of May, 2021

TAG A 318366  
TW# 1 of 3  
2021241

  
(Engineer)

Shaping our future together  
Ensemble, formons notre avenir

City of  
Gatineau  
8243 Vire



Kollaard Associates

Engineers

P.O. Box 189

210 Prescott Street, Unit 1

Kemptville, Ontario K0G 1J0



Measurements recorded in:  Metric  Imperial

## Well Owner's Information

First Name	Last Name/Organization <b>Crestview Innovation Inc.</b>	E-mail Address	<input type="checkbox"/> Well Constructed by Well Owner
Mailing Address (Street Number/Name) <b>12 Escade Drive</b>	Municipality <b>Ottawa</b>	Province <b>ON</b>	Postal Code <b>K2G 6R9</b>
		Telephone No. (inc. area code)	

## Well Location

Address of Well Location (Street Number/Name) <b>3200 Reids Lane</b>	Township <b>Osgoode</b>	Lot <b>P/L 27428 1</b>	Concession
County/District/Municipality <b>Ottawa Carleton</b>	City/Town/Village <b>Osgoode</b>	Province <b>Ontario</b>	Postal Code
UTM Coordinates NAD 83 <b>18 452078</b>	Zone <b>18</b>	Easting <b>452078</b>	Northing <b>4999307</b>
			Municipal Plan and Sublot Number <b>4R-20D40 (Parts 4+5)</b>
			Other <b>TW#2</b>

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (m/ft)
	Sand	9	Boulders & Clay, Gravel	0' 52'
Grey	Black	Limestone		52' 180'
Grey	Black	Limestone	w/ Gray White Sandstone Mix	180' 238'
Grey	Black	Limestone	w/ Gray White Sandstone Mix	238' 244'

\*Test well 2 of 3 \*

Annular Space		
Depth Set at (m/ft) From <b>52'</b>	Type of Sealant Used (Material and Type) <b>Neat cement</b>	Volume Placed (m <sup>3</sup> /ft) <b>10.9</b>
To <b>52'</b>		

Method of Construction		Well Use			
<input type="checkbox"/> Cable Tool	<input type="checkbox"/> Diamond	<input type="checkbox"/> Public	<input type="checkbox"/> Commercial	<input type="checkbox"/> Not used	
<input type="checkbox"/> Rotary (Conventional)	<input type="checkbox"/> Jetting	<input checked="" type="checkbox"/> Domestic	<input type="checkbox"/> Municipal	<input type="checkbox"/> Dewatering	
<input type="checkbox"/> Rotary (Reverse)	<input type="checkbox"/> Driving	<input type="checkbox"/> Livestock	<input type="checkbox"/> Test Hole	<input type="checkbox"/> Monitoring	
<input checked="" type="checkbox"/> Boring	<input type="checkbox"/> Digging	<input type="checkbox"/> Irrigation	<input type="checkbox"/> Cooling & Air Conditioning		
<input type="checkbox"/> Air percussion		<input type="checkbox"/> Industrial			
<input type="checkbox"/> Other, specify		<input type="checkbox"/> Other, specify			

Construction Record - Casing			Status of Well		
Inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	Depth (m/ft)	From	To
<b>6 1/4"</b>	<b>Steel</b>	<b>.188"</b>	<b>+2'</b>	<b>62'</b>	
<b>6"</b>	<b>Open Hole</b>			<b>62'</b>	<b>244'</b>

Construction Record - Screen		
Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.

Water Details		Hole Diameter
Water found at Depth <b>238' (m/ft)</b>	Kind of Water: <input type="checkbox"/> Fresh <input type="checkbox"/> Untested <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify	Depth (m/ft) From <b>0'</b>
Water found at Depth <b>(m/ft)</b>	Kind of Water: <input type="checkbox"/> Fresh <input type="checkbox"/> Untested <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify	To <b>62'</b>
Water found at Depth <b>(m/ft)</b>	Kind of Water: <input type="checkbox"/> Fresh <input type="checkbox"/> Untested <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify	Depth (m/ft) From <b>62'</b>
		To <b>244'</b>
		Depth (m/ft) From <b>62'</b>
		To <b>6"</b>

Well Contractor and Well Technician Information		
Business Name of Well Contractor <b>Air Rock Drilling Co. Ltd.</b>	Well Contractor's Licence No. <b>7691</b>	
Business Name of Well Technician (Last Name, First Name) <b>Hanna, Jeremy</b>	Municipality <b>Richmond</b>	

Province <b>ON</b>	Postal Code <b>K0A 2Z0</b>	Business E-mail Address <b>air-rock@sympatico.ca</b>
Business Telephone No. (inc. area code) <b>6138382170</b>	Name of Well Technician (Last Name, First Name) <b>Hanna, Jeremy</b>	

Well Operator's Licence No.	Signature of Technician and/or Contractor	Date Issued <b>05 31</b>	Y Y Y M M D D
<b>T5632</b>	<i>[Signature]</i>		<i>[Signature]</i>

Results of Well Yield Testing					
After test of well yield, water was:	Draw Down	Recovery			
<input type="checkbox"/> Clear and sand free	Time (min)	Water Level (m/ft)			
<input type="checkbox"/> Other, specify <b>Not tested</b>					
If pumping discontinued, give reason:					
Static Level <b>22.5'</b>					27.8'
Pump intake set at <b>220'</b>					
Pumping rate (l/min/GPM) <b>20</b>					
Duration of pumping <b>1 hrs + 0 min</b>					
Final water level end of pumping (m/ft) <b>27.8'</b>					
If flowing give rate (l/min/GPM)					
X					
Recommended pump depth (m/ft) <b>140'</b>					
27.8'					
Recommended pump rate (l/min/GPM) <b>20</b>					
Well production (l/min/GPM) <b>20</b>					
Desired? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>					

Map of Well Location		
Please provide a map below following instructions on the back.		
Comments:	<i>1/2 hr 10 GPM set @ 140 ft</i>	
Well owner's information package delivered <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	Date Package Delivered <b>2021 04 29</b>	Ministry Use Only Audit No. <b>Z355078</b>
	Date Work Completed <b>2021 04 27</b>	Received

# CERTIFICATE OF WELL COMPLIANCE



I ( Jeremy Hanna ) AIR ROCK DRILLING CO. LTD. - DO HEREBY CERTIFY

that I am licensed to drill water wells in the Province of Ontario, and that I have

supervised the drilling of the water well on the property of :

OWNER: CRESTVIEW INNOVATION Inc.

Location: # 3200 REIDS LANE, Osgoode

Part 27 LOT: 28 CON: 1 PLAN # 4R-20040 S# Part 415

Ottawa-Carleton / Geographical Township of Osgoode

I CERTIFY FURTHER that, I am aware of the well drilling requirements, the guidelines, recommendations and regulations of the Ministry of the Environment governing well installations in the Province of Ontario, and the standards specified in any subdivision agreement and hydrogeological report applicable to this site and City Standards.

AND DO HEREBY CERTIFY THAT the said well has been drilled, cased, grouted (cement or bentonite) as applicable and constructed in strict conformity with the standards required.

Signed this 27<sup>TH</sup> Day of APRIL, 2021



Jeremy Hanna (T3632)

Air Rock Drilling Co. Ltd. (C-7681)

The Engineer on behalf of the Landowner set out above, Certifies that he/she has inspected the well and it was constructed in accordance with the specifications in O.Reg 903, this report and the Hydrogeological Report with regards to casing length and grouting requirements.

Signed this 11<sup>th</sup> day of May, 2021,

TAG A318392  
TW#2 of 3  
2021242

  
(Engineer)

Shaping our future together  
Ensemble, formons notre avenir

City of Ottawa  
Client Service Centre  
8745 Victoria Street



Kollaard Associates  
Engineers  
P.O. Box 189  
210 Prescott Street, Unit 1  
Kemptville, Ontario K0G 1J0



# CERTIFICATE OF WELL COMPLIANCE



I (Jeremy Hanna) AIR ROCK DRILLING CO. LTD. - DO HEREBY CERTIFY

that I am licensed to drill water wells in the Province of Ontario, and that I have supervised the drilling of the water well on the property of :

OWNER: CRESTVIEW INNOVATION INC.

Location: # 3200 REIDS LANE, Osgoode  
Part 27  
LOT: 28 CON: 1 PLAN # 4R-20040 SITE# Part 4NS

Ottawa-Carleton / Geographical Township of Osgoode

I CERTIFY FURTHER that, I am aware of the well drilling requirements, the guidelines, recommendations and regulations of the Ministry of the Environment governing well installations in the Province of Ontario, and the standards specified in any subdivision agreement and hydrogeological report applicable to this site and City Standards.

AND DO HEREBY CERTIFY THAT the said well has been drilled, cased, grouted (cement or bentonite) as applicable and constructed in strict conformity with the standards required.

Signed this 26<sup>th</sup> Day of April, 2021



Jeremy Hanna (T3632)

Air Rock Drilling Co. Ltd. (C-7681)

The Engineer on behalf of the Landowner set out above, Certifies that he/she has inspected the well and it was constructed in accordance with the specifications in O.Reg 903, this report and the Hydrogeological Report with regards to casing length and grouting requirements.

Signed this 11<sup>th</sup> day of May, 2021, TAG A318365  
TW#3 of 3  
2021240.

Plummer  
(Engineer)

Shaping our future together  
Ensemble, formons notre avenir

City of Ottawa  
Client Services  
8743 Victoria



Kollaard Associates

Engineers  
P.O. Box 189  
210 Prescott Street, Unit 1  
Kemptville, Ontario K0G 1J0



Measurements recorded in:  Metric  Imperial

A318365

Page \_\_\_\_\_ of \_\_\_\_\_

## Well Owner's Information

First Name	Last Name/Organization	E-mail Address	<input type="checkbox"/> Well Constructed by Well Owner
Crestview Innovation Inc.			
Mailing Address (Street Number/Name)	Municipality	Province	Postal Code
12 Escade Drive	Ottawa	ON	K2G 6R9

## Well Location

Address of Well Location (Street Number/Name)	Township	Lot	Concession
3200 Reids Lane	Osgoode	P/L 27	1
County/District/Municipality	City/Town/Village	Province	Postal Code
Ottawa Carleton	Osgoode	Ontario	
UTM Coordinates Zone Easting	Northing	Municipal Plan and Sublot Number	Other
NAD 8/3 18 452036	4990431	4R-20040	(Lots 4+5) TW3

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (m) From	Depth (m) To
	Sand	+ Stones		0'	11'
	Clay			11'	37'
	Boulders	+ Gravel		37'	52'
Grey	Limestone			52'	70'
Grey	Limestone			70'	83'
Grey	Limestone			83'	100'

*\*Test well #3 of 3\**

Annular Space			
Depth Set at (mft) From	To	Type of Sealant Used (Material and Type)	Volume Placed (m <sup>3</sup> /ft)
62'	52'	Neat cement	9.36
52'	0'	Bentonite slurry	25.2

Method of Construction		Well Use		
<input type="checkbox"/> Cable Tool	<input type="checkbox"/> Diamond	<input checked="" type="checkbox"/> Public	<input type="checkbox"/> Commercial	<input type="checkbox"/> Not used
<input type="checkbox"/> Rotary (Conventional)	<input type="checkbox"/> Jetting	<input type="checkbox"/> Domestic	<input type="checkbox"/> Municipal	<input type="checkbox"/> Dewatering
<input type="checkbox"/> Rotary (Reverse)	<input type="checkbox"/> Driving	<input type="checkbox"/> Livestock	<input type="checkbox"/> Test Hole	<input type="checkbox"/> Monitoring
<input type="checkbox"/> Boring	<input type="checkbox"/> Digging	<input type="checkbox"/> Irrigation	<input type="checkbox"/> Cooling & Air Conditioning	
<input checked="" type="checkbox"/> Air percussion		<input type="checkbox"/> Industrial		
<input type="checkbox"/> Other, specify		<input type="checkbox"/> Other, specify		

Construction Record - Casing			Status of Well
Inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fiberglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	Depth (mft) From To
6 1/4"	Steel	.188"	+2' 62'
6"	Open Hole		62' 100'

Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (mft) From To

Water Details		Hole Diameter	
Water found at Depth (mft)	Kind of Water: <input type="checkbox"/> Fresh <input type="checkbox"/> Untested	Depth (mft) From To	Diameter (cm/in)
70' (mft) <input type="checkbox"/> Gas	<input type="checkbox"/> Other, specify		
93' (mft) <input type="checkbox"/> Gas	<input type="checkbox"/> Other, specify	0' 62'	9 3/4"
Water found at Depth (mft) <input type="checkbox"/> Gas	Kind of Water: <input type="checkbox"/> Fresh <input type="checkbox"/> Untested	62' 100'	6"
	<input type="checkbox"/> Other, specify		

Well Contractor and Well Technician Information		
Business Name of Well Contractor	Well Contractor's Licence No.	
Air Rock Drilling Co. Ltd.	7681	

Business Address (Street Number/Name)	Municipality
8859 Franktown Road	Richmond

Province	Postal Code	Business E-mail Address
ON	K0A 2Z0	air-rock@sympatico.ca

Bus. Telephone No. (inc. area code)	Name of Well Technician (Last Name, First Name)
613-382-2170	Hanna, Jeremy

Well Technician's Licence No.	Signature of Technician and/or Contractor	Date Submitted
T3632	<i>[Signature]</i>	2021 05 31

0506E (2020/06) © Queen's Printer for Ontario, 2020

Results of Well Yield Testing	
Draw Down (min)	Recovery (min)
Time (min)	Water Level (mft)
Static Level 15.3"	16.2"
1 15.5	15.3
2 15.5	15.3"
3 15.6	3
4 15.6	4
5 15.6	5
10 15.7	10
15 15.8	15
20 15.9	20
25 15.9	25
30 16.0	30
40 16.1	40
50 16.2	50
60 16.2"	60

Recommended pump depth (mft)  
80'Recommended pump rate (l/min/GPM)  
20Well production (l/min/GPM)  
20Disinfected?  
 Yes  No









Tag# A193411

**Well Owner's Information**

First Name	Last Name / Organization	E-mail Address	<input type="checkbox"/> Well Constructed by Well Owner	
Barrie Construction 2354 Summerside Drive		Municipality	Province	Postal Code
		Manotick	ON	K4H 1B4

**Well Location**

Address of Well Location (Street Number/Name)	Township	Lot	Concession		
5560 Lombardy Drive	Osgoode	Plot 3+32	Plan 4M-830		
County/District/Municipality	City/Town/Village	Province	Postal Code		
Ottawa	Osgoode	Ontario	K0A 1A0		
UTM Coordinates	Zone	Easting	Northing	Municipal Plan and Sublot Number	Other
NAD 83	18	41510188	4999A599	Parts 17/18 R44R-14828	

**Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)**

General Colour	Most Common Material	Other Materials	General Description	Depth (m/ft) From	To
Brown	Sandy Clay		Packed	0'	10'
Brown	Sand		Packed	10'	25'
Grey	Sand	Gravel	Packed	25'	55'
Grey	Limestone		Hard	55'	161'

**Annular Space**

Depth Set at (m/ft) From	Type of Sealant Used (Material and Type)	Volume Placed (m³/ft³)
60' 40'	Cement Pressure Grouted	6.77
40' 0'	Bentonite Pressure Grouted	13.54

**Method of Construction**

		Well Use					
<input type="checkbox"/> Cable Tool	<input type="checkbox"/> Diamond	<input type="checkbox"/> Public	<input type="checkbox"/> Commercial	<input type="checkbox"/> Not used	<input type="checkbox"/> Domestic	<input type="checkbox"/> Municipal	<input type="checkbox"/> Dewatering
<input checked="" type="checkbox"/> Rotary (Conventional)	<input type="checkbox"/> Jetting	<input type="checkbox"/> Driving	<input type="checkbox"/> Livestock	<input type="checkbox"/> Test Hole	<input type="checkbox"/> Monitoring	<input type="checkbox"/> Irrigation	<input type="checkbox"/> Cooling & Air Conditioning
<input type="checkbox"/> Rotary (Reverse)	<input type="checkbox"/> Digging	<input type="checkbox"/> Industrial	<input type="checkbox"/> Other, specify				
<input type="checkbox"/> Boring							
<input checked="" type="checkbox"/> Air percussion							
<input type="checkbox"/> Other, specify							

**Construction Record - Casing**

Inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	Depth (m/ft)	From	To	Status of Well
9 1/8"	Mud (Open Hole)		0'	60'		
6 1/4"	Steel	.188	0'	60'		
6 1/8"	Open Hole		60'	160'		

**Construction Record - Screen**

Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (m/ft)	From	To	Status of Well

**Water Details**

Water found at Depth (m/ft)	Kind of Water: <input type="checkbox"/> Fresh <input checked="" type="checkbox"/> Untested <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify	Depth (m/ft)	Diameter (cm/in)
135' (m/ft)			

**Well Contractor and Well Technician Information**


Business Name of Well Contractor 1426486 Ontario Ltd aka Splash Well Drilling	Well Contractor's Licence No. A18177
Business Address (Street Number/Name) PO BOX 1083	Municipality Prescott
Province ON	Postal Code K0E 1T0
Business Telephone No. (inc. area code) 613-925-4825	Name of Well Technician (Last Name, First Name) Fernandes, Jonathan
Well Technician's Licence No. Q181519	Signature of Technician and/or Contractor Fernandes, Jonathan
Date Submitted 2016/01/20	Date Work Completed 2016/01/20

**Results of Well Yield Testing**

Draw Down	Recovery		
Time (min)	Water Level (m/ft)	Time (min)	Water Level (m/ft)
Static Level	20.6	137.3	
1	25.9	1	131.5
2	30.2	2	126.9
3	34.05	3	123.4
4	37.7	4	120
5	41	5	116.75
10	55.2	10	101.5
15	66.85	15	97.55
20	77.3	20	75.55
25	86.75	25	64.8
30	95.3	30	55.7
40	111.2	40	41.2
50	125.1	50	31.3
60	137.3	60	25.1

**Map of Well Location**

Please provide a map below following instructions on the back.



Comments:

145 Chlorine after Drilling  
0 Chlorine after Yield Test

Well owner's information package delivered <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	Date Package Delivered 2016/01/20	Ministry Use Only
Audit No. 2243019	Received 2016/01/20	



Measurements recorded in:  Metric  Imperial

Well Tag No. (Place Sticker and/or Print Below)

Tag # A193412

Well Record

Regulation 903 Ontario Water Resources Act

Page \_\_\_\_\_ of \_\_\_\_\_

Well Owner's Information

First Name	Last Name / Organization	E-mail Address	<input type="checkbox"/> Well Constructed by Well Owner
Barefoot Construction			
Mailing Address (Street Number/Name)	Municipality	Province	Postal Code
2354 Summerside Drive	Merrick ON	K4H1M1	B3T1N7

Well Location

Address of Well Location (Street Number/Name)	Township	Lot	Concession		
5554 Lombardy Drive	Osgoode	pt lot 31	Plan 4m - 830		
County/District/Municipality	City/Town/Village	Province	Postal Code		
Ottawa	Osgoode	Ontario	K0A0L0		
UTM Coordinates	Zone	Easting	Northing	Municipal Plan and Sublot Number	Other
NAD 83	18	12415BD	6616499915BR	Part 1516 RP43-14828	

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (m/ft) From	To
Brown	Clay		Packed	0'	8'
Brown	Sand		Packed	8'	15'
Grey	Sand	Gravel	Packed	15'	51'6"
Grey	Limestone		Hard	51'6"	121'

Annular Space

Depth Set at (m/ft) From	Type of Sealant Used (Material and Type)	Volume Placed (m³/ft³)
56'6"	Cement Pressure Grouted	6.77
46'6"	Bentonite Pressure Grouted	13.54

Method of Construction

Well Use

<input type="checkbox"/> Cable Tool	<input type="checkbox"/> Diamond	<input type="checkbox"/> Public	<input type="checkbox"/> Commercial	<input type="checkbox"/> Not used
<input checked="" type="checkbox"/> Rotary (Conventional)	<input type="checkbox"/> Jetting	<input type="checkbox"/> Domestic	<input type="checkbox"/> Municipal	<input type="checkbox"/> Dewatering
<input type="checkbox"/> Rotary (Reverse)	<input type="checkbox"/> Driving	<input type="checkbox"/> Livestock	<input type="checkbox"/> Test Hole	<input type="checkbox"/> Monitoring
<input type="checkbox"/> Boring	<input type="checkbox"/> Digging	<input type="checkbox"/> Irrigation	<input type="checkbox"/> Cooling & Air Conditioning	
<input checked="" type="checkbox"/> Air percussion		<input type="checkbox"/> Industrial		
<input type="checkbox"/> Other, specify		<input type="checkbox"/> Other, specify		

Construction Record - Casing

Status of Well

Inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	Depth (m/ft)	From	To	<input type="checkbox"/> Water Supply	<input type="checkbox"/> Replacement Well	<input type="checkbox"/> Test Hole	<input type="checkbox"/> Recharge Well	<input type="checkbox"/> Dewatering Well	<input type="checkbox"/> Observation and/or Monitoring Hole	<input type="checkbox"/> Alteration (Construction)	<input type="checkbox"/> Abandoned, Insufficient Supply	<input type="checkbox"/> Abandoned, Poor Water Quality	<input type="checkbox"/> Abandoned, other, specify	<input type="checkbox"/> Other, specify	
97/8" (mud)	(Open Hole)		0'	56'6"													
67/4" Steel	188	0	0'	56'6"													
67/8" Open Hole			56'6"	121'													

Construction Record - Screen

Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (m/ft)	From	To

Water Details

Hole Diameter

Water found at Depth (m/ft)	Kind of Water: <input type="checkbox"/> Fresh <input checked="" type="checkbox"/> Untested	Depth (m/ft)	Diameter (cm/in)
115' (m/ft) <input type="checkbox"/> Gas	<input type="checkbox"/> Other, specify	From	To
Water found at Depth (m/ft) <input type="checkbox"/> Gas	Kind of Water: <input type="checkbox"/> Fresh <input type="checkbox"/> Untested	0'	56'6" 47/8"
Water found at Depth (m/ft) <input type="checkbox"/> Gas	<input type="checkbox"/> Other, specify	56'6"	121" 67/8"

Well Contractor and Well Technician Information


Business Name of Well Contractor	Well Contractor's Licence No.
1425486 Ontario Ltd	4181717
Business Address (Street Number/Name)	Municipality
PO Box 1083	PICKSCOTT
Province	Postal Code
ON	K0E1V0
Bus. Telephone No. (inc. area code)	Name of Well Technician (Last Name, First Name)
613-925-4825	Ferguson Johnathan
Well Technician's Licence No.	Signature of Technician and/or Contractor
2181519	Date Submitted

Results of Well Yield Testing

Draw Down (min)	Water Level (m/ft)	Recovery (min)	Water Level (m/ft)
Static Level	16.9		56.4
1	21.05	1	50.95
2	23.15	2	45.7
3	25.2	3	42.4
4	27	4	39.3
5	28.65	5	36
10	35	10	23.4
15	39.5	15	18.3
20	43	20	17.6
25	45.8	25	17.05
30	47.5	30	17.025
40	52.8	40	17
50	54.85	50	17
60	56.4	60	16.975

Map of Well Location

Please provide a map below following instructions on the back.



Comments:

140 chlorine after Drilling  
& chlorine after Field Test

Well owner's information package delivered	Date Package Delivered	Ministry Use Only
<input checked="" type="checkbox"/> Yes	2016/11/23	Audit No. 2243020
<input type="checkbox"/> No	2016/11/23	Received

31G/4h



UTM 118iz 4151211910E

Con 15R 4191919101810N

The Ontario Water Resources Commission Act

Elev. 141R 1013110

**WATER WELL RECORD**

Basin 215 Coal

County or District Con 1 P. 1 Lot 28

Owner Coady Constr Co

(print in block letters)

Township, Village, Town or City

Osgoode

Date completed

2

(day)

Feb

month

63

year

Address 220 Ellendale Cres Ottawa

**Casing and Screen Record**

Inside diameter of casing 5"

Total length of casing 62'

Type of screen

Length of screen

Depth to top of screen

Diameter of finished hole 5"

**Pumping Test**

Static level 31

Test-pumping rate 8 G.P.M.

Pumping level 60

Duration of test pumping 1 hr

Water clear or cloudy at end of test cloudy

Recommended pumping rate 8 G.P.M.

with pump setting of 75 feet below ground surface

**Well Log**

## Overburden and Bedrock Record

sand  
clay  
sandstone  
blue limestone

From ft.	To ft.	Depth(s) at which water(s) found	Kind of water (fresh, salty, sulphur)
0	20'	100	fresh
20	36'	120	fresh
36	59'	131	"
59	133		

For what purpose(s) is the water to be used?

Post office

Is well on upland, in valley or on hillside? upland

Drilling or Boring Firm Capital Water Supply

Address 1243 Heron Rd

Licence Number 482 976

Name of Driller or Borer S Huff


Address

Date 4 Feb 1963

Signature of Licensed Drilling or Boring Contractor

**Location of Well**

In diagram below show distances of well from road and lot line. Indicate north by arrow



31G/4h



UTM 118iz 4151211910E

CON 15R 4191919101810N

The Ontario Water Resources Commission Act

Elev. 141R 1013110

**WATER WELL RECORD**

GROUND WATER BRANCH

15 MAY 21 1963

7118

ONTARIO WATER  
RESOURCES COMMISSION

Basin 215 Coal

County or District P. 1 Lot 28

Township, Village, Town or City Osgoode

Date completed 2 Feb 63

Owner Coady Constr Co

(print in block letters)

Address 220 Ellendale Cres Ottawa

**Casing and Screen Record****Pumping Test**

Inside diameter of casing 5"

Total length of casing 62'

Type of screen

Length of screen

Depth to top of screen

Diameter of finished hole 5"

Static level 31

Test-pumping rate 8 G.P.M.

Pumping level 60

Duration of test pumping 1 hr

Water clear or cloudy at end of test cloudy

Recommended pumping rate 8 G.P.M.

with pump setting of 75 feet below ground surface

**Well Log****Water Record**

## Overburden and Bedrock Record

From ft.	To ft.	Depth(s) at which water(s) found	Kind of water (fresh, salty, sulphur)
0	20'	100	fresh
20	36'	120	fresh
36	59'	131	"
59	133		

For what purpose(s) is the water to be used?

Post office

**Location of Well**

Is well on upland, in valley or on hillside?

In diagram below show distances of well from road and lot line. Indicate north by arrow

Drilling or Boring Firm Capital Water Supply

Address 1243 Heron Rd

Licence Number 482 976


Name of Driller or Borer S Huff

Address

Date 4 Feb 1963

Signature of Licensed Drilling or Boring Contractor

Form 7 10M-62-1152





**Ministry  
of the  
Environment**

**The Ontario Water Resources Act  
WATER WELL RECORD**

**Print only in spaces provided.**

Mark correct box with a checkmark, where applicable.

## OTTAWA-CARLETON

11

1533843

Municipality  
**15009**

Con.

Con.

10

County or District <b>Carleton</b>	Township/Borough/City/Town/Village <b>OSGOODE (Ottawa)</b>	Con block tract survey, etc. <b>1 Plan 393</b>	Lot <b>46 547</b>
	Address <b>5503 OSGOODE Main St.</b>	Date completed <b>9 of 03</b>	48-53 month year

71	Pumping test method 1 Pump 2 Bailler	10	Pumping rate <b>12</b> GPM	11-14 15-16 Hours	Duration of pumping 17-18 Mins		
	Static level 19-21 feet	Water level end of pumping 22-24 feet	25 Water levels during 15 minutes 26-28 feet <b>40</b>	26-28 feet <b>60</b>	30 minutes 29-31 feet <b>60</b>	35-37 feet <b>60</b>	Pumping 45 minutes 32-34 feet <b>60</b>
If flowing give rate <input type="checkbox"/> GPM		Pump intake set at feet			Water at end of test <input checked="" type="checkbox"/> Clear <input type="checkbox"/> Cloudy		
Recommended pump type <input type="checkbox"/> Shallow <input checked="" type="checkbox"/> Deep		Recommended pump setting <b>70</b> feet		43-45 feet	Recommended pump rate <b>10</b> GPM		
50-53							

<b>FINAL STATUS OF WELL</b>		54
1 <input checked="" type="checkbox"/> Water supply	5 <input type="checkbox"/> Abandoned, insufficient supply	9 <input type="checkbox"/> Unfinished
2 <input type="checkbox"/> Observation well	6 <input type="checkbox"/> Abandoned, poor quality	10 <input type="checkbox"/> Replacement well
3 <input type="checkbox"/> Test hole	7 <input type="checkbox"/> Abandoned (Other)	
4 <input type="checkbox"/> Recharge well	8 <input type="checkbox"/> Dewatering	

<b>WATER USE</b>	55-56	
1 <input checked="" type="checkbox"/> Domestic	5 <input type="checkbox"/> Commercial	9 <input type="checkbox"/> Not use
2 <input type="checkbox"/> Stock	6 <input type="checkbox"/> Municipal	10 <input type="checkbox"/> Other .....
3 <input type="checkbox"/> Irrigation	7 <input type="checkbox"/> Public supply	
4 <input type="checkbox"/> Industrial	8 <input type="checkbox"/> Cooling & air conditioning	

<b>METHOD OF CONSTRUCTION</b>		
1 <input checked="" type="checkbox"/> Cable tool	5 <input type="checkbox"/> Air percussion	9 <input type="checkbox"/> Driving
2 <input type="checkbox"/> Rotary (conventional)	6 <input type="checkbox"/> Boring	10 <input type="checkbox"/> Digging
3 <input type="checkbox"/> Rotary (reverse)	7 <input type="checkbox"/> Diamond	11 <input type="checkbox"/> Other .....
4 <input type="checkbox"/> Rotary (air)	8 <input type="checkbox"/> Jetting	

Name of Well Contractor <b>B. MOORE WELL DRILLING</b>	Well Contractor's Licence No. <b>6455</b>
Address <b>Box 436 OSGOODE ON. K0A 2W0</b>	
Name of Well Technician <b>Bob MOORE</b>	Well Technician's Licence No. <b>F-0319</b>
Signature of Technician/Contractor <b>Bob Moore</b>	Submission date day <b>01</b> md <b>03</b> yr <b>03</b>

43		54		65		75			
<b>CORD</b>		Sizes of opening (Slot No.)		31-33		Diameter 34-38		Length 39-40	
Depth - feet						inches		feet	
From	To								
0	53 <sup>16</sup>								
53	80								
20-23									
27-30									
61		<b>PLUGGING &amp; SEALING RECORD</b>							
		<input checked="" type="checkbox"/> Annular space <input type="checkbox"/> Abandonment							
Depth set at - feet		Material and type (Cement grout, bentonite, etc.)							
From	To								
0 <sup>13</sup>	53 <sup>16</sup>	Bentonite							
18-21	22-25	Quick Grout							
26-29	30-33								

**LOCATION OF WELL**

In diagram below show distances of well from road and lot line.  
Indicate north by arrow.

Village  
of  
OSGOODE

OSGOODE Main st.

George st.

pit less

244318

2 - MINISTRY OF THE ENVIRONMENT COPY

0506 (07/00) Front Form 9

## Well Owner's Information

5502 Osgoode Main

County/District/Municipality

Ottawa

UTM Coordinates Zone Easting Northing

NAD 8 3 184520 374991 220

Osgoode

City/Town/Village

Osgoode

Municipal Plan and Sublot Number

23

Province  
OntarioPostal Code  
K0A 2W0

Other

## Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (m/ft) From	Depth (m/ft) To
Brown	Sand		Hard	0	2.5
Yellow	Course Sand		Soft	2.5	9.7
Grey	clay		Soft	9.7	13.5
Grey	gravel		packed	13.5	14.9
Grey	limestone		layered	14.9	24.3

Annular Space					
Depth Set at (m/ft) From	To	Type of Sealant Used (Material and Type)	Volume Placed (m³/ft³)		
0	6	ciment grout	4 Bag		

Method of Construction		Well Use			
<input type="checkbox"/> Cable Tool	<input type="checkbox"/> Diamond	<input type="checkbox"/> Public	<input type="checkbox"/> Commercial	<input type="checkbox"/> Not used	
<input type="checkbox"/> Rotary (Conventional)	<input type="checkbox"/> Jetting	<input checked="" type="checkbox"/> Domestic	<input type="checkbox"/> Municipal	<input type="checkbox"/> Dewatering	
<input type="checkbox"/> Rotary (Reverse)	<input type="checkbox"/> Driving	<input type="checkbox"/> Livestock	<input type="checkbox"/> Test Hole	<input type="checkbox"/> Monitoring	
<input type="checkbox"/> Boring	<input type="checkbox"/> Digging	<input type="checkbox"/> Irrigation	<input type="checkbox"/> Cooling & Air Conditioning		
<input type="checkbox"/> Air percussion		<input type="checkbox"/> Industrial			
<input type="checkbox"/> Other, specify		<input type="checkbox"/> Other, specify			


Construction Record - Casing				Status of Well	
Inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	Depth (m/ft)	From	To
1555	Steel	.48	1.60	14.9	
1555	Open Hole			14.9	24.3

Construction Record - Screen			
Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (m/ft)
From	To		

Water Details		Hole Diameter	
Water found at Depth (m/ft)	Kind of Water: <input checked="" type="checkbox"/> Fresh <input type="checkbox"/> Untested <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify	Depth (m/ft) From	Diameter (cm/in) To
20		0	21.23
		6	24.3 15.65

Well Contractor and Well Technician Information					
Business Name of Well Contractor		Well Contractor's Licence No.			
<i>Bourgeois Well Drilling</i>					
Business Address (Street Number/Name)		Municipality			
1128 Route 900 East		<i>Nation</i>			
Province	Postal Code	Business E-mail Address			
Ontario	K0A 3C0	<i>NA</i>			
Bus. Telephone No. (inc. area code)		Name of Well Technician (Last Name, First Name)			
613 987 5291		<i>Michael Genier</i>			
Well Technician's Licence No.		Signature of Technician and/or Contractor			
3493		<i>Michael Genier</i>			
Date Submitted		2009 02 20			

Results of Well Yield Testing					
After test of well yield, water was:		Draw Down		Recovery	
Time (min)	Water Level (m/ft)	Time (min)	Water Level (m/ft)	Time (min)	Water Level (m/ft)
0	2.80	1	8.51	1	8.08
1	8.07	2	7.94	2	
3	8.19	3	7.83	3	
4	8.25	4	7.81	4	
5	8.30	5	7.80	5	
10	8.41	10		10	
15	8.47	15		15	
20	8.47	20		20	
25	8.47	25		25	
30	8.48	30		30	
40	8.48	40		40	
50	8.50	50		50	
60	8.51	60		60	



Well owner's information package delivered	Date Package Delivered
<input type="checkbox"/> Yes	Y Y Y Y M M D D
<input checked="" type="checkbox"/> No	Date Work Completed
	2009 02 17

Ministry Use Only

Audit No. **Z 90541**

Received **MAY 6 2009**

© Queen's Printer for Ontario, 2007



Crestview Innovations Inc.  
May 10, 2023

## Hydrogeological Investigation and Terrain Evaluation

3200 Reids Lane, Ottawa, Ontario  
210064

### ATTACHMENT C


#### GRAIN SIZE ANALYSES OF REPRESENTATIVE SOIL SAMPLES

# Grain Size Distribution Analysis



Kollaard Associates  
Engineers

SAND



SIEVE SIZE (mm)	76.2	53	26.5	19.0	16	13.2	9.5	4.75	2.36	1.180	0.600	0.300	0.15	0.075	
SAMPLE PASSING									100.0	99.8	99.3	89.2	21.4	5.8	3.7

CLIENT:	Crestview Innovations Inc.		
PROJECT:	3200 Reids Lane, Ossgoode	OUR REF.:	210064
TYPE OF MATERIAL:	Sand	INTENDED USE:	Residential
DATE SAMPLED:	February 3, 2021	DATE TESTED:	February 11, 2021
SOURCE:	BH1 - 0.76-1.37	SAMPLE NO:	SS2
REMARKS:	<hr/> <hr/>		



**Kollaard Associates**  
Engineers

Box 189, 210 Prescott Street  
Kemptville, Ontario K0G 1J0  
(613) 860-0923, FAX: (613) 258-0475

Issued by:

Date:


Dean Tataryn, B.E.S., EP  
February 12, 2021

# Grain Size Distribution Analysis



Kollaard Associates  
Engineers

SAND



SIEVE SIZE (mm)	76.2	53	26.5	19.0	16	13.2	9.5	4.75	2.36	1.180	0.600	0.300	0.15	0.075	
SAMPLE PASSING										100.0	99.0	83.7	19.0	7.1	5.2

CLIENT:	Crestview Innovations Inc.		
PROJECT:	3200 Reids Lane, Ossgoode	OUR REF.:	210064
TYPE OF MATERIAL:	Sand	INTENDED USE:	Residential
DATE SAMPLED:	February 3, 2021	DATE TESTED:	February 11, 2021
SOURCE:	BH3 - 0.76 - 1.37	SAMPLE NO:	SS2
REMARKS:	<hr/> <hr/>		



**Kollaard Associates**  
Engineers

Box 189, 210 Prescott Street  
Kemptville, Ontario K0G 1J0  
(613) 860-0923, FAX: (613) 258-0475

Issued by:

Date:


  
Dean Tartaryn, B.E.S. EP  
February 12, 2021

# Grain Size Distribution Analysis



Kollaard Associates  
Engineers

SAND



SIEVE SIZE (mm)	76.2	53	26.5	19.0	16	13.2	9.5	4.75	2.36	1.180	0.600	0.300	0.15	0.075	
SAMPLE PASSING										100.0	99.9	93.8	17.5	4.7	3.4

CLIENT:	Crestview Innovations Inc.		
PROJECT:	3200 Reids Lane, Ossgoode	OUR REF.:	210064
TYPE OF MATERIAL:	Sand	INTENDED USE:	Residential
DATE SAMPLED:	February 3, 2021	DATE TESTED:	February 11, 2021
SOURCE:	BH5 - 0.76 - 1.37	SAMPLE NO:	SS2
REMARKS:	<hr/> <hr/>		



**Kollaard Associates**  
Engineers


Box 189, 210 Prescott Street  
Kemptville, Ontario K0G 1J0  
(613) 860-0923, FAX: (613) 258-0475

Issued by:

Date:

*Dean Tataryn*  
Dean Tataryn, B.E.S. EP  
February 12, 2021

## Unified Soil Classification System



Sample ID	Depth	% Gravel	% Sand	% Silt	% Clay
BH2 SS9	7.62-8.22 m	17.7	32.1	45.2	5.0
BH4 SS7	4.52-5.18 m	0.0	85.9	10.1	4.0

## GRAIN SIZE DISTRIBUTION

Figure No.

Kollaard Associates Inc. File # 210064  
3200 Reid Lane, Osgoode



Project No. 1222410003

# Particle-Size Analysis of Soils

L5702  
AASHTO T88

PROJECT DETAILS	
Client:	Kollaard Associates Inc. File # 210064
Project:	3200 Reid Lane, Osgoode
Material Type:	Soil
Source:	BL2
Sample No.:	SS9
Sample Depth	7.62-8.22 m
Date Tested:	February 15, 2021

SOIL INFORMATION	
Liquid Limit (LL)	
Plasticity Index (PI)	
Soil Classification	
Specific Gravity ( $G_s$ )	2.750
Sg. Correction Factor ( $\alpha$ )	0.978
Mass of Dispersing Agent/Litre	40 g

CALCULATION OF DRY SOIL MASS	
Oven Dried Mass ( $M_o$ ), (g)	101.04
Air Dried Mass ( $M_a$ ), (g)	101.21
Hgrosopic Corr. Factor ( $F = M_d/M_a$ )	0.9983
Air Dried Mass in Analysis ( $M_d$ ), (g)	56.58
Oven Dried Mass in Analysis ( $M_o$ ), (g)	56.48
Percent Passing 2.0 mm Sieve ( $P_{10}$ ), (%)	75.62
Sample Represented ( $M$ ), (g)	74.69

WASH TEST DATA		
Oven Dry Mass in Hydrometer Analysis (g)	56.48	
Sample Weight after Hydrometer and Wash (g)	20.26	
Percent Passing No. 200 Sieve (%)	64.1	
Percent Passing Corrected (%)	48.50	

PERCENT LOSS IN SIEVE		
Sample Weight Before Sieve (g)	1062.00	
Sample Weight After Sieve (g)	1059.20	
Percent Loss in Sieve (%)	0.26	

HYDROMETER DETAILS	
Volume of Bulb ( $V_b$ ), (cm <sup>3</sup> )	63.0
Length of Bulb ( $L_2$ ), (cm)	14.47
Length from '0' Reading to Top of Bulb ( $L_1$ ), (cm)	10.29
Scale Dimension ( $H_s$ ), (cm/Div)	0.155
Cross-Sectional Area of Cylinder ( $A$ ), (cm <sup>2</sup> )	27.25
Meniscus Correction ( $H_m$ ), (g/l)	1.0

START TIME \_\_\_\_\_ 9:33 AM \_\_\_\_\_

## HYDROMETER ANALYSIS

Date	Time	Elapsed Time T Mins	$H_c$ g/l	Divisions g/L	Temperature $T_c$ °C	Corrected Reading $R = H_s - H_c$ g/L	Percent Passing P %	L cm	$\eta$ Poise	K	Diameter D mm
15-Feb-21	9:34 AM	1	36.0	7.0	21.0	29.0	37.99	10.63404	9.84835	0.013126	0.04280
15-Feb-21	9:35 AM	2	32.0	7.0	21.0	25.0	32.75	11.25404	9.84835	0.013126	0.03114
15-Feb-21	9:38 AM	5	28.0	7.0	21.0	21.0	27.51	11.87404	9.84835	0.013126	0.02023
15-Feb-21	9:48 AM	15	22.0	7.0	21.0	15.0	19.65	12.80404	9.84835	0.013126	0.01213
15-Feb-21	10:03 AM	30	19.0	7.0	21.0	12.0	15.72	13.26904	9.84835	0.013126	0.00873
15-Feb-21	10:33 AM	60	16.0	7.0	21.0	9.0	11.79	13.75404	9.84835	0.013126	0.00628
15-Feb-21	1:43 PM	250	12.0	7.0	22.0	5.0	6.5492	14.35404	9.61570	0.012970	0.00311
16-Feb-21	9:33 AM	1440	10.0	7.0	22.0	3.0	3.9285	14.66404	9.61570	0.012970	0.00131

Remarks:

Reviewed By: Brian Rodriguez  
Date: February 23, 2021

# Particle-Size Analysis of Soils

 LASHTO T88  
 LS702

PROJECT DETAILS	
Client:	Kollaard Associates Inc. File # 210064
Project:	3200 Reid Lane, Osgoode
Material Type:	Soil
Source:	BH4
Sample No.:	SS7
Sample Depth	4.52-5.18 m
Date Tested:	February 15, 2021

SOIL INFORMATION	
Liquid Limit (LL)	
Plasticity Index (PI)	
Soil Classification	
Specific Gravity ( $G_s$ )	2.750
Sg. Correction Factor ( $\alpha$ )	0.978
Mass of Dispersing Agent/Litre	24 g

CALCULATION OF DRY SOIL MASS	
Oven Dried Mass ( $M_o$ ), (g)	80.13
Air Dried Mass ( $M_a$ ), (g)	80.22
Hygroscopic Corr. Factor ( $f = M_d/M_a$ )	0.9989
Air Dried Mass in Analysis ( $M_a$ ), (g)	99.30
Oven Dried Mass in Analysis ( $M_o$ ), (g)	99.19
Percent Passing 2.0 mm Sieve ( $P_{2.0}$ ), (%)	99.89
Sample Represented ( $W$ ), (g)	99.30

WASH TEST DATA	
Oven Dry Mass in Hydrometer Analysis (g)	99.19
Sample Weight after Hydrometer and Wash (g)	87.02
Percent Passing No. 200 Sieve (%)	12.3
Percent Passing Corrected (%)	12.25

PERCENT LOSS IN SIEVE	
Sample Weight Before Sieve (g)	623.50
Sample Weight After Sieve (g)	623.40
Percent Loss in Sieve (%)	0.02

HYDROMETER DETAILS	
Volume of Bulb ( $V_B$ ), (cm <sup>3</sup> )	63.0
Length of Bulb ( $L_2$ ), (cm)	14.47
Length from '0' Reading to Top of Bulb ( $L_1$ ), (cm)	10.29
Scale Dimension ( $H_s$ ), (cm/Div)	0.155
Cross-Sectional Area of Cylinder ( $A$ ), (cm <sup>2</sup> )	27.25
Meniscus Correction ( $H_m$ ), (g/L)	1.0

START TIME 9:40 AM

## HYDROMETER ANALYSIS

Date	Time	Elapsed Time T Mins	$H_s$ Divisions	$H_c$ Divisions	Temperature $T_c$ °C	Corrected Reading $R = H_s - H_c$ g/L	Percent Passing P %	L cm	$\eta$ Poise	K	Diameter D mm
15-Feb-21	9:41 AM	1	12.0	3.5	22.0	8.5	8.37	14.35404	9.61570	0.012970	0.04914
15-Feb-21	9:42 AM	2	11.0	3.5	22.0	7.5	7.39	14.50904	9.61570	0.012970	0.03493
15-Feb-21	9:45 AM	5	11.0	3.5	22.0	7.5	7.39	14.50904	9.61570	0.012970	0.02209
15-Feb-21	9:55 AM	15	10.0	3.5	21.5	6.5	6.40	14.66404	9.73081	0.013047	0.01290
15-Feb-21	10:10 AM	30	9.0	3.5	21.5	5.5	5.42	14.81904	9.73081	0.013047	0.00917
15-Feb-21	10:40 AM	60	9.0	3.5	21.5	5.5	5.42	14.81904	9.73081	0.013047	0.00648
15-Feb-21	1:50 PM	250	8.0	3.5	22	4.5	4.43	14.97404	9.61570	0.012970	0.00317
15-Feb-21	9:40 AM	7.0	3.5	22	3.5	3.45	15.12904	9.61570	0.012970	0.00133	

Remarks:

 Reviewed By: Brian Picard  
 Date: February 23, 2021



Crestview Innovations Inc.  
May 10, 2023

## Hydrogeological Investigation and Terrain Evaluation

3200 Reids Lane, Ottawa, Ontario  
210064

### ATTACHMENT D

#### RESULTS OF LABORATORY NITROGEN TESTING OF RECEIVING AQUIFER SAMPLES

## Environment Testing

Client: Kollaard Associates Inc.  
210 Prescott St., Box 189  
Kempville, ON  
K0G 1J0

Attention: Ms. Colleen Vermeersch  
PO#:  
Invoice to: Kollaard Associates Inc.

Dear Colleen Vermeersch:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

Report Number: 1947810  
Date Submitted: 2021-02-12  
Date Reported: 2021-02-18  
Project: 210064  
COC #: 211512

Page 1 of 3



Addrine Thomas  
2021.02.18  
14:41:20 -05'00'

APPROVAL:

Addrine Thomas, Inorganics Supervisor

All analysis is completed at Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) unless otherwise indicated.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on the scope of accreditation. The scope is available at: <http://www.cal.ca/scopes/2602.pdf>.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is licensed by the Ontario Ministry of the Environment, Conservation, and Parks (MECP) for specific tests in drinking water (license #2318). A copy of the license is available upon request.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by the Ontario Ministry of Agriculture, Food, and Rural Affairs for specific tests in agricultural soils.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes only). Eurofins recommends consulting the official provincial or federal guideline as required. Unless otherwise stated, measurement uncertainty is not taken into account when determining guideline or regulatory exceedances.



## Certificate of Analysis

### Environment Testing

Client: Kollaard Associates Inc.  
210 Prescott St., Box 189  
Kemptville, ON  
K0G 1J0  
Attention: Ms. Colleen Vermeersch  
PO#:  
Invoice to: Kollaard Associates Inc.

Report Number: 1947810  
Date Submitted: 2021-02-12  
Date Reported: 2021-02-18  
Project: 210064  
COC #: 211512

Group	Analyte	MRL	Units	Guideline
Nutrients	N-NH <sub>3</sub>	0.010	mg/L	<0.010
	Total Kjeldahl Nitrogen	0.100	mg/L	0.393
Others	N-NO <sub>2</sub>	0.10	mg/L	0.17
	N-NO <sub>3</sub>	0.10	mg/L	5.80

Lab I.D.	1542143	1542144	1542145
Sample Matrix	GW	GW	GW
Sample Type			
Sampling Date	2021-02-12	2021-02-12	2021-02-12
Sample I.D.	MW2	MW4	MW6

**Guideline = \* = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.  
Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

## Certificate of Analysis

### Environment Testing

Client: Kollaard Associates Inc.  
 210 Prescott St., Box 189  
 Kemptonville, ON  
 K0G 1J0

Attention: Ms. Colleen Vermeersch  
 PO#:  
 Invoice to: Kollaard Associates Inc.

Report Number: 1947810  
 Date Submitted: 2021-02-12  
 Date Reported: 2021-02-18  
 Project: 210064  
 COC #: 211512

### QC Summary

Analyte		Blank	QC % Rec	QC Limits
Run No	396258	Analysis/Extraction Date	2021-02-16	Analyst SKH
Method	C SV4500-NO3-F		<0.10 mg/L	96
	N-NO2		<0.10 mg/L	103
	N-NO3			
Run No	396301	Analysis/Extraction Date	2021-02-17	Analyst SKH
Method	EPA 350.1			
	N-NH3		<0.010 mg/L	100
				80-120
Run No	396312	Analysis/Extraction Date	2021-02-17	Analyst SKH
Method	EPA 351.2			
	Total Kjeldahl Nitrogen		<0.100 mg/L	112
				70-130

**Guideline =** \* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.  
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Certificate of Analysis

Client: Kollaard Associates Inc.  
210 Prescott St., Box 189  
Kemptville, ON  
K0G 1J0

Attention: Ms. Colleen Vermeersch  
PO#:  
Invoice to: Kollaard Associates Inc.

Report Number: 1972761  
Date Submitted: 2022-03-04  
Date Reported: 2022-03-09  
Project: 210064  
COC #: 886841

Page 1 of 4

**Dear Colleen Vermeersch:**

**Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).**

Report Comments:



Addrine Thomas  
2022.03.09  
14:30:11 -05'00'

APPROVAL:

\_\_\_\_\_  
Addrine Thomas, Inorganics Supervisor

All analysis is completed at Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) unless otherwise indicated.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on the scope of accreditation. The scope is available at: <http://www.cala.ca/scopes/2602.pdf>.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is licensed by the Ontario Ministry of the Environment, Conservation, and Parks (MECP) for specific tests in drinking water (license #2318). A copy of the license is available upon request.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by the Ontario Ministry of Agriculture, Food, and Rural Affairs for specific tests in agricultural soils.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required. Unless otherwise stated, measurement uncertainty is not taken into account when determining guideline or regulatory exceedances.

## Certificate of Analysis

Client: Kollaard Associates Inc.  
 210 Prescott St., Box 189  
 Kemptville, ON  
 K0G 1J0  
 Attention: Ms. Colleen Vermeersch  
 PO#:  
 Invoice to: Kollaard Associates Inc.

Report Number: 1972761  
 Date Submitted: 2022-03-04  
 Date Reported: 2022-03-09  
 Project: 210064  
 COC #: 886841

				Lab I.D.	1613058	1613059
Group	Analyte	MRL	Units	Sample Matrix	Water	Water
Nutrients	N-NH3	0.010	mg/L	Sampling Date	<0.010	<0.010
	Total Kjeldahl Nitrogen	0.100	mg/L		0.737	0.309
Others	N-NO2	0.10	mg/L	Sample I.D.	0.16	<0.10
	N-NO3	0.10	mg/L		19.7	0.72

**Guideline =**

**\* = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.  
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

# Certificate of Analysis

Client: Kollaard Associates Inc.  
 210 Prescott St., Box 189  
 Kemptville, ON  
 K0G 1J0  
 Attention: Ms. Colleen Vermeersch  
 PO#:  
 Invoice to: Kollaard Associates Inc.

Report Number: 1972761  
 Date Submitted: 2022-03-04  
 Date Reported: 2022-03-09  
 Project: 210064  
 COC #: 886841

## **QC Summary**

Analyte	Blank	QC % Rec	QC Limits
<b>Run No</b> 418148 <b>Analysis/Extraction Date</b> 2022-03-07		<b>Analyst</b> SKH	
<b>Method</b> EPA 351.2			
Total Kjeldahl Nitrogen	<0.100 mg/L	101	70-130
<b>Run No</b> 418208 <b>Analysis/Extraction Date</b> 2022-03-08		<b>Analyst</b> SKH	
<b>Method</b> C SM4500-NO3-F			
N-NO2	<0.10 mg/L	88	80-120
N-NO3	<0.10 mg/L	99	80-120
<b>Run No</b> 418237 <b>Analysis/Extraction Date</b> 2022-03-09		<b>Analyst</b> SKH	
<b>Method</b> EPA 350.1			
N-NH3	0.013 mg/L	118	80-120

**Guideline =**

**\* = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.  
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

## Certificate of Analysis

Client: Kollaard Associates Inc.  
210 Prescott St., Box 189  
Kemptville, ON  
K0G 1J0  
Attention: Ms. Colleen Vermeersch  
PO#:  
Invoice to: Kollaard Associates Inc.

Report Number: 1972761  
Date Submitted: 2022-03-04  
Date Reported: 2022-03-09  
Project: 210064  
COC #: 886841

### ***Sample Comment Summary***

Sample ID: 1613058 BH1 Sediment not included in TKN analysis for this report.

**Guideline =**

**\* = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.  
Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

## Certificate of Analysis

Client: Kollaard Associates Inc.  
210 Prescott St., Box 189  
Kemptville, ON  
K0G 1J0  
Attention: Ms. Colleen Vermeersch  
PO#:  
Invoice to: Kollaard Associates Inc.

Report Number: 1973212  
Date Submitted: 2022-03-11  
Date Reported: 2022-03-18  
Project: 210064  
COC #: 887286

Page 1 of 4

**Dear Colleen Vermeersch:**

**Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).**

Report Comments:

Addrine Thomas  
2022.03.18  
10:21:15 -04'00'



APPROVAL:

\_\_\_\_\_  
Addrine Thomas, Inorganics Supervisor

All analysis is completed at Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) unless otherwise indicated.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on the scope of accreditation. The scope is available at: <http://www.cala.ca/scopes/2602.pdf>.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is licensed by the Ontario Ministry of the Environment, Conservation, and Parks (MECP) for specific tests in drinking water (license #2318). A copy of the license is available upon request.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by the Ontario Ministry of Agriculture, Food, and Rural Affairs for specific tests in agricultural soils.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required. Unless otherwise stated, measurement uncertainty is not taken into account when determining guideline or regulatory exceedances.

## Certificate of Analysis

Client: Kollaard Associates Inc.  
 210 Prescott St., Box 189  
 Kemptville, ON  
 K0G 1J0  
 Attention: Ms. Colleen Vermeersch  
 PO#:  
 Invoice to: Kollaard Associates Inc.

Report Number: 1973212  
 Date Submitted: 2022-03-11  
 Date Reported: 2022-03-18  
 Project: 210064  
 COC #: 887286

				Lab I.D.	
				Sample Matrix	
				Sampling Date	
				Sample I.D.	
				1614181 Water	
				2022-03-10 BH3	
Group	Analyte	MRL	Units	Guideline	
Nutrients	N-NH3	0.010	mg/L		
	Total Kjeldahl Nitrogen	0.100	mg/L		
Others	N-NO2	0.10	mg/L	<0.10	
	N-NO3	0.10	mg/L	<0.10	

**Guideline =**

**\* = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.  
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

## Certificate of Analysis

Client: Kollaard Associates Inc.  
 210 Prescott St., Box 189  
 Kemptville, ON  
 K0G 1J0  
 Attention: Ms. Colleen Vermeersch  
 PO#:  
 Invoice to: Kollaard Associates Inc.

Report Number: 1973212  
 Date Submitted: 2022-03-11  
 Date Reported: 2022-03-18  
 Project: 210064  
 COC #: 887286

### **QC Summary**

Analyte	Blank	QC % Rec	QC Limits
<b>Run No</b> 418445 <b>Analysis/Extraction Date</b> 2022-03-14		<b>Analyst</b> SKH	
<b>Method</b> EPA 350.1			
N-NH3	<0.010 mg/L	101	80-120
<b>Run No</b> 418494 <b>Analysis/Extraction Date</b> 2022-03-14		<b>Analyst</b> SKH	
<b>Method</b> EPA 351.2			
Total Kjeldahl Nitrogen	<0.100 mg/L	99	70-130
<b>Run No</b> 418535 <b>Analysis/Extraction Date</b> 2022-03-15		<b>Analyst</b> SKH	
<b>Method</b> C SM4500-NO3-F			
N-NO2	<0.10 mg/L	98	80-120
N-NO3	<0.10 mg/L	98	80-120

**Guideline =**

**\* = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.  
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

## Certificate of Analysis

Client: Kollaard Associates Inc.  
210 Prescott St., Box 189  
Kemptville, ON  
K0G 1J0  
Attention: Ms. Colleen Vermeersch  
PO#:  
Invoice to: Kollaard Associates Inc.

Report Number: 1973212  
Date Submitted: 2022-03-11  
Date Reported: 2022-03-18  
Project: 210064  
COC #: 887286

### ***Sample Comment Summary***

Sample ID: 1614181 BH3 Sediment not included in TKN analysis.

**Guideline =**

**\* = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.  
Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Certificate of Analysis

Client: Kollaard Associates Inc.  
210 Prescott St., Box 189  
Kemptville, ON  
K0G 1J0

Attention: Ms. Colleen Vermeersch  
PO#:  
Invoice to: Kollaard Associates Inc.

Report Number: 1979883  
Date Submitted: 2022-06-22  
Date Reported: 2022-06-28  
Project: 210064  
COC #: 892186

Page 1 of 3

**Dear Colleen Vermeersch:**

**Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).**

Report Comments:

Emma-  
Dawn  
  
Ferguson  
2022.06.2  
8 15:05:21  
-04'00'

APPROVAL:

\_\_\_\_\_  
Emma-Dawn Ferguson, Chemist

All analysis is completed at Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) unless otherwise indicated.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on the scope of accreditation. The scope is available at: <https://directory.cala.ca/>.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is licensed by the Ontario Ministry of the Environment, Conservation, and Parks (MECP) for specific tests in drinking water (license #2318). A copy of the license is available upon request.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by the Ontario Ministry of Agriculture, Food, and Rural Affairs for specific tests in agricultural soils.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required. Unless otherwise stated, measurement uncertainty is not taken into account when determining guideline or regulatory exceedances.

## Certificate of Analysis

Client: Kollaard Associates Inc.  
 210 Prescott St., Box 189  
 Kemptville, ON  
 K0G 1J0  
 Attention: Ms. Colleen Vermeersch  
 PO#:  
 Invoice to: Kollaard Associates Inc.

Report Number: 1979883  
 Date Submitted: 2022-06-22  
 Date Reported: 2022-06-28  
 Project: 210064  
 COC #: 892186

				Lab I.D.	
				Sample Matrix	
				Sampling Date	
				Sample I.D.	
				1632864	
				Water	
				2022-06-17	
				MW1	
Group	Analyte	MRL	Units	Guideline	
Nutrients	N-NH3	0.010	mg/L		
	Total Kjeldahl Nitrogen	0.100	mg/L		
Others	N-NO2	0.10	mg/L	<0.10	
	N-NO3	0.10	mg/L	8.11	

**Guideline =**

**\* = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.  
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

## Certificate of Analysis

Client: Kollaard Associates Inc.  
 210 Prescott St., Box 189  
 Kemptville, ON  
 K0G 1J0  
 Attention: Ms. Colleen Vermeersch  
 PO#:  
 Invoice to: Kollaard Associates Inc.

Report Number: 1979883  
 Date Submitted: 2022-06-22  
 Date Reported: 2022-06-28  
 Project: 210064  
 COC #: 892186

### **QC Summary**

Analyte	Blank	QC % Rec	QC Limits
Run No 424404	Analysis/Extraction Date 2022-06-23	Analyst	ML
Method EPA 350.1			
N-NH3	<0.010 mg/L	99	80-120
Run No 424476	Analysis/Extraction Date 2022-06-24	Analyst	SKH
Method C SM4500-NO3-F			
N-NO2	<0.10 mg/L	102	80-120
N-NO3	<0.10 mg/L	103	80-120
Run No 424502	Analysis/Extraction Date 2022-06-24	Analyst	SKH
Method EPA 351.2			
Total Kjeldahl Nitrogen	<0.100 mg/L	105	70-130

**Guideline =**

**\* = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.  
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Kollaard Associates Inc.  
210 Prescott St., Box 189  
Kemptville, ON  
K0G 1J0

Attention: Ms. Colleen Vermeersch  
PO#:  
Invoice to: Kollaard Associates Inc.

Report Number: 1993661  
Date Submitted: 2023-02-10  
Date Reported: 2023-02-14  
Project: 210064  
COC #: 905438

Page 1 of 3

**Dear Colleen Vermeersch:**

**Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).**

Report Comments:

Raheleh  
Zafari

R Zafari 2023.02.1  
4 17:11:18  
-05'00'

APPROVAL:

Raheleh Zafari, Environmental Chemist

All analysis is completed at Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) unless otherwise indicated.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on the scope of accreditation. The scope is available at: <https://directory.cala.ca/>.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is licensed by the Ontario Ministry of the Environment, Conservation, and Parks (MECP) for specific tests in drinking water (license #2318). A copy of the license is available upon request.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by the Ontario Ministry of Agriculture, Food, and Rural Affairs for specific tests in agricultural soils.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required. Unless otherwise stated, measurement uncertainty is not taken into account when determining guideline or regulatory exceedances.

## Certificate of Analysis

Client: Kollaard Associates Inc.  
 210 Prescott St., Box 189  
 Kemptville, ON  
 K0G 1J0  
 Attention: Ms. Colleen Vermeersch  
 PO#:  
 Invoice to: Kollaard Associates Inc.

Report Number: 1993661  
 Date Submitted: 2023-02-10  
 Date Reported: 2023-02-14  
 Project: 210064  
 COC #: 905438

				Lab I.D.	
				Sample Matrix	
				Sampling Date	
				Sample I.D.	
				1674214 Water	
				2023-02-09 BH1	
Group	Analyte	MRL	Units	Guideline	
Nutrients	N-NH3	0.020	mg/L	<0.020	
	Total Kjeldahl Nitrogen	0.100	mg/L	0.572	
Others	N-NO2	0.10	mg/L	0.14	
	N-NO3	0.10	mg/L	19.3	

**Guideline =**

**\* = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.  
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

# Certificate of Analysis

Client: Kollaard Associates Inc.  
 210 Prescott St., Box 189  
 Kemptville, ON  
 K0G 1J0  
 Attention: Ms. Colleen Vermeersch  
 PO#:  
 Invoice to: Kollaard Associates Inc.

Report Number: 1993661  
 Date Submitted: 2023-02-10  
 Date Reported: 2023-02-14  
 Project: 210064  
 COC #: 905438

## **QC Summary**

Analyte	Blank	QC % Rec	QC Limits
<b>Run No</b> 437473 <b>Analysis/Extraction Date</b> 2023-02-13		<b>Analyst</b> SKH	
<b>Method</b> EPA 350.1			
N-NH3	<0.020 mg/L	92	80-120
<b>Run No</b> 437476 <b>Analysis/Extraction Date</b> 2023-02-13		<b>Analyst</b> SKH	
<b>Method</b> C SM4500-NO3-F			
N-NO2	<0.10 mg/L	100	80-120
N-NO3	<0.10 mg/L	101	80-120
<b>Run No</b> 437487 <b>Analysis/Extraction Date</b> 2023-02-13		<b>Analyst</b> SKH	
<b>Method</b> EPA 351.2			
Total Kjeldahl Nitrogen	<0.100 mg/L	116	70-130

**Guideline =**

**\* = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.  
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range



Crestview Innovations Inc.  
May 10, 2023

## Hydrogeological Investigation and Terrain Evaluation

3200 Reids Lane, Ottawa, Ontario  
210064

### ATTACHMENT E

#### SEPTIC EFFLUENT DILUTION CALCULATIONS

May 2023

210064

#### SEPTIC EFFLUENT DILUTION CALCULATIONS

Number of Lots	7
Gross Site Area	35438 m <sup>2</sup>
Env. Can. Water Surplus (NPI)	379 mm

#### Hard Surface Area (Post-Development)

Roadway	2054
Dwellings, driveways other impervious areas (up to 600 m <sup>2</sup> per lot)	<u>4200</u>
Total	6254 m <sup>2</sup>

Net Infiltration Area = Gross Site Area - Hard Surface Area (Post-Development)  
29184 m<sup>2</sup>

Infiltration Reduction Factor:

Topography (rolling)	0.20
Soil (open sandy loam)	0.40
<u>Cover (cultivated/orchard)</u>	<u>0.10</u>
Total IRF	0.70

Septic Dilution For 7 Septic Systems:

$$\frac{\text{Number of Lots} \times 365 \text{ m}^3 \text{ Effluent Per Year} \times 40 \text{ mg/L NO}_3}{\text{Number of Lots} \times 365 \text{ m}^3 \text{ Effluent Per Year} + (\text{Net Infiltration Area} \times \text{NPI} \times \text{IRF})} = 9.9 \text{ mg/L NO}_3\text{-N}$$

Ottawa Intl A

WATER BUDGET MEANS FOR THE PERIOD 1939-2021 DC20492

LAT.... 45.32      WATER HOLDING CAPACITY... 75 MM      HEAT INDEX... 36.75  
 LONG... 75.67      LOWER ZONE..... 45 MM      A..... 1.080

DATE	TEMP (C)	PCPN	RAIN	MELT	PE	AE	DEF	SURP	SNOW	SOIL	ACC P
31- 1	-10.6	62	12	14	0	0	0	25	83	74	294
28- 2	-9.0	56	10	16	1	1	0	26	111	74	350
31- 3	-2.8	65	31	77	6	6	0	103	68	75	416
30- 4	5.7	73	68	73	31	31	0	110	0	75	489
31- 5	13.1	75	75	0	80	80	0	14	0	56	565
30- 6	18.3	85	85	0	116	107	-9	5	0	29	650
31- 7	20.9	88	88	0	136	103	-33	3	0	11	737
31- 8	19.7	84	84	0	118	83	-35	1	0	11	822
30- 9	14.8	82	82	0	75	65	-10	4	0	24	904
31-10	8.3	78	78	0	37	36	-1	14	0	52	78
30-11	1.2	76	59	8	10	10	0	38	9	71	154
31-12	-6.9	79	27	14	1	1	0	36	47	74	233
AVE	6.0 TTL	903	699	202	611	523	-88	379			

Ottawa Intl A

STANDARD DEVIATIONS FOR THE PERIOD 1939-2021 DC20492

DATE	TEMP (C)	PCPN	RAIN	MELT	PE	AE	DEF	SURP	SNOW	SOIL	ACC P
31- 1	2.9	26	15	17	1	1	0	28	44	3	59
28- 2	2.6	26	14	25	1	1	0	34	59	3	63
31- 3	2.6	28	22	49	5	5	0	55	87	0	71
30- 4	1.8	32	33	88	9	9	0	89	2	2	80
31- 5	1.8	34	34	2	12	12	0	24	0	22	94
30- 6	1.2	38	38	0	8	17	18	16	0	29	105
31- 7	1.2	45	45	0	8	31	33	16	0	22	117
31- 8	1.3	37	37	0	9	29	31	4	0	21	126
30- 9	1.5	39	39	0	8	16	16	15	0	28	132
31-10	1.5	37	37	1	7	7	2	21	0	27	37
30-11	1.8	27	27	8	4	4	0	32	13	12	45
31-12	3.0	30	22	13	1	1	0	30	34	4	55



Crestview Innovations Inc.  
May 10, 2023

## Hydrogeological Investigation and Terrain Evaluation

3200 Reids Lane, Ottawa, Ontario  
210064

### ATTACHMENT F

#### RESULTS OF LABORATORY TESTING OF TEST WELL WATER SAMPLES

## Environment Testing

Client: Kollaard Associates Inc.  
210 Prescott St., Box 189  
Kempville, ON  
K0G 1J0

Attention: Ms. Colleen Vermeersch  
PO#:  
Invoice to: Kollaard Associates Inc.

Page 1 of 7

Dear Colleen Vermeersch:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

Addrline  
  
Thomas  
2021.05.20  
16:03:15 -04'00'

APPROVAL:

Addrline Thomas, Inorganics Supervisor

All analysis is completed at Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) unless otherwise indicated.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on the scope of accreditation. The scope is available at: <http://www.calacalascopes/2602.pdf>.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is licensed by the Ontario Ministry of the Environment, Conservation, and Parks (MECP) for specific tests in drinking water (license #2318). A copy of the license is available upon request.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by the Ontario Ministry of Agriculture, Food, and Rural Affairs for specific tests in agricultural soils.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes only). Eurofins recommends consulting the official provincial or federal guideline as required. Unless otherwise stated, measurement uncertainty is not taken into account when determining guideline or regulatory exceedances.

## Certificate of Analysis

### **Environment Testing**

Client: Kollaard Associates Inc.  
 210 Prescott St., Box 189  
 Kemptonville, ON  
 K0G 1J0

Attention: Ms. Colleen Vermeersch  
 PO#:  
 Invoice to: Kollaard Associates Inc.

Report Number: 1953233  
 Date Submitted: 2021-05-13  
 Date Reported: 2021-05-20  
 Project: 210064  
 COC #: 873626

Group	Analyte	MRL	Units	Guideline	
				Lab I.D.	Sample Matrix
Anions	Cl	1	mg/L	AO 250	178
	F	0.10	mg/L	MAC 1.5	0.83
	N-NO2	0.10	mg/L	MAC 1.0	<0.50
	N-NO3	0.10	mg/L	MAC 10.0	<0.50
	SO4	1	mg/L	AO 500	44
General Chemistry	Alkalinity as CaCO3	5	mg/L	OG 500	142
	Colour	2	TCU	<2	<2
	Conductivity	5	uS/cm	AO 5	951
	DOC	0.5	mg/L	AO 5	1.8
	pH	1.00		6.5-8.5	8.19
	S2-	0.01	mg/L	AO 0.05	1.10*
	TDS (COND - CALC)	1	mg/L	AO 500	618*
	Turbidity	0.1	NTU	AO 5.0	2.2
Hardness	Hardness as CaCO3	1	mg/L	OG 100	229*
Indices/Calc	Ion Balance	0.01		OG 100	229*
Metals	Al	0.01	mg/L	OG 0.1	1.03
	As	0.001	mg/L	IMAC 0.01	<0.01
	B	0.01	mg/L	IMAC 5.0	0.54
	Ba	0.01	mg/L	MAC 1.0	0.08
	Ca	1	mg/L	44	44
	Cd	0.0001	mg/L	MAC 0.005	<0.0001
	Co	0.0002	mg/L	<0.0002	<0.0002
	Cr	0.001	mg/L	MAC 0.05	<0.001
	Cu	0.001	mg/L	AO 1.0	<0.001
	Fe	0.03	mg/L	AO 0.3	0.16

**Guideline = ODWSOG** \* = Guideline Exceedence

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Results relate only to the parameters tested on the samples submitted.  
 Methods references and/or additional QA/QC information available on request.



## Certificate of Analysis

### Environment Testing

Client: Kollaard Associates Inc.  
210 Prescott St., Box 189  
Kempville, ON  
K0G 1J0

Attention: Ms. Colleen Vermeersch  
PO#:  
Invoice to: Kollaard Associates Inc.

Report Number: 1953233  
Date Submitted: 2021-05-13  
Date Reported: 2021-05-20  
Project: 210064  
COC #: 873626

Group	Analyte	MRL	Units	Guideline	
Metals	Hg	0.0001	mg/L	MAC 0.001	<0.0001
	K	1	mg/L		11
	Mg	1	mg/L		29
	Mn	0.01	mg/L	AO 0.05	0.01
	Na	2	mg/L	AO 200	98
	Pb	0.001	mg/L	MAC 0.010	<0.001
	Sb	0.0005	mg/L	IMAC 0.006	<0.0005
	Se	0.001	mg/L	MAC 0.05	<0.001
	Sr	0.001	mg/L		3.92
	U	0.001	mg/L	MAC 0.02	<0.001
	V	0.001	mg/L		<0.001
	Zn	0.01	mg/L	AO 5.0	<0.01
Nutrients	N-NH <sub>3</sub>	0.010	mg/L		0.303
	Total Kjeldahl Nitrogen	0.100	mg/L		0.391
Subcontract	Phenols	0.001	mg/L	<0.0010	0.504
	Tannin & Lignin	0.1	mg/L		0.1

Lab I.D.	Sample Matrix	Sampling Date	
1556912	Water	2021-05-12	1556913 Water TW#1-6 hr

**Guideline = ODWSOG** \* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.  
Methods references and/or additional Q/AQC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

## Certificate of Analysis

### Environment Testing

Client: Kollaard Associates Inc.  
210 Prescott St., Box 189  
Kemptville, ON  
K0G 1J0

Attention: PO#:  
Ms. Colleen Vermeersch  
Invoice to: Kollaard Associates Inc.

Report Number: 1953233  
Date Submitted: 2021-05-13  
Date Reported: 2021-05-20  
Project: 210064  
COC #: 873626

### QC Summary

Analyte	Blank	QC % Rec	QC Limits
Run No 400541 Method C SM2/130B	Analysis/Extraction Date 2021-05-13	Analyst K B	
Turbidity	0.6 NTU	101	70-130
Run No 400603 Method C SM2/120C	Analysis/Extraction Date 2021-05-14	Analyst SKH	
Colour	<2 TCU	102	90-110
Run No 400654 Method EPA 200.8	Analysis/Extraction Date 2021-05-14	Analyst SKH	
Aluminum	<0.01 mg/L	106	80-120
Arsenic	<0.001 mg/L	100	80-120
Boron (total)	<0.01 mg/L	106	80-120
Barium	<0.01 mg/L	95	80-120
Cadmium	<0.0001 mg/L	100	80-120
Cobalt	<0.0002 mg/L	104	80-120
Chromium Total	<0.001 mg/L	105	80-120
Copper	<0.001 mg/L	105	80-120
Iron	<0.03 mg/L	99	80-120
Mercury	<0.0001 mg/L	90	80-120

#### Guideline = ODWSOG

#### \* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.  
Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

**Environment Testing**

Client: Kollaard Associates Inc.  
 210 Prescott St., Box 189  
 Kemptonville, ON  
 K0G 1J0

Attention: PO#:  
 Ms. Colleen Vermeersch  
 Invoice to: Kollaard Associates Inc.

Report Number: 1953233  
 Date Submitted: 2021-05-13  
 Date Reported: 2021-05-20  
 Project: 210064  
 COC #: 873626

**QC Summary**

Analyte	Blank	QC % Rec	QC Limits
Manganese	<0.01 mg/L	100	80-120
Lead	<0.001 mg/L	106	80-120
Antimony	<0.0005 mg/L	96	80-120
Selenium	<0.001 mg/L	94	80-120
Strontium	<0.001 mg/L	94	80-120
Uranium	<0.001 mg/L	107	80-120
Vanadium	<0.001 mg/L	104	80-120
Zinc	<0.01 mg/L	104	80-120
<b>Run No</b>	<b>Analysis/Extraction Date</b>	<b>Analyst</b>	<b>SWS</b>
<b>Method</b>	<b>SM/2320,2510,4500HF/F</b>		
F	<0.10 mg/L	100	90-110
pH		100	90-110
<b>Run No</b>	<b>Analysis/Extraction Date</b>	<b>Analyst</b>	<b>SWS</b>
<b>Method</b>	<b>SM 5310B</b>		
DOC	<0.5 mg/L	89	80-120
<b>Run No</b>	<b>Analysis/Extraction Date</b>	<b>Analyst</b>	<b>SKH</b>
<b>Method</b>	<b>EPA 350.1</b>		
N-NH3	<0.010 mg/L	99	80-120

**Guideline = ODWSOG**
**\* = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.  
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

## Certificate of Analysis

### Environment Testing

Client: Kollaard Associates Inc.  
 210 Prescott St., Box 189  
 Kemptonville, ON  
 K0G 1J0

Attention:  
 PO#:  
 Invoice to:

Ms. Colleen Vermeersch  
 Kollaard Associates Inc.

Report Number: 1953233  
 Date Submitted: 2021-05-13  
 Date Reported: 2021-05-20  
 Project: 210064  
 COC #: 873626

### QC Summary

Analyte	Blank	QC % Rec	QC Limits
<b>Run No</b> 400779	Analysis/Extraction Date 2021-05-17	Analyst SKH	
<b>Method</b> EPA 351.2			
Total Kjeldahl Nitrogen	<0.100 mg/L	102	70-130
<b>Run No</b> 400737	Analysis/Extraction Date 2021-05-18	Analyst Z S	
<b>Method</b> M SM3120B-3500C			
Calcium	<1 mg/L	100	90-110
Potassium	<1 mg/L	102	87-113
Magnesium	<1 mg/L	98	76-124
Sodium	<2 mg/L	105	82-118
<b>Run No</b> 400792	Analysis/Extraction Date 2021-05-17	Analyst SWS	
<b>Method</b> SM2320,2510,4500H/F			
Alkalinity (CaCO <sub>3</sub> )	<5 mg/L	97	90-110
Conductivity	<5 uS/cm	97	90-110
<b>Run No</b> 400797	Analysis/Extraction Date 2021-05-19	Analyst AET	
<b>Method</b> SM 4110			
Chloride	<5 mg/L		90-110
N-NO <sub>2</sub>	<0.50 mg/L	98	90-110
N-NO <sub>3</sub>	<0.50 mg/L	105	90-110
SO <sub>4</sub>	<5 mg/L	100	90-110

**Guideline = ODWSOG**

\* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.  
 Methods references and/or additional Q/A/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

## Certificate of Analysis

### Environment Testing

Client: Kollaard Associates Inc.  
 210 Prescott St., Box 189  
 Kemptonville, ON  
 K0G 1J0

Attention: Ms. Colleen Vermeersch  
 PO#:  
 Invoice to: Kollaard Associates Inc.

Report Number: 1953233  
 Date Submitted: 2021-05-13  
 Date Reported: 2021-05-20  
 Project: 210064  
 COC #: 873626

### QC Summary

QC Summary					
	Analyte		Blank	QC % Rec	QC Limits
Run No	400811	Analysis/Extraction Date	2021-05-19	Analyst	AET
Method	C SM2340B				
	Hardness as CaCO <sub>3</sub>				
	Ion Balance				
	TDS (COND - CALC)				
Run No	400865	Analysis/Extraction Date	2021-05-14	Analyst	AET
Method	SUBCONTRACT-A				
	Phenols	<0.0010 mg/L		98	
	Tannin & Lignin	<0.10 mg/L		103	
Run No	400982	Analysis/Extraction Date	2021-05-20	Analyst	AET
Method	C SM4500-S2-D				
	S2-	<0.01 mg/L		104	80-120

**Guideline = ODWSOG** \* = Guideline Exceedence

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Results relate only to the parameters tested on the samples submitted.  
 Methods references and/or additional Q/A/QC information available on request.

**Environment Testing**

Client: Kollaard Associates Inc.  
210 Prescott St., Box 189  
Kempville, ON  
K0G 1J0  
Attention: Ms. Colleen Vermeersch  
PO#:  
Invoice to: Kollaard Associates Inc.

Report Number: 1953218  
Date Submitted: 2021-05-13  
Date Reported: 2021-05-16  
Project: 210064  
COC #: 873626

Page 1 of 2

Dear Colleen Vermeersch:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

Dragana  
*Dragana Dzeletovic* Dzeletovic  
2021.05.16  
08:33:26 -04'00'  
APPROVAL: \_\_\_\_\_  
Dragana Dzeletovic-Andric, Microbiology Team Lead

All analysis is completed at Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) unless otherwise indicated.  
Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on the scope of accreditation. The scope is available at: <http://www.cala.ca/scopes/2602.pdf>.  
Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is licensed by the Ontario Ministry of the Environment, Conservation, and Parks (MECP) for specific tests in drinking water (license #2318). A copy of the license is available upon request.  
Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by the Ontario Ministry of Agriculture, Food, and Rural Affairs for specific tests in agricultural soils.  
Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes only). Eurofins recommends consulting the official provincial or federal guideline as required. Unless otherwise stated, measurement uncertainty is not taken into account when determining guideline or regulatory exceedances.



## Certificate of Analysis

### Environment Testing

Client: Kollaard Associates Inc.  
210 Prescott St., Box 189  
Kempville, ON  
K0G 1J0  
Attention: Ms. Colleen Vermeersch  
PO#:  
Invoice to:

Kollaard Associates Inc.

Report Number: 1953218  
Date Submitted: 2021-05-13  
Date Reported: 2021-05-16  
Project: 210064  
COC #: 873626

Group	Analyte	MRL	Units	Guideline	
Microbiology	Escherichia Coli	0	ct/100mL	MAC 0	0
	Faecal Coliforms	0	ct/100mL		0
	Heterotrophic Plate Count	0	ct/1mL		0
	Total Coliforms	0	ct/100mL	MAC 0	0

Lab I.D.	1556873	Water	1556874
Sample Matrix			
Sample Type			
Sampling Date	2021-05-12		
Sample I.D.	TW#1-3 hr	2021-05-12	TW#1-6 hr

**Guideline = ODWSOG**

\* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.

**Analytical Method: AMBCOLM1**  
additional QA/QC information available on request

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

## Environment Testing

Client: Kollaard Associates Inc.  
210 Prescott St., Box 189  
Kempville, ON  
K0G 1J0

Attention: Ms. Colleen Vermeersch  
PO#:  
Invoice to: Kollaard Associates Inc.

Report Number: 1952974  
Date Submitted: 2021-05-11  
Date Reported: 2021-05-19  
Project: 210064  
COC #: 873496

Page 1 of 7

Dear Colleen Vermeersch:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

Addrine  
Thomas  
  
2021.05.19  
16:06:04  
APPROVAL: -0400-  
Addrine Thomas, Inorganics Supervisor

All analysis is completed at Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) unless otherwise indicated.  
Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on the scope of accreditation. The scope is available at: <http://www.cal.ca/scopes/2602.pdf>.  
Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is licensed by the Ontario Ministry of the Environment, Conservation, and Parks (MECP) for specific tests in drinking water (license #2318). A copy of the license is available upon request.  
Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by the Ontario Ministry of Agriculture, Food, and Rural Affairs for specific tests in agricultural soils.  
Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes only). Eurofins recommends consulting the official provincial or federal guideline as required. Unless otherwise stated, measurement uncertainty is not taken into account when determining guideline or regulatory exceedances.

## Certificate of Analysis

### Environment Testing

Client: Kollaard Associates Inc.  
210 Prescott St., Box 189  
Kempville, ON  
K0G 1J0

Attention: Ms. Colleen Vermeersch  
PO#:  
Invoice to: Kollaard Associates Inc.

Report Number: 1952974  
Date Submitted: 2021-05-11  
Date Reported: 2021-05-19  
Project: 210064  
COC #: 873496

Group	Analyte	MRL	Units	Guideline	
				Lab I.D.	Sample Matrix
Anions	Cl	1	mg/L	AO 250	155
	F	0.10	mg/L	MAC 1.5	0.94
	N-NO2	0.10	mg/L	MAC 1.0	<0.10
	N-NO3	0.10	mg/L	MAC 10.0	<0.10
	SO4	1	mg/L	AO 500	47
General Chemistry	Alkalinity as CaCO3	5	mg/L	OG 500	139
	Colour	2	TCU	<2	<2
	Conductivity	5	uS/cm	AO 5	829
	DOC	0.5	mg/L	AO 5	1.8
	pH	1.00		6.5-8.5	8.01
	S2-	0.01	mg/L	AO 0.05	0.27*
	TDS (COND - CALC)	1	mg/L	AO 500	539*
	Turbidity	0.1	NTU	AO 5.0	5.7*
Hardness	Hardness as CaCO3	1	mg/L	OG 100	211*
Indices/Calc	Ion Balance	0.01			233*
Metals	Al	0.01	mg/L	OG 0.1	0.97
	As	0.001	mg/L	IMAC 0.01	<0.01
	B	0.01	mg/L	IMAC 5.0	0.57
	Ba	0.01	mg/L	MAC 1.0	0.26
	Ca	1	mg/L	40	44
	Cd	0.0001	mg/L	MAC 0.005	<0.0001
	Co	0.0002	mg/L	<0.0002	<0.0002
	Cr	0.001	mg/L	MAC 0.05	<0.001
	Cu	0.001	mg/L	AO 1.0	<0.001
	Fe	0.03	mg/L	AO 0.3	0.46*
					0.14

**Guideline = ODWSOG** \* = Guideline Exceedence

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Results relate only to the parameters tested on the samples submitted.  
Methods references and/or additional QA/QC information available on request.



## Certificate of Analysis

### Environment Testing

Client: Kollaard Associates Inc.  
210 Prescott St., Box 189  
Kempville, ON  
K0G 1J0

Attention: Ms. Colleen Vermeersch  
PO#:  
Invoice to: Kollaard Associates Inc.

Report Number: 1952974  
Date Submitted: 2021-05-11  
Date Reported: 2021-05-19  
Project: 210064  
COC #: 873496

Group	Analyte	MRL	Units	Guideline	
				Lab I.D.	Sample Matrix
Metals	Hg	0.0001	mg/L	MAC 0.001	<0.0001
	K	1	mg/L		11
	Mg	1	mg/L		30
	Mn	0.01	mg/L	AO 0.05	0.02
	Na	2	mg/L	AO 200	78
	Pb	0.001	mg/L	MAC 0.010	<0.001
	Sb	0.0005	mg/L	IMAC 0.006	<0.0005
	Se	0.001	mg/L	MAC 0.05	<0.001
	Sr	0.001	mg/L		3.28
	U	0.001	mg/L	MAC 0.02	<0.001
	V	0.001	mg/L		<0.001
	Zn	0.01	mg/L	AO 5.0	<0.01
Nutrients	N-NH <sub>3</sub>	0.010	mg/L		0.307
	Total Kjeldahl Nitrogen	0.100	mg/L		0.272
Subcontract	Phenols	0.001	mg/L	<0.0010	<0.0010
	Tannin & Lignin	0.1	mg/L		0.2

**Guideline = ODWSOG** \* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.  
Methods references and/or additional Q/AQC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

## Certificate of Analysis

### Environment Testing

Client: Kollaard Associates Inc.  
 210 Prescott St., Box 189  
 Kemptonville, ON  
 K0G 1J0

Attention: Ms. Colleen Vermeersch  
 PO#:  
 Invoice to: Kollaard Associates Inc.

Report Number: 1952974  
 Date Submitted: 2021-05-11  
 Date Reported: 2021-05-19  
 Project: 210064  
 COC #: 873496

### QC Summary

Analyte	Blank	QC % Rec	QC Limits
Run No 400409	Analysis/Extraction Date 2021-05-12	Analyst K B	
Method C SM2/130B	<0.1 NTU	101	70-130
Turbidity			
Run No 400492	Analysis/Extraction Date 2021-05-13	Analyst K B	
Method C SM2/120C	<2 TCU	87	90-110
Colour			
Run No 400510	Analysis/Extraction Date 2021-05-13	Analyst SKH	
Method EPA 200.8			
Aluminum	<0.01 mg/L	100	80-120
Arsenic	<0.001 mg/L	102	80-120
Boron (total)	<0.01 mg/L	108	80-120
Barium	<0.01 mg/L	89	80-120
Cadmium	<0.0001 mg/L	97	80-120
Cobalt	<0.0002 mg/L	114	80-120
Chromium Total	<0.001 mg/L	109	80-120
Copper	<0.001 mg/L	116	80-120
Iron	<0.03 mg/L	103	80-120
Mercury	<0.0001 mg/L	96	80-120

**Guideline = ODWSOG**

\* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.  
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

**Environment Testing**

Client: Kollaard Associates Inc.  
 210 Prescott St., Box 189  
 Kemptonville, ON  
 K0G 1J0

Attention: PO#:  
 Ms. Colleen Vermeersch  
 Invoice to: Kollaard Associates Inc.

Report Number: 1952974  
 Date Submitted: 2021-05-11  
 Date Reported: 2021-05-19  
 Project: 210064  
 COC #: 873496

**QC Summary**

Analyte	Blank	QC % Rec	QC Limits
Manganese	<0.01 mg/L	99	80-120
Lead	<0.001 mg/L	111	80-120
Antimony	<0.0005 mg/L	90	80-120
Selenium	<0.001 mg/L	87	80-120
Strontium	<0.001 mg/L	86	80-120
Uranium	<0.001 mg/L	110	80-120
Vanadium	<0.001 mg/L	108	80-120
Zinc	<0.01 mg/L	108	80-120
<b>Run No</b>	<b>Analysis/Extraction Date</b>	<b>Analyst</b>	<b>SWS</b>
Method SM 5310B	2021-05-12		
DOC	<0.5 mg/L	92	80-120
<b>Run No</b>	<b>Analysis/Extraction Date</b>	<b>Analyst</b>	<b>AET</b>
Method SM 4110	2021-05-14		
N-NO2	<0.10 mg/L	101	90-110
N-NO3	<0.10 mg/L	105	90-110
SO4	<1 mg/L	100	90-110
<b>Run No</b>	<b>Analysis/Extraction Date</b>	<b>Analyst</b>	<b>SKH</b>
Method EPA 350.1	2021-05-13		
N-NH3	<0.010 mg/L	106	80-120

**Guideline = ODWSOG**
**\* = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.  
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

**Environment Testing**

Client: Kollaard Associates Inc.  
 210 Prescott St., Box 189  
 Kemptonville, ON  
 K0G 1J0

Attention: PO#:  
 Ms. Colleen Vermeersch  
 Invoice to: Kollaard Associates Inc.

Report Number: 1952974  
 Date Submitted: 2021-05-11  
 Date Reported: 2021-05-19  
 Project: 210064  
 COC #: 873496

**QC Summary**

Analyte	Blank	QC % Rec	QC Limits
<b>Run No</b> 400568 <b>Analysis/Extraction Date</b> 2021-05-13	<b>Analyst</b> SKH		
<b>Method</b> EPA 351.2			
Total Kjeldahl Nitrogen	<0.100 mg/L	95	70-130
<b>Run No</b> 400570 <b>Analysis/Extraction Date</b> 2021-05-13	<b>Analyst</b> SWS		
<b>Method</b> SM2320/2510/4500H/F			
Alkalinity (CaCO <sub>3</sub> )	<5 mg/L	98	90-110
Conductivity	<5 uS/cm	100	90-110
F	<0.10 mg/L	101	90-110
pH		100	90-110
<b>Run No</b> 400624 <b>Analysis/Extraction Date</b> 2021-05-14	<b>Analyst</b> Z S		
<b>Method</b> M SM3120B-3500C			
Calcium	<1 mg/L	99	90-110
Potassium	<1 mg/L	102	87-113
Magnesium	<1 mg/L	98	76-124
Sodium	<2 mg/L	102	82-118
<b>Run No</b> 400722 <b>Analysis/Extraction Date</b> 2021-05-18	<b>Analyst</b> AET		
<b>Method</b> SM 4110			
Chloride	<5 mg/L		90-110

**Guideline = ODWSOG**

\* = Guideline Exceedence

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Results relate only to the parameters tested on the samples submitted.  
 Methods references and/or additional QA/QC information available on request.

## Certificate of Analysis

### Environment Testing

Client: Kollaard Associates Inc.  
 210 Prescott St., Box 189  
 Kemptonville, ON  
 K0G 1J0

Attention: Ms. Colleen Vermeersch  
 PO#:  
 Invoice to: Kollaard Associates Inc.

Report Number: 1952974  
 Date Submitted: 2021-05-11  
 Date Reported: 2021-05-19  
 Project: 210064  
 COC #: 873496

### QC Summary

QC Summary					
	Analyte		Blank	QC % Rec	QC Limits
Run No	400734	Analysis/Extraction Date	2021-05-18	Analyst	AET
Method	C SM2340B				
	Hardness as CaCO <sub>3</sub>				
	Ion Balance				
	TDS (COND - CALC)				
Run No	400761	Analysis/Extraction Date	2021-05-18	Analyst	AET
Method	C SM4500-S2-D				
	S2-		<0.01 mg/L		80-120
Run No	400865	Analysis/Extraction Date	2021-05-18	Analyst	AET
Method	SUBCONTRACT-A				
	Phenols		<0.0010 mg/L	103	
	Tannin & Lignin		<0.10 mg/L	100	

**Guideline = ODWSOG** \* = Guideline Exceedence

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Results relate only to the parameters tested on the samples submitted.  
 Methods references and/or additional QA/QC information available on request.

## Environment Testing

Client: Kollaard Associates Inc.  
210 Prescott St., Box 189  
Kempville, ON  
K0G 1J0  
Attention: Ms. Colleen Vermeersch  
PO#:  
Invoice to: Kollaard Associates Inc.

Report Number: 1952957  
Date Submitted: 2021-05-11  
Date Reported: 2021-05-13  
Project: 210064  
COC #: 873496

Page 1 of 2

Dear Colleen Vermeersch:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

Steven

Tosh

2021.05.13

11:33:30

-04'00'

APPROVAL:

Steven Tosh, Operations Manager

All analysis is completed at Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) unless otherwise indicated.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on the scope of accreditation. The scope is available at: <http://www.cala.ca/scopes/2602.pdf>.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is licensed by the Ontario Ministry of the Environment, Conservation, and Parks (MECP) for specific tests in drinking water (license #2318). A copy of the license is available upon request.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by the Ontario Ministry of Agriculture, Food, and Rural Affairs for specific tests in agricultural soils.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes only). Eurofins recommends consulting the official provincial or federal guideline as required. Unless otherwise stated, measurement uncertainty is not taken into account when determining guideline or regulatory exceedances.



## Certificate of Analysis

### Environment Testing

Client: Kollaard Associates Inc.  
210 Prescott St., Box 189  
Kempville, ON  
K0G 1J0  
Attention: Ms. Colleen Vermeersch  
PO#:  
Invoice to:

Kollaard Associates Inc.

Report Number: 1952957  
Date Submitted: 2021-05-11  
Date Reported: 2021-05-13  
Project: 210064  
COC #: 873496

Group	Analyte	MRL	Units	Guideline	
Microbiology	Escherichia Coli	0	ct/100mL	MAC 0	0
	Faecal Coliforms	0	ct/100mL		0
	Heterotrophic Plate Count	0	ct/1mL		5
	Total Coliforms	0	ct/100mL	MAC 0	0

Lab I.D.	1556225	Water	1556226
Sample Matrix			
Sample Type			
Sampling Date	2021-05-10		
Sample I.D.	TW2-3 hrs	TW2-6 hrs	

**Guideline = ODWSOG**

\* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.

**Analytical Method: AMBCOLM1**  
additional QA/QC information available on request

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

## Environment Testing

Client: Kollaard Associates Inc.  
210 Prescott St., Box 189  
Kempville, ON  
K0G 1J0

Attention: Ms. Colleen Vermeersch  
PO#:  
Invoice to: Kollaard Associates Inc.

Report Number: 1952723  
Date Submitted: 2021-05-06  
Date Reported: 2021-05-13  
Project: 210064  
COC #: 873355

Page 1 of 8

Dear Colleen Vermeersch:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:



Addrine Thomas  
2021.05.13  
15:56:08 -04:00'

APPROVAL:



Addrine Thomas, Inorganics Supervisor

All analysis is completed at Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) unless otherwise indicated.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on the scope of accreditation. The scope is available at: <http://www.cal.ca/scopes/2602.pdf>.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is licensed by the Ontario Ministry of the Environment, Conservation, and Parks (MECP) for specific tests in drinking water (license #2318). A copy of the license is available upon request.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by the Ontario Ministry of Agriculture, Food, and Rural Affairs for specific tests in agricultural soils.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes only). Eurofins recommends consulting the official provincial or federal guideline as required. Unless otherwise stated, measurement uncertainty is not taken into account when determining guideline or regulatory exceedances.

## Certificate of Analysis

### **Environment Testing**

Client: Kollaard Associates Inc.  
210 Prescott St., Box 189  
Kemptville, ON  
K0G 1J0

Attention: Ms. Colleen Vermeersch  
PO#:  
Invoice to: Kollaard Associates Inc.

Report Number: 1952723  
Date Submitted: 2021-05-06  
Date Reported: 2021-05-13  
Project: 210064  
COC #: 873355

Group	Analyte	MRL	Units	Guideline	
Anions	Cl	1	mg/L	AO 250	167
	F	0.10	mg/L	MAC 1.5	0.17
	N-NO2	0.10	mg/L	MAC 1.0	<0.10
	N-NO3	0.10	mg/L	MAC 10.0	<0.10
	SO4	1	mg/L	AO 500	49
General Chemistry	Alkalinity as CaCO3	5	mg/L	OG 500	154
	Colour	2	TCU		<2
	Conductivity	5	uS/cm	AO 5	879
	DOC	0.5	mg/L		1.9
	pH	1.00		6.5-8.5	8.01
	S2-	0.01	mg/L	AO 0.05	<0.01
	TDS (COND - CALC)	1	mg/L	AO 500	<b>571*</b>
	Turbidity	0.1	NTU	AO 5.0	3.2
Hardness	Hardness as CaCO3	1	mg/L	OG 100	<b>298*</b>
Indices/Calc	Ion Balance	0.01			<b>310*</b>
Metals	Al	0.01	mg/L	OG 0.1	1.00
	As	0.001	mg/L	IMAC 0.01	<0.01
	B	0.01	mg/L	IMAC 5.0	0.06
	Ba	0.01	mg/L	MAC 1.0	0.32
	Ca	1	mg/L		65
	Cd	0.0001	mg/L	MAC 0.005	<0.0001
	Co	0.0002	mg/L		<0.0002
	Cr	0.001	mg/L	MAC 0.05	<0.001
	Cu	0.001	mg/L	AO 1.0	<0.001
	Fe	0.03	mg/L	AO 0.3	<b>0.54*</b>
					0.21

**Guideline = ODWSOG** \* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.  
Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

## Certificate of Analysis

### Environment Testing

Client: Kollaard Associates Inc.  
210 Prescott St., Box 189  
Kempville, ON  
K0G 1J0

Attention: Ms. Colleen Vermeersch  
PO#:  
Invoice to: Kollaard Associates Inc.

Report Number: 1952723  
Date Submitted: 2021-05-06  
Date Reported: 2021-05-13  
Project: 210064  
COC #: 873355

Group	Analyte	MRL	Units	Guideline	
Metals	Hg	0.0001	mg/L	MAC 0.001	<0.0001
	K	1	mg/L		4
	Mg	1	mg/L		34
	Mn	0.01	mg/L	AO 0.05	0.01
	Na	2	mg/L	AO 200	64
	Pb	0.001	mg/L	MAC 0.010	<0.001
	Sb	0.0005	mg/L	IMAC 0.006	<0.0005
	Se	0.001	mg/L	MAC 0.05	<0.001
	Sr	0.001	mg/L		0.677
	U	0.001	mg/L	MAC 0.02	<0.001
	V	0.001	mg/L		<0.001
	Zn	0.01	mg/L	AO 5.0	<0.01
Nutrients	N-NH <sub>3</sub>	0.010	mg/L		0.171
	Total Kjeldahl Nitrogen	0.100	mg/L		0.184
Subcontract	Phenols	0.001	mg/L	<0.0010	<0.0010
	Tannin & Lignin	0.1	mg/L		0.7
					0.6

**Guideline = ODWSOG** \* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.  
Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

## Certificate of Analysis

### Environment Testing

Client: Kollaard Associates Inc.  
 210 Prescott St., Box 189  
 Kemptonville, ON  
 K0G 1J0

Attention: PO#:  
 Ms. Colleen Vermeersch  
 Invoice to: Kollaard Associates Inc.

Report Number: 1952723  
 Date Submitted: 2021-05-06  
 Date Reported: 2021-05-13  
 Project: 210064  
 COC #: 873355

### QC Summary

Analyte	Blank	QC % Rec	QC Limits
Run No 400186	Analysis/Extraction Date 2021-05-07	Analyst K B	
Method C SM2130B			
Turbidity	<0.1 NTU	101	70-130
Run No 400216	Analysis/Extraction Date 2021-05-07	Analyst AET	
Method C SM4500-S2-D			
S2-	<0.01 mg/L	82	80-120
Run No 400254	Analysis/Extraction Date 2021-05-07	Analyst SKH	
Method EPA 351.2			
Total Kjeldahl Nitrogen	<0.100 mg/L	101	70-130
Run No 400261	Analysis/Extraction Date 2021-05-07	Analyst SWS	
Method SM 5310B			
DOC	<0.5 mg/L	89	80-120
Run No 400292	Analysis/Extraction Date 2021-05-10	Analyst Z S	
Method M SM3120B-3500C			
Calcium	<1 mg/L	105	90-110
Potassium	<1 mg/L	106	87-113
Magnesium	<1 mg/L	103	76-124
Sodium	<2 mg/L	106	82-118

**Guideline = ODWSOG** \* = Guideline Exceedence

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Results relate only to the parameters tested on the samples submitted.  
 Methods references and/or additional QA/QC information available on request.

**Environment Testing**

Client: Kollaard Associates Inc.  
 210 Prescott St., Box 189  
 Kemptonville, ON  
 K0G 1J0

Attention: PO#:  
 Ms. Colleen Vermeersch  
 Invoice to: Kollaard Associates Inc.

Report Number: 1952723  
 Date Submitted: 2021-05-06  
 Date Reported: 2021-05-13  
 Project: 210064  
 COC #: 873355

**QC Summary**

Analyte		Blank	QC % Rec	QC Limits
Run No	400294	Analysis/Extraction Date	2021-05-10	Analyst SKH
Method	EPA 200.8			
Aluminum		<0.01 mg/L	100	80-120
Arsenic		<0.001 mg/L	97	80-120
Boron (total)		<0.01 mg/L	103	80-120
Cobalt		<0.0002 mg/L	100	80-120
Chromium Total		<0.001 mg/L	99	80-120
Copper		<0.001 mg/L	100	80-120
Iron		<0.03 mg/L	96	80-120
Manganese		<0.01 mg/L	98	80-120
Selenium		<0.001 mg/L	92	80-120
Vanadium		<0.001 mg/L	100	80-120
Zinc		<0.01 mg/L	99	80-120
Run No	400341	Analysis/Extraction Date	2021-05-10	Analyst SKH
Method	EPA 350.1			
N-NH3		<0.010 mg/L	108	80-120
Run No	400382	Analysis/Extraction Date	2021-05-11	Analyst K B
Method	C SM2120C			
Colour		<2 TCU	82	90-110

**Guideline = ODWSOG**
**\* = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.  
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

### Environment Testing

Client: Kollaard Associates Inc.  
210 Prescott St., Box 189  
Kempville, ON  
K0G 1J0

Attention:  
PO#:  
Invoice to:

Ms. Colleen Vermeersch  
Kollaard Associates Inc.

Report Number: 1952723  
Date Submitted: 2021-05-06  
Date Reported: 2021-05-13  
Project: 210064  
COC #: 873355

### **QC Summary**

Analyte		Blank	QC % Rec	QC Limits
Run No	400384	Analysis/Extraction Date	2021-05-11	Analyst SKH
Method	EPA 200.8			
Barium		<0.01 mg/L	94	80-120
Cadmium		<0.0001 mg/L	99	80-120
Mercury		<0.0001 mg/L	91	80-120
Lead		<0.001 mg/L	105	80-120
Antimony		<0.0005 mg/L	100	80-120
Strontrium		<0.001 mg/L	93	80-120
Uranium		<0.001 mg/L	105	80-120
Run No	400405	Analysis/Extraction Date	2021-05-11	Analyst SKH
Method	EPA 351.2			
Total Kjeldahl Nitrogen		<0.100 mg/L	130	70-130
Run No	400415	Analysis/Extraction Date	2021-05-12	Analyst AET
Method	SM 4110			
N-NO2		<0.10 mg/L	99	90-110
N-NO3		<0.10 mg/L	101	90-110
SO4		<1 mg/L	95	90-110
Run No	400418	Analysis/Extraction Date	2021-05-11	Analyst SWS
Method	C SM4500-FC			

**Guideline = ODWSOG**

\* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.  
Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

### Environment Testing

**Client:** Kollaard Associates Inc.  
 210 Prescott St., Box 189  
 Kemptonville, ON  
 K0G 1J0

**Attention:** Ms. Colleen Vermeersch  
**PO#:** PO#:  
**Invoice to:** Kollaard Associates Inc.

Report Number: 1952723  
 Date Submitted: 2021-05-06  
 Date Reported: 2021-05-13  
 Project: 210064  
 COC #: 873355

### **QC Summary**

Analyte	Blank	QC % Rec	QC Limits
F	<0.10 mg/L	94	90-110
<b>Run No</b> 400423	<b>Analysis/Extraction Date</b> 2021-05-10	<b>Analyst</b> AET	
<b>Method</b> SUBCONTRACT-A			
Phenols	<0.0010 mg/L	101	
Tannin & Lignin	<0.10 mg/L	100	
<b>Run No</b> 400441	<b>Analysis/Extraction Date</b> 2021-05-11	<b>Analyst</b> SWS	
<b>Method</b> C SM2510B			
Conductivity	<5 uS/cm	99	95-105
<b>Run No</b> 400442	<b>Analysis/Extraction Date</b> 2021-05-11	<b>Analyst</b> SWS	
<b>Method</b> SM2320,2510,4500H/F			
pH	5.85	100	90-110
<b>Run No</b> 400451	<b>Analysis/Extraction Date</b> 2021-05-11	<b>Analyst</b> SWS	
<b>Method</b> SM 2320B			
Alkalinity (CaCO3)	<5 mg/L	100	95-105
<b>Run No</b> 400525	<b>Analysis/Extraction Date</b> 2021-05-13	<b>Analyst</b> AET	
<b>Method</b> SM 4/110			
Chloride	<1 mg/L	100	90-110
<b>Run No</b> 400544	<b>Analysis/Extraction Date</b> 2021-05-13	<b>Analyst</b> AET	
<b>Method</b> C SM2340B			

**Guideline = ODWSOG**

\* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.  
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

**Environment Testing**

Client: Kollaard Associates Inc.  
210 Prescott St., Box 189  
Kemptville, ON  
K0G 1J0

Attention: Ms. Colleen Vermeersch  
PO#:  
Invoice to: Kollaard Associates Inc.

Report Number: 1952723  
Date Submitted: 2021-05-06  
Date Reported: 2021-05-13  
Project: 210064  
COC #: 873355

**QC Summary**

Analyte	Blank	QC % Rec	QC Limits
Hardness as CaCO <sub>3</sub>			
Ion Balance			
TDS (COND - CALC)			

**Guideline = ODWSOG****\* = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.  
Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

## Environment Testing

Client: Kollaard Associates Inc.  
210 Prescott St., Box 189  
Kempville, ON  
K0G 1J0  
Attention: Ms. Colleen Vermeersch  
PO#:  
Invoice to: Kollaard Associates Inc.

Report Number: 1952724  
Date Submitted: 2021-05-06  
Date Reported: 2021-05-09  
Project: 210064  
COC #: 873355

Page 1 of 2

Dear Colleen Vermeersch:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

Dragana  
*Dragana Dzeletovic*  
Dzeletovic 2021.05.09  
10:54:46 -04'00'  
APPROVAL: \_\_\_\_\_  
Dragana Dzeletovic-Andric, Microbiology Team Lead

All analysis is completed at Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) unless otherwise indicated.  
Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on the scope of accreditation. The scope is available at: <http://www.cala.ca/scopes/2602.pdf>.  
Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is licensed by the Ontario Ministry of the Environment, Conservation, and Parks (MECP) for specific tests in drinking water (license #2318). A copy of the license is available upon request.  
Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by the Ontario Ministry of Agriculture, Food, and Rural Affairs for specific tests in agricultural soils.  
Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes only). Eurofins recommends consulting the official provincial or federal guideline as required. Unless otherwise stated, measurement uncertainty is not taken into account when determining guideline or regulatory exceedances.



## Certificate of Analysis

### Environment Testing

Client: Kollaard Associates Inc.  
210 Prescott St., Box 189  
Kempville, ON  
K0G 1J0  
Attention: Ms. Colleen Vermeersch  
PO#:  
Invoice to:

Kollaard Associates Inc.

Report Number: 1952724  
Date Submitted: 2021-05-06  
Date Reported: 2021-05-09  
Project: 210064  
COC #: 873355

Group	Analyte	MRL	Units	Guideline	
Microbiology	Escherichia Coli	0	ct/100mL	MAC 0	0
	Faecal Coliforms	0	ct/100mL		0
	Heterotrophic Plate Count	0	ct/1mL		1
	Total Coliforms	0	ct/100mL	MAC 0	0

Lab I.D.	1555613	Water	1555614
Sample Matrix			
Sample Type			
Sampling Date	2021-05-05		
Sample I.D.	TW#3-3 hr		

**Guideline = ODWSOG**

\* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.

**Analytical Method: AMBCOLM1**  
additional QA/QC information available on request

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

## Certificate of Analysis

Client: Kollaard Associates Inc.  
210 Prescott St., Box 189  
Kemptville, ON  
K0G 1J0  
Attention: Ms. Colleen Vermeersch  
PO#:  
Invoice to: Kollaard Associates Inc.

Report Number: 1972763  
Date Submitted: 2022-03-04  
Date Reported: 2022-03-10  
Project:  
COC #: 886843

Page 1 of 8

**Dear Colleen Vermeersch:**

**Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).**

Report Comments:

Charlie  
Long Qu  
2022.03.1  
0 16:40:36  
-05'00'  


APPROVAL:

Long Qu, Organics Supervisor

All analysis is completed at Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) unless otherwise indicated.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on the scope of accreditation. The scope is available at: <http://www.cala.ca/scopes/2602.pdf>.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is licensed by the Ontario Ministry of the Environment, Conservation, and Parks (MECP) for specific tests in drinking water (license #2318). A copy of the license is available upon request.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by the Ontario Ministry of Agriculture, Food, and Rural Affairs for specific tests in agricultural soils.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required. Unless otherwise stated, measurement uncertainty is not taken into account when determining guideline or regulatory exceedances.

# Certificate of Analysis

Client: Kollaard Associates Inc.  
 210 Prescott St., Box 189  
 Kemptville, ON  
 K0G 1J0  
 Attention: Ms. Colleen Vermeersch  
 PO#:  
 Invoice to: Kollaard Associates Inc.

Report Number: 1972763  
 Date Submitted: 2022-03-04  
 Date Reported: 2022-03-10  
 Project:  
 COC #: 886843

				Lab I.D. Sample Matrix Sample Type Sampling Date Sample I.D.	1613062 Water 2022-03-04 TW1	1613063 Water 2022-03-04 TW2	1613064 Water 2022-03-04 TW3
Group	Analyte	MRL	Units	Guideline			
Hydrocarbons	F1 (C6-C10)	20	ug/L	<20	<20	<20	<20
	F1-BTEX (C6-C10)	20	ug/L	<20	<20	<20	<20
	F2 (C10-C16)	20	ug/L	<20	<20	<20	<20
	F3 (C16-C34)	50	ug/L	<50	<50	<50	<50
	F4 (C34-C50)	50	ug/L	<50	<50	<50	<50
PHC Surrogate	Alpha-androstrane	0	%	87	88	86	
VOCs Surrogates	1,2-dichloroethane-d4	0	%	107	109	116	
	4-bromofluorobenzene	0	%	92	91	91	
	Toluene-d8	0	%	101	101	99	
Volatile	1,1,1,2-tetrachloroethane	0.5	ug/L	<0.5	<0.5	<0.5	<0.5
	1,1,1-trichloroethane	0.4	ug/L	<0.4	<0.4	<0.4	<0.4
	1,1,2,2-tetrachloroethane	0.5	ug/L	<0.5	<0.5	<0.5	<0.5
	1,1,2-trichloroethane	0.4	ug/L	<0.4	<0.4	<0.4	<0.4
	1,1-dichloroethane	0.4	ug/L	<0.4	<0.4	<0.4	<0.4
	1,1-dichloroethylene	0.5	ug/L	MAC 14	<0.5	<0.5	<0.5
	1,2-dichlorobenzene	0.4	ug/L	MAC 200	<0.4	<0.4	<0.4
	1,2-dichloroethane	0.2	ug/L	IMAC 5	<0.2	<0.2	<0.2
	1,2-dichloropropane	0.5	ug/L		<0.5	<0.5	<0.5
	1,3,5-trimethylbenzene	0.3	ug/L		<0.3	<0.3	<0.3
	1,3-dichlorobenzene	0.4	ug/L		<0.4	<0.4	<0.4
	1,3-Dichloropropylene (cis+trans)	0.3	ug/L		<0.3	<0.3	<0.3
	1,4-dichlorobenzene	0.4	ug/L	MAC 5	<0.4	<0.4	<0.4
	Acetone	30	ug/L		<30	<30	<30
	Benzene	0.5	ug/L	MAC 1	<0.5	<0.5	<0.5
	Bromodichloromethane	0.3	ug/L		<0.3	<0.3	<0.3

**Guideline = ODWSOG**

**\* = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.  
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

# Certificate of Analysis

Client: Kollaard Associates Inc.  
 210 Prescott St., Box 189  
 Kemptville, ON  
 K0G 1J0  
 Attention: Ms. Colleen Vermeersch  
 PO#:  
 Invoice to: Kollaard Associates Inc.

Report Number: 1972763  
 Date Submitted: 2022-03-04  
 Date Reported: 2022-03-10  
 Project:  
 COC #: 886843

Group	Analyte	MRL	Units	Guideline	Lab I.D.	1613062	1613063	1613064
					Sample Matrix	Water	Water	Water
Volatile	Bromoform	0.4	ug/L		<0.4	<0.4	<0.4	<0.4
	Bromomethane	0.5	ug/L		<0.5	<0.5	<0.5	<0.5
	c-1,2-Dichloroethylene	0.4	ug/L		<0.4	<0.4	<0.4	<0.4
	c-1,3-Dichloropropylene	0.2	ug/L		<0.2	<0.2	<0.2	<0.2
	Carbon Tetrachloride	0.2	ug/L	MAC 2	<0.2	<0.2	<0.2	<0.2
	Chloroethane	0.2	ug/L		<0.2	<0.2	<0.2	<0.2
	Chloroform	0.5	ug/L		<0.5	<0.5	<0.5	<0.5
	Dibromochloromethane	0.3	ug/L		<0.3	<0.3	<0.3	<0.3
	Dichlorodifluoromethane	0.5	ug/L		<0.5	<0.5	<0.5	<0.5
	Dichloromethane	4.0	ug/L	MAC 50	<4.0	<4.0	<4.0	<4.0
	Ethylbenzene	0.5	ug/L	MAC 140	<0.5	<0.5	<0.5	<0.5
	Ethylene Dibromide	0.2	ug/L		<0.2	<0.2	<0.2	<0.2
	Hexane	5	ug/L		<5	<5	<5	<5
	m/p-xylene	0.4	ug/L		<0.4	<0.4	<0.4	<0.4
	Methyl Ethyl Ketone (MEK)	10	ug/L		<10	<10	<10	<10
	Methyl Isobutyl Ketone (MIBK)	10	ug/L		<10	<10	<10	<10
	Methyl Tert Butyl Ether (MTBE)	2	ug/L	AO 15	<2	<2	<2	<2
	Monochlorobenzene	0.5	ug/L	MAC 80	<0.5	<0.5	<0.5	<0.5
	o-xylene	0.4	ug/L		<0.4	<0.4	<0.4	<0.4
	Styrene	0.5	ug/L		<0.5	<0.5	<0.5	<0.5
	t-1,2-Dichloroethylene	0.4	ug/L		<0.4	<0.4	<0.4	<0.4
	t-1,3-Dichloropropylene	0.2	ug/L		<0.2	<0.2	<0.2	<0.2
	Tetrachloroethylene	0.3	ug/L	MAC 10	<0.3	<0.3	<0.3	<0.3
	Toluene	0.4	ug/L	MAC 60	<0.4	<0.4	<0.4	<0.4
	Trichloroethylene	0.3	ug/L	MAC 5	<0.3	<0.3	<0.3	<0.3

**Guideline = ODWSOG**

**\* = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.  
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

## Certificate of Analysis

Client: Kollaard Associates Inc.  
 210 Prescott St., Box 189  
 Kemptville, ON  
 K0G 1J0  
 Attention: Ms. Colleen Vermeersch  
 PO#:  
 Invoice to: Kollaard Associates Inc.

Report Number: 1972763  
 Date Submitted: 2022-03-04  
 Date Reported: 2022-03-10  
 Project:  
 COC #: 886843

				Lab I.D. Sample Matrix Sample Type Sampling Date Sample I.D.	1613062 Water 2022-03-04 TW1	1613063 Water 2022-03-04 TW2	1613064 Water 2022-03-04 TW3
Group	Analyte	MRL	Units	Guideline			
Volatile	Trichlorofluoromethane	0.5	ug/L		<0.5	<0.5	<0.5
	Vinyl Chloride	0.2	ug/L	MAC 1	<0.2	<0.2	<0.2
	Xylene; total	0.5	ug/L	MAC 90	<0.5	<0.5	<0.5

**Guideline = ODWSOG**

**\* = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.  
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Kollaard Associates Inc.  
 210 Prescott St., Box 189  
 Kemptville, ON  
 K0G 1J0  
 Attention: Ms. Colleen Vermeersch  
 PO#:  
 Invoice to: Kollaard Associates Inc.

Report Number: 1972763  
 Date Submitted: 2022-03-04  
 Date Reported: 2022-03-10  
 Project:  
 COC #: 886843

### **QC Summary**

Analyte	Blank	QC % Rec	QC Limits
Run No 418252	Analysis/Extraction Date 2022-03-07	Analyst YH	
Method EPA 8260			
Tetrachloroethane, 1,1,1,2-	<0.5 ug/L	102	60-130
Trichloroethane, 1,1,1-	<0.4 ug/L	94	60-130
Tetrachloroethane, 1,1,2,2-	<0.5 ug/L	104	60-130
Trichloroethane, 1,1,2-	<0.4 ug/L	94	60-130
Dichloroethane, 1,1-	<0.4 ug/L	104	60-130
Dichloroethylene, 1,1-	<0.5 ug/L	89	60-130
Dichlorobenzene, 1,2-	<0.4 ug/L	102	60-130
Dichloroethane, 1,2-	<0.2 ug/L	96	60-130
Dichloropropane, 1,2-	<0.5 ug/L	98	60-130
1,3,5-trimethylbenzene	<0.3 ug/L	104	60-130
Dichlorobenzene, 1,3-	<0.4 ug/L	103	60-130
Dichloropropene, 1,3-	<0.3 ug/L		
Dichlorobenzene, 1,4-	<0.4 ug/L	105	60-130
Acetone	<30 ug/L		60-130
Benzene	<0.5 ug/L	98	60-130
Bromodichloromethane	<0.3 ug/L	91	60-130

**Guideline = ODWSOG**

**\* = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.  
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Kollaard Associates Inc.  
 210 Prescott St., Box 189  
 Kemptville, ON  
 K0G 1J0  
 Attention: Ms. Colleen Vermeersch  
 PO#:  
 Invoice to: Kollaard Associates Inc.

Report Number: 1972763  
 Date Submitted: 2022-03-04  
 Date Reported: 2022-03-10  
 Project:  
 COC #: 886843

### **QC Summary**

Analyte	Blank	QC % Rec	QC Limits
Bromoform	<0.4 ug/L	91	60-130
Bromomethane	<0.5 ug/L	118	60-130
Dichloroethylene, 1,2-cis-	<0.4 ug/L	93	60-130
Dichloropropene,1,3-cis-	<0.2 ug/L	82	60-130
Carbon Tetrachloride	<0.2 ug/L	98	60-130
Chloroethane	<0.2 ug/L	92	60-130
Chloroform	<0.5 ug/L	100	60-130
Dibromochloromethane	<0.3 ug/L	83	60-130
Dichlorodifluoromethane	<0.5 ug/L	115	60-130
Methylene Chloride	<4.0 ug/L	115	60-130
Ethylbenzene	<0.5 ug/L	100	60-130
Ethylene dibromide	<0.2 ug/L	83	60-130
Hexane (n)	<5 ug/L	110	60-130
m/p-xylene	<0.4 ug/L	105	60-130
Methyl Ethyl Ketone	<10 ug/L		60-130
Methyl Isobutyl Ketone	<10 ug/L		60-130
Methyl tert-Butyl Ether (MTBE)	<2 ug/L	100	60-130
Chlorobenzene	<0.5 ug/L	96	60-130

**Guideline = ODWSOG**

**\* = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.  
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

## Certificate of Analysis

Client: Kollaard Associates Inc.  
 210 Prescott St., Box 189  
 Kemptville, ON  
 K0G 1J0  
 Attention: Ms. Colleen Vermeersch  
 PO#:  
 Invoice to: Kollaard Associates Inc.

Report Number: 1972763  
 Date Submitted: 2022-03-04  
 Date Reported: 2022-03-10  
 Project:  
 COC #: 886843

### **QC Summary**

Analyte	Blank	QC % Rec	QC Limits
o-xylene	<0.4 ug/L	94	60-130
Styrene	<0.5 ug/L	92	60-130
Dichloroethylene, 1,2-trans-	<0.4 ug/L	114	60-130
Dichloropropene,1,3-trans-	<0.2 ug/L	86	60-130
Tetrachloroethylene	<0.3 ug/L	91	60-130
Toluene	<0.4 ug/L	95	60-130
Trichloroethylene	<0.3 ug/L	92	60-130
Trichlorofluoromethane	<0.5 ug/L	101	60-130
Vinyl Chloride	<0.2 ug/L	91	60-130
<b>Run No</b> 418258 <b>Analysis/Extraction Date</b> 2022-03-09 <b>Analyst</b> YH			
<b>Method</b> CCME O.Reg 153/04			
Petroleum Hydrocarbons F1	<20 ug/L	100	60-140
<b>Run No</b> 418262 <b>Analysis/Extraction Date</b> 2022-03-09 <b>Analyst</b> YH			
<b>Method</b> EPA 8260			
Xylene Mixture			
<b>Run No</b> 418263 <b>Analysis/Extraction Date</b> 2022-03-09 <b>Analyst</b> YH			
<b>Method</b> CCME O.Reg 153/04			
Petroleum Hydrocarbons F1-BTEX			

**Guideline = ODWSOG**

**\* = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.  
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

## Certificate of Analysis

Client: Kollaard Associates Inc.  
 210 Prescott St., Box 189  
 Kemptville, ON  
 K0G 1J0  
 Attention: Ms. Colleen Vermeersch  
 PO#:  
 Invoice to: Kollaard Associates Inc.

Report Number: 1972763  
 Date Submitted: 2022-03-04  
 Date Reported: 2022-03-10  
 Project:  
 COC #: 886843

### ***QC Summary***

Analyte	Blank	QC % Rec	QC Limits
Run No 418303	Analysis/Extraction Date 2022-03-10	Analyst R G	
Method CCME O.Reg 153/04			
Petroleum Hydrocarbons F2	<20 ug/L	88	60-140
Petroleum Hydrocarbons F3	<50 ug/L	88	60-140
Petroleum Hydrocarbons F4	<50 ug/L	88	60-140

**Guideline = ODWSOG**

**\* = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.  
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range



Crestview Innovations Inc.  
May 10, 2023

**Hydrogeological Investigation and Terrain Evaluation**

3200 Reids Lane, Ottawa, Ontario  
210064

**ATTACHMENT G**

**RESULTS OF LABORATORY TESTING OF EXISTING NEIGHBOURING WELL WATER  
SAMPLES**

## Environment Testing

Client: Kollaard Associates Inc.  
210 Prescott St., Box 189  
Kempville, ON  
K0G 1J0

Attention: Ms. Colleen Vermeersch  
PO#:  
Invoice to: Kollaard Associates Inc.

Dear Colleen Vermeersch:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

Addrline  
  
Thomas  
2021.06.01  
16:17:46 -04'00'

APPROVAL:

Addrline Thomas, Inorganics Supervisor

All analysis is completed at Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) unless otherwise indicated. Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on the scope of accreditation. The scope is available at: <http://www.calacalascopes/2602.pdf>. Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is licensed by the Ontario Ministry of the Environment, Conservation, and Parks (MECP) for specific tests in drinking water (license #2318). A copy of the license is available upon request. Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by the Ontario Ministry of Agriculture, Food, and Rural Affairs for specific tests in agricultural soils. Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes only). Eurofins recommends consulting the official provincial or federal guideline as required. Unless otherwise stated, measurement uncertainty is not taken into account when determining guideline or regulatory exceedances.

Report Number: 1953824  
Date Submitted: 2021-05-21  
Date Reported: 2021-06-01  
Project: 210064  
COC #: 106009

Page 1 of 6

## Certificate of Analysis

### **Environment Testing**

Client: Kollaard Associates Inc.  
 210 Prescott St., Box 189  
 Kemptonville, ON  
 K0G 1J0

Attention: Ms. Colleen Vermeersch  
 PO#:  
 Invoice to: Kollaard Associates Inc.

Report Number: 1953824  
 Date Submitted: 2021-05-21  
 Date Reported: 2021-06-01  
 Project: 210064  
 COC #: 106009

Group	Analyte	MRL	Units	Guideline
Anions	Cl	1	mg/L	AO 250
	F	0.10	mg/L	MAC 1.5
	SO4	1	mg/L	AO 500
General Chemistry	Alkalinity as CaCO3	5	mg/L	OG 30-500
	Colour (True)	2	TCU	132
	Conductivity	5	µS/cm	2
	DOC	0.5	mg/L	AO 5
	pH	1.00		6.5-8.5
	S2-	0.01	mg/L	AO 0.05
	TDS (COND - CALC)	1	mg/L	1.22*
	Turbidity	0.1	NTU	AO 5
Hardness	Hardness as CaCO3	1	mg/L	OG 80-100
Indices/Calc	Ion Balance	0.01		161*
Metals	Ca	1	mg/L	560
	Fe	0.03	mg/L	AO 0.3
	K	1	mg/L	2.4
	Mg	1	mg/L	AO 0.05
	Mn	0.01	mg/L	AO 200
	Na	2	mg/L	78
Nutrients	N-NH3	0.010	mg/L	0.88
	Total Kjeldahl Nitrogen	0.100	mg/L	30
Others	N-NO2	0.10	mg/L	0.20
	N-NO3	0.10	mg/L	9
Subcontract	Phenols	0.001	mg/L	21
	Tannin & Lignin	0.1	mg/L	0.01
				0.387
				0.503
				<0.10
				<0.10
				<0.0010
				<0.10

**Guideline = ODWSOG**

\* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.  
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

**Environment Testing**

Client: Kollaard Associates Inc.  
 210 Prescott St., Box 189  
 Kemptonville, ON  
 K0G 1J0

Attention: PO#:  
 Ms. Colleen Vermeersch  
 Invoice to: Kollaard Associates Inc.

Report Number: 1953824  
 Date Submitted: 2021-05-21  
 Date Reported: 2021-06-01  
 Project: 210064  
 COC #: 106009

**QC Summary**

Analyte		Blank	QC % Rec	QC Limits
Run No	401175	Analysis/Extraction Date	2021-05-25	Analyst SWS
Method	C SM2/130B			
Turbidity		<0.1 NTU	100	70-130
Run No	401245	Analysis/Extraction Date	2021-05-26	Analyst SWS
Method	SM2320/2510,4500H/F			
Alkalinity (CaCO <sub>3</sub> )		<5 mg/L	103	90-110
Conductivity		<5 uS/cm	99	90-110
F		<0.10 mg/L	100	90-110
pH			99	90-110
Run No	401327	Analysis/Extraction Date	2021-05-27	Analyst AET
Method	C SM4500-S2-D			
S <sub>2-</sub>		<0.01 mg/L	98	80-120
Run No	401387	Analysis/Extraction Date	2021-05-27	Analyst SKH
Method	C SM4500-NO3-F			
N-NO <sub>2</sub>		<0.10 mg/L	94	
N-NO <sub>3</sub>		<0.10 mg/L	101	
Run No	401397	Analysis/Extraction Date	2021-05-28	Analyst SKH
Method	EPA 200.8			
Iron		<0.03 mg/L	105	80-120

**Guideline = ODWSOG**
**\* = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.  
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

## Certificate of Analysis

### Environment Testing

Client: Kollaard Associates Inc.  
210 Prescott St., Box 189  
Kemptville, ON  
K0G 1J0

Attention: PO#:  
Ms. Colleen Vermeersch  
Invoice to: Kollaard Associates Inc.

Report Number: 1953824  
Date Submitted: 2021-05-21  
Date Reported: 2021-06-01  
Project: 210064  
COC #: 106009

### QC Summary

Analyte	Blank	QC % Rec	QC Limits
Manganese	<0.01 mg/L	112	80-120
<b>Run No</b> 401388	<b>Analysis/Extraction Date</b> 2021-05-27	<b>Analyst</b> SKH	
<b>Method</b> EPA 351.2			
Total Kjeldahl Nitrogen	<0.100 mg/L	90	70-130
<b>Run No</b> 401411	<b>Analysis/Extraction Date</b> 2021-05-28	<b>Analyst</b> SWS	
<b>Method</b> C SM2120C			
Colour (True)	<2 TCU	98	90-110
<b>Run No</b> 401449	<b>Analysis/Extraction Date</b> 2021-05-28	<b>Analyst</b> Z S	
<b>Method</b> M SM3120B-3500C			
Calcium	<1 mg/L	104	90-110
Potassium	<1 mg/L	107	87-113
Magnesium	<1 mg/L	105	76-124
Sodium	<2 mg/L	109	82-118
<b>Run No</b> 401482	<b>Analysis/Extraction Date</b> 2021-05-31	<b>Analyst</b> SWS	
<b>Method</b> SM 5310B			
DOC	<0.5 mg/L	108	80-120
<b>Run No</b> 401484	<b>Analysis/Extraction Date</b> 2021-05-31	<b>Analyst</b> AET	
<b>Method</b> SM 4110			
SO4	2 mg/L	115	90-110

#### Guideline = ODWSOG

#### \* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.  
Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

**Environment Testing**

Client: Kollaard Associates Inc.  
 210 Prescott St., Box 189  
 Kemptonville, ON  
 K0G 1J0

Attention: Ms. Colleen Vermeersch  
 PO#:  
 Invoice to: Kollaard Associates Inc.

Report Number: 1953824  
 Date Submitted: 2021-05-21  
 Date Reported: 2021-06-01  
 Project: 210064  
 COC #: 106009

**QC Summary**

Analyte	Blank	QC % Rec	QC Limits
<b>Run No</b> 401528	Analysis/Extraction Date 2021-05-31	Analyst SKH	
<b>Method</b> EPA 350.1	<0.010 mg/L	108	80-120
<b>Run No</b> 401582	Analysis/Extraction Date 2021-05-28	Analyst AET	
<b>Method</b> SUBCONTRACT-A			
Phenols	<0.0010 mg/L	102	
Tannin & Lignin	<0.10 mg/L	106	
<b>Run No</b> 401632	Analysis/Extraction Date 2021-06-01	Analyst AX	
<b>Method</b> SM 4110	<5 mg/L		90-110
Chloride			
<b>Run No</b> 401654	Analysis/Extraction Date 2021-06-01	Analyst AET	
<b>Method</b> C SM2340B			
Hardness as CaCO <sub>3</sub>			
Ion Balance			
TDS (COND - CALC)			

**Guideline = ODWSOG**
**\* = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.  
 Methods references and/or additional Q/A/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range



## Certificate of Analysis

### Environment Testing

Client: Kollaard Associates Inc.  
210 Prescott St., Box 189  
Kempville, ON  
K0G 1J0

Attention: Ms. Colleen Vermeersch  
PO#:  
Invoice to: Kollaard Associates Inc.

Report Number: 1953824  
Date Submitted: 2021-05-21  
Date Reported: 2021-06-01  
Project: 210064  
COC #: 106009

### Sample Comment Summary

Sample ID: 1558614 5529 Osgoode Main Turbidity ran past holding time. The Ion Balance is outside Eurofins acceptable tolerance levels. All results have been confirmed.

#### **Guideline = ODWSOG**

\* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.  
Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

**Environment Testing**

Client: Kollaard Associates Inc.  
210 Prescott St., Box 189  
Kempville, ON  
K0G 1J0  
Attention: Ms. Colleen Vermeersch  
PO#:  
Invoice to: Kollaard Associates Inc.

Report Number: 1953822  
Date Submitted: 2021-05-21  
Date Reported: 2021-05-23  
Project: 210064  
COC #: 106009

Page 1 of 2

Dear Colleen Vermeersch:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

Dragana  
Dzeletovic  
*Dragana Dzeletovic* 2021.05.23  
10:47:43  
APPROVAL: \_\_\_\_\_  
-04'00'  
\_\_\_\_\_  
Dragana Dzeletovic-Andric, Microbiology Team Lead

All analysis is completed at Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) unless otherwise indicated.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on the scope of accreditation. The scope is available at: <http://www.cala.ca/scopes/2602.pdf>.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is licensed by the Ontario Ministry of the Environment, Conservation, and Parks (MECP) for specific tests in drinking water (license #2318). A copy of the license is available upon request.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by the Ontario Ministry of Agriculture, Food, and Rural Affairs for specific tests in agricultural soils.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes only). Eurofins recommends consulting the official provincial or federal guideline as required. Unless otherwise stated, measurement uncertainty is not taken into account when determining guideline or regulatory exceedances.



## Certificate of Analysis

### Environment Testing

Client: Kollaard Associates Inc.  
210 Prescott St., Box 189  
Kempville, ON  
K0G 1J0  
Attention: Ms. Colleen Vermeersch  
PO#:  
Invoice to:

Kollaard Associates Inc.

Report Number: 1953822  
Date Submitted: 2021-05-21  
Date Reported: 2021-05-23  
Project: 210064  
COC #: 106009

Group	Analyte	MRL	Units	Guideline
Microbiology	Escherichia Coli	0	ct/100mL	MAC 0
	Faecal Coliforms	0	ct/100mL	0
	Heterotrophic Plate Count	0	ct/1mL	10
	Total Coliforms	0	ct/100mL	MAC 0

Lab I.D.	1558612
Sample Matrix	Water
Sample Type	2021-05-21
Sampling Date	5529 Osgoode Main

**Guideline = ODWSOG**

\* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.

**Analytical Method: AMBCOLM1**  
additional QA/QC information available on request

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

## Environment Testing

Client: Kollaard Associates Inc.  
210 Prescott St., Box 189  
Kempville, ON  
K0G 1J0

Attention: Ms. Colleen Vermeersch  
PO#:  
Invoice to: Kollaard Associates Inc.

Report Number: 1953235  
Date Submitted: 2021-05-13  
Date Reported: 2021-05-20  
Project: 210064  
COC #: 873627

Page 1 of 5

Dear Colleen Vermeersch:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

Addrline  
  
Thomas  
2021.05.20  
16:02:46 -04'00'  
APPROVAL: \_\_\_\_\_  
Addrline Thomas, Inorganics Supervisor

All analysis is completed at Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) unless otherwise indicated.  
Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on the scope of accreditation. The scope is available at: <http://www.cal.ca/scopes/2602.pdf>.  
Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is licensed by the Ontario Ministry of the Environment, Conservation, and Parks (MECP) for specific tests in drinking water (license #2318). A copy of the license is available upon request.  
Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by the Ontario Ministry of Agriculture, Food, and Rural Affairs for specific tests in agricultural soils.  
Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes only). Eurofins recommends consulting the official provincial or federal guideline as required. Unless otherwise stated, measurement uncertainty is not taken into account when determining guideline or regulatory exceedances.

## Certificate of Analysis

### **Environment Testing**

Client: Kollaard Associates Inc.

210 Prescott St., Box 189  
Kempville, ON  
K0G 1J0

Attention: Ms. Colleen Vermeersch  
PO#:

Invoice to: Kollaard Associates Inc.

Report Number:  
1953235  
Date Submitted:  
2021-05-13  
Date Reported:  
2021-05-20  
Project:  
210064  
COC #:  
873627

Group	Analyte	MRL	Units	Guideline	
Anions	Cl	1	mg/L	AO 250	222
	F	0.10	mg/L	MAC 1.5	1.48
	N-NO2	0.10	mg/L	MAC 1.0	<0.50
	N-NO3	0.10	mg/L	MAC 10.0	<0.50
	SO4	1	mg/L	AO 500	46
General Chemistry	Alkalinity as CaCO3	5	mg/L	OG 500	172
	Colour	2	TCU		<2
	Conductivity	5	uS/cm	AO 5	187
	DOC	0.5	mg/L		
	pH	1.00		6.5-8.5	0.69
	S2-	0.01	mg/L	AO 0.05	<0.50
	TDS (COND - CALC)	1	mg/L	AO 500	2021-05-12
	Turbidity	0.1	NTU	AO 5.0	5560 Lombardy
Hardness	Hardness as CaCO3	1	mg/L	OG 100	1556917 Water
Indices/Calc	Ion Balance	0.01			1556918 Water
Metals	Ca	1	mg/L		1556919 Water
	Fe	0.03	mg/L	AO 0.3	2021-05-12
	K	1	mg/L		5560 Lombardy - treated
	Mg	1	mg/L		
	Mn	0.01	mg/L	AO 0.05	
	Na	2	mg/L	AO 200	
Nutrients	N-NH3	0.010	mg/L		
	Total Kjeldahl Nitrogen	0.100	mg/L		
Subcontract	Phenols	0.001	mg/L		
	Tannin & Lignin	0.1	mg/L		

**Guideline = ODWSOG**

\* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.  
Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

## Certificate of Analysis

### Environment Testing

Client: Kollaard Associates Inc.  
210 Prescott St., Box 189  
Kemptville, ON  
K0G 1J0

Attention: PO#:  
Ms. Colleen Vermeersch  
Invoice to: Kollaard Associates Inc.

Report Number: 1953235  
Date Submitted: 2021-05-13  
Date Reported: 2021-05-20  
Project: 210064  
COC #: 873627

### QC Summary

Analyte	Blank	QC % Rec	QC Limits
Run No 400541	Analysis/Extraction Date 2021-05-13	Analyst K B	
Method C SM2/130B	0.6 NTU	101	70-130
Turbidity			
Run No 400603	Analysis/Extraction Date 2021-05-14	Analyst SKH	
Method C SM2/120C	<2 TCU	102	90-110
Colour			
Run No 400654	Analysis/Extraction Date 2021-05-14	Analyst SKH	
Method EPA 200.8			
Iron	<0.03 mg/L	99	80-120
Manganese	<0.01 mg/L	100	80-120
Run No 4006666	Analysis/Extraction Date 2021-05-14	Analyst SWS	
Method SM 5310B			
DOC	<0.5 mg/L	89	80-120
Run No 400717	Analysis/Extraction Date 2021-05-17	Analyst SKH	
Method EPA 350.1			
N-NH3	<0.010 mg/L	99	80-120
Run No 400719	Analysis/Extraction Date 2021-05-17	Analyst SKH	
Method EPA 351.2			
Total Kjeldahl Nitrogen	<0.100 mg/L	102	70-130

**Guideline = ODWSOG**

\* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.  
Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

**Environment Testing**

Client: Kollaard Associates Inc.  
210 Prescott St., Box 189  
Kemptville, ON  
K0G 1J0

Attention: PO#:  
Invoice to: Ms. Colleen Vermeersch  
Kollaard Associates Inc.

Report Number: 1953235  
Date Submitted: 2021-05-13  
Date Reported: 2021-05-20  
Project: 210064  
COC #: 873627

**QC Summary**

Analyte	Blank	QC % Rec	QC Limits
<b>Run No</b> 400737 <b>Analysis/Extraction Date</b> 2021-05-18	<b>Analyst</b> Z S		
<b>Method</b> M SM3120B-3500C			
Calcium	<1 mg/L	100	90-110
Potassium	<1 mg/L	102	87-113
Magnesium	<1 mg/L	98	76-124
Sodium	<2 mg/L	105	82-118
<b>Run No</b> 400782 <b>Analysis/Extraction Date</b> 2021-05-17	<b>Analyst</b> SWS		
<b>Method</b> SM2320,2510,4500H/F			
Alkalinity (CaCO <sub>3</sub> )	<5 mg/L	97	90-110
Conductivity	<5 uS/cm	97	90-110
F	<0.10 mg/L	91	90-110
pH		100	90-110
<b>Run No</b> 400797 <b>Analysis/Extraction Date</b> 2021-05-19	<b>Analyst</b> AET		
<b>Method</b> SM 4110			
Chloride	<5 mg/L		90-110
N-NO <sub>2</sub>	<0.50 mg/L	98	90-110
N-NO <sub>3</sub>	<0.50 mg/L	105	90-110
SO <sub>4</sub>	<5 mg/L	100	90-110

**Guideline = ODWSOG** \* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.  
Methods references and/or additional Q/A/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

## Certificate of Analysis

### Environment Testing

Client: Kollaard Associates Inc.  
 210 Prescott St., Box 189  
 Kemptonville, ON  
 K0G 1J0

Attention: Ms. Colleen Vermeersch  
 PO#:  
 Invoice to: Kollaard Associates Inc.

Report Number: 1953235  
 Date Submitted: 2021-05-13  
 Date Reported: 2021-05-20  
 Project: 210064  
 COC #: 873627

### QC Summary

QC Summary					
	Analyte		Blank	QC % Rec	QC Limits
Run No	400811	Analysis/Extraction Date	2021-05-19	Analyst	AET
Method	C SM2340B				
	Hardness as CaCO <sub>3</sub>				
	Ion Balance				
	TDS (COND - CALC)				
Run No	400865	Analysis/Extraction Date	2021-05-14	Analyst	AET
Method	SUBCONTRACT-A				
	Phenols	<0.0010 mg/L		98	
	Tannin & Lignin	<0.10 mg/L		103	
Run No	400982	Analysis/Extraction Date	2021-05-20	Analyst	AET
Method	C SM4500-S2-D				
	S2-	<0.01 mg/L		104	80-120

**Guideline = ODWSOG** \* = Guideline Exceedence

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Results relate only to the parameters tested on the samples submitted.  
 Methods references and/or additional Q/A/QC information available on request.

**Environment Testing**

Client: Kollaard Associates Inc.  
210 Prescott St., Box 189  
Kempville, ON  
K0G 1J0  
Attention: Ms. Colleen Vermeersch  
PO#:  
Invoice to: Kollaard Associates Inc.

Report Number: 1953220  
Date Submitted: 2021-05-13  
Date Reported: 2021-05-16  
Project: 210064  
COC #: 873627

Page 1 of 2

Dear Colleen Vermeersch:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

Dragana  
Dzeletovic  
*Dragana Dzeletovic* 2021.05.16  
08:34:53  
-04'00'  
APPROVAL: \_\_\_\_\_  
Dragana Dzeletovic-Andric, Microbiology Team Lead

All analysis is completed at Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) unless otherwise indicated.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on the scope of accreditation. The scope is available at: <http://www.cala.ca/scopes/2602.pdf>.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is licensed by the Ontario Ministry of the Environment, Conservation, and Parks (MECP) for specific tests in drinking water (license #2318). A copy of the license is available upon request.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by the Ontario Ministry of Agriculture, Food, and Rural Affairs for specific tests in agricultural soils.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes only). Eurofins recommends consulting the official provincial or federal guideline as required. Unless otherwise stated, measurement uncertainty is not taken into account when determining guideline or regulatory exceedances.



## Certificate of Analysis

### Environment Testing

Client: Kollaard Associates Inc.  
210 Prescott St., Box 189  
Kempville, ON  
K0G 1J0  
Attention: Ms. Colleen Vermeersch  
PO#:  
Invoice to:

Kollaard Associates Inc.

Report Number: 1953220  
Date Submitted: 2021-05-13  
Date Reported: 2021-05-16  
Project: 210064  
COC #: 873627

Group	Analyte	MRL	Units	Guideline	
Microbiology	Escherichia Coli	0	ct/100mL	MAC 0	0
	Faecal Coliforms	0	ct/100mL		0
	Heterotrophic Plate Count	0	ct/1mL		197
	Total Coliforms	0	ct/100mL	MAC 0	0

Lab I.D.	1556876	Water	1556877	Water
Sample Matrix				2021-05-12
Sample Type				5560 Lombardy

**Guideline = ODWSOG**

\* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.

**Analytical Method: AMBCOLM1**  
additional QA/QC information available on request

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Certificate of Analysis

Client: Kollaard Associates Inc.  
210 Prescott St., Box 189  
Kemptville, ON  
K0G 1J0

Attention: Ms. Colleen Vermeersch  
PO#:  
Invoice to: Kollaard Associates Inc.

Report Number: 1977214  
Date Submitted: 2022-05-12  
Date Reported: 2022-05-19  
Project: 210064  
COC #: 890555

Page 1 of 4

**Dear Colleen Vermeersch:**

**Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).**

Report Comments:

Emma-  
Dawn  
Ferguson  
2022.05.19  
15:49:22  
-04'00'



APPROVAL:

\_\_\_\_\_  
Emma-Dawn Ferguson, Chemist

All analysis is completed at Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) unless otherwise indicated.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on the scope of accreditation. The scope is available at: <http://www.cala.ca/scopes/2602.pdf>.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is licensed by the Ontario Ministry of the Environment, Conservation, and Parks (MECP) for specific tests in drinking water (license #2318). A copy of the license is available upon request.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by the Ontario Ministry of Agriculture, Food, and Rural Affairs for specific tests in agricultural soils.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required. Unless otherwise stated, measurement uncertainty is not taken into account when determining guideline or regulatory exceedances.

## Certificate of Analysis

Client: Kollaard Associates Inc.  
 210 Prescott St., Box 189  
 Kemptville, ON  
 K0G 1J0  
 Attention: Ms. Colleen Vermeersch  
 PO#:  
 Invoice to: Kollaard Associates Inc.

Report Number: 1977214  
 Date Submitted: 2022-05-12  
 Date Reported: 2022-05-19  
 Project: 210064  
 COC #: 890555

					Lab I.D.	1625779 Water	1625780 Water	1625781 Water	1625782 Water
Group	Analyte	MRL	Units	Guideline	Sample Matrix	Sampling Date	Sample I.D.		
Anions	N-NO2	0.10	mg/L	MAC 1.0	<0.10	0.72	<0.10	<0.10	<0.10
	N-NO3	0.10	mg/L	MAC 10.0	<0.10	30.8*	12.3*	22.3*	
Nutrients	N-NH3	0.010	mg/L		0.249	0.182	0.060	0.095	
	Total Kjeldahl Nitrogen	0.100	mg/L		0.145	0.740	0.298	0.533	

**Guideline = ODWSOG**

**\* = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.  
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

## Certificate of Analysis

Client: Kollaard Associates Inc.  
 210 Prescott St., Box 189  
 Kemptville, ON  
 K0G 1J0  
 Attention: Ms. Colleen Vermeersch  
 PO#:  
 Invoice to: Kollaard Associates Inc.

Report Number: 1977214  
 Date Submitted: 2022-05-12  
 Date Reported: 2022-05-19  
 Project: 210064  
 COC #: 890555

### **QC Summary**

Analyte	Blank	QC % Rec	QC Limits
<b>Run No</b> 421994 <b>Analysis/Extraction Date</b> 2022-05-17		<b>Analyst</b> AaN	
<b>Method</b> SM 4110			
N-NO2	<0.10 mg/L	97	90-110
N-NO3	<0.10 mg/L	102	90-110
<b>Run No</b> 422119 <b>Analysis/Extraction Date</b> 2022-05-18		<b>Analyst</b> SKH	
<b>Method</b> SM 4110			
N-NO3	<1.0 mg/L	111	90-110
<b>Run No</b> 422273 <b>Analysis/Extraction Date</b> 2022-05-18		<b>Analyst</b> SKH	
<b>Method</b> EPA 351.2			
Total Kjeldahl Nitrogen	<0.100 mg/L	114	70-130
<b>Run No</b> 422331 <b>Analysis/Extraction Date</b> 2022-05-19		<b>Analyst</b> SKH	
<b>Method</b> EPA 350.1			
N-NH3	<0.010 mg/L	89	80-120

**Guideline = ODWSOG**

**\* = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.  
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

## Certificate of Analysis

Client: Kollaard Associates Inc.  
210 Prescott St., Box 189  
Kemptville, ON  
K0G 1J0  
Attention: Ms. Colleen Vermeersch  
PO#:  
Invoice to: Kollaard Associates Inc.

Report Number: 1977214  
Date Submitted: 2022-05-12  
Date Reported: 2022-05-19  
Project: 210064  
COC #: 890555

### Sample Comment Summary

Sample ID: 1625779 5503 Osgoode Main For workorder: Holding time for N-NO2 & N-NO3 analysis was exceeded.

Sample ID: 1625780 3216 Reids Lane NO3 MRL elevated due to matrix interference (dilution was done).

Sample ID: 1625781 5535 Osgoode Main NO3 MRL elevated due to matrix interference (dilution was done).

Sample ID: 1625782 5519 Osgoode Main NO3 MRL elevated due to matrix interference (dilution was done).

**Guideline = ODWSOG**

**\* = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.  
Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range



Crestview Innovations Inc.  
May 10, 2023


**Hydrogeological Investigation and Terrain Evaluation**

3200 Reids Lane, Ottawa, Ontario  
210064

**ATTACHMENT H**

**PUMPING TEST DATA FOR TW1**

## TW1-WELL DRAWDOWN VS. TIME-KOLLAARD FILE 210064



**DRAWDOWN DATA TW1**


Time Lapsed (minutes)	Abs Pres (kPa)	Temp (°C)	Water Level (m)	Drawdown (m)
0	388.094	8.382	-6.86	0.00
1	387.814	8.282	-6.889	0.03
2	383.442	8.282	-7.334	0.47
3	379.072	8.282	-7.78	0.92
4	376.956	8.282	-7.996	1.14
5	376.305	8.282	-8.062	1.20
6	376.115	8.282	-8.082	1.22
7	375.925	8.282	-8.101	1.24
8	375.789	8.282	-8.115	1.26
9	375.754	8.182	-8.118	1.26
10	375.672	8.182	-8.127	1.27
11	375.618	8.182	-8.132	1.27
12	375.564	8.182	-8.138	1.28
13	375.374	8.182	-8.157	1.30
14	375.483	8.182	-8.146	1.29
15	375.564	8.182	-8.138	1.28
16	375.564	8.182	-8.138	1.28
17	375.555	8.082	-8.139	1.28
18	375.528	8.082	-8.141	1.28
19	375.528	8.082	-8.141	1.28
20	375.393	8.082	-8.155	1.30
21	375.447	8.082	-8.15	1.29
22	375.447	8.082	-8.15	1.29
23	375.393	8.082	-8.155	1.30
24	375.366	8.082	-8.158	1.30
25	375.366	8.082	-8.158	1.30
26	375.393	8.082	-8.155	1.30
27	375.393	8.082	-8.155	1.30
28	375.366	8.082	-8.158	1.30
29	375.366	8.082	-8.158	1.30
30	375.366	8.082	-8.158	1.30
31	375.393	8.082	-8.155	1.30
32	375.366	8.082	-8.158	1.30
33	375.284	8.082	-8.166	1.31
34	375.338	8.082	-8.161	1.30
35	375.338	8.082	-8.161	1.30
36	375.338	8.082	-8.161	1.30
37	375.284	8.082	-8.166	1.31
38	375.393	8.082	-8.155	1.30
39	375.338	8.082	-8.161	1.30
40	375.23	8.082	-8.172	1.31
41	375.23	8.082	-8.172	1.31
42	375.284	8.082	-8.166	1.31
43	375.311	8.082	-8.164	1.30
44	375.284	8.082	-8.166	1.31
45	375.311	8.082	-8.164	1.30
46	375.257	8.082	-8.169	1.31
47	375.393	8.082	-8.155	1.30
48	375.284	8.082	-8.166	1.31
49	375.257	8.082	-8.169	1.31
50	375.311	8.082	-8.164	1.30
51	375.284	8.082	-8.166	1.31
52	375.311	8.082	-8.164	1.30
53	375.311	8.082	-8.164	1.30
54	375.338	8.082	-8.161	1.30
55	375.311	8.082	-8.164	1.30
56	375.284	8.082	-8.166	1.31
57	375.284	8.082	-8.166	1.31
58	375.284	8.082	-8.166	1.31
59	375.311	8.082	-8.164	1.30
60	375.284	8.082	-8.166	1.31
61	375.284	8.082	-8.166	1.31
62	375.23	8.082	-8.172	1.31
63	375.23	8.082	-8.172	1.31
64	375.203	8.082	-8.175	1.32
65	375.23	8.082	-8.172	1.31
66	375.203	8.082	-8.175	1.32
67	375.067	8.082	-8.188	1.33
68	375.176	8.082	-8.177	1.32
69	375.203	8.082	-8.175	1.32
70	375.121	8.082	-8.183	1.32
71	375.067	8.082	-8.188	1.33
72	375.04	8.082	-8.191	1.33
73	375.094	8.082	-8.186	1.33
74	375.094	8.082	-8.186	1.33
75	375.04	8.082	-8.191	1.33
76	375.067	8.082	-8.188	1.33
77	375.149	8.082	-8.18	1.32
78	375.121	8.082	-8.183	1.32
79	375.176	8.082	-8.177	1.32
80	375.121	8.082	-8.183	1.32
81	375.067	8.082	-8.188	1.33
82	375.121	8.082	-8.183	1.32
83	375.067	8.082	-8.188	1.33
84	375.067	8.082	-8.188	1.33
85	375.067	8.082	-8.188	1.33
86	375.067	8.082	-8.188	1.33

87	375.067	8.082	-8.188	1.33
88	375.04	8.082	-8.191	1.33
89	375.067	8.082	-8.188	1.33
90	375.094	8.082	-8.186	1.33
91	375.094	8.082	-8.186	1.33
92	375.04	8.082	-8.191	1.33
93	375.013	8.082	-8.194	1.33
94	375.094	8.082	-8.186	1.33
95	374.986	8.082	-8.197	1.34
96	375.013	8.082	-8.194	1.33
97	374.959	8.082	-8.199	1.34
98	374.904	8.082	-8.205	1.35
99	374.823	8.082	-8.213	1.35
100	374.85	8.082	-8.211	1.35
101	374.823	8.082	-8.213	1.35
102	374.85	8.082	-8.211	1.35
103	374.904	8.082	-8.205	1.35
104	374.85	8.082	-8.211	1.35
105	374.796	8.082	-8.216	1.36
106	374.769	8.082	-8.219	1.36
107	374.688	8.082	-8.227	1.37
108	374.742	8.082	-8.222	1.36
109	374.715	8.082	-8.224	1.36
110	374.715	8.082	-8.224	1.36
111	374.715	8.082	-8.224	1.36
112	374.715	8.082	-8.224	1.36
113	374.742	8.082	-8.222	1.36
114	374.769	8.082	-8.219	1.36
115	374.688	8.082	-8.227	1.37
116	374.715	8.082	-8.224	1.36
117	374.742	8.082	-8.222	1.36
118	374.769	8.082	-8.219	1.36
119	374.769	8.082	-8.219	1.36
120	374.796	8.082	-8.216	1.36
121	374.85	8.082	-8.211	1.35
122	374.85	8.082	-8.211	1.35
123	374.715	8.082	-8.224	1.36
124	374.769	8.082	-8.219	1.36
125	374.796	8.082	-8.216	1.36
126	374.769	8.082	-8.219	1.36
127	374.85	8.082	-8.211	1.35
128	374.904	8.082	-8.205	1.35
129	374.932	8.082	-8.202	1.34
130	374.904	8.082	-8.205	1.35
131	374.904	8.082	-8.205	1.35
132	374.877	8.082	-8.208	1.35
133	374.932	8.082	-8.202	1.34
134	374.986	8.082	-8.197	1.34
135	374.959	8.082	-8.199	1.34
136	374.932	8.082	-8.202	1.34
137	374.932	8.082	-8.202	1.34
138	374.932	8.082	-8.202	1.34
139	374.932	8.082	-8.202	1.34
140	374.986	8.082	-8.197	1.34
141	374.904	8.082	-8.205	1.35
142	374.986	8.082	-8.197	1.34
143	374.959	8.082	-8.199	1.34
144	374.959	8.082	-8.199	1.34
145	374.986	8.082	-8.197	1.34
146	374.986	8.082	-8.197	1.34
147	375.013	8.082	-8.194	1.33
148	375.067	8.082	-8.188	1.33
149	374.986	8.082	-8.197	1.34
150	375.04	8.082	-8.191	1.33
151	375.094	8.082	-8.186	1.33
152	374.986	8.082	-8.197	1.34
153	374.959	8.082	-8.199	1.34
154	375.013	8.082	-8.194	1.33
155	374.986	8.082	-8.197	1.34
156	374.959	8.082	-8.199	1.34
157	374.959	8.082	-8.199	1.34
158	374.986	8.082	-8.197	1.34
159	374.986	8.082	-8.197	1.34
160	374.904	8.082	-8.205	1.35
161	374.823	8.082	-8.213	1.35
162	374.823	8.082	-8.213	1.35
163	374.904	8.082	-8.205	1.35
164	374.85	8.082	-8.211	1.35
165	374.877	8.082	-8.208	1.35
166	374.877	8.082	-8.208	1.35
167	374.877	8.082	-8.208	1.35
168	374.904	8.082	-8.205	1.35
169	374.932	8.082	-8.202	1.34
170	374.877	8.082	-8.208	1.35
171	374.959	8.082	-8.199	1.34
172	374.986	8.082	-8.197	1.34
173	374.932	8.082	-8.202	1.34
174	374.904	8.082	-8.205	1.35
175	374.85	8.082	-8.211	1.35
176	374.715	8.082	-8.224	1.36
177	374.769	8.082	-8.219	1.36
178	374.796	8.082	-8.216	1.36
179	374.796	8.082	-8.216	1.36

180	374.85	8.082	-8.211	1.35
181	374.823	8.082	-8.213	1.35
182	374.85	8.082	-8.211	1.35
183	374.796	8.082	-8.216	1.36
184	374.715	8.082	-8.224	1.36
185	374.742	8.082	-8.222	1.36
186	374.688	8.082	-8.227	1.37
187	374.66	8.082	-8.23	1.37
188	374.633	8.082	-8.233	1.37
189	374.66	8.082	-8.23	1.37
190	374.715	8.082	-8.224	1.36
191	374.688	8.082	-8.227	1.37
192	374.688	8.082	-8.227	1.37
193	374.715	8.082	-8.224	1.36
194	374.66	8.082	-8.23	1.37
195	374.742	8.082	-8.222	1.36
196	374.66	8.082	-8.23	1.37
197	374.66	8.082	-8.23	1.37
198	374.688	8.082	-8.227	1.37
199	374.688	8.082	-8.227	1.37
200	374.742	8.082	-8.222	1.36
201	374.742	8.082	-8.222	1.36
202	374.796	8.082	-8.216	1.36
203	374.769	8.082	-8.219	1.36
204	374.769	8.082	-8.219	1.36
205	374.796	8.082	-8.216	1.36
206	374.796	8.082	-8.216	1.36
207	374.823	8.082	-8.213	1.35
208	374.85	8.082	-8.211	1.35
209	374.877	8.082	-8.208	1.35
210	374.796	8.082	-8.216	1.36
211	374.796	8.082	-8.216	1.36
212	374.796	8.082	-8.216	1.36
213	374.85	8.082	-8.211	1.35
214	374.823	8.082	-8.213	1.35
215	374.85	8.082	-8.211	1.35
216	374.85	8.082	-8.211	1.35
217	374.85	8.082	-8.211	1.35
218	374.877	8.082	-8.208	1.35
219	374.85	8.082	-8.211	1.35
220	374.85	8.082	-8.211	1.35
221	374.904	8.082	-8.205	1.35
222	374.904	8.082	-8.205	1.35
223	374.85	8.082	-8.211	1.35
224	374.877	8.082	-8.208	1.35
225	374.877	8.082	-8.208	1.35
226	374.877	8.082	-8.208	1.35
227	374.877	8.082	-8.208	1.35
228	374.877	8.082	-8.208	1.35
229	374.904	8.082	-8.205	1.35
230	374.877	8.082	-8.208	1.35
231	374.85	8.082	-8.211	1.35
232	374.877	8.082	-8.208	1.35
233	374.85	8.082	-8.211	1.35
234	374.932	8.082	-8.202	1.34
235	374.904	8.082	-8.205	1.35
236	374.877	8.082	-8.208	1.35
237	374.85	8.082	-8.211	1.35
238	374.823	8.082	-8.213	1.35
239	374.85	8.082	-8.211	1.35
240	374.823	8.082	-8.213	1.35
241	374.85	8.082	-8.211	1.35
242	374.85	8.082	-8.211	1.35
243	374.85	8.082	-8.211	1.35
244	374.877	8.082	-8.208	1.35
245	374.796	8.082	-8.216	1.36
246	374.742	8.082	-8.222	1.36
247	374.688	8.082	-8.227	1.37
248	374.742	8.082	-8.222	1.36
249	374.688	8.082	-8.227	1.37
250	374.688	8.082	-8.227	1.37
251	374.688	8.082	-8.227	1.37
252	374.742	8.082	-8.222	1.36
253	374.742	8.082	-8.222	1.36
254	374.66	8.082	-8.23	1.37
255	374.715	8.082	-8.224	1.36
256	374.66	8.082	-8.23	1.37
257	374.715	8.082	-8.224	1.36
258	374.769	8.082	-8.219	1.36
259	374.742	8.082	-8.222	1.36
260	374.715	8.082	-8.224	1.36
261	374.688	8.082	-8.227	1.37
262	374.66	8.082	-8.23	1.37
263	374.66	8.082	-8.23	1.37
264	374.66	8.082	-8.23	1.37
265	374.66	8.082	-8.23	1.37
266	374.688	8.082	-8.227	1.37
267	374.688	8.082	-8.227	1.37
268	374.633	8.082	-8.233	1.37
269	374.66	8.082	-8.23	1.37
270	374.606	8.082	-8.235	1.38
271	374.606	8.082	-8.235	1.38
272	374.633	8.082	-8.233	1.37

273	374.606	8.082	-8.235	1.38
274	374.633	8.082	-8.233	1.37
275	374.552	8.082	-8.241	1.38
276	374.606	8.082	-8.235	1.38
277	374.688	8.082	-8.227	1.37
278	374.66	8.082	-8.23	1.37
279	374.688	8.082	-8.227	1.37
280	374.66	8.082	-8.23	1.37
281	374.633	8.082	-8.233	1.37
282	374.606	8.082	-8.235	1.38
283	374.606	8.082	-8.235	1.38
284	374.633	8.082	-8.233	1.37
285	374.498	8.082	-8.246	1.39
286	374.471	8.082	-8.249	1.39
287	374.471	8.082	-8.249	1.39
288	374.498	8.082	-8.246	1.39
289	374.498	8.082	-8.246	1.39
290	374.498	8.082	-8.246	1.39
291	374.471	8.082	-8.249	1.39
292	374.471	8.082	-8.249	1.39
293	374.471	8.082	-8.249	1.39
294	374.498	8.082	-8.246	1.39
295	374.525	8.082	-8.244	1.38
296	374.552	8.082	-8.241	1.38
297	374.552	8.082	-8.241	1.38
298	374.552	8.082	-8.241	1.38
299	374.552	8.082	-8.241	1.38
300	374.606	8.082	-8.235	1.38
301	374.552	8.082	-8.241	1.38
302	374.552	8.082	-8.241	1.38
303	374.579	8.082	-8.238	1.38
304	374.552	8.082	-8.241	1.38
305	374.498	8.082	-8.246	1.39
306	374.552	8.082	-8.241	1.38
307	374.552	8.082	-8.241	1.38
308	374.579	8.082	-8.238	1.38
309	374.552	8.082	-8.241	1.38
310	374.525	8.082	-8.244	1.38
311	374.525	8.082	-8.244	1.38
312	374.552	8.082	-8.241	1.38
313	374.579	8.082	-8.238	1.38
314	374.552	8.082	-8.241	1.38
315	374.579	8.082	-8.238	1.38
316	374.606	8.082	-8.235	1.38
317	374.525	8.082	-8.244	1.38
318	374.579	8.082	-8.238	1.38
319	374.525	8.082	-8.244	1.38
320	374.552	8.082	-8.241	1.38
321	374.552	8.082	-8.241	1.38
322	374.579	8.082	-8.238	1.38
323	374.552	8.082	-8.241	1.38
324	374.579	8.082	-8.238	1.38
325	374.579	8.082	-8.238	1.38
326	374.525	8.082	-8.244	1.38
327	374.606	8.082	-8.235	1.38
328	374.552	8.082	-8.241	1.38
329	374.579	8.082	-8.238	1.38
330	374.525	8.082	-8.244	1.38
331	374.579	8.082	-8.238	1.38
332	374.579	8.082	-8.238	1.38
333	374.552	8.082	-8.241	1.38
334	374.416	8.082	-8.255	1.40
335	374.362	8.082	-8.26	1.40
336	374.416	8.082	-8.255	1.40
337	374.471	8.082	-8.249	1.39
338	374.498	8.082	-8.246	1.39
339	374.606	8.082	-8.235	1.38
340	374.579	8.082	-8.238	1.38
341	374.579	8.082	-8.238	1.38
342	374.552	8.082	-8.241	1.38
343	374.579	8.082	-8.238	1.38
344	374.552	8.082	-8.241	1.38
345	374.525	8.082	-8.244	1.38
346	374.525	8.082	-8.244	1.38
347	374.552	8.082	-8.241	1.38
348	374.579	8.082	-8.238	1.38
349	374.579	8.082	-8.238	1.38
350	374.579	8.082	-8.238	1.38
351	374.579	8.082	-8.238	1.38
352	374.579	8.082	-8.238	1.38
353	374.579	8.082	-8.238	1.38
354	374.579	8.082	-8.238	1.38
355	374.552	8.082	-8.241	1.38
356	374.525	8.082	-8.244	1.38
357	374.579	8.082	-8.238	1.38
358	374.552	8.082	-8.241	1.38
359	374.579	8.082	-8.238	1.38
360	374.552	8.082	-8.241	1.38

## TW1- WELL RECOVERY VS. TIME - KOLLAARD FILE 210064



## RECOVERY DATA TW-1

t'	t / t'	Abs Pres (kPa)	Temp (°C)	Water Level (m)	Drawdown (m)	Recovery (%)
1	361	385.053	8.082	-7.17	0.31	78%
2	181.0	386.275	8.082	-7.045	0.19	87%
3	121.0	386.601	8.082	-7.012	0.15	89%
4	91.0	386.846	8.082	-6.987	0.13	91%
5	73.0	386.954	8.082	-6.976	0.12	92%
6	61.0	387.063	8.082	-6.965	0.11	92%
7	52.4	387.144	8.082	-6.957	0.10	93%
8	46.0	387.199	8.082	-6.951	0.09	93%
9	41.0	387.226	8.082	-6.949	0.09	94%
10	37.0	387.253	8.082	-6.946	0.09	94%
11	33.7	387.28	8.082	-6.943	0.08	94%
12	31.0	387.307	8.082	-6.94	0.08	94%
13	28.7	387.335	8.082	-6.937	0.08	94%
14	26.7	387.416	8.082	-6.929	0.07	95%
15	25.0	387.443	8.082	-6.926	0.07	95%
16	23.5	387.443	8.082	-6.926	0.07	95%
17	22.2	387.498	8.082	-6.921	0.06	96%
18	21.0	387.498	8.082	-6.921	0.06	96%
19	19.9	387.525	8.082	-6.918	0.06	96%
20	19.0	387.525	8.082	-6.918	0.06	96%
21	18.1	387.525	8.082	-6.918	0.06	96%
22	17.4	387.525	8.082	-6.918	0.06	96%
23	16.7	387.498	8.082	-6.921	0.06	96%
24	16.0	387.525	8.082	-6.918	0.06	96%
25	15.4	387.552	8.082	-6.915	0.05	96%
26	14.8	387.525	8.082	-6.918	0.06	96%
27	14.3	387.416	8.082	-6.929	0.07	95%
28	13.9	386.248	8.082	-7.048	0.19	86%
29	13.4	386.628	8.082	-7.009	0.15	89%
30	13.0	387.498	8.082	-6.921	0.06	96%
31	12.6	387.552	8.082	-6.915	0.05	96%
32	12.3	387.579	8.082	-6.913	0.05	96%
33	11.9	387.579	8.082	-6.913	0.05	96%
34	11.6	387.579	8.082	-6.913	0.05	96%
35	11.3	387.579	8.082	-6.913	0.05	96%
36	11.0	387.606	8.082	-6.91	0.05	96%
37	10.7	387.642	8.182	-6.906	0.05	97%
38	10.5	387.633	8.082	-6.907	0.05	97%
39	10.2	387.669	8.182	-6.903	0.04	97%
40	10.0	387.669	8.182	-6.903	0.04	97%
41	9.8	387.669	8.182	-6.903	0.04	97%
42	9.6	387.669	8.182	-6.903	0.04	97%
43	9.4	387.669	8.182	-6.903	0.04	97%
44	9.2	387.669	8.182	-6.903	0.04	97%
45	9.0	387.696	8.182	-6.901	0.04	97%
46	8.8	387.696	8.182	-6.901	0.04	97%
47	8.7	387.669	8.182	-6.903	0.04	97%
48	8.5	387.696	8.182	-6.901	0.04	97%
49	8.3	387.696	8.182	-6.901	0.04	97%
50	8.2	387.669	8.182	-6.903	0.04	97%
51	8.1	387.669	8.182	-6.903	0.04	97%
52	7.9	387.669	8.182	-6.903	0.04	97%
53	7.8	387.669	8.182	-6.903	0.04	97%
54	7.7	387.669	8.182	-6.903	0.04	97%
55	7.5	387.669	8.182	-6.903	0.04	97%
56	7.4	387.669	8.182	-6.903	0.04	97%
57	7.3	387.669	8.182	-6.903	0.04	97%
58	7.2	387.669	8.182	-6.903	0.04	97%
59	7.1	387.669	8.182	-6.903	0.04	97%
60	7.0	387.642	8.182	-6.906	0.05	97%



Crestview Innovations Inc.  
May 10, 2023


**Hydrogeological Investigation and Terrain Evaluation**

3200 Reids Lane, Ottawa, Ontario  
210064

**ATTACHMENT I**

**PUMPING TEST DATA FOR TW2**

## TW2-WELL DRAWDOWN VS. TIME-KOLLAARD FILE 210064



**DRAWDOWN DATA TW2**


Time Lapsed (minutes)	Abs Pres (kPa)	Temp (°C)	Water Level (m)	Drawdown (m)
0	392.344	8.182	-6.68	0.00
1	390.194	8.182	-6.899	0.22
2	390.672	8.182	-6.85	0.17
3	386.79	8.182	-7.246	0.57
4	385.417	8.182	-7.386	0.71
5	384.969	8.182	-7.432	0.75
6	384.88	8.182	-7.441	0.76
7	384.73	8.182	-7.456	0.78
8	383.738	8.082	-7.558	0.88
9	383.35	8.082	-7.597	0.92
10	383.231	8.082	-7.609	0.93
11	383.112	8.082	-7.621	0.94
12	383.022	8.082	-7.631	0.95
13	382.992	8.082	-7.634	0.95
14	382.903	8.082	-7.643	0.96
15	382.903	8.082	-7.643	0.96
16	382.962	8.082	-7.637	0.96
17	382.955	7.983	-7.637	0.96
18	382.955	7.983	-7.637	0.96
19	382.866	7.983	-7.646	0.97
20	382.896	7.983	-7.643	0.96
21	382.985	7.983	-7.634	0.95
22	382.866	7.983	-7.646	0.97
23	382.866	7.983	-7.646	0.97
24	382.926	7.983	-7.64	0.96
25	382.806	7.983	-7.653	0.97
26	382.836	7.983	-7.65	0.97
27	382.806	7.983	-7.653	0.97
28	382.746	7.983	-7.659	0.98
29	382.687	7.983	-7.665	0.99
30	382.866	7.983	-7.646	0.97
31	382.717	7.983	-7.662	0.98
32	382.687	7.983	-7.665	0.99
33	382.687	7.983	-7.665	0.99
34	382.687	7.983	-7.665	0.99
35	382.657	7.983	-7.668	0.99
36	382.776	7.983	-7.656	0.98
37	382.687	7.983	-7.665	0.99
38	382.567	7.983	-7.677	1.00
39	382.538	7.983	-7.68	1.00
40	382.657	7.983	-7.668	0.99
41	382.687	7.983	-7.665	0.99
42	382.687	7.983	-7.665	0.99
43	382.717	7.983	-7.662	0.98
44	382.538	7.983	-7.68	1.00
45	382.508	7.983	-7.683	1.00
46	382.627	7.983	-7.671	0.99
47	382.508	7.983	-7.683	1.00
48	382.687	7.983	-7.665	0.99
49	382.597	7.983	-7.674	0.99
50	382.597	7.983	-7.674	0.99
51	382.657	7.983	-7.668	0.99
52	382.597	7.983	-7.674	0.99
53	382.597	7.983	-7.674	0.99
54	382.597	7.983	-7.674	0.99
55	382.687	7.983	-7.665	0.99
56	382.657	7.983	-7.668	0.99
57	382.597	7.983	-7.674	0.99
58	382.209	7.983	-7.713	1.03
59	382.329	7.983	-7.701	1.02
60	382.418	7.983	-7.692	1.01
61	382.567	7.983	-7.677	1.00
62	382.478	7.983	-7.686	1.01
63	382.508	7.983	-7.683	1.00
64	382.567	7.983	-7.677	1.00
65	382.388	7.983	-7.695	1.02
66	382.478	7.983	-7.686	1.01
67	382.538	7.983	-7.68	1.00
68	382.627	7.983	-7.671	0.99
69	382.508	7.983	-7.683	1.00
70	382.418	7.983	-7.692	1.01
71	382.508	7.983	-7.683	1.00
72	382.687	7.983	-7.665	0.99
73	382.448	7.983	-7.689	1.01
74	382.448	7.983	-7.689	1.01
75	382.508	7.983	-7.683	1.00
76	382.538	7.983	-7.68	1.00
77	382.388	7.983	-7.695	1.02
78	382.538	7.983	-7.68	1.00
79	382.567	7.983	-7.677	1.00
80	382.448	7.983	-7.689	1.01
81	382.478	7.983	-7.686	1.01
82	382.448	7.983	-7.689	1.01
83	382.418	7.983	-7.692	1.01
84	382.388	7.983	-7.695	1.02
85	382.508	7.983	-7.683	1.00
86	382.448	7.983	-7.689	1.01

87	382.448	7.983	-7.689	1.01
88	382.418	7.983	-7.692	1.01
89	382.508	7.983	-7.683	1.00
90	382.478	7.983	-7.686	1.01
91	382.418	7.983	-7.692	1.01
92	382.388	7.983	-7.695	1.02
93	382.388	7.983	-7.695	1.02
94	382.329	7.983	-7.701	1.02
95	382.358	7.983	-7.698	1.02
96	382.329	7.983	-7.701	1.02
97	382.388	7.983	-7.695	1.02
98	382.299	7.983	-7.704	1.02
99	382.299	7.983	-7.704	1.02
100	382.358	7.983	-7.698	1.02
101	382.329	7.983	-7.701	1.02
102	382.358	7.983	-7.698	1.02
103	382.388	7.983	-7.695	1.02
104	382.358	7.983	-7.698	1.02
105	382.388	7.983	-7.695	1.02
106	382.388	7.983	-7.695	1.02
107	382.418	7.983	-7.692	1.01
108	382.418	7.983	-7.692	1.01
109	382.299	7.983	-7.704	1.02
110	382.358	7.983	-7.698	1.02
111	382.388	7.983	-7.695	1.02
112	382.418	7.983	-7.692	1.01
113	382.329	7.983	-7.701	1.02
114	382.388	7.983	-7.695	1.02
115	382.388	7.983	-7.695	1.02
116	382.329	7.983	-7.701	1.02
117	382.299	7.983	-7.704	1.02
118	382.329	7.983	-7.701	1.02
119	382.329	7.983	-7.701	1.02
120	382.418	7.983	-7.692	1.01
121	382.388	7.983	-7.695	1.02
122	382.388	7.983	-7.695	1.02
123	382.388	7.983	-7.695	1.02
124	382.388	7.983	-7.695	1.02
125	382.329	7.983	-7.701	1.02
126	382.299	7.983	-7.704	1.02
127	382.299	7.983	-7.704	1.02
128	382.358	7.983	-7.698	1.02
129	382.329	7.983	-7.701	1.02
130	382.209	7.983	-7.713	1.03
131	382.448	7.983	-7.689	1.01
132	382.358	7.983	-7.698	1.02
133	382.508	7.983	-7.683	1.00
134	382.329	7.983	-7.701	1.02
135	382.448	7.983	-7.689	1.01
136	382.358	7.983	-7.698	1.02
137	382.239	7.983	-7.71	1.03
138	382.329	7.983	-7.701	1.02
139	382.358	7.983	-7.698	1.02
140	382.388	7.983	-7.695	1.02
141	382.358	7.983	-7.698	1.02
142	382.418	7.983	-7.692	1.01
143	382.448	7.983	-7.689	1.01
144	382.388	7.983	-7.695	1.02
145	382.388	7.983	-7.695	1.02
146	382.329	7.983	-7.701	1.02
147	382.239	7.983	-7.71	1.03
148	382.418	7.983	-7.692	1.01
149	382.269	7.983	-7.707	1.03
150	382.358	7.983	-7.698	1.02
151	382.299	7.983	-7.704	1.02
152	382.478	7.983	-7.686	1.01
153	382.448	7.983	-7.689	1.01
154	382.269	7.983	-7.707	1.03
155	382.269	7.983	-7.707	1.03
156	382.358	7.983	-7.698	1.02
157	382.448	7.983	-7.689	1.01
158	382.299	7.983	-7.704	1.02
159	382.388	7.983	-7.695	1.02
160	382.299	7.983	-7.704	1.02
161	382.478	7.983	-7.686	1.01
162	382.358	7.983	-7.698	1.02
163	382.388	7.983	-7.695	1.02
164	382.329	7.983	-7.701	1.02
165	382.299	7.983	-7.704	1.02
166	382.448	7.983	-7.689	1.01
167	382.269	7.983	-7.707	1.03
168	382.209	7.983	-7.713	1.03
169	382.269	7.983	-7.707	1.03
170	382.329	7.983	-7.701	1.02
171	382.329	7.983	-7.701	1.02
172	382.358	7.983	-7.698	1.02
173	382.299	7.983	-7.704	1.02
174	382.299	7.983	-7.704	1.02
175	382.299	7.983	-7.704	1.02
176	382.329	7.983	-7.701	1.02
177	382.239	7.983	-7.71	1.03
178	382.329	7.983	-7.701	1.02
179	382.358	7.983	-7.698	1.02

180	382.358	7.983	-7.698	1.02
181	382.299	7.983	-7.704	1.02
182	382.329	7.983	-7.701	1.02
183	382.329	7.983	-7.701	1.02
184	382.329	7.983	-7.701	1.02
185	382.299	7.983	-7.704	1.02
186	382.269	7.983	-7.707	1.03
187	382.299	7.983	-7.704	1.02
188	382.299	7.983	-7.704	1.02
189	382.269	7.983	-7.707	1.03
190	382.329	7.983	-7.701	1.02
191	382.269	7.983	-7.707	1.03
192	382.269	7.983	-7.707	1.03
193	382.209	7.983	-7.713	1.03
194	382.299	7.983	-7.704	1.02
195	382.239	7.983	-7.71	1.03
196	382.239	7.983	-7.71	1.03
197	382.239	7.983	-7.71	1.03
198	382.388	7.983	-7.695	1.02
199	382.239	7.983	-7.71	1.03
200	382.299	7.983	-7.704	1.02
201	382.209	7.983	-7.713	1.03
202	382.269	7.983	-7.707	1.03
203	382.239	7.983	-7.71	1.03
204	382.209	7.983	-7.713	1.03
205	382.269	7.983	-7.707	1.03
206	382.06	7.983	-7.729	1.05
207	382.09	7.983	-7.726	1.05
208	382.299	7.983	-7.704	1.02
209	382.179	7.983	-7.717	1.04
210	382.239	7.983	-7.71	1.03
211	382.179	7.983	-7.717	1.04
212	382.209	7.983	-7.713	1.03
213	382.06	7.983	-7.729	1.05
214	382.209	7.983	-7.713	1.03
215	382.12	7.983	-7.723	1.04
216	382.12	7.983	-7.723	1.04
217	382.12	7.983	-7.723	1.04
218	382.179	7.983	-7.717	1.04
219	382.179	7.983	-7.717	1.04
220	382.15	7.983	-7.719	1.04
221	382.15	7.983	-7.719	1.04
222	382.09	7.983	-7.726	1.05
223	382.09	7.983	-7.726	1.05
224	382.09	7.983	-7.726	1.05
225	382.06	7.983	-7.729	1.05
226	382.15	7.983	-7.719	1.04
227	382.06	7.983	-7.729	1.05
228	382.09	7.983	-7.726	1.05
229	382.03	7.983	-7.732	1.05
230	382.06	7.983	-7.729	1.05
231	382.03	7.983	-7.732	1.05
232	382.09	7.983	-7.726	1.05
233	382.09	7.983	-7.726	1.05
234	382	7.983	-7.735	1.06
235	382.06	7.983	-7.729	1.05
236	381.971	7.983	-7.738	1.06
237	381.941	7.983	-7.741	1.06
238	382	7.983	-7.735	1.06
239	382.179	7.983	-7.717	1.04
240	382.03	7.983	-7.732	1.05
241	382.06	7.983	-7.729	1.05
242	382.15	7.983	-7.719	1.04
243	382.09	7.983	-7.726	1.05
244	382.209	7.983	-7.713	1.03
245	382.12	7.983	-7.723	1.04
246	382.12	7.983	-7.723	1.04
247	382.09	7.983	-7.726	1.05
248	382.03	7.983	-7.732	1.05
249	382.03	7.983	-7.732	1.05
250	381.971	7.983	-7.738	1.06
251	382.03	7.983	-7.732	1.05
252	382	7.983	-7.735	1.06
253	381.971	7.983	-7.738	1.06
254	382.03	7.983	-7.732	1.05
255	382.209	7.983	-7.713	1.03
256	382	7.983	-7.735	1.06
257	382.09	7.983	-7.726	1.05
258	382.03	7.983	-7.732	1.05
259	382.03	7.983	-7.732	1.05
260	381.941	7.983	-7.741	1.06
261	382.06	7.983	-7.729	1.05
262	382.06	7.983	-7.729	1.05
263	382.06	7.983	-7.729	1.05
264	382.12	7.983	-7.723	1.04
265	382.06	7.983	-7.729	1.05
266	382.179	7.983	-7.717	1.04
267	382.06	7.983	-7.729	1.05
268	382.03	7.983	-7.732	1.05
269	382.09	7.983	-7.726	1.05
270	382.09	7.983	-7.726	1.05
271	382.179	7.983	-7.717	1.04
272	382.09	7.983	-7.726	1.05

273	382.12	7.983	-7.723	1.04
274	382.12	7.983	-7.723	1.04
275	382.12	7.983	-7.723	1.04
276	382.239	7.983	-7.71	1.03
277	382	7.983	-7.735	1.06
278	382.12	7.983	-7.723	1.04
279	382.15	7.983	-7.719	1.04
280	382	7.983	-7.735	1.06
281	382.12	7.983	-7.723	1.04
282	382.09	7.983	-7.726	1.05
283	382.15	7.983	-7.719	1.04
284	382.09	7.983	-7.726	1.05
285	382	7.983	-7.735	1.06
286	382.06	7.983	-7.729	1.05
287	382.03	7.983	-7.732	1.05
288	382	7.983	-7.735	1.06
289	382.179	7.983	-7.717	1.04
290	382.15	7.983	-7.719	1.04
291	382.12	7.983	-7.723	1.04
292	382.09	7.983	-7.726	1.05
293	382.09	7.983	-7.726	1.05
294	382.09	7.983	-7.726	1.05
295	382	7.983	-7.735	1.06
296	382.09	7.983	-7.726	1.05
297	381.941	7.983	-7.741	1.06
298	382.03	7.983	-7.732	1.05
299	382.12	7.983	-7.723	1.04
300	382.09	7.983	-7.726	1.05
301	382.06	7.983	-7.729	1.05
302	382.03	7.983	-7.732	1.05
303	382.06	7.983	-7.729	1.05
304	382	7.983	-7.735	1.06
305	382.03	7.983	-7.732	1.05
306	382.03	7.983	-7.732	1.05
307	382.06	7.983	-7.729	1.05
308	382.03	7.983	-7.732	1.05
309	382	7.983	-7.735	1.06
310	382.239	7.983	-7.71	1.03
311	381.941	7.983	-7.741	1.06
312	382.03	7.983	-7.732	1.05
313	381.971	7.983	-7.738	1.06
314	382.06	7.983	-7.729	1.05
315	382	7.983	-7.735	1.06
316	382.09	7.983	-7.726	1.05
317	381.941	7.983	-7.741	1.06
318	382.06	7.983	-7.729	1.05
319	381.971	7.983	-7.738	1.06
320	382.06	7.983	-7.729	1.05
321	381.911	7.983	-7.744	1.06
322	381.732	7.983	-7.762	1.08
323	381.881	7.983	-7.747	1.07
324	381.911	7.983	-7.744	1.06
325	381.971	7.983	-7.738	1.06
326	382.03	7.983	-7.732	1.05
327	382	7.983	-7.735	1.06
328	381.941	7.983	-7.741	1.06
329	382.12	7.983	-7.723	1.04
330	381.851	7.983	-7.75	1.07
331	381.971	7.983	-7.738	1.06
332	381.941	7.983	-7.741	1.06
333	381.971	7.983	-7.738	1.06
334	381.941	7.983	-7.741	1.06
335	381.941	7.983	-7.741	1.06
336	381.971	7.983	-7.738	1.06
337	382	7.983	-7.735	1.06
338	381.941	7.983	-7.741	1.06
339	382	7.983	-7.735	1.06
340	382	7.983	-7.735	1.06
341	382	7.983	-7.735	1.06
342	381.941	7.983	-7.741	1.06
343	382.12	7.983	-7.723	1.04
344	381.971	7.983	-7.738	1.06
345	382	7.983	-7.735	1.06
346	381.911	7.983	-7.744	1.06
347	381.971	7.983	-7.738	1.06
348	382.06	7.983	-7.729	1.05
349	382	7.983	-7.735	1.06
350	382	7.983	-7.735	1.06
351	381.941	7.983	-7.741	1.06
352	381.971	7.983	-7.738	1.06
353	381.971	7.983	-7.738	1.06
354	382.06	7.983	-7.729	1.05
355	381.971	7.983	-7.738	1.06
356	382.09	7.983	-7.726	1.05
357	381.971	7.983	-7.738	1.06
358	382.09	7.983	-7.726	1.05
359	381.971	7.983	-7.738	1.06
360	382.15	7.983	-7.719	1.04
361	382.06	7.983	-7.729	1.05
362	382	7.983	-7.735	1.06
363	381.941	7.983	-7.741	1.06
364	382.06	7.983	-7.729	1.05
365	382.179	7.983	-7.717	1.04

## TW2- WELL RECOVERY VS. TIME - KOLLAARD FILE 210064



**RECOVERY DATA TW-2**

t'	t / t'	Abs Pres (kPa)	Temp (°C)	Water Level (m)	Drawdown (m)	Recovery (%)
1	366.0	389.523	7.983	-6.968	0.29	73%
2	183.5	390.359	7.983	-6.882	0.20	81%
3	122.7	390.687	7.983	-6.849	0.17	84%
4	92.3	390.896	7.983	-6.828	0.15	86%
5	74.0	391.016	7.983	-6.815	0.14	87%
6	61.8	391.105	7.983	-6.806	0.13	88%
7	53.1	391.195	7.983	-6.797	0.12	89%
8	46.6	391.255	7.983	-6.791	0.11	90%
9	41.6	391.314	7.983	-6.785	0.11	90%
10	37.5	391.374	7.983	-6.779	0.10	91%
11	34.2	391.374	7.983	-6.779	0.10	91%
12	31.4	391.374	7.983	-6.779	0.10	91%
13	29.1	391.434	7.983	-6.773	0.09	91%
14	27.1	391.464	7.983	-6.77	0.09	91%
15	25.3	391.494	7.983	-6.767	0.09	92%
16	23.8	391.523	7.983	-6.764	0.08	92%
17	22.5	391.523	7.983	-6.764	0.08	92%
18	21.3	391.523	7.983	-6.764	0.08	92%
19	20.2	391.523	7.983	-6.764	0.08	92%
20	19.3	391.523	7.983	-6.764	0.08	92%
21	18.4	391.494	7.983	-6.767	0.09	92%
22	17.6	391.523	7.983	-6.764	0.08	92%
23	16.9	391.553	7.983	-6.761	0.08	92%
24	16.2	391.553	7.983	-6.761	0.08	92%
25	15.6	391.553	7.983	-6.761	0.08	92%
26	15.0	391.553	7.983	-6.761	0.08	92%
27	14.5	391.553	7.983	-6.761	0.08	92%
28	14.0	391.583	7.983	-6.758	0.08	93%
29	13.6	391.553	7.983	-6.761	0.08	92%
30	13.2	391.583	7.983	-6.758	0.08	93%
31	12.8	391.583	7.983	-6.758	0.08	93%
32	12.4	391.553	7.983	-6.761	0.08	92%
33	12.1	391.553	7.983	-6.761	0.08	92%
34	11.7	391.553	7.983	-6.761	0.08	92%
35	11.4	391.583	7.983	-6.758	0.08	93%
36	11.1	391.583	7.983	-6.758	0.08	93%
37	10.9	391.613	7.983	-6.755	0.08	93%
38	10.6	391.583	7.983	-6.758	0.08	93%
39	10.4	391.583	7.983	-6.758	0.08	93%
40	10.1	391.583	7.983	-6.758	0.08	93%
41	9.9	391.583	7.983	-6.758	0.08	93%
42	9.7	391.583	7.983	-6.758	0.08	93%
43	9.5	391.583	7.983	-6.758	0.08	93%
44	9.3	391.613	7.983	-6.755	0.08	93%
45	9.1	391.553	7.983	-6.761	0.08	92%
46	8.9	390.687	7.983	-6.849	0.17	84%
47	8.8	391.673	7.983	-6.748	0.07	94%
48	8.6	391.613	7.983	-6.755	0.08	93%
49	8.4	391.673	7.983	-6.748	0.07	94%
50	8.3	391.643	7.983	-6.751	0.07	93%
51	8.2	391.643	7.983	-6.751	0.07	93%
52	8.0	391.673	7.983	-6.748	0.07	94%
53	7.9	391.673	7.983	-6.748	0.07	94%
54	7.8	390.986	7.983	-6.818	0.14	87%
55	7.6	391.016	7.983	-6.815	0.14	87%
56	7.5	391.703	7.983	-6.745	0.07	94%
57	7.4	391.733	7.983	-6.742	0.06	94%
58	7.3	391.942	7.983	-6.721	0.04	96%

59	7.2	391.673	7.983	-6.748	0.07	94%
60	7.1	391.643	7.983	-6.751	0.07	93%
61	7.0	391.673	7.983	-6.748	0.07	94%
62	6.9	391.673	7.983	-6.748	0.07	94%
63	6.8	391.673	7.983	-6.748	0.07	94%
64	6.7	391.703	7.983	-6.745	0.07	94%
65	6.6	391.74	8.082	-6.742	0.06	94%
66	6.5	391.74	8.082	-6.742	0.06	94%
67	6.4	391.74	8.082	-6.742	0.06	94%
68	6.4	391.77	8.082	-6.739	0.06	94%
69	6.3	391.77	8.082	-6.739	0.06	94%
70	6.2	391.77	8.082	-6.739	0.06	94%
71	6.1	391.77	8.082	-6.739	0.06	94%
72	6.1	391.799	8.082	-6.736	0.06	95%
73	6.0	391.77	8.082	-6.739	0.06	94%
74	5.9	391.77	8.082	-6.739	0.06	94%
75	5.9	391.799	8.082	-6.736	0.06	95%
76	5.8	391.799	8.082	-6.736	0.06	95%
77	5.7	391.799	8.082	-6.736	0.06	95%
78	5.7	391.799	8.082	-6.736	0.06	95%
79	5.6	391.829	8.082	-6.733	0.05	95%
80	5.6	391.859	8.082	-6.729	0.05	95%
81	5.5	391.859	8.082	-6.729	0.05	95%
82	5.5	391.859	8.082	-6.729	0.05	95%
83	5.4	391.859	8.082	-6.729	0.05	95%
84	5.3	391.829	8.082	-6.733	0.05	95%
85	5.3	391.829	8.082	-6.733	0.05	95%
86	5.2	391.829	8.082	-6.733	0.05	95%
87	5.2	391.829	8.082	-6.733	0.05	95%
88	5.1	391.829	8.082	-6.733	0.05	95%
89	5.1	391.829	8.082	-6.733	0.05	95%
90	5.1	391.829	8.082	-6.733	0.05	95%
91	5.0	391.829	8.082	-6.733	0.05	95%
92	5.0	391.859	8.082	-6.729	0.05	95%
93	4.9	391.859	8.082	-6.729	0.05	95%
94	4.9	391.889	8.082	-6.726	0.05	96%
95	4.8	391.859	8.082	-6.729	0.05	95%
96	4.8	391.859	8.082	-6.729	0.05	95%
97	4.8	391.859	8.082	-6.729	0.05	95%
98	4.7	391.859	8.082	-6.729	0.05	95%
99	4.7	391.859	8.082	-6.729	0.05	95%
100	4.7	391.889	8.082	-6.726	0.05	96%
101	4.6	391.889	8.082	-6.726	0.05	96%
102	4.6	391.889	8.082	-6.726	0.05	96%
103	4.5	391.919	8.082	-6.723	0.04	96%
104	4.5	391.919	8.082	-6.723	0.04	96%
105	4.5	391.919	8.082	-6.723	0.04	96%
106	4.4	391.919	8.082	-6.723	0.04	96%
107	4.4	391.889	8.082	-6.726	0.05	96%
108	4.4	391.919	8.082	-6.723	0.04	96%
109	4.3	391.949	8.082	-6.72	0.04	96%
110	4.3	391.949	8.082	-6.72	0.04	96%
111	4.3	391.979	8.082	-6.717	0.04	97%
112	4.3	391.979	8.082	-6.717	0.04	97%
113	4.2	391.979	8.082	-6.717	0.04	97%
114	4.2	392.008	8.082	-6.714	0.03	97%
115	4.2	391.979	8.082	-6.717	0.04	97%
116	4.1	391.979	8.082	-6.717	0.04	97%
117	4.1	391.979	8.082	-6.717	0.04	97%
118	4.1	391.979	8.082	-6.717	0.04	97%
119	4.1	391.979	8.082	-6.717	0.04	97%
120	4.0	392.008	8.082	-6.714	0.03	97%



Crestview Innovations Inc.  
May 10, 2023


**Hydrogeological Investigation and Terrain Evaluation**

3200 Reids Lane, Ottawa, Ontario  
210064

**ATTACHMENT J**

**PUMPING TEST DATA FOR TW3**

## TW3-WELL DRAWDOWN VS. TIME-KOLLAARD FILE 210064



**DRAWDOWN DATA TW3**


Time Lapsed (minutes)	Abs Pres (kPa)	Temp (°C)	Water Level (m)	Drawdown (m)
0	359.25	7.983	-4.53	0.00
1	358.863	7.983	-4.569	0.04
2	358.833	7.983	-4.573	0.04
3	358.774	7.983	-4.579	0.05
4	358.714	7.983	-4.585	0.05
5	358.506	7.983	-4.606	0.08
6	358.535	7.983	-4.603	0.07
7	358.416	7.983	-4.615	0.09
8	358.446	7.983	-4.612	0.08
9	358.357	7.983	-4.621	0.09
10	358.297	7.983	-4.627	0.10
11	358.297	7.983	-4.627	0.10
12	358.238	7.983	-4.633	0.10
13	358.208	7.983	-4.636	0.11
14	358.118	7.983	-4.645	0.11
15	358.148	7.983	-4.642	0.11
16	358.118	7.983	-4.645	0.11
17	358.029	7.983	-4.655	0.13
18	357.94	7.983	-4.664	0.13
19	357.91	7.983	-4.667	0.14
20	357.88	7.983	-4.67	0.14
21	357.91	7.983	-4.667	0.14
22	357.91	7.983	-4.667	0.14
23	357.91	7.983	-4.667	0.14
24	357.94	7.983	-4.664	0.13
25	357.94	7.983	-4.664	0.13
26	357.94	7.983	-4.664	0.13
27	357.94	7.983	-4.664	0.13
28	357.969	7.983	-4.661	0.13
29	357.94	7.983	-4.664	0.13
30	357.999	7.983	-4.658	0.13
31	357.969	7.983	-4.661	0.13
32	357.999	7.983	-4.658	0.13
33	357.969	7.983	-4.661	0.13
34	358.029	7.983	-4.655	0.13
35	357.91	7.983	-4.667	0.14
36	357.969	7.983	-4.661	0.13
37	357.969	7.983	-4.661	0.13
38	357.91	7.983	-4.667	0.14
39	357.88	7.983	-4.67	0.14
40	357.82	7.983	-4.676	0.15
41	357.85	7.983	-4.673	0.14
42	357.82	7.983	-4.676	0.15
43	357.791	7.983	-4.679	0.15
44	357.791	7.983	-4.679	0.15
45	357.791	7.983	-4.679	0.15
46	357.791	7.983	-4.679	0.15
47	357.82	7.983	-4.676	0.15
48	357.82	7.983	-4.676	0.15
49	357.672	7.983	-4.691	0.16
50	357.731	7.983	-4.685	0.15
51	357.701	7.983	-4.688	0.16
52	357.672	7.983	-4.691	0.16
53	357.642	7.983	-4.694	0.16
54	357.701	7.983	-4.688	0.16
55	357.642	7.983	-4.694	0.16
56	357.612	7.983	-4.697	0.17
57	357.672	7.983	-4.691	0.16
58	357.672	7.983	-4.691	0.16
59	357.463	7.983	-4.712	0.18
60	357.582	7.983	-4.7	0.17
61	357.582	7.983	-4.7	0.17
62	357.612	7.983	-4.697	0.17
63	357.582	7.983	-4.7	0.17
64	357.552	7.983	-4.703	0.17
65	357.552	7.983	-4.703	0.17
66	357.642	7.983	-4.694	0.16
67	357.523	7.983	-4.706	0.18
68	357.552	7.983	-4.703	0.17
69	357.582	7.983	-4.7	0.17
70	357.582	7.983	-4.7	0.17
71	357.582	7.983	-4.7	0.17
72	357.582	7.983	-4.7	0.17
73	357.523	7.983	-4.706	0.18
74	357.523	7.983	-4.706	0.18
75	357.523	7.983	-4.706	0.18
76	357.552	7.983	-4.703	0.17
77	357.552	7.983	-4.703	0.17
78	357.582	7.983	-4.7	0.17
79	357.582	7.983	-4.7	0.17
80	357.552	7.983	-4.703	0.17
81	357.344	7.983	-4.724	0.19
82	357.374	7.983	-4.721	0.19
83	357.403	7.983	-4.718	0.19
84	357.403	7.983	-4.718	0.19
85	357.284	7.983	-4.73	0.20

86	357.284	7.983	-4.73	0.20
87	357.314	7.983	-4.727	0.20
88	357.344	7.983	-4.724	0.19
89	357.284	7.983	-4.73	0.20
90	357.255	7.983	-4.733	0.20
91	357.284	7.983	-4.73	0.20
92	357.255	7.983	-4.733	0.20
93	357.255	7.983	-4.733	0.20
94	357.225	7.983	-4.736	0.21
95	357.284	7.983	-4.73	0.20
96	357.314	7.983	-4.727	0.20
97	357.374	7.983	-4.721	0.19
98	357.344	7.983	-4.724	0.19
99	357.344	7.983	-4.724	0.19
100	357.403	7.983	-4.718	0.19
101	357.374	7.983	-4.721	0.19
102	357.403	7.983	-4.718	0.19
103	357.344	7.983	-4.724	0.19
104	357.374	7.983	-4.721	0.19
105	357.374	7.983	-4.721	0.19
106	357.374	7.983	-4.721	0.19
107	357.403	7.983	-4.718	0.19
108	357.403	7.983	-4.718	0.19
109	357.403	7.983	-4.718	0.19
110	357.403	7.983	-4.718	0.19
111	357.433	7.983	-4.715	0.19
112	357.403	7.983	-4.718	0.19
113	357.433	7.983	-4.715	0.19
114	357.433	7.983	-4.715	0.19
115	357.433	7.983	-4.715	0.19
116	357.433	7.983	-4.715	0.19
117	357.463	7.983	-4.712	0.18
118	357.433	7.983	-4.715	0.19
119	357.403	7.983	-4.718	0.19
120	357.463	7.983	-4.712	0.18
121	357.523	7.983	-4.706	0.18
122	357.374	7.983	-4.721	0.19
123	357.523	7.983	-4.706	0.18
124	357.552	7.983	-4.703	0.17
125	357.433	7.983	-4.715	0.19
126	357.463	7.983	-4.712	0.18
127	357.433	7.983	-4.715	0.19
128	357.433	7.983	-4.715	0.19
129	357.374	7.983	-4.721	0.19
130	357.463	7.983	-4.712	0.18
131	357.403	7.983	-4.718	0.19
132	357.403	7.983	-4.718	0.19
133	357.374	7.983	-4.721	0.19
134	357.433	7.983	-4.715	0.19
135	357.403	7.983	-4.718	0.19
136	357.284	7.983	-4.73	0.20
137	357.403	7.983	-4.718	0.19
138	357.374	7.983	-4.721	0.19
139	357.374	7.983	-4.721	0.19
140	357.403	7.983	-4.718	0.19
141	357.374	7.983	-4.721	0.19
142	357.225	7.983	-4.736	0.21
143	357.284	7.983	-4.73	0.20
144	357.284	7.983	-4.73	0.20
145	357.344	7.983	-4.724	0.19
146	357.284	7.983	-4.73	0.20
147	357.314	7.983	-4.727	0.20
148	357.344	7.983	-4.724	0.19
149	357.403	7.983	-4.718	0.19
150	357.284	7.983	-4.73	0.20
151	357.284	7.983	-4.73	0.20
152	357.284	7.983	-4.73	0.20
153	357.195	7.983	-4.74	0.21
154	357.255	7.983	-4.733	0.20
155	357.225	7.983	-4.736	0.21
156	357.314	7.983	-4.727	0.20
157	357.314	7.983	-4.727	0.20
158	357.255	7.983	-4.733	0.20
159	357.284	7.983	-4.73	0.20
160	357.165	7.983	-4.743	0.21
161	357.195	7.983	-4.74	0.21
162	357.284	7.983	-4.73	0.20
163	357.225	7.983	-4.736	0.21
164	357.195	7.983	-4.74	0.21
165	357.225	7.983	-4.736	0.21
166	357.255	7.983	-4.733	0.20
167	357.195	7.983	-4.74	0.21
168	357.165	7.983	-4.743	0.21
169	357.165	7.983	-4.743	0.21
170	357.165	7.983	-4.743	0.21
171	357.225	7.983	-4.736	0.21
172	357.195	7.983	-4.74	0.21
173	357.255	7.983	-4.733	0.20
174	357.255	7.983	-4.733	0.20
175	357.284	7.983	-4.73	0.20
176	357.255	7.983	-4.733	0.20

177	357.195	7.983	-4.74	0.21
178	357.255	7.983	-4.733	0.20
179	357.255	7.983	-4.733	0.20
180	357.284	7.983	-4.73	0.20
181	357.255	7.983	-4.733	0.20
182	357.344	7.983	-4.724	0.19
183	357.344	7.983	-4.724	0.19
184	357.344	7.983	-4.724	0.19
185	357.284	7.983	-4.73	0.20
186	357.314	7.983	-4.727	0.20
187	357.284	7.983	-4.73	0.20
188	357.314	7.983	-4.727	0.20
189	357.314	7.983	-4.727	0.20
190	357.284	7.983	-4.73	0.20
191	357.284	7.983	-4.73	0.20
192	357.225	7.983	-4.736	0.21
193	357.344	7.983	-4.724	0.19
194	357.195	7.983	-4.74	0.21
195	357.314	7.983	-4.727	0.20
196	357.255	7.983	-4.733	0.20
197	357.284	7.983	-4.73	0.20
198	357.284	7.983	-4.73	0.20
199	357.225	7.983	-4.736	0.21
200	357.225	7.983	-4.736	0.21
201	357.255	7.983	-4.733	0.20
202	357.255	7.983	-4.733	0.20
203	357.284	7.983	-4.73	0.20
204	357.255	7.983	-4.733	0.20
205	357.314	7.983	-4.727	0.20
206	357.255	7.983	-4.733	0.20
207	357.225	7.983	-4.736	0.21
208	357.284	7.983	-4.73	0.20
209	357.314	7.983	-4.727	0.20
210	357.314	7.983	-4.727	0.20
211	357.284	7.983	-4.73	0.20
212	357.344	7.983	-4.724	0.19
213	357.344	7.983	-4.724	0.19
214	357.374	7.983	-4.721	0.19
215	357.374	7.983	-4.721	0.19
216	357.314	7.983	-4.727	0.20
217	357.344	7.983	-4.724	0.19
218	357.344	7.983	-4.724	0.19
219	357.314	7.983	-4.727	0.20
220	357.284	7.983	-4.73	0.20
221	357.374	7.983	-4.721	0.19
222	357.314	7.983	-4.727	0.20
223	357.374	7.983	-4.721	0.19
224	357.314	7.983	-4.727	0.20
225	357.225	7.983	-4.736	0.21
226	357.284	7.983	-4.73	0.20
227	357.255	7.983	-4.733	0.20
228	357.225	7.983	-4.736	0.21
229	357.165	7.983	-4.743	0.21
230	357.135	7.983	-4.746	0.22
231	357.165	7.983	-4.743	0.21
232	357.135	7.983	-4.746	0.22
233	357.135	7.983	-4.746	0.22
234	357.165	7.983	-4.743	0.21
235	357.165	7.983	-4.743	0.21
236	357.135	7.983	-4.746	0.22
237	357.106	7.983	-4.749	0.22
238	357.165	7.983	-4.743	0.21
239	357.046	7.983	-4.755	0.23
240	357.135	7.983	-4.746	0.22
241	357.106	7.983	-4.749	0.22
242	357.076	7.983	-4.752	0.22
243	357.195	7.983	-4.74	0.21
244	357.165	7.983	-4.743	0.21
245	357.165	7.983	-4.743	0.21
246	357.165	7.983	-4.743	0.21
247	357.165	7.983	-4.743	0.21
248	357.195	7.983	-4.74	0.21
249	357.135	7.983	-4.746	0.22
250	357.165	7.983	-4.743	0.21
251	357.195	7.983	-4.74	0.21
252	357.195	7.983	-4.74	0.21
253	357.016	7.983	-4.758	0.23
254	357.076	7.983	-4.752	0.22
255	357.106	7.983	-4.749	0.22
256	357.106	7.983	-4.749	0.22
257	357.165	7.983	-4.743	0.21
258	357.135	7.983	-4.746	0.22
259	357.106	7.983	-4.749	0.22
260	357.106	7.983	-4.749	0.22
261	357.135	7.983	-4.746	0.22
262	356.986	7.983	-4.761	0.23
263	357.016	7.983	-4.758	0.23
264	357.076	7.983	-4.752	0.22
265	356.986	7.983	-4.761	0.23
266	357.046	7.983	-4.755	0.23
267	357.016	7.983	-4.758	0.23

268	356.986	7.983	-4.761	0.23
269	357.046	7.983	-4.755	0.23
270	357.076	7.983	-4.752	0.22
271	357.016	7.983	-4.758	0.23
272	357.076	7.983	-4.752	0.22
273	357.106	7.983	-4.749	0.22
274	356.957	7.983	-4.764	0.23
275	357.135	7.983	-4.746	0.22
276	357.076	7.983	-4.752	0.22
277	357.165	7.983	-4.743	0.21
278	357.225	7.983	-4.736	0.21
279	357.165	7.983	-4.743	0.21
280	357.195	7.983	-4.74	0.21
281	357.225	7.983	-4.736	0.21
282	357.195	7.983	-4.74	0.21
283	357.255	7.983	-4.733	0.20
284	357.225	7.983	-4.736	0.21
285	357.195	7.983	-4.74	0.21
286	357.135	7.983	-4.746	0.22
287	357.135	7.983	-4.746	0.22
288	357.195	7.983	-4.74	0.21
289	357.046	7.983	-4.755	0.23
290	357.046	7.983	-4.755	0.23
291	357.106	7.983	-4.749	0.22
292	357.106	7.983	-4.749	0.22
293	357.106	7.983	-4.749	0.22
294	357.135	7.983	-4.746	0.22
295	357.165	7.983	-4.743	0.21
296	357.135	7.983	-4.746	0.22
297	357.135	7.983	-4.746	0.22
298	357.135	7.983	-4.746	0.22
299	357.165	7.983	-4.743	0.21
300	357.195	7.983	-4.74	0.21
301	357.165	7.983	-4.743	0.21
302	357.165	7.983	-4.743	0.21
303	357.165	7.983	-4.743	0.21
304	357.195	7.983	-4.74	0.21
305	357.165	7.983	-4.743	0.21
306	357.135	7.983	-4.746	0.22
307	357.135	7.983	-4.746	0.22
308	357.135	7.983	-4.746	0.22
309	357.195	7.983	-4.74	0.21
310	357.165	7.983	-4.743	0.21
311	357.165	7.983	-4.743	0.21
312	357.135	7.983	-4.746	0.22
313	357.106	7.983	-4.749	0.22
314	357.076	7.983	-4.752	0.22
315	357.046	7.983	-4.755	0.23
316	357.046	7.983	-4.755	0.23
317	356.957	7.983	-4.764	0.23
318	356.927	7.983	-4.767	0.24
319	356.927	7.983	-4.767	0.24
320	356.986	7.983	-4.761	0.23
321	356.957	7.983	-4.764	0.23
322	356.927	7.983	-4.767	0.24
323	356.897	7.983	-4.77	0.24
324	356.867	7.983	-4.773	0.24
325	356.838	7.983	-4.776	0.25
326	356.897	7.983	-4.77	0.24
327	356.927	7.983	-4.767	0.24
328	356.897	7.983	-4.77	0.24
329	356.927	7.983	-4.767	0.24
330	357.016	7.983	-4.758	0.23
331	356.986	7.983	-4.761	0.23
332	356.897	7.983	-4.77	0.24
333	356.897	7.983	-4.77	0.24
334	356.897	7.983	-4.77	0.24
335	356.897	7.983	-4.77	0.24
336	356.927	7.983	-4.767	0.24
337	356.897	7.983	-4.77	0.24
338	356.957	7.983	-4.764	0.23
339	356.897	7.983	-4.77	0.24
340	356.897	7.983	-4.77	0.24
341	356.867	7.983	-4.773	0.24
342	356.897	7.983	-4.77	0.24
343	356.927	7.983	-4.767	0.24
344	356.957	7.983	-4.764	0.23
345	356.897	7.983	-4.77	0.24
346	356.838	7.983	-4.776	0.25
347	356.867	7.983	-4.773	0.24
348	356.867	7.983	-4.773	0.24
349	356.778	7.983	-4.782	0.25
350	356.808	7.983	-4.779	0.25
351	356.838	7.983	-4.776	0.25
352	356.808	7.983	-4.779	0.25
353	356.838	7.983	-4.776	0.25
354	356.927	7.983	-4.767	0.24
355	356.927	7.983	-4.767	0.24
356	356.927	7.983	-4.767	0.24
357	356.986	7.983	-4.761	0.23
358	356.986	7.983	-4.761	0.23

## TW3- WELL RECOVERY VS. TIME - KOLLAARD FILE 210064



## RECOVERY DATA TW-3

t'	t / t'	Abs Pres (kPa)	Temp (°C)	Water Level (m)	Drawdown (m)	Recovery (%)
1	359.0	357.195	7.983	-4.74	95.24	
2	180.0	357.344	7.983	-4.724	95.22	
3	120.3	357.433	7.983	-4.715	0.19	12%
4	90.5	357.493	7.983	-4.709	0.18	15%
5	72.6	357.582	7.983	-4.7	0.17	19%
6	60.7	357.672	7.983	-4.691	0.16	23%
7	52.1	357.731	7.983	-4.685	0.15	26%
8	45.8	357.761	7.983	-4.682	0.15	28%
9	40.8	357.82	7.983	-4.676	0.15	30%
10	36.8	357.85	7.983	-4.673	0.14	32%
11	33.5	357.94	7.983	-4.664	0.13	36%
12	30.8	357.88	7.983	-4.67	0.14	33%
13	28.5	357.94	7.983	-4.664	0.13	36%
14	26.6	357.969	7.983	-4.661	0.13	38%
15	24.9	357.999	7.983	-4.658	0.13	39%
16	23.4	358.089	7.983	-4.648	0.12	44%
17	22.1	358.059	7.983	-4.651	0.12	42%
18	20.9	358.089	7.983	-4.648	0.12	44%
19	19.8	358.089	7.983	-4.648	0.12	44%
20	18.9	358.267	7.983	-4.63	0.10	52%
21	18.0	358.178	7.983	-4.639	0.11	48%
22	17.3	358.238	7.983	-4.633	0.10	51%
23	16.6	357.94	7.983	-4.664	0.13	36%
24	15.9	358.297	7.983	-4.627	0.10	54%
25	15.3	358.327	7.983	-4.624	0.09	55%
26	14.8	358.357	7.983	-4.621	0.09	57%
27	14.3	358.357	7.983	-4.621	0.09	57%
28	13.8	358.327	7.983	-4.624	0.09	55%
29	13.3	358.357	7.983	-4.621	0.09	57%
30	12.9	358.327	7.983	-4.624	0.09	55%
31	12.5	358.416	7.983	-4.615	0.09	60%
32	12.2	358.446	7.983	-4.612	0.08	61%
33	11.8	358.476	7.983	-4.609	0.08	62%
34	11.5	358.476	7.983	-4.609	0.08	62%
35	11.2	358.446	7.983	-4.612	0.08	61%
36	10.9	358.506	7.983	-4.606	0.08	64%
37	10.7	358.565	7.983	-4.6	0.07	67%
38	10.4	358.565	7.983	-4.6	0.07	67%
39	10.2	358.595	7.983	-4.597	0.07	68%
40	10.0	358.595	7.983	-4.597	0.07	68%
41	9.7	358.625	7.983	-4.594	0.06	70%
42	9.5	358.625	7.983	-4.594	0.06	70%
43	9.3	358.625	7.983	-4.594	0.06	70%
44	9.1	358.655	7.983	-4.591	0.06	71%
45	9.0	358.684	7.983	-4.588	0.06	72%
46	8.8	358.684	7.983	-4.588	0.06	72%

47	8.6	358.655	7.983	-4.591	0.06	71%
48	8.5	358.655	7.983	-4.591	0.06	71%
49	8.3	358.714	7.983	-4.585	0.05	74%
50	8.2	358.714	7.983	-4.585	0.05	74%
51	8.0	358.714	7.983	-4.585	0.05	74%
52	7.9	358.744	7.983	-4.582	0.05	75%
53	7.8	358.744	7.983	-4.582	0.05	75%
54	7.6	358.774	7.983	-4.579	0.05	77%
55	7.5	358.774	7.983	-4.579	0.05	77%
56	7.4	358.684	7.983	-4.588	0.06	72%
57	7.3	358.655	7.983	-4.591	0.06	71%
58	7.2	358.655	7.983	-4.591	0.06	71%
59	7.1	358.684	7.983	-4.588	0.06	72%
60	7.0	358.595	7.983	-4.597	0.07	68%
61	6.9	358.535	7.983	-4.603	0.07	65%
62	6.8	358.595	7.983	-4.597	0.07	68%
63	6.7	358.595	7.983	-4.597	0.07	68%
64	6.6	358.625	7.983	-4.594	0.06	70%
65	6.5	358.655	7.983	-4.591	0.06	71%
66	6.4	358.655	7.983	-4.591	0.06	71%
67	6.3	358.714	7.983	-4.585	0.05	74%
68	6.3	358.714	7.983	-4.585	0.05	74%
69	6.2	358.714	7.983	-4.585	0.05	74%
70	6.1	358.714	7.983	-4.585	0.05	74%
71	6.0	358.714	7.983	-4.585	0.05	74%
72	6.0	358.744	7.983	-4.582	0.05	75%
73	5.9	358.744	7.983	-4.582	0.05	75%
74	5.8	358.744	7.983	-4.582	0.05	75%
75	5.8	358.803	7.983	-4.576	0.05	78%
76	5.7	358.803	7.983	-4.576	0.05	78%
77	5.6	358.803	7.983	-4.576	0.05	78%
78	5.6	358.833	7.983	-4.573	0.04	80%
79	5.5	358.833	7.983	-4.573	0.04	80%
80	5.5	358.863	7.983	-4.569	0.04	81%
81	5.4	358.893	7.983	-4.566	0.04	83%
82	5.4	358.833	7.983	-4.573	0.04	80%
83	5.3	358.863	7.983	-4.569	0.04	81%
84	5.3	358.893	7.983	-4.566	0.04	83%
85	5.2	358.893	7.983	-4.566	0.04	83%
86	5.2	358.893	7.983	-4.566	0.04	83%
87	5.1	358.893	7.983	-4.566	0.04	83%
88	5.1	358.923	7.983	-4.563	0.03	84%
89	5.0	358.863	7.983	-4.569	0.04	81%
90	5.0	358.863	7.983	-4.569	0.04	81%
91	4.9	358.893	7.983	-4.566	0.04	83%
92	4.9	358.923	7.983	-4.563	0.03	84%
93	4.8	358.893	7.983	-4.566	0.04	83%
94	4.8	358.923	7.983	-4.563	0.03	84%
95	4.8	358.952	7.983	-4.56	0.03	86%
96	4.7	358.923	7.983	-4.563	0.03	84%

97	4.7	358.982	7.983	-4.557	0.03	87%
98	4.7	359.012	7.983	-4.554	0.02	89%
99	4.6	358.982	7.983	-4.557	0.03	87%
100	4.6	359.012	7.983	-4.554	0.02	89%
101	4.5	359.072	7.983	-4.548	0.02	91%
102	4.5	359.042	7.983	-4.551	0.02	90%
103	4.5	359.042	7.983	-4.551	0.02	90%
104	4.4	358.982	7.983	-4.557	0.03	87%
105	4.4	359.012	7.983	-4.554	0.02	89%
106	4.4	359.042	7.983	-4.551	0.02	90%
107	4.3	359.042	7.983	-4.551	0.02	90%
108	4.3	359.012	7.983	-4.554	0.02	89%
109	4.3	359.072	7.983	-4.548	0.02	91%
110	4.3	359.072	7.983	-4.548	0.02	91%
111	4.2	359.042	7.983	-4.551	0.02	90%
112	4.2	359.012	7.983	-4.554	0.02	89%
113	4.2	359.042	7.983	-4.551	0.02	90%
114	4.1	359.072	7.983	-4.548	0.02	91%
115	4.1	359.101	7.983	-4.545	0.01	93%
116	4.1	359.042	7.983	-4.551	0.02	90%
117	4.1	359.072	7.983	-4.548	0.02	91%
118	4.0	359.072	7.983	-4.548	0.02	91%
119	4.0	359.072	7.983	-4.548	0.02	91%
120	4.0	359.072	7.983	-4.548	0.02	91%
121	4.0	359.042	7.983	-4.551	0.02	90%
122	3.9	359.072	7.983	-4.548	0.02	91%
123	3.9	359.072	7.983	-4.548	0.02	91%
124	3.9	359.072	7.983	-4.548	0.02	91%
125	3.9	359.042	7.983	-4.551	0.02	90%
126	3.8	359.012	7.983	-4.554	0.02	89%
127	3.8	359.012	7.983	-4.554	0.02	89%
128	3.8	359.012	7.983	-4.554	0.02	89%
129	3.8	358.952	7.983	-4.56	0.03	86%
130	3.8	358.952	7.983	-4.56	0.03	86%
131	3.7	358.982	7.983	-4.557	0.03	87%
132	3.7	358.952	7.983	-4.56	0.03	86%
133	3.7	358.982	7.983	-4.557	0.03	87%
134	3.7	358.863	7.983	-4.569	0.04	81%
135	3.7	358.923	7.983	-4.563	0.03	84%
136	3.6	358.952	7.983	-4.56	0.03	86%
137	3.6	358.952	7.983	-4.56	0.03	86%
138	3.6	358.893	7.983	-4.566	0.04	83%
139	3.6	358.923	7.983	-4.563	0.03	84%
140	3.6	358.923	7.983	-4.563	0.03	84%
141	3.5	358.923	7.983	-4.563	0.03	84%
142	3.5	358.923	7.983	-4.563	0.03	84%
143	3.5	358.923	7.983	-4.563	0.03	84%
144	3.5	358.923	7.983	-4.563	0.03	84%
145	3.5	358.923	7.983	-4.563	0.03	84%
146	3.5	358.923	7.983	-4.563	0.03	84%

147	3.4	358.923	7.983	-4.563	0.03	84%
148	3.4	358.923	7.983	-4.563	0.03	84%
149	3.4	358.952	7.983	-4.56	0.03	86%
150	3.4	358.923	7.983	-4.563	0.03	84%
151	3.4	358.833	7.983	-4.573	0.04	80%
152	3.4	358.952	7.983	-4.56	0.03	86%
153	3.3	358.952	7.983	-4.56	0.03	86%
154	3.3	358.952	7.983	-4.56	0.03	86%
155	3.3	358.833	7.983	-4.573	0.04	80%
156	3.3	358.923	7.983	-4.563	0.03	84%
157	3.3	358.923	7.983	-4.563	0.03	84%
158	3.3	358.923	7.983	-4.563	0.03	84%
159	3.3	358.833	7.983	-4.573	0.04	80%
160	3.2	358.833	7.983	-4.573	0.04	80%
161	3.2	358.893	7.983	-4.566	0.04	83%
162	3.2	358.923	7.983	-4.563	0.03	84%
163	3.2	358.952	7.983	-4.56	0.03	86%
164	3.2	358.803	7.983	-4.576	0.05	78%
165	3.2	358.923	7.983	-4.563	0.03	84%
166	3.2	358.952	7.983	-4.56	0.03	86%
167	3.1	358.923	7.983	-4.563	0.03	84%
168	3.1	358.982	7.983	-4.557	0.03	87%
169	3.1	358.893	7.983	-4.566	0.04	83%
170	3.1	358.982	7.983	-4.557	0.03	87%
171	3.1	358.982	7.983	-4.557	0.03	87%
172	3.1	358.982	7.983	-4.557	0.03	87%
173	3.1	358.923	7.983	-4.563	0.03	84%
174	3.1	358.952	7.983	-4.56	0.03	86%
175	3.0	358.982	7.983	-4.557	0.03	87%
176	3.0	359.012	7.983	-4.554	0.02	89%
177	3.0	358.982	7.983	-4.557	0.03	87%
178	3.0	358.982	7.983	-4.557	0.03	87%
179	3.0	358.982	7.983	-4.557	0.03	87%
180	3.0	358.952	7.983	-4.56	0.03	86%
181	3.0	358.863	7.983	-4.569	0.04	81%
182	3.0	358.893	7.983	-4.566	0.04	83%
183	3.0	358.923	7.983	-4.563	0.03	84%
184	2.9	358.982	7.983	-4.557	0.03	87%
185	2.9	359.042	7.983	-4.551	0.02	90%
186	2.9	359.042	7.983	-4.551	0.02	90%
187	2.9	359.042	7.983	-4.551	0.02	90%
188	2.9	359.042	7.983	-4.551	0.02	90%
189	2.9	359.042	7.983	-4.551	0.02	90%
190	2.9	359.012	7.983	-4.554	0.02	89%
191	2.9	359.072	7.983	-4.548	0.02	91%
192	2.9	359.101	7.983	-4.545	0.01	93%
193	2.9	359.072	7.983	-4.548	0.02	91%
194	2.8	359.072	7.983	-4.548	0.02	91%
195	2.8	359.101	7.983	-4.545	0.01	93%
196	2.8	359.101	7.983	-4.545	0.01	93%

197	2.8	359.131	7.983	-4.542	0.01	94%
198	2.8	359.131	7.983	-4.542	0.01	94%
199	2.8	359.042	7.983	-4.551	0.02	90%
200	2.8	359.042	7.983	-4.551	0.02	90%
201	2.8	359.042	7.983	-4.551	0.02	90%
202	2.8	359.101	7.983	-4.545	0.01	93%
203	2.8	359.072	7.983	-4.548	0.02	91%
204	2.8	359.072	7.983	-4.548	0.02	91%
205	2.7	359.072	7.983	-4.548	0.02	91%
206	2.7	359.042	7.983	-4.551	0.02	90%
207	2.7	359.042	7.983	-4.551	0.02	90%
208	2.7	359.042	7.983	-4.551	0.02	90%
209	2.7	358.774	7.983	-4.579	0.05	77%
210	2.7	358.982	7.983	-4.557	0.03	87%
211	2.7	359.012	7.983	-4.554	0.02	89%
212	2.7	359.012	7.983	-4.554	0.02	89%
213	2.7	358.982	7.983	-4.557	0.03	87%
214	2.7	358.982	7.983	-4.557	0.03	87%
215	2.7	358.923	7.983	-4.563	0.03	84%
216	2.7	358.893	7.983	-4.566	0.04	83%
217	2.6	358.833	7.983	-4.573	0.04	80%
218	2.6	358.863	7.983	-4.569	0.04	81%
219	2.6	358.893	7.983	-4.566	0.04	83%
220	2.6	358.893	7.983	-4.566	0.04	83%
221	2.6	358.893	7.983	-4.566	0.04	83%
222	2.6	358.923	7.983	-4.563	0.03	84%
223	2.6	358.893	7.983	-4.566	0.04	83%
224	2.6	358.893	7.983	-4.566	0.04	83%
225	2.6	358.774	7.983	-4.579	0.05	77%
226	2.6	358.893	7.983	-4.566	0.04	83%
227	2.6	358.893	7.983	-4.566	0.04	83%
228	2.6	358.863	7.983	-4.569	0.04	81%
229	2.6	358.833	7.983	-4.573	0.04	80%
230	2.6	358.863	7.983	-4.569	0.04	81%
231	2.5	358.863	7.983	-4.569	0.04	81%
232	2.5	358.893	7.983	-4.566	0.04	83%
233	2.5	358.863	7.983	-4.569	0.04	81%
234	2.5	358.863	7.983	-4.569	0.04	81%
235	2.5	358.863	7.983	-4.569	0.04	81%
236	2.5	358.893	7.983	-4.566	0.04	83%
237	2.5	358.863	7.983	-4.569	0.04	81%
238	2.5	358.863	7.983	-4.569	0.04	81%
239	2.5	358.893	7.983	-4.566	0.04	83%
240	2.5	358.923	7.983	-4.563	0.03	84%
241	2.5	358.952	7.983	-4.56	0.03	86%
242	2.5	358.923	7.983	-4.563	0.03	84%
243	2.5	358.952	7.983	-4.56	0.03	86%
244	2.5	358.982	7.983	-4.557	0.03	87%
245	2.5	358.982	7.983	-4.557	0.03	87%
246	2.5	358.952	7.983	-4.56	0.03	86%

247	2.4	359.012	7.983	-4.554	0.02	89%
248	2.4	359.012	7.983	-4.554	0.02	89%
249	2.4	359.042	7.983	-4.551	0.02	90%
250	2.4	359.042	7.983	-4.551	0.02	90%
251	2.4	359.101	7.983	-4.545	0.01	93%
252	2.4	359.042	7.983	-4.551	0.02	90%
253	2.4	359.131	7.983	-4.542	0.01	94%
254	2.4	359.101	7.983	-4.545	0.01	93%
255	2.4	358.863	7.983	-4.569	0.04	81%
256	2.4	358.982	7.983	-4.557	0.03	87%
257	2.4	358.952	7.983	-4.56	0.03	86%
258	2.4	358.952	7.983	-4.56	0.03	86%
259	2.4	358.923	7.983	-4.563	0.03	84%
260	2.4	358.923	7.983	-4.563	0.03	84%
261	2.4	358.893	7.983	-4.566	0.04	83%
262	2.4	358.952	7.983	-4.56	0.03	86%
263	2.4	358.923	7.983	-4.563	0.03	84%
264	2.4	358.893	7.983	-4.566	0.04	83%
265	2.4	358.923	7.983	-4.563	0.03	84%
266	2.3	358.923	7.983	-4.563	0.03	84%
267	2.3	358.952	7.983	-4.56	0.03	86%
268	2.3	358.923	7.983	-4.563	0.03	84%
269	2.3	358.923	7.983	-4.563	0.03	84%
270	2.3	358.982	7.983	-4.557	0.03	87%
271	2.3	359.012	7.983	-4.554	0.02	89%
272	2.3	358.863	7.983	-4.569	0.04	81%
273	2.3	358.923	7.983	-4.563	0.03	84%
274	2.3	358.952	7.983	-4.56	0.03	86%
275	2.3	358.952	7.983	-4.56	0.03	86%
276	2.3	358.952	7.983	-4.56	0.03	86%
277	2.3	358.893	7.983	-4.566	0.04	83%
278	2.3	358.982	7.983	-4.557	0.03	87%
279	2.3	359.012	7.983	-4.554	0.02	89%
280	2.3	358.982	7.983	-4.557	0.03	87%
281	2.3	358.982	7.983	-4.557	0.03	87%
282	2.3	358.893	7.983	-4.566	0.04	83%
283	2.3	358.863	7.983	-4.569	0.04	81%
284	2.3	358.982	7.983	-4.557	0.03	87%
285	2.3	358.982	7.983	-4.557	0.03	87%
286	2.3	358.982	7.983	-4.557	0.03	87%
287	2.2	359.012	7.983	-4.554	0.02	89%
288	2.2	359.012	7.983	-4.554	0.02	89%
289	2.2	358.952	7.983	-4.56	0.03	86%
290	2.2	358.952	7.983	-4.56	0.03	86%
291	2.2	358.952	7.983	-4.56	0.03	86%
292	2.2	358.863	7.983	-4.569	0.04	81%
293	2.2	358.863	7.983	-4.569	0.04	81%
294	2.2	358.893	7.983	-4.566	0.04	83%
295	2.2	358.893	7.983	-4.566	0.04	83%
296	2.2	358.952	7.983	-4.56	0.03	86%

297	2.2	358.923	7.983	-4.563	0.03	84%
298	2.2	358.833	7.983	-4.573	0.04	80%
299	2.2	358.684	7.983	-4.588	0.06	72%
300	2.2	358.744	7.983	-4.582	0.05	75%
301	2.2	358.714	7.983	-4.585	0.05	74%
302	2.2	358.446	7.983	-4.612	0.08	61%
303	2.2	358.506	7.983	-4.606	0.08	64%
304	2.2	358.625	7.983	-4.594	0.06	70%
305	2.2	358.655	7.983	-4.591	0.06	71%
306	2.2	358.595	7.983	-4.597	0.07	68%
307	2.2	358.595	7.983	-4.597	0.07	68%
308	2.2	358.595	7.983	-4.597	0.07	68%
309	2.2	358.625	7.983	-4.594	0.06	70%
310	2.2	358.625	7.983	-4.594	0.06	70%
311	2.2	358.655	7.983	-4.591	0.06	71%
312	2.1	358.655	7.983	-4.591	0.06	71%
313	2.1	358.684	7.983	-4.588	0.06	72%
314	2.1	358.655	7.983	-4.591	0.06	71%
315	2.1	358.684	7.983	-4.588	0.06	72%
316	2.1	358.684	7.983	-4.588	0.06	72%
317	2.1	358.714	7.983	-4.585	0.05	74%
318	2.1	358.714	7.983	-4.585	0.05	74%
319	2.1	358.595	7.983	-4.597	0.07	68%
320	2.1	358.506	7.983	-4.606	0.08	64%
321	2.1	358.595	7.983	-4.597	0.07	68%
322	2.1	358.595	7.983	-4.597	0.07	68%
323	2.1	358.595	7.983	-4.597	0.07	68%
324	2.1	358.595	7.983	-4.597	0.07	68%
325	2.1	358.625	7.983	-4.594	0.06	70%
326	2.1	358.655	7.983	-4.591	0.06	71%
327	2.1	358.655	7.983	-4.591	0.06	71%
328	2.1	358.655	7.983	-4.591	0.06	71%
329	2.1	358.535	7.983	-4.603	0.07	65%
330	2.1	358.625	7.983	-4.594	0.06	70%
331	2.1	358.684	7.983	-4.588	0.06	72%
332	2.1	358.655	7.983	-4.591	0.06	71%
333	2.1	358.714	7.983	-4.585	0.05	74%
334	2.1	358.684	7.983	-4.588	0.06	72%
335	2.1	358.625	7.983	-4.594	0.06	70%
336	2.1	358.506	7.983	-4.606	0.08	64%
337	2.1	358.565	7.983	-4.6	0.07	67%
338	2.1	358.506	7.983	-4.606	0.08	64%
339	2.1	358.565	7.983	-4.6	0.07	67%
340	2.1	358.565	7.983	-4.6	0.07	67%
341	2.0	358.625	7.983	-4.594	0.06	70%
342	2.0	358.684	7.983	-4.588	0.06	72%
343	2.0	358.714	7.983	-4.585	0.05	74%
344	2.0	358.684	7.983	-4.588	0.06	72%
345	2.0	358.714	7.983	-4.585	0.05	74%
346	2.0	358.744	7.983	-4.582	0.05	75%

347	2.0	358.744	7.983	-4.582	0.05	75%
348	2.0	358.714	7.983	-4.585	0.05	74%
349	2.0	358.684	7.983	-4.588	0.06	72%
350	2.0	358.714	7.983	-4.585	0.05	74%
351	2.0	358.714	7.983	-4.585	0.05	74%
352	2.0	358.595	7.983	-4.597	0.07	68%
353	2.0	358.655	7.983	-4.591	0.06	71%
354	2.0	358.625	7.983	-4.594	0.06	70%
355	2.0	358.655	7.983	-4.591	0.06	71%
356	2.0	358.684	7.983	-4.588	0.06	72%
357	2.0	358.684	7.983	-4.588	0.06	72%
358	2.0	358.684	7.983	-4.588	0.06	72%
359	2.0	358.744	7.983	-4.582	0.05	75%
360	2.0	358.714	7.983	-4.585	0.05	74%
361	2.0	358.774	7.983	-4.579	0.05	77%
362	2.0	358.714	7.983	-4.585	0.05	74%
363	2.0	358.714	7.983	-4.585	0.05	74%
364	2.0	358.744	7.983	-4.582	0.05	75%
365	2.0	358.744	7.983	-4.582	0.05	75%
366	2.0	358.714	7.983	-4.585	0.05	74%
367	2.0	358.714	7.983	-4.585	0.05	74%
368	2.0	358.744	7.983	-4.582	0.05	75%
369	2.0	358.655	7.983	-4.591	0.06	71%
370	2.0	358.655	7.983	-4.591	0.06	71%
371	2.0	358.595	7.983	-4.597	0.07	68%
372	2.0	358.625	7.983	-4.594	0.06	70%
373	2.0	358.684	7.983	-4.588	0.06	72%
374	2.0	358.684	7.983	-4.588	0.06	72%
375	2.0	358.625	7.983	-4.594	0.06	70%
376	2.0	358.655	7.983	-4.591	0.06	71%
377	1.9	358.565	7.983	-4.6	0.07	67%
378	1.9	358.595	7.983	-4.597	0.07	68%
379	1.9	358.595	7.983	-4.597	0.07	68%
380	1.9	358.565	7.983	-4.6	0.07	67%
381	1.9	358.684	7.983	-4.588	0.06	72%
382	1.9	358.655	7.983	-4.591	0.06	71%
383	1.9	358.714	7.983	-4.585	0.05	74%
384	1.9	358.655	7.983	-4.591	0.06	71%
385	1.9	358.714	7.983	-4.585	0.05	74%
386	1.9	358.684	7.983	-4.588	0.06	72%
387	1.9	358.714	7.983	-4.585	0.05	74%
388	1.9	358.684	7.983	-4.588	0.06	72%
389	1.9	358.714	7.983	-4.585	0.05	74%
390	1.9	358.714	7.983	-4.585	0.05	74%
391	1.9	358.744	7.983	-4.582	0.05	75%
392	1.9	358.744	7.983	-4.582	0.05	75%
393	1.9	358.774	7.983	-4.579	0.05	77%
394	1.9	358.744	7.983	-4.582	0.05	75%
395	1.9	358.774	7.983	-4.579	0.05	77%
396	1.9	358.774	7.983	-4.579	0.05	77%

397	1.9	358.744	7.983	-4.582	0.05	75%
398	1.9	358.774	7.983	-4.579	0.05	77%
399	1.9	358.774	7.983	-4.579	0.05	77%
400	1.9	358.774	7.983	-4.579	0.05	77%
401	1.9	358.684	7.983	-4.588	0.06	72%
402	1.9	358.744	7.983	-4.582	0.05	75%
403	1.9	358.774	7.983	-4.579	0.05	77%
404	1.9	358.774	7.983	-4.579	0.05	77%
405	1.9	358.774	7.983	-4.579	0.05	77%
406	1.9	358.684	7.983	-4.588	0.06	72%
407	1.9	358.714	7.983	-4.585	0.05	74%
408	1.9	358.744	7.983	-4.582	0.05	75%
409	1.9	358.774	7.983	-4.579	0.05	77%
410	1.9	358.744	7.983	-4.582	0.05	75%
411	1.9	358.774	7.983	-4.579	0.05	77%
412	1.9	358.744	7.983	-4.582	0.05	75%
413	1.9	358.803	7.983	-4.576	0.05	78%
414	1.9	358.833	7.983	-4.573	0.04	80%
415	1.9	358.863	7.983	-4.569	0.04	81%
416	1.9	358.863	7.983	-4.569	0.04	81%
417	1.9	358.893	7.983	-4.566	0.04	83%
418	1.9	358.863	7.983	-4.569	0.04	81%
419	1.9	358.893	7.983	-4.566	0.04	83%
420	1.9	358.923	7.983	-4.563	0.03	84%
421	1.9	358.893	7.983	-4.566	0.04	83%
422	1.8	358.893	7.983	-4.566	0.04	83%
423	1.8	358.893	7.983	-4.566	0.04	83%
424	1.8	358.982	7.983	-4.557	0.03	87%
425	1.8	358.982	7.983	-4.557	0.03	87%
426	1.8	358.982	7.983	-4.557	0.03	87%
427	1.8	359.012	7.983	-4.554	0.02	89%
428	1.8	359.012	7.983	-4.554	0.02	89%
429	1.8	359.042	7.983	-4.551	0.02	90%
430	1.8	359.012	7.983	-4.554	0.02	89%
431	1.8	359.042	7.983	-4.551	0.02	90%
432	1.8	359.072	7.983	-4.548	0.02	91%
433	1.8	359.042	7.983	-4.551	0.02	90%
434	1.8	359.072	7.983	-4.548	0.02	91%
435	1.8	359.131	7.983	-4.542	0.01	94%
436	1.8	359.101	7.983	-4.545	0.01	93%
437	1.8	359.072	7.983	-4.548	0.02	91%
438	1.8	359.161	7.983	-4.539	0.01	96%
439	1.8	359.131	7.983	-4.542	0.01	94%
440	1.8	359.131	7.983	-4.542	0.01	94%
441	1.8	359.161	7.983	-4.539	0.01	96%
442	1.8	359.191	7.983	-4.536	0.01	97%
443	1.8	359.191	7.983	-4.536	0.01	97%
444	1.8	359.191	7.983	-4.536	0.01	97%
445	1.8	359.25	7.983	-4.53	0.00	100%



Crestview Innovations Inc.  
May 10, 2023


## Hydrogeological Investigation and Terrain Evaluation

3200 Reids Lane, Ottawa, Ontario  
210064

### ATTACHMENT K

#### OBSERVATION WELL DATA USING PRESSURE TRANSDUCER LOGGERS

### Drawdown vs. Time in Observation Well During Pumping Test for TW2



### Drawdown vs. Time in Observation Well During Pumping Test for TW1

