Appendix A **Water** Supply Servicing August 1, 2019

# Appendix A WATER SUPPLY SERVICING

## A.1 DOMESTIC WATER DEMAND ESTIMATE



6102 Renaud Road - Based on Rosaline J. Hill Architect Inc. Site Plan 05/09/2019 (160401467)

Building ID	Area	Population	Daily Rate of	Avg Day	Demand	Max Day	Demand <sup>2</sup>	Peak Hour	Demand <sup>2</sup>
	(m <sup>2</sup> )		Demand 1	(L/min)	(L/s)	(L/min)	(L/s)	(L/min)	(L/s)
Townhomes		75.6	350	18.4	0.31	45.9	0.77	101.1	1.68
Back to Back, Stacked		36.8	350	8.9	0.15	22.4	0.37	49.2	0.82
Total Site :				27.3	0.46	68.3	1.14	150.3	2.50

<sup>1</sup> Population counts based on a conversion factor of 2.7 persons/townhome and 2.3 persons/2Duples

maximum day demand rate = 2.5 x average day demand rate peak hour demand rate = 2.2 x maximum day demand rate

Referenced from the City of Ottawa Design Guidelines: Water Distribution (July 2010)

<sup>2</sup> Average day water demand for residential areas equal to 350 L/cap/d

<sup>3</sup> The City of Ottawa water demand criteria used to estimate peak demand rates for residential areas are as follows:

Appendix A **Water** Supply Servicing August 1, 2019

### A.2 FIRE FLOW REQUIREMENTS PER FUS





Stantec Project #: 160401422
Project Name: Richcraft Block 221 Riverside
Date: 6/4/2019
Fire Flow Calculation #: 1
Description: Back-to-back Stacked Block 1

Step	Task				Notes			Value Used	Req'd Fire Flow (L/min)
1	Determine Type of Construction				Wood Fra	me		1.5	-
2	Determine Ground Floor Area of One Unit				-			400	-
	Determine Number of Adjoining Units		Includes ad	ljacent woo	d frame struc	tures separat	ted by 3m or less	1	-
3	Determine Height in Storeys		Does not i	nclude floor	s >50% belov	v grade or op	en attic space	3	-
4	Determine Required Fire Flow		(F :	= 220 x C x A	$\lambda^{1/2}$ ). Round t	o nearest 100	0 L/min	-	11000
5	Determine Occupancy Charge			L	imited Comb	ustible		-15%	9350
					None			0%	
6	Determine Sprinkler Reduction			Non-Sta	ndard Water	Supply or N/A	A	0%	0
	Determine Sprinkler Reduction			Not	Fully Supervi	sed or N/A		0%	U
				% Cov	erage of Spri	nkler System		0%	
		Direction	Exposure Distance (m)	Exposed Length (m)	Exposed Height (Stories)	Length-Height Factor (m x stories)	Construction of Adjacent Wall	-	-
		North	30.1 to 45	26	2	31-60	Wood Frame or Non-Combustible	5%	
7	Determine Increase for Exposures (Max. 75%)	East	20.1 to 30	16	1	0-30	Wood Frame or Non-Combustible	8%	2992
		South	10.1 to 20	26	3	61-90	Wood Frame or Non-Combustible	14%	2772
		West	30.1 to 45	16	2	31-60	Wood Frame or Non-Combustible	5%	
			То	tal Required	Fire Flow in I	/min, Rounde	ed to Nearest 1000L/min		12000
8	Determine Final Required Fire Flow				Total Req	uired Fire Flov	v in L/s		200.0
$ $	Determine hindi kequiled file flow				Required Du	ration of Fire	Flow (hrs)		2.50
					Required Vo	lume of Fire I	Flow (m³)		1800



Stantec Project #: 160401422
Project Name: Richcraft Block 221 Riverside
Date: 6/4/2019
Fire Flow Calculation #: 1
Description: Back-to-back Townhomes Block 2

Step	Task				Notes			Value Used	Req'd Fire Flow (L/min)
1	Determine Type of Construction				Wood Frai	ne		1.5	-
2	Determine Ground Floor Area of One Unit				-			604	-
	Determine Number of Adjoining Units		Includes ac	djacent wood	d frame struc	tures separa	ted by 3m or less	1	-
3	Determine Height in Storeys		Does not i	nclude floor	s >50% below	grade or op	oen attic space	3	-
4	Determine Required Fire Flow		(F	= 220 x C x A	$\chi^{1/2}$ ). Round to	o nearest 100	00 L/min	-	14000
5	Determine Occupancy Charge			L	imited Comb	ustible		-15%	11900
					None			0%	
6	Determine Sprinkler Reduction			Non-Sta	ndard Water	Supply or N/	A	0%	0
ľ	Determine Spirikler Reduction			Not	Fully Supervis	ed or N/A		0%	U
				% Cov	erage of Spri	nkler System		0%	
		Direction	Exposure Distance (m)	Exposed Length (m)	Exposed Height (Stories)	Length-Height Factor (m x stories)	Construction of Adjacent Wall	-	-
		North	10.1 to 20	32	3	91-120	Wood Frame or Non-Combustible	15%	
7	Determine Increase for Exposures (Max. 75%)	East	20.1 to 30	15.1	3	31-60	Wood Frame or Non-Combustible	8%	5117
		South	10.1 to 20	32	3	91-120	Wood Frame or Non-Combustible	15%	3117
		West	30.1 to 45	15.1	2	31-60	Wood Frame or Non-Combustible	5%	
			То	tal Required	Fire Flow in L	/min, Rounde	ed to Nearest 1000L/min		17000
8	Determine Final Required Fire Flow				Total Requ	uired Fire Flow	v in L/s		283.3
ľ	Determine rinar kequirea rire flow				Required Du	ration of Fire	Flow (hrs)		3.50
					Required Vo	lume of Fire I	Flow (m <sup>3</sup> )		3570



Stantec Project #: 160401422
Project Name: Richcraft Block 221 Riverside
Date: 6/4/2019
Fire Flow Calculation #: 1
Description: Back-to-back Townhomes Block 3

Step	Task				Notes			Value Used	Req'd Fire Flow (L/min)
1	Determine Type of Construction				Wood Fra	me		1.5	-
2	Determine Ground Floor Area of One Unit				-			483	-
	Determine Number of Adjoining Units		Includes ad	jacent woo	d frame struc	tures separat	ted by 3m or less	1	-
3	Determine Height in Storeys		Does not i	nclude floor	s >50% belov	v grade or op	pen attic space	3	-
4	Determine Required Fire Flow		(F :	= 220 x C x A	1 <sup>1/2</sup> ). Round t	o nearest 100	0 L/min	-	13000
5	Determine Occupancy Charge			L	imited Comb	ustible		-15%	11050
					None			0%	
6	Determine Sprinkler Reduction			Non-Sta	ndard Water	Supply or N/A	4	0%	0
l °	Determine sprinkler Reduction			Not	Fully Supervis	sed or N/A		0%	U
				% Cov	erage of Spri	nkler System		0%	
		Direction	Exposure Distance (m)	Exposed Length (m)	Exposed Height (Stories)	Length-Height Factor (m x stories)	Construction of Adjacent Wall	-	-
		North	10.1 to 20	26	3	61-90	Wood Frame or Non-Combustible	14%	
7	Determine Increase for Exposures (Max. 75%)	East	20.1 to 30	19	3	31-60	Wood Frame or Non-Combustible	8%	4531
		South	10.1 to 20	26	3	61-90	Wood Frame or Non-Combustible	14%	4551
		West	30.1 to 45	19	2	31-60	Wood Frame or Non-Combustible	5%	
			То	tal Required	Fire Flow in I	/min, Rounde	ed to Nearest 1000L/min		16000
8	Determine Final Required Fire Flow				Total Req	uired Fire Flov	v in L/s		266.7
*	Determine rinal kequired rire flow				Required Du	ration of Fire	Flow (hrs)		3.50
					Required Vo	lume of Fire I	Flow (m³)		3360



Stantec Project #: 160401422
Project Name: Richcraft Block 221 Riverside
Date: 6/4/2019
Fire Flow Calculation #: 1
Description: Back-to-back Townhomes Block 4

Step	Task				Notes			Value Used	Req'd Fire Flow (L/min)
1	Determine Type of Construction				Wood Fra	me		1.5	-
2	Determine Ground Floor Area of One Unit				-			604	-
2	Determine Number of Adjoining Units		Includes ac	ljacent woo	d frame struc	tures separat	ted by 3m or less	1	-
3	Determine Height in Storeys		Does not i	nclude floor	s >50% belov	v grade or op	pen attic space	3	-
4	Determine Required Fire Flow		(F	= 220 x C x A	$\lambda^{1/2}$ ). Round t	o nearest 100	0 L/min	-	14000
5	Determine Occupancy Charge			L	imited Comb	oustible		-15%	11900
					None			0%	
6	Determine Sprinkler Reduction			Non-Sta	ndard Water	Supply or N/A	4	0%	0
•	Determine sprinker Reduction			Not	Fully Supervis	sed or N/A		0%	0
				% Cov	erage of Spri	nkler System		0%	
		Direction	Exposure Distance (m)	Exposed Length (m)	Exposed Height (Stories)	Length-Height Factor (m x stories)	Construction of Adjacent Wall	-	-
		North	10.1 to 20	32	3	91-120	Wood Frame or Non-Combustible	15%	
7	Determine Increase for Exposures (Max. 75%)	East	20.1 to 30	19	3	31-60	Wood Frame or Non-Combustible	8%	4284
		South	30.1 to 45	32	2	61-90	Wood Frame or Non-Combustible	5%	4204
		West	20.1 to 30	19	2	31-60	Wood Frame or Non-Combustible	8%	
			То	tal Required	Fire Flow in I	./min, Rounde	ed to Nearest 1000L/min		16000
8	Determine Final Required Fire Flow				Total Req	uired Fire Flov	v in L/s		266.7
Ů	Determine Final Required Fire flow				Required Du	ration of Fire	Flow (hrs)		3.50
					Required Vo	lume of Fire I	Flow (m³)		3360

Appendix A **Water** Supply Servicing August 1, 2019

### A.3 BOUNDARY CONDITIONS



## **BOUNDARY CONDITIONS**



### **Boundary Conditions For: 6201 Renaud Rd**

**Date of Boundary Conditions: 2019-Jun-13** 

### **Provided Information:**

Scenario	Den	nand
	L/min	L/s
Average Daily Demand	27.6	0.5
Maximum Daily Demand	68.4	1.1
Peak Hour	150	2.5
Fire Flow #1 Demand	12,000	200.0
Fire Flow #2 Demand	17,000	283.3

### **Number Of Connections: 2**

### **Location:**



#### **BOUNDARY CONDITIONS**



#### **Results:**

#### Connection #: 1

Demand Scenario	Head (m)	Pressure <sup>1</sup> (psi)
Maximum HGL	130.8	74.7
Peak Hour	127.0	69.3
Max Day Plus Fire (12,000) L/min	121.9	62.0
Max Day Plus Fire (17,000) L/min	116.7	54.7

<sup>1</sup>Elevation: **78.29 m** 

#### **Connection #: 2**

Demand Scenario	Head (m)	Pressure <sup>1</sup> (psi)
Maximum HGL	130.8	77.7
Peak Hour	127.0	72.3
Max Day Plus Fire (12,000) L/min	118.7	60.5
Max Day Plus Fire (17,000) L/min	110.7	49.1

<sup>1</sup>Elevation: **76.17 m** 

#### **Notes:**

- 1) As per the Ontario Building Code in areas that may be occupied, the static pressure at any fixture shall not exceed 552 kPa (80 psi.) Pressure control measures to be considered are as follows, in order of preference:
  - a) If possible, systems to be designed to residual pressures of 345 to 552 kPa (50 to 80 psi) in all occupied areas outside of the public right-of-way without special pressure control equipment.
  - b) Pressure reducing valves to be installed immediately downstream of the isolation valve in the home/ building, located downstream of the meter so it is owner maintained.
- 2) Insert an isolation valve in between the two connections so that the property can have an uninterrupted water service in the event of watermain closure on Renaud Rd or on Rolling Meadow Cres.

### **Disclaimer**

The boundary condition information is based on current operation of the city water distribution system. The computer model simulation is based on the best information available at the time.



### **BOUNDARY CONDITIONS**

The operation of the water distribution system can change on a regular basis, resulting in a variation in boundary conditions. The physical properties of watermains deteriorate over time, as such must be assumed in the absence of actual field test data. The variation in physical watermain properties can therefore alter the results of the computer model simulation. Fire Flow analysis is a reflection of available flow in the watermain; there may be additional restrictions that occur between the watermain and the hydrant that the model cannot take into account.

Appendix B **Wastewater** Servicing August 1, 2019

# Appendix B WASTEWATER SERVICING

## **B.1** SANITARY SEWER DESIGN SHEET





SUBDIVISION:

1702599 ONTARIO INC

DATE: 8/1/2019
REVISION: 1
DESIGNED BY: MJS
CHECKED BY: DT

#### SANITARY SEWER DESIGN SHEET (City of Ottawa)

FILE NUMBER: 160401467

DESIGN PARAMETERS


MAX PEAK FACTOR (RES.)= MIN PEAK FACTOR (RES.)= AVG. DAILY FLOW / PERSON MINIMUM VELOCITY 4.0 280 l/p/day 0.60 m/s 2.0 COMMERCIAL 28,000 l/ha/day MAXIMUM VELOCITY 3.00 m/s PEAKING FACTOR (INDUSTRIAL): 2.4 INDUSTRIAL (HEAVY) 55,000 l/ha/day MANNINGS n 0.013 PEAKING FACTOR (ICI >20%): INDUSTRIAL (LIGHT) 35,000 l/ha/day BEDDING CLASS В 28,000 l/ha/day 0.33 l/s/Ha PERSONS / SINGLE INSTITUTIONAL 3.4 MINIMUM COVER 2.50 m PERSONS / TOWNHOME 2.7 INFILTRATION HARMON CORRECTION FACTOR 8.0

																PERSONS /	APARTMENT		2.3																	
	LOCATION	N					RESIDENTIA	L AREA AND P	OPULATION				COM	MERCIAL	INDUS	TRIAL (L)	INDUS	TRIAL (H)	INSTITU	UTIONAL	GREEN	UNUSED	C+I+I		INFILTRATION	N	TOTAL				PIF	PΕ				
AREA ID		FROM	TO	AREA		UNI		POP.		JLATIVE	PEAK	PEAK	AREA	ACCU.	AREA	ACCU.	AREA	ACCU.	AREA	ACCU.	AREA	ACCU.	PEAK	TOTAL	ACCU.	INFILT.	FLOW	LENGTH	DIA	MATERIAL	CLASS	SLOPE	CAP.	CAP. V	VEL.	VEL.
NUMBER	l l	M.H.	M.H.		SINGLE	TOWN	BACK-TO-BAC	KS .	AREA	POP.	FACT.	FLOW		AREA		AREA		AREA		AREA		AREA	FLOW	AREA	AREA	FLOW							(FULL)	PEAK FLOW	(FULL)	(ACT.)
				(ha)					(ha)			(l/s)	(ha)	(ha)	(ha)	(ha)	(ha)	(ha)	(ha)	(ha)	(ha)	(ha)	(l/s)	(ha)	(ha)	(l/s)	(l/s)	(m)	(mm)			(%)	(l/s)	(%)	(m/s)	(m/s)
R6A		6	5	0.09	0	7	0	19	0.09	19	3.71	0.2	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0	0.09	0.09	0.0	0.3	22.2	200	PVC	SDR 35	0.65	27.0	0.95%	0.85	0.23
R5A		5	4	0.03	0	2	0	5	0.12	24	3.69	0.3	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0	0.03	0.12	0.0	0.3	13.3	200	PVC	SDR 35	0.65	27.0	1.23%	0.85	0.24
D04		•	•	0.44		_		22	0.11	20	0.00	2.4	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0	0.44	0.44		2.4	05.0	202	D) (0	000.05	0.40	04.4	4.0=0/	0.07	0.00
R9A		9	8	0.11	U	5	8	32	0.11	32	3.68	0.4	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0	0.11	0.11	0.0	0.4	35.0	200	PVC	SDR 35	0.40	21.1	1.97%	0.67	0.22
R11A		11	10	0.04	0	0	Q	10	0.04	10	3.71	0.2	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0	0.04	0.04	0.0	0.2	21.4	200	PVC	SDR 35	0.65	27.0	0.87%	0.85	0.23
G10A	- 1	10	Ω	0.04	0	0	0	0	0.04	10	3.71	0.2	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.05	0.05	0.0	0.04	0.04	0.0	0.2	28.4	200	DVC	SDR 35	0.65	27.0	0.92%	0.85	0.23
GIUA	i i	10	0	0.00		0			0.04	10	3.71	0.2	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.05	0.03	0.0	0.03	0.09	0.0	0.2	20.4	200	FVC	3DIC 33	0.03	21.0	0.52 /6	0.03	0.23
G8A		8	7	0.00	0	0	0	0	0.14	50	3.65	0.6	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.01	0.06	0.0	0.01	0.20	0.1	0.7	4.8	200	PVC	SDR 35	0.40	21.1	3.13%	0.67	0.25
G7A		7	4	0.00	0	0	0	0	0.14	50	3.65	0.6	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.02	0.08	0.0	0.02	0.22	0.1	0.7	28.4	200	PVC	SDR 35	0.40	21.1	3.16%	0.67	0.25
G4A		4	3	0.00	0	0	0	0	0.27	75	3.62	0.9	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.02	0.10	0.0	0.02	0.37	0.1	1.0	26.2	200	PVC	SDR 35	0.40	21.1	4.72%	0.67	0.28
R3A		3	2	0.04	0	2	0	5	0.30	80	3.62	0.9	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.10	0.0	0.04	0.41	0.1	1.1	11.3	200	PVC	SDR 35	0.40	21.1	5.07%	0.67	0.29
R2A		2	1	0.11	0	7	0	19	0.41	99	3.60	1.2	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.10	0.0	0.11	0.52	0.2	1.3	32.6	200	PVC	SDR 35	0.40	21.1	6.25%	0.67	0.31
		1	EX.SAN	0.00	0	0	0	0	0.41	99	3.60	1.2	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.10	0.0	0.00	0.52	0.2	1.3	14.2	200	PVC	SDR 35	0.40	21.1	6.25%	0.67	0.31
																													200							

Appendix B **Wastewater** Servicing August 1, 2019

# **B.2** BACKGROUND EXCERPTS (SANITARY DRAINAGE)







CCL/IBI 1770 WOODWARD DRIVE OTTAWA, ONTARIO K2C OP8

SANITARY SEWER DESIGN SHEET

PROJECT: CLARIDGE HOMES, NAVAN ROAD

CUMBERLAND CLARIDGE HOMES LOCATION: DEVELOPER:

PAGE: 1 OF 2 JOB: 3625-LD DATE: Dec 2008

DESIGN: DY FILE: 3625-LD Sewers.xls

LOCATION			INDIV	DUAL			CUMU	LATIVE				DESIGN FL	.OW			PROPOSEI	SEWER			
			com/Inst		idential	Com/Inst	1	I	Pop	POPLN	Com/In	s:Com/Inst	INFILT	PEAK		VELOCITY				AVAIL.
STREET	FROM	то	area	AREA	POP.	Area	POP.	AREA		FLOW	Peak	Peak	FLOW	FLOW	CAPACITY	(full)	LGTH.	PIPE	GRADI	-
	МН	МН	На	(Ha)		На		(Ha)	II .	(I/s)	Fact	Flow	(I/s)	(I/s)	l/s	m/s	(m)	(mm		(%)
Phase 2 & External								<u> </u>									. ,	•	•	, ,
Fountainhead Drive		162A				0.00	853.70	10.36	3.84	13.29	1.5	0.0	0 2.9	0 <b>16.</b> 1	9					
Felicity Crescent	162A	195A		0.12	0.0	0.00	853.70	10.48	3.84	13.29	9.5	0.0	0 2.9	3 <b>16.2</b>	2 32.	2 <b>3</b> 0.	64	78 2	50 0.	27 49.67
D																				
Phase 2 & External		4054				4.00	000 50	40.04		40.50		0 11		. 450	<u> </u>					
Joshua Avenue	_	195A				1.30	669.50	12.81	3.91	10.59	1.5	0 1.1	3 3.9	05 <b>15.6</b>	<del>' </del>					
Phase 2																				
Spring Valley		195A				2.83	667.60	9.43	3.91	10.56	1.5	0 2.4	6 3.4	3 <b>16.</b> 4	5					
Lasta a Alasta	1054	400D		0.54	0 040	1.10	0004.00	00.00	0.55	04.00	\ 15	0 0.5	0 10	7 40.0		14	00	75 6	75 0	1.4 00.00
Joshua Avenue	195A	130B	-	0.54		4.13		33.26	3.55						_					14 32.69
Joshua Avenue	130B	130A		0.39	0 20.4	4.13	2245.20	33.65	3.55	32.25	1.5	0 3.5	9 10.5	i8 <b>46.</b> 4	2 68.	F1 U.	60	75 3	<i>1</i> 5 0.	14 32.15
Felicity Crescent	162A	161A		0.48	0 30.6	0.00	30.60	0.48	4.00	0.50	1.5	0.0	0 0.1	3 0.6	3 27.0	<b>60</b> 0.	85 66	6.1 2	00 0.	65 97.72
Felicity Crescent	161A	160B		0.17	0 6.8	0.00	37.40	0.65	4.00	0.61	1.5	0.0	0 0.1	8 0.7	9 27.0	<b>60</b> 0.	85 12	2.6 2	00 0.	35 97 <b>.</b> 14
Felicity Crescent	160B	160A		0.43	0 27.2	0.00	64.60	1.08	4.00	1.05	1.5	0.0	0 0.3	30 1.3	5 27.0	<b>0.</b>	85	65 2	00 0.	35 95.11
Felicity Crescent	160A	120B		0.49	0 27.2	0.00	91.80	1.57	4.00	1.49	1.5	0.0	0 0.4	4 1.9	3 30.	l <b>0</b> 0.	60	68 2	50 0.	24 93.65
	1000			0.10			0.4.00	4.00												
Saddleridge Drive	120B	201A		0.12	0.0	0.00	91.80	1.69	4.00	1.49	2.5	0.0	0 0.4	7 1.9	6 30.4	i <b>0</b> 0.	60 7	5.8 2	50 0.	24 93.55
Fountainhead Drive	203A	223A		0.54	0 34,0	0.00	34.00	0.54	4,00	0,55	3.5	0.0	0 0.1	5 <b>0.7</b>	0 27,0	<b>60</b> 0.	85 63	3.9 2	00 0.	35 97.46
Fountainhead Drive	223A	201A		0.44	0 27.2	0.00	61.20	0.98	4.00	0.99	4.5	0.0	0 0.2	.7 <b>1.2</b>	6 19.	<b>36</b> 0.	60 79	9.9 2	00 0.	32 93.49
Fountainhead Drive	162A	123A		0.40	0 27.2	0.00	27.20	0.40	4.00	0.44	4.5	0.0	0 0.1	1 0.5	5 27.0	<b>0.</b>	85 7	3.4 2	00 0.	98.01
Fountainhead Drive	123A	201A		0.41	0 27.2	0.00	54.40	0.81	4.00	0.88	5.5	0.0	0 0.2	23 <b>1.</b> 1	1 27.	<b>0</b> .	85 72	2.4 2	00 0.	95.98
Saddleridge Drive	201A	130A		0.46	0 27.2	0,00	234,60	3.94	4.00	3.80	7.5	0.0	0 1.1	0 4.9	0 30,	I <b>0</b> 0	60 78	3.1 2	50 0.	24 83.88
Gaddienage Drive	2017	130/4		0.40	0 21.2	0.00	234.00	3.54	7.00	0.00	, ,,,	0.0	0 1.1	U 4.6	30.	0.	00 /	2.1 2	<u> </u>	24 00,00
Rolling Meadow Crescent	142B	142A		0.12	0 8.1	0.00	8.10	0.12	4.00	0.13	1.5	0.0	0.0	)3 <b>0.</b> 1	6 57.	27 1.	77 !	9.7 2	00 2.	30 99.72
Rolling Meadow Crescent	142A	141A		0.63	0 62.1	0.00	70.20	0.75	4.00	1.14	1.5	0.0	0 0.2	.1 <b>1.</b> 3	5 57.	27 1.	77 8:	3.2 2	00 2.	30 97 <u>.</u> 64
Rolling Meadow Crescent	141A	140A		0.21	0 18.9	0.00	89.10	0.96	4.00	1.44	1.5	0.0	0 0.2	?7 <b>1.</b> 7	1 57.:	<b>27</b> 1.	77 34	1.9 2	00 2.	30 97.01
Rolling Meadow Crescent	140A	139A		0.59	0 54.0	0.00	143.10	1.55	4.00	2.32	1.5	0.0	0 0.4	3 <b>2.7</b>	5 66.	<b>'1</b> 2.	06 100	).1 2	00 3.	30 95.88
Rolling Meadow Crescent	139A	138A		0.29	0 29.7	0.00		1.84	4.00	2.80	1.5	0.0	0 0.5	52 <b>3.</b> 3					00 1.	00 90.30
Rolling Meadow Crescent	138A	137A		0.61	0 62.1	0.00	234.90	2.45	4.00	3.81	1.5	0.0	0 0.6	9 <b>4.</b> 5	0 34.:	2 <b>1</b> 1.	06	90 2	00 1.	00 86.85
Esterbrook Drive	143A	137A		0.27	0 21.6	0.00	21.60	0.27	4.00	0.35	5 1.5	0.0	0.0	0.4	3 41.9	00 1	29 5	2.1 2	00 1.	50 98.97
LSICIDIOOK DIIVC	140/1	10771		0.27	0 21.0	0.00	21.00	0.27	7.00	0.00	7 1.5	0 0.0	0 0.0	,	71.	1.	20 0	2	00 1.	30.37
Esterbrook Drive	137A	136A		0.22	0 13.5	0.00	270.00	2.94	4.00	4.38	3 1.5	0.0	3.0 0	32 <b>5.2</b>	0 34.:	? <b>1</b> 1.	06	75 2	00 1.	00 84.80
Dayahayan Ctraat	1264	1224		0.46	0 27.2	0.00	207.20	2.40	4.00	4.00	) 15	0 00	0 00	) E = E =	7 24	10 0	76	70 0	00 0	FO 76.1 <i>E</i>
Dovehaven Street	136A	133A	-	0.46	0 27.2	0.00	297.20	3.40	4.00	4.82	2 1.5	0.0	0.0	)5 <b>5.7</b>	7 24.	<u>ت</u> 0.	75	79 2	00 0.	50 76.15
Rolling Meadow Crescent	155A	154A		0.51	0 45.9	0.00	45.90	0.51	4.00	0.74	1.5	0.0	0 0.1	4 0.8	8 57.:	27 1.	77 5	5.8 2	00 2.	30 98.46
Rolling Meadow Crescent	154A	153A		0.22	0 21.6	0.00	67.50	0.73	4.00	1.09	1.5	0.0	0 0.2	20 1.2	9 72.	<b>58</b> 2.	24 3 <sup>-</sup>	1.5 2	00 4.	50 98.22
Rolling Meadow Crescent	153A	152A		0.56	0 54.0	0.00	121.50	1.29	4.00	1.97	' 1.5	0.0	0 0.3	36 <b>2.</b> 3	3 72.	<b>58</b> 2.	24 79	9.9 2	00 4.	50 96.79
Rolling Meadow Crescent	152A	151A		0.19				1.48											00 4.	
Rolling Meadow Crescent	151A	150A		0.19	0 16.2	0.00	153.90	1.67	4.00	2.49	1.5	0.0	0 0.4	7 2.9	6 51.	1.	59 39	9.2 2	00 2.	27 94.26
Rolling Meadow Crescent	150A	300A		0.00	0.0	0.00	153.90	1.67	4.00	2.49	1.5	0.0	0.4	7 2.9	6 21.0	0.	67 13	3.4 2	00 0.	40 86.32
Rolling Meadow Crescent	300A	145A		0.93	0 111.6	0.00	265.50	2.60	4.00	4.30	1.5	0.0	0.7	<b>5.0</b>	21.	0.	67 103	3.4	00 0.	76.75
Saddleridge Drive	156A	145A	_	0.69	0 82.8	0,00	82.80	0.69	4.00	1.34	1.5	0.0	0.1	9 1.5	3 41.	1	29	70 2	00 1.	96.35
Saddlelluge Dilve	1304	HUM		0.09	02.0	II 0.00	02.00	0.09	II 4.00	1.34	1.5	0.0	0.1	U I I I	41.	, <del>,</del>	20	70 2	UU 1.	30.33

Where Q = average daily per capita flow
I = Unit of peak extraneous flow

350 l/cap/d 0.28 l/sec/Ha

SPECIFY
Coeff. of friction (n) =

0.013



CCL/IBI 1770 WOODWARD DRIVE OTTAWA, ONTARIO K2C OP8

#### **SANITARY SEWER DESIGN SHEET**

PROJECT: **CLARIDGE HOMES, NAVAN ROAD** 

LOCATION: CUMBERLAND DEVELOPER: **CLARIDGE HOMES** 

JOB: 3625-LD DATE: Dec 2008

PAGE: 2 OF 2

DESIGN: DY

)-55053444045																		FILE:	3625-LD S	ewers.xls
LOCATION			INDIV	DUAL			CUMU	ILATIVE				DESIGN FL					D SEWER			
			com/Inst	Re	sidential	Com/Inst			Pop	POPLN	Com/In:	siCom/Inst	INFILT	PEAK		VELOCITY	<b>′</b>			AVAIL.
STREET	FROM	то	area	AREA	POP.	Area	POP.	AREA	PEAK	FLOW	Peak	Peak	FLOW	FLOW	CAPACITY	(full)	LGTH.	PIPE	GRADE	
	МН	MH	На	(Ha)		На		(Ha)	FACT.	(I/s)	Fact	Flow	(I/s)	(l/s)	l/s	m/s	(m)	(mm)	%	(%)
Gossamer St	200A	201A		0.6	340 27.2	0.00	27.20	0.64	4.00	0.44	1 1.50	0.0	0.1	8 <b>0.62</b>	27.60	0 (	0.85	0 20	0 0.6	5 97.75%
Gossamer St	201A	202A		0.0	70 0.0	0.00	27.20	0.71	4.00	0.44	1 1.50	0.0	0.2	0.64	24.19	9 (	0.75 41	5 20	0 0.5	0 97.35%
Prairie St	202A	145A		0.3	350 17.0	0.00	44.20	1.06	4.00	0.72	2 1.50	0.0	0.3	0 1.02	39.2	2 (	0.77 8	7 25	0 0.4	0 97.40%
Saddleridge Drive	145A	134A		0.4		0.00			4.00								1.29 65			
Saddleridge Drive	134A	133A		0.5	37.4	0.00	463.90	5.36	3.99	7.50	1.50	0.0	00 1.5	0 ( <b>9.0</b> 0	41.9	0) (	1.29 65	.8 20	0 1.5	78.52%
Saddleridge Drive	133A	132A		0.6													0.75 93			
Saddleridge Drive	132A	130A		0.3	320 17.0	0.00	822.30	9.70	3.85	12.84	1.50	0.0	00 2.7	2 <b>15.5</b> 6	24.19	9 (	0.75 4	4 20	0 0.5	0 35.68%
Joshua Street	130A	127B		0.3	390 17.0	4.13	3319.10	47.68	3.40	45.78	3 1.50	3.5	9 14.5	1 63.88	68.4	1 (	0.60 95.0	5 37	5 0.1	4 6.62%
Phase 1B & External																				
Gossamer St	203A	204A		0.7														7 20		
Gossamer St	204A	205A		0.7											-		1.06 86			
Gossamer St	205A	127B		0.2	210 10.8	0.00	151.20	1.64	4.00	2.4	5 1.50	0.0	0.4	6 <b>2.9</b> 1	24.19	9 (	0.75 36	6 20	0 0.5	0 87.97%
Joshua Street	127B	116A		0.4	50 10.2	4.13	3480.50	49.77	3.39	47.7	1.50	3.5	9 15.0	9 66.43	68.4	1 (	0.60 65	5 37	5 0.1	4 2.90%
Joshua Street	116A	104D				4.13	3480.50	49.77	3.39	47.75	5 1.50	3.5	9 15.0	9 66.43	68.4	1 (	0.60 7	8 37	5 0.1	4 2.90%
Felicity Crescent	120A	111B	-	0.5	90 44.2	0.00	44.20	0.59	4.00	0.72	2 3.50	0.0	0 0.1	7 <b>0.8</b> 9	27.6	0 (	0.85 7	6 20	0 0.6	5 96.78%
Felicity Crescent	111B	101A		0.5													0.60 69			
Felicity Crescent	101A	101B		0,1														3 25		
Felicity Crescent	101B	102A		0.5														4 60		
Felicity Crescent	102A	103A		0.6			139.40	2.51	4.00	2.26			0.7	0 <b>2.96</b>	313.7	5	1.08 7	5 60	0 0.2	
Felicity Crescent	103A	104D		0.1	40 6.8	0.00	146.20	2.65	4.00	2.37	7 1.50	0.0	0.7	4 3.11	311.13	3	1.07 32	.8 60	0 0.2	4 99.00%
External																				
Street 1	116C	116B		1.6														2 25		
Joshua Street	116B	104C		0.2	200 3.4	0.00	143.80	1.83	4.00	2.33	3 1.50	0.0	0.5	1 2.84	30.4	0 (	0.60 60	4 25	0 0.2	4 90.66%
Joshua Street	104A	104C		0.3	6.8	0.00	6.80	0.30	4.00	0.1	1.50	0.0	0.0	8 <b>0.1</b> 9	27.6	0 (	0.85 4	5 20	0 0.6	5 99.31%
Joshua Street	104C	104D				0.00	150.60	2.13	4.00	) 2.44	1 1.50	0.0	0.6	0 3.04	62.0	2	1.22 2	.5 25	0 1.0	0 95.10%
Joshua Street	104D	EX				4.13	3777.30	54.55	3.36	51.34	1.50	3.5	9 16.4	3 <b>71.3</b> 6	85.8	5 (	0.75 49	6 37	5 0.2	2 16.88%
\\//bass				1/222/4												CDECIEV				

Where Q = average daily per capita flow

350 **l**/cap/d

I = Unit of peak extraneous flow 0.28 l/sec/Ha

 $M = Peaking Factor = 1+(14/(4+P)^0.5)), P=POP. IN 1000'S, Max of 4$ 

Q(p) = Peak population flow (I/s)

Q(i) = peak extraneous flow (I/s)

Population = AVERAGE Per unit =

3.4 singles

2.7 Townhouses

General Population Densities

Low Density = 120 pers / per gross hectare

Commercial and School - Average flow 50,000 I/ha/day with Peaking Factor = 1.5

SPECIFY

Coeff. of friction (n) =

0.013

REV.#:

9 15-Dec-08

Appendix C **Stormwater** Management August 1, 2019

# Appendix C STORMWATER MANAGEMENT

## C.1 STORM SEWER DESIGN SHEET



				_			STORM	M SEWE	ER		DESIGN	PARAME	TERS																										
Stantec		1702599 (	ONTARIO IN	C			DESIG	N SHEE	ET		I = a / (t+			(As per C	ity of Otta	wa Guidel	ines, 2012	2)																					
Stantec	DATE:		2019	-08-01			(City o	of Ottawa	a)			1:2 yr	1:5 yr	1:10 yr	1:100 yr																								
	REVISIO			1							a =		998.071	1174.184				0.013		BEDDING	CLASS =	В																	
	DESIGN				FILE NUM	MBER:	1604014	167			b =	6.199	6.053	6.014	6.014			2.00																					
	CHECKE	D BY:		TC							c =	0.810	0.814	0.816	0.820		ENTRY	10	min																				
LOCATION									_						AINAGE AF																		PIPE SELEC						
AREA ID NUMBER	FROM M.H.	TO M.H.	AREA (2-YEAR)	AREA	AREA (10-YEAR)	AREA	AREA R) (ROOF)	C (2-YEAR	C R) (5-YEAR)	C (10-YEAR	C ) (100-YEAR	A x C (2-YEAR)	ACCUM AxC (2YR)		ACCUM.	A x C	ACCUM.	AxC	ACCUM.  ACC (100YR)	T of C	2-YEAR	I <sub>5-YEAR</sub>	10-YEAR	100-YEAR	Q <sub>CONTROL</sub>	ACCUM. Q <sub>CONTROL</sub>	Q <sub>ACT</sub>	LENGTH PI	DIAMETE		PIPE SHAPE	MATERIAL	CLASS	SLOPE	(FULL)	% FULL	(FULL)	VEL. (ACT)	TIME OF FLOW
NUMBER	M.H.	M.H.	(2-YEAR) (ha)	(b-TEAR) (ha)	(10-TEAR) (ha)	(100-YEAR (ha)	(ha)	(2-TEAR	() (5-YEAR)	(10-YEAR	) (100-TEAR	(2-TEAR) (ha)	(ha)	(b-TEAR) (ha)	(ha)	(ha)	(ha)	(ha)	(ha)	(min)	(mm/h)	(mm/h)	(mm/h)	(mm/h)	(L/s)	(L/s)	(L/s)	(m)	(mm)	(mm)	(-)	(-)	(-)	%	(L/s)	(-)	(M/S)	(MCT) (m/s)	(min)
	į			()	()	()	()			- (/	- (/	()	()	()	()	()	(/	()	()	()	(	(	(	(	(==)	( -,	(= 4)	()	()						(/	( )	. ,	()	
	110	109	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	10.00	76.81	104.19	122.14	178.56	0.0	0.0	0.0	35.0	300	300	CIRCULAR	PVC	-	0.50	68.0	0.00%	0.97	0.00	0.00
	-																			10.00																			
	504	109	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000		76.81	104.19	122.14	178.56	0.0	0.0	0.0	11.1	200	200	CIRCULAR	PVC	-	1.00	33.3	0.00%	1.05	0.00	0.00
	i .																			10.00																			
L109A	109	108	0.05	0.00	0.00	0.00	0.00	0.87	0.00	0.00	0.00	0.046	0.046	0.000	0.000	0.000	0.000	0.000	0.000	10.00	76.81	104.19	122.14	178.56	0.0	0.0	9.7	7.5	300	300	CIRCULAR	PVC		0.50	68.0	14.30%	0.97	0.57	0.22
LIOSA	108			0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.000	0.046		0.000		0.000					103.06				0.0	9.6	27.3	300	300	CIRCULAR	PVC	-	0.50		14.14%		0.56	
	i .																			11.03																			
	34	503	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	10.00	76.81	104.19	122.14	178.56	0.0	0.0	0.0	21.1	900	900	CIRCULAR	CONCRETE		0.10	600.7	0.00%	0.91	0.00	0.00
	503	107	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	10.00	76.81	104.19	122.14		0.0	0.0	0.0	3.1	200	200	CIRCULAR	PVC	-	1.00	33.3	0.00%	1.05	0.00	0.00
L107A	107	106	0.11	0.00	0.00	0.00	0.00	0.73	0.00	0.00	0.00	0.084	0.084	0.000	0.000	0.000	0.000	0.000	0.000	10.00	76.81	104.19	122.14	178.56	0.0	0.0	17.8	28.4	300	300	CIRCULAR	PVC	-	0.50	68.0	26.21%	0.97	0.68	0.70
	106	105	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.000	0.084	0.000	0.000	0.000	0.000	0.000	0.000	10.70 11.07	74.22	100.64	117.96	172.42	0.0	0.0	17.2	15.2	300	300	CIRCULAR	PVC	-	0.50	68.0	25.33%	0.97	0.68	0.37
																				11.07																			
	105	101	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.000	0.129	0.000	0.000	0.000	0.000	0.000	0.000	11.07	72.92	98.85	115.85	169.32	0.0	0.0	26.1	30.8	375	375	CIRCULAR	PVC	-	0.50	116.6	22.43%	1.11	0.74	0.69
																				11.77																			
	505	500	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	10.00	76.81	104.19	122.14	178.56	0.0	0.0	0.0	19.8	900	900	CIRCULAR	CONCRETE	-	0.10	597.2	0.00%	0.91	0.00	0.00
	500	104	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	10.00	76.81	104.19	122.14	178.56	0.0	0.0	0.0	7.7	200	200	CIRCULAR	PVC	-	1.00	33.3	0.00%	1.05	0.00	0.00
																				10.00																			
	502	501	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	10.00	76.81	104.19	122.14	178.56	0.0	0.0	0.0	22.4	900	900	CIRCULAR	CONCRETE	-	0.10	597.2	0.00%	0.91	0.00	0.00
	501	104	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	10.00	76.81	104.19	122.14	178.56	0.0	0.0	0.0	4.1	200	200	CIRCULAR	PVC	-	1.00	33.3	0.00%	1.05	0.00	0.00
	į																			10.00																			
L104A, L104B	104	103	0.31	0.00	0.00	0.00	0.00	0.72	0.00	0.00	0.00	0.226	0.226	0.000	0.000	0.000	0.000	0.000	0.000	10.00	76.81	104.19	122.14	178.56	0.0	0.0	48.2	29.3	300	300	CIRCULAR	PVC	-	0.50	68.0	70.88%	0.97	0.92	0.53
	103	102	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.000	0.226	0.000	0.000	0.000	0.000	0.000	0.000	10.53	74.82	101.46	118.92	173.83	0.0	0.0	46.9	7.6	300	300	CIRCULAR	PVC	-	0.50	68.0	69.05%	0.97	0.91	0.14
	102	101	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.000	0.226	0.000	0.000	0.000	0.000	0.000	0.000	10.67 10.76	74.32	100.78	118.12	172.65	0.0	0.0	46.6	5.0	300	300	CIRCULAR	PVC	-	0.50	68.0	68.59%	0.97	0.91	0.09
																				10.76																			
	101	100	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.000	0.355	0.000	0.000	0.000	0.000	0.000	0.000	11.77	70.63	95.71	112.15	163.89	0.0	0.0	69.6	35.5	375	375	CIRCULAR	PVC	-	2.70	270.9	25.71%	2.57	1.80	0.33
	1																			12.09									375	375									

Appendix C **Stormwater** Management August 1, 2019

## C.2 PCSWMM MODEL



### EPA STORM WATER MANAGEMENT MODEL - VERSION 5.1 (Build 5.1.013)

**********  Element Count  *********  Number of rain gages  Number of subcatchmer  Number of nodes  Number of links  Number of pollutants  Number of land uses	nts 6 17 16 0				_	
**************************************					<b>.</b>	
Name	Data Source			Data Type	Interva	ng 1
RG1	OTT_CHI_100YR_(			INTENSITY	_	 ·
**************************************	Area	Width	%Imperv	%slope	Rain Gag	e
L104A	0.22	73.20	71.43	3.0000	RG1	
501-S L104B	0.10	30.40	80.00	3.0000	RG1	
500-S L107A	0.11	18.10	75.71	3.0000	RG1	
503-S L109A	0.05	16.70	95.71	3.0000	RG1	
504-S UNC-1	0.05	13.80	82.86	3.0000	RG1	
1001 UNC-2 1002	0.04	12.80	64.29	3.0000	RG1	
**************************************			Invest	May	Ponded	External
Name	Туре		Invert Elev.	Max. Depth	Area	Inflow
1000 1001 1002 101 102 103 104	OUTFALL OUTFALL STORAGE STORAGE STORAGE STORAGE STORAGE		72.09 0.00 0.00 72.27 72.38 72.48 72.67	0.68 0.00 0.00 4.67 4.54 4.39 4.01	0.0 0.0 0.0 0.0 0.0 0.0	

72.46 72.46 72.61 72.78 Page 1

STORAGE

STORAGE

STORAGE

STORAGE

104

105

106

107

0.0

0.0

0.0

0.0

4.01

4.92

4.88 4.55

108 109 110 500-S 501-S 503-S 504-S	2019- STORAGE STORAGE STORAGE STORAGE STORAGE STORAGE	-07-31-100yr 72. 72. 72. 74. 74. 75.	67 73 95 67 16 18	5.95 5.81 5.00 2.60 2.60 2.60 1.85	0.0 0.0 0.0 0.0 0.0 0.0		
********** Link Summary ********* Name %Slope Roughness	From Node	To Node		Туре	Len	gth	
 Pipe_11	105	101		CONDUIT	3	0.8	
0.4971 0.0130 Pipe_13	108	105		CONDUIT	2	7.3	
0.4989 0.0130 Pipe_14	106	105		CONDUIT	1	5.6	
0.5003 0.0130 Pipe_15	101	1000		CONDUIT	3	5.5	
0.4988 0.0130 Pipe_16	104	103		CONDUIT	3	32.0	
0.4999 0.0130 Pipe_17	103	102		CONDUIT		7.6	
0.5010 0.0130 Pipe_19 0.5007 0.0130 Pipe_23	107	106		CONDUIT	2	8.0	
	109	108		CONDUIT		7.5	
0.4962 0.0130 Pipe_24	110	109		CONDUIT	3	7.9	
0.5008 0.0130 Pipe_25	102	101	CONDUIT			5.0	
0.7235 0.0130 501-IC 503-IC W1 W2 500-IC 504-IC	501-S 503-S 503-S 500-S 500-S 504-S	104 OF 107 OF 500-S WE 501-S WE 104 OU		ORIFICE ORIFICE WEIR WEIR OUTLET OUTLET			
**************************************	mmary			·			
Full		Full	Full	,	Max.	No. of	
Conduit Flow	Shape	Depth	Area	. Rad.	Width	Barrels	
 Pipe_11	CIRCULAR	0.38	0.11	0.09	0.38	1	
123.62 Pipe_13	CIRCULAR	0.30	0.07	0.07	0.30	1	
68.31 Pipe_14	CIRCULAR	0.30	0.07	0.07	0.30	1	
68.40 Pipe_15	CIRCULAR	0.38	0.11	0.09	0.38	1	
123.84		Page 2					

		2019-07-31-100	yrCHI.rpt			
Pipe_16 68.38	CIRCULAR	0.30	0.07	0.07	0.30	1
Pipe_17 68.45	CIRCULAR	0.30	0.07	0.07	0.30	1
Pipe_19 68.43	CIRCULAR	0.30	0.07	0.07	0.30	1
Pipe_23 68.12	CIRCULAR	0.30	0.07	0.07	0.30	1
Pipe_24	CIRCULAR	0.30	0.07	0.07	0.30	1
68.43 Pipe_25 82.26	CIRCULAR	0.30	0.07	0.07	0.30	1

Transect	PrivateRd
Area:	

Arcu.	0.0004 0.0144 0.0484 0.1024 0.1764 0.2704 0.3844 0.5184 0.6724 0.8464	0.0016 0.0196 0.0576 0.1156 0.1936 0.2916 0.4096 0.5476 0.7056 0.8836	0.0036 0.0256 0.0676 0.1296 0.2116 0.3136 0.4356 0.5776 0.7396 0.9216	0.0064 0.0324 0.0784 0.1444 0.2304 0.3364 0.4624 0.6084 0.7744 0.9604	0.0100 0.0400 0.0900 0.1600 0.2500 0.3600 0.4900 0.6400 0.8100
Hrad:	0.0200	0.0400	0.0600	0.0800	0.1000
	0.1200	0.1400	0.1600	0.1800	0.2000
	0.2200	0.2400	0.2600	0.2800	0.3000
	0.3200	0.3400	0.3600	0.3800	0.4000
	0.4200	0.4400	0.4600	0.4800	0.5000
	0.5200	0.5400	0.5600	0.5800	0.6000
	0.6200	0.6400	0.6600	0.6800	0.7000
	0.7200	0.7400	0.7600	0.7800	0.8000
و ما عدام و	0.8200	0.8400	0.8600	0.8800	0.9000
	0.9200	0.9400	0.9600	0.9800	1.0000
Width:	0.0200	0.0400	0.0600	0.0800	0.1000
	0.1200	0.1400	0.1600	0.1800	0.2000
	0.2200	0.2400	0.2600	0.2800	0.3000
	0.3200	0.3400	0.3600	0.3800	0.4000
	0.4200	0.4400	0.4600	0.4800	0.5000
	0.5200	0.5400	0.5600	0.5800	0.6000
	0.6200	0.6400	0.6600	0.6800	0.7000
	0.7200	0.7400	0.7600	0.7800	0.8000
	0.8200	0.8400	0.8600	0.8800	0.9000
	0.9200	0.9400	0.9600	0.9800	1.0000

\*\*\*\*\*\*\*\*\*\*\*\*\*

NOTE: The summary statistics displayed in this report are based on results found at every computational time step, not just on results from each reporting time step.

\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*
Analysis Options

#### 2019-07-31-100yrCHI.rpt \*\*\*\*\*\* Flow Units ..... LPS Process Models: Rainfall/Runoff ..... YES RDII ..... NO Snowmelt ..... NO Groundwater ..... NO Flow Routing ..... YES Ponding Allowed ..... YES Water Quality ..... NO Infiltration Method ..... HORTON Flow Routing Method ..... DYNWAVE Surcharge Method ...... EXTRAN Starting Date ...... 05/09/2019 00:00:00 Ending Date ..... 05/10/2019 00:00:00 Antecedent Dry Days ..... 0.0 Report Time Step ..... 00:01:00 Routing Time Step ..... 1.00 sec Variable Time Step ..... NO Maximum Trials ..... 8 Number of Threads ...... 1 Head Tolerance ...... 0.001500 m \*\*\*\*\*\*\*\* ∨olume Depth Runoff Quantity Continuity hectare-m mm Total Precipitation ..... 0.041 71.667 Evaporation Loss ..... 0.000 0.000 Infiltration Loss ...... Surface Runoff ...... Final Storage ..... 10.994 0.006 59.563 0.034 0.001 1.200 Continuity Error (%) ..... -0.126\*\*\*\*\*\*\* **Volume** Volume Flow Routing Continuity 10^6 ltr hectare-m Dry Weather Inflow ...... Wet Weather Inflow ...... 0.000 0.000 0.034 0.342 Groundwater Inflow ...... 0.000 0.000 RDII Inflow ..... 0.000 0.000 External Inflow ..... 0.000 0.000 External Outflow ..... 0.034 0.342 Flooding Loss ..... 0.000 0.000 Evaporation Loss ...... Exfiltration Loss .....

\*\*\*\*\*\*\* Highest Continuity Errors \*\*\*\*\*\*\*\*\* Node 501-S (-2.08%)

Initial Stored Volume ....

Final Stored Volume .....

Continuity Error (%) .....

\*\*\*\*\*\*\* Highest Flow Instability Indexes 0.000

0.000

0.000

0.000

-0.763

0.000

0.000

0.000

0.003

### All links are stable.

Minimum Time Step : 1.00 sec
Average Time Step : 1.00 sec
Maximum Time Step : 1.00 sec
Percent in Steady State : 0.00
Average Iterations per Step : 2.00
Percent Not Converging : 0.00

Perv	Total	Total Peak	Total Runoff	Total	Total	Imperv	
1 61 7	rocar	Precip	Runon	Evap	Infil	Runoff	
Runoff	Runoff	Runoff Runof	f Coeff	•			
Subcato	chment	mm	mm	mm	mm	mm	
mm	mm	10∧6 ltr LPS					
L104A		71.67	0.00	0.00	12.68	50.14	
7.82	57.96	0.13 101.36	0.809				
L104B		71.67	0.00	0.00	8.84	56.15	
5.51	61.66	0.06 45.52	0.860				
L107A		71.67	0.00	0.00	10.91	53.13	
6.51	59.64	0.07 51.77	0.832				
L109A		71.67	0.00	0.00	1.88	67.18	
1.20	68.38	0.04 25.82	0.954				
UNC-1	60.20	71.67	0.00	0.00	10.10	58.15	
60.38	60.38	0.03 25.22		0.00	10.00	45 43	
UNC-2	FO 0F	71.67	0.00	0.00	19.93	45.13	
50.85	50.85	0.02 19.47	0.709				

Node	Туре	Average Depth Meters	Maximum Depth Meters	Maximum HGL Meters	Occu	of Max rrence hr:min	Reported Max Depth Meters
1000	OUTFALL	0.00	0.00	72.09	0	00:00	0.00
1001	OUTFALL	0.00	0.00	0.00	0	00:00	0.00
1002	OUTFALL	0.00	0.00	0.00	0	00:00	0.00
101	STORAGE	0.31	0.47	72.74	0	01:21	0.47
102	STORAGE	0.31	0.41	72.80	0	01:23	0.41
103	STORAGE	0.31	0.43	72.91	0	01:23	0.43
104	STORAGE	0.31	0.43	73.10	0	01:23	0.43
105	STORAGE	0.30	0.42	72.88	0	01:13	0.42
106	STORAGE	0.30	0.45	73.06	0	01:12	0.45
107	STORAGE	0.30	0.43	73.21	Ŏ	01:12	0.43
		Da	ae 5				

Page 5

2019-07-31-100yrCHI.rpt								
108	STORAGE	0.30	0.35	73.02	0	01:28	0.35	
109	STORAGE	0.30	0.35	73.09	0	01:27	0.35	
110	STORAGE	0.00	0.00	72.95	0	00:00	0.00	
500-s	STORAGE	0.26	2.22	76.89	0	01:32	2.22	
501-S	STORAGE	0.14	2.23	76.39	0	01:21	2.23	
503-S	STORAGE	0.04	2.17	77.35	0	01:12	2.17	
504-S	STORAGE	0.07	1.19	78.24	0	01:26	1.19	

Total Inflow Volume Node ltr	Flow Balance Error Percent	Туре	Maximum Lateral Inflow LPS	Maximum Total Inflow LPS	0ccu	of Max rrence hr:min	Lateral Inflow Volume 10^6 ltr	10^6
1000 0.289 1001 0.0312 1002 0.0211 101 0.29 102 0.188 103 0.188 104 0.188 105 0.103 106 0.0679 107 0.0683 108 0.0355 109 0.0358 110 0 500-S 0.0589 501-S 0.127 503-S 0.0682 504-S 0.0358	0.000 0.000 0.000 0.011 0.005 0.006 0.005 -0.027 0.016 0.014 -0.062 0.034 0.000 ltr 0.011 -2.033 -0.039 0.001	OUTFALL OUTFALL STORAGE	0.00 25.22 19.47 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 45.52 101.36 51.77 25.82	52.82 25.22 19.47 52.86 25.07 25.07 27.83 25.62 25.63 3.95 3.95 0.00 45.52 101.36 51.77 25.82		01:22 01:10 01:10 01:21 01:23 01:23 01:22 01:13 01:12 01:12 01:27 01:26 00:00 01:10 01:10 01:10	0 0.0312 0.0211 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	

No nodes were surcharged.

No nodes were flooded.

of Max	Maximum	Average	Avg	Evap	Exfil	Maximum	Max	Time
		Volume	Pcnt	Pcnt	Pcnt	Volume	Pcnt	
Occurrence Storage hr:min		1000 m3	Full	Loss	Loss	1000 m3	Full	days
101		0.000	 7	0	0	0.001	10	0
01:21	52.82							
102 01:23	25.07	0.000	7	0	0	0.000	9	0
103		0.000	7	0	0	0.000	10	0
01:23 104	25.07	0.000	8	0	0	0.000	11	0
01:23	25.07			U	U			U
105 01:13	27.82	0.000	6	0	0	0.000	9	0
106	27.02	0.000	6	0	0	0.001	9	0
01:12	25.62							
107 01:12	25.62	0.000	7	0	0	0.000	9	0
108		0.000	5	0	0	0.000	6	0
01:28 109	3.95	0.000	5	0	0	0.000	6	0
01:27	3.95							
110	0.00	0.000	0	0	0	0.000	0	0
00:00 500-s	0.00	0.003	9	0	0	0.034	96	0
01:32	4.82							
501-S 01:21	20.27	0.003	4	0	0	0.059	95	0
503-s		0.000	2	0	0	0.017	89	0
01:12 504-s	25.63	0.002	10	0	0	0.020	90	0
01:18	3.95	0.002	10	U	U	0.020	30	U

Outfall Node	Flow	AVg	Max	Total
	Freq	Flow	Flow	Volume
	Pcnt	LPS	LPS	10^6 ltr
1000	23.11	14.49	52.82	0.289
1001	10.72	3.37	25.22	0.031
1002	9.66	2.53	19.47	0.021
System	14.50	20.39	19.47	0.342

Link	Туре	Maximum  Flow  LPS	Time of Max Occurrence days hr:min	Maximum  Veloc  m/sec	Max/ Full Flow	Max/ Full Depth
Pipe_11 Pipe_13 Pipe_14 Pipe_15 Pipe_16 Pipe_17 Pipe_19 Pipe_23 Pipe_24 Pipe_25 501-IC 503-IC W1 W2 500-IC 504-IC	CONDUIT WEIFICE WEIR WEIR DUMMY DUMMY	27.82 3.95 25.62 52.82 25.07 25.62 3.95 0.00 25.07 20.27 25.63 0.00 0.00 4.82 3.95	0 01:13 0 01:28 0 01:13 0 01:22 0 01:23 0 01:23 0 01:12 0 01:27 0 00:00 0 01:23 0 01:21 0 00:00 0 00:00 0 00:32 0 01:26	0.82 0.54 0.82 1.10 0.91 0.90 0.92 0.52 0.00	0.23 0.06 0.37 0.43 0.37 0.37 0.06 0.00	0.35 0.16 0.46 0.45 0.41 0.42 0.16 0.04 0.38 1.00 1.00 0.00

-	Adjusted			Fract	ion of	Time	in Flo	w Clas	S
Tulot	/Actual		Up	Down	Sub	Sup	Up	Down	Norm
Inlet Conduit Ctrl	Length	Dry	Dry	Dry	Crit	Crit	Crit	Crit	Ltd
- Pipe_11 0.00	1.00	0.03	0.00	0.00	0.10	0.00	0.00	0.87	0.09
Pipe_13	1.00	0.03	0.00	0.00	0.01	0.00	0.00	0.96	0.01
0.00 Pipe_14 0.00	1.00	0.03	0.00	0.00	0.00	0.00	0.00	0.97	0.00
Pipe_15	1.00	0.03	0.00 Page		0.00	0.00	0.00	0.97	0.00

	21	019-07-	-2T-TO	ууг Спт.	ipt				
0.00 Pipe_16	1.00	0.02	0.00	0.00	0.00	0.00	0.00	0 98	0.00
0.00		0.02							0.00
Pipe_17 0.00	1.00	0.02	0.00	0.00	0.00	0.00	0.00	0.98	0.00
Pipe_19	1.00	0.02	0.00	0.00	0.00	0.00	0.00	0.98	0.00
0.00 Pipe_23	1.00	0.03	0.00	0.00	0.00	0.00	0.00	0.97	0.00
0.00 Pipe_24	1.00	0.82	0.18	0.00	0.00	0.00	0.00	0.00	0.00
0.00 Pipe_25	1.00	0.02	0.00	0.00	0.00	0.00	0.00	0.98	0.00
0.00	1.00	0.02	0.00	0.00	0.00	0.00	0.00	0.50	0.00

\*\*\*\*\*\* Conduit Surcharge Summary

No conduits were surcharged.

Analysis begun on: Thu Aug 1 13:10:26 2019 Analysis ended on: Thu Aug 1 13:10:28 2019 Total elapsed time: 00:00:02

IDs:	1000		Combined
Date/Time	Total inflov Total		
M/d/yyyy 5/9/2019 0:01	L/s L/s	0	./s 0
5/9/2019 0:02	0	0	0
5/9/2019 0:02	0	0	0
5/9/2019 0:04	0	0	0
5/9/2019 0:05	0	0	0
5/9/2019 0:06	0	0	0
5/9/2019 0:07	0	0	0
5/9/2019 0:08	0	0	0
5/9/2019 0:09	0	0	0
5/9/2019 0:10	0	0	0
5/9/2019 0:11	0	0	0
5/9/2019 0:12	0	0	0
5/9/2019 0:13	0	0	0
5/9/2019 0:14	0	0	0
5/9/2019 0:15	0	0	0
5/9/2019 0:16	0	0	0
5/9/2019 0:17	0	0	0
5/9/2019 0:18	0	0	0
5/9/2019 0:19 5/9/2019 0:20	0 0	0 0	0 0
5/9/2019 0:21	0	0	0
5/9/2019 0:22	0	0	0
5/9/2019 0:23	0	0	0
5/9/2019 0:24	0	0	0
5/9/2019 0:25	0	0	0
5/9/2019 0:26	0	0	0
5/9/2019 0:27	0	0	0
5/9/2019 0:28	0	0	0
5/9/2019 0:29	0	0	0
5/9/2019 0:30	0	0	0
5/9/2019 0:31	0	0	0
5/9/2019 0:32	0	0	0
5/9/2019 0:33	0	0	0
5/9/2019 0:34	0	0	0
5/9/2019 0:35	0	0	0
5/9/2019 0:36	0	0	0
5/9/2019 0:37 5/9/2019 0:38	1.937701 3.856439	0 0	1.937701 3.856439
5/9/2019 0:39		0	4.755203
5/9/2019 0:40		0	5.160965
5/9/2019 0:40		0	5.374757
5/9/2019 0:42	5.555173	0	5.555173
5/9/2019 0:43	6.64827	0	6.64827
5/9/2019 0:44		0	8.029394

```
5/9/2019 0:45 8.921937
                              0 8.921937
5/9/2019 0:46 9.660272 0.012949 9.673221
5/9/2019 0:47 10.33572
                         0.1352 10.47092
5/9/2019 0:48 11.07053 0.327306 11.39784
5/9/2019 0:49 11.60917 0.545537 12.15471
5/9/2019 0:50 12.05302 0.760511 12.81353
5/9/2019 0:51 12.37909 1.101755 13.48085
5/9/2019 0:52 12.76886 1.713663 14.48253
5/9/2019 0:53 13.63045 2.470674 16.10113
5/9/2019 0:54 14.94776 3.216472 18.16424
5/9/2019 0:55 16.39298 3.846977 20.23996
5/9/2019 0:56 17.53414 4.327959
                                 21.8621
5/9/2019 0:57 18.58926 4.670991 23.26025
5/9/2019 0:58 19.49928 4.905598 24.40488
5/9/2019 0:59 20.26409 5.062397 25.32648
5/9/2019 1:00
               20.9227 5.166362 26.08907
5/9/2019 1:01 21.50517 6.680394 28.18556
5/9/2019 1:02 22.39859 12.20691
                                 34.6055
5/9/2019 1:03 24.32121
                        18.0198 42.34101
5/9/2019 1:04 27.32848 21.80431 49.13279
5/9/2019 1:05 33.47167 23.73278 57.20444
5/9/2019 1:06 36.80436 24.60131 61.40567
5/9/2019 1:07 39.15523 24.96995 64.12518
5/9/2019 1:08 40.69577
                        25.1233 65.81907
5/9/2019 1:09 42.43733 25.18811 67.62544
5/9/2019 1:10 47.43558 25.21736 72.65294
5/9/2019 1:11 50.83064 23.34134 74.17198
5/9/2019 1:12 52.00333 17.12795 69.13129
5/9/2019 1:13
              52.4323 13.02233 65.45464
5/9/2019 1:14 52.58932 10.63985 63.22918
5/9/2019 1:15 52.63081 9.269826 61.90064
5/9/2019 1:16 52.61367 8.477025 61.09069
5/9/2019 1:17 52.56041 8.016709 60.57711
5/9/2019 1:18 52.48021 7.750023 60.23023
5/9/2019 1:19 52.38068
                        7.59662
                                 59.9773
5/9/2019 1:20 52.39928 7.509405 59.90869
5/9/2019 1:21
              52.6359 7.164547 59.80045
5/9/2019 1:22 52.82446 6.297185 59.12164
5/9/2019 1:23 52.04871
                        5.50889 57.55759
5/9/2019 1:24 49.39414 4.912232 54.30637
5/9/2019 1:25 46.60036 4.487175 51.08754
5/9/2019 1:26 45.34741 4.191989
                                 49.5394
5/9/2019 1:27 45.04031 3.989748 49.03006
5/9/2019 1:28 44.88925 3.852486 48.74173
5/9/2019 1:29 44.73677 3.760101 48.49687
5/9/2019 1:30 44.57446 3.698446
                                  48.2729
5/9/2019 1:31 44.40488 3.576381 47.98127
```

```
5/9/2019 1:32 44.22169 3.340419 47.56211
5/9/2019 1:33 44.00172 3.102558 47.10427
5/9/2019 1:34 43.73721 2.900206 46.63741
5/9/2019 1:35
              43.4373 2.739798
                                 46.1771
5/9/2019 1:36 43.11415 2.617173 45.73132
5/9/2019 1:37 42.77502 2.525434 45.30045
5/9/2019 1:38 42.42472 2.457799 44.88251
5/9/2019 1:39 42.06667
                        2.40849 44.47515
5/9/2019 1:40
              41.7017 2.372879 44.07458
5/9/2019 1:41 41.33083 2.312394 43.64322
5/9/2019 1:42 40.95168 2.209642 43.16132
5/9/2019 1:43 40.54942 2.102004 42.65143
5/9/2019 1:44
              40.1173 2.005144 42.12244
5/9/2019 1:45
              39.6569 1.923855 41.58075
5/9/2019 1:46 39.17185 1.858207 41.03006
5/9/2019 1:47 38.66509 1.806446 40.47154
5/9/2019 1:48 38.13942 1.766297 39.90572
5/9/2019 1:49 37.59375 1.735532 39.32928
5/9/2019 1:50 37.02672 1.712184 38.73891
5/9/2019 1:51 36.43539 1.675896 38.11128
5/9/2019 1:52 35.81416 1.619457 37.43362
5/9/2019 1:53 35.15755 1.559416 36.71696
5/9/2019 1:54 34.46757 1.503636
                                 35.9712
5/9/2019 1:55 33.72833 1.455131 35.18346
5/9/2019 1:56 32.93579 1.414531 34.35033
5/9/2019 1:57 32.09859 1.381364 33.47995
5/9/2019 1:58 31.26113 1.354722 32.61585
5/9/2019 1:59 30.48879 1.333588 31.82238
5/9/2019 2:00 29.91633 1.316983 31.23332
5/9/2019 2:01 29.57631 1.292725 30.86903
5/9/2019 2:02 29.38337 1.257399 30.64077
                        1.21961 30.46116
5/9/2019 2:03 29.24155
5/9/2019 2:04 29.10728 1.183793 30.29108
              28.9782 1.151888 30.13008
5/9/2019 2:05
5/9/2019 2:06 28.86045 1.124495 29.98495
5/9/2019 2:07 28.75647 1.101535 29.85801
5/9/2019 2:08 28.66511 1.082612 29.74772
5/9/2019 2:09 28.58397 1.067209 29.65118
5/9/2019 2:10 28.51144 1.054791 29.56623
5/9/2019 2:11 28.44643 1.037332 29.48376
5/9/2019 2:12 28.38318
                        1.01306 29.39624
5/9/2019 2:13 28.30809 0.987034 29.29512
              28.2196 0.962022 29.18162
5/9/2019 2:14
5/9/2019 2:15 28.12733 0.939341 29.06668
5/9/2019 2:16 28.03935 0.919489 28.95884
5/9/2019 2:17 27.95875 0.902517 28.86126
5/9/2019 2:18 27.88562 0.888245 28.77387
```

```
5/9/2019 2:19 27.81895
                        0.87639 28.69534
5/9/2019 2:20 27.75757 0.866637
                                  28.6242
5/9/2019 2:21 27.69991
                       0.853469 28.55338
5/9/2019 2:22 27.64246 0.835937
                                  28.4784
5/9/2019 2:23 27.23057 0.817181 28.04775
5/9/2019 2:24 24.73656 0.798994 25.53555
5/9/2019 2:25 22.27139 0.782288 23.05368
5/9/2019 2:26 21.45463
                        0.76745 22.22208
5/9/2019 2:27
              21.1793 0.754567 21.93386
5/9/2019 2:28 20.99812 0.743559 21.74168
5/9/2019 2:29 20.83288 0.734267 21.56715
5/9/2019 2:30 20.67115 0.726496 21.39764
5/9/2019 2:31 20.50994 0.716247 21.22618
5/9/2019 2:32 20.34621 0.702996
                                  21.0492
5/9/2019 2:33 20.17276 0.688833 20.86159
5/9/2019 2:34
              19.9882
                          0.675
                                  20.6632
5/9/2019 2:35 19.79582 0.662157 20.45798
5/9/2019 2:36 19.60013
                        0.65061 20.25074
5/9/2019 2:37 19.40351 0.640454 20.04396
5/9/2019 2:38 19.20655 0.631661 19.83821
5/9/2019 2:39 19.00887 0.624138 19.63301
5/9/2019 2:40 18.80942 0.617759 19.42718
5/9/2019 2:41 18.60736 0.609491 19.21686
5/9/2019 2:42 18.40065 0.599046
                                  18.9997
5/9/2019 2:43 18.18228 0.587896 18.77017
5/9/2019 2:44 17.95051 0.576942 18.52745
5/9/2019 2:45 17.70808 0.566682 18.27476
5/9/2019 2:46
               17.4578 0.557364 18.01517
5/9/2019 2:47 17.20138 0.549079 17.75046
5/9/2019 2:48 16.93866 0.541823 17.48048
5/9/2019 2:49 16.66835 0.535542 17.20389
              16.3891 0.530154 16.91925
5/9/2019 2:50
5/9/2019 2:51 16.10032 0.523332 16.62366
5/9/2019 2:52 15.79786 0.514924 16.31278
5/9/2019 2:53 15.47768 0.505985 15.98366
5/9/2019 2:54 15.13336 0.497173 15.63053
5/9/2019 2:55 14.76437 0.488866 15.25324
5/9/2019 2:56 14.37151 0.481261 14.85277
5/9/2019 2:57 13.95447 0.474437 14.42891
5/9/2019 2:58 13.51246 0.468404 13.98087
5/9/2019 2:59 13.04491
                        0.46313 13.50804
5/9/2019 3:00 12.55176 0.458559 13.01032
5/9/2019 3:01 12.04139
                        0.45286 12.49425
5/9/2019 3:02 11.53274 0.445962 11.97871
5/9/2019 3:03 11.04644 0.438647 11.48508
5/9/2019 3:04 10.62177 0.431412 11.05318
5/9/2019 3:05
              10.3191 0.424551 10.74366
```

5/9/2019 3:06	10.12624	0.418224	10.54446
5/9/2019 3:07	10.04301	0.4125	10.45551
5/9/2019 3:08	9.997005	0.407398	10.4044
5/9/2019 3:09	9.965914	0.402897	10.36881
5/9/2019 3:10	9.942254	0.398962	10.34122
5/9/2019 3:11	9.921174	0.37524	10.29641
5/9/2019 3:12	9.823246	0.334133	10.15738
5/9/2019 3:13	9.521891	0.286492	9.808383
5/9/2019 3:14	9.098728	0.238492	9.33722
5/9/2019 3:15	8.622085	0.193313	8.815397
5/9/2019 3:16	8.255816	0.153313	8.408243
5/9/2019 3:17	7.963494	0.132427	8.079872
	7.732344	0.110379	7.817587
5/9/2019 3:18			
5/9/2019 3:19	7.548075	0.058896	7.606971
5/9/2019 3:20	7.397591	0.037174	7.434765
5/9/2019 3:21	7.2733	0.019999	7.293299
5/9/2019 3:22	7.167601	0.007526	7.175127
5/9/2019 3:23	7.078216	0.000571	7.078787
5/9/2019 3:24	7.000908	7.61E-06	7.000916
5/9/2019 3:25	6.930409	0	6.930409
5/9/2019 3:26	6.866066	0	6.866066
5/9/2019 3:27	6.810418	0	6.810418
5/9/2019 3:28	6.7601	0	6.7601
5/9/2019 3:29	6.649602	0	6.649602
5/9/2019 3:30	6.438038	0	6.438038
5/9/2019 3:31	6.177358	0	6.177358
5/9/2019 3:32	5.902721	0	5.902721
5/9/2019 3:33	5.629267	0	5.629267
5/9/2019 3:34	5.419872	0	5.419872
5/9/2019 3:35	5.309589	0	5.309589
5/9/2019 3:36	5.250773	0	5.250773
5/9/2019 3:37		0	5.213135
5/9/2019 3:38		0	5.183596
5/9/2019 3:39		0	5.157314
5/9/2019 3:40		0	5.132832
5/9/2019 3:41		0	5.109294
5/9/2019 3:42		0	5.086414
5/9/2019 3:43		0	5.06409
5/9/2019 3:44		0	5.042286
5/9/2019 3:45		0	
	5.02086		5.02086
5/9/2019 3:46	4.999696	0	4.999696
5/9/2019 3:47	4.978774	0	4.978774
5/9/2019 3:48	4.958079	0	4.958079
5/9/2019 3:49		0	4.937588
5/9/2019 3:50		0	4.917276
5/9/2019 3:51		0	4.897119
5/9/2019 3:52	4.877091	0	4.877091

5/9/2019 3:53	4.857172	0	4.857172
5/9/2019 3:54	4.837343	0	4.837343
5/9/2019 3:55	4.817594	0	4.817594
5/9/2019 3:56	4.79791	0	4.79791
5/9/2019 3:57	4.778269	0	4.778269
5/9/2019 3:58	4.758657	0	4.758657
5/9/2019 3:59	4.73908	0	4.73908
5/9/2019 4:00		0	
	4.71951		4.71951
5/9/2019 4:01	4.699916	0	4.699916
5/9/2019 4:02	4.680329	0	4.680329
5/9/2019 4:03	4.66074	0	4.66074
5/9/2019 4:04	4.64106	0	4.64106
5/9/2019 4:05	4.621263	0	4.621263
5/9/2019 4:06	4.601363	0	4.601363
5/9/2019 4:07	4.581367	0	4.581367
5/9/2019 4:08	4.561217	0	4.561217
5/9/2019 4:09	4.540736	0	4.540736
5/9/2019 4:10	4.520237	0	4.520237
5/9/2019 4:11		0	
	4.49973		4.49973
5/9/2019 4:12	4.479153	0	4.479153
5/9/2019 4:13	4.458469	0	4.458469
5/9/2019 4:14	4.437656	0	4.437656
5/9/2019 4:15	4.416697	0	4.416697
5/9/2019 4:16	4.395555	0	4.395555
5/9/2019 4:17	4.3742	0	4.3742
5/9/2019 4:18	4.35249	0	4.35249
5/9/2019 4:19	4.330461	0	4.330461
5/9/2019 4:20	4.30827	0	4.30827
5/9/2019 4:21	4.285987	0	4.285987
5/9/2019 4:22	4.263653	0	4.263653
		_	
5/9/2019 4:23	4.241199	0	4.241199
5/9/2019 4:24	4.218558	0	4.218558
5/9/2019 4:25	4.195735	0	4.195735
5/9/2019 4:26	4.172718	0	4.172718
5/9/2019 4:27	4.149594	0	4.149594
5/9/2019 4:28	4.126105	0	4.126105
5/9/2019 4:29	4.101791	0	4.101791
5/9/2019 4:30	4.077648	0	4.077648
5/9/2019 4:31	4.053291	0	4.053291
5/9/2019 4:32	4.028441	0	4.028441
5/9/2019 4:33	4.003329	0	4.003329
5/9/2019 4:34	3.978036	0	3.978036
5/9/2019 4:35	3.952497	0	3.952497
5/9/2019 4:36	3.92695	0	3.92695
5/9/2019 4:37	3.900989	0	3.900989
5/9/2019 4:38	3.874515	0	3.874515
5/9/2019 4:39	3.847622	0	3.847622

5/9/2019 4:40	3.820398	0	3.820398
5/9/2019 4:41	3.792899	0	3.792899
5/9/2019 4:42	3.764907	0	3.764907
5/9/2019 4:43	3.736387	0	3.736387
5/9/2019 4:44	3.707556	0	3.707556
5/9/2019 4:45	3.678297	0	3.678297
5/9/2019 4:46	3.648339	0	3.648339
5/9/2019 4:47	3.617808	0	3.617808
5/9/2019 4:48	3.586767	0	3.586767
5/9/2019 4:49	3.555435	0	3.555435
5/9/2019 4:50	3.523529	0	3.523529
5/9/2019 4:51	3.490802	0	3.490802
5/9/2019 4:52		0	3.457244
5/9/2019 4:53	3.422851	0	3.422851
5/9/2019 4:54	3.387525	0	3.387525
5/9/2019 4:55	3.351255	0	3.351255
5/9/2019 4:56	3.314045	0	3.314045
5/9/2019 4:57		0	3.275859
5/9/2019 4:58	3.236632	0	
			3.236632
5/9/2019 4:59	3.196311	0	3.196311
5/9/2019 5:00	3.154977	0	3.154977
5/9/2019 5:01	3.112205	0	3.112205
5/9/2019 5:02	3.067853	0	3.067853
5/9/2019 5:03	3.021835	0	3.021835
5/9/2019 5:04	2.973996	0	2.973996
5/9/2019 5:05	2.924396	0	2.924396
5/9/2019 5:06	2.872653	0	2.872653
5/9/2019 5:07		0	2.818173
5/9/2019 5:08	2.760628	0	2.760628
5/9/2019 5:09	2.700656	0	2.700656
5/9/2019 5:10	2.636053	0	2.636053
5/9/2019 5:11	2.565742	0	2.565742
• •	2.489034	0	2.489034
5/9/2019 5:13		0	2.403294
5/9/2019 5:14		0	2.302486
5/9/2019 5:15	2.180836	0	2.180836
5/9/2019 5:16	2.028031	0	2.028031
5/9/2019 5:17	1.855133	0	1.855133
5/9/2019 5:18	1.680052	0	1.680052
5/9/2019 5:19	1.542432	0	1.542432
5/9/2019 5:20	1.442613	0	1.442613
5/9/2019 5:21	1.368243	0	1.368243
5/9/2019 5:22	1.312948	0	1.312948
5/9/2019 5:23	1.270993	0	1.270993
5/9/2019 5:24	1.237326	0	1.237326
5/9/2019 5:25	1.208794	0	1.208794
5/9/2019 5:26	1.183591	0	1.183591
, -, 0.20		•	

5/9/2019 5:27         1.160635           5/9/2019 5:28         1.138988         0         1.138988           5/9/2019 5:29         1.117961         0         1.17961           5/9/2019 5:30         1.096904         0         1.096904           5/9/2019 5:31         1.075738         0         1.054487           5/9/2019 5:32         1.054487         0         1.054487           5/9/2019 5:33         1.032933         0         1.032933           5/9/2019 5:34         1.011078         0         1.011078           5/9/2019 5:35         0.989155         0         0.989155           5/9/2019 5:36         0.967158         0         0.967158           5/9/2019 5:37         0.944592         0         0.944592           5/9/2019 5:39         0.896556         0         0.896556           5/9/2019 5:40         0.871018         0         0.921081           5/9/2019 5:41         0.844282         0         0.844282           5/9/2019 5:42         0.816501         0         0.816501           5/9/2019 5:45         0.721354         0         0.721354           5/9/2019 5:46         0.682366         0         0.682366           5/9/2019 5:4				
5/9/2019 5:29         1.117961         0         1.096904           5/9/2019 5:31         1.075738         0         1.075738           5/9/2019 5:32         1.054487         0         1.054487           5/9/2019 5:33         1.032933         0         1.032933           5/9/2019 5:34         1.011078         0         1.011078           5/9/2019 5:35         0.989155         0         0.989155           5/9/2019 5:36         0.967158         0         0.967158           5/9/2019 5:37         0.944592         0         0.944592           5/9/2019 5:38         0.921081         0         0.921081           5/9/2019 5:39         0.896556         0         0.986556           5/9/2019 5:40         0.871018         0         0.871018           5/9/2019 5:41         0.844282         0         0.844282           5/9/2019 5:42         0.816501         0         0.816501           5/9/2019 5:43         0.787855         0         0.787855           5/9/2019 5:44         0.756259         0         0.756259           5/9/2019 5:45         0.721354         0         0.721354           5/9/2019 5:46         0.682366         0         0.682366 <td>5/9/2019 5:27</td> <td>1.160635</td> <td>0</td> <td>1.160635</td>	5/9/2019 5:27	1.160635	0	1.160635
5/9/2019 5:29         1.117961         0         1.096904           5/9/2019 5:31         1.075738         0         1.075738           5/9/2019 5:32         1.054487         0         1.054487           5/9/2019 5:33         1.032933         0         1.032933           5/9/2019 5:34         1.011078         0         1.011078           5/9/2019 5:35         0.989155         0         0.989155           5/9/2019 5:36         0.967158         0         0.967158           5/9/2019 5:37         0.944592         0         0.944592           5/9/2019 5:38         0.921081         0         0.921081           5/9/2019 5:39         0.896556         0         0.986556           5/9/2019 5:40         0.871018         0         0.871018           5/9/2019 5:41         0.844282         0         0.844282           5/9/2019 5:42         0.816501         0         0.816501           5/9/2019 5:43         0.787855         0         0.787855           5/9/2019 5:44         0.756259         0         0.756259           5/9/2019 5:45         0.721354         0         0.721354           5/9/2019 5:46         0.682366         0         0.682366 <td>5/9/2019 5:28</td> <td>1.138988</td> <td>0</td> <td>1.138988</td>	5/9/2019 5:28	1.138988	0	1.138988
5/9/2019 5:30         1.096904         0         1.096904           5/9/2019 5:31         1.075738         0         1.075738           5/9/2019 5:32         1.054487         0         1.054487           5/9/2019 5:33         1.032933         0         1.032933           5/9/2019 5:34         1.011078         0         1.011078           5/9/2019 5:35         0.989155         0         0.989155           5/9/2019 5:36         0.967158         0         0.967158           5/9/2019 5:37         0.944592         0         0.944592           5/9/2019 5:38         0.921081         0         0.921081           5/9/2019 5:39         0.896556         0         0.986556           5/9/2019 5:40         0.871018         0         0.871018           5/9/2019 5:41         0.844282         0         0.844282           5/9/2019 5:42         0.816501         0         0.816501           5/9/2019 5:43         0.787855         0         0.787855           5/9/2019 5:44         0.756259         0         0.756259           5/9/2019 5:45         0.721354         0         0.721354           5/9/2019 5:46         0.682366         0         0.682366 <td>• •</td> <td></td> <td></td> <td></td>	• •			
5/9/2019 5:31         1.075738         0         1.075738           5/9/2019 5:32         1.054487         0         1.054487           5/9/2019 5:33         1.032933         0         1.032933           5/9/2019 5:34         1.011078         0         1.011078           5/9/2019 5:35         0.989155         0         0.989155           5/9/2019 5:36         0.967158         0         0.967158           5/9/2019 5:37         0.944592         0         0.944592           5/9/2019 5:38         0.921081         0         0.921081           5/9/2019 5:39         0.896556         0         0.896556           5/9/2019 5:40         0.871018         0         0.871018           5/9/2019 5:41         0.844282         0         0.844282           5/9/2019 5:42         0.816501         0         0.816501           5/9/2019 5:43         0.787855         0         0.787855           5/9/2019 5:44         0.756259         0         0.756259           5/9/2019 5:45         0.721354         0         0.682366           5/9/2019 5:47         0.637832         0         0.682366           5/9/2019 5:48         0.721483         0         0.512948 <td>• •</td> <td></td> <td></td> <td></td>	• •			
5/9/2019 5:32         1.054487         0         1.032933           5/9/2019 5:34         1.011078         0         1.011078           5/9/2019 5:35         0.989155         0         0.989155           5/9/2019 5:36         0.967158         0         0.967158           5/9/2019 5:37         0.944592         0         0.944592           5/9/2019 5:38         0.921081         0         0.921081           5/9/2019 5:39         0.896556         0         0.896556           5/9/2019 5:40         0.871018         0         0.871018           5/9/2019 5:41         0.844282         0         0.846561           5/9/2019 5:42         0.816501         0         0.816501           5/9/2019 5:43         0.787855         0         0.787855           5/9/2019 5:44         0.756259         0         0.756259           5/9/2019 5:45         0.721354         0         0.721354           5/9/2019 5:46         0.682366         0         0.682366           5/9/2019 5:47         0.637832         0         0.637832           5/9/2019 5:49         0.512948         0         0.512948           5/9/2019 5:50         0.424853         0         0.424853 <td></td> <td></td> <td></td> <td></td>				
5/9/2019 5:34         1.032933         0 1.011078           5/9/2019 5:35         0.989155         0 0.989155           5/9/2019 5:36         0.967158         0 0.967158           5/9/2019 5:37         0.944592         0 0.944592           5/9/2019 5:38         0.921081         0 0.921081           5/9/2019 5:39         0.896556         0 0.896556           5/9/2019 5:40         0.871018         0 0.871018           5/9/2019 5:41         0.844282         0 0.844282           5/9/2019 5:42         0.816501         0 0.816501           5/9/2019 5:43         0.787855         0 0.787855           5/9/2019 5:44         0.756259         0 0.756259           5/9/2019 5:44         0.756259         0 0.721354           5/9/2019 5:45         0.721354         0 0.682366           5/9/2019 5:46         0.682366         0 0.682366           5/9/2019 5:47         0.637832         0 0.637832           5/9/2019 5:50         0.424853         0 0.424853           5/9/2019 5:51         0.345859         0 0.345859           5/9/2019 5:52         0.2848         0 0.2296           5/9/2019 5:54         0.188137         0 0.131917           5/9/2019 5:55         0.113257	5/9/2019 5:31	1.075738	0	1.075738
5/9/2019 5:34         1.011078         0 1.011078           5/9/2019 5:35         0.989155         0 0.989155           5/9/2019 5:36         0.967158         0 0.944592           5/9/2019 5:37         0.944592         0 0.944592           5/9/2019 5:38         0.921081         0 0.921081           5/9/2019 5:40         0.871018         0 0.871018           5/9/2019 5:41         0.844282         0 0.844282           5/9/2019 5:42         0.816501         0 0.816501           5/9/2019 5:43         0.787855         0 0.787855           5/9/2019 5:44         0.756259         0 0.756259           5/9/2019 5:44         0.756259         0 0.756259           5/9/2019 5:45         0.721354         0 0.721354           5/9/2019 5:46         0.682366         0 0.682366           5/9/2019 5:47         0.637832         0 0.637832           5/9/2019 5:49         0.512948         0 0.512948           5/9/2019 5:50         0.424853         0 0.424853           5/9/2019 5:51         0.345859         0 0.345859           5/9/2019 5:52         0.2848         0 0.2296           5/9/2019 5:54         0.118257         0 0.113257           5/9/2019 5:55         0.113257	5/9/2019 5:32	1.054487	0	1.054487
5/9/2019 5:34         1.011078         0 1.011078           5/9/2019 5:35         0.989155         0 0.989155           5/9/2019 5:36         0.967158         0 0.944592           5/9/2019 5:37         0.944592         0 0.944592           5/9/2019 5:38         0.921081         0 0.921081           5/9/2019 5:40         0.871018         0 0.871018           5/9/2019 5:41         0.844282         0 0.844282           5/9/2019 5:42         0.816501         0 0.816501           5/9/2019 5:43         0.787855         0 0.787855           5/9/2019 5:44         0.756259         0 0.756259           5/9/2019 5:44         0.756259         0 0.756259           5/9/2019 5:45         0.721354         0 0.721354           5/9/2019 5:46         0.682366         0 0.682366           5/9/2019 5:47         0.637832         0 0.637832           5/9/2019 5:49         0.512948         0 0.512948           5/9/2019 5:50         0.424853         0 0.424853           5/9/2019 5:51         0.345859         0 0.345859           5/9/2019 5:52         0.2848         0 0.2296           5/9/2019 5:54         0.118257         0 0.113257           5/9/2019 5:55         0.113257	5/9/2019 5:33	1.032933	0	1.032933
5/9/2019 5:35         0.989155         0.0967158           5/9/2019 5:36         0.967158         0.0967158           5/9/2019 5:37         0.944592         0.0944592           5/9/2019 5:38         0.921081         0.0921081           5/9/2019 5:39         0.896556         0.896556           5/9/2019 5:40         0.871018         0.0871018           5/9/2019 5:41         0.844282         0.0844282           5/9/2019 5:42         0.816501         0.0816501           5/9/2019 5:43         0.787855         0.0756259           5/9/2019 5:44         0.756259         0.0756259           5/9/2019 5:45         0.721354         0.0721354           5/9/2019 5:46         0.682366         0.0682366           5/9/2019 5:47         0.637832         0.0637832           5/9/2019 5:49         0.512948         0.0512948           5/9/2019 5:50         0.424853         0.0424853           5/9/2019 5:51         0.345859         0.02296           5/9/2019 5:52         0.2848         0.02296           5/9/2019 5:55         0.156404         0.0131917           5/9/2019 5:56         0.131917         0.0131257           5/9/2019 5:59         0.085762         0.006921	• •			
5/9/2019 5:36       0.967158       0.944592       0.0944592         5/9/2019 5:37       0.944592       0.0944592       0.921081         5/9/2019 5:38       0.921081       0.0921081       0.921081         5/9/2019 5:40       0.871018       0.0871018       0.871018         5/9/2019 5:41       0.844282       0.0844282       0.0844282         5/9/2019 5:42       0.816501       0.0816501       0.787855         5/9/2019 5:43       0.787855       0.0756259       0.0756259         5/9/2019 5:44       0.756259       0.0756259       0.721354         5/9/2019 5:45       0.721354       0.0721354       0.0721354         5/9/2019 5:46       0.682366       0.0682366       0.637832         5/9/2019 5:47       0.637832       0.0637832       0.0637832         5/9/2019 5:49       0.512948       0.0512948         5/9/2019 5:50       0.424853       0.0424853         5/9/2019 5:51       0.345859       0.02296         5/9/2019 5:52       0.2848       0.02296         5/9/2019 5:53       0.156404       0.0183137         5/9/2019 5:55       0.131917       0.0131917         5/9/2019 5:56       0.131917       0.0132572         5/9/201	• •			
5/9/2019 5:37         0.944592         0 0.921081           5/9/2019 5:38         0.921081         0 0.921081           5/9/2019 5:39         0.896556         0 0.896556           5/9/2019 5:40         0.871018         0 0.871018           5/9/2019 5:41         0.844282         0 0.844282           5/9/2019 5:42         0.816501         0 0.816501           5/9/2019 5:43         0.787855         0 0.787855           5/9/2019 5:44         0.756259         0 0.756259           5/9/2019 5:45         0.721354         0 0.721354           5/9/2019 5:46         0.682366         0 0.682366           5/9/2019 5:47         0.637832         0 0.637832           5/9/2019 5:48         0.584019         0 0.584019           5/9/2019 5:49         0.512948         0 0.512948           5/9/2019 5:50         0.424853         0 0.424853           5/9/2019 5:51         0.345859         0 0.345859           5/9/2019 5:52         0.2848         0 0.2296           5/9/2019 5:53         0.2296         0 0.2296           5/9/2019 5:54         0.188137         0 0.136404           5/9/2019 5:55         0.156404         0 0.136404           5/9/2019 5:59         0.085762 <t< td=""><td></td><td></td><td></td><td></td></t<>				
5/9/2019 5:38         0.921081         0.0921081           5/9/2019 5:39         0.896556         0.87656           5/9/2019 5:40         0.871018         0.871018           5/9/2019 5:41         0.844282         0.844282           5/9/2019 5:42         0.816501         0.816501           5/9/2019 5:43         0.787855         0.787855           5/9/2019 5:44         0.756259         0.0.756259           5/9/2019 5:45         0.721354         0.0721354           5/9/2019 5:46         0.682366         0.0682366           5/9/2019 5:47         0.637832         0.0637832           5/9/2019 5:49         0.512948         0.0512948           5/9/2019 5:50         0.424853         0.0424853           5/9/2019 5:51         0.345859         0.0345859           5/9/2019 5:52         0.2848         0.02296           5/9/2019 5:54         0.188137         0.0188137           5/9/2019 5:55         0.156404         0.0156404           5/9/2019 5:56         0.131917         0.0131917           5/9/2019 5:58         0.098129         0.0085762           5/9/2019 6:00         0.075521         0.0059674           5/9/2019 6:03         0.053757         0.0053757	5/9/2019 5:36	0.967158	0	0.967158
5/9/2019 5:39       0.896556       0 0.871018         5/9/2019 5:40       0.871018       0 0.871018         5/9/2019 5:41       0.844282       0 0.844282         5/9/2019 5:42       0.816501       0 0.787855         5/9/2019 5:43       0.787855       0 0.787855         5/9/2019 5:44       0.756259       0 0.756259         5/9/2019 5:45       0.721354       0 0.721354         5/9/2019 5:46       0.682366       0 0.682366         5/9/2019 5:47       0.637832       0 0.637832         5/9/2019 5:49       0.512948       0 0.512948         5/9/2019 5:50       0.424853       0 0.424853         5/9/2019 5:51       0.345859       0 0.345859         5/9/2019 5:52       0.2848       0 0.2296         5/9/2019 5:53       0.2296       0 0.2296         5/9/2019 5:54       0.188137       0 0.188137         5/9/2019 5:55       0.156404       0 0.156404         5/9/2019 5:56       0.131917       0 0.131917         5/9/2019 5:57       0.113257       0 0.098129         5/9/2019 6:00       0.075521       0 0.075521         5/9/2019 6:01       0.066921       0 0.059674         5/9/2019 6:05       0.043696       0 0.043696	5/9/2019 5:37	0.944592	0	0.944592
5/9/2019 5:39       0.896556       0 0.871018         5/9/2019 5:40       0.871018       0 0.871018         5/9/2019 5:41       0.844282       0 0.844282         5/9/2019 5:42       0.816501       0 0.787855         5/9/2019 5:43       0.787855       0 0.787855         5/9/2019 5:44       0.756259       0 0.756259         5/9/2019 5:45       0.721354       0 0.721354         5/9/2019 5:46       0.682366       0 0.682366         5/9/2019 5:47       0.637832       0 0.637832         5/9/2019 5:49       0.512948       0 0.512948         5/9/2019 5:50       0.424853       0 0.424853         5/9/2019 5:51       0.345859       0 0.345859         5/9/2019 5:52       0.2848       0 0.2296         5/9/2019 5:53       0.2296       0 0.2296         5/9/2019 5:54       0.188137       0 0.188137         5/9/2019 5:55       0.156404       0 0.156404         5/9/2019 5:56       0.131917       0 0.131917         5/9/2019 5:57       0.113257       0 0.098129         5/9/2019 6:00       0.075521       0 0.075521         5/9/2019 6:01       0.066921       0 0.059674         5/9/2019 6:05       0.043696       0 0.043696	5/9/2019 5:38	0.921081	0	0.921081
5/9/2019 5:40       0.871018       0 0.844282         5/9/2019 5:41       0.844282       0 0.844282         5/9/2019 5:42       0.816501       0 0.816501         5/9/2019 5:43       0.787855       0 0.787855         5/9/2019 5:44       0.756259       0 0.756259         5/9/2019 5:45       0.721354       0 0.721354         5/9/2019 5:46       0.682366       0 0.682366         5/9/2019 5:47       0.637832       0 0.637832         5/9/2019 5:49       0.512948       0 0.512948         5/9/2019 5:49       0.512948       0 0.512948         5/9/2019 5:50       0.424853       0 0.424853         5/9/2019 5:51       0.345859       0 0.345859         5/9/2019 5:52       0.2848       0 0.2296         5/9/2019 5:53       0.2296       0 0.2296         5/9/2019 5:54       0.188137       0 0.188137         5/9/2019 5:55       0.156404       0 0.156404         5/9/2019 5:56       0.131917       0 0.131917         5/9/2019 5:57       0.113257       0 0.098129         5/9/2019 6:00       0.075521       0 0.075521         5/9/2019 6:01       0.066921       0 0.059674         5/9/2019 6:05       0.043696       0 0.043696				
5/9/2019 5:41       0.844282       0       0.816501         5/9/2019 5:42       0.816501       0       0.816501         5/9/2019 5:43       0.787855       0       0.787855         5/9/2019 5:44       0.756259       0       0.756259         5/9/2019 5:45       0.721354       0       0.721354         5/9/2019 5:46       0.682366       0       0.682366         5/9/2019 5:47       0.637832       0       0.637832         5/9/2019 5:48       0.584019       0       0.584019         5/9/2019 5:49       0.512948       0       0.512948         5/9/2019 5:50       0.424853       0       0.424853         5/9/2019 5:51       0.345859       0       0.345859         5/9/2019 5:52       0.2848       0       0.2296         5/9/2019 5:53       0.2296       0       0.2296         5/9/2019 5:54       0.188137       0       0.188137         5/9/2019 5:55       0.156404       0       0.156404         5/9/2019 5:56       0.131917       0       0.131917         5/9/2019 5:57       0.113257       0       0.075521         5/9/2019 6:00       0.075521       0       0.075521				
5/9/2019 5:42       0.816501       0 0.816501         5/9/2019 5:43       0.787855       0 0.787855         5/9/2019 5:44       0.756259       0 0.756259         5/9/2019 5:45       0.721354       0 0.721354         5/9/2019 5:46       0.682366       0 0.682366         5/9/2019 5:47       0.637832       0 0.637832         5/9/2019 5:48       0.584019       0 0.584019         5/9/2019 5:49       0.512948       0 0.512948         5/9/2019 5:50       0.424853       0 0.424853         5/9/2019 5:51       0.345859       0 0.345859         5/9/2019 5:52       0.2848       0 0.2848         5/9/2019 5:53       0.2296       0 0.2296         5/9/2019 5:54       0.188137       0 0.188137         5/9/2019 5:55       0.156404       0 0.156404         5/9/2019 5:56       0.131917       0 0.131917         5/9/2019 5:58       0.098129       0 0.098129         5/9/2019 5:59       0.085762       0 0.075521         5/9/2019 6:00       0.075521       0 0.059674         5/9/2019 6:03       0.053757       0 0.053757         5/9/2019 6:05       0.043696       0 0.0435061         5/9/2019 6:06       0.039148       0 0.03506				
5/9/2019 5:43       0.787855       0       0.756259         5/9/2019 5:45       0.721354       0       0.721354         5/9/2019 5:46       0.682366       0       0.682366         5/9/2019 5:47       0.637832       0       0.637832         5/9/2019 5:48       0.584019       0       0.584019         5/9/2019 5:49       0.512948       0       0.512948         5/9/2019 5:50       0.424853       0       0.424853         5/9/2019 5:51       0.345859       0       0.345859         5/9/2019 5:52       0.2848       0       0.2296         5/9/2019 5:53       0.2296       0       0.2296         5/9/2019 5:54       0.188137       0       0.188137         5/9/2019 5:55       0.156404       0       0.156404         5/9/2019 5:56       0.131917       0       0.131917         5/9/2019 5:57       0.113257       0       0.098129         5/9/2019 5:59       0.085762       0       0.0985762         5/9/2019 6:00       0.075521       0       0.075521         5/9/2019 6:01       0.066921       0       0.059674         5/9/2019 6:03       0.053757       0       0.053757 <tr< td=""><td>5/9/2019 5:41</td><td>0.844282</td><td>0</td><td>0.844282</td></tr<>	5/9/2019 5:41	0.844282	0	0.844282
5/9/2019 5:44       0.756259       0 0.756259         5/9/2019 5:45       0.721354       0 0.721354         5/9/2019 5:46       0.682366       0 0.682366         5/9/2019 5:47       0.637832       0 0.637832         5/9/2019 5:48       0.584019       0 0.584019         5/9/2019 5:49       0.512948       0 0.512948         5/9/2019 5:50       0.424853       0 0.424853         5/9/2019 5:51       0.345859       0 0.345859         5/9/2019 5:52       0.2848       0 0.2848         5/9/2019 5:53       0.2296       0 0.2296         5/9/2019 5:54       0.188137       0 0.188137         5/9/2019 5:55       0.156404       0 0.156404         5/9/2019 5:56       0.131917       0 0.131917         5/9/2019 5:57       0.113257       0 0.0131917         5/9/2019 5:58       0.098129       0 0.098129         5/9/2019 6:00       0.075521       0 0.075521         5/9/2019 6:01       0.066921       0 0.056921         5/9/2019 6:02       0.059674       0 0.059674         5/9/2019 6:03       0.035061       0 0.043696         5/9/2019 6:06       0.039148       0 0.039148         5/9/2019 6:08       0.031484       0 0.02573	5/9/2019 5:42	0.816501	0	0.816501
5/9/2019 5:45       0.721354       0 0.721354         5/9/2019 5:46       0.682366       0 0.682366         5/9/2019 5:47       0.637832       0 0.637832         5/9/2019 5:48       0.584019       0 0.584019         5/9/2019 5:49       0.512948       0 0.512948         5/9/2019 5:50       0.424853       0 0.424853         5/9/2019 5:51       0.345859       0 0.345859         5/9/2019 5:52       0.2848       0 0.2848         5/9/2019 5:53       0.2296       0 0.2296         5/9/2019 5:54       0.188137       0 0.188137         5/9/2019 5:55       0.156404       0 0.156404         5/9/2019 5:56       0.131917       0 0.131917         5/9/2019 5:57       0.113257       0 0.0131257         5/9/2019 5:58       0.098129       0 0.098129         5/9/2019 6:00       0.075521       0 0.075521         5/9/2019 6:01       0.066921       0 0.066921         5/9/2019 6:02       0.059674       0 0.059674         5/9/2019 6:03       0.053757       0 0.035061         5/9/2019 6:06       0.039148       0 0.039148         5/9/2019 6:07       0.035061       0 0.035061         5/9/2019 6:09       0.028392       0 0.02839	5/9/2019 5:43	0.787855	0	0.787855
5/9/2019 5:45       0.721354       0 0.721354         5/9/2019 5:46       0.682366       0 0.682366         5/9/2019 5:47       0.637832       0 0.637832         5/9/2019 5:48       0.584019       0 0.584019         5/9/2019 5:49       0.512948       0 0.512948         5/9/2019 5:50       0.424853       0 0.424853         5/9/2019 5:51       0.345859       0 0.345859         5/9/2019 5:52       0.2848       0 0.2848         5/9/2019 5:53       0.2296       0 0.2296         5/9/2019 5:54       0.188137       0 0.188137         5/9/2019 5:55       0.156404       0 0.156404         5/9/2019 5:56       0.131917       0 0.131917         5/9/2019 5:57       0.113257       0 0.0131257         5/9/2019 5:58       0.098129       0 0.098129         5/9/2019 6:00       0.075521       0 0.075521         5/9/2019 6:01       0.066921       0 0.066921         5/9/2019 6:02       0.059674       0 0.059674         5/9/2019 6:03       0.053757       0 0.035061         5/9/2019 6:06       0.039148       0 0.039148         5/9/2019 6:07       0.035061       0 0.035061         5/9/2019 6:09       0.028392       0 0.02839	5/9/2019 5:44	0 756259	0	0.756259
5/9/2019 5:46       0.682366       0 0.682366         5/9/2019 5:47       0.637832       0 0.637832         5/9/2019 5:48       0.584019       0 0.584019         5/9/2019 5:49       0.512948       0 0.512948         5/9/2019 5:50       0.424853       0 0.424853         5/9/2019 5:51       0.345859       0 0.345859         5/9/2019 5:52       0.2848       0 0.2848         5/9/2019 5:53       0.2296       0 0.2296         5/9/2019 5:54       0.188137       0 0.188137         5/9/2019 5:55       0.156404       0 0.156404         5/9/2019 5:56       0.131917       0 0.131917         5/9/2019 5:57       0.113257       0 0.098129         5/9/2019 5:59       0.085762       0 0.085762         5/9/2019 6:00       0.075521       0 0.075521         5/9/2019 6:01       0.066921       0 0.066921         5/9/2019 6:03       0.053757       0 0.053757         5/9/2019 6:04       0.048541       0 0.048541         5/9/2019 6:05       0.043696       0 0.035061         5/9/2019 6:07       0.035061       0 0.035061         5/9/2019 6:09       0.028392       0 0.028392         5/9/2019 6:10       0.025732       0 0.025732				
5/9/2019 5:47       0.637832       0 0.637832         5/9/2019 5:48       0.584019       0 0.584019         5/9/2019 5:49       0.512948       0 0.512948         5/9/2019 5:50       0.424853       0 0.424853         5/9/2019 5:51       0.345859       0 0.345859         5/9/2019 5:52       0.2848       0 0.2848         5/9/2019 5:53       0.2296       0 0.2296         5/9/2019 5:54       0.188137       0 0.188137         5/9/2019 5:55       0.156404       0 0.156404         5/9/2019 5:56       0.131917       0 0.131917         5/9/2019 5:57       0.113257       0 0.098129         5/9/2019 5:59       0.085762       0 0.098129         5/9/2019 6:00       0.075521       0 0.075521         5/9/2019 6:01       0.066921       0 0.059674         5/9/2019 6:03       0.053757       0 0.053757         5/9/2019 6:04       0.048541       0 0.048541         5/9/2019 6:05       0.043696       0 0.043696         5/9/2019 6:07       0.035061       0 0.035061         5/9/2019 6:09       0.028392       0 0.028392         5/9/2019 6:10       0.025732       0 0.025732         5/9/2019 6:11       0.023282       0 0.023282				
5/9/2019 5:48       0.584019       0 0.584019         5/9/2019 5:49       0.512948       0 0.512948         5/9/2019 5:50       0.424853       0 0.424853         5/9/2019 5:51       0.345859       0 0.345859         5/9/2019 5:52       0.2848       0 0.2848         5/9/2019 5:53       0.2296       0 0.2296         5/9/2019 5:54       0.188137       0 0.188137         5/9/2019 5:55       0.156404       0 0.156404         5/9/2019 5:56       0.131917       0 0.131917         5/9/2019 5:57       0.113257       0 0.13257         5/9/2019 5:58       0.098129       0 0.098129         5/9/2019 5:59       0.085762       0 0.085762         5/9/2019 6:00       0.075521       0 0.075521         5/9/2019 6:01       0.066921       0 0.066921         5/9/2019 6:02       0.059674       0 0.059674         5/9/2019 6:03       0.053757       0 0.053757         5/9/2019 6:04       0.048541       0 0.048541         5/9/2019 6:05       0.043696       0 0.039148         5/9/2019 6:07       0.035061       0 0.035061         5/9/2019 6:09       0.028392       0 0.028392         5/9/2019 6:10       0.025732       0 0.025732<	• •			
5/9/2019 5:490.51294800.5129485/9/2019 5:500.42485300.4248535/9/2019 5:510.34585900.3458595/9/2019 5:520.284800.28485/9/2019 5:530.229600.22965/9/2019 5:540.18813700.1881375/9/2019 5:550.15640400.1564045/9/2019 5:560.13191700.1319175/9/2019 5:570.11325700.132575/9/2019 5:580.09812900.0981295/9/2019 5:590.08576200.0857625/9/2019 6:000.07552100.0755215/9/2019 6:010.06692100.0669215/9/2019 6:020.05967400.0596745/9/2019 6:030.05375700.0537575/9/2019 6:040.04854100.0485415/9/2019 6:050.04369600.0436965/9/2019 6:070.03506100.0350615/9/2019 6:080.03148400.0314845/9/2019 6:100.02573200.0257325/9/2019 6:110.02328200.0232825/9/2019 6:120.01971400.019714	5/9/2019 5:47	0.637832	0	0.637832
5/9/2019 5:500.42485300.4248535/9/2019 5:510.34585900.3458595/9/2019 5:520.284800.28485/9/2019 5:530.229600.22965/9/2019 5:540.18813700.1881375/9/2019 5:550.15640400.1564045/9/2019 5:560.13191700.1319175/9/2019 5:570.11325700.0132575/9/2019 5:580.09812900.0981295/9/2019 5:590.08576200.0857625/9/2019 6:000.07552100.0755215/9/2019 6:010.06692100.0669215/9/2019 6:020.05967400.0596745/9/2019 6:030.05375700.0537575/9/2019 6:040.04854100.0485415/9/2019 6:050.04369600.0391485/9/2019 6:070.03506100.0350615/9/2019 6:080.03148400.0283925/9/2019 6:100.02573200.0257325/9/2019 6:110.02328200.0232825/9/2019 6:120.01971400.019714	5/9/2019 5:48	0.584019	0	0.584019
5/9/2019 5:500.42485300.4248535/9/2019 5:510.34585900.3458595/9/2019 5:520.284800.28485/9/2019 5:530.229600.22965/9/2019 5:540.18813700.1881375/9/2019 5:550.15640400.1564045/9/2019 5:560.13191700.1319175/9/2019 5:570.11325700.0132575/9/2019 5:580.09812900.0981295/9/2019 5:590.08576200.0857625/9/2019 6:000.07552100.0755215/9/2019 6:010.06692100.0669215/9/2019 6:020.05967400.0596745/9/2019 6:030.05375700.0537575/9/2019 6:040.04854100.0485415/9/2019 6:050.04369600.0391485/9/2019 6:070.03506100.0350615/9/2019 6:080.03148400.0283925/9/2019 6:100.02573200.0257325/9/2019 6:110.02328200.0232825/9/2019 6:120.01971400.019714	5/9/2019 5:49	0.512948	0	0.512948
5/9/2019 5:510.34585900.3458595/9/2019 5:520.284800.28485/9/2019 5:530.229600.22965/9/2019 5:540.18813700.1881375/9/2019 5:550.15640400.1564045/9/2019 5:560.13191700.1319175/9/2019 5:570.11325700.1132575/9/2019 5:580.09812900.0981295/9/2019 5:590.08576200.0857625/9/2019 6:000.07552100.0755215/9/2019 6:010.06692100.0669215/9/2019 6:020.05967400.0596745/9/2019 6:030.05375700.0537575/9/2019 6:040.04854100.0485415/9/2019 6:050.04369600.0391485/9/2019 6:060.03914800.0391485/9/2019 6:070.03506100.0350615/9/2019 6:090.02839200.0283925/9/2019 6:100.02573200.0257325/9/2019 6:110.02328200.0232825/9/2019 6:120.01971400.019714	5/9/2019 5:50	0.424853	0	0.424853
5/9/2019 5:520.284800.28485/9/2019 5:530.229600.22965/9/2019 5:540.18813700.1881375/9/2019 5:550.15640400.1564045/9/2019 5:560.13191700.1319175/9/2019 5:570.11325700.1132575/9/2019 5:580.09812900.0981295/9/2019 5:590.08576200.0857625/9/2019 6:000.07552100.0755215/9/2019 6:010.06692100.0669215/9/2019 6:020.05967400.0596745/9/2019 6:030.05375700.0537575/9/2019 6:040.04854100.0485415/9/2019 6:050.04369600.0391485/9/2019 6:070.03506100.0350615/9/2019 6:080.03148400.0314845/9/2019 6:100.02573200.0257325/9/2019 6:110.02328200.0232825/9/2019 6:120.01971400.019714				
5/9/2019 5:530.229600.22965/9/2019 5:540.18813700.1881375/9/2019 5:550.15640400.1564045/9/2019 5:560.13191700.1319175/9/2019 5:570.11325700.1132575/9/2019 5:580.09812900.0981295/9/2019 5:590.08576200.0857625/9/2019 6:000.07552100.0755215/9/2019 6:010.06692100.0669215/9/2019 6:020.05967400.0596745/9/2019 6:030.05375700.0537575/9/2019 6:040.04854100.0485415/9/2019 6:050.04369600.0436965/9/2019 6:060.03914800.0350615/9/2019 6:080.03148400.0314845/9/2019 6:090.02839200.0283925/9/2019 6:100.02573200.0257325/9/2019 6:110.02328200.0232825/9/2019 6:120.01971400.019714				
5/9/2019 5:540.18813700.1881375/9/2019 5:550.15640400.1564045/9/2019 5:560.13191700.1319175/9/2019 5:570.11325700.1132575/9/2019 5:580.09812900.0981295/9/2019 5:590.08576200.0857625/9/2019 6:000.07552100.0755215/9/2019 6:010.06692100.0669215/9/2019 6:020.05967400.0596745/9/2019 6:030.05375700.0537575/9/2019 6:040.04854100.0485415/9/2019 6:050.04369600.0391485/9/2019 6:060.03914800.0350615/9/2019 6:070.03506100.0350615/9/2019 6:090.02839200.0283925/9/2019 6:100.02573200.0257325/9/2019 6:110.02328200.0232825/9/2019 6:120.01971400.019714				
5/9/2019 5:550.15640400.1564045/9/2019 5:560.13191700.1319175/9/2019 5:570.11325700.1132575/9/2019 5:580.09812900.0981295/9/2019 5:590.08576200.0857625/9/2019 6:000.07552100.0755215/9/2019 6:010.06692100.0669215/9/2019 6:020.05967400.0596745/9/2019 6:030.05375700.0537575/9/2019 6:040.04854100.0485415/9/2019 6:050.04369600.0391485/9/2019 6:060.03914800.0350615/9/2019 6:070.03506100.0350615/9/2019 6:090.02839200.0283925/9/2019 6:100.02573200.0257325/9/2019 6:110.02328200.0232825/9/2019 6:120.01971400.019714				
5/9/2019 5:560.13191700.1319175/9/2019 5:570.11325700.1132575/9/2019 5:580.09812900.0981295/9/2019 5:590.08576200.0857625/9/2019 6:000.07552100.0755215/9/2019 6:010.06692100.0596745/9/2019 6:020.05967400.0596745/9/2019 6:030.05375700.0537575/9/2019 6:040.04854100.0485415/9/2019 6:050.04369600.0391485/9/2019 6:060.03914800.0350615/9/2019 6:070.03506100.0350615/9/2019 6:080.03148400.0314845/9/2019 6:100.02573200.0283925/9/2019 6:110.02328200.0232825/9/2019 6:120.01971400.019714			0	
5/9/2019 5:570.11325700.1132575/9/2019 5:580.09812900.0981295/9/2019 5:590.08576200.0857625/9/2019 6:000.07552100.0755215/9/2019 6:010.06692100.0669215/9/2019 6:020.05967400.0596745/9/2019 6:030.05375700.0537575/9/2019 6:040.04854100.0485415/9/2019 6:050.04369600.0391485/9/2019 6:060.03914800.0350615/9/2019 6:070.03506100.0350615/9/2019 6:080.03148400.0314845/9/2019 6:100.02573200.0257325/9/2019 6:110.02328200.0232825/9/2019 6:120.01971400.019714	5/9/2019 5:55	0.156404	0	0.156404
5/9/2019 5:580.09812900.0981295/9/2019 5:590.08576200.0857625/9/2019 6:000.07552100.0755215/9/2019 6:010.06692100.0669215/9/2019 6:020.05967400.0596745/9/2019 6:030.05375700.0537575/9/2019 6:040.04854100.0485415/9/2019 6:050.04369600.0436965/9/2019 6:060.03914800.0391485/9/2019 6:070.03506100.0350615/9/2019 6:080.03148400.0314845/9/2019 6:100.02573200.0257325/9/2019 6:110.02328200.0232825/9/2019 6:120.01971400.019714	5/9/2019 5:56	0.131917	0	0.131917
5/9/2019 5:580.09812900.0981295/9/2019 5:590.08576200.0857625/9/2019 6:000.07552100.0755215/9/2019 6:010.06692100.0669215/9/2019 6:020.05967400.0596745/9/2019 6:030.05375700.0537575/9/2019 6:040.04854100.0485415/9/2019 6:050.04369600.0436965/9/2019 6:060.03914800.0391485/9/2019 6:070.03506100.0350615/9/2019 6:080.03148400.0314845/9/2019 6:100.02573200.0257325/9/2019 6:110.02328200.0232825/9/2019 6:120.01971400.019714	5/9/2019 5:57	0.113257	0	0.113257
5/9/2019 5:590.08576200.0857625/9/2019 6:000.07552100.0755215/9/2019 6:010.06692100.0669215/9/2019 6:020.05967400.0596745/9/2019 6:030.05375700.0537575/9/2019 6:040.04854100.0485415/9/2019 6:050.04369600.0391485/9/2019 6:060.03914800.0350615/9/2019 6:070.03506100.0314845/9/2019 6:080.03148400.0283925/9/2019 6:100.02573200.0257325/9/2019 6:110.02328200.0232825/9/2019 6:120.01971400.019714				
5/9/2019 6:000.07552100.0755215/9/2019 6:010.06692100.0669215/9/2019 6:020.05967400.0596745/9/2019 6:030.05375700.0537575/9/2019 6:040.04854100.0485415/9/2019 6:050.04369600.0436965/9/2019 6:060.03914800.0391485/9/2019 6:070.03506100.0350615/9/2019 6:080.03148400.0314845/9/2019 6:100.02839200.0283925/9/2019 6:110.02328200.0232825/9/2019 6:120.01971400.019714				
5/9/2019 6:010.06692100.0669215/9/2019 6:020.05967400.0596745/9/2019 6:030.05375700.0537575/9/2019 6:040.04854100.0485415/9/2019 6:050.04369600.0436965/9/2019 6:060.03914800.0391485/9/2019 6:070.03506100.0350615/9/2019 6:080.03148400.0314845/9/2019 6:090.02839200.0283925/9/2019 6:100.02573200.0257325/9/2019 6:110.02328200.0232825/9/2019 6:120.01971400.019714				
5/9/2019 6:020.05967400.0596745/9/2019 6:030.05375700.0537575/9/2019 6:040.04854100.0485415/9/2019 6:050.04369600.0436965/9/2019 6:060.03914800.0391485/9/2019 6:070.03506100.0350615/9/2019 6:080.03148400.0314845/9/2019 6:090.02839200.0283925/9/2019 6:100.02573200.0257325/9/2019 6:110.02328200.0232825/9/2019 6:120.01971400.019714				
5/9/2019 6:030.05375700.0537575/9/2019 6:040.04854100.0485415/9/2019 6:050.04369600.0436965/9/2019 6:060.03914800.0391485/9/2019 6:070.03506100.0350615/9/2019 6:080.03148400.0314845/9/2019 6:090.02839200.0283925/9/2019 6:100.02573200.0257325/9/2019 6:110.02328200.0232825/9/2019 6:120.01971400.019714	5/9/2019 6:01	0.066921	0	0.066921
5/9/2019 6:040.04854100.0485415/9/2019 6:050.04369600.0436965/9/2019 6:060.03914800.0391485/9/2019 6:070.03506100.0350615/9/2019 6:080.03148400.0314845/9/2019 6:090.02839200.0283925/9/2019 6:100.02573200.0257325/9/2019 6:110.02328200.0232825/9/2019 6:120.01971400.019714	5/9/2019 6:02	0.059674	0	0.059674
5/9/2019 6:040.04854100.0485415/9/2019 6:050.04369600.0436965/9/2019 6:060.03914800.0391485/9/2019 6:070.03506100.0350615/9/2019 6:080.03148400.0314845/9/2019 6:090.02839200.0283925/9/2019 6:100.02573200.0257325/9/2019 6:110.02328200.0232825/9/2019 6:120.01971400.019714	5/9/2019 6:03	0.053757	0	0.053757
5/9/2019 6:050.04369600.0436965/9/2019 6:060.03914800.0391485/9/2019 6:070.03506100.0350615/9/2019 6:080.03148400.0314845/9/2019 6:090.02839200.0283925/9/2019 6:100.02573200.0257325/9/2019 6:110.02328200.0232825/9/2019 6:120.01971400.019714	• •		0	0.048541
5/9/2019 6:060.03914800.0391485/9/2019 6:070.03506100.0350615/9/2019 6:080.03148400.0314845/9/2019 6:090.02839200.0283925/9/2019 6:100.02573200.0257325/9/2019 6:110.02328200.0232825/9/2019 6:120.01971400.019714				
5/9/2019 6:070.0350610 0.0350615/9/2019 6:080.0314840 0.0314845/9/2019 6:090.0283920 0.0283925/9/2019 6:100.0257320 0.0257325/9/2019 6:110.0232820 0.0232825/9/2019 6:120.0197140 0.019714				
5/9/2019 6:08       0.031484       0 0.031484         5/9/2019 6:09       0.028392       0 0.028392         5/9/2019 6:10       0.025732       0 0.025732         5/9/2019 6:11       0.023282       0 0.023282         5/9/2019 6:12       0.019714       0 0.019714	• •			
5/9/2019 6:090.02839200.0283925/9/2019 6:100.02573200.0257325/9/2019 6:110.02328200.0232825/9/2019 6:120.01971400.019714		0.035061	0	0.035061
5/9/2019 6:10       0.025732       0 0.025732         5/9/2019 6:11       0.023282       0 0.023282         5/9/2019 6:12       0.019714       0 0.019714	5/9/2019 6:08	0.031484	0	0.031484
5/9/2019 6:11       0.023282       0 0.023282         5/9/2019 6:12       0.019714       0 0.019714	5/9/2019 6:09	0.028392	0	0.028392
5/9/2019 6:11       0.023282       0 0.023282         5/9/2019 6:12       0.019714       0 0.019714	5/9/2019 6:10	0.025732	0	0.025732
5/9/2019 6:12 0.019714 0 0.019714				
0 0.01/09/ 0 0.01/09/				
	5/9/2019 6:13	0.01/09/	U	0.01/09/

5/9/2019 6:14	0.015185	0	0.015185
5/9/2019 6:15	0.013764	0	0.013764
5/9/2019 6:16	0.01271	0	0.01271
5/9/2019 6:17	0.01191	0	0.01191
5/9/2019 6:18	0.011284	0	0.011284
5/9/2019 6:19	0.010779	0	0.010779
5/9/2019 6:20	0.01036	0	0.01036
5/9/2019 6:21	0.010005	0	0.010005
5/9/2019 6:22	0.009696	0	0.009696
5/9/2019 6:23	0.009422	0	0.009422
5/9/2019 6:24	0.009174	0	0.009174
5/9/2019 6:25	0.008948	0	0.008948
5/9/2019 6:26	0.008738	0	0.008738
5/9/2019 6:27	0.008542	0	0.008542
	0.008356		0.008356
5/9/2019 6:28		0	
5/9/2019 6:29	0.00818	0	0.00818
5/9/2019 6:30	0.008011	0	0.008011
5/9/2019 6:31	0.007849	0	0.007849
5/9/2019 6:32	0.007693	0	0.007693
5/9/2019 6:33	0.007543	0	0.007543
5/9/2019 6:34			0.007343
	0.007397	0	
5/9/2019 6:35	0.007256	0	0.007256
5/9/2019 6:36	0.007149	0	0.007149
5/9/2019 6:37	0.007085	0	0.007085
5/9/2019 6:38	0.007016	0	0.007016
5/9/2019 6:39	0.006944	0	0.006944
5/9/2019 6:40	0.006868	0	0.006868
5/9/2019 6:41	0.00679		0.00679
		0	
5/9/2019 6:42	0.006711	0	0.006711
5/9/2019 6:43	0.006629	0	0.006629
5/9/2019 6:44	0.006546	0	0.006546
5/9/2019 6:45	0.006462	0	0.006462
5/9/2019 6:46	0.006377	0	0.006377
5/9/2019 6:47	0.006292	0	0.006292
5/9/2019 6:48	0.006205	0	0.006205
5/9/2019 6:49	0.006119	0	0.006119
5/9/2019 6:50	0.006031	0	0.006031
5/9/2019 6:51	0.005944	0	0.005944
5/9/2019 6:52	0.005857	0	0.005857
5/9/2019 6:53	0.00577	0	0.00577
5/9/2019 6:54	0.005683	0	0.005683
5/9/2019 6:55	0.005597	0	0.005597
5/9/2019 6:56	0.00551	0	0.00551
5/9/2019 6:57	0.005425	0	0.005425
5/9/2019 6:58	0.00534	0	0.00534
5/9/2019 6:59	0.005256	0	0.005256
5/9/2019 7:00	0.005172	0	0.005172
5/5/2015 7.00	5.005172	3	3.003172


5/9/2019 7:01	0.00509	0	0.00509
5/9/2019 7:02	0.005008	0	0.005008
5/9/2019 7:03	0.004927	0	0.004927
5/9/2019 7:04	0.004848	0	0.004848
5/9/2019 7:05	0.004769	0	0.004769
5/9/2019 7:06	0.004691	0	0.004691
5/9/2019 7:07	0.004615	0	0.004615
5/9/2019 7:08	0.004539	0	0.004539
5/9/2019 7:09	0.004465	0	0.004465
5/9/2019 7:10	0.004392	0	0.004392
5/9/2019 7:11	0.00432	0	0.00432
5/9/2019 7:12	0.004249	0	0.004249
5/9/2019 7:13	0.00418	0	0.004243
5/9/2019 7:14	0.004111	0	0.004111
5/9/2019 7:15	0.004042	0	0.004042
5/9/2019 7:16	0.003973	0	0.003973
5/9/2019 7:17	0.003905	0	0.003905
5/9/2019 7:18	0.003838	0	0.003838
5/9/2019 7:19	0.003771	0	0.003771
5/9/2019 7:20	0.003706	0	0.003706
5/9/2019 7:21	0.003641	0	0.003641
5/9/2019 7:22	0.003577	0	0.003577
5/9/2019 7:23	0.003514	0	0.003514
5/9/2019 7:24	0.003452	0	0.003452
5/9/2019 7:25	0.003392	0	0.003392
5/9/2019 7:26	0.003333	0	0.003333
5/9/2019 7:27	0.003274	0	0.003274
5/9/2019 7:28	0.003217	0	0.003217
5/9/2019 7:29	0.003162	0	0.003162
5/9/2019 7:30	0.003107	0	0.003107
5/9/2019 7:31	0.003054	0	0.003054
5/9/2019 7:32	0.003002	0	0.003002
5/9/2019 7:33	0.002951	0	0.002951
5/9/2019 7:34	0.002901	0	0.002901
5/9/2019 7:35	0.002852	0	0.002852
5/9/2019 7:36	0.002805	0	0.002805
5/9/2019 7:37	0.002759	0	0.002759
5/9/2019 7:38	0.002714	0	0.002714
5/9/2019 7:39	0.00267	0	0.00267
5/9/2019 7:40	0.002627	0	0.002627
5/9/2019 7:41	0.002585	0	0.002585
5/9/2019 7:42	0.002544	0	0.002544
5/9/2019 7:43	0.002504	0	0.002504
5/9/2019 7:44	0.002465	0	0.002465
5/9/2019 7:45	0.002403	0	0.002403
5/9/2019 7:46	0.00239	0	0.00239
5/9/2019 7:47	0.002354	0	0.002354

## SERVICING REPORT - 6102 RENAUD RD, ORLÉANS

Appendix C **Stormwater** Management August 1, 2019

# C.3 BACKGROUND EXCERPTS (STORM DRAINAGE)





IBI GROUP

CCL/IBI 1770 WOODWARD DRIVE OTTAWA, ONTARIO

K2C OP8

STORM SEWER DESIGN SHEET
PROJECT: SPRING VALLEY LOCATION:

JOB #:

PAGE:

3625-LD

1 OF 2

CITY OF OTTAWA DATE: **JULY 2006** DEVELOPER: CLARIDGE HOMES DESIGN: DY

LOCATION		1120 01				AREA (Ha.)				I		DESIGN F					SEWEF		DEGION.		
STREET	FROM	ТО	C=	C=	C=		C=	INDIV.	ACCUM.	INLET		TOTAL		PEAK FLOW	CAP.	LENGTH	PIPE	I I	n	VEL.	AVAIL.
OTREET	МН	MH	0.25	0.45	0.53	0.6	0.8		2.78AC	(min.)	IN PIPE			(I/s)	(I/s)	(M)	(mm)	(%)		(M/s)	CAP (%)
Street 1	Stub	116				1.40		2.34	2.34	15.00	0.29	15.29	83.60	195.62	` '	25.0	525	0.5	0.013	<u> </u>	38.35%
Joshua Avenue	116	108		0.39				0.49	2.83	15.00	0.59	15.59	83.60	236.59	274.17	58.8	450	0.85	0.013	1.67	13.71%
Joshua Avenue	108	104						0.00	2.83	15.59	0.05	15.63	81.70	231.21	473.15	7.9	450	2.53	0.013	2.882	51.13%
Joshua Avenue	104B	104		0.16				0.20	0.20	10.00	0.36	10.36	104.20	20.84	87.71	37.0	250	) 2	0.013	1.731	76.24%
Felicity Crescent	104	103						0.00	3.03	15.63	0.20	15.83	81.60	247.25	515.18		450		0.013	3.138	52.01%
Felicity Crescent	103	102	0.430	0.45				0.86	3.89	15.83			81.00	315.09			525		0.013	2.289	
Felicity Crescent	102	101		0.88				1.10	4.99	16.42	0.53	16.95	79.20	395,21	527.14	75.5	525	1.38	0.013	2,359	25.03%
Rolling Meadow Crescent	155	154	1			0.09		0.15	0.15	15.00	0.46	15.46	83.60	12.54	103.82	56.9	250	2.8	0.013	2.049	87.92%
Rolling Meadow Crescent	154	153				0.20		0.33	0.48	15.46	0.20	15.66	82.10	39.41	131.59	31.2	250		0.013	2.597	70.05%
Rolling Meadow Crescent	153	152				0.55		0.92	1.40	15.66	0.51	16.17	81.50	114.10	131.59	79.6	250	4.5	0.013	2.597	13.29%
Rolling Meadow Crescent	152	151				0.00		0.00	1.40	16.17	0.18	16.35	79.90	111.86	214.01	31.3	300	4.5	0.013	2.933	47.73%
Rolling Meadow Crescent	151	150B				0.18		0.30	1.70	16.35	0.30	16.66	79.40	134.98	156.95	39.2	300	2.42	0.013	2.151	14.00%
Rolling Meadow Crescent	150B	300				0.08	0.87	2.07	3.77	16.66	0.21	<mark>16.86</mark>	78.60	296.32	350.82	14.9	600	0.3	0.013	1.202	
Rolling Meadow Crescent	300	145	<b>_</b>					0.00	3.77	16.86	1.46	18.32	78.00	294.06	350.82	104.9	600	0.3	0.013	1.202	<mark>16.18%</mark>
Saddleridge Drive	156	145					0.54	1.20	1.20	10.00	0.68	10.68	104.20	125.04	142.65	80.0	300	2	0.013	1.955	12.34%
Gossamer	200	201		0.15				0.19	0.19	15.00	0.74	15.74	83.60	15.88	43.88	38.5	250	0.5	0.013	0.866	63.80%
Gossamer	201	202		0.62				0.78	0.97	15.74			81.20	78.76			375		0.013	1 134	
Prairie	202	145		0.31				0.39	1.36				79.50	108.12			375		0.013	1.134	
Saddleridge Drive	145	134		0.26	0.310	)		0.78	7,11	18.32	0.42	18.74	74.20	527.56	784.53	68.2	600	1.5	0,013	2.688	32.75%
Saddleridge Drive	134			0.20	0.010			0.00	7.11	18.74		19.15	73.10	519.74	784.53		600		0.013		33.75%
External		1420	4.200					2.92	2.92	20.00	0.11	20.11	70.30	205.20	205 22	12.0	375	1 26	0.013	1 001	0.03%
Rolling Meadow Crescent	143B	143B 142	4.200	<u>'</u>		0.12		0.20	3.12	20.00 20.11	0.11 0.05	20.11	70.30	205.28 218.40	205.33 306.11		375		0.013 0.013	1.801 2.685	
Rolling Meadow Crescent	1436	141				0.12		0.20	3.79	20.17			69.90	264.92			375		0.013	2.685	
Rolling Meadow Crescent	141	140	1			0.40		0.00	3.79	20.69		20.03	68.80	260.75			375		0.013	2.685	
Rolling Meadow Crescent	140	139				0.82		1.37	5.16	20.93		21.39	68.30	352.43			450		0.013	3.532	
Rolling Meadow Crescent	139	138				0.38		0.63		21.39			67.30	389.67			525		0.013	2,008	
Rolling Meadow Crescent	138	137				0.40		0.67	6.46	21.68		22.35	66.80	431.53			600		0.013	2.195	

Q = Peak Flow in Litres per Second (I/s)
A = Area in Hectares (ha.)
I = Rainfall Intensity in Millimeters per Hour (mm/hr)
C = Runoff Coeff<u>icient</u>

REV.#:

July 22, 2008

### SERVICING REPORT - 6102 RENAUD RD, ORLÉANS

Appendix D **Geotechnical** Investigation August 1, 2019

# Appendix D GEOTECHNICAL INVESTIGATION





## • 2597237 Ontario Ltd.

## **Geotechnical Investigation**

Type of Document **Draft** 

Project Name
Proposed Residential Development
6102 Renaud Road
Ottawa, Ontario

Project Number OTT-00246046-A0

Prepared By: Susan M. Potyondy, P.Eng.

Reviewed By: Ismail M. Taki, M.Eng., P.Eng.

EXP Services Inc. 100-2650 Queensview Drive Ottawa, ON K2B 8H6 Canada

Date Submitted May 18, 2018

## **2597237 Ontario Ltd.**

## **Geotechnical Investigation**

Type of Document: **Draft** 

**Project Name:** 

Proposed Residential Development 6102 Renaud Road Ottawa, Ontario

Project Number: OTT-00246046-A0

Prepared By:

EXP 100-2650 Queensview Drive Ottawa, ON K2B 8H6 Canada T: 613 688-1899

F: 613 225-7337 www.exp.com

Susan M. Potyondy, P.Eng.
Senior Project Manager, Geotechnical Services
Earth and Environment

Ismail M. Taki, M.Eng., P.Eng. Manager, Geotechnical Services Earth and Environment

Date Submitted: May 18, 2018

# **Legal Notification**

This report was prepared by EXP Services Inc. for the account of 2597237 Ontario Ltd.

Any use which a third party makes of this report, or any reliance on or decisions to be made based on it, are the responsibility of such third parties. EXP Services Inc. accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions based on this project.



## **Executive Summary**

EXP Services Inc. (EXP) is pleased to present the results of the geotechnical investigation recently completed for the proposed new residential development to be located at 6102 Renaud Road in the City of Ottawa, ON. The site location is shown on Figure 1. This work was authorized by Mr. Sael Nemorin of 2597237 Ontario Ltd.

The subject site is approximately 0.6 hectare (1.4 acres) in size and is currently occupied by buildings that will be demolished as part of the proposed development. It is our understanding that the proposed preliminary development plans consist of four-storey apartment buildings with one underground parking level.

The fieldwork for the geotechnical investigation was undertaken from April 16 to 18, 2018 and consisted of five (5) boreholes (Borehole Nos. 1 to 5) at the locations shown on the Borehole Location Plan, Figure 2. The boreholes were advanced to termination depths from 8.1 m to 11.6 m and dynamic cone refusal depths of 26.1 m and 27.0 m below existing grade. The fieldwork was supervised on a full-time basis by a representative from EXP.

The geotechnical investigation revealed the subsurface soil conditions at the site to comprise of a surficial topsoil layer and pavement structure underlain by fill, silty sand and an extensive compressible marine clay deposit. Groundwater level measurements ranged from 0.4 m to 1.4 m depths (Elevation 76.4 m to 75.4 m).

The subsurface soils are not considered to be liquefiable.

The site is classified as **Class D** for seismic site response in accordance with Table 4.1.8.4.A of the 2012 Ontario Building Code.

The site is underlain by a compressible marine clay prone to consolidation settlement if overstressed by loads imposed on it by site grade raise, foundations and groundwater lowering resulting in settlement of foundations. Based on a review of the engineering properties of the clay, it is considered that the maximum site grade raise may be up to 1.0 m when combined with a one to two storey building with or without a basement, supported by footings founded at a 1.0 m depth below existing grade and designed for a bearing pressure at serviceability limit state (SLS) of 96 kPa and factored geotechnical resistance at ultimate limit state (ULS) of 120 kPa. Settlements of the footings designed for the SLS value above and properly constructed are expected to be within the normally tolerated limits of 25 mm total and 19 mm differential movements.

For the proposed four-storey apartment building with one level underground parking and for other types of residential building configurations requiring higher bearing pressure values than indicated above in combination with a maximum 1.0 m grade raise, the buildings may be supported by footings, raft or pile foundations in combination with soil fill and light weight fill.

Since the bearing values of foundations supported by the marine clay depend on the magnitude of the site grade raise, it is recommended that once the grade raise of the site is known and the grading plan is available, EXP be contacted to provide more detailed foundation recommendations.



For the pile foundation option, an additional geotechnical investigation will be required to determine the depth to bedrock.

The lowest floor slabs of the one- to two-storey buildings with or without basement may be designed on slabs on grade. Perimeter drains for buildings without a basement will not be required provided the floor slab is set at least 150 mm above the final grade. Perimeter drains will be required for buildings with a basement. The need for underfloor drains will have to be assessed during detailed design.

Subsurface basement walls should be designed to resist static lateral earth pressure and dynamic lateral earth pressure during a seismic event.

The excavations at the site may be undertaken as open cut provided they meet the requirements of the Ontario Occupational Health and Safety Act (OHSA). Seepage of water is expected in the excavations and maybe handled by conventional sump-pump techniques. High capacity pumps may be required in zones of persistent seepage.

Based on the geotechnical investigation, the majority of material required for backfilling against subsurface walls, footings and service trenches would have to be imported and should conform to the OPSS requirements of Granular B Type II and Select Subgrade Material (SSM). On-site soils may be used as backfill in landscaped areas.

The pavement structure for light duty traffic areas may consist of 65 mm of asphaltic concrete underlain by 150 mm of OPSS 1010 Granular A base and 450 mm of OPSS 1010 Granular B Type II sub-base. The pavement structure for heavy duty traffic areas may consist of 90 mm of asphaltic concrete underlain by 150 mm of OPSS 1010 Granular A base and 600 mm of OPSS 1010 Granular B Type II sub-base.

Normal Portland cement may be used in the sub-surface concrete at this site. The subsurface soils are considered to be moderately to mildly corrosive to buried steel members/structures. Appropriate measures should be undertaken to protect buried steel elements from corrosion.

Tree planting restrictions and setbacks will require consultation with a landscape architect and should be in accordance with City of Ottawa guidelines and policy.

The above and other related considerations are discussed in greater detail in the main body of this report.



# **Table of Contents**

				Page
Exe	cutive	Summa	ry	i
1	Intro	duction.		1
2	Phas	e II ESA	Information	3
3	Site I	Descript	ion	4
4	Proc	edure		5
5	Subs	urface S	Soil and Groundwater Conditions	6
	5.1	Topsoil		6
	5.2	Pavem	ent Structure	6
	5.3	Fill		6
	5.4	Silty Sa	and	6
	5.5	Clay		7
		5.5.1	Brown Clay (Desiccated Crust)	7
		5.5.2	Grey Clay	8
	5.6	Inferred	d Boulders and Bedrock	9
	5.7	Ground	lwater	9
6	Lique	faction	Potential and Seismic Site Classification	11
	6.1	Liquefa	ction Potential	11
	6.2	Seismi	c Site Classification	11
7	Grad	e Raise	Restrictions	12
8	Site (	Grading	Operations	13
9	Foun	dation C	Considerations	14
	9.1	Footing	JS	14
	9.2	Genera	al Comment	15
10	Floor	Slab an	nd Drainage Requirements	16
11	Subs	urface V	Valls	17
12	Pipe	Bedding	Requirements	18
13	Exca	vations	and De-Watering Requirements	19
	13.1	Excava	tions	19
	13.2	De-Wa	tering Requirements	19
14	Back	filling R	equirements and Suitability of On-Site Soils for Backfilling Purposes	21
15	Pave	ment St	ructures	22
16	Corre	sion Po	otential of Subsurface Soils	24
17	Tree	Planting	Restrictions	25
12	Λddi	ional Co	ommont	26



19 General Comments	27
List of Tables	
	Page
Table I: Summary of Results from Grain Size Analysis – Silty Sand Sample	7
Table II: Summary of Results from Grain Size Analysis – Brown Clay Sample	7
Table III: Summary of Atterberg Limit Results – Brown Clay Sample	8
Table IV: Summary of Atterberg Limit Results – Grey Clay Samples	8
Table V: One-Dimensional Oedometer (Consolidation) Test Results on Grey Clay Samples	ş9
Table VI: Summary of Groundwater Levels in Boreholes	9
Table VII: Recommended Pavement Structure Thicknesses	22
Table VIII: Results of pH, Sulphate, Chloride and Resistivity Tests on Soil Samples	24

# **List of Figures**

Figure 1: Site Location Plan

Figure 2: Borehole Location Plan Figures 3 to 7: Borehole Logs

Figures 8 and 9: Grain Size Distribution Curves

Figure 10 and 11: One-Dimensional Consolidation (Oedometer) Test Results Figure 12: Criteria Chart for Liquefaction Assessment of Fine Grained Soils

# **List of Appendices**

Appendix A: 2015 National Building Code Seismic Hazard Calculation

**Appendix B: AGAT Certificate of Analysis** 



Project Number: OTT-00246046-A0
May 18, 2018

## 1 Introduction

EXP Services Inc. (EXP) is pleased to present the results of the geotechnical investigation recently completed for the proposed new residential development to be located at 6102 Renaud Road in the City of Ottawa, Ontario. The site location is shown on Figure 1. This work was authorized by Mr. Sael Nemorin of 2597237 Ontario Ltd. on April 4, 2018.

The subject site is approximately 0.6 hectare (1.4 acres) in size and is currently occupied by buildings that will be demolished as part of the proposed development. It is our understanding that the proposed preliminary development plans consist of four-storey apartment buildings with one underground parking level.

EXP completed a Phase I Environmental Site Assessment (ESA) of the site and the results are presented in our report dated September 18, 2017. EXP completed a Phase II ESA of the site and the results are presented in our report dated October 30, 2017.

The geotechnical investigation was undertaken to:

- a) Establish the subsurface soil and groundwater conditions at the five (5) boreholes located on site and a review of the subsurface soil and groundwater conditions of boreholes from the Phase II ESA:
- Assess the potential for liquefaction of the subsurface soils during a seismic event and classify the site for seismic site response in accordance with the requirements of the 2012 Ontario Building Code (OBC);
- c) Comment on grade-raise restrictions;
- d) Make recommendations regarding the most suitable type of foundations, founding depth and bearing pressure at serviceability limit state (SLS) and factored geotechnical resistance at ultimate limit state (ULS) of the founding strata and comment on the anticipated total and differential settlements of the recommended foundation type;
- e) Discuss slab-on-grade construction and permanent drainage system requirements;
- f) Provide lateral earth pressure parameters for subsurface basement wall design;
- g) Comment on excavation conditions and de-watering requirements during construction;
- h) Provide comments regarding pipe bedding requirements;
- i) Discuss backfilling requirements and suitability of on-site soils for backfilling purposes;
- j) Comment on subsurface concrete requirements for buried concrete structures/members and corrosion potential of subsurface soils to buried metal structures/members;
- k) Recommend pavement structures for the parking lots and access roads; and
- I) Provide recommendations for the planting of trees.

The comments and recommendations given in this report assume that the above-described design concept will proceed into construction. If changes are made either in the design phase or during construction, this office must be retained to review these modifications. The result of this review may be a modification of



our recommendations or it may require additional field or laboratory work to check whether the changes are acceptable from a geotechnical viewpoint.



## 2 Phase II ESA Information

A Phase II Environmental Site Assessment (ESA) of the site was undertaken by EXP and the results are presented in the report titled, "Phase II Environmental Site Assessment, 6102 Renaud Road, Ottawa, Ontario" dated October 30, 2017 (EXP Project No. OTT-00246046-A0).

The Phase II ESA consisted of four (4) boreholes located inside and outside the existing buildings on site. The borehole information indicates that below interior concrete slabs, the subsurface soil conditions consist of fill to a 1.8 m depth underlain by native silty clay. The boreholes terminated within the silty clay at 3.7 m to 4.8 m depths. The groundwater levels measured in the monitoring wells installed in the four (4) boreholes ranges from 1.5 m to 1.7 m depths (Elevation 76.9 m to 75.5 m).



# 3 Site Description

The site is located on the south side of Renaud Road and east of Saddleridge Drive in Ottawa, Ontario. The site is approximately 0.6 hectare (1.4 acres) in size and is occupied by a residential building in the north part and a commercial building in the south part of the site. The surrounding properties consist of residential development. The site location is shown in Figure 1.

Based on the approximate ground surface elevations of the boreholes ranging from Elevation 79.1 m near the front of the property along Renaud Road to Elevation 76.7 m at the rear of the property, the topography of the site is relatively flat.



## 4 Procedure

The fieldwork for the geotechnical investigation was undertaken from April 16 to 18, 2018 and consisted of five boreholes (Borehole Nos. 1 to 5) at the locations shown on the Borehole Location Plan, Figure 2. The boreholes were advanced to termination depths from 8.1 m to 11.6 m and dynamic cone refusal depths of 26.1 m and 27.0 m below existing grade. The fieldwork was supervised on a full-time basis by a representative from EXP.

The borehole locations and geodetic elevations were estimated from the spot elevations provided on the survey plan titled, "Part of Lot 6, Concession 4 (Ottawa Front) Geographic Township of Gloucester, City of Ottawa", dated September 22, 2017 and prepared by Annis, O'Sullivan, Vollebekk Ltd. (AOV). Therefore, the ground surface elevations indicated on the borehole logs should be considered approximate. The borehole locations were cleared of private and public underground services, prior to the start of drilling operations.

The boreholes were drilled with a CME-55 truck-mounted drill rig equipped with continuous flight hollow-stem auger equipment. Standard penetration tests (ASTM 1586) were performed in all the boreholes at 0.75 m to 3.0 m depth intervals and soil samples retrieved by the split-barrel sampler. Relatively undisturbed thin-walled tube samples (Shelby tube samples) were retrieved at selected depth intervals within the clay. The undrained shear strength of the clay was measured by conducting penetrometer and in-situ vane tests at selected depth intervals. Borehole Nos. 1 and 4 were advanced unsampled from 10.1 m to cone refusal depth of 27.0 m in Borehole No. 1 and from 19.2 m to cone refusal depth of 26.1 m in Borehole No. 4.

Groundwater levels were measured in the open boreholes upon completion of drilling. In addition, 19 mm diameter slotted standpipe piezometers were installed in three boreholes for long-term monitoring of the groundwater levels. The standpipe piezometers were installed in accordance with EXP standard practice and their installation configuration is documented on the respective borehole log.

On completion of the fieldwork, all the soil samples were transported to the EXP laboratory located in the City of Ottawa. All the borehole samples were visually examined in the laboratory by a senior geotechnical engineer for textural classification. The engineer also assigned the laboratory testing, which consisted of performing the following tests in accordance with the American Society for Testing and Materials (ASTM).

Natural Moisture Content	48 tests
Natural Unit Weight	10 tests
Grain-Size Analyses	2 tests
Atterberg Limits	4 tests
pH, Sulphate Chlorides and Resistivity Analyses	2 tests
Consolidation Tests	2 tests



## 5 Subsurface Soil and Groundwater Conditions

A detailed description of the subsurface soil and groundwater conditions determined from the boreholes are given on the attached borehole logs, Figure Nos. 3 to 7.

The borehole logs and related information depict subsurface conditions only at the specific locations and times indicated. Subsurface conditions and water levels at other locations may differ from conditions at the locations where sampling was conducted. The passage of time also may result in changes in the conditions interpreted to exist at the locations where sampling was conducted. Boreholes were drilled to provide representation of subsurface conditions as part of a geotechnical exploration program and are not intended to provide evidence of potential environmental conditions.

It should be noted that the soil boundaries indicated on the borehole logs are inferred from non-continuous sampling and observations during drilling. These boundaries are intended to reflect approximate transition zones for the purpose of geotechnical design and should not be interpreted as exact planes of geological change. The "Notes on Sample Descriptions" preceding the borehole logs form an integral part of this report and should be read in conjunction with this report.

A review of the borehole logs indicates the following soil stratigraphy with depth and groundwater level measurements.

#### 5.1 Topsoil

A 50 mm thick surficial topsoil layer was contacted in Borehole Nos. 3 and 4.

#### 5.2 Pavement Structure

Borehole No. 1 is located within the existing paved driveway. The pavement structure consists of 50 mm thick asphaltic concrete underlain by 150 mm thick crushed limestone gravel layer.

#### 5.3 Fill

Fill was surficially encountered in Borehole Nos. 2 and 5 and below the topsoil in Borehole Nos. 3 and 4. The fill extends to depths of 0.7 m and 0.9 m (Elevation 76.8 m to 76.0 m). The fill consists of a mixture of gravel, silty sand with topsoil, roots, rootlets and wood debris (Borehole No. 5). Based on the N-values of 4 to 21 from the Standard Penetration Test (SPT), the fill is in a loose to compact state. The natural moisture content of the fill is 15 percent to 27 percent.

#### 5.4 Silty Sand

The fill in Borehole No. 1 is underlain by silty sand to a 2.2 m depth (Elevation 76.9 m). Based on N-values of 8 and 13 from the SPT, the silty sand is in a loose to compact state. The natural moisture content of the silty sand ranges from 18 percent to 27 percent.



The results of the grain-size analysis of one sample of the silty sand is summarized in Table I. The grain-size distribution curve is shown in Figure 8.

Table I: Summary of Results from Grain-size Analysis – Silty Sand Sample								
	Donth (Flourition)	G	Frain Size A	Analysis (%)				
Borehole - Sample No.	Depth (Elevation) (m)	Gravel	Sand	Fines				
	()	Glavei	Saliu	(Silt and Clay)				
BH 1 - SS3	1.5 – 2.1 (77.6 – 77.0)	0	80	20				

Based on a review of the results from the grain-size analysis, the soil may be described as a silty sand (SM) in accordance with the Unified Soil Classification System (USCS).

#### **5.5** Clay

Sensitive marine clay was contacted beneath the fill and silty sand at 0.7 m to 0.9 m depths (Elevation 76.8 m to 76.0 m) in the five (5) boreholes. The clay consists of an upper desiccated brown crust underlain by grey clay.

#### 5.5.1 Brown Clay (Desiccated Crust)

The brown clay crust was contacted in Borehole Nos. 2 to 5 and was not present in Borehole No. 1. The upper crust extends to depths ranging from 2.1 to 3.0 m depths (Elevation 75.3 m to 74.2 m). The clay crust is approximately 1.4 m to 2.1 m thick. The undrained shear strength of the crust is 82 kPa to 192 kPa indicating a stiff to very stiff consistency. The sensitivity values of the clay are 4.9 and 7.2, indicating the sensitivity of the clay may be described as sensitive. The natural moisture content and unit weight of the crust are 23 percent to 60 percent and 16.9 kN/m³ to 19.0 kN/m³ respectively. Grain-size analysis and Atterberg limit determination of two (2) samples of the brown clay crust are summarized in Tables II and III. The grain-size distribution curve is shown in Figure 9.

Table II: Summary of Results from Grain-size Analysis – Brown Clay Sample									
		Grain :	Size Analy	/sis (%)					
Borehole No Sample No.	Depth (Elevation) (m)	Gravel	Sand	Fines (Silt and Clay)					
BH2 – SS2	0.8 – 1.4 (76.7 – 76.1)	0	2	98					



Table III: Summary of Atterberg Limit Results – Brown Clay Sample										
Borehole No Sample No.	Depth (Elevation) (m)	Atterberg Limit Results (%)								
Borenoie No Sample No.	Deptil (Lievation) (iii)	Wn	LL	PL	PI					
BH4 – SS2	0.8 – 1.4 (75.9 – 75.3)	45	72	29	43					
<b>W</b> <sub>n</sub> : Natural Moisture Content; <b>LL</b> : Liquid  (1): Refer to Casagrande Plasticity Chart (		ty Index								

Based on a review of the results from the grain-size analysis and the Atterberg limits, the soil may be classified as a high plastic clay (CH), in accordance with the Unified Soil Classification System (USCS).

#### 5.5.2 Grey Clay

The silty sand in Borehole No. 1 and the brown clay crust in Borehole Nos. 2 to 5 are underlain by the grey clay contacted at 2.1 m to 3.0 m depths (Elevation 76.9 m to 74.2 m). The undrained shear strength of the clay ranges from 29 to 86 kPa with one measurement of 115 kPa at 14.6 m (Elevation 62.1 m) in Borehole No. 4. The grey clay has a weaker zone in the upper 1.0 m in Borehole Nos. 2 and 3, as indicated by the lowest measured undrained shear strength values of 29 kPa and 34 kPa. Based on the undrained shear strength measurements the clay has a firm to stiff consistency with a very stiff zone at 14.6 m depth (Elevation 62.1 m) in Borehole No. 4. The sensitivity values of 4.6 to 18 indicate the clay has a sensitivity that may be described a sensitive to quick. The silty clay has a moisture content of 35 percent to 88 percent and a natural unit weight measured from one sample of 17.9 kN/m³.

Atterberg limit values of the clay are summarized in Table IV.

Table IV: Summary of Atterberg Limit Results – Grey Clay Samples										
Borehole No Sample No. Depth (Elevation) (m)  Atterberg Limit Res										
Borenoie No Sample No.	Deptii (Lievation) (iii)	Wn	LL	PL	PI					
BH3 - SS6	3.8 – 4.4 (73.6 – 72.4)	82	59	27	32					
BH4 – SS8	6.1 – 6.7 (70.6 – 70.0)	78	59	25	34					
BH4 – SS11	10.7 – 11.3 (66.0 – 65.4)	76	60	30	30					
W <sub>n</sub> : Natural Moisture Content; LL  (1): Refer to Casagrande Plasticity	: Liquid Limit; <b>PL:</b> Plastic Limit; <b>PI</b> : Plastic Chart (1932).	city Index								

Based on a review of the results from the grain-size analysis and the Atterberg limits, the soil may be classified as a high plastic clay (CH), in accordance with the USCS.

One-dimensional oedometer (consolidation) test was conducted on two (2) thin walled tube samples of the grey clay and the results are summarized in Table V. The stress versus void ratio curves are shown in Figures 10 and 11.



Table V: One-Dimensional Oedometer (Consolidation) Test Results on Grey Clay Samples										
Borehole - Sample No.	Depth (Elevation) (m)	σ' <sub>ν0</sub> (kPa)	w <sub>c</sub> (%)	γ (kN/m³)	σ' <sub>p</sub> (kPa)	eo	Cr	Cc	OCR	ОС
BH 1- ST8	6.1-6.7 (73.0 – 72.4)	68	84	14.9	150	2.322	0.037	2.80	2.2	82
BH 5- ST6	3.8-4.4 (73.4 – 72.8)	47	81	15.1	110	2.229	0.034	2.66	2.3	63

 $\sigma'_{v0}$  = estimated effective overburden pressure (kPa);  $w_c$ : natural moisture content (%),  $\gamma$ : estimated natural unit weight (kN/m³)  $\sigma'_p$  = pre-consolidation pressure (kPa),  $e_o$  = initial void ratio;  $e_o$  = re-compression index;  $e_o$  = compression index; OCR = Over consolidation ratio; OC= over-consolidation pressure (kPa);

Based on a review of the consolidation test results, the over consolidation ratio is 2.2 and 2.3 indicating the clay is over consolidated.

#### 5.6 Inferred Boulders and Bedrock

Boulders within glacial till and bedrock are inferred at cone refusal depths of 26.1 m and 27.0 m (Elevation 52.1 m and 50.6 m) in Borehole Nos. 1 and 4. Review of published geology maps indicate the bedrock is limestone of the Ottawa Formation.

#### 5.7 Groundwater

The groundwater level measurements taken several days following the completion of drilling in the standpipe piezometers installed in selected boreholes are summarized in Table VI.

Table VI: Summary of Groundwater Levels in Boreholes							
Borehole No.	Ground Surface Elevation (m)	Drill Date	Date of Groundwater Level Measurement (Number of Days After Drilling)	Depth of Groundwater Level Below Ground Surface (m)	Elevation of Groundwater Level (m)		
3	76.81	April 17, 2018	May 7, 2018 (20 days)	0.4	76.4		
4	76.67	April 17, 2018	May 7, 2018 (20 days)	1.3	75.4		
5	77.18	April 18, 2018	May 7, 2018 (19 days)	1.4	75.8		

A review of Table VI indicates that the groundwater level ranges from 0.4 m to 1.4 m depth (Elevation 76.4 m to 75.4 m).

Water levels were determined in the boreholes at the times and under the conditions stated in the scope of services. Note that fluctuations in the level of groundwater may occur due to a seasonal variation such as



<sup>(1)-</sup> estimated  $\sigma'_{v0}$  based on May 7, 2018 groundwater level measurements.

precipitation, snowmelt, rainfall activities, and other factors not evident at the time of measurement and therefore may be at a higher level during wet weather periods.



Project Number: OTT-00246046-A0

May 18, 2018

# 6 Liquefaction Potential and Seismic Site Classification

#### 6.1 Liquefaction Potential

Based on the findings from this geotechnical investigation, it is recommended the proposed buildings be supported by footings founded on the compact zone of the silty sand and on the stiff to very stiff clay.

The compact zone of the silty sand is not considered liquefiable.

As indicated in Section 5.5 of this report, the liquid limit of the brown and grey silty clay from four (4) tested samples ranges from 59 percent to 72 percent and the plasticity index from 30 to 43 percent. Based on the results of the Atterberg limits and natural moisture contents, the brown and grey clay are not susceptible to liquefaction during a seismic event as per Bray et. al. (2004) criteria for fine-grained soils shown in Figure 12.

#### 6.2 Seismic Site Classification

The subsoil information at this site has been examined in relation to Section 4.1.8.4 of the 2012 Ontario Building Code (OBC). The average shear-wave velocity value of the clay, inferred glacial till and bedrock to a 30-m depth was estimated.

The shear-wave velocity value of the clay deposit was correlated to the undrained shear strength values (Su) using the Dickenson, S.E.  $(1994)^1$  formula:

$$Vs(m/s) = 23.Su^{0.475}$$

The shear-wave velocity value of the inferred glacial till was correlated to the standard penetration test values using Imai and Tonouchi2 (1982) formula:

$$Vs(m/s) = 91.7 N^{0.26}$$

The shear-wave velocity of the inferred bedrock was assumed as 360 m/s.

The average shear-wave velocity to 30 m depth was estimated at 221 m/s. On this basis, the site may be classified as Class D for seismic site response in accordance with Table 4.1.8.4 A of the 2012 OBC.

<sup>&</sup>lt;sup>1</sup> Dickenson, S.E. (1994), "Dynamic Response of Soft and Deep Cohesive Soils during the Loma Prieta Earthquake".

<sup>2</sup> Imai, T, and K Tonouchi (1982). Correlation of N value with S-wave velocity and shear modulus, Proc., 2<sup>nd</sup> European Symp. on Penetration Testing, Amsterdam, pp. 67–72.

## 7 Grade Raise Restrictions

The site is underlain by a sensitive marine clay deposit consisting of a brown clay crust of limited thickness underlain by a grey clay which weakens with depth to a minimum value and thereafter increases with depth. The marine clay deposit is prone to consolidation settlement if overstressed by loads imposed on it by site grade raise, foundations, and by groundwater level lowering following construction. Overstressing of the clay stratum may result in its consolidation and subsequent settlement of foundations, which may exceed the tolerable limits of the structure resulting in cracking of the structure.

Based on a review of the engineering properties of the clay, it is considered that the site grade raise may be 1.0 m in conjunction with the footings designed as per Section 9 of this report. An allowance for groundwater lowering was not required as part of the review, since the proposed footings will be at or above the measured groundwater level in the clay and measures are employed in new service trenches to minimize the permanent lowering of the groundwater level at the site (use of clay seals), as recommended in Sections 12 and 14.



# 8 Site Grading Operations

As part of the site preparation, the site grading within the footprint of the proposed building and paved areas should consist of the excavation and removal of all topsoil, paved surfaces, fill and any organic stained soils from the site. Any soft/loose areas identified in the interior of the building footprint should be excavated and replaced with Ontario Provincial Standard Specification (OPSS 1010 as amended by SSP110S13) Granular B Type II compacted to 98 percent standard Proctor maximum dry density (SPMDD).

It may be possible to leave some of the existing fill and silty sand in-place in the parking lot/access road areas, pending further evaluation in the field during construction and acceptability from an environmental perspective. For budgeting purposes, the contractor should assume that all the existing fill material will be required to be removed and replaced with imported granular material from the area of the proposed building and parking lot/access road areas.

Following approval of the exposed subgrade, the grades beneath the floor slabs may be raised to the underside of the 300 mm thick clear stone layer by the placement of engineered fill consisting of OPSS 1010 Granular B Type II placed in 300 mm thick lifts and each lift compacted to 98 percent of the SPMDD.

For the proposed parking and access road areas, the site grades may be raised to the design subgrade level by the placement of OPSS 1010 select subgrade material (SSM) compacted to 95 percent of the SPMDD.

In-place density tests should be performed on each lift of placed material to ensure that it has been compacted to the project specifications.



## 9 Foundation Considerations

The investigation has revealed that for the maximum permissible grade raise of 1.0 m, the geotechnical conditions at the site are suitable for the construction of residential one- to two-storey wood-frame type structures with or without a basement supported by conventional strip and spread footings designed for the limit state bearing pressure values indicated below.

For the proposed four-storey apartment building with one level underground parking and other types of residential building configurations requiring higher bearing pressure values than indicated below in combination with a maximum 1.0 m grade raise, the buildings may be supported by footings, raft or pile foundations in combination with soil fill and light weight fill.

Since the bearing values of foundations supported by the marine clay depend on the magnitude of the site grade raise, it is recommended that once the grade raise of the site is known and the grading plan is available, EXP be contacted to provide more detailed foundation recommendations.

For the pile foundation option, an additional geotechnical investigation will be required to determine the depth to bedrock.

#### 9.1 Footings

The one- to two-storey wood-frame type buildings with a basement and 1.0 m grade raise may be supported by maximum 1.0 m wide strip and 3 m by 3 m square pad footings founded on the compact zone of the silty sand and stiff to very stiff clay at a maximum depth of 1.0 m below existing grade and designed for a bearing pressure at serviceability limit state (SLS) of 96 kPa and a factored geotechnical resistance at ultimate limit state (ULS) of 120 kPa. The factored ULS value includes a resistance factor of 0.5 in accordance with the 2006 Canadian Foundation Engineering Manual (CFEM). The above SLS value is considered valid, provided the site grade raise of 1.0 m is respected.

Settlements of the footings designed for the SLS value above and properly constructed are expected to be within the normally tolerated limits of 25 mm total and 19 mm differential movements.

In areas where the founding soil is the silty sand (Borehole No. 1), the footing excavation will need to extend to the compact zone of the silty sand contacted at approximately 1.8 m depth (Elevation 77.3 m). The sub-excavated area may be backfilled with lean concrete or engineered fill compacted to 100 percent SPMDD.

The footings should be kept at the maximum 1.0 m depth below existing grade, to minimize overstressing the weaker zone of the underlying grey clay and excavations below the measured groundwater level.

All the footing beds should be examined by a geotechnical engineer to ensure that the founding surfaces are capable of supporting the design bearing pressure at SLS and that the footing beds have been properly prepared.

A minimum of 1.5 m of earth cover should be provided to the exterior foundations of heated structures to protect them from damage due to frost penetration. The frost cover should be increased to 2.1 m for unheated structures if snow will not be removed from their vicinity and to 2.4 m if snow will be removed



from the vicinity of the structure. When earth cover is less than the minimum required, an equivalent combination of earth cover and rigid insulation (such as Styrofoam HI-40) or rigid insulation alone should be provided. EXP can provide additional comments in this regard, if required.

The footings should be reinforced, and nominal reinforcing steel should be provided in the basement walls to minimize cracking. For guidance, the reinforcement in the basement walls may consist of a minimum of two upper and two lower 15M-size reinforcing bar sizes. The required reinforcing detail for the footings and basement walls will need to be determined by the structural engineer.

It should be noted that the surface of the clay is susceptible to disturbance due to movement of workers and construction equipment especially if the excavations are undertaken during wet weather periods. It is therefore considered that depending on the weather conditions prevailing at the time of construction, footing beds may have to be covered with a mud slab to prevent disturbance to the clay subgrade.

The depth to the native silty sand and clay may vary from that indicated on the borehole logs due to presence of the existing buildings on site. For example, the fill thickness and depth to native silty sand and clay may be deeper than shown on the borehole logs at locations close to and/or within the footprint of existing buildings and underground service trenches. The boreholes from the Phase II ESA indicate the fill extends to 1.8 m depth below existing grade. Therefore, it is recommended that once the existing buildings have been demolished and foundations, foundation walls and floor slabs have been removed, additional boreholes be undertaken within the footprints of the existing buildings to determine the subsurface conditions, suitable founding soil conditions and depths for footings, the groundwater level, bearing pressure at SLS and factored geotechnical resistance at ULS, excavation and dewatering requirements.

#### 9.2 General Comment

The recommended bearing pressure at SLS and factored geotechnical resistances at ULS have been calculated by EXP from the borehole information for the design stage only. The investigation and comments are necessarily on-going as new information of underground conditions becomes available. For example, more specific information is available with respect to conditions between boreholes when foundation construction is underway. The interpretation between boreholes and the recommendations of this report must therefore be checked through field monitoring provided by an experienced geotechnical engineer to validate the information for use during the construction stage.



# 10 Floor Slab and Drainage Requirements

The floor slabs of the buildings may be constructed as slabs-on-grade provided they are set on a bed of well-packed 19 mm clear stone at least 300 mm thick placed on native soil or on well compacted engineered fill prepared as indicated in Section 8 of the report. The clear stone would prevent the capillary rise of moisture from the sub-soil to the floor slab. Adequate saw cuts should be provided in the floor slabs to control cracking.

Perimeter drains are not required for buildings with no basement, provided the floor slab is set at least 150 mm higher than the surrounding finished grade. For buildings with a basement, perimeter drains will be required as discussed in Section 11.

The need for underfloor drains for buildings with and without basements will have to be assessed once the slab elevation is available and compared with the elevation of the prevailing groundwater level.

The finished exterior grade should be sloped away from the buildings at an inclination of at least two percent to prevent surface ponding close to the exterior walls.



## 11 Subsurface Walls

The subsurface basement walls should be backfilled with free draining material, such as OPSS 1010 Granular B Type II and equipped with a perimeter drainage system to prevent the buildup of hydrostatic pressure behind the walls. The walls will be subjected to lateral static and dynamic (seismic) earth forces. The expressions below assume free draining backfill material, a perimeter drainage system, level backfill surface behind the wall and vertical face on the back side of the wall.

For design purposes, the lateral static earth thrust against the subsurface walls may be computed from the following equation:

 $P = K_0 h (\frac{1}{2} \gamma h + q)$ 

where P = lateral earth thrust acting on the subsurface wall; kN/m

K<sub>0</sub> = lateral earth pressure coefficient for 'at rest' condition for Granular B Type II backfill material = 0.50

γ = unit weight of free draining granular backfill; Granular B Type II = 22 kN/m³

h = depth of point of interest below top of backfill, m

q = surcharge load, kPa

The lateral seismic thrust may be computed from the equation given below:

 $\Delta_{\text{Pe}} = \gamma H^2 \frac{a_h}{q} F_b$ 

where  $\Delta_{Pe}$  = dynamic thrust in kN/m of wall

H = height of wall, m

γ = unit weight of backfill material = 22 kN/m<sup>3</sup>

 $\frac{a_h}{g}$  = seismic coefficient = 0.309 (refer to 2015 National Building Code Seismic Hazard Calculation shown in Appendix A)

 $F_b$  = thrust factor = 1.0

The dynamic thrust does not take into account the surcharge load. The resultant force acts approximately at 0.63H above the base of the wall.

All subsurface basement walls should be properly damp-proofed.



## 12 Pipe Bedding Requirements

It is recommended that the bedding for the underground services including material specifications, thickness of cover material and compaction requirements conform to City of Ottawa requirements and/or Ontario Provincial Standard Specification and Drawings (OPSS and OPSD).

Due to the presence of the sand and clay and high groundwater level, it is recommended the pipe bedding consist of 300 mm thick OPSS 1010 Granular B Type II sub-bedding material overlain by 150 mm thick OPSS 1010 Granular A bedding material. The bedding materials should be compacted to at least 95 percent SPMDD.

The bedding thickness may be further increased in areas where the sand and clay subgrade become disturbed. Trench base stabilization techniques, such as removal of loose/soft material, placement of crushed stone sub-bedding (Granular B Type II), completely wrapped in a non-woven geotextile, may also be used if trench base disturbance becomes a problem in wet or soft areas.

If the backfill for the service trenches will consist of granular fill, clay seals should be installed in the service trenches at select intervals as per City of Ottawa Drawing No. S8. The seals should be 1 m wide, extend over the entire trench width and from the bottom of the trench to the underside of the pavement structure. The clay should be compacted to 95 percent SPMDD. The purpose of the clay seals is to prevent the permanent lowering of the groundwater level.



## 13 Excavations and De-Watering Requirements

#### 13.1 Excavations

Excavations for the construction of the proposed structures and installation of the underground services assuming a site grade raise of 1.0 m are anticipated to extend to a 2.0 m depth below existing grade. The excavations are expected to extend through the silty sand and into the clay. The excavations are anticipated to be up to 1.6 m below the groundwater level.

Upon completion of the demolition and removal of the existing buildings and their floor slabs, foundation walls and footings, the soils at the site may be excavated with conventional mechanical equipment capable of removing possible debris within the existing fill.

The excavations at the site may be undertaken as open cut provided they meet the requirements of the Ontario Occupational Health and Safety Act (OHSA). The overall soils are classified as Type 3 and must be cut back at 1H:1V from the bottom of the excavation. For excavations that extend below the groundwater level, the side slopes should be cut back at 2H:1V to H:1V from the bottom of the excavation. If space restrictions prevent open cut excavations, such as for underground service trenches, the excavations may be undertaken within the confines of a prefabricated support system (trench box) or engineered support system designed and installed in accordance with the above noted regulation.

Excavations up to a 2.0 m depth below existing grade are not expected to experience base-heave type failure.

The silty sand and clay stratum at the site are susceptible to disturbance due to the movement of construction equipment, and personnel on its surface. It is therefore recommended that the excavation at the site should be undertaken by equipment that does not travel on the excavated surface, such as a gradall or mechanical shovel. It is anticipated that temporary granular roads may be required to gain access to the site.

Many geologic materials deteriorate rapidly upon exposure to meteorological elements. Unless otherwise specifically indicated in this report, walls and floors of excavations must be protected from moisture, desiccation, and frost action throughout the course of construction.

#### 13.2 De-Watering Requirements

Seepage of the surface and subsurface water into the excavations is anticipated. However, it should be possible to collect water entering the excavations at low points and to remove it by conventional pumping techniques. In areas of high infiltration or in areas where more permeable soil layers may exist (such as the silty sand) a higher seepage rate should be anticipated. Therefore, the need for high capacity pumps to keep the excavation dry should not be ignored.

It has been assumed that the maximum excavation depth at the site will be approximately 2.0 m and would necessitate groundwater removal from the site. It is noteworthy to mention that new legislation came into force in Ontario on March 29, 2016 to regulate groundwater takings for construction dewatering purposes. Prior to March 29, 2016, a Category 2 Permit to Take Water (PTTW) was required from the Ontario Ministry



of the Environment and Climate Change (MOECC) for groundwater takings related to construction dewatering, where taking volumes in excess of 50 m<sup>3</sup>/day, but less than 400 m<sup>3</sup>/day, and the taking duration was no more than 30 consecutive days. The new legislation replaces the Category 2 PTTW for construction dewatering with a new process under the Environmental Activity and Sector Registry (EASR). The EASR is an on-line registry, which allows persons engaged in prescribed activities, such as water takings, to register with the MOECC instead of applying for a PTTW.

To be eligible for the new EASR process, the construction dewatering taking must be less than 400 m³/day under normal conditions. The water taking can be groundwater, storm water, or a combination of both. It should be noted that the 30-consecutive day limit on the water taking under the old Category 2 PTTW process has been removed in the new EASR process. Also, it should be noted that the EASR process requires two technical studies be prepared by a Qualified Person, prior to any water taking. These studies include a Water Taking Report, which provides assurance that the taking will not cause any unacceptable impacts, and a Discharge Plan, which provides assurance that the discharge will not result in any adverse impacts to the environment. A significant advantage of the new EASR process over the former Category 2 PTTW process, is that the groundwater taking may begin immediately after completing the on-line registration of the taking and paying the applicable fee, assuming the accompanying technical studies have been completed. The former PTTW process typically took more than 90 days, which had the potential to impact construction schedules. EXP can provide assistance during the EASR/PTTW process, if required.

Although this investigation has estimated the groundwater levels at the time of the fieldwork, and commented on dewatering and general construction problems, conditions may be present which are difficult to establish from standard boring and excavating techniques and which may affect the type and nature of dewatering procedures used by the contractor in practice. These conditions include local and seasonal fluctuations in the groundwater table, erratic changes in the soil profile, thin layers of soil with large or small permeabilities compared with the soil mass, etc. Only carefully controlled tests using pumped wells and observation wells will yield the quantitative data on groundwater volumes and pressures that are necessary to adequately engineer construction dewatering systems.



# 14 Backfilling Requirements and Suitability of On-Site Soils for Backfilling Purposes

The on-site soils to be excavated are anticipated to consist of a granular fill, silty sand, brown clay (desiccated crust) and grey clay. Select portions of the granular fill, silty sand and brown clay (desiccated crust) from above the groundwater level may be used in service trenches outside the building area, subject to further examination and testing during the early stages of construction. These soils are moisture sensitive and should be protected from the effects of weather if stockpiled on site. The brown and grey clay below the groundwater level are considered too wet to achieve the required degree of compaction. Therefore, these soils may be used for general grading purposes in landscaped areas, provided the moisture content of these soils is lowered by air-drying in the sun.

It is anticipated that the majority of the material required for backfilling purposes or as subgrade fill for the project would have to be imported and should preferably conform to the following specification:

- ➤ Engineered fill under slabs-on-grade OPSS 1010 Granular B Type II placed in 300 mm thick lifts and each lift compacted to 98 percent of the SPMDD.
- ➤ Backfill in services trenches inside buildings OPSS 1010 Granular B Type II placed in 300 mm thick lifts and each lift compacted to 98 percent of the SPMDD.
- Trench backfill and subgrade fill in parking area and access roadways OPSS 1010 Select Subgrade Material (SSM) placed in 300 mm thick lifts and each lift compacted to 95 percent of the SPMDD. To minimize settlement of the pavement structure over services trenches, the trench backfill material within the frost zone should match the existing material along the trench walls to minimize differential frost heaving of the subgrade soil, provided this material is compactible. Other wise, frost tapers may be required.

As previously indicated, if the backfill for the service trenches will consist of granular fill, clay seals should be installed in the service trenches at select intervals as per City of Ottawa Drawing No. S8. The seals should be 1 m wide, extend over the entire trench width and from the bottom of the trench to the underside of the pavement structure. The clay should be compacted to 95 percent SPMDD. The purpose of the clay seals is to minimize the permanent lowering of the groundwater level.



## 15 Pavement Structures

Pavement structures for the surface parking areas and access roads are given on Table VII below for the anticipated engineered fill subgrade used to raise the site grades and for the native silty sand and clay subgrades. The pavement structures are based upon the assumption that the subgrade will be properly prepared and assumes a functional design life of 15 to 18 years. The proposed functional design life represents the number of years to the first rehabilitation, assuming regular maintenance is carried out.

Table VII: Recommended Pavement Structure Thicknesses							
	Compaction Requirements	Computed Pavement Structure					
Pavement Layer		Light Duty Traffic (Parking Lots - Cars Only)	Heavy Duty (Parking Lots and Access Roads)				
Asphaltic Concrete (PG 58-34)	92-97% MRD	65 mm HL3/SP12.5 mm/ Cat.B	40 mm HL3/SP12.5 Cat. B 50 mm HL8/SP 19 Cat. B				
OPSS 1010 Granular A Base (crushed limestone)	100% SPMDD	150 mm	150 mm				
OPSS 1010 Granular B Type II Sub-base	100% SPMDD	450 mm	600 mm				

#### Notes:

- 1. SPMDD denotes standard Proctor maximum dry density, ASTM, D-698-12e2.
- 2. MRD denotes Maximum Relative Density, ASTM D2041.

The upper 300 mm of the subgrade fill must be compacted to 98% SPMDD.

Additional comments on the construction of the parking lot and access roads are as follows:

- 1. As part of the subgrade preparation, the proposed parking areas and access roads should be stripped of topsoil and other obviously unsuitable material. Fill required to raise the grades to design elevations should conform to requirement as per Section 8 and should be placed and compacted to 95 percent of the SPMDD. The subgrade should be properly shaped, crowned, then proofrolled with a heavy vibratory roller in the full-time presence of a representative of this office. Any soft or spongy subgrade areas detected should be sub excavated and properly replaced with suitable approved backfill compacted to 95 percent SPMDD (ASTM D698-12e2).
- 2. The long-term performance of the pavement structure is highly dependent upon the subgrade support conditions. Stringent construction control procedures should be maintained to ensure that uniform subgrade moisture and density conditions are achieved. The need for adequate drainage cannot be over-emphasized. Subdrains should be installed on both sides of the access road(s). Subdrains must be installed in the proposed parking area at low points and should be continuous between catchbasins to intercept excess surface and subsurface moisture and to prevent subgrade softening. This will ensure no water collects in the granular course, which could result in pavement failure during the spring thaw. The location and extent of subdrainage required within the paved areas should be reviewed by this office in conjunction with the proposed site grading.



- 3. To minimize the problems of differential movement between the pavement and catchbasins/manhole due to frost action, the backfill around the structures should consist of free-draining granular preferably conforming to OPSS Granular B Type II material. Weep holes should be provided in the catchbasins/manholes to facilitate drainage of any water that may accumulate in the granular fill.
- 4. The most severe loading conditions on light-duty pavement areas and the subgrade may occur during construction. Consequently, special provisions such as restricted lanes, half-loads during paving, temporary construction roadways, etc., may be required, especially if construction is carried out during unfavorable weather.
- 5. The finished pavement surface should be free of depressions and should be sloped (preferably at a minimum cross fall of 2 percent) to provide effective surface drainage towards catch basins. Surface water should not be allowed to pond adjacent to the outside edges of paved areas.
- 6. Relatively weaker subgrade may develop over service trenches at subgrade level. These areas may require the use of thicker/coarser sub-base material and the use of a geotextile at the subgrade level. If this is the case, it is recommended that additional 150 mm of granular sub-base, OPSS Granular B Type II, should be provided in these areas, in addition to the use of a geotextile at the subgrade level.
- 7. The granular materials used for pavement construction should conform to Ontario Provincial Standard Specifications (OPSS 1010) for Granular A and Granular B Type II and should be compacted to 100 percent of the SPMDD.

The asphaltic concrete used and its placement should meet OPSS 1150 or 1151 requirements. It should be compacted from 92 to 97 percent of the MRD (ASTM D2041). Asphalt placement should be in accordance with OPSS 310 and OPSS 313.

It is recommended that EXP be retained to review the final pavement structure design and drainage plans prior to construction to ensure they are consistent with the recommendations of this report.



## 16 Corrosion Potential of Subsurface Soils

Chemical tests limited to pH, sulphate, chloride and resistivity tests were performed on two (2) selected soil samples. The results are shown on Table No. VIII. The Certificate of Analysis is included in Appendix B.

Table VIII: Results of pH, Sulphate, Chloride and Resistivity Tests on Soil Samples								
Borehole No	Depth (Elevation) (m)	Soil	рН	Sulphate (%)	Chloride Content (%)	Resistivity (ohm.cm)		
Sample No.	, ,		<5	>0.1 %	>0.04 %			
BH 1 – SS4	2.3 – 2.9 (76.8 – 76.2)	Grey Clay	7.54	0.0025	0.0051	6,170		
BH 4 – SS3	1.5 – 2.1 (75.2 – 74.6)	Brown Clay	7.05	0.0122	0.0054	4,270		

The results indicate a soil with a sulphate content of less than 0.1 percent. This concentration of sulphate in the soil would have a negligible potential of sulphate attack on subsurface concrete. The concrete should be designed in accordance with CSA A.23.1-14. However, the concrete should be dense, well compacted and cured.

The results of the resistivity tests indicate that the soil is moderately to mildly corrosive to buried steel elements. Appropriate measures should be undertaken to protect buried steel elements from corrosion.



May 18, 2018

## 17 Tree Planting Restrictions

The brown clay crust extends to depths ranging from 2.1 m to 3.0 m (Elevation 75.3 m to 74.2 m) and the footings are proposed to be set at 0.1 m to 0.3 m below the surface of the brown clay crust at a 1.0 m depth below existing grade in Borehole Nos. 2 to 5.

Based on the City of Ottawa document titled, "Tree Planting in Sensitive Marine Clay Soils – 2017 Guidelines," the modified plasticity index of the brown clay was estimated at 43 percent indicating the brown clay crust has a high potential for soil volume change.

The grey clay was contacted beneath the silty sand in Borehole No. 1 and the brown clay crust in the remaining boreholes at 2.1 m to 3.0 m depth (Elevation 76.9 m to 74.2 m). The modified plasticity index of the grey clay is estimated at 32 percent indicating the grey clay has a medium potential for soil volume change.

In accordance with the above referenced 2017 guidelines, for high potential volume change soil types, the tree planting restrictions and setbacks from structures should follow the 2005 clay soil policy.

For medium potential volume change soil types, the tree planting restrictions and setbacks from structures should follow the above noted 2017 guidelines.

A landscape architect should be consulted to ensure the applicable tree planting restrictions and setbacks for the development of this site are in accordance with the applicable City of Ottawa guideline and policy.



### 18 Additional Comment

The depth to the native silty sand and clay may vary from that indicated on the borehole logs due to presence of the existing buildings on site. For example, the fill thickness and depth to native silty sand and clay may be deeper than shown on the borehole logs at locations close to and/or within the footprint of existing buildings and underground service trenches. The boreholes from the Phase II ESA indicate the fill extends to 1.8 m depth below existing grade. Therefore, it is recommended that once the existing buildings have been demolished and foundations, foundation walls and floor slabs have been removed, additional boreholes be undertaken within the footprints of the existing buildings to determine the subsurface conditions, suitable founding soil conditions and depths for footings, the groundwater level, bearing pressure at SLS and factored geotechnical resistance at ULS, excavation and dewatering requirements.



## 19 General Comments

The comments given in this report are intended only for the guidance of design engineers. The number of boreholes required to determine the localized underground conditions between boreholes affecting construction costs, techniques, sequencing, equipment, scheduling, etc., would be much greater than has been carried out for the design purposes. Contractors bidding on or undertaking the works should, in this light, decide on their own investigations, as well as their own interpretations of the factual borehole results, so that they may draw their own conclusions as to how the subsurface conditions may affect them.

The information contained in this report is not intended to reflect on environmental aspects of the soils. Should specific information be required, including for example, the presence of pollutants, contaminants or other hazards in the soil, additional testing may be required.

We trust that the information contained in this report will be satisfactory for your purposes. Should you have any questions, please do not hesitate to contact this office.




## **Figures**



trow standard, july 01, 2004.ctb Pen Table::

Plotted by: RevellJ

Filename: r:\240000\246000\246046-a0 6102 renaud rd\246046-ge.dwg : 5/7/2018 3:30:55 PM 1: 5/8/2018 9:42:16 AM Last Saved: ast Plotted:



## **Notes On Sample Descriptions**

1. All sample descriptions included in this report follow the Canadian Foundations Engineering Manual soil classification system. This system follows the standard proposed by the International Society for Soil Mechanics and Foundation Engineering. Laboratory grain size analyses provided by **exp** Services Inc. also follow the same system. Different classification systems may be used by others; one such system is the Unified Soil Classification. Please note that, with the exception of those samples where a grain size analysis has been made, all samples are classified visually. Visual classification is not sufficiently accurate to provide exact grain sizing or precise differentiation between size classification systems.

							ISSMFE S	OIL CLAS	SIFIC	OITAC	V				
CLAY			SILT	3 #1013 g			SAND	20 00 00	7.		GRAV	EL	a magazina (	COBBLES	BOULDERS
		FINE	MEDIUM	COAR:	SE	FINE	MEDIUM	COAR	SE	FINE	MEDIL	JM	COARSE		
	0.00	12	0.006	0.02	0.06		0.2	0.6	2. <b>I</b>	0	6.0 	20	60 <b>I</b>	20	00 L
CLAY (F	DI A CI	FIC) TO			EQUI	FINE	NT GRAIN	N DIAMET	ER IN	CRS.	METRES  FINE	Loc	DARSE	7	
SILT (NO						LINE		SAND		GIO.	I HAL	GRAVE		<u> </u>	
			·			ALATE ALAE	Comment of the Commen	etos deser utiliza	White warms		0.0000000000000000000000000000000000000				

UNIFIED SOIL CLASSIFICATION

- 2. Fill: Where fill is designated on the borehole log it is defined as indicated by the sample recovered during the boring process. The reader is cautioned that fills are heterogeneous in nature and variable in density or degree of compaction. The borehole description may therefore not be applicable as a general description of site fill materials. All fills should be expected to contain obstruction such as wood, large concrete pieces or subsurface basements, floors, tanks, etc., none of these may have been encountered in the boreholes. Since boreholes cannot accurately define the contents of the fill, test pits are recommended to provide supplementary information. Despite the use of test pits, the heterogeneous nature of fill will leave some ambiguity as to the exact composition of the fill. Most fills contain pockets, seams, or layers of organically contaminated soil. This organic material can result in the generation of methane gas and/or significant ongoing and future settlements. Fill at this site may have been monitored for the presence of methane gas and, if so, the results are given on the borehole logs. The monitoring process does not indicate the volume of gas that can be potentially generated nor does it pinpoint the source of the gas. These readings are to advise of the presence of gas only, and a detailed study is recommended for sites where any explosive gas/methane is detected. Some fill material may be contaminated by toxic/hazardous waste that renders it unacceptable for deposition in any but designated land fill sites; unless specifically stated the fill on this site has not been tested for contaminants that may be considered toxic or hazardous. This testing and a potential hazard study can be undertaken if requested. In most residential/commercial areas undergoing reconstruction, buried oil tanks are common and are generally not detected in a conventional geotechnical site investigation.
- 3. Till: The term till on the borehole logs indicates that the material originates from a geological process associated with glaciation. Because of this geological process the till must be considered heterogeneous in composition and as such may contain pockets and/or seams of material such as sand, gravel, silt or clay. Till often contains cobbles (60 to 200 mm) or boulders (over 200 mm). Contractors may therefore encounter cobbles and boulders during excavation, even if they are not indicated by the borings. It should be appreciated that normal sampling equipment cannot differentiate the size or type of any obstruction. Because of the horizontal and vertical variability of till, the sample description may be applicable to a very limited zone; caution is therefore essential when dealing with sensitive excavations or dewatering programs in till materials.



## RH 1

roject:	OTT-00246046-A0  Geotechnical Investigation - Proposed Residential Development									Figure	No	3	_		
roject: ocation:	6102 Renaud Road, Ottawa, ON		sidentia	ט וו	evelopm	ent				Pa	ige	1_ of	3_		
	'April 18, 2018	ν.													_
				_	Split Spo Auger Sa		ple					pour Read Content	ling		□ <b>X</b>
	CME-55 Truck Mount Drill Rig  Approximate Elevation			_	SPT (N)		est		· -		rg Limits ied Triaxi	al at	H		<b>⊕</b>
ogged by:	ML Checked by:	SMP		_	Shelby T Shear St		v			% Straii	n at Failu Strength I	ire			<b>⊕</b>
oggod by.	ME Official by	Olvii			Vane Te		у	+ s			meter Te				•
S Y M B O	SOIL DESCRIPTION		Approximat	te E	)		enetration 40		lue 80	2	250 5		50	S A M P	Natura Unit W
M B O L	SOIL DESCRIFTION		Elevation m 79.11	ı F	۱ ا	Strength			kPa 200	1		ture Conte s (% Dry W 40 6	nt % /eight) 60	LLES	kN/m <sup>3</sup>
	HALTIC CONCRETE ~50 mm ~ 150 mm		79.0 78.8		.9.									M	
	ned limestone, grey, moist Y SAND														
	zed stains, brown, moist, (loose to	0 _		1	8 ©				#####		×	######################################		$\bigvee$	
	•	_			2012				11.201						
					<b>13</b>						×				
CLA	<i>,</i>	_	76.9	2	3313							<del>                                      </del>	3333		
	tive to extra-sensitive, grey, wet,	(firm to –	Ha	mm	er Weight.	· ! · ? · ? · !					×			M	
		_		3	, <del>                                    </del>	<mark>77</mark>		1.2.2.1.3						/\ m	
			Ha	mm	er Weight	s=9.1						×	· · · · · ·	M	
		_			38										
		_	Ha 74.9		er Wes=8.0	) 					<del>                                     </del>	<del>                                      </del>	· · · · >	82 <sup>7</sup>	
		_			36						::::::  ::::::	######################################			
		_	Ha	mm	er Wes=10								×		
					36									:/\ .m	
		_			s=6.0										
		_		6	: <del>  </del>		· · · · · · · · · · · · · · · · · · ·				1.5 (1.5	- (-1 (-			
		_													
						62									
		_		7	'   <del>                                   </del>	s=6.9									
		_			33.13										
		_	Ha	mm 8	er Weight			<u> </u>				# (: 1 2 f: # : 1 2 f:	×	X	
						67								7	
		_			2000	s=7.0									
		_		9											
		_	Ha	ımm	er Weight			1:::::::	<del></del>				×		
						77						#			
OTES:	Continued Next Page		WATI	ER	LEVEL RE	s=4.6	3			C	ORE DR	ILLING RE	ECORD		
Borehole data re use by others	equires interpretation by EXP before	Elaps	sed		Water Level (m)		Hole Op To (m		Run No.	Dep (m	oth	% Red		RC	QD %
. Borehole backfi	lled upon completion of drilling.	Compl			4.2		8.2			(,,					


Project No: OTT-00246046-A0

Figure No.

"exp

Project: Geotechnical Investigation - Proposed Residential Development

Page. 2 of 3



#### NOTES:

LOG OF BOREHOLE

- Borehole data requires interpretation by EXP before use by others
- 2. Borehole backfilled upon completion of drilling.
- 3. Field work supervised by an EXP representative.
- 4. See Notes on Sample Descriptions
- $5.\,\mathrm{Log}$  to be read with EXP Report OTT-00246046-A0

WA	WATER LEVEL RECORDS								
Elapsed Time	Water Level (m)	Hole Open To (m)							
Completion	4.2	8.2							

CORE DRILLING RECORD									
Depth (m)	% Rec.	RQD %							
	Depth	Depth % Rec.							


Project No: OTT-00246046-A0

Figure No.

"exp

Project: Geotechnical Investigation - Proposed Residential Development

Page. 3 of 3



#### NOTES


LOG OF BOREHOLE

- Borehole data requires interpretation by EXP before use by others
- 2. Borehole backfilled upon completion of drilling.
- 3. Field work supervised by an EXP representative.
- 4. See Notes on Sample Descriptions
- $5.\,\mathrm{Log}$  to be read with EXP Report OTT-00246046-A0

WATER LEVEL RECORDS								
Elapsed	Water	Hole Open						
Time	Level (m)	To (m)						
Completion	4.2	8.2						

	CORE DRILLING RECORD									
Run No.	Depth (m)	RQD %								

Project No:	OTT-00246046-A0	og o	of E	80	rel	าด	)le	<u> </u>	<u>3</u> H	<u> 2</u>							E	X
Project:	Geotechnical Investigation - Pro	oposed Re	esidenti	al D	evelopr	nent					F	igure			4	_		
-ocation:	6102 Renaud Road, Ottawa, O				•							Pa	ige.	_1	_ of			
ate Drilled:	'April 16, 2018				Split Sp	oon S	Samp	le	Б			Combu	stible \	/apoi	ur Read	dina		
Orill Type:	CME-55 Truck Mount Drill Rig			_	Auger S	Samp	е					Natural	Moistu	ire C		9		×
)atum:	Approximate Elevation			_	SPT (N Dynami			st		) <del>-</del>		Atterbe Undrair	ed Tria	axial a	at			—⊖ ⊕
ogged by:	AN Checked by:	SMP		_	Shelby Shear S		ıth by					% Strai Shear S	Strengt	h by				<b>⊕</b>
33 ,					Vane Te		,		;	Ś		Penetro	meter	Test				
S Y M B O	SOIL DESCRIPTION		Approxim Elevation	1 6	?	20	40	etration 7	est N V	80	kPa	2	250	500	r Readii ) 7 e Conte % Dry V	50	SAMPLES	Natura Unit W kN/m³
	~ 150 mm		77.53 77.3	Ċ	; <del> </del>	50	10	0 1	50	200	<del></del> .		20	40		30	Š	
FILL	hed limestone, grey, moist	/_											×		::::::::::::::::::::::::::::::::::::::			
Mixtu sand.	re of crushed limestone gravel a , grey and brown, wet	nd silty	76.8							102								7
CLA		stiff)		1	Ø::::					<b>A</b>				×	•			17.6
		_			2			3-1-3-5 3-1-3-5	· · · · · · · · · · · · · · · · · · ·	· · · · ·	) (- i - ) (- i -		1.2.2.3		<u>u : : :</u>	1000		17.1
		_		2	, [		82	* i · i · i · i · i · i · i · i · i · i			: : . : .: : : :							17.1
CLA		r\	75.3		1		=4.9											
Extra	-sensitive, grey, wet, (firm to stiff	r) –			34			: 1 · 5 · 5 · 5 · 5 · 5 · 5 · 5 · 5 · 5 ·	3 3 1		· · · · · · · · · · · · · · · · · · ·	0000				X		
		-		amm	s=14 er Weigh			* 1 . 3 . 5									83	] /
		_	ַ ''		Φ: :::::			* ! * * *									XX	
					4	3												
		_	- H	amm	er Weiß=	9.0		****							<del>: : : : :</del>		$ \mathbf{x} $	
		_	_			58									::::::::::::::::::::::::::::::::::::::			1
			н	amm	er Weigh	s=12.0	)::::: ::::	* 1 · 3 · 5 * 1 · 3 · 5								×		*
					`   : : : : : : : : : : : : : : : : : :											201		4
		-			33333	1.1		3.1.3.3			; (- i - ; (- i - i ; (- i - i				· · · · · · · · · · · · · · · · · · ·			
		_		6	,	.s=1	3.0	÷ i · i · i			: : . : .: : : : : : : : : : : : : :				: : : : : : : : : : : <del>: : : : :</del>			
			н	amm	er Weigh													1
		_																
		_		7	er Weigh	67	:::	****									82	<b>X</b>
		_	_ "	amm	O::::::			* ! * * *									×X	
					33333	67												
Be	orehole Terminated at 8.1 m d	epth	69.4	8	3	s=14	1.0	****		##		<del>  : : : :</del>   : : : :						
OTES:			WA	ΓER	LEVEL R	ECO	RDS					C	ORE D	RILL	.ING RI	ECOR		
Borehole data rouse by others	equires interpretation by EXP before	Elap:	sed		Water Level (m			Hole Op To (m)		R	un Io	Dep (m	oth		% Re			RQD %
	illed upon completion of drilling.	Compl			_0v0i (III	,		10 (111)		18		(11	.,					
	ervised by an EXP representative.  Sample Descriptions																	
	with EXP Report OTT-00246046-A0																	



246046 - 6102 RENAUD ROAD.GPJ TROW OTTAWA.GDT 5/14/1

- 1. Borehole data requires interpretation by EXP before
- 2.A 19 mm diameter standpipe piezometer installed as
- 3. Field work supervised by an EXP representative.
- 4. See Notes on Sample Descriptions
- 5. Log to be read with EXP Report OTT-00246046-A0

WATER LEVEL RECORDS								
Elapsed	Water	Hole Open						
Time	Level (m)	To (m)						
Completion	5.2	7.3						
20 days	0.4							

	CORE DRILLING RECORD								
Run No.	Depth (m)	% Rec.	RQD %						

Project No: OTT-00246046-A0 Figure No. Project: Geotechnical Investigation - Proposed Residential Development 1 of 3 Page. Location: 6102 Renaud Road, Ottawa, ON. Date Drilled: 'April 17, 2018 Split Spoon Sample  $\boxtimes$ Combustible Vapour Reading X Auger Sample Natural Moisture Content Drill Type: CME-55 Truck Mount Drill Rig 0 SPT (N) Value 0 Atterberg Limits Dynamic Cone Test Undrained Triaxial at Datum: Approximate Elevation  $\oplus$ % Strain at Failure Shelby Tube Shear Strength by Logged by: Checked by: SMP Shear Strength by Penetrometer Test Standard Penetration Test N Value Combustible Vapour Reading (ppm) SYMBO-Approximate 250 500 Natural G W L SOIL DESCRIPTION Natural Moisture Content % Atterberg Limits (% Dry Weight) Elevation Unit Wt kN/m<sup>3</sup> 76.67 TOPSOIL ~ 50 mm 76.6 Mixture of crushed limestone gravel, silty 76.0 sand, topsoil and rootlets, black, moist, (compact) **CLAY** 18.3 75.37 High plasticity, brown, moist, (very stiff) 19.0 74.6 High plasticity, sensitive to quick, grey, wet, (firm to very stiff) s=18.0 Continued Next Page WATER LEVEL RECORDS CORE DRILLING RECORD 1. Borehole data requires interpretation by EXP before Water RQD % Elapsed Hole Open Depth % Rec. Level (m) Time To (m) No. (m) 2.A 19 mm diameter standpipe piezometer installed as Completion 2.3 20 days 1.3 3. Field work supervised by an EXP representative. 4. See Notes on Sample Descriptions 5. Log to be read with EXP Report OTT-00246046-A0

246046 - 6102 RENAUD ROAD.GPJ TROW OTTAWA.GDT 5/14/1


Project No: OTT-00246046-A0

Figure No.

ex

Project: Geotechnical Investigation - Proposed Residential Development

Page. 2 of 3



NOTES:

-0G OF

Borehole data requires interpretation by EXP before use by others

2. A 19 mm diameter standpipe piezometer installed as shown.

3. Field work supervised by an EXP representative.

4. See Notes on Sample Descriptions

5. Log to be read with EXP Report OTT-00246046-A0

WATER LEVEL RECORDS								
Elapsed	Water	Hole Open						
Time	Level (m)	To (m)						
Completion	2.3							
20 days	1.3							

CORE DRILLING RECORD									
Run No.	Depth % Rec. RQD 9								


Project No: OTT-00246046-A0

Figure No.

exp

Project: Geotechnical Investigation - Proposed Residential Development

Page. 3 of 3



#### NOTES

- Borehole data requires interpretation by EXP before use by others
- 2.A 19 mm diameter standpipe piezometer installed as shown.
- 3. Field work supervised by an EXP representative.
- 4. See Notes on Sample Descriptions
- $5. Log \ to \ be \ read \ with EXP \ Report \ OTT-00246046-A0$

WA	WATER LEVEL RECORDS				
Elapsed	Water	Hole Open			
Time	Level (m)	To (m)			
Completion	2.3				
20 days	1.3				

CORE DRILLING RECORD				
Run	Depth	% Rec.	RQD %	
No.	(m)			

Project No: OTT-00246046-A0 Figure No. Project: Geotechnical Investigation - Proposed Residential Development Page. Location: 6102 Renaud Road, Ottawa, ON. Date Drilled: 'April 18, 2018 Split Spoon Sample  $\boxtimes$ Combustible Vapour Reading X Auger Sample Natural Moisture Content Drill Type: CME-55 Truck Mount Drill Rig 0 SPT (N) Value 0 Atterberg Limits Undrained Triaxial at Dynamic Cone Test Datum: Approximate Elevation  $\oplus$ % Strain at Failure Shelby Tube Shear Strength by Logged by: Checked by: SMP Shear Strength by Penetrometer Test Standard Penetration Test N Value Combustible Vapour Reading (ppm) SYMBO-Approximate Natural 250 500 G W L SOIL DESCRIPTION Natural Moisture Content % Atterberg Limits (% Dry Weight) Elevation Unit Wt kN/m<sup>3</sup> 77.18 **FILL** ~ 150 mm 77.0 Crushed limestone, grey, wet Mixture of gravel, silty sand, clay, topsoil and 76.3 wood debris, brown and black, moist, (loose to compact) >120 **CLAY** 75.78 Sensitive, brown, moist, (stiff to very stiff) 17.8 74.2 **CLAY** Sensitive to extra-senstive, grey, wet, (firm to :38 ner Weight Hammer Weight 62: 67 :::: Continued Next Page WATER LEVEL RECORDS CORE DRILLING RECORD 1. Borehole data requires interpretation by EXP before Water RQD % Elapsed Hole Open Depth % Rec. Level (m) Time To (m) No. (m) 2.A 19 mm diameter standpipe piezometer installed as Completion 3.6 10 1

19 days

1.4

246046 - 6102 RENAUD ROAD.GPJ TROW OTTAWA.GDT 5/14/1

3. Field work supervised by an EXP representative.

5. Log to be read with EXP Report OTT-00246046-A0

4. See Notes on Sample Descriptions


Project No: OTT-00246046-A0

Figure No.

"exp

Project: Geotechnical Investigation - Proposed Residential Development

Page. 2 of 2



#### NOTES

- Borehole data requires interpretation by EXP before use by others
- 2. A 19 mm diameter standpipe piezometer installed as shown.
- 3. Field work supervised by an EXP representative.
- 4. See Notes on Sample Descriptions
- $5. Log \ to \ be \ read \ with EXP \ Report \ OTT-00246046-A0$

WA	TER LEVEL RECO	RDS
Elapsed	Water	Hole Open
Time	Level (m)	To (m)
Completion	3.6	10.1
19 days	1.4	

CORE DRILLING RECORD					
Run No.	Depth (m)	% Rec.	RQD %		



Percent Passing

#### Grain-Size Distribution Curve Method of Test For Particle Size Analysis of Soil ASTM C-136/ASTM D422

100-2650 Queensview Drive Ottawa, ON K2B 8H6

#### **Unified Soil Classification System** SAND GRAVEL CLAY AND SILT Fine Medium Coarse Fine Coarse GRAIN SIZE IN MICROMETERS SIEVE DESIGNATION (Imperial) 75 #200 30 50 3/8" 1/2" 3/4" 1" #50 #100 100.0 95.0 90.0 85.0 80.0 75.0 70.0 65.0 60.0 55.0 50.0 45.0 40.0 35.0 30.0 25.0 20.0 15.0 10.0 5.0 0.0 1 0.01 0.1 10 Grain Size (mm)


EXP Project No.:	OTT-00246046 - A0	Project Name :		Geotechnical In	vestigati	on - Proposed	d Re	sidenti	al Development	
Client :	2597237 Ontario Ltd.	Project Location	Project Location : 6102 Renaud Road, Ottawa, ON.							
Date Sampled :	April 18, 2018	Borehole No:		BH1	San	ple No.:	SS	3	Depth (m) :	1.5-2.1
Sample Description :		% Silt and Clay	20	% Sand	80	% Gravel		0	Figure :	
Sample Description :		Silty Sand (SM)			rigure .	8				

www.exp.com



#### Grain-Size Distribution Curve Method of Test For Particle Size Analysis of Soil ASTM C-136/ASTM D422

100-2650 Queensview Drive Ottawa, ON K2B 8H6



EXP Project No.:	OTT-00246046 - A0	Project Name :	roject Name : Geotechnical Investigation - Proposed Residential Development							
Client :	2597237 Ontario Ltd.	Project Location	:	6102 Renaud Ro	ad, Otta	wa, ON.				
Date Sampled :	April 16, 2018	Borehole No:		BH2	Sam	ple No.:	SS	32	Depth (m) :	0.8-1.4
Sample Description :		% Silt and Clay	98	% Sand	2	% Gravel		0	Eigung .	
Sample Description :		Clay (CH)			9					


www.exp.com



# One-Dimensional Consolidation Properties of Soils Using Incremental Loading

ASTM D 2435 - Taylor Method

Client:	Y/Projec	t: OTT-00246046- <i>A</i>	<b>A</b> 0		Date :	2018-04-24
Project : EXP Ontario				Our file No. :	P-0011703-6-01	
Boring No	o. :	BH-1, ST-8	Sample No. :	12	Depth (m) :	6,3 to 6,4m
Hydrostatic stress at the test (date) :		:		Provided by   the	client   Englobe	



#### Initial humid unit weight $(\gamma_h)$ : 14,9 kN/m3 Initial effective stress ( $\sigma'_v$ ): 68 kPa Initial saturation degree (S<sub>r</sub>): Preconsolidation pressure $(\sigma'_p)$ : 99,5% 150 kPa Overconsolidation deviation ( $\Delta \sigma$ ): 82 kPa Coefficient of consolidation Cv kPa 2,14E-01 m2/j at 79 Coefficient of consolidation Cv 6,74E-02 m2/j at 183 kPa

**Remarks :** The sampling and transportation of the sample were carried out by a client's representative. The initial effective stress has been provided by the client.

· · · · · · · · · · · · · · · · · · ·	• • •
_A-Bocodmo	
Adlane Bouadma, ir Eng	Fai

Prepared by:

Verified by :


Famakhan Fainke, Eng



## **One-Dimensional Consolidation Properties** of Soils Using Incremental Loading

ASTM D 2435 - Taylor Method

Client:	Y/Projec	t: OTT-00246046-A	40		Date :	2018-04-26
Project : EXP Ontario				Our file No. :	P-0011703-6-01	
Boring N	o. :	BH-5, ST-6	Sample No. :	13	Depth (m) :	4,2 à 4,3m
Hydrostatic stress at the test (date) :		:		Provided by   the	client   Englobe	



#### Initial effective stress $(\sigma'_v)$ : Initial humid unit weight $(\gamma_h)$ : $15,1 \text{ kN/m}^3$ 47 kPa Initial saturation degree (S<sub>r</sub>): 99,9% Preconsolidation pressure $(\sigma'_p)$ : 110 kPa Overconsolidation deviation ( $\Delta \sigma$ ): 63 kPa Coefficient of consolidation Cv 2,19E-01 m2/j at 53 kPa Coefficient of consolidation Cv 9,52E-02 m2/j at 122 kPa

The sampling and transportation of the sample were carried out by a client's representative. Remarks: The initial effective stress has been provided by the client.


Adlane Bouadma, jr Eng

Prepared by:

Famakhan Fainke, Eng

Verified by:

EQ-09-IM-274 Rev. 06 (18-04)



# BRAY ET AL. (2004) CRITERIA FOR LIQUEFACTION ASSESSMENT OF FINE GRAINED SOILS



#### exp Services Inc.

t: +1.613.688.1899 | f: +1.613.225.7337 2650 Queensview Drive, Suite 100 Ottawa, ON K2B 8H6 Canada

#### www.exp.com

- BUILDINGS EARTH & ENVIRONMENT ENERGY •
- INDUSTRIAL INFRASTRUCTURE SUSTAINABILITY •

N.1.5.	CLIENT: 2597237 Ontario Ltd.	project no. OTT-0024606-A0
drawn by: M.L.	TITLE: Proposed Residential Subdivision - 6102 Renaud Road, Ottawa, ON.	FIG 12

**Appendix A: 2015 National Building Code Seismic Hazard Calculation** 



## 2015 National Building Code Seismic Hazard Calculation

INFORMATION: Eastern Canada English (613) 995-5548 français (613) 995-0600 Facsimile (613) 992-8836 Western Canada English (250) 363-6500 Facsimile (250) 363-6565

April 26, 2018

Site: 45.4292 N, 75.518 W User File Reference: 6102 Renaud Road, Ottawa, ON.

Requested by: , EXP Services Inc.

National Building Code ground motions: 2% probability of exceedance in 50 years (0.000404 per annum)

Sa(0.05) Sa(0.1) Sa(0.2) Sa(0.3) Sa(0.5) Sa(1.0) Sa(2.0) Sa(5.0) Sa(10.0) PGA (g) PGV (m/s) 0.501 0.581 0.482 0.363 0.255 0.125 0.059 0.015 0.0055 0.309 0.211

**Notes.** Spectral (Sa(T), where T is the period in seconds) and peak ground acceleration (PGA) values are given in units of g (9.81 m/s²). Peak ground velocity is given in m/s. Values are for "firm ground" (NBCC 2015 Site Class C, average shear wave velocity 450 m/s). NBCC2015 and CSAS6-14 values are specified in **bold** font. Three additional periods are provided - their use is discussed in the NBCC2015 Commentary. Only 2 significant figures are to be used. **These values have been interpolated from a 10-km-spaced grid of points.** Depending on the gradient of the nearby points, values at this location calculated directly from the hazard program may vary. More than 95 percent of interpolated values are within 2 percent of the directly calculated values.

#### Ground motions for other probabilities:

Probability of exceedance per annum	0.010	0.0021	0.001
Probability of exceedance in 50 years	40%	10%	5%
Sa(0.05)	0.047	0.164	0.276
Sa(0.1)	0.065	0.204	0.331
Sa(0.2)	0.058	0.174	0.278
Sa(0.3)	0.046	0.133	0.211
Sa(0.5)	0.032	0.093	0.148
Sa(1.0)	0.016	0.046	0.073
Sa(2.0)	0.0062	0.021	0.034
Sa(5.0)	0.0013	0.0048	0.0084
Sa(10.0)	0.0006	0.0019	0.0032
PGA	0.035	0.110	0.179
PGV	0.022	0.072	0.118

#### References

National Building Code of Canada 2015 NRCC no. 56190; Appendix C: Table C-3, Seismic Design Data for Selected Locations in Canada

User's Guide - NBC 2015, Structural Commentaries NRCC no. xxxxxx (in preparation)


Commentary J: Design for Seismic Effects

**Geological Survey of Canada Open File 7893** Fifth Generation Seismic Hazard Model for Canada: Grid values of mean hazard to be used with the 2015 National Building Code of Canada

See the websites www.EarthquakesCanada.ca and www.nationalcodes.ca for more information

Aussi disponible en français





Ressources naturelles Canada Canadä

**Appendix B: AGAT Certificate of Analysis** 





5835 COOPERS AVENUE MISSISSAUGA, ONTARIO CANADA L4Z 1Y2 TEL (905)712-5100 FAX (905)712-5122 http://www.agatlabs.com

**CLIENT NAME: EXP SERVICES INC** 

2650 QUEENSVIEW DRIVE, UNIT 100

OTTAWA, ON K2B8H6

(613) 688-1899

**ATTENTION TO: Susan Potyondy** 

PROJECT: OTT-246046

AGAT WORK ORDER: 18Z331542

SOIL ANALYSIS REVIEWED BY: Amanjot Bhela, Inorganic Coordinator

DATE REPORTED: Apr 27, 2018

PAGES (INCLUDING COVER): 5

**VERSION\*: 1** 

Should you require any information regarding this analysis please contact your client services representative at (905) 712-5100

NOTES

All samples will be disposed of within 30 days following analysis. Please contact the lab if you require additional sample storage time.

AGAT Laboratories (V1)

\*NOTEC

Page 1 of 5

Member of: Association of Professional Engineers and Geoscientists of Alberta (APEGA)

Western Enviro-Agricultural Laboratory Association (WEALA) Environmental Services Association of Alberta (ESAA) AGAT Laboratories is accredited to ISO/IEC 17025 by the Canadian Association for Laboratory Accreditation Inc. (CALA) and/or Standards Council of Canada (SCC) for specific tests listed on the scope of accreditation. AGAT Laboratories (Mississauga) is also accredited by the Canadian Association for Laboratory Accreditation Inc. (CALA) for specific drinking water tests. Accreditations are location and parameter specific. A complete listing of parameters for each location is available from www.cala.ca and/or www.scc.ca. The tests in this report may not necessarily be included in the scope of accreditation.



**CLIENT NAME: EXP SERVICES INC** 

## **Certificate of Analysis**

AGAT WORK ORDER: 18Z331542

PROJECT: OTT-246046

**ATTENTION TO: Susan Potyondy** 

SAMPLING SITE:6102 Renau	d Road					SAMPLED BY:exp
				Ino	rganic Chemi	stry (Soil)
DATE RECEIVED: 2018-04-23						DATE REPORTED: 2018-04-26
				BH1 SS4 7.		
		SAMPLE DES	CRIPTION:	5'-9.5'	BH4 SS3 5'-7'	
		SAN	IPLE TYPE:	Soil	Soil	
		DATE	SAMPLED:	2018-04-18	2018-04-18	
Parameter	Unit	G/S	RDL	9195398	9195399	
pH, 2:1 CaCl2 Extraction	pH Units			7.54	7.05	
Chloride (2:1)	μg/g		2	51	54	
Sulphate (2:1)	μg/g		2	25	122	
Resistivity (2:1)	ohm.cm		1	6170	4270	

RDL - Reported Detection Limit; G / S - Guideline / Standard Comments:

9195398-9195399 EC/Resistivity, Chloride and Sulphate were determined on the DI water extract obtained from the 2:1 leaching procedure (2 parts DI water:1 part soil). pH was determined on the 0.01M CaCl2 extract prepared at 2:1 ratio.

Certified By:

Amanjot Bhela

5835 COOPERS AVENUE

MISSISSAUGA, ONTARIO CANADA L4Z 1Y2 TEL (905)712-5100 FAX (905)712-5122 http://www.agatlabs.com



5835 COOPERS AVENUE MISSISSAUGA, ONTARIO CANADA L4Z 1Y2 TEL (905)712-5100 FAX (905)712-5122 http://www.agatlabs.com

## **Quality Assurance**

**CLIENT NAME: EXP SERVICES INC** 

PROJECT: OTT-246046

AGAT WORK ORDER: 18Z331542 **ATTENTION TO: Susan Potyondy** 

SAMPLING SITE:6102 Renaud Road				SAMPLED BY:exp													
				Soi	l Ana	alysis	6										
RPT Date:			DUPLICATE			REFEREN	ICE MA	TERIAL	METHOD	BLANK	SPIKE	MATRIX SPIKE					
PARAMETER	Batch	Sample Id	Dup #1	Dup #2	RPD	Method Blank	Measured	Acceptable Limits		Recovery	Lin	ptable nits	Recover	Lie	ptable nits		
							Value	Lower	Upper	, ,		Upper	,		Upper		
Inorganic Chemistry (Soil)																	
pH, 2:1 CaCl2 Extraction	9195564		7.58	7.54	0.5%	NA	99%	80%	120%								
Chloride (2:1)	9194146		623	584	6.5%	< 2	107%	70%	130%	103%	70%	130%	101%	70%	130%		
Sulphate (2:1)	9194146		34	33	3.0%	< 2	97%	70%	130%	102%	70%	130%	100%	70%	130%		

Comments: NA signifies Not Applicable.

Duplicate Qualifier: As the measured result approaches the RL, the uncertainty associated with the value increases dramatically, thus duplicate acceptance limits apply only where the average of the two duplicates is greater than five times the RL.

Certified By:

Amanjot Bhela



5835 COOPERS AVENUE MISSISSAUGA, ONTARIO CANADA L4Z 1Y2 TEL (905)712-5100 FAX (905)712-5122 http://www.agatlabs.com

## **Method Summary**

**CLIENT NAME: EXP SERVICES INC** 

**SAMPLING SITE:6102 Renaud Road** 

PROJECT: OTT-246046

SAMPLED BY:exp

AGAT WORK ORDER: 18Z331542

**ATTENTION TO: Susan Potyondy** 

			•
PARAMETER	AGAT S.O.P	LITERATURE REFERENCE	ANALYTICAL TECHNIQUE
Soil Analysis			
pH, 2:1 CaCl2 Extraction	INOR-93-6031	MSA part 3 & SM 4500-H+ B	PH METER
Chloride (2:1)	INOR-93-6004	McKeague 4.12 & SM 4110 B	ION CHROMATOGRAPH
Sulphate (2:1)	INOR-93-6004	McKeague 4.12 & SM 4110 B	ION CHROMATOGRAPH
Resistivity (2:1)	INOR-93-6036	McKeague 4.12, SM 2510 B,SSA #5 Part 3	EC METER

Chain of Custody Record					Ories	of Custody Form		5.712	.5100 wet	335 Coope ga, Ontari Fax: 905 bearth.aga	712.6 dlabs	1Y2 5122					настични				54.		e. 12-1
Report Information:	Regulatory Requirements: No Regulatory Requirement								Custody Seal Intact: Yes No Notes:														
Contact: Sussa Address: 100-2650 Queen Office Offic	Regulation 153/04 Sewer Table marcast drue Sanit Ind/Coin Storm Res/Park Storm Agriculture Soil Texture (crock dwe) Coarse Fine MISA			m CCME  Prov. Water Quality Objectives (PWQO)					Turnaround														
Project Information: Project OTT- 2 Site Location: G102 I	renaud	Road			Is this submissi Record of Site Co			Cer	Michael Committee	Guidelir te of An		is		F	*TA	T is e	xclusi	ve of	weeks	ends a		tutory	TAT holidays GAT CPM
AGAT Quote #: Posse note: If quotettan number a not provided, cleant with be betted hish price for analysis.  Invoice Information:  Company: Contact: Address: Email:					Sample Matrix Le B Biota GW Ground Water O Oil P Paint S Soil SD Sediment SW Surface Water	gend	Preid Filtered - Metals, Hg, CW	s and Inorganics	Mate   153 Metals (avc). Hydrotes) or Metals   153 Metals (inc). Hydrotes)	DEC DROC DHE	Full Metals Scan	/Custom Met	DNO, DNO, HVO,		F1.F4		PCBs; C Total C Arodors	achiorine Pesticides	DM&I CIVOCe CIABNS CIBIGIP CIPOSS	Use	chafes	lon: des	who Resistionally
Sample Identification	Date Sampled	Time Sampled	f of Containers		mple Comments/ atrix Special Instructions			Metals	DAIM	2 2 4	Full Me	Regula	Nutrients:	Volatiles:	PHCs F1.	PAHs	PCBsc	Organ	TOLP: DIMBI	Sewer	1 3 Ph	7	N N
BH 1 554 7.5'-9.5' BH 4 553 5'-7'	Ap 18/18													*									,
Samples Relegations By (Port Name and Sign):  Research (Research of the Park State)		0otx Ap 2:	5/12		Surregue Sociolad Sy Schrigters Necknist by Schrigters Necknist by Schrigters Necknist by	Print Name and Steel	700	90	u	Ш	7	Date	Ap	1018	3 Time	h	30			Page		of_	1
Samples Relanges for By (Prett Rome and Sign)	•	Date	100	COL	Samples Received By	Print Name and Sign)			m At						Time Copy - A			14	- 1	0	63	3	79

## **List of Distribution**

#### **Report Distributed To:**

Sael Nemorin - sael@utopiagroup.ca
Chris Lacroix - chris@utopiagroup.ca
Daniel Paquette - paquetteplanning@sympatico.ca
Bruce Thomas - bruce.thomas@exp.com



### SERVICING REPORT - 6102 RENAUD RD, ORLÉANS

Appendix E **Drawings** August 1, 2019

Appendix E **DRAWINGS** 

