



PLANTING MIX TO BE APPROVED BY LANDSCAPE ARCHITECT.
ALL PLANT MATERIAL TO MEET CNLA STANDARDS, AND BE APPROVED BY LANDSCAPE ARCHITECT PRIOR TO PLANTING.
REFER TO CIVIL ENGINEER'S DRAWING FOR ELEVATIONS / GRADING.
ALL WORK TO INCLUDE 1 YEAR WARRANTY FROM DATE OF FINAL ACCEPTANCE.
MAINTAIN ALL AREAS UNTIL FINAL ACCEPTANCE, INCLUDING MOWING OF TURF, WEEDING OF BEDS, WATERING.
PROVIDE WATERING OF ALL PLANT MATERIAL AS REQUIRED FOR PROPER ESTABLISHMENT, UNTIL END OF WARRANTY PERIOD.
The Landscape Plan is to be read in conjunction with the grading and survey plan, underground services engineering drawings, construction details and contract documents and cannot be used for construction until signed by the landscape architect. Bare root material to be planted in season only. All plant material locations to be staked on site by the landscape contractor and checked by the landscape architect prior to planting. All trees to be preserved on or directly adjacent to the site will be protected. Plant material are to be installed a minimum of; 3.0m away from any part of any hydro transformer, 3.0m corridor between a fire hydrant and the curb, a 2.5m radius beside or behind a fire hydrant, 2.0m from any servicing/utility line or structure.




TYPICAL PLANTING BED NTS


During Excavation/Bed Preparation if Extreme Conditions are Encountered (Water, Rock, Gravel...) that Could Effect the Planting, Notify GJALA Immediately.



SHRUB PLANTING NTS




TYPICAL RIVERWASH STONE NTS




CONCRETE WALKWAY
32 MPA C2 c/w LIGHT BROOM FINISH - TOOL EDGE FIRST, THEN WIPE OFF TOOL MARKS WHILE APPLYING BROOM FINISH


GENERAL CONCRETE NOTES:
ALL CONCRETE FINISHES TO BE APPROVED BY GJA LANDSCAPE ARCHITECT.
SAWCUT LAYOUT FOR ALL AREAS TO BE MARKED ON SITE IN RED CHALK, REVIEWED, ADJUSTED AND APPROVED BY GJA LANDSCAPE ARCHITECT PRIOR TO ANY CUTTING.
EXPANSION JOINT LAYOUT FOR ALL AREAS TO BE LAID OUT ON SITE, REVIEWED, ADJUSTED AND APPROVED BY GJA LANDSCAPE ARCHITECT PRIOR TO ANY CONCRETE POURING.
FINISH: LIGHT BROOM - TOOL EDGE FIRST, THEN WIPE OFF TOOL MARKS WHILE APPLYING BROOM FINISH



UNIT PAVING
100 x 200 x 80mm Heritage Pavers or Approved Equal




SOLID WOOD FENCE 7' / 2.13m Ht.
All Wood To Be Local White Cedar



Drawing Remains the Property of Gino J. Aiello Landscape Architect. Copyright Reserved by Gino J. Aiello Landscape Architect. Do Not Use or Reproduce Without Approval of Gino J. Aiello. Do Not Use For Construction Unless Signed By Landscape Architect. Contractor is Responsible for Verification of Site Locations of all Utilities. Report any Discrepancies Between Site and Drawing Immediately to Gino J. Aiello.

- Proposed Planting Bed
- Proposed Riverwash Stone On Filter Cloth
- Proposed Precast Pavers, Colour/Pattern TBD

3	Rezoning Application	April 3 2018
2	For Site Plan Control	December 18 2017
1	For Review / Coordination	December 13 2017
No	Revision	Date
R E V I S I O N S		



Property Owner
Domicile Developments Inc.
371A Richmond Road Ottawa K2A 0E7

Consultant
Gino J. Aiello landscape architect www.gjala.com
gino@gjala.com (613) 852 1343
50 Camelot Drive, Nepean, Ontario K2G 5X8

Project
**Mixed Use Building
Commercial/Residential**
398, 402, 406 Roosevelt Avenue

Drawing
Landscape Plan

Drawn By: GJA
Design By: GJA
Date: December 2017
Scale: 1:125
Sheet Number
L1

Dwg -#####

D07-12-17-0171