

Engineering

- Land / Site Development
- Municipal Infrastructure
- Environmental / Water Resources
- Traffic / Transportation
- Structural
- Recreational

Planning

- Land / Site Development
- Planning Application Management
- Municipal Planning Documents & Studies
- Expert Witness (OMB)
- Wireless Industry

Landscape Architecture

- Urban Design & Streetscapes
- Open Space, Parks & Recreation Planning
- Community & Residential Developments
- Commercial & Institutional Sites
- Environmental Restoration



Proposed Residential Development 593 Laurier Avenue

Development Servicing and Stormwater Management Report

**PROPOSED RESIDENTIAL DEVELOPMENT
593 LAURIER AVENUE**

**DEVELOPMENT SERVICING AND
STORMWATER MANAGEMENT REPORT**

Prepared by:

NOVATECH

Suite 200, 240 Michael Cowpland Drive
Kanata, Ontario
K2M 1P6

December 9, 2019

Ref: R-2019-193
Novatech File No. 119019

December 9, 2019

Alexander Fleck House Inc.
250 Ste Anne Avenue
Ottawa, Ontario
K1L 7C4

Attention: Mr. Denis Michaud

Dear Sir:


**Re: Development Servicing and Stormwater Management Report
Proposed 16-Storey Residential Development
593 Laurier Avenue, Ottawa, ON
Novatech File No.: 119019**

Enclosed is a copy of the 'Development Servicing and Stormwater Management Report' for the proposed 16-storey residential development located at 593 Laurier Avenue, in the City of Ottawa. This report addresses the approach to site servicing and stormwater management and is submitted in support of a site plan control application.

Please contact the undersigned, should you have any questions or require additional information.

Yours truly,

NOVATECH



Miroslav Savic, P. Eng.
Senior Project Manager

cc: Shawn Wessel (City of Ottawa)
Ryan Koolwine (Project1 Studio)

TABLE OF CONTENTS

1.0	INTRODUCTION	1
1.1	Purpose	1
1.2	Site Description and Location	1
1.3	Pre-Consultation Information	1
1.4	Proposed Development.....	2
1.5	Reference Material.....	2
2.0	SITE SERVICING	2
2.1	Sanitary Sewage	2
2.2	Water	4
2.2.1	Domestic Water Demands and Watermain Analysis	4
2.2.2	Water Supply for Fire-Fighting.....	6
2.3	Storm Drainage and Stormwater Management.....	7
2.3.1	Stormwater Management Criteria and Objectives	8
2.3.2	Pre-Development Conditions and Allowable Release Rate	8
2.3.3	Post-Development Conditions	8
2.3.3.1	Area R-1: Controlled Flow - New Building Roof.....	8
2.3.3.2	Area A-1: Uncontrolled Direct Runoff to Laurier Avenue.....	9
2.3.3.3	Area A-2: Uncontrolled Runoff to Slater Street.....	9
2.3.3.4	Area A-3: Controlled Flow - Heritage House Roof and Amenity Areas	9
2.3.3.5	Stormwater Flow Summary	10
3.0	SITE GRADING	10
4.0	GEOTECHNICAL INVESTIGATIONS	11
5.0	EROSION AND SEDIMENT CONTROL	11
6.0	CONCLUSION	11

LIST OF FIGURES

Figure 1 Aerial Plan

LIST OF APPENDICES

Appendix A: Correspondence

Appendix B: Development Servicing Study Checklist

Appendix C: Water Demands, FUS Calculations and City of Ottawa Boundary Conditions

Appendix D: IDF Curves and SWM Calculations

Appendix E: Sanitary and Storm Sewer Design Sheets

Appendix F: Control Flow Roof Drain Information

Appendix G: Inlet Control Device (ICD) Information

LIST OF PLANS

General Plan of Services (119019-GP)

Outlet Sewer Plan and Profile (119019-P1)

Grading and Erosion & Sediment Control Plan (119019-GR)

Stormwater Management Plan (119019-SWM)

1.0 INTRODUCTION

The new 16-storey residential building is being proposed by 11258770 Canada Inc. and Novatech has been retained to complete the site servicing and stormwater management design for this project.

1.1 Purpose

This report addresses the approach to site servicing and stormwater management and is being submitted in support of a site plan control application.

1.2 Site Description and Location

The subject site is approximately 0.123 hectares in size and currently consists of single multi-unit residential building with accessible site access off Laurier Avenue West. The subject site is located on the northwest corner of Laurier Avenue West and Bronson Avenue. Residential lots abut the property to the north and west. The legal description of the subject site is designated as Part of Lot 40, Concession A (Ottawa Front), Geographic Township of Nepean, City of Ottawa.

Figure 1 – Aerial Plan provides an aerial view of the site.



1.3 Pre-Consultation Information

A pre-consultation meeting was held with the City of Ottawa in 2018 at which time the client was advised of the general submission requirements. Subsequent meetings were held with the City on April 26th and on June 26th, 2019. Refer to **Appendix A** for a summary of the correspondence related to the proposed development.

Based on a review of **O. Reg. 525/98: Approval Exemptions**, a Ministry of the Environment, Conservation and Parks (MECP) Environmental Compliance Approval (ECA) is anticipated to be required because the storm flows from this site are ultimately being directed into a combined sewer in Bronson Avenue.

1.4 Proposed Development

The proposed development will consist of a new 16-storey residential building adjoining the existing Heritage House facing Laurier Avenue. The proposed 16-storey residential building will be serviced by extending new laterals to the combined municipal sewer system in Bronson Avenue and to the municipal watermain in Laurier Avenue West. Barrier-free access to the proposed building will be provided off Laurier Avenue West. The Heritage House will be incorporated into the overall design of the site and will be serviced internally by the new building.

1.5 Reference Material

The following reports and studies were prepared and/or reviewed as part of the design process:

¹ The Geotechnical Investigation report (LRL File No.: 190227), prepared by LRL Engineering in June of 2019.

2.0 SITE SERVICING

The objective of the site servicing design is to provide proper sewage outlets, a suitable domestic water supply and to ensure that appropriate fire protection is provided for the proposed development. The servicing criteria, the expected sewage flows, and the water demands are to conform to the City of Ottawa municipal design guidelines for sewer and water distribution systems. Refer to the subsequent sections of the report for further details.

The City of Ottawa Servicing Study Guidelines for Development Applications requires that a Development Servicing Study Checklist be included to confirm that each applicable item is deemed complete and ready for review by City of Ottawa Infrastructure Approvals. A completed checklist is enclosed in **Appendix B** of the report.

2.1 Sanitary Sewage

The existing site does not have any municipal sewers along Laurier Avenue or Bronson Avenue. The sanitary sewage outlet for the existing building is to the north through the 140 Bronson Avenue building outletting to the existing sanitary sewer at the south-west corner of the intersection of Slater Street and Bronson Avenue. As per the pre-condition CCTV investigation, the existing 100mm service lateral is “Transite” pipe in good condition.

The following four options were considered for servicing the proposed development:

- Option 1 - Maintain the existing 100mm lateral if it is determined the slope is sufficient to carry the peak design flow from the proposed site.
- Option 2 - Replace the lateral with the required size generally in the same location as existing lateral within the 140 Bronson building.
- Option 3 - Relocate the lateral outside the 140 Bronson building but within the site.
- Option 4 - Install a new lateral within the Laurier Avenue north boulevard, extend the existing combined sewer within the boulevard and outlet to the Cambridge Avenue sewer.



The Option 3 was chosen through discussions with the City of Ottawa. Therefore, the proposed residential development will be serviced by a new 200mm dia. sanitary sewer that will be routed through the 140 Bronson property and connected to the existing 250mm dia. sanitary sewer at the corner of Slater Street and Bronson Avenue.

The City of Ottawa design criteria were used to calculate the theoretical sanitary flows for the proposed development. The following design criteria were taken from Section 4 – ‘Sanitary Sewer Systems’ and Appendix 4-A - ‘Daily Sewage Flow for Various Types of Establishments’ of the City of Ottawa Sewer Design Guidelines:

Residential and Commercial Uses

- Residential Units (Studio or 1-Bedroom): 1.4 people per unit
- Residential Units (2-Bedroom): 2.1 people per unit
- Average Daily Residential Sewage Flow: 280 L/person/day
- Residential Peaking Factor = 3.6 (Harmon Equation)
- Infiltration Allowance: 0.33 L/s/ha x 0.123 ha site = 0.04 L/s

Table 1 identifies the theoretical sanitary flows for the proposed residential development based on the above design criteria.

Table 1: Theoretical Post-Development Sanitary Flows

Residential Use	Unit Count	Design Population	Average Flow (L/s)	Peaking Factor	Peak Flow (L/s)	Total Flow (L/s)
New Building						
Studio / 1-Bedroom	64	90	0.29	3.6	1.04	1.04
2-Bedroom	20	42	0.14	3.6	0.50	0.50
Heritage House						
1-Bedroom	2	3	0.01	3.6	0.04	0.04
2-Bedroom	3	6	0.02	3.6	0.07	0.07
Infiltration Allowance	-	-	-	-	-	0.04
Total	89	141	0.46	3.6	1.65	1.69

A 200mm dia. sanitary gravity sewer at a minimum slope of 1.0% has a full flow conveyance capacity of 34.2 L/s and will have enough capacity to convey the theoretical sanitary flows for the proposed development. Refer to **Appendix E** for a copy of the sanitary sewer design sheet for the outlet sewer.

2.2 Water

The proposed residential development will be serviced by a new 150mm dia. water service connected to the existing 200mm dia. watermain in Laurier Avenue. The water service has been sized to provide the required domestic water demand and fire flow. A shut-off valve will be provided on the proposed water service. The water meter will be located within the water entry room, with a remote meter on the exterior face of the building.

2.2.1 Domestic Water Demands and Watermain Analysis

The City of Ottawa design criteria were used to calculate the theoretical water demands for the proposed development. The following design criteria were taken from Section 4 – ‘Water Distribution Systems’ of the Ottawa Design Guidelines – Water Distribution:

- Residential Units (Studio or 1 Bedroom): 1.4 people per unit
- Residential Units (2 Bedroom): 2.1 people per unit
- Average Daily Residential Water Demand: 350 L/person/day

- Maximum Day Demand Peaking Factor = 2.5 x Avg. Day Demand
- Peak Hour Demand Peaking Factor = 2.2 x Max. Day Demand

Table 2 identifies the theoretical domestic water demands for the development based on the above design criteria.

Table 2: Theoretical Water Demand for the Proposed Development

Residential Use	Unit Count	Design Population	Average Day Demand (L/s)	Max. Day Demand (L/s)	Peak Hour Demand (L/s)
New Building					
Studio / 1-Bedroom	64	90	0.36	0.90	1.98
2-Bedroom	20	42	0.17	0.43	0.95
Heritage House					
1-Bedroom	2	3	0.01	0.03	0.07
2-Bedroom	3	6	0.02	0.05	0.11
Total	89	141	0.56	1.41	3.11

The following design criteria were taken from Section 4.2.2 – ‘Watermain Pressure and Demand Objectives’ of the City of Ottawa Design Guidelines for Water Distribution:

- Minimum system pressures are not to be less than 276 kPa (40 psi) under Peak Hour demands
- Minimum system pressures are to be 140 kPa (20 psi) under Max Day + Fire Flow demands
- Maximum system pressure is not to exceed 552 kPa (80 psi)

Preliminary domestic water demands, and fire flow requirements were provided to the City of Ottawa. These values were used to generate the municipal watermain network boundary conditions. **Table 2.1** summarizes the watermain boundary conditions and the results of the hydraulic analysis. It is anticipated that a booster pump will be required to increase pressure to the upper floors of the building.

Table 2.2 : Hydraulic Boundary Condition Provided by the City

Municipal Watermain Boundary Condition	Boundary Condition	Water Demand (L/s)	Min/Max Operating Pressure (psi)	Design Pressure (psi)*
Minimum HGL (Peak Hour Demand)	106.8 m	3.11	40 psi (min.)	41.4
Maximum HGL (Avg Day Demand)	115.3 m	0.57	80 psi (max.)	53.5
Max Day + Fire Flow HGL	105 m	150 + 1.41	20 psi (min.)	38.8

*Based on the watermain elevation of 77.7m. Design pressure = (HGL – watermain elevation) x 1.42197 PSI/m

As indicated above, the existing municipal watermain should provide adequate system pressures to the proposed development.

2.2.2 Water Supply for Fire-Fighting

The proposed building will be fully sprinklered and supplied with a fire department (siamese) connection. The siamese connection will be located on the south side of the building, within 45m of the existing municipal fire hydrant on the SW corner of Laurier Ave. West and Bronson Ave.

The Fire Underwriters Survey (FUS) was used to estimate fire flow requirements for the proposed building. Based on information provided by the architect, a 16-storey, sprinklered building, constructed using fire resistive materials was used in the calculations. The existing Heritage House was considered as a four-storey building with wood frame construction and sprinkler system.

Table 2.2 summarizes the fire flow requirements for the proposed building, based on FUS calculations.

Table 2.2: Fire Flow Requirements for the Proposed Development

Type of Uses	Fire Flow Demand USGPM (L/s)
Existing Heritage Building	9,000 L/min (150 L/s)
Proposed Residential Building	3,000 L/min (50 L/s)

Refer to **Appendix C** for a copy of the preliminary FUS fire flow calculations and correspondence from the City of Ottawa.

The fire flow requirements include both sprinkler system and hose allowances in accordance with the OBC and NFPA 13. The sprinkler systems will be designed by the fire protection (sprinkler) contractor as this process involves detailed hydraulic calculations based on building layout, pipe runs, head losses, fire pump requirements, etc. Fire flow requirements calculated using the FUS method tend to generate higher values when compared to flows being calculated using the OBC and NFPA.

A multi-hydrant approach to fire-fighting is anticipated to be required. There are 3 Class AA (blue bonnet) hydrants within 90m of the proposed development (one hydrant on the SW corner of Laurier Avenue West and Bronson Avenue approximately 16m from the proposed building; another near the SW corner of Cambridge Street North and Laurier Avenue West approximately 60m from the proposed building; and a third hydrant across in front of 570 Laurier Avenue the south side of the roadway approximately 86m from the existing Heritage House. Based on *Table 1 Maximum flow to be considered from a given hydrant in Appendix I of Technical Bulletin ISTB-2018-02*, the combined flows from the three hydrants are summarized in **Table 2.3**.

Table 2.3: Combined Hydrant Flow Summary


Fire Hydrants < 75m from Building	Fire Hydrants > 75m < 150m from Building	Combined Fire Flow
2 x 5,700 L/min	1 x 3,800 L/min	15,200 L/min

The combined maximum flow from these hydrants will exceed the Max Day + Fire Flow requirement (9,000 L/min) of the proposed development. The existing municipal watermain network should therefore have adequate fire water supply for the proposed development.

2.3 Storm Drainage and Stormwater Management

There is currently no storm sewer/storm lateral serving the 593 Laurier site. Under existing conditions, surface drainage sheet flows in three directions; overland to Laurier Avenue, overland to Bronson Avenue and overland to the 140 Bronson site. The following two options were considered for servicing the proposed development:

- Option A – Similar to Option 3 for the sanitary lateral, a new storm connection would be constructed outletting to a new storm sewer which would be connected the existing sewer at the north-east corner of the intersection of Slater Street and Bronson Avenue.
- Option B – Similar to Option 4 for the sanitary lateral and new storm lateral would outlet to a new combined sewer extension and eventually to the existing combined sewer within the Laurier Avenue northern boulevard and outlet to Cambridge Avenue.



Through discussions with the City of Ottawa, a modified Option A was chosen with the outlet to the existing 250mm dia. combined sewer at the south-west corner of the intersection of Slater Street and Bronson Avenue, which in turn outlets into an 1800mm dia. combined sewer in Booth Street. The proposed storm drainage and stormwater management design for the site is discussed in the following sections of the report.

2.3.1 Stormwater Management Criteria and Objectives

The stormwater management criteria and objectives for the site are as follows:

- Maximize the use of on-site storage on the building roof to minimize the size of the underground SWM storage pipes.
- Provide best measures to attempt to control the post-development flows from the site to a target 2-year release rate specified by the City of Ottawa. Control post-development flows from the site being developed up to and including the 100-year design event.
- Minimize the impact on the existing combined sewer in Bronson Avenue by reducing the post-development storm flows from the site, when compared to current conditions.
- Provide guidelines to ensure that site preparation and construction is in accordance with the current Best Management Practices for Erosion and Sediment Control.

2.3.2 Pre-Development Conditions and Allowable Release Rate

The uncontrolled pre-development flows from the 0.123 ha site were calculated using the Rational Method to be 17.7 L/s during the 1:5-year design event and 34.6 L/s during the 1:100-year design event. Refer to **Appendix D** for detailed calculations. There are currently no water quantity or water quality control measures being provided on site.

As specified by the City of Ottawa, the target allowable release rate from the site was calculated using the Rational Method, to be approximately 10.5 L/s, based on a 10-minute rainfall intensity, using a 2-year return period (City of Ottawa IDF Curves) and a runoff coefficient of 0.40.

$$\begin{aligned}
 T_c &= 10 \text{ min} & C &= 0.40 \\
 I_{5yr} &= 76.81 \text{ mm/hr} & A &= 0.123 \text{ ha} \\
 \\
 Q_{allow} &= 2.78 \text{ CIA} \\
 &= 2.78 \times 0.40 \times 76.81 \times 0.123 \\
 &= 10.5 \text{ L/s}
 \end{aligned}$$

2.3.3 Post-Development Conditions

The proposed site will be serviced by connecting to the existing 250mm dia. combined sewer at the south-west corner of Slater Street and Bronson Avenue. As part of the stormwater management (SWM) strategy, stormwater runoff from the building roof will be attenuated using control flow roof drains. In addition to this, stormwater runoff from the lower roof terraces and ground level amenity areas will be directing to an oversized stormwater storage pipe system and controlled prior to being discharged into the municipal outlet sewer. Refer to plan 119019-SWM for drainage areas and detail. Refer to **Appendix E** for a copy of the storm sewer design sheet for the outlet sewer.

2.3.3.1 Area R-1: Controlled Flow - New Building Roof

The post-development flow from this sub-catchment area will be attenuated by using five (5) Watts adjustable 'Accutrol' control flow roof drains (model number RD-100-A-ADJ) prior to being directed to the proposed storm service.

Table 3 summarizes the post-development design flows from this sub-catchment area as well as the type of roof drains, the maximum anticipated ponding depths, storage volumes required, and storage volumes provided for both the 5-year and the 100-year design events.

Table 3: Design Flow and Roof Drain Table

Roof Drain ID & Drainage Area (ha)	Number of Roof Drains	Watts Roof Drain Model ID (Weir Opening)	Controlled Flow per Drain (L/s)		Approximate Ponding Depth Above Drains (m)		Storage Volume Required (m ³)		Max. Storage Available (m ³)
			5-Yr	100-Yr	5-Yr	100-Yr	5-Yr	100-Yr	
RD-1 (0.008 ha)	1	RD-100-A-ADJ (1/4 Exposed)	0.79	0.95	0.11	0.15	0.8	2.1	2.2
RD-2 (0.005 ha)	1	RD-100-A-ADJ (1/4 Exposed)	0.79	0.87	0.09	0.13	0.3	1.0	1.3
RD-3 (0.004 ha)	1	RD-100-A-ADJ (1/4 Exposed)	0.71	0.87	0.08	0.13	0.2	0.7	1.2
RD-4 (0.014 ha)	1	RD-100-A-ADJ (1/4 Exposed)	0.79	0.87	0.10	0.14	2.0	4.9	5.1
RD-5 (0.009 ha)	1	RD-100-A-ADJ (Closed)	0.32	0.32	0.10	0.14	1.6	3.9	4.4
Total Roof (0.040 ha)	5	-	3.40	3.88	-	-	4.9	12.6	14.2

Refer to **Appendix D** for detailed SWM calculations and to **Appendix F** for roof drain information. As indicated in the table above, the building roof will provide sufficient storage for both the 5-year and 100-year design events.

2.3.3.2 Area A-1: Uncontrolled Direct Runoff to Laurier Avenue

The uncontrolled post-development flow from this very small sub-catchment area was calculated using the Rational Method to be approximately 0.1 L/s during the 5-year design event and 0.2 L/s during the 100-year design event. Refer to **Appendix D** for SWM calculations.

2.3.3.3 Area A-2: Uncontrolled Runoff to Slater Street

The uncontrolled post-development flow from this very small sub-catchment area was calculated using the Rational Method to be approximately 0.9 L/s during the 5-year design event and 1.7 L/s during the 100-year design event. Refer to **Appendix D** for SWM calculations.

2.3.3.4 Area A-3: Controlled Flow - Heritage House Roof and Amenity Areas

Runoff from sub-catchment A-3 will be captured by the proposed on-site storm sewer system and attenuated by an ICD installed in the outlet pipe of STM MH 5.

Temporary storage is to be provided within the oversized underground storm pipes and manhole structures. The provided underground storage system will attenuate the runoff volumes for all storms up-to and including the 100-year storm event.

Table 3.1 summarizes the post-development design flow from this sub-catchment area as well as the type of ICD, the anticipated ponding elevations, storage volumes required and storage volume provided for the 2-year, 5-year and the 100-year design events.

Table 3.1: Stormwater Flows, ICD & Underground Storage System

Design Event	Controlled Site Flows from Area A-3				
	ICD Type	Design Flow	System Depth	Storage Vol. Required	Max Storage Provided
2-Year	Tempest Vortex LMF (Model 65)	2.5 L/s	0.45 m (76.45 m)	4.0 m ³	21.5 m ³
5-Year		2.6 L/s	0.63 m (76.63 m)	5.3 m ³	
100-Year		4.4 L/s	1.82 m (77.82 m)	10.7 m ³	
100-Year (+20%)		5.0 L/s	2.39 m (78.39 m)	13.3 m ³	

Refer to **Appendix G** for ICD information and to **Appendix D** for detailed SWM calculations.

2.3.3.5 Stormwater Flow Summary

Table 3.2 provides a summary of the total post-development flows from the site and compares them to the uncontrolled pre-development flows and target release rate specified by the City of Ottawa.

Table 3.2: Stormwater Flow Comparison Table

Design Event	Pre-Development Conditions		Post-Development Conditions					
	Uncontrolled Flow (L/s)	Target Release Rate (L/s)	R-1 Flow (L/s)	A-1 Flow (L/s)	A-2 Flow (L/s)	A-3 Flow (L/s)	Total Flow (L/s)	Reduction in Flow (L/s or %)*
5-Yr	17.7	10.5	3.4	0.1	0.9	2.6	7.0	10.7 or 60%
100-Yr	34.6	10.5	3.9	0.2	1.7	4.4	10.2	24.4 or 71%

*Reduced flow compared to uncontrolled pre-development conditions.

As indicated in the table above, both the 5-year and the 100-year post-development flows from the site will be less than the target allowable release rate specified by the City of Ottawa. Although the target release rate of 10.5 L/s is only just achieved during the 100-year event, this still represents significant reductions in total site flow rate when compared to the respective pre-development conditions.

3.0 SITE GRADING

The existing site is relatively flat, with elevations varying from approximately 81.0m near the southwest property corner down to approximately 80.1m near the northeast property corner adjacent to Bronson Avenue. Although the existing site does not slope too steeply, the site is perched above the surrounding properties on the north, east and south sides. The adjacent property to the west is at a similar elevation, while Laurier Avenue West drops to an elevation of approximately 79.0 at the intersection of Bronson Avenue. The grade continues to drop off significantly from south to north along Bronson Avenue. The road elevation at the intersection of Bronson and Slater is approximately 70.4m (nearly 11m below the on-site grades). There is a

significant retaining wall along the east property line to accommodate the grade change along Bronson Avenue. The existing building along the north property line on the adjacent property at 140 Bronson Avenue is bunkered into the escarpment along the shared property line. The western portion of that property has a tiered landscaped area with a stone retaining wall along the shared property line and an additional concrete retaining wall in the middle of the property to accommodate the grade change down to the north.

The finished floor elevation (FFE) of the proposed residential building will be set at an elevation of 82.45m to match into the existing main floor elevation of the Heritage House being preserved on-site. The grades along the north, east and west property lines will be maintained. The grades along the south property line will be lowered slightly to accommodate access off the lower Laurier Avenue West roadway. Refer to the enclosed Grading and Erosion & Sediment Control Plan (119019-GR) for details.

4.0 GEOTECHNICAL INVESTIGATIONS

A Geotechnical Investigation report has been prepared by LRL Engineering for the proposed project. Refer to the Geotechnical Report¹ for subsurface conditions, construction recommendations and geotechnical inspection requirements.

5.0 EROSION AND SEDIMENT CONTROL

To mitigate erosion and to prevent sediment from entering the storm sewer system, temporary erosion and sediment control measures will be implemented on-site during construction in accordance with the Best Management Practices for Erosion and Sediment Control. This includes the following temporary measures:

- Filter bags will be placed under the grates of nearby catchbasins, manholes and will remain in place until vegetation has been established and construction is completed.
- Silt fencing will be placed per OPSS 577 and OPSD 219.110 along the surrounding construction limits.
- A mud mat will be installed at the construction entrance for the site.
- Street sweeping and cleaning will be performed, as required, to suppress dust and to provide safe and clean roadways adjacent to the construction site.
- On-site dewatering is to be directed to a sediment trap and/or gravel splash pad and discharged safely to an approved outlet as directed by the engineer.

The temporary erosion and sediment control measures will be implemented prior to construction and will remain in place during all phases of construction. Regular inspection and maintenance of the erosion control measures will be undertaken.

6.0 CONCLUSION

This report has been prepared in support of a site plan control application for the proposed residential development located at 593 Laurier Avenue.

The conclusions are as follows:

- The proposed 16-storey residential building will be serviced by extending new laterals to the combined municipal sewer system in Bronson Avenue and the municipal watermain in Laurier Avenue West.
- The building will be sprinklered and supplied with a fire department siamese connection. The siamese connection will be located within 45m of the municipal fire hydrant near the south-west corner of the intersection of Laurier Avenue and Bronson Avenue.
- The site flows from sub-catchment area R-1 will be attenuated using control flow roof drains, while flows from area A-2 will be controlled by an ICD and controlled prior to being discharged into the municipal sewer system.
- The total post-development site flow will be approximately 7.0 L/s during the 5-year design event and 10.2 L/s during the 100-year event. Post-development flows will be reduced by approximately 10.7 L/s (or 60%) during the 5-year event and by as much as 24.4 L/s (or 71%) during the 100-year design event, compared to current conditions.
- Regular inspection and maintenance of the building services, roof drains, on-site SWM storage system and the sumps / ICD is recommended to ensure that the storm drainage system is clean and operational.
- Temporary erosion and sediment control measures are to be provided during construction.

It is recommended that the proposed site servicing and stormwater management design be approved for implementation.

NOVATECH

Prepared by:



Stephen Matthews, B.A. (Env.)
Senior Design Technologist

Reviewed by:



Miroslav Savic, P. Eng.
Senior Project Manager

APPENDIX A
Correspondence

Miro Savic

From: McCreight, Andrew <Andrew.McCreight@ottawa.ca>
Sent: Monday, July 8, 2019 10:31 AM
To: Danna SeeHar; Murray Chown
Cc: 'denis@henryinvestments.ca'; 'koolwine@project1studio.ca'; 'rmartin@robertsonmartin.com'; 'Eric Darwin'; POWELL MICHAEL; Wessel, Shawn; Moise, Christopher; Maloney, David; Lee Sheets; Gordon, Mark
Subject: 593 Laurier - 3rd pre-consult - confidential
Attachments: 593 Laurier Ave - 3rd Meeting Minutes.pdf

Hello,

Please find attached the minutes from the 3rd pre-consult meeting held on June 26, 2019. Please let me know if any comments were recorded incorrectly, or if anyone has additional comments.

From a planning perspective, it is important that I reiterate the comment about the current proposal triggering an Official Plan Amendment, as well as the concern relative to high-rise policies /guidelines.

The Department remains very concerned about the proposed height in it's current form. This is challenging site with competing interests between heritage, planning and engineering, but one that must find balance while achieving the review framework of all.

If the addition were to remain low-rise/mid-rise, urban design solutions will be workable. If the addition remains as a high-rise, then the rules of high-rise, such as tower separation, apply and will be instrumental to the Planning Rationale and review of the application(s). Locating height on the property cannot deny abutting property owners the same "right". As noted in the first two meetings, transition remains as a concern, and now with a high-rise in the mix, the setbacks and property relationship cause for further concern. The current proposal requires more analysis to accommodate the idea of a high-rise at this location, and potentially even land acquisition to the west. Otherwise, it is difficult to see how the proposal conforms with the Official Plan.

If anyone has further comments or questions, please do not hesitate to contact me.

Regards,
Andrew

Andrew McCreight MCIP RPP

Planner/Urbaniste

Development Review Central/Examen des demandes d'aménagement secteur centre

PLANNING, INFRASTRUCTURE AND ECONOMIC DEVELOPMENT

SERVICES DE PLANIFICATION, D'INFRASTRUCTURE ET DE DÉVELOPPEMENT ÉCONOMIQUE

110 Laurier Ave West | 4th Floor | Ottawa, ON | K1P 1J1

City of Ottawa | Ville d'Ottawa

☎ 613.580.2424 ext./poste 22568

ottawa.ca/planning / ottawa.ca/urbanisme

VACATION ALERT: I will be away July 19 - Aug 6.

Pre-application Consultation Meeting Minutes

Address: 593 Laurier Ave.

Formal Pre-consultation File No.: PC2019-0069

Date: Wednesday June 26, 2019, 1:30pm – 3:00pm

Location: Room Billings Room, City Hall, 110 Laurier Ave W

City Contact: Andrew McCreight

City of Ottawa Staff Present:

Andrew McCreight – File Lead, Planner, Development Review Central

Christopher Moise – Architect/Urban Designer

David Maloney – Heritage Planner

Shawn Wessel – Infrastructure Project Manager

Mark Gordon – Planning Co-op Student

Invitees Present:

Denis Michaud -Owner (c/o)

Danna Seehar – Planner, Novatech

Murray Chown – Planner, Novatech

Ryan Koolwine – Architect, Studio1

Robert Martin – Roberson Martin Architects

Lee Sheets, Engineer, Novatech

Miro Savic, Engineer, Novatech

Eric Darwin, Dalhousie Community Association

Michael Powell, Dalhousie Community Association

Introductions and Acknowledgements

- Round table introductions

Overview of Proposal (Applicant Team)

- Took feedback from previous meeting and made a big push on heritage. The new proposal has improved the visibility of the heritage building – particularly the turret.
- The previous proposal was an “L” shape, the new proposal is a “hockey stick” shape which gives more buffer to the building.
- Building anything at ground level would obstruct the view of the turret due to grade change. Change in configuration of the addition of results in a smaller floorplate resulting in a taller building.
- This will be an iconic structure on the skyline. Submission will review long views and different perspectives.
- Animated streetscape along the lane and narrow profile along Laurier Street are improvements from previous design and lightens the building mass.
- The skew of the addition opens up the views from Slater Street and other important views.

- Glazed recessed area references the turret. This was brought down from the previous proposal to make the new building subordinate to the heritage structure.
- Precedent – St. Charles Market on Beechwood Street with the “wrap” approach.
- Single-loaded corridor with five units per floor.
- Glazed room near turret could be amenity space but there is already a large amount of space at grade. The ultimate use of the space is TBD.
- The stone retaining wall may need to be demolished – could reuse the stone on foundations.
- Current plans have the front door of the original home serving the entire development.
- No parking garage is planned. Two visitor parking spaces are proposed at grade.
- Preliminary idea is to clad the base of the building in rough stone, then transition to a more polished cladding above.
- The intent is to build as soon as possible. Will start with modifying the existing building once we have taken possession.

Preliminary Comments from the City

Planning Comments (Andrew McCreight)

- Obvious that many of the changes made to the proposal are to do with the heritage, and less about general planning.
- Undecided on the appropriate height due to the complex layering of policy.
- At junction of the General Urban Area, Traditional Mainstreet, Central Area and a variety of accompanying zoning.
- With the General Urban Area designation, the current proposal would trigger an official plan amendment
- Anything beyond the a mid-rise is likely to trigger an OPA.
- Our comfort with the height will come down to the context.
- The new building is as close as 1 metre to the back lot line. What happens when the abutting sites develops? There appears to be no conformity with the high-rise policies / guidelines concerning tower separation, and property compatibility/relationship. This remains a significant concern.
- The taller the proposed buildings goes, the more challenging conversations become. The City is reactionary on height and cannot tell you a height to go to, but the concerns have been flagged to date.
- The façade may need to be quieted so that it doesn’t compete with the detailing on the house.

Heritage (David Maloney)

- There have been lots of good heritage moves with this version, but it is a lot of height.
- The stone wall is a heritage attribute and is protected with the home.
- The height proposed could work with the heritage homes as an urban frame, but we are not sure about supportability from a policy perspective.
- Could look at reducing the wrapping of the building.

- Quieting the expression of the new building would improve its relation to the heritage home.
- The balconies at the front of the new building could be moved or removed.
- We appreciate the additional breathing room provided to the historic home.

Urban Design (Christopher Moise)

- The current proposal has ramp users having to roll up the drive aisle before they can access the wheelchair ramp. The ramp also appears too short for the grade change and is already at 8% slope which is steep.
- Given the challenge of making up the grade change to enter through the door of the old home it may not be possible to make it barrier free. Why not set the new building at a lower height and animate the front of the new building.
- Analysis has focused on the heritage asset – show some further analysis for building height.
- Would rather see a high quality tall building than a mediocre mid-rise building.
- Consider what it would look like if your neighbours build the same thing.
- Walk people through your analyses to show people how you landed on your proposal.

Infrastructure Comments (Shawn Wessel)

- The site poses challenges for both storm and sanitary sewers.
- The current sewer runs through the neighbouring rear building. This will have to be removed.
- All possible new sewer configurations will involve easements across a neighbouring property.
- We suggest that your team firm up the proposal before having a meeting with City staff from various infrastructure departments. We can work together to find a solution for the sewers.
- Please arrange this meeting with Shawn Wessel at x33017 or shawn.wessel@ottawa.ca

Community Association

- We are happy with the view planes that will be protected.
- Could cut into the escarpment and build useable space underground and put fenestrations in the back wall along Bronson. A skylight could also provide light to this space.
- It would be better to have car shares rather than two visitor parking spaces.
- Looking for short layout spot for Ubers, pizza delivery etc. don't want these blocking the road and bike lanes.
- Not sure about the height but it is an odd site.
- Slater Street is going to be realigned – consider how this changes the development potential of parcels along Slater Street.
- The challenge with height is that you end up with a high-rise building intruding onto Laurier Street, which is a low-rise residential streetscape.

Next Steps

- Set up a meeting with City staff to go over infrastructure challenges.
- Discuss Planning Rationale and determine application requirements and next steps.
- It is recommended that the applicant team seek input from the Ward Councillor and neighbouring property owners.

APPENDIX B
Development Servicing Study Checklist

4. Development Servicing Study Checklist

The following section describes the checklist of the required content of servicing studies. It is expected that the proponent will address each one of the following items for the study to be deemed complete and ready for review by City of Ottawa Infrastructure Approvals staff.

The level of required detail in the Servicing Study will increase depending on the type of application. For example, for Official Plan amendments and re-zoning applications, the main issues will be to determine the capacity requirements for the proposed change in land use and confirm this against the existing capacity constraint, and to define the solutions, phasing of works and the financing of works to address the capacity constraint. For subdivisions and site plans, the above will be required with additional detailed information supporting the servicing within the development boundary.

4.1 General Content

- N/A Executive Summary (for larger reports only).
- Date and revision number of the report.
- Location map and plan showing municipal address, boundary, and layout of proposed development.
- Plan showing the site and location of all existing services.
- Development statistics, land use, density, adherence to zoning and official plan, and reference to applicable subwatershed and watershed plans that provide context to which individual developments must adhere.
- Summary of Pre-consultation Meetings with City and other approval agencies.
- N/A Reference and confirm conformance to higher level studies and reports (Master Servicing Studies, Environmental Assessments, Community Design Plans), or in the case where it is not in conformance, the proponent must provide justification and develop a defensible design criteria.
- Statement of objectives and servicing criteria.
- Identification of existing and proposed infrastructure available in the immediate area.
- N/A Identification of Environmentally Significant Areas, watercourses and Municipal Drains potentially impacted by the proposed development (Reference can be made to the Natural Heritage Studies, if available).

- Concept level master grading plan to confirm existing and proposed grades in the development. This is required to confirm the feasibility of proposed stormwater management and drainage, soil removal and fill constraints, and potential impacts to neighbouring properties. This is also required to confirm that the proposed grading will not impede existing major system flow paths.
- N/A Identification of potential impacts of proposed piped services on private services (such as wells and septic fields on adjacent lands) and mitigation required to address potential impacts.
- N/A Proposed phasing of the development, if applicable.
- Reference to geotechnical studies and recommendations concerning servicing.
- All preliminary and formal site plan submissions should have the following information:
- Metric scale
 - North arrow (including construction North)
 - Key plan
 - Name and contact information of applicant and property owner
 - Property limits including bearings and dimensions
 - Existing and proposed structures and parking areas
 - Easements, road widening and rights-of-way
 - Adjacent street names

4.2 Development Servicing Report: Water

- N/A Confirm consistency with Master Servicing Study, if available
- N/A Availability of public infrastructure to service proposed development
- Identification of system constraints
- Identify boundary conditions
- Confirmation of adequate domestic supply and pressure
- Confirmation of adequate fire flow protection and confirmation that fire flow is calculated as per the Fire Underwriter's Survey. Output should show available fire flow at locations throughout the development.
- Provide a check of high pressures. If pressure is found to be high, an assessment is required to confirm the application of pressure reducing valves.
- N/A Definition of phasing constraints. Hydraulic modeling is required to confirm servicing for all defined phases of the project including the ultimate design
- Address reliability requirements such as appropriate location of shut-off valves
- N/A Check on the necessity of a pressure zone boundary modification.

- Reference to water supply analysis to show that major infrastructure is capable of delivering sufficient water for the proposed land use. This includes data that shows that the expected demands under average day, peak hour and fire flow conditions provide water within the required pressure range
- Description of the proposed water distribution network, including locations of proposed connections to the existing system, provisions for necessary looping, and appurtenances (valves, pressure reducing valves, valve chambers, and fire hydrants) including special metering provisions.
- N/A Description of off-site required feeder mains, booster pumping stations, and other water infrastructure that will be ultimately required to service proposed development, including financing, interim facilities, and timing of implementation.
- Confirmation that water demands are calculated based on the City of Ottawa Design Guidelines.
- Provision of a model schematic showing the boundary conditions locations, streets, parcels, and building locations for reference.

4.3 Development Servicing Report: Wastewater

- Summary of proposed design criteria (Note: Wet-weather flow criteria should not deviate from the City of Ottawa Sewer Design Guidelines. Monitored flow data from relatively new infrastructure cannot be used to justify capacity requirements for proposed infrastructure).
- N/A Confirm consistency with Master Servicing Study and/or justifications for deviations.
- Consideration of local conditions that may contribute to extraneous flows that are higher than the recommended flows in the guidelines. This includes groundwater and soil conditions, and age and condition of sewers.
- N/A Description of existing sanitary sewer available for discharge of wastewater from proposed development.
- N/A Verify available capacity in downstream sanitary sewer and/or identification of upgrades necessary to service the proposed development. (Reference can be made to previously completed Master Servicing Study if applicable)
- N/A Calculations related to dry-weather and wet-weather flow rates from the development in standard MOE sanitary sewer design table (Appendix 'C') format.
- Description of proposed sewer network including sewers, pumping stations, and forcemains.

- N/A Discussion of previously identified environmental constraints and impact on servicing (environmental constraints are related to limitations imposed on the development in order to preserve the physical condition of watercourses, vegetation, soil cover, as well as protecting against water quantity and quality).
- N/A Pumping stations: impacts of proposed development on existing pumping stations or requirements for new pumping station to service development.
- N/A Forcemain capacity in terms of operational redundancy, surge pressure and maximum flow velocity.
- N/A Identification and implementation of the emergency overflow from sanitary pumping stations in relation to the hydraulic grade line to protect against basement flooding.
- Special considerations such as contamination, corrosive environment etc.

4.4 Development Servicing Report: Stormwater Checklist

- Description of drainage outlets and downstream constraints including legality of outlets (i.e. municipal drain, right-of-way, watercourse, or private property)
- N/A Analysis of available capacity in existing public infrastructure.
- A drawing showing the subject lands, its surroundings, the receiving watercourse, existing drainage patterns, and proposed drainage pattern.
- Water quantity control objective (e.g. controlling post-development peak flows to pre-development level for storm events ranging from the 2 or 5 year event (dependent on the receiving sewer design) to 100 year return period); if other objectives are being applied, a rationale must be included with reference to hydrologic analyses of the potentially affected subwatersheds, taking into account long-term cumulative effects.
- N/A Water Quality control objective (basic, normal or enhanced level of protection based on the sensitivities of the receiving watercourse) and storage requirements.
- Description of the stormwater management concept with facility locations and descriptions with references and supporting information.
- Set-back from private sewage disposal systems.
- N/A Watercourse and hazard lands setbacks.
- N/A Record of pre-consultation with the Ontario Ministry of Environment and the Conservation Authority that has jurisdiction on the affected watershed.
- N/A Confirm consistency with sub-watershed and Master Servicing Study, if applicable study exists.

- Storage requirements (complete with calculations) and conveyance capacity for minor events (1:5 year return period) and major events (1:100 year return period).
- N/A Identification of watercourses within the proposed development and how watercourses will be protected, or, if necessary, altered by the proposed development with applicable approvals.
- Calculate pre and post development peak flow rates including a description of existing site conditions and proposed impervious areas and drainage catchments in comparison to existing conditions.
- N/A Any proposed diversion of drainage catchment areas from one outlet to another.
- Proposed minor and major systems including locations and sizes of stormwater trunk sewers, and stormwater management facilities.
- N/A If quantity control is not proposed, demonstration that downstream system has adequate capacity for the post-development flows up to and including the 100-year return period storm event.
- N/A Identification of potential impacts to receiving watercourses
- N/A Identification of municipal drains and related approval requirements.
- Descriptions of how the conveyance and storage capacity will be achieved for the development.
- 100 year flood levels and major flow routing to protect proposed development from flooding for establishing minimum building elevations (MBE) and overall grading.
- N/A Inclusion of hydraulic analysis including hydraulic grade line elevations.
- Description of approach to erosion and sediment control during construction for the protection of receiving watercourse or drainage corridors.
- N/A Identification of floodplains – proponent to obtain relevant floodplain information from the appropriate Conservation Authority. The proponent may be required to delineate floodplain elevations to the satisfaction of the Conservation Authority if such information is not available or if information does not match current conditions.
- N/A Identification of fill constraints related to floodplain and geotechnical investigation.

4.5 Approval and Permit Requirements: Checklist

The Servicing Study shall provide a list of applicable permits and regulatory approvals necessary for the proposed development as well as the relevant issues affecting each approval. The approval and permitting shall include but not be limited to the following:

- NOTED Conservation Authority as the designated approval agency for modification of floodplain, potential impact on fish habitat, proposed works in or adjacent to a watercourse, cut/fill permits and Approval under Lakes and Rivers Improvement Act. The Conservation Authority is not the approval authority for the Lakes and Rivers Improvement Act. Where there are Conservation Authority regulations in place, approval under the Lakes and Rivers Improvement Act is not required, except in cases of dams as defined in the Act.
- NOTED Application for Certificate of Approval (CofA) under the Ontario Water Resources Act.
- N/A Changes to Municipal Drains.
- N/A Other permits (National Capital Commission, Parks Canada, Public Works and Government Services Canada, Ministry of Transportation etc.)

4.6 Conclusion Checklist

- Clearly stated conclusions and recommendations
- TBD Comments received from review agencies including the City of Ottawa and information on how the comments were addressed. Final sign-off from the responsible reviewing agency.
- All draft and final reports shall be signed and stamped by a professional Engineer registered in Ontario

APPENDIX C

Water Demands, FUS Calculations and City of Ottawa Boundary Conditions

Miro Savic

From: Wessel, Shawn <shawn.wessel@ottawa.ca>
Sent: Friday, October 11, 2019 2:27 PM
To: Miro Savic
Subject: 593 Laurier Avenue - Boundary Condition
Attachments: 593 Laurier Oct 2019.pdf

Good afternoon Mr. Savic.

Please find boundary conditions, as requested, below and attached:

The following are boundary conditions, HGL, for hydraulic analysis at 593 Laurier (zone 1W) assumed to be connected to the 203mm on Laurier (see attached PDF for location).

Minimum HGL = 106.8m

Maximum HGL = 115.3m

MaxDay + FireFlow (150 L/s) = 105.0m

MaxDay + FireFlow (50 L/s) = 108.0m

These are for current conditions and are based on computer model simulation.

Disclaimer: The boundary condition information is based on current operation of the city water distribution system. The computer model simulation is based on the best information available at the time. The operation of the water distribution system can change on a regular basis, resulting in a variation in boundary conditions. The physical properties of watermains deteriorate over time, as such must be assumed in the absence of actual field test data. The variation in physical watermain properties can therefore alter the results of the computer model simulation.

If you require additional information or clarification, please do not hesitate to contact me anytime.

Thank you

Regards,

Shawn Wessel, A.Sc.T.,rcji
Project Manager - Infrastructure Approvals
Gestionnaire de projet – Approbation des demandes d’infrastructures


Development Review Central Branch | Direction de l’examen des projets d’aménagement, Centrale
Planning, Infrastructure and Economic Development Department | Direction générale de la planification
de l’infrastructure et du développement économique
City of Ottawa | Ville d’Ottawa
110 Laurier Ave. W. | 110, avenue Laurier Ouest, Ottawa ON K1P 1J1
(613) 580 2424 Ext. | Poste 33017
Int. Mail Code | Code de Courrier Interne 01-14
shawn.wessel@ottawa.ca

 Please consider the environment before printing this email

This e-mail originates from the City of Ottawa e-mail system. Any distribution, use or copying of this e-mail or the information it contains by other than the intended recipient(s) is unauthorized. Thank you.

Le présent courriel a été expédié par le système de courriels de la Ville d’Ottawa. Toute distribution, utilisation ou reproduction du courriel ou des renseignements qui s’y trouvent par une personne autre que son destinataire prévu est interdite. Je vous remercie de votre collaboration.

Boundary Condition for 593 Laurier



Legend

Pipe Ownership

Ownership

- Private
- Public

FUS - Fire Flow Calculations

As per 1999 Fire Underwriter's Survey Guidelines



Engineers, Planners & Landscape Architects

Novatech Project #: 119019
 Project Name: 593 Laurier
 Date: 10/4/2019
 Input By: S.Matthews
 Reviewed By: M.Savic

Legend

Input by User

No Information or Input Required

Building Description: 4 Storey Heritage Home
 Wood frame

Step	Input		Value Used	Total Fire Flow (L/min)		
Base Fire Flow						
1	Construction Material		Multiplier			
	Coefficient related to type of construction C	Wood frame	Yes	1.5	1.5	
		Ordinary construction		1		
		Non-combustible construction		0.8		
		Modified Fire resistive construction (2 hrs)		0.6		
Fire resistive construction (> 3 hrs)			0.6			
2	Floor Area					
	A	Building Footprint (m ²)	175.5	702		
		Number of Floors/Storeys	4			
		Area of structure considered (m ²)				
F	Base fire flow without reductions		9,000			
		$F = 220 C (A)^{0.5}$				
Reductions or Surcharges						
3	Occupancy hazard reduction or surcharge		Reduction/Surcharge			
	(1)	Non-combustible		-25%	-15%	
		Limited combustible	Yes	-15%		
		Combustible		0%		
		Free burning		15%		
Rapid burning			25%			
4	Sprinkler Reduction		Reduction			
	(2)	Adequately Designed System (NFPA 13)	Yes	-30%		
		Standard Water Supply	Yes	-10%		
		Fully Supervised System	No	-10%		
Cumulative Total			-40%	-3,060		
5	Exposure Surcharge (cumulative %)		Surcharge			
	(3)	North Side	0 - 3 m	25%	4,208	
		East Side	> 45.1m	0%		
		South Side	30.1- 45 m	5%		
		West Side	0 - 3 m	25%		
Cumulative Total			55%			
Results						
6	(1) + (2) + (3)	Total Required Fire Flow, rounded to nearest 1000L/min		L/min	9,000	
		(2,000 L/min < Fire Flow < 45,000 L/min)		or	L/s	150
				or	USGPM	2,378
7	Storage Volume		Hours	2		
	Required Volume of Fire Flow (m ³)		m ³	1080		

FUS - Fire Flow Calculations

As per 1999 Fire Underwriter's Survey Guidelines



Engineers, Planners & Landscape Architects

Novatech Project #: 119019

Project Name: 593 Laurier

Date: 10/4/2019

Input By: S.Matthews

Reviewed By: M.Savic

Legend

Input by User

No Information or Input Required

Building Description: 16-Storey Residential Tower
Fire Resistive Construction


Step		Choose		Value Used	Total Fire Flow (L/min)
Base Fire Flow					
1	Construction Material		Multiplier		0.6
	C Coefficient related to type of construction	Wood frame		1.5	
		Ordinary construction		1	
		Non-combustible construction		0.8	
		Modified Fire resistive construction (2 hrs)	Yes	0.6	
Fire resistive construction (> 3 hrs)			0.6		
2	Floor Area				3,000
	A	Building Footprint (m ²)	402		
		Number of Floors/Storeys	16		
		Protected Openings (1 hr)	Yes		
		Area of structure considered (m ²)		603	
F	Base fire flow without reductions				
	$F = 220 C (A)^{0.5}$				
Reductions or Surcharges					
3	Occupancy hazard reduction or surcharge		Reduction/Surcharge		2,550
	(1)	Non-combustible		-25%	
		Limited combustible	Yes	-15%	
		Combustible		0%	
		Free burning		15%	
		Rapid burning		25%	
				-15%	
4	Sprinkler Reduction		Reduction		-1,020
	(2)	Adequately Designed System (NFPA 13)	Yes	-30%	
		Standard Water Supply	Yes	-10%	
		Fully Supervised System	No	-10%	
		Cumulative Total	-40%		
5	Exposure Surcharge (cumulative %)		Surcharge		1,913
	(3)	North Side	0 - 3 m		
		East Side	0 - 3 m		
		South Side	20.1 - 30 m		
		West Side	3.1 - 10 m		
		Cumulative Total	75%		
Results					
6	(1) + (2) + (3)	Total Required Fire Flow, rounded to nearest 1000L/min		L/min	3,000
		(2,000 L/min < Fire Flow < 45,000 L/min)	or	L/s	50
			or	USGPM	793
7	Storage Volume	Required Duration of Fire Flow (hours)		Hours	1.25
		Required Volume of Fire Flow (m ³)		m ³	225

APPENDIX D
IDF Curves and SWM Calculations

Ottawa Sewer Design Guidelines

APPENDIX 5-A

OTTAWA INTENSITY DURATION FREQUENCY (IDF) CURVE



Proposed 16-Storey Residential Development 593 Laurier Avenue

Pre - Development										
Description	Area (ha)	$A_{impervious} (ha)$ $C=0.9$	$A_{gravel} (ha)$ $C=0.6$	$A_{pervious} (ha)$ $C=0.2$	Weighted C_{w5}	Weighted C_{w100}	1:5 Year Flow (L/s)	1:100 Year Flow (L/s)	Allowable C_{value}	Allowable Flow
										2 year (L/s)
Total Site Area	0.123	0.052	0.000	0.071	0.50	0.57	17.7	34.6	0.4	10.5

$T_c = 10mins$

Post - Development : Uncontrolled Site								
Area	Description	Area (ha)	$A_{imp} (ha)$ $C=0.9$	$A_{perv} (ha)$ $C=0.2$	C_5	C_{100}	Uncontrolled Flow (L/s)	
							5 year	100 year
A-1	Direct Runoff to Laurier Ave.	0.001	0.000	0.001	0.38	0.44	0.1	0.2
A-2	UnControlled Runoff to Slater St.	0.004	0.003	0.001	0.77	0.86	0.9	1.7
A-3	Controlled Super-Pipe Storage	0.078	0.049	0.029	0.64	0.72	14.5	27.9
R-1	Controlled Flow Roof Drains	0.040	0.040	0.000	0.90	1.00	10.4	19.9

Summed Area Check: 0.123

$T_c = 10mins$ $T_c = 10mins$

Post - Development : Total Flows for Controlled Site + Uncontrolled Runoff						
Area	Description	Flow (L/s)		Storage Required (m ³)		Provided (m ³)
		5 year	100 year	5 year	100 year	
A-1	Direct Runoff to Laurier Ave.	0.1	0.2	-	-	-
A-2	UnControlled Runoff to Slater St.	0.9	1.7	-	-	-
A-3	Controlled Super-Pipe Storage	2.6	4.4	5.3	10.7	21.3
R-1	Controlled Flow Roof Drains	3.4	3.9	4.9	12.6	14.2
Totals :		7.0	10.2	10.2	23.3	35.5

Over Controlled: 3.5 0.3

Proposed 16-Storey Residential Development Novatech Project No. 119019 REQUIRED STORAGE - 1:2 YEAR EVENT Allowable Flow to Slater Street				
OTTAWA IDF CURVE				
Area =	0.123	ha	Qallow =	10.5 L/s
C =	0.40		Vol(max) =	0.0 m ³
Time (min)	Intensity (mm/hr)	Q (L/s)	Qnet (L/s)	Vol (m ³)
5	103.57	14.17	3.66	1.10
10	76.81	10.51	0.00	0.00
15	61.77	8.45	-2.06	-1.85
20	52.03	7.12	-3.39	-4.07
25	45.17	6.18	-4.33	-6.49
30	40.04	5.48	-5.03	-9.05
35	36.06	4.93	-5.57	-11.70
40	32.86	4.50	-6.01	-14.42
45	30.24	4.14	-6.37	-17.20
50	28.04	3.84	-6.67	-20.01
55	26.17	3.58	-6.93	-22.85
60	24.56	3.36	-7.15	-25.73
65	23.15	3.17	-7.34	-28.62
70	21.91	3.00	-7.51	-31.53
75	20.81	2.85	-7.66	-34.46
80	19.83	2.71	-7.79	-37.41
85	18.94	2.59	-7.91	-40.36
90	18.14	2.48	-8.02	-43.33

Proposed 16-Storey Residential Development				
Novatech Project No. 119019				
REQUIRED STORAGE - 1:5 YEAR EVENT				
AREA A-1 Direct Runoff to Laurier Avenue				
OTTAWA IDF CURVE				
Area =	0.001	ha	Qallow =	0.1 L/s
C =	0.38		Vol(max) =	0.0 m ³
Time (min)	Intensity (mm/hr)	Q (L/s)	Qnet (L/s)	Vol (m ³)
5	141.18	0.15	0.04	0.01
10	104.19	0.11	0.00	0.00
15	83.56	0.09	-0.02	-0.02
20	70.25	0.07	-0.04	-0.04
25	60.90	0.06	-0.05	-0.07
30	53.93	0.06	-0.05	-0.09
35	48.52	0.05	-0.06	-0.12
40	44.18	0.05	-0.06	-0.15
45	40.63	0.04	-0.07	-0.18
50	37.65	0.04	-0.07	-0.21
55	35.12	0.04	-0.07	-0.24
60	32.94	0.03	-0.07	-0.27
65	31.04	0.03	-0.08	-0.30
70	29.37	0.03	-0.08	-0.33
75	27.89	0.03	-0.08	-0.36
80	26.56	0.03	-0.08	-0.39
85	25.37	0.03	-0.08	-0.42
90	24.29	0.03	-0.08	-0.45

Proposed 16-Storey Residential Development				
Novatech Project No. 119019				
REQUIRED STORAGE - 1:100 YEAR EVENT				
AREA A-1 Direct Runoff to Laurier Avenue				
OTTAWA IDF CURVE				
Area =	0.001	ha	Qallow =	0.2 L/s
C =	0.44		Vol(max) =	0.0 m ³
Time (min)	Intensity (mm/hr)	Q (L/s)	Qnet (L/s)	Vol (m ³)
5	242.70	0.30	0.08	0.02
10	178.56	0.22	0.00	0.00
15	142.89	0.17	-0.04	-0.04
20	119.95	0.15	-0.07	-0.09
25	103.85	0.13	-0.09	-0.14
30	91.87	0.11	-0.11	-0.19
35	82.58	0.10	-0.12	-0.25
40	75.15	0.09	-0.13	-0.30
45	69.05	0.08	-0.13	-0.36
50	63.95	0.08	-0.14	-0.42
55	59.62	0.07	-0.14	-0.48
60	55.89	0.07	-0.15	-0.54
65	52.65	0.06	-0.15	-0.60
70	49.79	0.06	-0.16	-0.66
75	47.26	0.06	-0.16	-0.72
80	44.99	0.05	-0.16	-0.78
85	42.95	0.05	-0.16	-0.84
90	41.11	0.05	-0.17	-0.90

Proposed 16-Storey Residential Development				
Novatech Project No. 119019				
REQUIRED STORAGE - 1:5 YEAR EVENT				
AREA A-2 Uncontrolled Runoff to Slater Street				
OTTAWA IDF CURVE				
Area =	0.004	ha	Qallow =	0.9 L/s
C =	0.77		Vol(max) =	0.0 m ³
Time (min)	Intensity (mm/hr)	Q (L/s)	Qnet (L/s)	Vol (m ³)
5	141.18	1.20	0.32	0.09
10	104.19	0.89	0.00	0.00
15	83.56	0.71	-0.18	-0.16
20	70.25	0.60	-0.29	-0.35
25	60.90	0.52	-0.37	-0.55
30	53.93	0.46	-0.43	-0.77
35	48.52	0.41	-0.47	-1.00
40	44.18	0.38	-0.51	-1.23
45	40.63	0.35	-0.54	-1.46
50	37.65	0.32	-0.57	-1.70
55	35.12	0.30	-0.59	-1.94
60	32.94	0.28	-0.61	-2.19
65	31.04	0.26	-0.62	-2.43
70	29.37	0.25	-0.64	-2.68
75	27.89	0.24	-0.65	-2.93
80	26.56	0.23	-0.66	-3.18
85	25.37	0.22	-0.67	-3.43
90	24.29	0.21	-0.68	-3.68

Proposed 16-Storey Residential Development				
Novatech Project No. 119019				
REQUIRED STORAGE - 1:100 YEAR EVENT				
AREA A-2 Uncontrolled Runoff to Slater Street				
OTTAWA IDF CURVE				
Area =	0.004	ha	Qallow =	1.7 L/s
C =	0.86		Vol(max) =	0.0 m ³
Time (min)	Intensity (mm/hr)	Q (L/s)	Qnet (L/s)	Vol (m ³)
5	242.70	2.31	0.61	0.18
10	178.56	1.70	0.00	0.00
15	142.89	1.36	-0.34	-0.31
20	119.95	1.14	-0.56	-0.67
25	103.85	0.99	-0.71	-1.07
30	91.87	0.88	-0.83	-1.49
35	82.58	0.79	-0.92	-1.92
40	75.15	0.72	-0.99	-2.37
45	69.05	0.66	-1.04	-2.82
50	63.95	0.61	-1.09	-3.28
55	59.62	0.57	-1.13	-3.74
60	55.89	0.53	-1.17	-4.21
65	52.65	0.50	-1.20	-4.68
70	49.79	0.47	-1.23	-5.16
75	47.26	0.45	-1.25	-5.63
80	44.99	0.43	-1.27	-6.11
85	42.95	0.41	-1.29	-6.59
90	41.11	0.39	-1.31	-7.08

Proposed 16-Storey Residential Development				
Novatech Project No. 119019				
REQUIRED STORAGE - 1:5 YEAR EVENT				
AREA A-3 Controlled Flow-Underground Super-Pipe				
OTTAWA IDF CURVE				
Area =	0.040	ha	Qallow =	2.6 L/s
C =	0.90		Vol(max) =	5.3 m3
Time (min)	Intensity (mm/hr)	Q (L/s)	Qnet (L/s)	Vol (m3)
5	141.18	14.13	11.53	3.46
10	104.19	10.43	7.83	4.70
15	83.56	8.36	5.76	5.19
20	70.25	7.03	4.43	5.32
25	60.90	6.09	3.49	5.24
30	53.93	5.40	2.80	5.03
35	48.52	4.86	2.26	4.74
40	44.18	4.42	1.82	4.37
45	40.63	4.07	1.47	3.96
50	37.65	3.77	1.17	3.50
55	35.12	3.52	0.92	3.02
60	32.94	3.30	0.70	2.51
65	31.04	3.11	0.51	1.98
70	29.37	2.94	0.34	1.43
75	27.89	2.79	0.19	0.86
90	24.29	2.43	-0.17	-0.91
105	21.58	2.16	-0.44	-2.77
120	19.47	1.95	-0.65	-4.69
135	17.76	1.78	-0.82	-6.66
150	16.36	1.64	-0.96	-8.66

Proposed 16-Storey Residential Development				
Novatech Project No. 119019				
REQUIRED STORAGE - 1:100 YEAR EVENT				
AREA A-3 Controlled Flow-Underground Super-Pipe				
OTTAWA IDF CURVE				
Area =	0.040	ha	Qallow =	4.4 L/s
C =	1.00		Vol(max) =	10.7 m3
Time (min)	Intensity (mm/hr)	Q (L/s)	Qnet (L/s)	Vol (m3)
5	242.70	26.99	22.59	6.78
10	178.56	19.86	15.46	9.27
15	142.89	15.89	11.49	10.34
20	119.95	13.34	8.94	10.73
25	103.85	11.55	7.15	10.72
30	91.87	10.22	5.82	10.47
35	82.58	9.18	4.78	10.04
40	75.15	8.36	3.96	9.49
45	69.05	7.68	3.28	8.85
50	63.95	7.11	2.71	8.14
55	59.62	6.63	2.23	7.36
60	55.89	6.22	1.82	6.54
65	52.65	5.85	1.45	5.67
70	49.79	5.54	1.14	4.77
75	47.26	5.25	0.85	3.85
90	41.11	4.57	0.17	0.93
105	36.50	4.06	-0.34	-2.15
120	32.89	3.66	-0.74	-5.34
135	30.00	3.34	-1.06	-8.62
150	27.61	3.07	-1.33	-11.97

Structures	Size (mm)	Area (m²)	T/G	Inv IN	Inv OUT
STM MH 5	1219	1.17	80.55	76.00	75.87
CBMH 1	1219	1.17	80.40	76.02	76.01
CBMH 2	1524	1.82	80.25	76.09	76.03
CBMH 3	1219	0.36	80.05	-	76.10
CBMH 4	1219	0.36	79.90	78.43	78.35
CB 1	600 x 600	0.36	80.25	-	78.55

PI = 3.141592654
 pipe I.D. = 533 (concrete pipe)
 U/G Pipe Volume
 End Area 0.223 (m²)
 Total Length 10.4 (m)
 Pipe Volume 2.3 (m³)

U/G Pipe Size	525mm dia.	525mm dia.	525mm dia.
Pipe Segment	STM MH 5 - CBMH 1	CBMH 1 - CBMH 2	CBMH 2 - CBMH 3
Centre-Centre Length	6.5	7.5	7.1
Inside Structure	1.5	1.7	1.7
U/G Storage Length	5.0	5.8	5.4


Area A-3: Storage Table								Underground Storage	Total Storage		Design Head
Elevation (m)	System Depth (m)	STM MH 5 Volume (m³)	CBMH 1 Volume (m³)	CBMH 2 Volume (m³)	CBMH 3 Volume (m³)	CBMH 4 Volume (m³)	CB 1 Volume (m³)	Total Volume (m³)	Ponding Volume (m³)	Total Volume (m³)	
75.87	0.00	-	-	-	-	-	-	-	-	0	-
76.00	0.13	0.15	-	-	-	-	-	0.15	-	0.2	0.00
76.30	0.43	0.50	0.34	0.49	0.07	-	-	2.57	-	2.6	0.30
76.56	0.69	0.81	0.64	0.97	0.17	-	-	4.90	-	4.9	0.56
77.18	1.31	1.53	1.37	2.10	0.39	-	-	7.70	-	7.7	1.18
77.52	1.65	1.93	1.76	2.72	0.51	-	-	9.24	-	9.2	1.52
78.02	2.15	2.51	2.35	3.63	0.69	-	-	11.50	-	11.5	2.02
78.42	2.55	2.98	2.81	4.36	0.84	0.03	-	13.33	-	13.3	2.42
79.90	4.03	4.70	4.54	7.06	1.37	0.56	0.49	21.04	-	21.0	3.90
79.95	4.08	4.76	4.60	7.15	1.39	-	0.50	21.28	-	21.3	3.95
80.00	4.13	4.82	4.66	7.24	1.40	-	0.52	21.52	-	21.5	4.00

IPEX Tempest LMF ICD - Model 65	
1:100 Yr	
Flow (L/s) =	4.4
Head (m) =	1.82
Elevation (m) =	77.82
Outlet Pipe Dia. (mm) =	254
Volume (m3) =	10.7
1:5 Yr	
Flow (L/s) =	2.6
Head (m) =	0.63
Elevation (m) =	76.63
Outlet Pipe Dia. (mm) =	254
Volume (m3) =	5.3

Maximum Ponding Depth (cm)	
1:100 Yr	-
1:5 Yr	-

Orifice Size - 1:100 yr Flow Check		
Q=0.62xAx(2gh) ^{0.5}		
1:100 yr	Flow Check	
Q (m³/s) =	0.0044	0.0044
g (m/s²) =	9.81	9.81
h (m) =	1.82	1.82
A (m²) =	0.001186638	0.00119
D (m) =	0.038869964	0.03900
D (mm) =	39	39.0

1:5 yr Flow Check	
1:5 yr	
Q (m³/s) =	0.0026
g (m/s²) =	9.81
h (m) =	0.63
A (m²) =	0.00119
D (m) =	0.039
D (mm) =	39




Proposed 16-Storey Residential Development				
Novatech Project No. 119019				
REQUIRED STORAGE - 1:100 YR + 20% IDF Increase				
AREA A-3 Controlled Flow-Underground Super-Pipe				
OTTAWA IDF CURVE				
Area =	0.040	ha	Qallow =	5.0 L/s
C =	1.00		Vol(max) =	13.3 m3
Time (min)	Intensity (mm/hr)	Q (L/s)	Qnet (L/s)	Vol (m3)
5	291.24	32.39	27.39	8.22
10	214.27	23.83	18.83	11.30
15	171.47	19.07	14.07	12.66
20	143.94	16.01	11.01	13.21
25	124.62	13.86	8.86	13.29
30	110.24	12.26	7.26	13.07
35	99.09	11.02	6.02	12.64
40	90.17	10.03	5.03	12.07
45	82.86	9.21	4.21	11.38
50	76.74	8.53	3.53	10.60
55	71.55	7.96	2.96	9.76
60	67.07	7.46	2.46	8.85
65	63.18	7.03	2.03	7.90
70	59.75	6.64	1.64	6.90
75	56.71	6.31	1.31	5.88
90	49.33	5.49	0.49	2.62
105	43.80	4.87	-0.13	-0.82
120	39.47	4.39	-0.61	-4.40
135	36.00	4.00	-1.00	-8.08
150	33.13	3.68	-1.32	-11.84

Proposed 16-Storey Residential Development				
Novatech Project No. 119019				
REQUIRED STORAGE - 1:5 YEAR EVENT				
AREA R-1 Controlled Roof Drain #1				
OTTAWA IDF CURVE				
Area =	0.008	ha	Qallow =	0.79 L/s
C =	0.90		Vol(max) =	0.8 m3
Time (min)	Intensity (mm/hr)	Q (L/s)	Qnet (L/s)	Vol (m3)
5	141.18	2.83	2.04	0.61
10	104.19	2.09	1.30	0.78
15	83.56	1.67	0.88	0.79
20	70.25	1.41	0.62	0.74
25	60.90	1.22	0.43	0.64
30	53.93	1.08	0.29	0.52
35	48.52	0.97	0.18	0.38
40	44.18	0.88	0.09	0.23
45	40.63	0.81	0.02	0.06
50	37.65	0.75	-0.04	-0.11
55	35.12	0.70	-0.09	-0.29
60	32.94	0.66	-0.13	-0.47
65	31.04	0.62	-0.17	-0.66
70	29.37	0.59	-0.20	-0.85
75	27.89	0.56	-0.23	-1.04
90	24.29	0.49	-0.30	-1.64
105	21.58	0.43	-0.36	-2.26
120	19.47	0.39	-0.40	-2.88

Watts Accutrol Flow Control Roof Drains: RD-100-A-ADJ set to 1/4 Exposed					
Design Event	Flow/Drain (L/s)	Total Flow (L/s)	Ponding (cm)	Storage (m ³)	
				Required	Provided
1:5 Year	0.79	0.79	11	0.8	2.2
1:100 Year	0.95	0.95	15	2.1	2.2

Roof Drain Storage Table for Area RD 1		
Elevation	Area RD 1	Total Volume
m	m ²	m ³
0.00	0	0
0.05	4.76	0.1
0.10	19.03	0.7
0.15	42.38	2.2

Stage Storage Curve: Area R-1
Controlled Roof Drain #1




Proposed 16-Storey Residential Development				
Novatech Project No. 119019				
REQUIRED STORAGE - 1:100 YEAR EVENT				
AREA R-1 Controlled Roof Drain #1				
OTTAWA IDF CURVE				
Area =	0.008	ha	Qallow =	0.95 L/s
C =	1.00		Vol(max) =	2.1 m3
Time (min)	Intensity (mm/hr)	Q (L/s)	Qnet (L/s)	Vol (m3)
5	242.70	5.40	4.45	1.33
10	178.56	3.97	3.02	1.81
15	142.89	3.18	2.23	2.01
20	119.95	2.67	1.72	2.06
25	103.85	2.31	1.36	2.04
30	91.87	2.04	1.09	1.97
35	82.58	1.84	0.89	1.86
40	75.15	1.67	0.72	1.73
45	69.05	1.54	0.59	1.58
50	63.95	1.42	0.47	1.42
55	59.62	1.33	0.38	1.24
60	55.89	1.24	0.29	1.06
65	52.65	1.17	0.22	0.86
70	49.79	1.11	0.16	0.66
75	47.26	1.05	0.10	0.45
90	41.11	0.91	-0.04	-0.19
105	36.50	0.81	-0.14	-0.87
120	32.89	0.73	-0.22	-1.57

Proposed 16-Storey Residential Development				
Novatech Project No. 119019				
REQUIRED STORAGE - 1:5 YEAR EVENT				
AREA R-1		Controlled Roof Drain #2		
OTTAWA IDF CURVE				
Area =	0.005	ha	Qallow =	0.79 L/s
C =	0.90		Vol(max) =	0.3 m3
Time (min)	Intensity (mm/hr)	Q (L/s)	Qnet (L/s)	Vol (m3)
5	141.18	1.77	0.98	0.29
10	104.19	1.30	0.51	0.31
15	83.56	1.05	0.26	0.23
20	70.25	0.88	0.09	0.11
25	60.90	0.76	-0.03	-0.04
30	53.93	0.67	-0.12	-0.21
35	48.52	0.61	-0.18	-0.38
40	44.18	0.55	-0.24	-0.57
45	40.63	0.51	-0.28	-0.76
50	37.65	0.47	-0.32	-0.96
55	35.12	0.44	-0.35	-1.16
60	32.94	0.41	-0.38	-1.36
65	31.04	0.39	-0.40	-1.57
70	29.37	0.37	-0.42	-1.77
75	27.89	0.35	-0.44	-1.99
90	24.29	0.30	-0.49	-2.63
105	21.58	0.27	-0.52	-3.28
120	19.47	0.24	-0.55	-3.93

Watts Accutrol Flow Control Roof Drains: RD-100-A-ADJ set to 1/4 Exposed					
Design Event	Flow/Drain (L/s)	Total Flow (L/s)	Ponding (cm)	Storage (m ³)	
				Required	Provided
1:5 Year	0.79	0.79	9	0.3	1.3
1:100 Year	0.87	0.87	13	1.0	1.3

Roof Drain Storage Table for Area RD 2		
Elevation	Area RD 2	Total Volume
m	m ²	m ³
0.00	0	0
0.05	2.51	0.1
0.10	10.05	0.4
0.15	25.99	1.3

Stage Storage Curve: Area R-1
Controlled Roof Drain #2




Proposed 16-Storey Residential Development				
Novatech Project No. 119019				
REQUIRED STORAGE - 1:100 YEAR EVENT				
AREA R-1		Controlled Roof Drain #2		
OTTAWA IDF CURVE				
Area =	0.005	ha	Qallow =	0.87 L/s
C =	1.00		Vol(max) =	1.0 m3
Time (min)	Intensity (mm/hr)	Q (L/s)	Qnet (L/s)	Vol (m3)
5	242.70	3.37	2.50	0.75
10	178.56	2.48	1.61	0.97
15	142.89	1.99	1.12	1.00
20	119.95	1.67	0.80	0.96
25	103.85	1.44	0.57	0.86
30	91.87	1.28	0.41	0.73
35	82.58	1.15	0.28	0.58
40	75.15	1.04	0.17	0.42
45	69.05	0.96	0.09	0.24
50	63.95	0.89	0.02	0.06
55	59.62	0.83	-0.04	-0.14
60	55.89	0.78	-0.09	-0.34
65	52.65	0.73	-0.14	-0.54
70	49.79	0.69	-0.18	-0.75
75	47.26	0.66	-0.21	-0.96
90	41.11	0.57	-0.30	-1.61
105	36.50	0.51	-0.36	-2.28
120	32.89	0.46	-0.41	-2.97

Proposed 16-Storey Residential Development				
Novatech Project No. 119019				
REQUIRED STORAGE - 1:5 YEAR EVENT				
AREA R-1		Controlled Roof Drain #3		
OTTAWA IDF CURVE				
Area =	0.004	ha	Qallow =	0.71 L/s
C =	0.90		Vol(max) =	0.2 m3
Time (min)	Intensity (mm/hr)	Q (L/s)	Qnet (L/s)	Vol (m3)
5	141.18	1.41	0.70	0.21
10	104.19	1.04	0.33	0.20
15	83.56	0.84	0.13	0.11
20	70.25	0.70	-0.01	-0.01
25	60.90	0.61	-0.10	-0.15
30	53.93	0.54	-0.17	-0.31
35	48.52	0.49	-0.22	-0.47
40	44.18	0.44	-0.27	-0.64
45	40.63	0.41	-0.30	-0.82
50	37.65	0.38	-0.33	-1.00
55	35.12	0.35	-0.36	-1.18
60	32.94	0.33	-0.38	-1.37
65	31.04	0.31	-0.40	-1.56
70	29.37	0.29	-0.42	-1.75
75	27.89	0.28	-0.43	-1.94
90	24.29	0.24	-0.47	-2.52
105	21.58	0.22	-0.49	-3.11
120	19.47	0.19	-0.52	-3.71

Watts Accutrol Flow Control Roof Drains: RD-100-A-ADJ set to 1/4 Exposed					
Design Event	Flow/Drain (L/s)	Total Flow (L/s)	Ponding (cm)	Storage (m ³)	
				Required	Provided
1:5 Year	0.71	0.71	8	0.2	1.2
1:100 Year	0.87	0.87	13	0.7	1.2

Roof Drain Storage Table for Area RD 3		
Elevation	Area RD 3	Total Volume
m	m ²	m ³
0.00	0	0
0.05	1.92	0.0
0.10	9.68	0.3
0.15	23.6	1.2

Stage Storage Curve: Area R-1
Controlled Roof Drain #3




Proposed 16-Storey Residential Development				
Novatech Project No. 119019				
REQUIRED STORAGE - 1:100 YEAR EVENT				
AREA R-1		Controlled Roof Drain #3		
OTTAWA IDF CURVE				
Area =	0.004	ha	Qallow =	0.87 L/s
C =	1.00		Vol(max) =	0.7 m3
Time (min)	Intensity (mm/hr)	Q (L/s)	Qnet (L/s)	Vol (m3)
5	242.70	2.70	1.83	0.55
10	178.56	1.99	1.12	0.67
15	142.89	1.59	0.72	0.65
20	119.95	1.33	0.46	0.56
25	103.85	1.15	0.28	0.43
30	91.87	1.02	0.15	0.27
35	82.58	0.92	0.05	0.10
40	75.15	0.84	-0.03	-0.08
45	69.05	0.77	-0.10	-0.28
50	63.95	0.71	-0.16	-0.48
55	59.62	0.66	-0.21	-0.68
60	55.89	0.62	-0.25	-0.89
65	52.65	0.59	-0.28	-1.11
70	49.79	0.55	-0.32	-1.33
75	47.26	0.53	-0.34	-1.55
90	41.11	0.46	-0.41	-2.23
105	36.50	0.41	-0.46	-2.92
120	32.89	0.37	-0.50	-3.63

Proposed 16-Storey Residential Development				
Novatech Project No. 119019				
REQUIRED STORAGE - 1:5 YEAR EVENT				
AREA R-1		Controlled Roof Drain #4		
OTTAWA IDF CURVE				
Area =	0.014	ha	Qallow =	0.79 L/s
C =	0.90		Vol(max) =	2.0 m3
Time (min)	Intensity (mm/hr)	Q (L/s)	Qnet (L/s)	Vol (m3)
5	141.18	4.95	4.16	1.25
10	104.19	3.65	2.86	1.72
15	83.56	2.93	2.14	1.92
20	70.25	2.46	1.67	2.00
25	60.90	2.13	1.34	2.01
30	53.93	1.89	1.10	1.98
35	48.52	1.70	0.91	1.91
40	44.18	1.55	0.76	1.82
45	40.63	1.42	0.63	1.71
50	37.65	1.32	0.53	1.59
55	35.12	1.23	0.44	1.45
60	32.94	1.15	0.36	1.31
65	31.04	1.09	0.30	1.16
70	29.37	1.03	0.24	1.00
75	27.89	0.98	0.19	0.84
90	24.29	0.85	0.06	0.33
105	21.58	0.76	-0.03	-0.21
120	19.47	0.68	-0.11	-0.78

Watts Accutrol Flow Control Roof Drains: RD-100-A-ADJ set to 1/4 Exposed					
Design Event	Flow/Drain (L/s)	Total Flow (L/s)	Ponding (cm)	Storage (m ³)	
				Required	Provided
1:5 Year	0.79	0.79	10	2.0	5.1
1:100 Year	0.87	0.87	14	4.9	5.1

Roof Drain Storage Table for Area RD 4		
Elevation	Area RD 4	Total Volume
m	m ²	m ³
0.00	0	0
0.05	10.81	0.3
0.10	43.21	1.6
0.15	94.46	5.1

Stage Storage Curve: Area R-1
Controlled Roof Drain #4




Proposed 16-Storey Residential Development				
Novatech Project No. 119019				
REQUIRED STORAGE - 1:100 YEAR EVENT				
AREA R-1		Controlled Roof Drain #4		
OTTAWA IDF CURVE				
Area =	0.014	ha	Qallow =	0.87 L/s
C =	1.00		Vol(max) =	4.9 m3
Time (min)	Intensity (mm/hr)	Q (L/s)	Qnet (L/s)	Vol (m3)
5	242.70	9.45	8.58	2.57
10	178.56	6.95	6.08	3.65
15	142.89	5.56	4.69	4.22
20	119.95	4.67	3.80	4.56
25	103.85	4.04	3.17	4.76
30	91.87	3.58	2.71	4.87
35	82.58	3.21	2.34	4.92
40	75.15	2.92	2.05	4.93
45	69.05	2.69	1.82	4.91
50	63.95	2.49	1.62	4.86
55	59.62	2.32	1.45	4.79
60	55.89	2.18	1.31	4.70
65	52.65	2.05	1.18	4.60
70	49.79	1.94	1.07	4.48
75	47.26	1.84	0.97	4.36
90	41.11	1.60	0.73	3.94
105	36.50	1.42	0.55	3.47
120	32.89	1.28	0.41	2.95

Proposed 16-Storey Residential Development					
Novatech Project No. 119019					
REQUIRED STORAGE - 1:5 YEAR EVENT					
AREA R-1		Controlled Roof Drain #5			
OTTAWA IDF CURVE					
Area =	0.009	ha	Qallow =	0.32	L/s
C =	0.90		Vol(max) =	1.6	m3
Time (min)	Intensity (mm/hr)	Q (L/s)	Qnet (L/s)	Vol (m3)	
5	141.18	3.18	2.86	0.86	
10	104.19	2.35	2.03	1.22	
15	83.56	1.88	1.56	1.41	
20	70.25	1.58	1.26	1.51	
25	60.90	1.37	1.05	1.58	
30	53.93	1.21	0.89	1.61	
35	48.52	1.09	0.77	1.62	
40	44.18	0.99	0.67	1.62	
45	40.63	0.91	0.59	1.61	
50	37.65	0.85	0.53	1.58	
55	35.12	0.79	0.47	1.55	
60	32.94	0.74	0.42	1.52	
65	31.04	0.70	0.38	1.48	
70	29.37	0.66	0.34	1.43	
75	27.89	0.63	0.31	1.39	
90	24.29	0.55	0.23	1.23	
105	21.58	0.49	0.17	1.05	
120	19.47	0.44	0.12	0.85	

Watts Accutrol Flow Control Roof Drains:			RD-100-A-ADJ set to Closed		
Design Event	Flow/Drain (L/s)	Total Flow (L/s)	Ponding (cm)	Storage Required (m ³)	Storage Provided (m ³)
1:5 Year	0.32	0.32	10	1.6	4.4
1:100 Year	0.32	0.32	14	3.9	4.4

Roof Drain Storage Table for Area RD 5		
Elevation	Area RD 5	Total Volume
m	m ²	m ³
0.00	0	0
0.05	9.2	0.2
0.10	36.8	1.4
0.15	83.41	4.4

Stage Storage Curve: Area R-1
Controlled Roof Drain #5



Proposed 16-Storey Residential Development					
Novatech Project No. 119019					
REQUIRED STORAGE - 1:100 YEAR EVENT					
AREA R-1		Controlled Roof Drain #5			
OTTAWA IDF CURVE					
Area =	0.009	ha	Qallow =	0.32	L/s
C =	1.00		Vol(max) =	3.9	m3
Time (min)	Intensity (mm/hr)	Q (L/s)	Qnet (L/s)	Vol (m3)	
5	242.70	6.07	5.75	1.73	
10	178.56	4.47	4.15	2.49	
15	142.89	3.58	3.26	2.93	
20	119.95	3.00	2.68	3.22	
25	103.85	2.60	2.28	3.42	
30	91.87	2.30	1.98	3.56	
35	82.58	2.07	1.75	3.67	
40	75.15	1.88	1.56	3.74	
45	69.05	1.73	1.41	3.80	
50	63.95	1.60	1.28	3.84	
55	59.62	1.49	1.17	3.87	
60	55.89	1.40	1.08	3.88	
65	52.65	1.32	1.00	3.89	
70	49.79	1.25	0.93	3.89	
75	47.26	1.18	0.86	3.88	
90	41.11	1.03	0.71	3.83	
105	36.50	0.91	0.59	3.74	
120	32.89	0.82	0.50	3.62	

APPENDIX E

Sanitary and Storm Sewer Design Sheets

593 Laurier Avenue - Residential Development Sanitary Sewer Design Sheet



PROJECT : 119019
 DESIGNED BY: SM
 CHECKED BY: MS
 DATE: November 8, 2019

Location			Residential		Commercial / Institutional		Residential Cumulative		Peak Factor		Residential	Infiltration		PEAK DESIGN FLOW (l/s)	Pipe Data					
Street / Area	From	To	Population	Area (ha)	Area (ha)	Accu. Area (ha)	Pop.	Area (ha)	Res Peak Factor	Comm Peak Factor	Acc. Peak Flow (l/s)	Infil. Flow (l/s)	Accu Infil. Flow		Size (mm)	Slope (%)	Length (m)	Capacity (l/s)	Full Flow Vel. (m/s)	Q/Q _{full} (%)
593 Laurier Avenue	BLDG	SAN MH 4	141.0	0.123	0.00	0.00	141.0	0.12	3.6	1.5	1.63	0.04	0.04	1.67	200	6.0	8.2	80.3	2.56	2.1%
140 Bronson Avenue	SAN MH 4	SAN MH 3	0.0	0.00	0.00	0.00	141.0	0.12	3.6	1.5	1.63	0.00	0.04	1.67	200	2.6	15.1	52.8	1.68	3.2%
140 Bronson Avenue	SAN MH 3	SAN MH 2	0.0	0.00	0.00	0.00	141.0	0.12	3.6	1.5	1.63	0.00	0.04	1.67	200	1.0	15.9	32.8	1.04	5.1%
140 Bronson Avenue	SAN MH 2	SAN MH 1	0.0	0.00	0.00	0.00	141.0	0.12	3.6	1.5	1.63	0.00	0.04	1.67	200	1.0	28.1	32.8	1.04	5.1%
140 Bronson Avenue	SAN MH 1	EX.COMB	25.2	0.134	0.00	0.00	166.2	0.26	3.5	1.5	1.91	0.04	0.08	1.99	250	1.0	5.9	59.4	1.21	3.4%

City of Ottawa Sewer Design Guidelines

Apartment Units - Studio / 1-Bedroom	1.4	persons/unit
Average Apartment Unit	1.8	persons/unit
Apartment Units - 2-Bedroom	2.1	persons/unit
Single Family Lot	3.4	persons/unit
Average Townhome or Semi-Detached Unit	2.7	persons/unit
Average Domestic Flow	280	L/person/day
Institutional / Commercial Flow	50000	L/ha/day
Extraneous Flows	0.33	L/s/ha
Foundation Drain Allowance	5.0	L/s/ha (use 5.0 L/s/ha for tributary areas < 10 ha; 3.0 L/s/ha for tributary areas >10 ha < 100 ha; 2.0 L/s/ha for tributary areas >100 ha)
Residential Peaking Factor	Harmon Equation, Correction Factor = 0.8	
Institutional / Commercial Peaking Factor	1.5	

Note: The Average apt./persons per unit value of 1.8 was used when determining the apartment population for the 140 Bronson Avenue property.

593 Laurier Avenue - Residential Development 1:5 Year Storm Sewer Design Sheet

PROJECT : 119019
 DESIGNED BY: SM
 CHECKED BY: MS
 DATE: November 8, 2019



AREA	FROM MH	TO MH	AREA (ha)			INDIV 2.78 AC	ACCUM 2.78 AC	TIME OF CONC. (min)	RAINFALL INTENSITY (mm/hr)	CONTROLLED FLOW* Q (L/s)	PEAK FLOW Q (L/s)	PROPOSED SEWER										
			C =	C =	C =							TYPE OF PIPE	PIPE SIZE (mm)	PIPE ID (mm)	GRADE (%)	LENGTH (m)	CAPACITY (L/s)	FULL FLOW VELOCITY (m/s)	TIME OF FLOW (min)	PERCENTAGE OF CAPACITY		
			0.20	0.60	0.90																	
A-3 Controlled	CB 1	CBMH 4	0.004		0.009	0.02	0.02	10.00	104.19		2.6	PVC	200	203.2	1.00	11.4	34.2	1.06	0.18	8%		
A-3 Controlled	CBMH 4	STM MH 5	0.002		0.016	0.04	0.07	10.18	103.25		6.8	PVC	250	254.0	1.00	26.6	62.0	1.22	0.36	11%		
								10.54														
A-3 Controlled	CBMH 3	CBMH 2	0.012		0.008	0.03	0.03	10.00	104.19		2.8	CONC	525	533.4	0.20	9.7	200.6	0.90	0.18	1%		
A-3 Controlled	CBMH 2	CBMH 1	0.004		0.006	0.02	0.04	10.18	103.25		4.5	CONC	525	533.4	0.20	7.8	200.6	0.90	0.14	2%		
A-3 Controlled	CBMH 1	STM MH 5	0.006		0.006	0.02	0.06	10.32	102.51		6.4	CONC	525	533.4	0.20	5.6	200.6	0.90	0.10	3%		
								10.43														
Controlled Flow From A-3			A-3 is controlled to 2.6 L/s by an Ipxex Tempest LMF ICD in the outlet pipe of STM MH 5									2.6	2.6	PVC	250	254.0	6.00	21.1	152.0	3.00	0.12	2%
A-2 Un-Controlled	AD 1	Service Tee			0.027	0.07	0.07	10.00	104.19		7.0	PVC	250	254.0	1.00	26.6	62.0	1.22	0.36	11%		
								10.36														
Controlled Flow From R-1			R-1 (0.040 ha) is controlled to 3.4 L/s by Five (5) Watts Accutrol Control Flow Roof Drains									3.4	3.4	PVC	200	203.2	1.00	21.1	34.2	1.06	0.33	10%
593 Laurier Avenue Site	STM MH 5	STM MH 4						10.54	101.41		13.0	PVC	250	254.0	6.00	21.1	152.0	3.00	0.12	9%		
								10.66														
140 Bronson Avenue Site	STM MH 4	STM MH 3						10.66	100.83		13.0	PVC	250	254.0	3.00	15.7	107.5	2.12	0.12	12%		
140 Bronson Avenue Site	STM MH 3	STM MH 2						10.78	100.23		13.0	PVC	250	254.0	1.00	19.0	62.0	1.22	0.26	21%		
140 Bronson Avenue Site	STM MH 2	STM MH 1						11.04	99.00		13.0	PVC	250	254.0	1.00	22.6	62.0	1.22	0.31	21%		
140 Bronson Avenue Site	STM MH 1	SAN MH 1						11.35	97.57		13.0	PVC	250	254.0	1.00	4.5	62.0	1.22	0.06	21%		
								11.41														

NOTES:

- 1) Refer to Novatech DSS & SWM Report (R-2019-193) for storm drainage and stormwater details
- 2) Refer to Novatech Drawings 119019-GP and 119019-P1 for the storm structure designations, storm pipe details and control structure tables.

APPENDIX F

Control Flow Rood Drain Information



Adjustable Accutrol Weir
 Tag: RD-100-A-ADJ

**Adjustable Flow Control
 for Roof Drains**



ADJUSTABLE ACCUTROL (for Large Sump Roof Drains only)

For more flexibility in controlling flow with heads deeper than 2", Watts Drainage offers the Adjustable Accutrol. The Adjustable Accutrol Weir is designed with a single parabolic opening that can be covered to restrict flow above 2" of head to less than 5 gpm per inch, up to 6" of head. To adjust the flow rate for depths over 2" of head, set the slot in the adjustable upper cone according to the flow rate required. Refer to Table 1 below.
 Note: Flow rates are directly proportional to the amount of weir opening that is exposed.

EXAMPLE:

For example, if the adjustable upper cone is set to cover 1/2 of the weir opening, flow rates above 2" of head will be restricted to 2-1/2 gpm per inch of head.

Therefore, at 3" of head, the flow rate through the Accutrol Weir that has 1/2 the slot exposed will be:
 [5 gpm (per inch of head) x 2 inches of head] + 2-1/2 gpm (for the third inch of head) = 12-1/2 gpm.



1/2 Weir Opening Exposed Shown Above

TABLE 1. Adjustable Accutrol Flow Rate Settings

Weir Opening Exposed	1"	2"	3"	4"	5"	6"
	Flow Rate (gallons per minute)					
Fully Exposed	5	10	15	20	25	30
3/4	5	10	13.75	17.5	21.25	25
1/2	5	10	12.5	15	17.5	20
1/4	5	10	11.25	12.5	13.75	15
Closed	5	5	5	5	5	5

Job Name _____
 Job Location _____
 Engineer _____

Contractor _____
 Contractor's P.O. No. _____
 Representative _____

Watts product specifications in U.S. customary units and metric are approximate and are provided for reference only. For precise measurements, please contact Watts Technical Service. Watts reserves the right to change or modify product design, construction, specifications, or materials without prior notice and without incurring any obligation to make such changes and modifications on Watts products previously or subsequently sold.

USA: Tel: (800) 338-2581 • Fax: (828) 248-3929 • Watts.com
Canada: Tel: (905) 332-4090 • Fax: (905) 332-7068 • Watts.ca
Latin America: Tel: (52) 81-1001-8600 • Fax: (52) 81-8000-7091 • Watts.com



A Watts Water Technologies Company

APPENDIX G

Inlet Control Device (ICD) Information

IPEX Tempest™ Inlet Control Devices

Municipal Technical Manual Series

Vol. I, 2nd Edition

© 2012 by IPEX. All rights reserved. No part of this book may be used or reproduced in any manner whatsoever without prior written permission. For information contact: IPEX, Marketing, 2441 Royal Windsor Drive, Mississauga, Ontario, Canada, L5J 4C7.

The information contained here within is based on current information and product design at the time of publication and is subject to change without notification. IPEX does not guarantee or warranty the accuracy, suitability for particular applications, or results to be obtained therefrom.

PRODUCT INFORMATION: TEMPEST LOW, MEDIUM FLOW (LMF) ICD

Purpose

To control the amount of storm water runoff entering a sewer system by allowing a specified flow volume out of a catch basin or manhole at a specified head. This approach conserves pipe capacity so that catch basins downstream do not become uncontrollably surcharged, which can lead to basement floods, flash floods and combined sewer overflows.

Product Description

Our LMF ICD is designed to accommodate catch basins or manholes with sewer outlet pipes 6" in diameter and larger. Any storm sewer larger than 12" may require custom modification. However, IPEX can custom build a TEMPEST device to accommodate virtually any storm sewer size.

Available in 14 preset flow curves, the LMF ICD has the ability to provide flow rates: 2lps – 17lps (31gpm – 270gpm)

Product Function

The LMF ICD vortex flow action allows the LMF ICD to provide a narrower flow curve using a larger orifice than a conventional orifice plate ICD, making it less likely to clog. When comparing flows at the same head level, the LMF ICD has the ability to restrict more flow than a conventional ICD during a rain event, preserving greater sewer capacity.

Product Construction

Constructed from durable PVC, the LMF ICD is light weight 8.9 Kg (19.7 lbs).

Product Applications

Will accommodate both square and round applications:




Chart 1: LMF 14 Preset Flow Curves





Chart 2: LMF Flow vs. ICD Alternatives



PRODUCT INSTALLATION

Instructions to assemble a TEMPEST LMF ICD into a Square Catch Basin:

STEPS:

1. Materials and tooling verification:
 - Tooling: impact drill, 3/8" concrete bit, torque wrench for 9/16" nut, hand hammer, level, and marker.
 - Material: (4) concrete anchor 3/8 x 3-1/2, (4) washers, (4) nuts, universal mounting plate, ICD device.
2. Use the mounting wall plate to locate and mark the hole (4) pattern on the catch basin wall. You should use a level to ensure that the plate is at the horizontal.
3. Use an impact drill with a 3/8" concrete bit to make the four holes at a minimum of 1-1/2" depth up to 2-1/2". Clean the concrete dust from the holes.
4. Install the anchors (4) in the holes by using a hammer. Thread the nuts on the top of the anchors to protect the threads when you hit the anchors with the hammer. Remove the nuts from the ends of the anchors.
5. Install the universal mounting plate on the anchors and screw the 4 nuts in place with a maximum torque of 40 N.m (30 lbf-ft). There should be no gap between the wall mounting plate and the catch basin wall.
6. From the ground above using a reach bar, lower the ICD device by hooking the end of the reach bar to the handle of the ICD device. Align the triangular plate portion into the mounting wall plate. Push down the device to be sure it has centered in to the universal mounting plate and has created a seal.



WARNING

- Verify that the outlet pipe doesn't protrude into the catch basin. If it does, cut down the pipe flush to the catch basin wall.
- Call your IPEX representative for more information or if you have any questions about our products.

Instructions to assemble a TEMPEST LMF ICD into a Round Catch Basin:

STEPS:

1. Materials and tooling verification.
 - Tooling: impact drill, 3/8" concrete bit, torque wrench for 9/16" nut, hand hammer, level and marker.
 - Material: (4) concrete anchor 3/8 x 3-1/2, (4) washers and (4) nuts, spigot CB wall plate, universal mounting plate hub adapter, ICD device.
2. Use the spigot catch basin wall plate to locate and mark the hole (4) pattern on the catch basin wall. You should use a level to ensure that the plate is at the horizontal.
3. Use an impact drill with a 3/8" concrete bit to make the four holes at a depth between 1-1/2" to 2-1/2". Clean the concrete dust from the holes.
4. Install the anchors (4) in the holes by using a hammer. Thread the nuts on the top of the anchors to protect the threads when you hit the anchors with the hammer. Remove the nuts from the ends of the anchors.
5. Install the CB spigot wall plate on the anchors and screw the 4 nuts in place with a maximum torque of 40 N.m (30 lbf-ft). There should be no gap between the spigot wall plate and the catch basin wall.
6. Apply solvent cement on the hub of the universal mounting plate, hub adapter and the spigot of the CB wall plate, then slide the hub over the spigot. Make sure the universal mounting plate is at the horizontal and its hub is completely inserted onto the spigot. Normally, the corners of the universal mounting plate hub adapter should touch the catch basin wall.
7. From ground above using a reach bar, lower the ICD device by hooking the end of the reach bar to the handle of the ICD device. Align the triangular plate portion into the mounting wall plate. Push down the device to be sure it has centered in to the mounting plate and has created a seal.



WARNING

- Verify that the outlet pipe doesn't protrude into the catch basin. If it does, cut back the pipe flush to the catch basin wall.
- The solvent cement which is used in this installation is to be approved for PVC.
- The solvent cement should not be used below 0°C (32°F) or in a high humidity environment. Refer to the IPEX solvent cement guide to confirm the required curing time or visit the IPEX Online Solvent Cement Training Course available at www.ipexinc.com.
- Call your IPEX representative for more information or if you have any questions about our products.

PRODUCT TECHNICAL SPECIFICATION

General

Inlet control devices (ICD's) are designed to provide flow control at a specified rate for a given water head level and also provide odour and floatable control. All ICD's will be IPEX Tempest or approved equal.

All devices shall be removable from a universal mounting plate. An operator from street level using only a T-bar with a hook will be able to retrieve the device while leaving the universal mounting plate secured to the catch basin wall face. The removal of the TEMPEST devices listed above must not require any unbolting or special manipulation or any special tools.

High Flow (HF) Sump devices will consist of a removable threaded cap which can be accessible from street level with out entry into the catchbasin (CB). The removal of the threaded cap shall not require any special tools other than the operator's hand.

ICD's shall have no moving parts.

Materials

ICD's are to be manufactured from Polyvinyl Chloride (PVC) or Polyurethane material, designed to be durable enough to withstand multiple freeze-thaw cycles and exposure to harsh elements.

The inner ring seal will be manufactured using a Buna or Nitrile material with hardness between Duro 50 and Duro 70.

The wall seal is to be comprised of a 3/8" thick Neoprene Closed Cell Sponge gasket which is attached to the back of the wall plate.





All hardware will be made from 304 stainless steel.

Dimensioning


The Low Medium Flow (LMF), High Flow (HF) and the High Flow (HF) Sump shall allow for a minimum outlet pipe diameter of 200mm with a 600mm deep Catch Basin sump.



Installation

Contractor shall be responsible for securing, supporting and connecting the ICD's to the existing influent pipe and catchbasin/manhole structure as specified and designed by the Engineer.




SECTION A-A





- GENERAL NOTES:**
- COORDINATE AND SCHEDULE ALL WORK WITH OTHER TRADES AND CONTRACTORS.
 - DETERMINE THE EXACT LOCATION, SIZE, MATERIAL AND ELEVATION OF ALL EXISTING UTILITIES PRIOR TO COMMENCING CONSTRUCTION. PROTECT AND ASSUME RESPONSIBILITY FOR ALL EXISTING UTILITIES WHETHER OR NOT SHOWN ON THIS DRAWING.
 - OBTAIN ALL NECESSARY PERMITS AND APPROVALS FROM THE CITY OF OTTAWA BEFORE COMMENCING CONSTRUCTION.
 - BEFORE COMMENCING CONSTRUCTION OBTAIN AND PROVIDE PROOF OF COMPREHENSIVE, ALL RISK AND OPERATIONAL LIABILITY INSURANCE FOR \$5,000,000.00. INSURANCE POLICY TO NAME OWNERS, ENGINEERS AND ARCHITECTS AS CO-INSURED.
 - RESTORE ALL DISTURBED AREAS ON-SITE AND OFF-SITE, INCLUDING TRENCHES AND SURFACES ON PUBLIC ROAD ALLOWANCES TO EXISTING CONDITIONS OR BETTER TO THE SATISFACTION OF THE CITY OF OTTAWA AND ENGINEER.
 - REMOVE FROM SITE ALL EXCESS EXCAVATED MATERIAL, ORGANIC MATERIAL AND DEBRIS UNLESS OTHERWISE INSTRUCTED BY ENGINEER. EXCAVATE AND REMOVE FROM SITE ANY CONTAMINATED MATERIAL. ALL CONTAMINATED MATERIAL SHALL BE DISPOSED OF AT A LICENSED LANDFILL FACILITY.
 - ALL ELEVATIONS ARE GEODETIC.
 - REFER TO GEOTECHNICAL REPORT (No. 190227, DATED JUNE, 2019), PREPARED BY LRL ENGINEERING FOR SUBSURFACE CONDITIONS, CONSTRUCTION RECOMMENDATIONS AND GEOTECHNICAL INSPECTION REQUIREMENTS. THE GEOTECHNICAL CONSULTANT IS TO REVIEW ON-SITE CONDITIONS AFTER EXCAVATION PRIOR TO PLACEMENT OF THE GRANULAR MATERIAL.
 - REFER TO ARCHITECT'S AND LANDSCAPE ARCHITECT'S DRAWINGS FOR BUILDING AND HARD SURFACE AREAS AND DIMENSIONS.
 - REFER TO DEVELOPMENT SERVICING & STORMWATER MANAGEMENT REPORT (R-2019-193) PREPARED BY NOVATECH.
 - SAW CUT AND KEY GRIND ASPHALT AT ALL ROAD CUTS AND ASPHALT TIE IN POINTS AS PER CITY OF OTTAWA STANDARDS (R10).



PROPOSED 150mmØ WATER SERVICE TABLE

STATION	SURFACE ELEVATION	T/W M ELEVATION	COMMENTS
0+00	79.85a	77.45	150mmØ WM CONNECTION TO EX. 200mmØ WM
0+05.3	79.77	77.37	CROSS BELOW EX. 50mmØ GAS LINE (1.4mz CLEAR)
0+10	80.15	77.65	---
0+11.8	80.24	77.74	PROPERTY LINE / 150mmØ V&B
0+12.1	80.25	77.75	CAP 1.0m FROM FOUNDATION WALL

* CONNECTION TO EXISTING 200mmØ WATERMAIN. EXACT ELEVATIONS TO BE FIELD DETERMINED.
 ** PROVIDE THERMAL INSULATION AS PER CITY OF OTTAWA DETAIL W22 IN SHALLOW TRENCHES AND/OR CITY OF OTTAWA DETAIL W23 ADJACENT TO OPEN STRUCTURES.

SITE FLOWS & STORMWATER MANAGEMENT TABLE

DESIGN EVENT	PRE-DEVELOPMENT CONDITIONS			POST-DEVELOPMENT CONDITIONS				REDUCTION IN FLOW (L/S OR %) *
	UNCONTROLLED FLOW (L/s)	ALLOWABLE RELEASE RATE (L/s)	R-1 FLOW (L/s)	A-1 FLOW (L/s)	A-2 FLOW (L/s)	A-3 FLOW (L/s)	TOTAL FLOW (L/s)	
1.5 YR	17.7	10.5	3.4	0.1	0.9	2.6	7.0	10.7 or 60%
1:100 YR	34.6	10.5	3.9	0.2	1.7	4.4	10.2	24.4 or 71%

* REDUCED FLOW COMPARED TO PRE-DEVELOPMENT UNCONTROLLED CONDITIONS

INLET CONTROL DEVICE DATA TABLE - CBMH 1

DESIGN EVENT	ICD TYPE (VORTEX MODEL)	DIAMETER OF OUTLET PIPE (mm)	DESIGN FLOW (L/s)	DESIGN HEAD (m)	WATER ELEVATION (m)	VOLUME (m³)	AVAILABLE STORAGE
1:2 YR	IPEX	250mmØ PVC	2.5	0.45	76.45	4.0	21.5 m³
1.5 YR	TEMPEST LMF (MODEL 65)	250mmØ PVC	2.6	0.63	76.63	5.3	
1:100 YR	TEMPEST LMF (MODEL 65)	250mmØ PVC	4.4	1.82	77.82	10.7	

ROOF DRAIN TABLE: AREA R-1 (ROOF DRAINS 1 to 5)

AREA ID	ROOF DRAIN NO. (WATTS MODEL)	ROOF DRAIN OPENING SETTING	1.5 YEAR RELEASE RATE	APPROX. 5-YR PONDING DEPTH	1:100 YEAR RELEASE RATE	APPROX. 100-YR PONDING DEPTH
R-1	RD 1 (RD-100-A-ADJ)	1/4 EXPOSED	0.79 L/s	11 cm	0.95 L/s	15 cm
R-1	RD 2 (RD-100-A-ADJ)	1/4 EXPOSED	0.79 L/s	9 cm	0.87 L/s	13 cm
R-1	RD 3 (RD-100-A-ADJ)	1/4 EXPOSED	0.71 L/s	8 cm	0.87 L/s	13 cm
R-1	RD 4 (RD-100-A-ADJ)	1/4 EXPOSED	0.79 L/s	10 cm	0.87 L/s	14 cm
R-1	RD 5 (RD-100-A-ADJ)	CLOSED	0.32 L/s	10 cm	0.32 L/s	14 cm

* REFER TO THE 'DEVELOPMENT SERVICING AND STORMWATER MANAGEMENT REPORT' (R-2019-193) PREPARED BY NOVATECH FOR DRAINAGE AREA IDENTIFIERS AND STORMWATER MANAGEMENT DETAILS.
 ** ALL CONTROLLED FLOW ROOF DRAINS FOR THE PROPOSED BUILDING TO BE WATTS 'ADJUSTABLE ACCUTROL' ROOF DRAINS.

- SEWER NOTES:**
- SUPPLY AND CONSTRUCT ALL SEWERS AND APPURTENANCES IN ACCORDANCE WITH THE MOST CURRENT CITY OF OTTAWA STANDARDS AND SPECIFICATIONS.
 - SPECIFICATIONS:

ITEM	SPEC. No.	REFERENCE
CATCHBASIN (600x600mm)	705.010	OPSD
STORM / SANITARY MANHOLE (1200mmØ)	701.010	OPSD
STORM MANHOLE (1500mmØ)	701.020	OPSD
CB, FRAME & COVER	400.020	OPSD
STORM / SANITARY MH FRAME & COVER	401.010	OPSD
AREA DRAIN	S31	CITY OF OTTAWA
SEWER TRENCH	S6	CITY OF OTTAWA
SANITARY / STORM SEWER / CB LEAD	PVC DR 35	
 - ALL STORM AND SANITARY SERVICE LATERALS SHALL BE EQUIPPED WITH BACKFLOW PREVENTION DEVICES AS PER THE CITY OF OTTAWA STANDARD DETAILS S14 AND S14.1 OR S14.2.
 - INSULATE ALL PIPES (SAN/STM) THAT HAVE LESS THAN 1.5m COVER WITH HI-40 INSULATION PER INSULATION DETAIL FOR SHALLOW SEWERS. PROVIDE 150mm CLEARANCE BETWEEN PIPE AND INSULATION.
 - SERVICES ARE TO BE CONSTRUCTED TO 1.0m FROM FACE OF BUILDING AT A MINIMUM SLOPE OF 1.0%.
 - PIPE BEDDING, COVER AND BACKFILL ARE TO BE COMPACTED TO AT LEAST 95% OF THE STANDARD PROCTOR MAXIMUM DRY DENSITY. THE USE OF CLEAR CRUSHED STONE AS A BEDDING LAYER SHALL NOT BE PERMITTED.
 - FLEXIBLE CONNECTIONS ARE REQUIRED FOR CONNECTING PIPES TO MANHOLES (FOR EXAMPLE KOR-N-SEAL, PSX: POSITIVE SEAL AND DURASEAL). THE CONCRETE CRADLE FOR THE PIPE CAN BE ELIMINATED.
 - THE OWNER SHALL REQUIRE THAT THE SITE SERVICING CONTRACTOR PERFORM FIELD TESTS FOR QUALITY CONTROL OF ALL SANITARY SEWERS. LEAKAGE TESTING SHALL BE COMPLETED IN ACCORDANCE WITH OPSS 410.07.16, 410.07.16.04 AND 407.07.24. DYE TESTING IS TO BE COMPLETED ON ALL SANITARY SEWERS TO CONFIRM PROPER CONNECTION TO THE SANITARY SEWER MAIN. THE FIELD TESTS SHALL BE PERFORMED IN THE PRESENCE OF A CERTIFIED PROFESSIONAL ENGINEER WHO SHALL SUBMIT A CERTIFIED COPY OF THE TEST RESULTS.
 - ALL STORM MANHOLES AND CATCHBASIN MANHOLES ARE TO HAVE 600mm SUMPS UNLESS OTHERWISE INDICATED. ALL CATCHBASINS ARE TO HAVE 600mm SUMPS UNLESS OTHERWISE INDICATED.
 - ALL CATCHBASINS, MANHOLES AND/OR CATCHBASIN MANHOLES THAT ARE TO HAVE ICD'S INSTALLED WITHIN THEM ARE TO HAVE 600mm SUMPS.
 - ALL WEeping TILE CONNECTIONS TO BE MADE TO THE PROPOSED STORM SEWER SYSTEM DOWNSTREAM OF ANY INLET CONTROL DEVICES.
 - THE CONTRACTOR IS TO TELEVISION (CCTV) ALL PROPOSED SEWERS, 200mmØ OR GREATER PRIOR TO BASE COURSE ASPHALT. UPON COMPLETION OF CONTRACT, THE CONTRACTOR IS RESPONSIBLE TO FLUSH AND CLEAN ALL SEWERS & APPURTENANCES.
 - CONTRACTOR TO PROVIDE THE CONSULTANT WITH A GENERAL PLAN OF SERVICES INDICATING ALL APPLICABLE SERVICING AS-BUILT INFORMATION SHOWN ON THIS PLAN. AS-BUILT INFORMATION MUST INCLUDE: PIPE MATERIAL, SIZES, LENGTHS, SLOPES, INVERT AND TIG ELEVATIONS, STRUCTURE LOCATIONS AND ANY ALIGNMENT CHANGES, ETC.

- WATERMAIN NOTES:**
- SUPPLY AND CONSTRUCT ALL WATERMANS AND APPURTENANCES IN ACCORDANCE WITH THE CITY OF OTTAWA STANDARDS AND SPECIFICATIONS. EXCAVATION, BACKFILL AND RESTORATION OF ALL WATERMANS BY THE CONTRACTOR. CONNECTIONS AND SHUT-OFFS AT THE MAIN BY CITY OF OTTAWA FORCES. CHLORINATION OF THE WATER SYSTEM SHALL BE PERFORMED BY THE CONTRACTOR IN THE PRESENCE CITY OF OTTAWA FORCES.
 - SPECIFICATIONS:

ITEM	SPEC. No.	REFERENCE
WATERMAIN TRENCHING	W17	CITY OF OTTAWA
THERMAL INSULATION IN SHALLOW TRENCHES	W22	CITY OF OTTAWA
THERMAL INSULATION AT OPEN STRUCTURES	W23	CITY OF OTTAWA
WATERMAIN CROSSING BELOW SEWER	W25	CITY OF OTTAWA
WATERMAIN	PVC DR 18	
 - WATERMAIN SHALL BE MINIMUM 2.4m DEPTH BELOW GRADE UNLESS OTHERWISE INDICATED.
 - PROVIDE MINIMUM 0.5m CLEARANCE BETWEEN OUTSIDE OF PIPES AT ALL CROSSINGS.
 - WATER SERVICE IS TO BE CONSTRUCTED TO WITHIN 1.0m OF FOUNDATION WALL AND CAPPED, UNLESS OTHERWISE INDICATED.

NOTE:
 THE POSITION OF ALL POLE LINES, CONDUITS, WATERMANS, SEWERS AND OTHER UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED. BEFORE STARTING WORK, DETERMINE THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES AND ASSUME ALL LIABILITY FOR DAMAGE TO THEM.

OWNER INFORMATION
 ALEXANDER FLECK HOUSE INC.
 250 STE ANNE AVENUE,
 OTTAWA, ONTARIO, K1L 7C4
 DENIS MICHAUD
 PHONE: (613) 402-2855
 denis@henryinvestments.ca

SCALE
 1:150

DESIGN
 SM / MS
 CHECKED

DRAWN
 MS
 BF / SM
 CHECKED

APPROVED
 JLS
 MS

No.	ISSUED FOR SITE PLAN APPROVAL	DATE	BY
1		DEC 9/19	MS
	REVISION	DATE	BY

FOR REVIEW ONLY

PROFESSIONAL ENGINEER
 M. SAVIC
 100102651
 12/19/19
 PROVINCE OF ONTARIO

NOVATECH
 Engineers, Planners & Landscape Architects
 Suite 200, 240 Michael Cowpland Drive
 Ottawa, Ontario, Canada K2M 1P6
 Telephone: (613) 254-9643
 Facsimile: (613) 254-5867
 Website: www.novatech-eng.com

LOCATION
 CITY OF OTTAWA
 593 LAURIER AVENUE

DRAWING NAME
 GENERAL PLAN OF SERVICES




PROJECT No.
 119019

REV # 1
 119019-GP

CITY PLAN #
 -GP

M:\2019\119019\119019-GP.dwg, GP, Dec 06, 2019 - 2:11pm, smathews

D07-12-19-



NOTE:
THE POSITION OF ALL POLE LINES, CONDUITS, WATERMANS, SEWERS AND OTHER UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED. BEFORE STARTING WORK, DETERMINE THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES AND ASSUME ALL LIABILITY FOR DAMAGE TO THEM.

OWNER INFORMATION
ALEXANDER FLECK HOUSE INC.
250 STE ANNE AVENUE,
OTTAWA, ONTARIO, K1L 7C4
DENIS MICHAUD
PHONE: (613) 402-2855
denis@henryinvestments.ca

SCALE
1:150
1:75

DESIGN
MS
CHECKED
MS
DRAWN
BF
CHECKED
MS
APPROVED
MS

FOR REVIEW ONLY



NOVATECH
Engineers, Planners & Landscape Architects
Suite 200, 240 Michael Cowpland Drive
Ottawa, Ontario, Canada K2M 1P6
Telephone: (613) 254-9643
Facsimile: (613) 254-5867
Website: www.novatech-eng.com

LOCATION
CITY OF OTTAWA
593 LAURIER AVENUE / 140 BRONSON AVENUE

DRAWING NAME
OUTLET SEWER
PLAN AND PROFILE

PROJECT No. 119019
REV #1
DRAWING No. 119019-P1

D07-12-19-



Erosion and Sediment Control Responsibilities:

ESC Measure	Symbol	Specification	Installation Responsibility	Inspection/Maintenance Responsibility	Inspection Frequency	Approval to Remove	Removal Responsibility	Inspection/Maintenance Responsibility
Silt Fence	---	OPSD 219.110	Developer's Contractor	Developer's Contractor	Weekly (as a minimum)	Consultant	Developer's Contractor	N/A
Filter Fabric	---	Location as Indicated in ESC Note #s	Developer's Contractor	Developer's Contractor	Weekly (as a minimum)	Consultant	Developer's Contractor	N/A
Mud Mat	[M]	Drawing Details	Developer's Contractor	Developer's Contractor	Weekly (as a minimum)	Developer's Contractor	Developer's Contractor	N/A
Dust Control	[D]	Location as Required Around Site	Developer's Contractor	Developer's Contractor	Weekly (as a minimum)	Consultant	Developer's Contractor	N/A
Stabilized Material Stockpiling	[S]	Location as Required by Contractor	Developer's Contractor	Developer's Contractor	Weekly (as a minimum)	Developer's Contractor	Developer's Contractor	N/A
Sediment Basin (for flows being pumped out of excavations)	[B]	Location as Required by Contractor	Developer's Contractor	Developer's Contractor	After Every Rainstorm	Developer's Contractor	Developer's Contractor	N/A

GENERAL NOTES:

- COORDINATE AND SCHEDULE ALL WORK WITH OTHER TRADES AND CONTRACTORS.
- DETERMINE THE EXACT LOCATION, SIZE, MATERIAL AND ELEVATION OF ALL EXISTING UTILITIES PRIOR TO COMMENCING CONSTRUCTION. PROTECT AND ASSUME RESPONSIBILITY FOR ALL EXISTING UTILITIES WHETHER OR NOT SHOWN ON THIS DRAWING.
- OBTAIN ALL NECESSARY PERMITS AND APPROVALS FROM THE CITY OF OTTAWA BEFORE COMMENCING CONSTRUCTION.
- BEFORE COMMENCING CONSTRUCTION OBTAIN AND PROVIDE PROOF OF COMPREHENSIVE, ALL RISK AND OPERATIONAL LIABILITY INSURANCE FOR \$5,000,000.00. INSURANCE POLICY TO NAME OWNERS, ENGINEERS AND ARCHITECTS AS CO-INSURED.
- RESTORE ALL DISTURBED AREAS ON-SITE AND OFF-SITE, INCLUDING TRENCHES AND SURFACES ON PUBLIC ROAD ALLOWANCES TO EXISTING CONDITIONS OR BETTER TO THE SATISFACTION OF THE CITY OF OTTAWA AND ENGINEER.
- REMOVE FROM SITE ALL EXCESS EXCAVATED MATERIAL, ORGANIC MATERIAL AND DEBRIS UNLESS OTHERWISE INSTRUCTED BY ENGINEER. EXCAVATE AND REMOVE FROM SITE ANY CONTAMINATED MATERIAL. ALL CONTAMINATED MATERIAL SHALL BE DISPOSED OF AT A LICENSED LANDFILL FACILITY.
- ALL ELEVATIONS ARE GEODETIC.
- REFER TO GEOTECHNICAL REPORT (No. 190227, DATED JUNE, 2019), PREPARED BY LRL ENGINEERING FOR SUBSURFACE CONDITIONS, CONSTRUCTION RECOMMENDATIONS, AND GEOTECHNICAL INSPECTION REQUIREMENTS. THE GEOTECHNICAL CONSULTANT IS TO REVIEW ON-SITE CONDITIONS AFTER EXCAVATION PRIOR TO PLACEMENT OF THE GRANULAR MATERIAL.
- REFER TO ARCHITECT'S AND LANDSCAPE ARCHITECT'S DRAWINGS FOR BUILDING AND HARD SURFACE AREAS AND DIMENSIONS.
- REFER TO DEVELOPMENT SERVICING & STORMWATER MANAGEMENT REPORT (R-2019-193) PREPARED BY NOVATECH.
- SAW CUT AND KEY GRIND ASPHALT AT ALL ROAD CUTS AND ASPHALT TIE IN POINTS AS PER CITY OF OTTAWA STANDARDS (R10).

EROSION AND SEDIMENT CONTROL NOTES:

- ALL EROSION AND SEDIMENT CONTROLS ARE TO BE INSTALLED TO THE SATISFACTION OF THE ENGINEER AND THE CITY OF OTTAWA. THEY ARE TO BE APPROPRIATE TO THE SITE CONDITIONS, PRIOR TO UNDERTAKING ANY SITE ALTERATIONS (FILLING, GRADING, REMOVAL OF VEGETATION, ETC.) AND DURING ALL PHASES OF SITE PREPARATION AND CONSTRUCTION. THESE PRACTICES ARE TO BE IMPLEMENTED IN ACCORDANCE WITH THE CURRENT BEST MANAGEMENT PRACTICES FOR EROSION AND SEDIMENT CONTROL AND SHOULD INCLUDE AS A MINIMUM THOSE MEASURES INDICATED ON THE PLAN.
- TO PREVENT SURFACE EROSION FROM ENTERING ANY STORM SEWER SYSTEM DURING CONSTRUCTION, FILTER CLOTH WILL BE PLACED UNDER GRATES OF NEARBY CATCHBASINS AND STRUCTURES. A LIGHT DUTY SILT FENCE BARRIER WILL ALSO BE INSTALLED AROUND THE CONSTRUCTION AREA (WHERE APPLICABLE). THESE CONTROL MEASURES WILL REMAIN IN PLACE UNTIL CONSTRUCTION IS COMPLETE.
- THE SEDIMENT CONTROL MEASURES SHALL ONLY BE REMOVED WHEN, IN THE OPINION OF THE ENGINEER, THE MEASURES ARE NO LONGER REQUIRED. NO CONTROL MEASURES MAY BE PERMANENTLY REMOVED WITHOUT PRIOR AUTHORIZATION FROM THE ENGINEER.
- THE CONTRACTOR SHALL IMMEDIATELY REPORT TO THE ENGINEER ANY ACCIDENTAL DISCHARGES OF SEDIMENT MATERIAL INTO ANY STORM SEWER SYSTEM. APPROPRIATE RESPONSE MEASURES, INCLUDING ANY REPAIRS TO EXISTING CONTROL MEASURES OR THE IMPLEMENTATION OF ADDITIONAL CONTROL MEASURES, SHALL BE CARRIED OUT BY THE CONTRACTOR WITHOUT DELAY.
- THE CONTRACTOR ACKNOWLEDGES THAT FAILURE TO IMPLEMENT EROSION AND SEDIMENT CONTROL MEASURES MAY BE SUBJECT TO PENALTIES IMPOSED BY ANY APPLICABLE REGULATORY AGENCY.
- ROADWAYS ARE TO BE SWEEP AS REQUIRED OR AS DIRECTED BY THE ENGINEER AND/OR MUNICIPALITY.
- THE CONTRACTOR SHALL ENSURE PROPER DUST CONTROL IS PROVIDED WITH THE APPLICATION OF WATER (AND IF REQUIRED, CALCIUM CHLORIDE) DURING DRY PERIODS.

GRADING NOTES:

- ALL TOPSOIL, ORGANIC OR DELETERIOUS MATERIAL MUST BE ENTIRELY REMOVED FROM BENEATH THE PROPOSED PAVED AREAS AS DIRECTED BY THE SITE ENGINEER OR GEOTECHNICAL ENGINEER.
- EXPOSED SUBGRADES IN PROPOSED PAVED AREAS SHOULD BE PROOF ROLLED WITH A LARGE STEEL DRUM ROLLER AND INSPECTED BY THE GEOTECHNICAL ENGINEER PRIOR TO THE PLACEMENT OF GRANULARS.
- ANY SOFT AREAS EVIDENT FROM THE PROOF ROLLING SHOULD BE SUB-EXCAVATED AND REPLACED WITH SUITABLE MATERIAL THAT IS PROOF COMPATIBLE WITH THE EXISTING SOILS AS RECOMMENDED BY THE GEOTECHNICAL ENGINEER.
- THE GRANULAR BASE SHOULD BE COMPACTED TO AT LEAST 100% OF THE STANDARD PROCTOR MAXIMUM DRY DENSITY VALUE. ANY ADDITIONAL GRANULAR FILL USED BELOW THE PROPOSED PAVEMENT SHOULD BE COMPACTED TO AT LEAST 95% OF THE STANDARD PROCTOR MAXIMUM DRY DENSITY VALUE.
- MINIMUM OF 2% GRADE FOR ALL GRASS AREAS UNLESS OTHERWISE NOTED.
- MAXIMUM TERRACING GRADE TO BE 3:1 UNLESS OTHERWISE NOTED.
- ALL GRADES BY CURBS ARE EDGE OF PAVEMENT GRADES UNLESS OTHERWISE INDICATED.
- ALL CURBS SHALL BE BARRIER CURB (150mm) UNLESS OTHERWISE NOTED AND CONSTRUCTED AS PER CITY OF OTTAWA STANDARDS (SC1.1).
- REFER TO LANDSCAPE PLAN FOR PLANTING AND OTHER LANDSCAPE FEATURE DETAILS.
- CONTRACTOR TO PROVIDE THE CONSULTANT WITH A GRADING PLAN INDICATING AS-BUILT ELEVATIONS OF ALL DESIGN GRADES SHOWN ON THIS PLAN.

PAVEMENT STRUCTURE:

- LIGHT DUTY PAVEMENT
 - 50mm HL-3 or SUPERPAVE 12.5
 - 150mm GRANULAR "A"
 - 350mm GRANULAR "B" TYPE II
 - ASPHALT GRADE PG 58-34
- HEAVY DUTY PAVEMENT
 - 40mm HL-3 or SUPERPAVE 12.5
 - 50mm HL-5 or SUPERPAVE 19.0
 - 150mm GRANULAR "A"
 - 450mm GRANULAR "B" TYPE II
 - ASPHALT GRADE PG 58-34
- HEAVY DUTY PERVIOUS PAVERS
 - PERVIOUS PAVERS (PER MANUFACTURER'S RECOMMENDATIONS)
 - 150mm GRANULAR "A"
 - 450mm GRANULAR "B" TYPE II
 - SUBDRAIN OUTLET TO CBMH 4

PRELIMINARY

NOTE: THE POSITION OF ALL POLE LINES, CONDUITS, WATERMANS, SEWERS AND OTHER UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED. BEFORE STARTING WORK, DETERMINE THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES AND ASSUME ALL LIABILITY FOR DAMAGE TO THEM.

OWNER INFORMATION
 ALEXANDER FLECK HOUSE INC.
 250 STE ANNE AVENUE,
 OTTAWA, ONTARIO, K1L 7C4
 DENIS MICHAUD
 PHONE: (613) 402-2855
 denis@henryinvestments.ca

No.	REVISION	DATE	BY
1	ISSUED FOR SITE PLAN APPROVAL	DEC 9/19	MS

SCALE: 1:150

DESIGN: SM / MS
 CHECKED: MS
 DRAWN: BF / SM
 CHECKED: JLS
 APPROVED: MS

1:150


FOR REVIEW ONLY

NOVATECH
 Engineers, Planners & Landscape Architects
 Suite 200, 240 Michael Cowpland Drive
 Ottawa, Ontario, Canada K2M 1P6
 Telephone: (613) 254-9643
 Facsimile: (613) 254-5867
 Website: www.novatech-emp.com

LOCATION CITY OF OTTAWA 593 LAURIER AVENUE	PROJECT No. 119019
DRAWING NAME GRADING AND EROSION & SEDIMENT CONTROL PLAN	REV # 1 119019-GR
CITY PLAN # -GR	

M:\2019\119019\CAD\Design\119019-GR.dwg, GR, Dec 08, 2019 - 2:22pm, smathews


D07-12-19-



REFER TO PLAN 119019-P1 FOR CONTINUATION OF OUTLET SEWERS

LEGEND

- PROPOSED BARRIER CURB
- PROPOSED DEPRESSED CURB
- DRAINAGE AREA LIMITS
- APPROXIMATE PONDING LIMITS
- POST-DEVELOPMENT AREA ID
- POST-DEVELOPMENT DRAINAGE AREA (ha)
- 1.5 YEAR WEIGHTED RUNOFF COEFFICIENT
- FFE
- T/FND
- USF
- PROPOSED CONTROLLED FLOW ROOF DRAIN
- PROPOSED STORM SEWER AND FLOW DIRECTION
- EMERGENCY OVERLAND FLOW ROUTE
- PROPOSED BUILDING ENTRANCE / EXIT
- EXISTING STORM MH & SEWER
- EXISTING CATCHBASIN & CATCHBASIN LEAD



GENERAL NOTES:

1. COORDINATE AND SCHEDULE ALL WORK WITH OTHER TRADES AND CONTRACTORS.
2. DETERMINE THE EXACT LOCATION, SIZE, MATERIAL AND ELEVATION OF ALL EXISTING UTILITIES PRIOR TO COMMENCING CONSTRUCTION. PROTECT AND ASSUME RESPONSIBILITY FOR ALL EXISTING UTILITIES WHETHER OR NOT SHOWN ON THIS DRAWING.
3. OBTAIN ALL NECESSARY PERMITS AND APPROVALS FROM THE CITY OF OTTAWA BEFORE COMMENCING CONSTRUCTION.
4. BEFORE COMMENCING CONSTRUCTION OBTAIN AND PROVIDE PROOF OF COMPREHENSIVE, ALL RISK AND OPERATIONAL LIABILITY INSURANCE FOR \$5,000,000.00. INSURANCE POLICY TO NAME OWNERS, ENGINEERS AND ARCHITECTS AS CO-INSURED.
5. RESTORE ALL DISTURBED AREAS ON-SITE AND OFF-SITE, INCLUDING TRENCHES AND SURFACES ON PUBLIC ROAD ALLOWANCES TO EXISTING CONDITIONS OR BETTER TO THE SATISFACTION OF THE CITY OF OTTAWA AND ENGINEER.
6. REMOVE FROM SITE ALL EXCESS EXCAVATED MATERIAL, ORGANIC MATERIAL AND DEBRIS UNLESS OTHERWISE INSTRUCTED BY ENGINEER. EXCAVATE AND REMOVE FROM SITE ANY CONTAMINATED MATERIAL. ALL CONTAMINATED MATERIAL SHALL BE DISPOSED OF AT A LICENSED LANDFILL FACILITY.
7. ALL ELEVATIONS ARE GEODETIC.
8. REFER TO GEOTECHNICAL REPORT (No. 190227, DATED JUNE, 2019), PREPARED BY LRL ENGINEERING FOR SUBSURFACE CONDITIONS, CONSTRUCTION RECOMMENDATIONS AND GEOTECHNICAL INSPECTION REQUIREMENTS. THE GEOTECHNICAL CONSULTANT IS TO REVIEW ON-SITE CONDITIONS AFTER EXCAVATION PRIOR TO PLACEMENT OF THE GRANULAR MATERIAL.
9. REFER TO ARCHITECT'S AND LANDSCAPE ARCHITECT'S DRAWINGS FOR BUILDING AND HARD SURFACE AREAS AND DIMENSIONS.
10. REFER TO DEVELOPMENT SERVICING & STORMWATER MANAGEMENT REPORT (R-2019-193) PREPARED BY NOVATECH.
11. SAW CUT AND KEY GRIND ASPHALT AT ALL ROAD CUTS AND ASPHALT TIE IN POINTS AS PER CITY OF OTTAWA STANDARDS (R10).

DESIGN EVENT	PRE-DEVELOPMENT CONDITIONS		POST-DEVELOPMENT CONDITIONS					REDUCTION IN FLOW (L/s OR %)*
	UNCONTROLLED FLOW (L/s)	ALLOWABLE RELEASE RATE (L/s)	R-1 FLOW (L/s)	A-1 FLOW (L/s)	A-2 FLOW (L/s)	A-3 FLOW (L/s)	TOTAL FLOW (L/s)	
1.5 YR	17.7	10.5	3.4	0.1	0.9	2.6	7.0	10.7 or 60%
1:100 YR	34.6	10.5	3.9	0.2	1.7	4.4	10.2	24.4 or 71%

* REDUCED FLOW COMPARED TO PRE-DEVELOPMENT UNCONTROLLED CONDITIONS

DESIGN EVENT	ICD TYPE (VORTEX MODEL)	DIAMETER OF OUTLET PIPE (mm)	DESIGN FLOW (L/s)	DESIGN HEAD (m)	WATER ELEVATION (m)	VOLUME (m ³)	AVAILABLE STORAGE
1.2 YR	IPEX	250mmØ PVC	2.5	0.45	76.45	4.0	21.5 m ³
1.5 YR	TEMPEST LMF (MODEL 65)		2.6	0.63	76.63	5.3	
1:100 YR			4.4	1.82	77.82	10.7	

AREA ID	ROOF DRAIN No. (WATTS MODEL)	ROOF DRAIN OPENING SETTING	1.5 YEAR RELEASE RATE	APPROX. 5-YR PONDING DEPTH	1:100 YEAR RELEASE RATE	APPROX. 100-YR PONDING DEPTH
R-1	RD 1 (RD-100-A-ADJ)	1/4 EXPOSED	0.79 L/s	11 cm	0.95 L/s	15 cm
R-1	RD 2 (RD-100-A-ADJ)	1/4 EXPOSED	0.79 L/s	9 cm	0.87 L/s	13 cm
R-1	RD 3 (RD-100-A-ADJ)	1/4 EXPOSED	0.71 L/s	8 cm	0.87 L/s	13 cm
R-1	RD 4 (RD-100-A-ADJ)	1/4 EXPOSED	0.79 L/s	10 cm	0.87 L/s	14 cm
R-1	RD 5 (RD-100-A-ADJ)	CLOSED	0.32 L/s	10 cm	0.32 L/s	14 cm

* REFER TO THE 'DEVELOPMENT SERVICING AND STORMWATER MANAGEMENT REPORT' (R-2019-193) PREPARED BY NOVATECH FOR DRAINAGE AREA IDENTIFIERS AND STORMWATER MANAGEMENT DETAILS.
 **ALL CONTROLLED FLOW ROOF DRAINS FOR THE PROPOSED BUILDING TO BE WATTS 'ADJUSTABLE ACCUTROL' ROOF DRAINS.

NOTE: THE POSITION OF ALL POLE LINES, CONDUITS, WATERMANS, SEWERS AND OTHER UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED. BEFORE STARTING WORK, DETERMINE THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES AND ASSUME ALL LIABILITY FOR DAMAGE TO THEM.

OWNER INFORMATION
 ALEXANDER FLECK HOUSE INC.
 250 STE ANNE AVENUE,
 OTTAWA, ONTARIO, K1L 7C4
 DENIS MICHAUD
 PHONE: (613) 402-2855
 denis@henryinvestments.ca

No.	REVISION	DATE	BY
1	ISSUED FOR SITE PLAN APPROVAL	DEC 9/19	MS

SCALE

1:150

DESIGN	SM / MS
CHECKED	MS
DRAWN	BF / SM
CHECKED	JLS
APPROVED	MS

FOR REVIEW ONLY

NOVATECH
 Engineers, Planners & Landscape Architects
 Suite 200, 240 Michael Cowpland Drive
 Ottawa, Ontario, Canada K2M 1P6
 Telephone: (613) 254-9643
 Facsimile: (613) 254-5867
 Website: www.novatech-eng.com

LOCATION
 CITY OF OTTAWA
 593 LAURIER AVENUE

DRAWING NAME
 STORMWATER MANAGEMENT PLAN

PROJECT No.
 119019

REV # 1
 119019-SWM

CITY PLAN #

D07-12-19-