

Transportation Impact Study  
**400 Albert Street  
Residential Development**

**PARSONS**



**400 Albert Street  
Residential Development**

**Transportation Impact Assessment**

prepared for:  
Albert and Main Development Inc.  
Main and Main  
109 Atlantic Avenue  
Toronto ON M6K 1X4

prepared by:  
**PARSONS**  
1223 Michael Street  
Suite 100  
Ottawa, ON K1J 7T2

May 4, 2020

477196 - 01000

# Table of Contents

---

1. SCREENING.....	1
2. SCOPING REPORT.....	3
2.1. EXISTING AND PLANNED CONDITIONS.....	3
2.1.1. Proposed Development .....	3
2.1.2. Existing Conditions.....	3
2.1.3. Planned Conditions.....	10
2.2. STUDY AREA AND TIME PERIODS .....	13
2.2.1. Study Area .....	13
2.2.2. Time Periods.....	14
2.2.3. Horizon Years .....	14
2.3. EXEMPTION REVIEW .....	14
3. FORECASTING REPORT .....	14
3.1. DEVELOPMENT-GENERATED TRAVEL DEMAND.....	14
3.1.1. Trip Generation and Mode Shares.....	14
3.1.2. Trip Distribution.....	17
3.1.3. Trip Assignment.....	18
3.2. BACKGROUND NETWORK TRAVEL DEMANDS .....	19
3.2.1. Transportation Network Plans.....	19
3.2.2. Background Growth .....	19
3.2.3. Other Developments .....	19
3.3. DEMAND RATIONALIZATION .....	19
4. STRATEGY REPORT.....	19
4.1. PARKING.....	19
4.1.1. Parking Supply.....	19
4.2. BOUNDARY STREET DESIGN .....	20
4.3. ACCESS INTERSECTION DESIGN.....	20
4.3.1. Location and Design of Access .....	20
4.3.2. Intersection Control .....	21
4.4. TRANSPORTATION DEMAND MANAGEMENT .....	21
4.5. NEIGHBOURHOOD TRAFFIC MANAGEMENT.....	22
4.6. TRANSIT.....	22
4.7. REVIEW OF NETWORK CONCEPT .....	22
4.8. INTERSECTION DESIGN .....	23
4.8.1. Existing Conditions.....	23
4.9. DEVELOPMENT DESIGN .....	24
4.9.1. Design for Sustainable Modes .....	24

4.9.2.	Circulation and Access.....	24
4.9.3.	Total Projected Conditions – Full Build Out.....	25
5.	FINDINGS, CONCLUSIONS AND RECOMMENDATIONS.....	28

## List of Appendices

APPENDIX A – Screening Form
APPENDIX B – Intersection Turning Movement Counts
APPENDIX C – Collision Data and Analysis
APPENDIX D – Other Area Development Traffic Volumes
APPENDIX E – Background Traffic Growth Analysis
APPENDIX F – TDM Checklists
APPENDIX G – Existing Zoning Trip Generation Analysis
APPENDIX H – MMLoS and SYNCHRO Analysis – Existing Conditions
APPENDIX I – Truck Turning Templates
APPENDIX J – MMLoS and SYNCHRO Analysis – Projected Conditions
APPENDIX K – Comment/Response Letter

## List of Figures

Figure 1: Local Context .....	1
Figure 2: Proposed Site Plan .....	2
Figure 3: Ottawa Cycling Plan .....	4
Figure 4: Area Transit Network .....	5
Figure 5: Existing Peak Hour Traffic Volumes* .....	8
Figure 6: Planned LRT Phase 1 and 2 .....	10
Figure 7: Preliminary Design for Bay Street Cycling Facility.....	11
Figure 8: Albert and Slater Redesign .....	12
Figure 9: Study Area .....	13
Figure 10: ‘New’ and ‘Pass-by’ Site-Generated Traffic.....	18
Figure 11: Total Projected Traffic Volumes.....	26

## List of Tables

Table 1: 2009 TRANS Residential Trip Generation Rates .....	14
Table 2: Projected RESIDENTIAL Site Vehicle Trip Generation.....	14
Table 3: RESIDENTIAL Person Trip Generation – Based on existing mode splits .....	15
Table 4: Projected RESIDENTIAL Person Trip Generation.....	15
Table 5: ITE Trip Generation Rates .....	16
Table 6: Modified Person Trip Generation .....	16
Table 7: RETAIL Trip Generation.....	16
Table 8: Total Site Trip Generation.....	17
Table 9: Bay/Slater Historical Background Growth (2007 – 2015) .....	19
Table 10: MMLoS – Boundary Road Segments .....	20
Table 11: Existing Performance at Study Area Intersections .....	23
Table 12: Existing MMLOS – Signalized Study Area Intersections.....	23
Table 13: Total Projected Performance at Study Area Intersections .....	27
Table 14: Projected MMLOS – Signalized Study Area Intersections.....	27



# Transportation Impact Assessment

## 1. SCREENING

It is our understanding that Main and Main has acquired the majority of the downtown city block bounded by Bay Street, Albert Street, Lyon Street and Slater Street from 25007701 Ontario Inc. A Community Transportation Study was previously prepared and submitted by Parsons (May 2017) for 25007701 Ontario Inc.'s proposed development/Site Plan.

Main and Main now have a revised redevelopment plan and a TIA consistent with the City's 2017 TIA Guidelines is required. The Screening Form was completed for submission to City of Ottawa staff in May 2019. All triggers were met based on the number of proposed dwelling units, the location within a Design Priority Area and the development's proximity to existing traffic signals. The estimated number of trips generated by the proposed development is greater than 60 persons per hour, which meets minimum requirements. The Screening Form is provided in Appendix A. The local context of the site is provided as Figure 1 and the proposed Site Plan is provided as Figure 2.

Figure 1: Local Context



CLIENT  
5015218 Ontario Inc. and  
Albert & Main  
Developments Inc.  
100 Atlantic Avenue, Toronto, ON, M6K 1Y4


CONTRACT  
5015218-01  
100 Atlantic Avenue, Toronto, ON, M6K 1Y4  
100 Atlantic Avenue, Toronto, ON, M6K 1Y4  
100 Atlantic Avenue, Toronto, ON, M6K 1Y4

NO.	DESCRIPTION	DATE
01	ISSUED FOR PERMITTING	2020-04-01
02	ISSUED FOR PERMITTING	2020-04-01



PROJECT CONSULTANT  
IBI GROUP  
10000  
10000  
10000

PROJECT	400 Albert Street
PROJECT NO.	585 Slater Street/400 Albert Street
PROJECT NO.	585 Slater Street/400 Albert Street
SCALE	1:1000
SHEET TITLE	GROUND FLOOR PLAN
SHEET NUMBER	A201



## 2. SCOPING REPORT

### 2.1. EXISTING AND PLANNED CONDITIONS

#### 2.1.1. PROPOSED DEVELOPMENT

---

The revised Site Plan consists of three residential buildings; one 23 storey building fronting Albert Street (Tower A) and two buildings fronting Slater Street of 29 storeys (Tower B) and 35 storeys (Tower C). The total number of dwelling units proposed is 930 units; 231 dwelling units are planned for Tower A, 306 units are proposed to Tower B, and 393 units are proposed to Tower C. On the ground floor of Towers A and B a 19,849 ft<sup>2</sup> retail store is proposed and 3,700 ft<sup>2</sup> of ground floor retail is proposed for Tower C. A three-level underground parking garage with 430 vehicle parking spaces and 465 bicycle parking spaces is proposed with full-movement vehicle access to Bay Street. A shared-use drop-off/pick-up laneway is proposed through the site to/from Slater Street and Albert Street, truck loading is proposed to/from Albert Street and garbage pick-up is proposed on-site within the midblock shared-use connection laneway.

The land parcel is located in the Central Area and is zoned as residential fifth density. The northeast corner of the site is planned as a City-owned urban park. The estimated date of occupancy is 2025 to 2026. The previous land use was an office building which has since been demolished and pay-and-display parking lot in the north-east corner that generates approximately 30 to 45 two-way vehicle trips during the peak hours based on a recent count.

#### 2.1.2. EXISTING CONDITIONS

---

##### **Area Road Network**

**Slater Street** is an arterial roadway, which operates one-way in the eastbound direction. Within the study area, the cross-section of Slater Street consists of two passenger vehicle travel lanes and a transit/taxi travel lane with on-street parking provided along the south side of the roadway and on-street parking is permitted during off-peak hours between 3 p.m. – 9 a.m. along the north side of the roadway. The unposted speed limit is understood to be 50 km/h.

**Albert Street** is an arterial roadway, which operates one-way in the westbound direction. Within the study area, the cross-section of Albert Street consists of two passenger vehicle travel lanes and a transit/taxi travel lane with on-street parking provided along the north side of the roadway and on-street parking is permitted during off-peak hours between 3 p.m. – 9 a.m. along the south side of the roadway. The unposted speed limit is understood to be 50 km/h.

**Bay Street** is a local roadway, which operates one-way in the northbound direction. Its vehicular lane arrangement consists of two travel lanes and the unposted speed limit is understood to be 50 km/h.

**Lyon Street** is an arterial roadway, which operates one-way in the southbound direction. Within the study area, the vehicular lane arrangement of Lyon Street consists of three lanes. The unposted speed limit is understood to be 50 km/h.

**Queen Street** is an east-west local roadway, which extends from Bronson Avenue in the west to Elgin Street in the east. Within the study area, Queen Street has a two-lane cross section with on-street parking provided along the south side of the roadways. The posted speed limit is 50 km/h.


**Laurier Avenue** is an arterial roadway with one vehicle travel lane in each direction. Segregated cycle tracks are provided along both sides of the roadway. Within the study area, along Laurier Avenue east of Bay Street a vehicle loading zone is provided along the south side of the roadway. West of Bay Street, on-street parking is provided along the south side of the road. The unposted speed limit is understood to be 50 km/h.



## **Pedestrian/Cycling Network**

With regard to non-auto modes, the subject site is very well serviced by cycling and pedestrian facilities. According to the City's Cycling Plan, Slater Street, Bay Street, Albert Street, Lyon Street and Laurier Avenue are classified as "spine" cycling routes and Queen Street is classified as a local cycling route. Bike lanes are currently provided along the east side of Bay Street, the west side of Lyon Street and segregated bike lanes are provided one block south of Slater Street along both sides of Laurier Avenue (cross-town bikeway). Sidewalks are currently provided along both sides of all study area roadways connecting pedestrians to transit service and other adjacent development/recreational facilities.

Figure 3: Ottawa Cycling Plan



## **Transit Network**

In Fall 2019, the Confederation Line commenced operation from Blair Station in the east to Tunney's Pasture Station in the west. This is the first stage of three planned stages for the Confederation Light Rail Transit Line that runs in the east-west direction. Prior to the opening of the LRT Confederation Line, Bus Rapid Transit (BRT) was provided adjacent to the site along Albert Street and Slater Street in transit only lanes.

The Confederation Line within the vicinity of the site operates underground and the nearest LRT station is located within 300 m or less walking distance from the proposed development at the Queen/Lyon intersection. This station has pedestrian access on Queen Street and Lyon Street, where stairs, escalators and elevators provide access to the underground trains. During peak commuter hours trains are scheduled to run every 4 minutes.

A major bus stop is located adjacent to the Lyon LRT Station entrance at the southwest corner of the Lyon/Queen intersection. This bus stop serves OC Transpo bus routes number 10, 15, 16, 17, 57, 61 and 75 and STO bus route number 20. A bus stop along Bay Street, adjacent to the site, provides service for OC Transpo bus routes number 10, 16, 57, 61 and 75.

Bus route number 10 is considered a 'frequent' route, with service provided every 15 minutes and operates during weekdays and weekends. Bus routes number 15, 16, and 17 are local routes and provide frequent local service on weekdays only (route number 16 provides weekend service). Routes number 57, 61 and 75 provide service for this area only at night (between 1:00 a.m. to 5:00 a.m.) while the LRT Confederation line is not operating.




Figure 4: Area Transit Network



### **Existing Study Area Intersection**


#### **Bay/Albert**

The Bay/Albert intersection is a signalized four-legged intersection. The westbound approach consists of three through lanes (one lane is transit/taxi only) and a right-turn lane. The northbound approach consists of a through lane and a shared through/left-turn lane. Bay Street and Albert Street both operate as one-way roadways in the north and westbound directions, respectively.



#### **Bay/Slater**


The Bay/Slater intersection is a signalized four-legged intersection. The eastbound approach consists of a shared through/left-turn lane and two through lanes (one lane is transit/taxi only). The northbound approach consists of a through lane and a shared through/right-turn lane. Bay Street and Slater Street both operate as one-way roadways in the north and eastbound directions, respectively.



# PARSONS


## Lyon/Albert

The Lyon/Albert intersection is a signalized four-legged intersection. The westbound approach consists of two through lane (one lane is transit/taxi only) and a shared through/left-turn lane. The southbound approach consists of two through lanes and transit lane. Lyon Street and Albert Street operate as one-way roadways in the southbound and westbound directions, respectively. The southbound right-turn movement is prohibited (except for busses) and a transit priority signal is provided.




## Lyon/Slater

The Lyon/Slater intersection is a signalized four-legged intersection. The eastbound approach consists of three through lanes (one lane is transit/taxi only) and a right-turn lane. The southbound approach consists of a shared through/left-turn lane and two through lane. Lyon Street and Slater Street operate as one-way roadways in the southbound and eastbound directions, respectively.




## Bay/Queen

The Bay/Queen intersection is a signalized four-legged intersection. The westbound approach was recently reconstructed to include one through lane and one right-turn lane. The eastbound approach consists of a shared through/left-turn lane. The northbound approach consists of a shared through/left-turn lane and a shared through/right-turn lane. Southbound movements are prohibited at this location as Bay Street operates as a one-way in the northbound direction.



## Laurier/Bay

The Bay/Laurier intersection is a signalized four-legged intersection. The eastbound approach consists of a shared through/left-turn lane. The westbound approach consists of a shared through/right-turn lane. The northbound approach consists of a shared through/left-turn lane and a shared through/right-turn lane. Bay Street operates as a one-way roadway in the northbound direction.




Illustrated as Figure 5, are the most recent weekday morning and afternoon peak hour traffic volumes obtained from the City of Ottawa at the Lyon/Albert, Lyon/Slater, Bay/Queen, Bay/Albert, Bay/Slater, and Bay/Laurier intersections. These peak hour traffic volumes are included as Appendix B and were balanced throughout the network based on the most recent 2019 and 2017 counts. It is noteworthy that at the time of this study these counts are the most recent available and represent pre-LRT conditions. As such, all heavy vehicle movements were removed from Albert Street and Slater Street (old Transitway corridor) to account for the removal of the bus rapid transit (BRT) service on Albert and Slater.

In addition, with the implementation of the LRT and the bus routes serving the Lyon LRT Station, the southbound right-turn movement is no longer permitted for passenger vehicles (busses are permitted) at the Albert/Lyon intersection. As such, the 'existing' southbound right-turning vehicles at this location were reassigned to turn right on Queen Street (60%) and continue south to turn right on Laurier Avenue (40%). This is reflected in the following Figure 5.



**Figure 5: Existing Peak Hour Traffic Volumes\***



\*Heavy vehicle volumes along Slater and Albert Streets are not included in the figure as they represent mostly OC Transpo BRT busses that no longer operate along these roadways.

### **Existing Road Safety Conditions**

Collision history for study area roads (2013 to 2017, inclusive) was obtained from the City of Ottawa and most collisions (74%) involved only property damage, indicating low impact speeds, and 26% involved personal injuries. The primary causes of collisions cited by police include; angle (30%), sideswipe (26%), turning movement (19%), and rear end (10%) type collisions.

A standard unit of measure for assessing collisions at an intersection is based on the number collisions per million entering vehicles (MEV). At intersections within the study area, reported collisions have historically take place at a rate of:

- 0.55/MEV at the Albert/Bay intersection (representing 12 collision in 5 years);
- 0.81/MEV at the Albert/Lyon intersection (representing 26 collision in 5 years);
- 0.44/MEV at the Bay/Queen intersection (representing 9 collision in 5 years);
- 0.39/MEV at the Bay/Laurier intersection (representing 6 collision in 5 years);
- 0.57/MEV at the Slater/Lyon intersection (representing 23 collision in 5 years); and
- 1.40/MEV at the Slater/Bay intersection (representing 33 collision in 5 years).

The Slater/Bay intersection had the highest number and rate of collisions of the study area intersections. Based on the data the following is noteworthy at this location:

- The most common type of collision (12 out of 33) were turning movement collisions. Ten of these collisions involved left-turning vehicles from Slater Street onto Bay Street. While the collision data does not provide clear enough data to understand the details of the collisions, it is noteworthy that 7 out of 10 of these collisions occurred at times when parking in the left curb side lane was permitted. It is possible there is a confusion or conflict occurring with vehicles from the parking lane proceeding while vehicles in the travel lane are turning from the centre lane. With the redesign of the Slater/Bay intersection, this conflict will not occur as there is a proposed bulb-out at the intersection separating the parking lane from the intersection.
- There was one collision involving a pedestrian and an eastbound left-turning vehicle. The collision resulted in non-fatal injuries.
- Two collisions involved cyclists on Bay Street and right-turning vehicles (the improvements to the Bay Street cycling facilities will help alert drivers to cyclists on their righthand side).
- About 30% of collisions were angle type collisions, 15% involved changing lanes (sideswipe collisions) and another 5% were related to rear-end collisions.
- Ten of the 33 collisions occurred during wet or snowy conditions.
- Four collisions involved busses along Slater Street in the BRT lanes (confusion and conflicts with BRT lanes will be reduced when Slater Street is redesigned and BRT is removed from the roadway).

Mid-block on Bay Street, between Albert and Slater, where the parking garage access is proposed, no collisions have occurred along this part of Bay Street in the most recent 5-years of data. Along the Slater Street frontage (between Lyon and Bay) there were 8 reported collisions in the most recent 5-year data. Similarly, along the Albert Street frontage (between Lyon and Bay) there were 8 reported collisions. With regard to active modes, 12 collisions (out of 125) in the study area involved pedestrians, all resulting in non-fatal injuries and three involved cyclists. The source collision data as provided by the City of Ottawa and related analysis is provided as Appendix C.

## **Existing Driveways**

The subject site, which is currently a surface parking lot, has one driveway to Bay Street and two to each of Slater Street and Albert Street. The following provides a list of driveways serving adjacent developments within the study area:

Bay Street		Distance from proposed site driveway and land use	
East Side of roadway		West Side of Roadway	
180 m	Hotel parking	165 m	Church
80 m	151 Bay residential building	75 m	Albert at Bay hotel
7 m	414 Albert Street residential building	4 m	Loading garage for school
1 m	408 Albert Street residential building	80 m	200 Bay Street residential building
80 m	400 Slater Street apartment building	90-122 m	204-216 Bay Street townhomes
96 m	475 Laurier Avenue residential building		

Albert Street	South Side of Roadway		North Side of Roadway	
	1 m	408 Albert Street residential alleyway	15 m	Future development (383 Albert)
	90 m	School alleyway	90 m	Delta hotel
Slater Street	North Side of Roadway		South Side of Roadway	
	200 m	Constitution square parking	15 m	Public parking
	125 m	Constitution square parking		School parking


## 2.1.3. PLANNED CONDITIONS

### Planned Study Area Transportation Network Changes

#### LRT

As previously mentioned, a notable transportation network change within the study area is the completion of Stage 1 of the east-west Confederation LRT, which is the conversion of the City's BRT corridor to LRT between the current Blair transit station and Tunney's Pasture station, connected via a tunnel through the City's Downtown. Stage 2 of the LRT is planned to extend from Trim station in the east to Moodie station in the west. Stage 2 also includes an extension of the existing north-south LRT Trillium Line from South Keys station to Limebank and the Airport. Stage 2 of the LRT expansion is expected to be completed in 2023. The following Figure 6 illustrates the existing Stage 1 and planned Stage 2 of the Confederation and Trillium LRT Lines.

Figure 6: Planned LRT Phase 1 and 2






## Bay Street Cycling Facility

The City of Ottawa is implementing a cycling facility along both sides of Bay Street between Wellington Street and Laurier Avenue, with the estimated time of completion being 2020. The preliminary design plan is provided as Figure 7. The design includes northbound and southbound segregated cycle tracks on either side of the roadway with two lanes of vehicle traffic.


Figure 7: Preliminary Design for Bay Street Cycling Facility



## Albert and Slater Streets

As part of the post LRT implementation, Albert Street and Slater Street are planned to be repurposed. The design will consist of cycling lanes and parking facilities along both sides of the roadway and a removal of the transit-only lanes. The resulting vehicular lane arrangement of the roadway will be two general purpose travel lanes with auxiliary turn lanes at key intersections. The functional design plan within the vicinity of the site is provided as Figure 8.

Figure 8: Albert and Slater Redesign



## Other Area Development

With respect to other area developments, the following development applications have been prepared and/or submitted to the City of Ottawa in the vicinity of the proposed site:

### 343 Gloucester Street

Upscale Homes is proposing to construct a 21-storey residential apartment building located at 343 Gloucester Street. The development consists of 116 residential units and approximately 12 underground parking spots. The Transportation Impact Assessment (prepared by Parsons) projected an increase in person trips of approximately 75 to 85 persons per hour during the peak hours, of which 12 are expected to be vehicle trips.

### 383 Albert Street and 340 Queen Street

Claridge Homes is proposing the construction of a three-tower residential complex consisting of approximately 590 dwelling units, located at the above noted address. The Transportation Impact Study (prepared by Novatech) projected an increase in person trips of 350 to 540 persons per hour during the morning and afternoon peak hours, of which 40 to 70 are expected to be vehicle trips.

## 350 Sparks Street – Hotel and Residential Development

Morguard Real Estate Investment Trust is proposing the redevelopment of the above-noted address. The redevelopment will consist of demolishing the existing hotel and small residential buildings and constructing a new hotel and apartment building instead. The existing office building will remain as is. The Transportation Study projects an increase in two-way vehicle traffic of approximately 35 veh/h during the morning and afternoon peak hours.

## 412 Sparks

Cathedral Hill GP Inc. is proposing the construction of a retirement residential development at the above-noted address. The Transportation Impact Study (prepared by Parsons) projects a total of 40 to 50 persons per hour during the morning and afternoon peak hours, of which 15 to 20 are expected to be vehicle trips.

Given the downtown context of these developments and the high transit and non-auto modes projected for the mixed-use developments, the traffic volumes associated with these local area developments are minimal, however they are included in the projected vehicle analysis and are summarized from their respective TIAs as Appendix D.


## 2.2. STUDY AREA AND TIME PERIODS

### 2.2.1. STUDY AREA

The proposed study area is outlined below and highlighted in Figure 9.

- Queen/Bay intersection;
- Albert/Bay intersection;
- Slater/Bay intersection;
- Laurier/Bay intersection;
- Albert/Lyon intersection;
- Slater/Lyon intersection;
- Albert Street, Lyon Street, Bay Street and Slater Street – adjacent to the site.

Figure 9: Study Area





## 2.2.2. TIME PERIODS

The time periods to be assessed are the weekday morning and afternoon commuter peak hours.

## 2.2.3. HORIZON YEARS

The expected build out date for the proposed development is year 2025. The horizon year 2030, representing 5-years beyond site build out will also be assessed.

## 2.3. EXEMPTION REVIEW

Based on the City's TIA guidelines and the subject site, the following sections of the TIA process will be exempt, unless otherwise directed.

Module	Element	Exemption Consideration
4.1 Development Design	4.1.3 New Streets Network	Not required for applications involving site plans.
4.2 Parking	4.2.2 Spill-over Parking	The proposed number of parking stalls is expected to meet the parking demand.
4.8 Review of Network Concept	All elements	This development is not expected to generate 200 person-trips more than the permitted zoning for the site.

## 3. FORECASTING REPORT

### 3.1. DEVELOPMENT-GENERATED TRAVEL DEMAND

#### 3.1.1. TRIP GENERATION AND MODE SHARES

##### Residential Trip Generation

Appropriate trip generation rates for the proposed development consisting of approximately 930 high-rise dwelling units were obtained from the City's 2009 TRANS Trip Generation – Residential Trip Rates Report. These rates are summarized in Table 1.

Table 1: 2009 TRANS Residential Trip Generation Rates

Land Use	ITE Land Use Code	Trip Rates	
		AM Peak	PM Peak
High-Rise Apartments	ITE 222	T = 0.17(du)	T = 0.16(du)
Notes: T = Average Vehicle Trip Ends du = Dwelling units			

Using the TRANS Trip Generation rates, the total amount of vehicle trips generated by the proposed residential portion of the development (930 units) was calculated. The results are summarized in Table 2.

Table 2: Projected RESIDENTIAL Site Vehicle Trip Generation

Land Use	Area	AM Peak (Veh/h)			PM Peak (Veh/h)		
		In	Out	Total	In	Out	Total
High-Rise Apartments	930 units	44	114	158	86	63	149

As shown in Table 2, a total of 149 to 158 veh/h are projected to travel to/from the proposed development during the weekday morning and afternoon commuter peak hours according to the TRANS Trip Generation 2009 values. Using the TRANS auto trips projected in Table 2, the total person trips projected to travel to/from the proposed development can be calculated based on existing mode splits from the TRANS Trip Generation Report.

Table 3: RESIDENTIAL Person Trip Generation – Based on existing mode splits

Travel Mode	AM Mode Share	AM Peak (Person Trips/h)			PM Mode Share	PM Peak (Person Trips/h)		
		In	Out	Total		In	Out	Total
Auto Driver	27%	44	114	158	23%	86	63	149
Auto Passenger	3%	6	12	18	6%	23	15	38
Transit	27%	44	113	157	29%	109	79	188
Non-motorized	43%	71	181	252	42%	158	115	273
<b>Total Person Trips</b>	<b>100%</b>	<b>165</b>	<b>420</b>	<b>585</b>	<b>100%</b>	<b>376</b>	<b>272</b>	<b>648</b>

As shown in Table 3, based on the TRANS Trip Generation method, the proposed 930 dwelling units are projected to generate approximately 585 and 648 person trips per hour during the weekday morning and afternoon commuter peak hours, respectively. However, these model splits are based on the old transit system, which was an at-grade rapid transit system that used to travel adjacent to the site through the downtown core. The 2019 opening of the LRT is expected to increase the number of transit riders in the area with an ultimate goal of 65% transit riders for developments located within 600 m of LRT stations.

To account for this change in the transit system, revised ‘future’ modal splits are applied to the total person trips in Table 3 (585 and 648 persons/h). As this development is located in the downtown core, the number of non-motorized travelers is expected to remain similar to the existing splits outlined in Table 3, however an increased transit mode has been applied based on the City’s projected targets for Transit-Oriented Developments (TODs), these are shown in Table 4.

Table 4: Projected RESIDENTIAL Person Trip Generation

Travel Mode	Mode Share	AM Peak (Person Trips/h)			PM Peak (Person Trips/h)		
		In	Out	Total	In	Out	Total
Auto Driver	15%	24	64	88	56	41	97
Auto Passenger	5%	9	20	29	19	14	33
Transit	38%	62	161	223	142	104	246
Non-motorized	42%	68	177	245	157	115	272
<b>Total Person Trips</b>	<b>100%</b>	<b>163</b>	<b>422</b>	<b>585</b>	<b>374</b>	<b>274</b>	<b>648</b>
<i>Less Existing Auto Trips</i>		-25	-22	-47	-12	-18	-30
<b>Total ‘New’ Auto Trips</b>		<b>0</b>	<b>42</b>	<b>42</b>	<b>44</b>	<b>23</b>	<b>66</b>

The existing peak hour vehicle trips to/from the parking lot were counted and are shown in Table 4. These were removed from the projected number of vehicle trips for the proposed development. The total net increase in two-way vehicle traffic is expected to be 42 and 66 veh/h during the morning and afternoon weekday peak hours, respectively. The increase in two-way transit person trips along the LRT are projected to be 225 and 245 persons/h and an increase in non-motorized trips of 245 to 270 persons/h is expected with the development of the residential towers.

To further break down the non-motorized or active mode trips, the City of Ottawa’s Origin-Destination (OD) Survey was consulted for the Ottawa Centre area. The OD survey shows the majority (about 90% to 95%) of active mode trips traveling from the area in the morning and to the area in the afternoon are pedestrians. Using these values the proposed

development is projected to generate approximately 220 and 245 pedestrians/h during the morning and afternoon peak hours, respectively, and 25 and 27 cyclists/h during the morning and afternoon peak hours, respectively.

## **Retail Trip Generation**

Appropriate trip generation rates for the proposed retail stores (19,849 ft<sup>2</sup> in Tower A/B and 3,700 ft<sup>2</sup> in Tower C) were obtained from the ITE Trip Generation Manual (10<sup>th</sup> Edition). As the tenants for these retail pads have not been confirmed, for the purposed of this study the Tower A/B retail store is assumed to be a grocery store and the retail land use in Tower C is assumed to be generic shopping centre. The retail land use rates are summarized in Table 5.

Table 5: ITE Trip Generation Rates

Land Use	ITE Land Use Code	Trip Rates	
		AM Peak	PM Peak
Supermarket	ITE 850	T = 3.82(X)	T = 9.24(X)
Shopping Centre	ITE 820	T = 0.94(X)	T = 3.81(X)
Notes: X = 1,000 ft <sup>2</sup> GFA T = Average Vehicle Trip Ends Shopping centre is used as a generic shopping use as the tenant for the space has not been confirmed at this stage of development			

As ITE trip generation surveys only record vehicle trips and typically reflect highly suburban locations (with little to no access by travel modes other than private automobiles), adjustment factors appropriate to the more urban study area context were applied to attain estimates of person trips for the proposed development.

To convert ITE vehicle trip rates to person trips, an auto occupancy factor and a non-auto trip factor were applied to the ITE vehicle trip rates. Based on the TIA Guidelines, the average vehicle occupancy factor is 1.15 and the default non-auto mode share is 10%. As such, a combined factor of approximately 1.28 can be used to convert ITE's vehicle trip rates to person-trip rates. The person-trip generation for the proposed retail developments is summarized in Table 6.

Table 6: Modified Person Trip Generation

Land Use	Area	AM Peak (Person Trip/h)			PM Peak (Person Trip/h)		
		In	Out	Total	In	Out	Total
Supermarket	19,849 ft <sup>2</sup>	58	39	97	119	116	235
Shopping Centre	3,700 ft <sup>2</sup>	2	2	4	8	10	18
<b>Total Person Trips</b>		<b>60</b>	<b>41</b>	<b>101</b>	<b>127</b>	<b>126</b>	<b>253</b>

## **Mode Shares Retail**

Based on the City's targets for TOD areas and given the retail is expected to serve residents and employees in the area, the future mode splits for the proposed development are summarized in Table 7. The person trip generation for the retail components of the site (Table 6) were then reduced by these modal shares and are shown in Table 7. A pass-by rate of 35% was used based on the ITE Trip Generation Handbook, which indicates an average pass-by rate of 36% for the supermarket land use and 34% for the shopping centre land use.

Table 7: RETAIL Trip Generation

Travel Mode	Mode Share	AM Peak (Person Trips/h)			PM Peak (Person Trips/h)		
		In	Out	Total	In	Out	Total
Auto Driver	15%	9	7	16	20	19	39
Auto Passenger	5%	3	2	5	6	7	13
Transit	30%	18	12	30	38	37	75
Non-motorized	50%	30	20	50	63	63	126
Total Person Trips	100%	60	41	101	127	126	253
Less Pass-by (35%)		-3	-3	-6	-7	-7	-14
<b>Total 'New' Auto Trips</b>		<b>6</b>	<b>4</b>	<b>10</b>	<b>13</b>	<b>12</b>	<b>25</b>



As shown in Table 7, the resulting number of potential 'new' two-way vehicle trips for the proposed retail development is approximately 10 and 25 veh/h during the weekday morning and afternoon peak hours, respectively.

The number of pedestrian and cyclist trips travelling to/from the retail land use was estimated based on the OD Survey results for pedestrians and cyclists travelling to the area in the morning peak hour, from the area in the afternoon peak hour, and within the area during both peak hours. The retail land uses are projected to generate approximately 35 and 86 pedestrians/h during the morning and afternoon peak hours, respectively, and 15 and 40 cyclists/h during the morning and afternoon peak hours, respectively.

## **Total Trip Generation**

The combined projected trips for the entire development (residential and commercial) are summarized in Table 8.

Table 8: Total Site Trip Generation

Travel Mode	AM Peak (Person Trips/h)			PM Peak (Person Trips/h)		
	In	Out	Total	In	Out	Total
Auto Driver	33	71	104	76	60	136
Auto Passenger	12	22	34	25	21	46
Transit	80	173	253	180	141	321
Non-motorized	98	197	295	220	178	398
<b>Total Person Trips</b>	<b>223</b>	<b>463</b>	<b>686</b>	<b>501</b>	<b>400</b>	<b>901</b>
<i>Less Retail Auto Pass-by (35%)</i>	-3	-3	-6	-7	-7	-14
<i>Less Existing Site Auto Trips</i>	-25	-22	-47	-12	-18	-30
<b>Total 'New' Auto Trips</b>	<b>6</b>	<b>46</b>	<b>51</b>	<b>57</b>	<b>35</b>	<b>92</b>

As shown in Table 8, the total number of new person trips to the development is expected to be 686 and 901 persons/h during the morning and afternoon peak hours, respectively. The projected increase in vehicle traffic is expected to be 50 and 92 veh/h during the weekday morning and afternoon peak hours, respectively. This increase in vehicle traffic is the 'net' difference between the existing traffic traveling to/from the surface parking lot on the subject site and the proposed development projected peak hour vehicle trips.

The transit rider increase is estimated to be 253 and 320 persons/h during the peak hours. With regards to active modes, approximately 255 and 330 pedestrians per hour and 40 and 68 cyclists per hour are projected to travel to/from the proposed development.

### **3.1.2. TRIP DISTRIBUTION**


The projected 'new' and 'pass-by' trips were distributed based on the site's connectivity to the existing road network and our knowledge of the surrounding area. The resultant distribution is assumed to be:

- 55% to/from the west via Slater Street, Albert Street, Kent Street, and Laurier Avenue; and
  - 45% to/from the north via Lyon Street, Bay Street, and Queen Street.
- 100%

## 3.1.3. TRIP ASSIGNMENT

A full movement driveway connection to Bay Street is proposed to serve the subject development's underground parking lot. There is a proposed pick-up/drop-off driveway connection to/from Slater Street and Albert Street and truck loading is proposed to Albert Street. For the purposes of this analysis, the vehicle trips are assigned to the Bay Street access only as the number of vehicle trips to/from the Albert and Slater Street driveways are expected to be negligible in terms of capacity analysis. As 'pass-by' trips are trips that are already travelling along the roadway, they have not been added to the network, but they have been added to the site's driveway. 'New' and 'Pass-by' site-generated vehicle trips are assigned to the study area network and illustrated as Figure 10.

Figure 10: 'New' and 'Pass-by' Site-Generated Traffic



## 3.2. BACKGROUND NETWORK TRAVEL DEMANDS

### 3.2.1. TRANSPORTATION NETWORK PLANS

---

Refer to Section 2.1.3 Planned Conditions – Planned Study Area Transportation Network Changes.

### 3.2.2. BACKGROUND GROWTH

---

The following background traffic growth (summarized in Table 9) was calculated based on historical traffic count data (years 2007, 2011 and 2015) provided by the City of Ottawa at the Bay/Slater intersection. Detailed background traffic growth analysis is included as Appendix E. Because of LRT construction, using more current data would not reflect actual growth conditions as there were many changes due to construction within the study area in the past four years.

Table 9: Bay/Slater Historical Background Growth (2007 – 2015)

Time Period	Percent Annual Change				
	North Leg	South Leg	East Leg	West Leg	Overall
8 hrs	-1.10%	-2.30%	-2.00%	-2.00%	-1.84%
AM Peak	-3.44%	-4.49%	-2.13%	-2.01%	-2.48%
PM Peak	-1.12%	-2.78%	-2.15%	-5.32%	-2.77%

As show in Table 9, the Bay/Slater intersection has experienced negative overall growth (calculated as weighted average) over an 8-year time period. As an average background traffic growth rate of -2% was calculated, and since the study area is located within the downtown core, directly adjacent to the LRT, no overall growth rate has been applied on forecasted background traffic volumes. This is consistent with the anticipated decline in vehicular traffic within this area outline in the TMP.

### 3.2.3. OTHER DEVELOPMENTS

---

Refer to Section 2.1.4 Planned Conditions – Other Area Developments.

## 3.3. DEMAND RATIONALIZATION

---

As part of the City's plans to increase density in areas located close to the LRT, this development is expected to increase people trips, however, the number of vehicle trips is not expected to significantly increase in the study area due to this development. In addition, vehicular traffic in the Central Area is also expected to plateau or decrease over time with the continued expansion of the Confederation Line LRT. Therefore, there are no anticipated concerns with network capacity and traffic demand related to or associated with the proposed development.

## 4. STRATEGY REPORT

### 4.1. PARKING

#### 4.1.1. PARKING SUPPLY

---

Refer to Section 4.1.1

## 4.2. BOUNDARY STREET DESIGN

As shown in Section 2.1.3, the City of Ottawa is implementing a cycling facility along both sides of Bay Street between Wellington Street and Laurier Avenue, with the estimated time of completion being 2020. The design includes northbound and southbound segregated cycle tracks on either side of the roadway with two lanes of vehicle traffic.

In addition, as part of the LRT implementation, Albert Street and Slater Street are planned to be repurposed. The design will consist of cycling lanes and parking facilities along both sides of the roadway and a removal of the transit-only lanes. The resulting vehicle lane arrangement of the roadway will be two general purpose travel lanes with auxiliary turn lanes at key intersections. The design plans for all three boundary streets are shown as Figures 7 and 8 of this report.

The proposed development will have three driveways intersecting these three boundary roadways. The Bay Street driveway connection will be right-in/right-out only and may require utility pole relocation. The proponent will work with the City to address the design of the driveway during the construction of the Bay Street cycle lanes. With regard to the Albert Street and Slater Street driveways, they will not conflict with the City's plans to redesign these roadways. The sidewalks that cross the three proposed driveways are to be depressed concrete with the final width/location to be determined by the City during the redesign of the adjacent streets.

The following Table 10 provides the MMLoS analysis for the boundary streets adjacent to the site. It is noteworthy that the analysis assumes the proposed future roadway designs as outlined in this report and includes the Site Plan's designs. The detailed analysis is provided as Appendix J and assesses the side of the street directly adjacent to the site.

Table 10: MMLoS – Boundary Road Segments

Road Segment	Level of Service							
	Pedestrian (PLOS)		Bicycle (BLOS)		Transit (TLOS)		Truck (TKLOS)	
	PLOS	Target	BLOS	Target	TLOS	Target	TKLOS	Target
Bay Street	A	A	A	B	D	No Target	A	No Target
Lyon Street	B	A	C	C	D	No Target	C	No Target
Slater Street	A	A	A	C	D	No Target	A	D
Albert Street	A	A	A	C	D	No Target	A	D

As shown in Table 10, the existing or proposed boundary streets meet the target levels of service for bicycles, transit and truck routes. The pedestrian level of service target is high (PLOS 'A') as the site is located in the central area. The sidewalks adjacent to the site along Lyon and Bay are proposed to be 2 m or more with cycle lanes/tracks as boulevards. The sidewalks along Slater and Albert, adjacent to the site are proposed to be approximately 4 m or more wide. The PLOS results in a score of 'A' for all adjacent boundary roads except Lyon Street because of the number of vehicles travelling along Lyon Street is higher than the other roadways.

With regard to boundary street road safety, there were no collisions in the most recent 5-years of available data along Bay Street. There were eight collisions, mid-block along each of Albert Street and Slater Street between Bay Street and Lyon Street in the 5-year period (which equates to one or two collisions per year on average). One collision along Albert Street involved a pedestrian, resulting in non-fatal injuries. The majority (88%) of collisions resulted in property damage only, while two of the collisions resulted in non-fatal injuries.

## 4.3. ACCESS INTERSECTION DESIGN

### 4.3.1. LOCATION AND DESIGN OF ACCESS

The proposed access garage ramp is located along Bay Street approximately 1 m from the northern property line. It is mid-block between Slater and Albert Street, approximately 25 m north of Slater Street and approximately 30 m south of Albert



Street. According to the City's Private Approach By-Laws, the driveway should be 60 m from these arterial roadways. However, Bay Street is the boundary street with the lowest vehicle volumes and is designated a local roadway, whereas the other three boundary streets are arterial roadways with higher traffic volumes. As such, the driveway is proposed to Bay Street and is located as far from the two adjacent arterial roadways as possible.

There is an existing alleyway leading to a residential parking garage located approximately 1 m to the north of the site's proposed Bay Street driveway and the adjacent building's garage access is located approximately 7 m north of the proposed access. The driveways to the adjacent properties were observed with very low traffic volumes and there is an existing driveway to the surface parking lot (on the site) that operates well. Bay Street operates as a one-way roadway, minimizing the amount of turning movement conflicts that can occur at driveways and the road is straight with good sight lines. As such, the distance between the proposed site's driveway and the adjacent buildings' driveways does not create a traffic hazard. Given the combination of good sight lines, relatively low traffic volumes and one-way Bay Street operation there are no safety concerns for the location of this driveway and a By-Law variance may be required. A utility pole will likely require relocation for the driveway implementation.

The width of the garage access driveway to Bay Street is noted as 6 m, which meets the City's By-Law requirements. The ramp grade for the proposed parking garage access/egress starts 4.6 m from the property line and 8.9 m from the roadway. The ramp grade is planned at 15% with transition grades at the top and bottom of the ramp.

With regards to the proposed Albert Street shared-use driveway, it will replace an existing driveway, which is located mid-block between Bay Street and Lyon Street and is directly adjacent to the property line. The adjacent property's driveway is located along Bay Street, as such there is no conflict between the proposed site driveway and the adjacent property's driveway. In addition, the location of this driveway does not create a traffic hazard and the one-way operation of Albert Street reduces the number of conflict of vehicles entering and exiting the site. The driveway's width is approximately 8 m wide, which meets the City's By-Law requirement. Based on the foregoing, the location of the Albert Street share-use driveway does not cause any safety issues and a By-Law variance may be required.

A truck loading bay is proposed to serve the retail store and is located approximately 5 m east of the proposed Albert Street shared-use vehicle access. Given the truck access is for loading only and will have extremely low traffic volumes, its location close to the vehicle shared-use access driveway is considered acceptable. The truck loading bay width is approximately 9 m wide and trucks will back in from Albert Street and leave driving forward.

The Slater Street shared-use driveway is also located mid-block between Bay Street and Lyon Street and is approximately 8 m wide. The two Albert and Slater shared-use driveways connect through the site and are intended for pedestrian and cycling activity and some drop-off/pick-up vehicle movements. The connection is intended for vehicles to operate in both directions and there is no parking access to these driveways. As such, the vehicle volumes will be relatively low and the driveway should be constructed as a woonerf to indicate that the area is designed mainly for pedestrians and cyclists and vehicles should proceed with caution.

#### 4.3.2. INTERSECTION CONTROL

---

Based on the location and operation of all three driveways, STOP control on the minor approach (site) only is recommended. No additional turn lanes or intersection control is warranted.

#### 4.4. TRANSPORTATION DEMAND MANAGEMENT

---

Depending on the nature of a development, Transportation Demand Management (TDM) strategies have the potential to be an integral part of a planned development in order to address and support the City's policies with regard to TDM. For this particular site, its location within 600 m of the LRT Confederation Line and its location within the downtown core are considered very advantageous in lessening the reliance on the private automobile. The close proximity of significant

employment and residential uses will also contribute to a high walk percentage. The proximity of dedicated on-road cycling facilities will contribute to maximizing the bicycle mode split.

As part of the development, a pathway for pedestrians, cyclists and pick-up/drop-off vehicles is proposed through the site to provide walking and biking routes to local amenities and the LRT station. This pathway is proposed to be constructed as a woonerf to indicate it is a shared-use area and drivers should proceed with caution.

A number of other TDM measures could also be considered to reduce vehicle use, including:

- ride-sharing programs (e.g. community forum where residents can register/arrange carpooling or on-site parking can be reserved for VRTUCAR cars);
- carpool incentives (e.g. reserved preferred parking for carpooling residents and carpool drop-off areas);
- providing preferential parking for hybrid vehicles that are less harmful to the environment; and
- provide an on-site transit information booth to direct visitors and encourage residents to utilize transit.

The TDM strategy checklists are attached as Appendix F.

## 4.5. NEIGHBOURHOOD TRAFFIC MANAGEMENT

---

TDM strategies are designed to reduce the number of passenger vehicles travelling to/from the proposed site. However, if the number of vehicles travelling to/from the proposed development is higher than projected, there are no significant impacts on the residential, institutional, recreational or natural land uses within the vicinity of the site. Given the downtown context, there is already significant traffic in the area, as well all the study area intersections are projected to operate at acceptable levels of service and are expected to continue to do so if more traffic is added to the roadways.

## 4.6. TRANSIT

---

Transit service within the vicinity of the site is currently provided by the LRT located underground through the downtown core. The closest LRT station is located on the southwest quadrant of the Queen/Lyon intersection, which is an approximate 100 m to 215 m walk for residents and patrons of the proposed site. A bus stop is also located adjacent to the site along Bay Street providing service to OC Transpo bus routes number 10 and 16.

Based on the trip generation analysis, an increase in transit ridership associated with the proposed development is estimated to be 250 to 320 two-way person trips per hour during the commuter peak hours. This increase in transit ridership is consistent with the City's goals in increasing density in areas around the LRT.

## 4.7. REVIEW OF NETWORK CONCEPT

---

Based on the existing residential fifth density zoning, the increase in GFA of the proposed site compared to what is permitted is calculated to be approximately 121,520 ft<sup>2</sup> (assuming three buildings of maximum height of 27 storeys under existing zoning). This increase in GFA was then broken down into dwelling units, assuming similar sized units as the proposed site. The increase in dwelling units for the proposed site compared to the existing zoning was calculated to be approximately 220 apartment units.

The retail uses are permitted under the current zoning, so the difference in the trip generation is assumed to be the increase in number of units proposed (compared to what is permitted). As such, trip generation analysis was performed for the calculated 220 units. This detailed trip generation analysis is provided as Appendix G. The results show that the additional 220 units generate approximately 140 to 150 additional person trips during the peak hours. As such, this section is exempt as the proposed site is not expected to generate more than 200 more person trips than what is allotted under the current zoning.

## 4.8. INTERSECTION DESIGN

### 4.8.1. EXISTING CONDITIONS

The following Table 11 provides a summary of existing traffic operations at study area intersections based on the SYNCHRO (V10) traffic analysis software. The subject intersections were assessed in terms of the volume-to-capacity (v/c) ratio and the corresponding Level of Service (LoS) for the critical movement(s). The intersections 'as a whole' were assessed based on a weighted v/c ratio and the SYNCHRO model output of existing conditions is provided within Appendix H.

Table 11: Existing Performance at Study Area Intersections

INTERSECTION	WEEKDAY AM PEAK (PM PEAK)					
	CRITICAL MOVEMENT			INTERSECTION 'AS A WHOLE'		
	LOS	MAX. V/C OR AVG. DELAY (S)	MOVEMENT	DELAY (S)	LOS	V/C
Bay/Slater	A(A)	0.53(0.52)	EBT(NBT)	9.4(11.2)	A(A)	0.50(0.47)
Bay/Albert	A(A)	0.40(0.50)	NBT(NBT)	12.8(10.1)	A(A)	0.31(0.45)
Lyon/Slater	B(A)	0.70(0.54)	EBT(SBT)	15.2(7.2)	B(A)	0.63(0.51)
Lyon/Albert	C(C)	0.75(0.80)	SBT(SBT)	16.4(21.3)	B(B)	0.64(0.68)
Bay/Queen	C(A)	0.79(0.49)	EBT(EBT)	15.0(8.1)	A(A)	0.55(0.46)
Bay/Laurier	A(B)	0.48(0.65)	EBT(WBT)	16.4(16.5)	A(A)	0.38(0.47)
Notes: Analysis of signalized intersections assumes a PHF of 0.95 and a saturation flow rate of 1800 veh/h/lane. Study area located within Central Business District (CBD).						

As shown in Table 11, SYNCHRO analysis indicates that study area intersections 'as a whole' are currently operating at LoS 'B' or better during both weekday commuter peak hours. With regard to 'critical movements' at study area intersections, they are currently operating at LoS 'C' or better during both peak hours.

Field observations at study area intersections confirm the above findings. However, minor delays to vehicles travelling along all study area roads were observed, caused by signalized intersections, loading and unloading vehicles, vehicles negotiating on-street parking, pedestrians, cyclists, etc. As the study area is located in the Downtown Core, these minor delays are considered acceptable.

### **Multi-Modal Level of Service – Existing Conditions**

The MMLOS analysis for the signalized intersections within the study area is summarized in Table 12. The existing detailed MMLoS analysis is provided as Appendix H.

Table 12: Existing MMLoS – Signalized Study Area Intersections

Intersection	Level of Service									
	Pedestrian (PLOS)		Bicycle (BLOS)		Transit (TLOS)		Truck (TkLoS)		Vehicle (LoS)	
	PLOS	Target	BLOS	Target	TLOS	TkLoS	TkLoS	Target	LoS	Target
Bay/Laurier	C	A	C	A	No bus routes		E	D	B	E
Bay/Slater	C	A	E	B	B	No target	D	D	A	E
Bay/Albert	C	A	D	B	C	No target	D	D	A	E
Bay/Queen	B	A	C	B	B	No target	E	No target	C	E
Albert/Lyon	C	A	E	C	C	D	D	D	C	E
Slater/Lyon	C	A	E	C	B	No target	D	D	B	E

The letters identified in red text in Table 12 do not meet the MMLoS targets for their designated area (central area). However, the plans for Bay, Albert, and Slater Streets will likely improve the bicycle and pedestrian levels of service (however the target PLOS of 'A' is impossible to achieve at signalized intersections). This is assessed in the following section 4.9.3.

## 4.9. DEVELOPMENT DESIGN

### 4.9.1. DESIGN FOR SUSTAINABLE MODES

---

#### *Vehicle and Bicycle Parking*

A total of 348 residential vehicle parking spaces and 82 visitor parking spaces (total of 430 spaces) are proposed to serve the subject development within three levels of underground parking. As the site is located within Area Z, as identified in Schedule 1A of the City's Zoning By-Law, there is no required minimum parking supply for residents, however a minimum of 82 visitor parking spaces is required according to the City's By-Law requirements. No parking is required for the retail land uses and as such the proposed amount of parking meets the City's requirements. It is noteworthy that the amount of parking also does not exceed the maximum amount of parking allowed for developments within 600 m of LRT stations. The parking spaces are noted as being 5.2 m in length and 2.6 m in width, which are the City's By-Law requirements.

With regard to bicycle parking, according to the City's By-Law requirements, bicycle parking should be provided at a rate of 0.5 per dwelling unit and at a rate of 1 per 250 m<sup>2</sup> for the retail land uses. Based on these rates a minimum of 465 bicycle parking spaces are provided for the residential land uses and 9 spots are provided for retail land uses. Residential bicycle parking is proposed to the underground parking garage. Nine retail bicycle parking spaces are proposed at-grade.

#### *Transit and Pedestrians*

To connect pedestrians to transit service and other nearby employment, shopping and recreation opportunities, sidewalks are currently provided along both sides of all study area roads. The site is located within close proximity to the Lyon LRT Station which currently provides access to Line 1/Confederation Line which operates frequently providing east/west service between Blair Station and Tunney's Pasture Station.

An urban park is proposed in the northeast corner of the site and a mid-block connection is proposed to connect pedestrians, cyclists and drop-off/pick-up vehicles through the site from Albert Street to Slater Street. It is recommended that this connection be constructed as a woonerf to promote pedestrian activity and alert drivers to pedestrians and cyclists along the roadway connection.

With regard to pedestrian access, all the exterior access doors are within 400 m walking distance to the Lyon LRT Station. The following shows the walking distance from each door to the Lyon LRT Station:

Slater	Western entrance	215 m
	Eastern entrance	160 m
Albert	Eastern entrance	100 m
	Western entrance	110 m
Lyon	Southern entrance	115 m
	Northern entrance	100 m
Mid-block connections		180 to 200 m

### 4.9.2. CIRCULATION AND ACCESS

---

A right-in/right-out driveway is proposed to Bay Street to connect to the underground parking garage. As Bay Street is a one-way roadway in the northbound direction, vehicles can turn northbound right into the driveway and must exit heading



north as well. As mentioned in Section 2.1.3, a northbound cycle track is planned along the east side of Bay Street in front of the proposed driveway. As such, it is recommended to provide green thermoplastic across the driveway to alert drivers of the cycle track.

Truck loading is proposed mid-block along Albert Street within the on-site truck loading bay. Garbage for all three towers will be stored in the underground parking garages and brought to ground level for pick up. Garbage pick-up is proposed to occur at-grade and on-site. The garbage loading bay is located at the northeast corner of Tower C along the mid-block shared use connection. Truck turning templates are provided herein as Appendix I and show that the garbage truck will access the site via Slater Street and flag men will likely be required for the truck movements on Albert Street.

A pick-up/drop-off area is proposed along the shared use multi-function connection located mid-block that extends through the site from Albert Street to Slater Street. This link is planned as a two-way driveway through the site so that drop-off/pick-up vehicles are not required to turn around on-site. As this connection/link is intended for multi-modal use, it is recommended that it be constructed as a woonerf to promote active modes and reduce vehicle speeds.


Through consultation with the City, we are advised that Road Modification Applications (RMA) are not required for the site's proposed driveway connections.

#### **4.9.3. TOTAL PROJECTED CONDITIONS – FULL BUILD OUT**

---

The total projected traffic volumes at full site build-out were derived by superimposing the site-generated traffic volumes (Figure 10) and the other area development traffic volumes (Appendix D) onto existing traffic volumes (Figure 5). The resulting total projected traffic volumes are illustrated in Figure 11.

Figure 11: Total Projected Traffic Volumes



The following Table 13 provides a summary of the total projected operations at the study area intersection based on the SYNCHRO (V10) traffic analysis software. As the study area will have undergone significant redesign along Albert Street, Slater Street and Bay Street, some assumption in signal timing for the future condition were made, including no right-turn-on-red restrictions anywhere where cars cross a cycle-track and advanced pedestrian/cycle phases at all cycle tracks. The SYNCHRO model output of total projected conditions is provided within Appendix J.

Table 13: Total Projected Performance at Study Area Intersections

Intersection	Weekday AM Peak (PM Peak)					
	Critical Movement			Intersection 'As a whole'		
	LoS	max. v/c or avg. delay (s)	Movement	Delay (s)	LoS	v/c
Bay/Slater	A(B)	0.59(0.65)	EBT(NBT)	13.1(17.4)	A(A)	0.58(0.56)
Bay/Albert	A(A)	0.52(0.59)	NBT(NBT)	15.3(14.7)	A(A)	0.41(0.55)
Lyon/Slater	C(A)	0.72(0.59)	EBT(SBT)	13.7(10.1)	B(A)	0.65(0.55)
Lyon/Albert	C(D)	0.78(0.87)	SBT(SBT)	18.7(29.0)	B(C)	0.66(0.75)
Bay/Queen	E(C)	0.93(0.72)	EBT(EBT)	27.3(16.7)	B(A)	0.65(0.58)
Bay/Laurier	A(B)	0.49(0.68)	EBT(WBT)	19.2(19.8)	A(A)	0.40(0.50)
Note: Analysis of signalized intersections assumes a PHF of 1.0 and a saturation flow rate of 1800 veh/h/lane.						

As shown in Table 13, the study area intersections are projected to continue to operate 'as a whole' at acceptable levels of service once the development is constructed. All critical movements are projected to operate at acceptable levels of service (LoS 'E' or better).

## Multi-Modal Level of Service – Projected Conditions

Based on the proposed changes to the study area roadways, the projected MMLoS results of the study area are summarized in Table 14. The detailed analysis is provided as Appendix J.

Table 14: Projected MMLoS – Signalized Study Area Intersections

Intersection	Level of Service									
	Pedestrian (PLOS)		Bicycle (BLOS)		Transit (TLOS)		Truck (TkLOS)		Vehicle (LoS)	
	PLOS	Target	BLOS	Target	TLOS	TkLOS	TkLOS	Target	LoS	Target
Bay/Laurier	C	A	A	A	No bus routes		E	D	B	E
Bay/Slater	C	A	A	B	B	No target	D	D	C	E
Bay/Albert	C	A	A	B	C	No target	D	D	A	E
Bay/Queen	B	A	B	B	B	No target	E	No target	E	E
Albert/Lyon	B	A	D	C	C	D	D	D	D	E
Slater/Lyon	B	A	A	C	B	No target	D	D	C	E

As shown in Table 14, the majority of the bike, transit, truck and vehicle level of service targets are projected to be met with the proposed changes to the road network. The exceptions being BLOS at Albert/Lyon where no cycle lane is proposed north of Albert Street because of the transit only lane and the TkLOS for Bay/Laurier (which is related to trucks turning onto Bay Street, which is not a truck route, and trucks serving the subject site will not need to use Bay Street).

With regard to pedestrian level of service, as mentioned previously the target PLOS 'A' is impossible to achieve because of the calculation required for the delay score. The PETSI (Pedestrian Exposure at Traffic Signalized Intersections) scores at Bay/Laurier, Bay/Slater and Bay/Albert are projected to be PLOS 'A' in the future (the delay scores are PLOS 'C' because of signal timing). PETSI scores at Bay/Queen, Albert/Lyon and Slater/Lyon are PLOS 'B' due to longer crossing distances along Lyon Street and Queen Street.

The Bay Street intersections result in a PLOS 'C' because of the delay score. These scores are lower because the east-west arterials (Slater, Albert and Laurier) are given more green time and as such pedestrians crossing these arterials are delayed slightly longer. With the implementation of the LRT and the removal of the transit way from Slater and Albert Streets, the green times may be adjusted at the discretion of the City's Traffic Signals Group and the delay score may increase to a PLOS 'B' (PLOS 'A' for delay cannot be achieved).

## 5. FINDINGS, CONCLUSIONS AND RECOMMENDATIONS

### Existing Conditions

- The proposed development is located in the downtown core, within close proximity of the LRT Lyon Station;
- Bike lanes are currently provided along the east side of Bay Street and segregated bike lanes are provided one block south of Slater Street along both sides of Laurier Avenue. Sidewalks are currently provided along both sides of all study area roadways connecting pedestrians to transit service and other adjacent development/recreational facilities;
- Study area intersections 'as a whole' are currently operating at LoS 'B' or better during the morning and afternoon peak hours, with critical movements operating at LoS 'C' or better. These results meet the MMLoS guidelines minimum target level of operation for vehicles;
- Pedestrian, cyclist and transit level of service MMLoS target are not currently being met at the majority of study area intersection, however, with the construction of the LRT, the redesign of Albert and Slater Street and the implementation of cycle tracks on Bay Street, these MMLoS targets are expected to improve;

### Projected Conditions

- Stage 1 of the LRT recently commenced operation in the Fall of 2019. The Lyon LRT Station at the Queen/Lyon intersection is approximately 1½ blocks north of the subject site;
- With the implementation of the LRT, the City has plans to redesign the existing Transitway along Albert and Slater Streets. The plans include cycle tracks and reduced number of vehicle travel lanes;
- As part of a City project, cycle tracks are planned along Bay Street;
- Given the study area has experienced negative traffic growth within the past few years and given the planned improvements for transit within the vicinity of the site, the future projected background traffic volumes are expected to be similar to the existing traffic volumes and no future background traffic growth was applied;
- The proposed development is projected to generate 'new' two-way vehicle volumes of approximately 50 and 92 veh/h during the weekday morning and afternoon peak hours, respectively. Transit ridership is projected to increase by 253 and 320 persons/h during the morning and afternoon peak hours, respectively. An estimated 255 to 330 additional pedestrians/h are expected to travel to/from the development during peak hours and approximately 40 to 68 cyclists/h are projected to be generated by the proposed development;
- At full site development of all three towers, study area intersections 'as a whole' are projected to operate similar to existing conditions, with acceptable levels of service of LoS 'C' or better during the peak hours and critical movements of LoS 'E' or better. These results meet the City's MMLoS targets for vehicle capacity performance;
- Given the proposed changes to Albert Street, Slater Street and Bay Street adjacent to the site, the MMLoS for pedestrians, cyclists and transit modes are expected to increase for the future condition;



- The pedestrian levels of service at study area intersections are projected to range between PLOS 'B' to 'C'. As PLOS 'A' is impossible to achieve due to the delay score there are no further recommendations provided to improve the PLOS scores. It is noteworthy that the PETSI scores are 'A' for intersections along Bay Street (except Bay/Queen) and a PETSI score of 'B' is achieved at Bay/Queen, Albert/Lyon and Slater/Lyon;
- The cycling level of service scores all meet the target MMLoS with the exception of the BLOS at the Albert/Lyon intersection. This is due to the lack of cycling facilities along the north leg of Lyon Street which was recently redesigned with larger sidewalks to accommodate the LRT Station;
- The transit level of service along the roadways is projected to meet the targets for roadway with no transit priority. It is noteworthy that the grade-separated LRT is considered to achieve an TLoS 'A';
- Given the site's close proximity to the Lyon LRT Station, TDM measures should be implemented for the development to encourage the use of transit and non-auto modes. The development will have good connections to Albert Street, Slater Street, Bay Street and Lyon Street all with sidewalks and Albert Street, Slater Street and Bay Street will have cycle tracks. The Lyon LRT Station is located approximately 100 to 200 m from the proposed development and the downtown location of the site is ideal for active mode commuting;

## Site Plan Review

- The proposed supply of vehicle and bicycle parking spaces meet the City's by-law minimum and maximum requirements;
- The parking garage driveway to Bay Street meets the City's By-Law requirements in terms of width and the driveway is offset as much as possible from the adjacent street's intersection;
  - The driveway is located approximately 1 m from the adjacent building's driveway, however due to the downtown context, the one-way operation of Bay Street and the relatively low number of vehicles using the driveway, its location is acceptable;
- The truck loading is provided along Albert Street and garbage pick-up is proposed at-grade and on-site via the mid-block shared use connection. This shared use connection is proposed for drop-off/pick-up activity as well as garbage pick-up. Vehicles will be able to continue through the site to Slater Street instead of needing to turn around on site;
  - This connection will function as a public space and a pedestrian connection and should be designed as a woonerf to alert drivers that it is a multi-purpose space;
- The sidewalks that cross the three proposed driveways are to be depressed concrete and 2.0m to 3.0m wide, with the final width/location to be determined by the City during the redesign of the adjacent streets;
- The ramp grade for the proposed parking garage access/egress starts 4.5 m from the property line and about 8.9 m from the roadway edge. The ramp grade is planned at 15% with transition grades at the top and bottom of the ramp.

Comments were received from the City of Ottawa in Fall 2019 regarding this TIA. The TIA was subsequently updated per the City's comments. This is the updated TIA, which was finalized in May 2020. The comment and response letter is included as Appendix K.

# PARSONS

Based on the foregoing, the proposed development fits well into the context of the surrounding area, and its location and design serves to promote use of walking, cycling, and transit modes, thus supporting City of Ottawa policies, goals and objectives with respect to redevelopment, intensification and modal share.


Therefore, the proposed 400 Albert development is recommended from a transportation perspective.

Prepared By:



André Sponder, P.Eng.  
Transportation Engineer

Reviewed by:



Ronald Jack, P.Eng.  
Senior Transportation Engineer



# Appendix A

Screening Form

---

City of Ottawa 2017 TIA Guidelines

Date

23-May-19

## TIA Screening Form

Project

400 Albert Street

Project Number

908489-50053

Results of Screening	Yes/No
Development Satisfies the Trip Generation Trigger	Yes
Development Satisfies the Location Trigger	Yes
Development Satisfies the Safety Trigger	Yes

### Module 1.1 - Description of Proposed Development

Municipal Address	400 Albert Street/393 Slater Street
Description of location	Bounded by Albert, Slater, Lyon and Bay
Land Use	Primarily residential units
Development Size	820 residential units with 3,000 sq. m of office and 5,320 sq. m of retail
Number of Accesses and Locations	Midlock on each of Albert, Slater, Bay
Development Phasing	3 phases
Buildout Year	2025/2026
Sketch Plan / Site Plan	See attached

### Module 1.2 - Trip Generation Trigger

Land Use Type	Townhomes or Apartments
Development Size	820 Units
Trip Generation Trigger Met?	Yes

### Module 1.3 - Location Triggers

Development Proposes a new driveway to a boundary street that is designated as part of the City's Transit Priority, Rapid Transit, or Spine Bicycle Networks (See Sheet 3)	Yes
Development is in a Design Priority Area (DPA) or Transit-oriented Development (TOD) zone. (See Sheet 3)	Yes
Location Trigger Met?	Yes

### Module 1.4 - Safety Triggers

Posted Speed Limit on any boundary road	<80 km/h
Horizontal / Vertical Curvature on a boundary street limits sight lines at a proposed driveway	No
A proposed driveway is within the area of influence of an adjacent traffic signal or roundabout (i.e. within 300 m of intersection in rural conditions, or within 150 m of intersection in urban/ suburban conditions) or within auxiliary lanes of an intersection;	Yes
A proposed driveway makes use of an existing median break that serves an existing site	No
There is a documented history of traffic operations or safety concerns on the boundary streets within 500 m of the development	Yes
The development includes a drive-thru facility	No
Safety Trigger Met?	Yes





# Appendix B

Traffic Count Data

---



## Public Works - Traffic Services

### Turning Movement Count - Peak Hour Diagram


#### ALBERT ST @ BAY ST

**Survey Date:** Thursday, June 18, 2015

**Start Time:** 07:00

**WO No:** 34725

**Device:** Jamar Technologies, Inc



**Comments**

## Public Works - Traffic Services

## Turning Movement Count - Peak Hour Diagram


**ALBERT ST @ BAY ST**

**Survey Date:** Thursday, June 18, 2015

**Start Time:** 07:00

**WO No:** 34725

**Device:** Jamar Technologies, Inc



## Comments



# Transportation Services - Traffic Services

## Turning Movement Count - Peak Hour Diagram


### ALBERT ST @ LYON ST

**Survey Date:** Thursday, June 11, 2015

**Start Time:** 07:00

**WO No:** 34679

**Device:** Jamar Technologies, Inc



**Comments**

## Turning Movement Count - Peak Hour Diagram


### ALBERT ST @ LYON ST

**Survey Date:** Thursday, June 11, 2015

**Start Time:** 07:00

**WO No:** 34679

**Device:** Jamar Technologies, Inc





## Public Works - Traffic Services

## Turning Movement Count - Peak Hour Diagram


## BAY ST @ SLATER ST

**Survey Date:** Thursday, June 25, 2015

**Start Time:** 07:00

**WO No:** 34784

**Device:** Jamar Technologies, Inc



## Comments

## Public Works - Traffic Services

## Turning Movement Count - Peak Hour Diagram


## BAY ST @ SLATER ST

**Survey Date:** Thursday, June 25, 2015

**Start Time:** 07:00

**WO No:** 34784

**Device:** Jamar Technologies, Inc



## Comments



# Transportation Services - Traffic Services

## Turning Movement Count - Peak Hour Diagram


### BAY ST @ QUEEN ST

**Survey Date:** Thursday, March 07, 2019

**Start Time:** 07:00

**WO No:** 38428

**Device:** Miovision



## Turning Movement Count - Peak Hour Diagram


### BAY ST @ QUEEN ST

**Survey Date:** Thursday, March 07, 2019

**Start Time:** 07:00

**WO No:** 38428

**Device:** Miovision





# Transportation Services - Traffic Services

## Turning Movement Count - Full Study Peak Hour Diagram


### BAY ST @ LAURIER AVE

**Survey Date:** Wednesday, April 05, 2017

**Start Time:** 07:00

**WO No:** 36858

**Device:** Miovision






**Survey Date:** Wednesday, April 05, 2017

**Start Time:** 07:00

**WO No:** 36858

**Device:** Miovision



## Transportation Services - Traffic Services

## Turning Movement Count - Peak Hour Diagram


**LYON ST @ SLATER ST**

**Survey Date:** Thursday, March 07, 2019

**Start Time:** 07:00

**WO No:** 38427

**Device:** Miovision



## Comments

## Turning Movement Count - Peak Hour Diagram


**LYON ST @ SLATER ST**

**Survey Date:** Thursday, March 07, 2019

**Start Time:** 07:00

**WO No:** 38427

Device: Miovision



## Comments

# Appendix C

Collision Data and Analysis

---

#### Total Area

Classification of Accident	Rear End	Turning Movement	Sideswipe	Angle	Approaching	Single Vehicle (other)	Single vehicle (Unattended vehicle)	Other	Total	
P.D. only	10	22	29	27	0	0	3	2	93	74%
Non-fatal injury	3	2	4	11	0	12	0	0	32	26%
Non reportable	0	0	0	0	0	0	0	0	0	0%
Total	13	24	33	38	0	12	3	2	125	100%
	#4 or 10%	#3 or 19%	#2 or 26%	#1 or 30%	#8 or 0%	#5 or 10%	#6 or 2%	#7 or 2%		

#### Lyon/Slater

Years	Total # Collisions	24 Hr AADT Veh Volume	Days	Collisions/MEV
2013-2017	23	22,020	1825	0.57

Classification of Accident	Rear End	Turning Movement	Sideswipe	Angle	Approaching	Single Vehicle (other)	Single vehicle (Unattended vehicle)	Other	Total	
P.D. only	2	2	4	10	0	0	0	0	18	78%
Non-fatal injury	1	0	0	2	0	2	0	0	5	22%
Non reportable	0	0	0	0	0	0	0	0	0	0%
Total	3	2	4	12	0	2	0	0	23	100%
	13%	9%	17%	52%	0%	9%	0%	0%		

#### Bay/Slater

Years	Total # Collisions	24 Hr AADT Veh Volume	Days	Collisions/MEV
2013-2017	33	12,910	1825	1.40

Classification of Accident	Rear End	Turning Movement	Sideswipe	Angle	Approaching	Single Vehicle (other)	Single vehicle (Unattended vehicle)	Other	Total	
P.D. only	2	12	3	9	0	0	0	0	26	79%
Non-fatal injury	0	2	2	2	0	1	0	0	7	21%
Non reportable	0	0	0	0	0	0	0	0	0	0%
Total	2	14	5	11	0	1	0	0	33	100%
	6%	42%	15%	33%	0%	3%	0%	0%		

#### Bay/Queen

Years	Total # Collisions	24 Hr AADT Veh Volume	Days	Collisions/MEV
2013-2017	9	11,330	1825	0.44

Classification of Accident	Rear End	Turning Movement	Sideswipe	Angle	Approaching	Single Vehicle (other)	Single vehicle (Unattended vehicle)	Other	Total	
P.D. only	1	2	4	0	0	0	0	1	8	89%
Non-fatal injury	0	0	1	0	0	0	0	0	1	11%
Non reportable	0	0	0	0	0	0	0	0	0	0%
Total	1	2	5	0	0	0	0	1	9	100%
	11%	22%	56%	0%	0%	0%	0%	11%		

#### Albert/Bay

Years	Total # Collisions	24 Hr AADT Veh Volume	Days	Collisions/MEV
2013-2017	12	11,863	1825	0.55

Classification of Accident	Rear End	Turning Movement	Sideswipe	Angle	Approaching	Single Vehicle (other)	Single vehicle (Unattended vehicle)	Other	Total	
P.D. only	1	1	3	2	0	0	0	0	7	58%
Non-fatal injury	0	0	0	3	0	2	0	0	5	42%
Non reportable	0	0	0	0	0	0	0	0	0	0%
Total	1	1	3	5	0	2	0	0	12	100%
	8%	8%	25%	42%	0%	17%	0%	0%		

#### Albert/Lyon

Years	Total # Collisions	24 Hr AADT Veh Volume	Days	Collisions/MEV
2013-2017	26	17,516	1825	0.81

Classification of Accident	Rear End	Turning Movement	Sideswipe	Angle	Approaching	Single Vehicle (other)	Single vehicle (Unattended vehicle)	Other	Total	
P.D. only	1	3	7	3	0	0	0	1	15	58%
Non-fatal injury	1	0	1	4	0	5	0	0	11	42%
Non reportable	0	0	0	0	0	0	0	0	0	0%
Total	2	3	8	7	0	5	0	1	26	100%
	8%	12%	31%	27%	0%	19%	0%	4%		

#### Bay/Laurier

Years	Total # Collisions	24 Hr AADT Veh Volume	Days	Collisions/MEV
2013-2017	6	8,480	1825	0.39

Classification of Accident	Rear End	Turning Movement	Sideswipe	Angle	Approaching	Single Vehicle (other)	Single vehicle (Unattended vehicle)	Other	Total	
P.D. only	2	1	1	1	0	0	0	0	5	83%
Non-fatal injury	0	0	0	0	0	1	0	0	1	17%
Non reportable	0	0	0	0	0	0	0	0	0	0%
Total	2	1	1	1	0	1	0	0	6	100%
	33%	17%	17%	17%	0%	17%	0%	0%		



# City Operations - Transportation Services

## Collision Details Report - Public Version

**From:** January 1, 2013 **To:** December 31, 2017

**Location:** ALBERT ST @ BAY ST

**Traffic Control:** Traffic signal

**Total Collisions:** 12

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2013-Feb-14, Thu,20:11	Clear	Rear end	P.D. only	Dry	West	Pulling away from shoulder or curb	Unknown	Other motor vehicle	
					West	Turning right	Passenger van	Other motor vehicle	
2013-Mar-08, Fri,18:53	Clear	Angle	Non-fatal injury	Dry	North	Going ahead	Automobile, station wagon	Other motor vehicle	
					West	Going ahead	Automobile, station wagon	Other motor vehicle	
2013-May-02, Thu,21:41	Clear	Sideswipe	P.D. only	Dry	West	Changing lanes	Automobile, station wagon	Other motor vehicle	
					West	Going ahead	Municipal transit bus	Other motor vehicle	
2014-Jan-03, Fri,15:30	Clear	Sideswipe	P.D. only	Dry	West	Changing lanes	Automobile, station wagon	Other motor vehicle	
					West	Going ahead	Automobile, station wagon	Other motor vehicle	
2014-Nov-17, Mon,15:40	Snow	Angle	P.D. only	Wet	North	Going ahead	Unknown	Other motor vehicle	
					West	Going ahead	Automobile, station wagon	Other motor vehicle	
2015-Apr-16, Thu,19:50	Clear	Sideswipe	P.D. only	Dry	West	Unknown	Pick-up truck	Other motor vehicle	



					West	Unknown	Pick-up truck	Other motor vehicle	
2015-Apr-27, Mon,07:50	Clear	Turning movement	P.D. only	Dry	West	Turning right	Bus (other)	Other motor vehicle	
					West	Stopped	Delivery van	Other motor vehicle	
2015-Jun-21, Sun,10:30	Clear	Angle	Non-fatal injury	Dry	North	Going ahead	Pick-up truck	Other motor vehicle	
					West	Going ahead	Pick-up truck	Other motor vehicle	
2016-Mar-15, Tue,21:13	Rain	SMV other	Non-fatal injury	Wet	North	Turning left	Automobile, station wagon	Pedestrian	1
2016-May-23, Mon,15:58	Clear	Angle	P.D. only	Dry	North	Going ahead	Automobile, station wagon	Other motor vehicle	
					West	Going ahead	Pick-up truck	Other motor vehicle	
2017-Jan-23, Mon,21:30	Clear	SMV other	Non-fatal injury	Dry	North	Turning left	Automobile, station wagon	Pedestrian	1
2017-Sep-21, Thu,22:48	Clear	Angle	Non-fatal injury	Dry	North	Going ahead	Automobile, station wagon	Other motor vehicle	
					West	Going ahead	Police vehicle	Other motor vehicle	

**Location:** ALBERT ST @ LYON ST

**Traffic Control:** Traffic signal

**Total Collisions:** 26

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2013-Jun-01, Sat,15:05	Clear	SMV other	Non-fatal injury	Dry	West	Turning left	Automobile, station wagon	Pedestrian	1

2013-Jun-11, Tue,13:05	Clear	Turning movement	P.D. only	Wet	West	Turning left	Automobile, station wagon	Other motor vehicle
					West	Going ahead	Automobile, station wagon	Other motor vehicle
2013-Jul-17, Wed,07:43	Clear	Sideswipe	P.D. only	Dry	South	Going ahead	Automobile, station wagon	Other motor vehicle
					South	Going ahead	Automobile, station wagon	Other motor vehicle
2013-Jul-24, Wed,11:15	Clear	Angle	Non-fatal injury	Dry	South	Going ahead	Automobile, station wagon	Other motor vehicle
					West	Going ahead	Pick-up truck	Other motor vehicle
2013-Jul-24, Wed,11:20	Clear	Sideswipe	P.D. only	Dry	West	Going ahead	Ambulance	Other motor vehicle
					West	Stopped	Pick-up truck	Other motor vehicle
2013-Aug-08, Thu,07:59	Clear	Turning movement	P.D. only	Dry	West	Turning left	Passenger van	Other motor vehicle
					West	Going ahead	Truck - dump	Other motor vehicle
2013-Oct-15, Tue,19:38	Clear	Sideswipe	P.D. only	Dry	West	Changing lanes	Automobile, station wagon	Other motor vehicle
					West	Going ahead	Municipal transit bus	Other motor vehicle
2013-Nov-10, Sun,12:12	Rain	Angle	Non-fatal injury	Wet	West	Going ahead	Pick-up truck	Other motor vehicle
					South	Going ahead	Delivery van	Other motor vehicle

2013-Dec-13, Fri,14:34	Clear	Other	P.D. only	Dry	East	Pulling onto shoulder or toward curb	Automobile, station wagon	Other motor vehicle	
					West	Going ahead	Municipal transit bus	Other motor vehicle	
2014-Mar-21, Fri,22:18	Clear	SMV other	Non-fatal injury	Dry	West	Turning left	Other	Pedestrian	1
2014-Sep-16, Tue,09:00	Clear	Angle	Non-fatal injury	Dry	South	Going ahead	Pick-up truck	Other motor vehicle	
					West	Going ahead	Automobile, station wagon	Other motor vehicle	
					West	Going ahead	Municipal transit bus	Other motor vehicle	
2014-Oct-16, Thu,12:16	Clear	SMV other	Non-fatal injury	Dry	West	Turning left	Passenger van	Pedestrian	1
2014-Oct-20, Mon,21:40	Rain	Angle	P.D. only	Wet	South	Going ahead	Automobile, station wagon	Other motor vehicle	
					West	Going ahead	Automobile, station wagon	Other motor vehicle	
2014-Nov-05, Wed,16:25	Clear	Sideswipe	P.D. only	Dry	West	Changing lanes	Automobile, station wagon	Other motor vehicle	
					West	Going ahead	Automobile, station wagon	Other motor vehicle	
2014-Dec-16, Tue,11:20	Clear	Angle	Non-fatal injury	Wet	West	Going ahead	Automobile, station wagon	Other motor vehicle	
					South	Going ahead	Automobile, station wagon	Other motor vehicle	
2015-Feb-20, Fri,15:13	Clear	Sideswipe	P.D. only	Wet	South	Going ahead	Automobile, station wagon	Other motor vehicle	

					South	Stopped	Automobile, station wagon	Other motor vehicle
2015-Mar-10, Tue,16:17	Clear	Angle	P.D. only	Dry	North	Reversing	Pick-up truck	Other motor vehicle
					West	Going ahead	Municipal transit bus	Other motor vehicle
2015-Mar-16, Mon,15:13	Clear	Rear end	Non-fatal injury	Dry	South	Going ahead	Automobile, station wagon	Other motor vehicle
					South	Stopped	Automobile, station wagon	Other motor vehicle
2015-Aug-26, Wed,11:24	Clear	Turning movement	P.D. only	Dry	West	Turning left	Automobile, station wagon	Other motor vehicle
					West	Going ahead	Unknown	Other motor vehicle
2015-Sep-06, Sun,17:27	Clear	Rear end	P.D. only	Dry	South	Changing lanes	Passenger van	Other motor vehicle
					South	Slowing or stopping	Pick-up truck	Other motor vehicle
2015-Nov-02, Mon,11:15	Clear	Sideswipe	Non-fatal injury	Dry	South	Changing lanes	Tow truck	Other motor vehicle
					South	Stopped	Automobile, station wagon	Other motor vehicle
2016-Mar-09, Wed,14:05	Rain	Angle	P.D. only	Wet	South	Going ahead	Automobile, station wagon	Other motor vehicle
					West	Going ahead	Municipal transit bus	Other motor vehicle
2016-Jun-18, Sat,18:30	Clear	Sideswipe	P.D. only	Dry	West	Changing lanes	Automobile, station wagon	Other motor vehicle

					West	Going ahead	Automobile, station wagon	Other motor vehicle	
2016-Jul-27, Wed,07:15	Clear	SMV other	Non-fatal injury	Dry	West	Turning left	Automobile, station wagon	Pedestrian	1
2017-Apr-21, Fri,19:16	Clear	Sideswipe	P.D. only	Dry	West	Pulling onto shoulder or toward curb	Fire vehicle	Other motor vehicle	
					West	Stopped	Automobile, station wagon	Other motor vehicle	
2017-Sep-12, Tue,07:47	Clear	SMV other	Non-fatal injury	Dry	West	Turning left	Municipal transit bus	Pedestrian	1

**Location:** ALBERT ST btwn BAY ST & LYON ST N

**Traffic Control:** No control

**Total Collisions:** 8

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuver	Vehicle type	First Event	No. Ped
2013-Mar-03, Sun,13:00	Snow	SMV unattended vehicle	P.D. only	Loose snow	Unknown	Unknown	Unknown	Unattended vehicle	
2013-Oct-03, Thu,17:37	Clear	Sideswipe	P.D. only	Dry	West	Changing lanes	Automobile, station wagon	Other motor vehicle	
					West	Going ahead	Pick-up truck	Other motor vehicle	
2014-Jan-24, Fri,21:31	Clear	Sideswipe	P.D. only	Dry	West	Stopped	Automobile, station wagon	Other motor vehicle	
					West	Going ahead	Unknown	Other motor vehicle	
2014-May-22, Thu,10:33	Clear	Sideswipe	P.D. only	Dry	West	Stopped	Automobile, station wagon	Other motor vehicle	
					West	Going ahead	Municipal transit bus	Other motor vehicle	

2015-Feb-12, Thu,09:58	Snow	Turning movement	P.D. only	Loose snow	West	Turning right	Automobile, station wagon	Other motor vehicle	
					West	Going ahead	Municipal transit bus	Other motor vehicle	
2016-Jun-11, Sat,04:30	Clear	SMV other	Non-fatal injury	Dry	West	Pulling away from shoulder or curb	Automobile, station wagon	Pedestrian	1
2017-May-25, Thu,16:00	Rain	Angle	P.D. only	Wet	South	Turning right	Pick-up truck	Other motor vehicle	
					West	Changing lanes	Automobile, station wagon	Other motor vehicle	
2017-Dec-28, Thu,08:55	Clear	Rear end	Non-fatal injury	Ice	West	Slowing or stopping	Municipal transit bus	Other motor vehicle	
					West	Stopped	Municipal transit bus	Other motor vehicle	

**Location:** BAY ST @ LAURIER AVE

**Traffic Control:** Traffic signal

**Total Collisions:** 6

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2014-Oct-16, Thu,16:49	Rain	Rear end	P.D. only	Wet	West	Slowing or stopping	Automobile, station wagon	Other motor vehicle	
					West	Stopped	Automobile, station wagon	Other motor vehicle	
2014-Oct-20, Mon,07:35	Clear	Sideswipe	P.D. only	Dry	East	Going ahead	Automobile, station wagon	Other motor vehicle	
					East	Stopped	Construction equipment	Other motor vehicle	
2014-Dec-01, Mon,22:00	Clear	Rear end	P.D. only	Dry	West	Unknown	Unknown	Other motor vehicle	



					West	Stopped	Automobile, station wagon	Other motor vehicle	
2015-Jan-08, Thu,10:01	Snow	Turning movement	P.D. only	Ice	North	Turning left	Automobile, station wagon	Other motor vehicle	
					North	Going ahead	Automobile, station wagon	Other motor vehicle	
2015-Aug-17, Mon,13:08	Clear	Angle	P.D. only	Dry	North	Going ahead	Automobile, station wagon	Other motor vehicle	
					East	Going ahead	Automobile, station wagon	Other motor vehicle	
2017-Mar-28, Tue,15:24	Clear	SMV other	Non-fatal injury	Dry	East	Going ahead	Pick-up truck	Pedestrian	1

**Location:** BAY ST @ QUEEN ST

**Traffic Control:** Traffic signal

**Total Collisions:** 9

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuver	Vehicle type	First Event	No. Ped
2013-Feb-14, Thu,10:21	Clear	Sideswipe	P.D. only	Wet	North	Changing lanes	Automobile, station wagon	Other motor vehicle	
					North	Going ahead	Automobile, station wagon	Other motor vehicle	
2014-Jul-17, Thu,09:33	Clear	Turning movement	P.D. only	Dry	North	Turning left	Passenger van	Other motor vehicle	
					North	Going ahead	Automobile, station wagon	Other motor vehicle	
2015-Jan-13, Tue,10:21	Clear	Turning movement	P.D. only	Ice	East	Turning left	Pick-up truck	Other motor vehicle	
					West	Going ahead	Automobile, station wagon	Other motor vehicle	

2015-Feb-04, Wed,12:53	Snow	Sideswipe	P.D. only	Packed snow	North	Turning left	Pick-up truck	Other motor vehicle
					North	Turning left	Automobile, station wagon	Other motor vehicle
2015-Jun-15, Mon,07:33	Clear	Sideswipe	P.D. only	Dry	North	Changing lanes	Automobile, station wagon	Other motor vehicle
					North	Going ahead	Automobile, station wagon	Other motor vehicle
2015-Jun-18, Thu,07:05	Clear	Other	P.D. only	Dry	East	Reversing	Unknown	Other motor vehicle
					West	Stopped	Automobile, station wagon	Other motor vehicle
2016-Mar-16, Wed,15:30	Clear	Rear end	P.D. only	Wet	East	Going ahead	Pick-up truck	Other motor vehicle
					East	Stopped	Pick-up truck	Other motor vehicle
2016-Apr-14, Thu,06:33	Clear	Sideswipe	Non-fatal injury	Dry	East	Pulling away from shoulder or curb	Passenger van	Other motor vehicle
					East	Going ahead	Automobile, station wagon	Other motor vehicle
2017-Nov-11, Sat,22:45	Clear	Sideswipe	P.D. only	Dry	North	Pulling away from shoulder or curb	Automobile, station wagon	Other motor vehicle
					North	Going ahead	Automobile, station wagon	Other motor vehicle

**Location:** BAY ST @ SLATER ST

**Traffic Control:** Traffic signal

**Total Collisions:** 33

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2013-Jan-23, Wed,07:31	Clear	Angle	P.D. only	Dry	North	Going ahead	Automobile, station wagon	Other motor vehicle	

					East	Going ahead	Municipal transit bus	Other motor vehicle
2013-Jan-28, Mon,10:50	Snow	Turning movement	P.D. only	Loose snow	North	Overtaking	Automobile, station wagon	Other motor vehicle
					North	Turning left	Automobile, station wagon	Other motor vehicle
2013-May-31, Fri,22:35	Clear	Rear end	P.D. only	Dry	East	Going ahead	Automobile, station wagon	Other motor vehicle
					East	Stopped	Automobile, station wagon	Other motor vehicle
2013-Jun-17, Mon,14:59	Clear	Angle	Non-fatal injury	Dry	North	Going ahead	Pick-up truck	Other motor vehicle
					East	Going ahead	Automobile, station wagon	Other motor vehicle
2013-Jun-25, Tue,16:15	Clear	Sideswipe	Non-fatal injury	Dry	East	Changing lanes	Automobile, station wagon	Other motor vehicle
					East	Going ahead	Motorcycle	Other motor vehicle
2013-Jul-10, Wed,08:00	Clear	Turning movement	Non-fatal injury	Dry	North	Turning right	Pick-up truck	Cyclist
					North	Going ahead	Bicycle	Other motor vehicle
2013-Aug-20, Tue,18:42	Clear	Turning movement	P.D. only	Dry	North	Turning right	Pick-up truck	Cyclist
					North	Going ahead	Bicycle	Other motor vehicle
2013-Aug-29, Thu,08:35	Clear	Angle	P.D. only	Dry	North	Turning right	Automobile, station wagon	Other motor vehicle
					East	Going ahead	Automobile, station wagon	Other motor vehicle

					East	Going ahead	Automobile, station wagon	Other motor vehicle
2013-Nov-14, Thu,16:31	Clear	Sideswipe	P.D. only	Dry	East	Changing lanes	Pick-up truck	Other motor vehicle
					East	Going ahead	Municipal transit bus	Other motor vehicle
2013-Nov-22, Fri,17:12	Rain	Sideswipe	P.D. only	Wet	East	Changing lanes	Pick-up truck	Other motor vehicle
					East	Going ahead	Automobile, station wagon	Other motor vehicle
2013-Dec-12, Thu,07:50	Clear	Turning movement	P.D. only	Dry	East	Turning left	Tow truck	Other motor vehicle
					East	Turning left	Automobile, station wagon	Other motor vehicle
2014-Feb-08, Sat,18:46	Clear	Turning movement	P.D. only	Wet	East	Turning left	Automobile, station wagon	Other motor vehicle
					East	Going ahead	Passenger van	Other motor vehicle
2014-Mar-10, Mon,16:48	Clear	Sideswipe	P.D. only	Dry	East	Changing lanes	Pick-up truck	Other motor vehicle
					East	Going ahead	Passenger van	Other motor vehicle
2014-Mar-22, Sat,09:55	Snow	Angle	P.D. only	Packed snow	East	Going ahead	Passenger van	Other motor vehicle
					North	Going ahead	Pick-up truck	Other motor vehicle
2014-Sep-25, Thu,15:14	Clear	Angle	P.D. only	Dry	East	Slowing or stopping	Automobile, station wagon	Other motor vehicle

					North	Going ahead	Automobile, station wagon	Other motor vehicle
2014-Nov-11, Tue,10:48	Clear	Turning movement	P.D. only	Dry	East	Turning left	Automobile, station wagon	Other motor vehicle
					East	Going ahead	Automobile, station wagon	Other motor vehicle
2015-Jan-29, Thu,17:40	Snow	Rear end	P.D. only	Loose snow	East	Going ahead	Pick-up truck	Other motor vehicle
					East	Stopped	Automobile, station wagon	Other motor vehicle
2015-Feb-06, Fri,17:00	Clear	Turning movement	P.D. only	Slush	East	Going ahead	Automobile, station wagon	Other motor vehicle
					East	Turning left	Automobile, station wagon	Other motor vehicle
2015-Feb-13, Fri,18:58	Clear	Sideswipe	Non-fatal injury	Slush	East	Changing lanes	Automobile, station wagon	Other motor vehicle
					East	Going ahead	Police vehicle	Other motor vehicle
2015-Mar-06, Fri,13:07	Clear	Angle	P.D. only	Dry	East	Going ahead	Automobile, station wagon	Other motor vehicle
					North	Going ahead	Passenger van	Other motor vehicle
2015-Mar-11, Wed,19:05	Clear	Turning movement	P.D. only	Dry	East	Turning left	Automobile, station wagon	Other motor vehicle
					East	Going ahead	Automobile, station wagon	Other motor vehicle
2015-Apr-12, Sun,21:39	Clear	Angle	Non-fatal injury	Dry	East	Going ahead	Automobile, station wagon	Other motor vehicle

					North	Going ahead	Automobile, station wagon	Other motor vehicle	
2015-Apr-13, Mon,07:20	Clear	SMV other	Non-fatal injury	Dry	East	Turning left	Automobile, station wagon	Pedestrian	1
2015-Apr-15, Wed,17:09	Clear	Angle	P.D. only	Dry	East	Going ahead	Automobile, station wagon	Other motor vehicle	
					North	Going ahead	Automobile, station wagon	Other motor vehicle	
2015-Aug-07, Fri,23:25	Clear	Turning movement	P.D. only	Dry	East	Turning left	Municipal transit bus	Other motor vehicle	
					East	Going ahead	Pick-up truck	Other motor vehicle	
2015-Aug-15, Sat,18:55	Clear	Turning movement	P.D. only	Dry	East	Turning left	Automobile, station wagon	Other motor vehicle	
					East	Going ahead	Automobile, station wagon	Other motor vehicle	
2016-Mar-12, Sat,10:35	Clear	Turning movement	P.D. only	Dry	North	Turning right	Automobile, station wagon	Other motor vehicle	
					North	Turning right	Truck - closed	Other motor vehicle	
2016-Apr-26, Tue,01:51	Clear	Angle	P.D. only	Dry	North	Going ahead	Automobile, station wagon	Other motor vehicle	
					East	Going ahead	Automobile, station wagon	Other motor vehicle	
2016-Jul-01, Fri,20:06	Rain	Turning movement	Non-fatal injury	Wet	East	Turning left	Pick-up truck	Other motor vehicle	
					East	Going ahead	Municipal transit bus	Other motor vehicle	



2017-Jul-11, Tue,23:24	Clear	Turning movement	P.D. only	Dry	East	Turning left	Automobile, station wagon	Other motor vehicle
					East	Going ahead	Automobile, station wagon	Other motor vehicle
2017-Sep-07, Thu,16:28	Rain	Angle	P.D. only	Wet	East	Going ahead	Passenger van	Other motor vehicle
					North	Going ahead	Automobile, station wagon	Other motor vehicle
2017-Nov-10, Fri,11:13	Clear	Turning movement	P.D. only	Dry	East	Turning right	Automobile, station wagon	Other motor vehicle
					East	Going ahead	Pick-up truck	Other motor vehicle
2017-Dec-05, Tue,14:43	Clear	Angle	P.D. only	Wet	North	Going ahead	Automobile, station wagon	Other motor vehicle
					East	Going ahead	Municipal transit bus	Other motor vehicle

**Location:** LYON ST @ SLATER ST

**Traffic Control:** Traffic signal

**Total Collisions:** 23

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuver	Vehicle type	First Event	No. Ped
2013-Jan-12, Sat,23:04	Clear	Sideswipe	P.D. only	Wet	East	Changing lanes	Passenger van	Other motor vehicle	
					East	Going ahead	Municipal transit bus	Other motor vehicle	
2013-Jan-28, Mon,14:44	Snow	Rear end	P.D. only	Loose snow	South	Slowing or stopping	Automobile, station wagon	Cyclist	
					South	Slowing or stopping	Bicycle	Other motor vehicle	
2013-May-17, Fri,08:13	Clear	Sideswipe	P.D. only	Dry	East	Going ahead	Unknown	Other motor vehicle	

					East	Stopped	Municipal transit bus	Other motor vehicle
2013-Jun-20, Thu,17:54	Clear	Rear end	Non-fatal injury	Dry	South	Going ahead	Pick-up truck	Other motor vehicle
					South	Stopped	Automobile, station wagon	Other motor vehicle
2013-Sep-12, Thu,06:15	Rain	Angle	P.D. only	Wet	South	Going ahead	Pick-up truck	Other motor vehicle
					East	Going ahead	Pick-up truck	Other motor vehicle
2014-Apr-09, Wed,20:42	Clear	Rear end	P.D. only	Dry	South	Going ahead	Unknown	Other motor vehicle
					South	Going ahead	Automobile, station wagon	Other motor vehicle
2014-Jun-18, Wed,18:33	Clear	Angle	P.D. only	Dry	South	Going ahead	Automobile, station wagon	Other motor vehicle
					East	Going ahead	Automobile, station wagon	Other motor vehicle
2014-Sep-17, Wed,17:13	Clear	Sideswipe	P.D. only	Dry	East	Going ahead	Unknown	Other motor vehicle
					East	Stopped	Municipal transit bus	Other motor vehicle
2014-Oct-12, Sun,13:51	Clear	Angle	P.D. only	Dry	East	Going ahead	Automobile, station wagon	Other motor vehicle
					South	Going ahead	Automobile, station wagon	Other motor vehicle
2014-Nov-06, Thu,22:58	Rain	Angle	P.D. only	Wet	South	Going ahead	Automobile, station wagon	Other motor vehicle

					East	Going ahead	Automobile, station wagon	Other motor vehicle
2014-Nov-14, Fri,20:33	Clear	Angle	P.D. only	Dry	South	Going ahead	Pick-up truck	Other motor vehicle
					East	Going ahead	Passenger van	Other motor vehicle
2014-Nov-23, Sun,18:20	Clear	Sideswipe	P.D. only	Wet	East	Changing lanes	Automobile, station wagon	Other motor vehicle
					East	Going ahead	Automobile, station wagon	Other motor vehicle
2014-Dec-14, Sun,15:51	Clear	Angle	P.D. only	Wet	East	Going ahead	Automobile, station wagon	Other motor vehicle
					South	Going ahead	Automobile, station wagon	Other motor vehicle
2014-Dec-20, Sat,10:50	Clear	Angle	P.D. only	Dry	North	Going ahead	Automobile, station wagon	Other motor vehicle
					East	Going ahead	Pick-up truck	Other motor vehicle
2015-Jan-13, Tue,10:26	Clear	Turning movement	P.D. only	Dry	East	Turning left	Pick-up truck	Other motor vehicle
					East	Going ahead	Pick-up truck	Other motor vehicle
2015-Feb-03, Tue,11:50	Snow	Angle	P.D. only	Ice	South	Going ahead	Automobile, station wagon	Other motor vehicle
					East	Going ahead	Passenger van	Other motor vehicle
2015-Feb-14, Sat,15:09	Snow	Angle	Non-fatal injury	Loose snow	South	Going ahead	Automobile, station wagon	Other motor vehicle

					East	Going ahead	Municipal transit bus	Other motor vehicle	
2015-May-28, Thu,17:41	Clear	Turning movement	P.D. only	Dry	South	Turning left	Municipal transit bus	Other motor vehicle	
					South	Going ahead	Automobile, station wagon	Other motor vehicle	
2015-Nov-24, Tue,21:53	Clear	Angle	P.D. only	Dry	South	Going ahead	Automobile, station wagon	Other motor vehicle	
					East	Going ahead	Automobile, station wagon	Other motor vehicle	
2016-Jul-16, Sat,11:13	Clear	Angle	P.D. only	Dry	South	Going ahead	Automobile, station wagon	Other motor vehicle	
					East	Going ahead	Automobile, station wagon	Other motor vehicle	
2016-Aug-29, Mon,21:45	Clear	SMV other	Non-fatal injury	Dry	South	Turning left	Automobile, station wagon	Pedestrian	1
2016-Nov-05, Sat,01:38	Rain	Angle	Non-fatal injury	Wet	East	Going ahead	Automobile, station wagon	Other motor vehicle	
					South	Going ahead	Automobile, station wagon	Other motor vehicle	
2017-May-19, Fri,14:34	Clear	SMV other	Non-fatal injury	Dry	East	Turning right	Passenger van	Pedestrian	1

**Location:** SLATER ST btwn BAY ST & LYON ST N

**Traffic Control:** No control

**Total Collisions:** 8

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuver	Vehicle type	First Event	No. Ped
2013-Feb-16, Sat,10:47	Clear	Sideswipe	P.D. only	Dry	East	Changing lanes	Automobile, station wagon	Other motor vehicle	


					East	Going ahead	Pick-up truck	Other motor vehicle
2014-Jul-15, Tue,08:00	Clear	Rear end	P.D. only	Dry	East	Going ahead	Automobile, station wagon	Other motor vehicle
					East	Stopped	Pick-up truck	Other motor vehicle
2014-Sep-01, Mon,18:30	Clear	SMV unattended vehicle	P.D. only	Dry	East	Unknown	Unknown	Unattended vehicle
2015-Jun-25, Thu,07:39	Clear	Sideswipe	P.D. only	Dry	East	Turning right	Automobile, station wagon	Other motor vehicle
					East	Turning right	Pick-up truck	Other motor vehicle
2015-Jul-23, Thu,16:16	Clear	Angle	P.D. only	Dry	South	Turning left	Automobile, station wagon	Other motor vehicle
					East	Going ahead	Municipal transit bus	Other motor vehicle
2016-Feb-29, Mon,17:15	Clear	Sideswipe	P.D. only	Dry	East	Changing lanes	Passenger van	Other motor vehicle
					East	Going ahead	Automobile, station wagon	Other motor vehicle
2016-Apr-13, Wed,10:35	Clear	Sideswipe	P.D. only	Dry	East	Changing lanes	Automobile, station wagon	Other motor vehicle
					East	Going ahead	Automobile, station wagon	Other motor vehicle
2017-Mar-16, Thu,00:00	Clear	SMV unattended vehicle	P.D. only	Dry	Unknown	Unknown	Unknown	Unattended vehicle

# Appendix D

Other Area Development Traffic Volumes

---

## Other Area Development Peak Hour Traffic Volumes



These volumes are a combination of assumptions based on the Transportation Impact Assessments for the other area developments (343 Gloucester Street, 383 Albert Street and 340 Queen Street, 350 Sparks Street, and 412 Sparks).

# Appendix E

Traffic Growth Analysis

---



**Bay/Slater**  
**8 hrs**

Year	Date	North Leg		South Leg		East Leg		West Leg		Total
		SB	NB	NB	SB	WB	EB	EB	WB	
2007	Thursday, 5th July	0	3580	2453	0	0	5319	4820	0	16172
2011	Thursday, 9th August	0	2718	1940	0	0	4966	5311	0	14935
2015	Thursday, 25th June	0	3297	2054	0	0	4524	4058	0	13933

**North Leg**

Year	Counts				% Change			
	NB	SB	NB+SB	INT	NB	SB	NB+SB	INT
2007	3580			16172				
2011	2718			14935	-24.1%			-7.6%
2015	3297			13933	21.3%			-6.7%

Regression Estimate 2007 3340  
 Regression Estimate 2015 3057  
**Average Annual Change -1.10%**

**West Leg**

Year	Counts				% Change			
	EB	WB	EB+WB	INT	EB	WB	EB+WB	INT
2007	4820			16172				
2011	5311			14935	10.2%			-7.6%
2015	4058			13933	-23.6%			-6.7%

Regression Estimate 2007 5111  
 Regression Estimate 2015 4349  
**Average Annual Change -2.00%**

**East Leg**

Year	Counts				% Change			
	EB	WB	EB+WB	INT	EB	WB	EB+WB	INT
2007	5319			16172				
2011	4966			14935	-6.6%			-7.6%
2015	4524			13933	-8.9%			-6.7%

Regression Estimate 2007 5334  
 Regression Estimate 2015 4539  
**Average Annual Change -2.00%**

**South Leg**

Year	Counts				% Change			
	NB	SB	NB+SB	INT	NB	SB	NB+SB	INT
2007	2453			16172				
2011	1940			14935	-20.9%			-7.6%
2015	2054			13933	5.9%			-6.7%

Regression Estimate 2007 2349  
 Regression Estimate 2015 1950  
**Average Annual Change -2.30%**

**Bay/Slater**  
**AM Peak**

Year	Date	North Leg		South Leg		East Leg		West Leg		Total
		SB	NB	NB	SB	WB	EB	EB	WB	
2007	Thursday, 5th July	0	492	271	0	0	1057	960	0	2780
2011	Thursday, 9th August	0	312	198	0	0	883	836	0	2229
2015	Thursday, 25th June	0	382	191	0	0	895	819	0	2287

**North Leg**

Year	Counts				% Change			
	NB	SB	NB+SB	INT	NB	SB	NB+SB	INT
2007	492			2780				
2011	312			2229	-36.6%			-19.8%
2015	382			2287	22.4%			2.6%

Regression Estimate 2007 450  
 Regression Estimate 2015 340  
**Average Annual Change -3.44%**

**West Leg**

Year	Counts				% Change			
	EB	WB	EB+WB	INT	EB	WB	EB+WB	INT
2007	960			2780				
2011	836			2229	-12.9%			-19.8%
2015	819			2287	-2.0%			2.6%

Regression Estimate 2007 942  
 Regression Estimate 2015 801  
**Average Annual Change -2.01%**

**East Leg**

Year	Counts				% Change			
	EB	WB	EB+WB	INT	EB	WB	EB+WB	INT
2007	1057			2780				
2011	883			2229	-16.5%			-19.8%
2015	895			2287	1.4%			2.6%

Regression Estimate 2007 1026  
 Regression Estimate 2015 864  
**Average Annual Change -2.13%**

**South Leg**

Year	Counts				% Change			
	NB	SB	NB+SB	INT	NB	SB	NB+SB	INT
2007	271			2780				
2011	198			2229	-26.9%			-19.8%
2015	191			2287	-3.5%			2.6%

Regression Estimate 2007 260  
 Regression Estimate 2015 180  
**Average Annual Change -4.49%**

**Bay/Slater**  
**PM Peak**

Year	Date	North Leg		South Leg		East Leg		West Leg		Total
		SB	NB	NB	SB	WB	EB	EB	WB	
2007	Thursday, 5th July	0	716	531	0	0	684	803	0	2734
2011	Thursday, 9th August	0	423	303	0	0	704	650	0	2080
2015	Thursday, 25th June	0	662	436	0	0	571	520	0	2189

**North Leg**

Year	Counts				% Change			
	NB	SB	NB+SB	INT	NB	SB	NB+SB	INT
2007	716			2734				
2011	423			2080	-40.9%			-23.9%
2015	662			2189	56.5%			5.2%

Regression Estimate 2007 627

Regression Estimate 2015 573

Average Annual Change -1.12%

**West Leg**

Year	Counts				% Change			
	EB	WB	EB+WB	INT	EB	WB	EB+WB	INT
2007	803			2734				
2011	650			2080	-19.1%			-23.9%
2015	520			2189	-20.0%			5.2%

Regression Estimate 2007 799

Regression Estimate 2015 516

Average Annual Change -5.32%

**East Leg**

Year	Counts				% Change			
	EB	WB	EB+WB	INT	EB	WB	EB+WB	INT
2007	684			2734				
2011	704			2080	2.9%			-23.9%
2015	571			2189	-18.9%			5.2%

Regression Estimate 2007 710

Regression Estimate 2015 597

Average Annual Change -2.15%

**South Leg**

Year	Counts				% Change			
	NB	SB	NB+SB	INT	NB	SB	NB+SB	INT
2007	531			2734				
2011	303			2080	-42.9%			-23.9%
2015	436			2189	43.9%			5.2%

Regression Estimate 2007 471

Regression Estimate 2015 376

Average Annual Change -2.78%

# Appendix F

TDM Checklists

---

## **TDM-Supportive Development Design and Infrastructure Checklist:** *Non-Residential Developments (office, institutional, retail or industrial)*

<b>Legend</b>	
<b>REQUIRED</b>	The Official Plan or Zoning By-law provides related guidance that must be followed
<b>BASIC</b>	The measure is generally feasible and effective, and in most cases would benefit the development and its users
<b>BETTER</b>	The measure could maximize support for users of sustainable modes, and optimize development performance

<b>TDM-supportive design &amp; infrastructure measures:</b> <i>Non-residential developments</i>		<b>Check if completed &amp; add descriptions, explanations or plan/drawing references</b>
<b>1. WALKING &amp; CYCLING: ROUTES</b>		
<b>1.1 Building location &amp; access points</b>		
<b>BASIC</b>	1.1.1 Locate building close to the street, and do not locate parking areas between the street and building entrances	<input checked="" type="checkbox"/>
<b>BASIC</b>	1.1.2 Locate building entrances in order to minimize walking distances to sidewalks and transit stops/stations	<input checked="" type="checkbox"/>
<b>BASIC</b>	1.1.3 Locate building doors and windows to ensure visibility of pedestrians from the building, for their security and comfort	<input checked="" type="checkbox"/>
<b>1.2 Facilities for walking &amp; cycling</b>		
<b>REQUIRED</b>	1.2.1 Provide convenient, direct access to stations or major stops along rapid transit routes within 600 metres; minimize walking distances from buildings to rapid transit; provide pedestrian-friendly, weather-protected (where possible) environment between rapid transit accesses and building entrances; ensure quality linkages from sidewalks through building entrances to integrated stops/stations ( <i>see Official Plan policy 4.3.3</i> )	<input checked="" type="checkbox"/>
<b>REQUIRED</b>	1.2.2 Provide safe, direct and attractive pedestrian access from public sidewalks to building entrances through such measures as: reducing distances between public sidewalks and major building entrances; providing walkways from public streets to major building entrances; within a site, providing walkways along the front of adjoining buildings, between adjacent buildings, and connecting areas where people may congregate, such as courtyards and transit stops; and providing weather protection through canopies, colonnades, and other design elements wherever possible ( <i>see Official Plan policy 4.3.12</i> )	<input checked="" type="checkbox"/>

TDM-supportive design & infrastructure measures: <i>Non-residential developments</i>		Check if completed & add descriptions, explanations or plan/drawing references
REQUIRED	1.2.3 Provide sidewalks of smooth, well-drained walking surfaces of contrasting materials or treatments to differentiate pedestrian areas from vehicle areas, and provide marked pedestrian crosswalks at intersection sidewalks ( <i>see Official Plan policy 4.3.10</i> )	<input checked="" type="checkbox"/>
REQUIRED	1.2.4 Make sidewalks and open space areas easily accessible through features such as gradual grade transition, depressed curbs at street corners and convenient access to extra-wide parking spaces and ramps ( <i>see Official Plan policy 4.3.10</i> )	<input type="checkbox"/> To be refined at Site Plan
REQUIRED	1.2.5 Include adequately spaced inter-block/street cycling and pedestrian connections to facilitate travel by active transportation. Provide links to the existing or planned network of public sidewalks, multi-use pathways and on-road cycle routes. Where public sidewalks and multi-use pathways intersect with roads, consider providing traffic control devices to give priority to cyclists and pedestrians ( <i>see Official Plan policy 4.3.11</i> )	<input checked="" type="checkbox"/>
BASIC	1.2.6 Provide safe, direct and attractive walking routes from building entrances to nearby transit stops	<input checked="" type="checkbox"/>
BASIC	1.2.7 Ensure that walking routes to transit stops are secure, visible, lighted, shaded and wind-protected wherever possible	<input checked="" type="checkbox"/>
BASIC	1.2.8 Design roads used for access or circulation by cyclists using a target operating speed of no more than 30 km/h, or provide a separated cycling facility	<input type="checkbox"/> Cycling infrastructure is to be constructed on City roads surrounding the development
<b>1.3 Amenities for walking &amp; cycling</b>		
BASIC	1.3.1 Provide lighting, landscaping and benches along walking and cycling routes between building entrances and streets, sidewalks and trails	<input checked="" type="checkbox"/>
BASIC	1.3.2 Provide wayfinding signage for site access (where required, e.g. when multiple buildings or entrances exist) and egress (where warranted, such as when directions to reach transit stops/stations, trails or other common destinations are not obvious)	<input type="checkbox"/> Will be refined at Site Plan

TDM-supportive design & infrastructure measures: <i>Non-residential developments</i>		Check if completed & add descriptions, explanations or plan/drawing references
<b>2. WALKING &amp; CYCLING: END-OF-TRIP FACILITIES</b>		
<b>2.1 Bicycle parking</b>		
REQUIRED	2.1.1 Provide bicycle parking in highly visible and lighted areas, sheltered from the weather wherever possible ( <i>see Official Plan policy 4.3.6</i> )	<input checked="" type="checkbox"/> Will provide, refined at Site Plan
REQUIRED	2.1.2 Provide the number of bicycle parking spaces specified for various land uses in different parts of Ottawa; provide convenient access to main entrances or well-used areas ( <i>see Zoning By-law Section 111</i> )	<input checked="" type="checkbox"/> Will provide, refined at Site Plan
REQUIRED	2.1.3 Ensure that bicycle parking spaces and access aisles meet minimum dimensions; that no more than 50% of spaces are vertical spaces; and that parking racks are securely anchored ( <i>see Zoning By-law Section 111</i> )	<input checked="" type="checkbox"/> Will provide, refined at Site Plan
BASIC	2.1.4 Provide bicycle parking spaces equivalent to the expected number of commuter cyclists (assuming the cycling mode share target is met), plus the expected peak number of customer/visitor cyclists	<input type="checkbox"/> Will refine at Site Plan
BETTER	2.1.5 Provide bicycle parking spaces equivalent to the expected number of commuter and customer/visitor cyclists, plus an additional buffer (e.g. 25 percent extra) to encourage other cyclists and ensure adequate capacity in peak cycling season	<input type="checkbox"/> Will discuss and refine at Site Plan as required
<b>2.2 Secure bicycle parking</b>		
REQUIRED	2.2.1 Where more than 50 bicycle parking spaces are provided for a single office building, locate at least 25% of spaces within a building/structure, a secure area (e.g. supervised parking lot or enclosure) or bicycle lockers ( <i>see Zoning By-law Section 111</i> )	<input type="checkbox"/> n/a
BETTER	2.2.2 Provide secure bicycle parking spaces equivalent to the expected number of commuter cyclists (assuming the cycling mode share target is met)	<input type="checkbox"/> n/a
<b>2.3 Shower &amp; change facilities</b>		
BASIC	2.3.1 Provide shower and change facilities for the use of active commuters	<input type="checkbox"/>
BETTER	2.3.2 In addition to shower and change facilities, provide dedicated lockers, grooming stations, drying racks and laundry facilities for the use of active commuters	<input type="checkbox"/>
<b>2.4 Bicycle repair station</b>		
BETTER	2.4.1 Provide a permanent bike repair station, with commonly used tools and an air pump, adjacent to the main bicycle parking area (or secure bicycle parking area, if provided)	<input type="checkbox"/>

TDM-supportive design & infrastructure measures: <i>Non-residential developments</i>		Check if completed & add descriptions, explanations or plan/drawing references
<b>3. TRANSIT</b>		
<b>3.1 Customer amenities</b>		
BASIC	3.1.1 Provide shelters, lighting and benches at any on-site transit stops	<input type="checkbox"/> n/a
BASIC	3.1.2 Where the site abuts an off-site transit stop and insufficient space exists for a transit shelter in the public right-of-way, protect land for a shelter and/or install a shelter	<input type="checkbox"/> n/a
BETTER	3.1.3 Provide a secure and comfortable interior waiting area by integrating any on-site transit stops into the building	<input type="checkbox"/> n/a
<b>4. RIDESHARING</b>		
<b>4.1 Pick-up &amp; drop-off facilities</b>		
BASIC	4.1.1 Provide a designated area for carpool drivers (plus taxis and ride-hailing services) to drop off or pick up passengers without using fire lanes or other no-stopping zones	<input checked="" type="checkbox"/>
<b>4.2 Carpool parking</b>		
BASIC	4.2.1 Provide signed parking spaces for carpools in a priority location close to a major building entrance, sufficient in number to accommodate the mode share target for carpools	<input type="checkbox"/>
BETTER	4.2.2 At large developments, provide spaces for carpools in a separate, access-controlled parking area to simplify enforcement	<input type="checkbox"/>
<b>5. CARSHARING &amp; BIKESHARING</b>		
<b>5.1 Carshare parking spaces</b>		
BETTER	5.1.1 Provide carshare parking spaces in permitted non-residential zones, occupying either required or provided parking spaces ( <i>see Zoning By-law Section 94</i> )	<input type="checkbox"/>
<b>5.2 Bikeshare station location</b>		
BETTER	5.2.1 Provide a designated bikeshare station area near a major building entrance, preferably lighted and sheltered with a direct walkway connection	<input type="checkbox"/>



TDM-supportive design & infrastructure measures: <i>Non-residential developments</i>		Check if completed & add descriptions, explanations or plan/drawing references
<b>6. PARKING</b>		
<b>6.1 Number of parking spaces</b>		
<b>REQUIRED</b>	6.1.1 Do not provide more parking than permitted by zoning, nor less than required by zoning, unless a variance is being applied for	<input checked="" type="checkbox"/>
<b>BASIC</b>	6.1.2 Provide parking for long-term and short-term users that is consistent with mode share targets, considering the potential for visitors to use off-site public parking	<input type="checkbox"/>
<b>BASIC</b>	6.1.3 Where a site features more than one use, provide shared parking and reduce the cumulative number of parking spaces accordingly ( <i>see Zoning By-law Section 104</i> )	<input type="checkbox"/>
<b>BETTER</b>	6.1.4 Reduce the minimum number of parking spaces required by zoning by one space for each 13 square metres of gross floor area provided as shower rooms, change rooms, locker rooms and other facilities for cyclists in conjunction with bicycle parking ( <i>see Zoning By-law Section 111</i> )	<input type="checkbox"/>
<b>6.2 Separate long-term &amp; short-term parking areas</b>		
<b>BETTER</b>	6.2.1 Separate short-term and long-term parking areas using signage or physical barriers, to permit access controls and simplify enforcement (i.e. to discourage employees from parking in visitor spaces, and vice versa)	<input type="checkbox"/>
<b>7. OTHER</b>		
<b>7.1 On-site amenities to minimize off-site trips</b>		
<b>BETTER</b>	7.1.1 Provide on-site amenities to minimize mid-day or mid-commute errands	<input type="checkbox"/>

## **TDM-Supportive Development Design and Infrastructure Checklist:** *Residential Developments (multi-family or condominium)*

<b>Legend</b>	
<b>REQUIRED</b>	The Official Plan or Zoning By-law provides related guidance that must be followed
<b>BASIC</b>	The measure is generally feasible and effective, and in most cases would benefit the development and its users
<b>BETTER</b>	The measure could maximize support for users of sustainable modes, and optimize development performance

<b>TDM-supportive design &amp; infrastructure measures:</b> <i>Residential developments</i>		<b>Check if completed &amp; add descriptions, explanations or plan/drawing references</b>
<b>1. WALKING &amp; CYCLING: ROUTES</b>		
<b>1.1 Building location &amp; access points</b>		
<b>BASIC</b>	1.1.1 Locate building close to the street, and do not locate parking areas between the street and building entrances	<input checked="" type="checkbox"/>
<b>BASIC</b>	1.1.2 Locate building entrances in order to minimize walking distances to sidewalks and transit stops/stations	<input checked="" type="checkbox"/>
<b>BASIC</b>	1.1.3 Locate building doors and windows to ensure visibility of pedestrians from the building, for their security and comfort	<input checked="" type="checkbox"/>
<b>1.2 Facilities for walking &amp; cycling</b>		
<b>REQUIRED</b>	1.2.1 Provide convenient, direct access to stations or major stops along rapid transit routes within 600 metres; minimize walking distances from buildings to rapid transit; provide pedestrian-friendly, weather-protected (where possible) environment between rapid transit accesses and building entrances; ensure quality linkages from sidewalks through building entrances to integrated stops/stations ( <i>see Official Plan policy 4.3.3</i> )	<input checked="" type="checkbox"/>
<b>REQUIRED</b>	1.2.2 Provide safe, direct and attractive pedestrian access from public sidewalks to building entrances through such measures as: reducing distances between public sidewalks and major building entrances; providing walkways from public streets to major building entrances; within a site, providing walkways along the front of adjoining buildings, between adjacent buildings, and connecting areas where people may congregate, such as courtyards and transit stops; and providing weather protection through canopies, colonnades, and other design elements wherever possible ( <i>see Official Plan policy 4.3.12</i> )	<input checked="" type="checkbox"/>

TDM-supportive design & infrastructure measures: <i>Residential developments</i>		Check if completed & add descriptions, explanations or plan/drawing references
REQUIRED	1.2.3 Provide sidewalks of smooth, well-drained walking surfaces of contrasting materials or treatments to differentiate pedestrian areas from vehicle areas, and provide marked pedestrian crosswalks at intersection sidewalks ( <i>see Official Plan policy 4.3.10</i> )	<input checked="" type="checkbox"/>
REQUIRED	1.2.4 Make sidewalks and open space areas easily accessible through features such as gradual grade transition, depressed curbs at street corners and convenient access to extra-wide parking spaces and ramps ( <i>see Official Plan policy 4.3.10</i> )	<input checked="" type="checkbox"/> Will refine at Site Plan
REQUIRED	1.2.5 Include adequately spaced inter-block/street cycling and pedestrian connections to facilitate travel by active transportation. Provide links to the existing or planned network of public sidewalks, multi-use pathways and on-road cycle routes. Where public sidewalks and multi-use pathways intersect with roads, consider providing traffic control devices to give priority to cyclists and pedestrians ( <i>see Official Plan policy 4.3.11</i> )	<input checked="" type="checkbox"/>
BASIC	1.2.6 Provide safe, direct and attractive walking routes from building entrances to nearby transit stops	<input checked="" type="checkbox"/>
BASIC	1.2.7 Ensure that walking routes to transit stops are secure, visible, lighted, shaded and wind-protected wherever possible	<input checked="" type="checkbox"/> <input checked="" type="checkbox"/>
BASIC	1.2.8 Design roads used for access or circulation by cyclists using a target operating speed of no more than 30 km/h, or provide a separated cycling facility	<input type="checkbox"/>
<b>1.3 Amenities for walking &amp; cycling</b>		
BASIC	1.3.1 Provide lighting, landscaping and benches along walking and cycling routes between building entrances and streets, sidewalks and trails	<input type="checkbox"/> May be discussed at Site Plan
BASIC	1.3.2 Provide wayfinding signage for site access (where required, e.g. when multiple buildings or entrances exist) and egress (where warranted, such as when directions to reach transit stops/stations, trails or other common destinations are not obvious)	<input type="checkbox"/> May be discussed at Site Plan

TDM-supportive design & infrastructure measures: <i>Residential developments</i>		Check if completed & add descriptions, explanations or plan/drawing references
<b>2. WALKING &amp; CYCLING: END-OF-TRIP FACILITIES</b>		
<b>2.1 Bicycle parking</b>		
REQUIRED	2.1.1 Provide bicycle parking in highly visible and lighted areas, sheltered from the weather wherever possible (see <i>Official Plan policy 4.3.6</i> )	<input checked="" type="checkbox"/> Will provide
REQUIRED	2.1.2 Provide the number of bicycle parking spaces specified for various land uses in different parts of Ottawa; provide convenient access to main entrances or well-used areas (see <i>Zoning By-law Section 111</i> )	<input checked="" type="checkbox"/> Will provide
REQUIRED	2.1.3 Ensure that bicycle parking spaces and access aisles meet minimum dimensions; that no more than 50% of spaces are vertical spaces; and that parking racks are securely anchored (see <i>Zoning By-law Section 111</i> )	<input checked="" type="checkbox"/> Will provide
BASIC	2.1.4 Provide bicycle parking spaces equivalent to the expected number of resident-owned bicycles, plus the expected peak number of visitor cyclists	<input type="checkbox"/>
<b>2.2 Secure bicycle parking</b>		
REQUIRED	2.2.1 Where more than 50 bicycle parking spaces are provided for a single residential building, locate at least 25% of spaces within a building/structure, a secure area (e.g. supervised parking lot or enclosure) or bicycle lockers (see <i>Zoning By-law Section 111</i> )	<input type="checkbox"/> Likely will provide, to be refined at Site Plan
BETTER	2.2.2 Provide secure bicycle parking spaces equivalent to at least the number of units at condominiums or multi-family residential developments	<input type="checkbox"/>
<b>2.3 Bicycle repair station</b>		
BETTER	2.3.1 Provide a permanent bike repair station, with commonly used tools and an air pump, adjacent to the main bicycle parking area (or secure bicycle parking area, if provided)	<input type="checkbox"/>
<b>3. TRANSIT</b>		
<b>3.1 Customer amenities</b>		
BASIC	3.1.1 Provide shelters, lighting and benches at any on-site transit stops	<input type="checkbox"/> n/a
BASIC	3.1.2 Where the site abuts an off-site transit stop and insufficient space exists for a transit shelter in the public right-of-way, protect land for a shelter and/or install a shelter	<input type="checkbox"/> n/a
BETTER	3.1.3 Provide a secure and comfortable interior waiting area by integrating any on-site transit stops into the building	<input type="checkbox"/> n/a

TDM-supportive design & infrastructure measures: <i>Residential developments</i>		Check if completed & add descriptions, explanations or plan/drawing references
<b>4. RIDESHARING</b>		
<b>4.1 Pick-up &amp; drop-off facilities</b>		
<b>BASIC</b>	4.1.1 Provide a designated area for carpool drivers (plus taxis and ride-hailing services) to drop off or pick up passengers without using fire lanes or other no-stopping zones	<input checked="" type="checkbox"/>
<b>5. CARSHARING &amp; BIKESHARING</b>		
<b>5.1 Carshare parking spaces</b>		
<b>BETTER</b>	5.1.1 Provide up to three carshare parking spaces in an R3, R4 or R5 Zone for specified residential uses (see <i>Zoning By-law Section 94</i> )	<input type="checkbox"/>
<b>5.2 Bikeshare station location</b>		
<b>BETTER</b>	5.2.1 Provide a designated bikeshare station area near a major building entrance, preferably lighted and sheltered with a direct walkway connection	<input type="checkbox"/>
<b>6. PARKING</b>		
<b>6.1 Number of parking spaces</b>		
<b>REQUIRED</b>	6.1.1 Do not provide more parking than permitted by zoning, nor less than required by zoning, unless a variance is being applied for	<input checked="" type="checkbox"/>
<b>BASIC</b>	6.1.2 Provide parking for long-term and short-term users that is consistent with mode share targets, considering the potential for visitors to use off-site public parking	<input type="checkbox"/>
<b>BASIC</b>	6.1.3 Where a site features more than one use, provide shared parking and reduce the cumulative number of parking spaces accordingly (see <i>Zoning By-law Section 104</i> )	<input type="checkbox"/>
<b>BETTER</b>	6.1.4 Reduce the minimum number of parking spaces required by zoning by one space for each 13 square metres of gross floor area provided as shower rooms, change rooms, locker rooms and other facilities for cyclists in conjunction with bicycle parking (see <i>Zoning By-law Section 111</i> )	<input type="checkbox"/>
<b>6.2 Separate long-term &amp; short-term parking areas</b>		
<b>BETTER</b>	6.2.1 Provide separate areas for short-term and long-term parking (using signage or physical barriers) to permit access controls and simplify enforcement (i.e. to discourage residents from parking in visitor spaces, and vice versa)	<input type="checkbox"/>

# Appendix G

Existing Zoning Trip Generation Analysis

---

ITE Vehicle Trip Generation

Land Use	Data Source	Area	AM Peak (veh/h)			PM Peak (veh/h)		
			In	Out	Total	In	Out	Total
High-Rise Apartments	ITE 222	Units	28%	72%		55%	42%	
		220 du	10	27	37	20	15	35
		Total	10	27	37	20	15	35

0 m<sup>2</sup> to  
0 ft<sup>2</sup>

0 m<sup>2</sup> to  
0 ft<sup>2</sup>

Total Site Trip Generation

Travel Mode	AM Mode Share	AM Peak (persons/h)			PM Mode Share	PM Peak (persons/h)		
		In	Out	Total		In	Out	Total
Auto Driver	27%	10	27	37	23%	20	15	35
Auto Passenger	3%	2	2	4	6%	5	5	10
Transit	27%	11	26	37	29%	25	19	44
Non-motorized	43%	17	42	59	42%	36	27	63
<b>Total People Trips</b>	<b>100%</b>	<b>40</b>	<b>97</b>	<b>137</b>	<b>100%</b>	<b>86</b>	<b>66</b>	<b>152</b>
Total 'New' Auto Trips		10	27	37		20	15	35

Future Mode Share Trip Generation

Travel Mode	AM Mode Share	AM Peak (persons/h)			PM Mode Share	PM Peak (persons/h)		
		In	Out	Total		In	Out	Total
Auto Driver	15%	5	16	21	15%	12	10	22
Auto Passenger	5%	2	4	6	5%	4	4	8
Transit	38%	14	38	52	38%	33	25	58
Non-motorized	42%	16	42	58	42%	37	27	64
<b>Total People Trips</b>	<b>100%</b>	<b>37</b>	<b>100</b>	<b>137</b>	<b>100%</b>	<b>86</b>	<b>66</b>	<b>152</b>
Total 'New' Future Mode Share Auto Trips		5	16	21		12	10	22

# Appendix H

MMLoS and SYNCHRO Analysis – Existing Conditions

---



Multi-Modal Level of Service - Intersections Form

Consultant  
Scenario  
Comments

Parsons  
Existing


Project  
Date

400 Albert  
Aug-19

INTERSECTIONS																									
Crossing Side		Laurier/Bay				Slater/Bay				Albert/Bay				Queen/Bay				Albert/Lyon				Slater/Lyon			
Pedestrian	Lanes	0 - 2	0 - 2	0 - 2	0 - 2	0 - 2	0 - 2	3	3	0 - 2	0 - 2	4	3	0 - 2	0 - 2	0 - 2	0 - 2	3	3	4	3	3	3	3	4
	Median	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m
	Conflicting Left Turns	Protected/ Permissive	No left turn / Prohib.	No left turn / Prohib.	Permissive	Permissive	No left turn / Prohib.	No left turn / Prohib.	No left turn / Prohib.	Permissive	No left turn / Prohib.	No left turn / Prohib.	No left turn / Prohib.	Permissive	No left turn / Prohib.	No left turn / Prohib.	No left turn / Prohib.	No left turn / Prohib.	Permissive	No left turn / Prohib.	No left turn / Prohib.	Permissive	No left turn / Prohib.	No left turn / Prohib.	No left turn / Prohib.
	Conflicting Right Turns	Permissive or yield control	No right turn	Permissive or yield control	No right turn	No right turn	No right turn	Permissive or yield control	No right turn	Permissive or yield control	No right turn	No right turn	No right turn	Permissive or yield control	No right turn	Permissive or yield control	No right turn	No right turn	No right turn	Permissive or yield control	No right turn	Permissive or yield control	No right turn	No right turn	No right turn
	Right Turns on Red (RTorR) ?	RTOR prohibited	RTOR prohibited	RTOR prohibited	RTOR prohibited	RTOR prohibited	RTOR allowed	RTOR prohibited	RTOR prohibited	RTOR prohibited	RTOR allowed	RTOR allowed	RTOR prohibited	RTOR prohibited	RTOR allowed	RTOR allowed	RTOR allowed	RTOR allowed	RTOR prohibited	RTOR prohibited	RTOR prohibited	RTOR prohibited	RTOR prohibited	RTOR prohibited	RTOR allowed
	Ped Signal Leading Interval?	No	No	Yes	Yes	No	No	No	No	No	No	No	No	No	No	No	No	No	No	No	No	No	No	No	No
	Right Turn Channel	No Channel	No Channel	No Channel	No Channel	No Channel	No Channel	No Channel	No Channel	No Channel	No Channel	No Channel	No Channel	No Channel	No Channel	No Channel	No Channel	No Channel	No Channel	No Channel	No Channel	No Channel	No Channel	No Channel	No Channel
	Corner Radius	3-5m	3-5m	3-5m	3-5m	3-5m	3-5m	3-5m	3-5m	3-5m	3-5m	3-5m	3-5m	3-5m	3-5m	3-5m	3-5m	3-5m	3-5m	3-5m	3-5m	3-5m	3-5m	3-5m	3-5m
	Crosswalk Type	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings
	PETSI Score	90	103	100	97	95	100	83	88	98	100	68	80	90	100	95	92	85	80	71	83	88	83	80	68
	Ped. Exposure to Traffic LoS	A	A	A	A	A	A	B	B	A	A	C	B	A	A	A	A	B	B	C	B	B	B	B	C
	Cycle Length	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60
	Effective Walk Time	19	19	11	11	31	31	7	7	22	22	9	9	16	16	18	18	14	14	19	19	20	20	18	18
	Average Pedestrian Delay	14	14	20	20	7	7	23	23	12	12	22	22	16	16	15	15	18	18	14	14	13	13	15	15
	Pedestrian Delay LoS	B	B	C	C	A	A	C	C	B	B	C	C	B	B	B	B	B	B	B	B	B	B	B	B
	Level of Service	C				C				C				B				C				C			
Approach From		NORTH	SOUTH	EAST	WEST	NORTH	SOUTH	EAST	WEST	NORTH	SOUTH	EAST	WEST	NORTH	SOUTH	EAST	WEST	NORTH	SOUTH	EAST	WEST	NORTH	SOUTH	EAST	WEST
Bicycle	Bicycle Lane Arrangement on Approach	Curb Bike Lane, Cycletrack or MUP				Curb Bike Lane, Cycletrack or MUP				Curb Bike Lane, Cycletrack or MUP				Curb Bike Lane, Cycletrack or MUP				Mixed Traffic				Mixed Traffic			
	Right Turn Lane Configuration					≤ 50 m				≤ 50 m								≤ 50 m				≤ 50 m			
	Right Turning Speed					≤ 25 km/h				≤ 25 km/h								≤ 25 km/h				≤ 25 km/h			
	Cyclist relative to RT motorists	-	Not Applicable	Not Applicable	Not Applicable	-	Not Applicable	-	D	-	Not Applicable	D	-	-	Not Applicable	-	-	D	-	D	-	Not Applicable	-	-	D
	Separated or Mixed Traffic	-	Separated	Separated	Separated	-	Separated	-	Mixed Traffic	-	Separated	Mixed Traffic	-	-	Separated	-	-	Mixed Traffic	-	Mixed Traffic	-	Separated	-	-	Mixed Traffic
	Left Turn Approach	1 lane crossed				≥ 2 lanes crossed				1 lane crossed				1 lane crossed				≥ 2 lanes crossed				≥ 2 lanes crossed			
	Operating Speed	> 40 to ≤ 50 km/h				> 40 to ≤ 50 km/h				> 40 to ≤ 50 km/h				> 40 to ≤ 50 km/h				> 40 to ≤ 50 km/h				> 40 to ≤ 50 km/h			
Transit	Left Turning Cyclist	-	C	A	-	-	C	-	E	-	C	B	-	-	C	-	B	-	-	E	-	E	-	-	-
	Level of Service	-	C	A	-	-	C	-	E	-	C	D	-	-	C	-	B	-	-	E	-	E	-	-	-
		C				E				D				C				E				E			
Truck	Average Signal Delay					≤ 10 sec				≤ 10 sec				≤ 10 sec				≤ 10 sec				≤ 10 sec			
	Level of Service	-	-	-	-	-	-	B	B	-	B	B	B	-	B	C	-	-	-	B	-	-	-	B	B
		-				B				B				C				B				B			
Auto	Effective Corner Radius	10 - 15 m				< 10 m				< 10 m				10 - 15 m				< 10 m				< 10 m			
	Number of Receiving Lanes on Departure from Intersection	1				≥ 2				≥ 2				1				≥ 2				≥ 2			
	Level of Service	-	E	B	-	D	-	-	-	-	-	D	-	-	E	D	-	D	-	-	-	-	-	-	D
Auto	Volume to Capacity Ratio	0.61 - 0.70				0.0 - 0.60				0.0 - 0.60				0.71 - 0.80				0.71 - 0.80				0.61 - 0.70			
	Level of Service	B				A				A				C				C				B			

	→	↑
Lane Group	EBT	NBT
Lane Configurations	↔↔	↔↔
Traffic Volume (vph)	736	194
Future Volume (vph)	736	194
Lane Group Flow (vph)	976	284
Turn Type	NA	NA
Protected Phases	2	8
Permitted Phases		
Minimum Split (s)	29.0	19.2
Total Split (s)	41.0	19.0
Total Split (%)	68.3%	31.7%
Yellow Time (s)	3.3	3.3
All-Red Time (s)	1.7	1.9
Lost Time Adjust (s)	0.0	0.0
Total Lost Time (s)	5.0	5.2
Lead/Lag		
Lead-Lag Optimize?		
Act Effect Green (s)	36.0	13.8
Actuated g/C Ratio	0.60	0.23
v/c Ratio	0.53	0.41
Control Delay	7.5	16.0
Queue Delay	0.0	0.0
Total Delay	7.5	16.0
LOS	A	B
Approach Delay	7.5	16.0
Approach LOS	A	B
Queue Length 50th (m)	25.1	9.8
Queue Length 95th (m)	37.8	19.0
Internal Link Dist (m)	111.5	72.8
Turn Bay Length (m)		
Base Capacity (vph)	1837	693
Starvation Cap Reductn	0	0
Spillback Cap Reductn	0	0
Storage Cap Reductn	0	0
Reduced v/c Ratio	0.53	0.41
<b>Intersection Summary</b>		
Cycle Length: 60		
Actuated Cycle Length: 60		
Offset: 3 (5%), Referenced to phase 2:EBTL, Start of Green		
Natural Cycle: 50		
Control Type: Pretimed		
Maximum v/c Ratio: 0.53		
Intersection Signal Delay: 9.4		Intersection LOS: A
Intersection Capacity Utilization 50.5%		ICU Level of Service A
Analysis Period (min) 15		

Splits and Phases: 1: Bay & Slater






Lane Group	WBT	WBR	NBT
Lane Configurations	↑↑	↑	↑↑
Traffic Volume (vph)	246	87	350
Future Volume (vph)	246	87	350
Lane Group Flow (vph)	259	92	405
Turn Type	NA	Perm	NA
Protected Phases	8		2
Permitted Phases		8	
Minimum Split (s)	20.2	20.2	23.2
Total Split (s)	35.0	35.0	25.0
Total Split (%)	58.3%	58.3%	41.7%
Yellow Time (s)	3.3	3.3	3.3
All-Red Time (s)	1.9	1.9	1.9
Lost Time Adjust (s)	0.0	0.0	0.0
Total Lost Time (s)	5.2	5.2	5.2
Lead/Lag			
Lead-Lag Optimize?			
Act Effect Green (s)	29.8	29.8	19.8
Actuated g/C Ratio	0.50	0.50	0.33
v/c Ratio	0.17	0.13	0.40
Control Delay	14.0	7.7	13.2
Queue Delay	0.0	0.0	0.0
Total Delay	14.0	7.7	13.2
LOS	B	A	B
Approach Delay	12.4		13.2
Approach LOS	B		B
Queue Length 50th (m)	11.6	3.0	16.3
Queue Length 95th (m)	19.8	11.5	28.9
Internal Link Dist (m)	123.5		54.5
Turn Bay Length (m)		75.0	
Base Capacity (vph)	1515	724	1017
Starvation Cap Reductn	0	0	0
Spillback Cap Reductn	0	0	0
Storage Cap Reductn	0	0	0
Reduced v/c Ratio	0.17	0.13	0.40

#### Intersection Summary

Cycle Length: 60  
 Actuated Cycle Length: 60  
 Offset: 58 (97%), Referenced to phase 2:NBTL, Start of Green  
 Natural Cycle: 45  
 Control Type: Pretimed  
 Maximum v/c Ratio: 0.40  
 Intersection Signal Delay: 12.8  
 Intersection Capacity Utilization 29.5%  
 Analysis Period (min) 15


Intersection LOS: B  
 ICU Level of Service A


Splits and Phases: 2: Bay & Albert



	→	↓
Lane Group	EBT	SBT
Lane Configurations	↕↕	↕↕↕
Traffic Volume (vph)	637	810
Future Volume (vph)	637	810
Lane Group Flow (vph)	855	1121
Turn Type	NA	NA
Protected Phases	4	6
Permitted Phases		
Minimum Split (s)	21.2	24.3
Total Split (s)	29.0	31.0
Total Split (%)	48.3%	51.7%
Yellow Time (s)	3.3	3.3
All-Red Time (s)	1.9	2.0
Lost Time Adjust (s)	0.0	0.0
Total Lost Time (s)	5.2	5.3
Lead/Lag		
Lead-Lag Optimize?		
Act Effect Green (s)	23.8	25.7
Actuated g/C Ratio	0.40	0.43
v/c Ratio	0.70	0.58
Control Delay	25.3	7.2
Queue Delay	0.0	0.2
Total Delay	25.3	7.4
LOS	C	A
Approach Delay	25.3	7.4
Approach LOS	C	A
Queue Length 50th (m)	48.8	9.1
Queue Length 95th (m)	67.6	21.2
Internal Link Dist (m)	124.5	56.5
Turn Bay Length (m)		
Base Capacity (vph)	1213	1921
Starvation Cap Reductn	0	209
Spillback Cap Reductn	0	0
Storage Cap Reductn	0	0
Reduced v/c Ratio	0.70	0.65
<b>Intersection Summary</b>		
Cycle Length: 60		
Actuated Cycle Length: 60		
Offset: 14 (23%), Referenced to phase 6:SBTL, Start of Green		
Natural Cycle: 50		
Control Type: Pretimed		
Maximum v/c Ratio: 0.70		
Intersection Signal Delay: 15.2		Intersection LOS: B
Intersection Capacity Utilization 60.4%		ICU Level of Service B
Analysis Period (min) 15		

Splits and Phases: 3: Lyon & Slater





Lane Group	WBT	SBT
Lane Configurations	↔↔	↔↔
Traffic Volume (vph)	159	997
Future Volume (vph)	159	997
Lane Group Flow (vph)	312	1049
Turn Type	NA	NA
Protected Phases	6	4
Permitted Phases		
Minimum Split (s)	20.4	21.5
Total Split (s)	27.0	33.0
Total Split (%)	45.0%	55.0%
Yellow Time (s)	3.3	3.3
All-Red Time (s)	2.1	2.2
Lost Time Adjust (s)	0.0	0.0
Total Lost Time (s)	5.4	5.5
Lead/Lag		
Lead-Lag Optimize?		
Act Effect Green (s)	21.6	27.5
Actuated g/C Ratio	0.36	0.46
v/c Ratio	0.28	0.75
Control Delay	12.2	17.6
Queue Delay	0.0	0.0
Total Delay	12.2	17.6
LOS	B	B
Approach Delay	12.2	17.6
Approach LOS	B	B
Queue Length 50th (m)	10.3	47.1
Queue Length 95th (m)	18.2	68.2
Internal Link Dist (m)	117.5	50.0
Turn Bay Length (m)		
Base Capacity (vph)	1105	1398
Starvation Cap Reductn	0	0
Spillback Cap Reductn	0	0
Storage Cap Reductn	0	0
Reduced v/c Ratio	0.28	0.75

#### Intersection Summary

Cycle Length: 60

Actuated Cycle Length: 60

Offset: 48 (80%), Referenced to phase 6:WBTL, Start of Green

Natural Cycle: 50

Control Type: Pretimed

Maximum v/c Ratio: 0.75

Intersection Signal Delay: 16.4


Intersection LOS: B










Intersection Capacity Utilization 51.3%

ICU Level of Service A

Analysis Period (min) 15

Splits and Phases: 4: Lyon & Albert








					
Lane Group	EBL	EBT	WBT	WBR	NBT
Lane Configurations					
Traffic Volume (vph)	183	194	172	35	300
Future Volume (vph)	183	194	172	35	300
Lane Group Flow (vph)	0	397	181	37	415
Turn Type	Perm	NA	NA	Perm	NA
Protected Phases		2	6		8
Permitted Phases	2			6	
Minimum Split (s)	21.1	21.1	21.1	21.1	29.1
Total Split (s)	30.0	30.0	30.0	30.0	30.0
Total Split (%)	50.0%	50.0%	50.0%	50.0%	50.0%
Yellow Time (s)	3.3	3.3	3.3	3.3	3.3
All-Red Time (s)	1.8	1.8	1.8	1.8	1.8
Lost Time Adjust (s)		0.0	0.0	0.0	0.0
Total Lost Time (s)		5.1	5.1	5.1	5.1
Lead/Lag					
Lead-Lag Optimize?					
Act Effect Green (s)		24.9	24.9	24.9	24.9
Actuated g/C Ratio		0.42	0.42	0.42	0.42
v/c Ratio		0.79	0.27	0.06	0.33
Control Delay		29.7	13.0	4.5	2.9
Queue Delay		0.0	0.0	0.0	0.0
Total Delay		29.7	13.0	4.5	2.9
LOS		C	B	A	A
Approach Delay		29.7	11.5		2.9
Approach LOS		C	B		A
Queue Length 50th (m)		36.3	12.6	0.0	1.9
Queue Length 95th (m)		#79.1	24.3	4.3	4.9
Internal Link Dist (m)		51.6	57.9		57.5
Turn Bay Length (m)					
Base Capacity (vph)		503	666	588	1263
Starvation Cap Reductn		0	0	0	0
Spillback Cap Reductn		0	0	0	0
Storage Cap Reductn		0	0	0	0
Reduced v/c Ratio		0.79	0.27	0.06	0.33

#### Intersection Summary

Cycle Length: 60  
 Actuated Cycle Length: 60  
 Offset: 31 (52%), Referenced to phase 2:EBTL and 6:WBT, Start of Green  
 Natural Cycle: 60  
 Control Type: Pretimed  
 Maximum v/c Ratio: 0.79  
 Intersection Signal Delay: 15.0  
 Intersection LOS: B  
 Intersection Capacity Utilization 60.4%  
 ICU Level of Service B  
 Analysis Period (min) 15  
 # 95th percentile volume exceeds capacity, queue may be longer.  
 Queue shown is maximum after two cycles.

#### Splits and Phases: 7: Bay & Queen



						
Lane Group	EBL	EBT	WBT	NBT	Ø1	Ø5
Lane Configurations						
Traffic Volume (vph)	58	209	96	213		
Future Volume (vph)	58	209	96	213		
Lane Group Flow (vph)	0	281	198	286		
Turn Type	Perm	NA	NA	NA		
Protected Phases		2	6	8	1	5
Permitted Phases	2					
Minimum Split (s)	20.4	20.4	20.4	23.4	5.0	5.0
Total Split (s)	32.0	32.0	32.0	28.0	5.0	5.0
Total Split (%)	49.2%	49.2%	49.2%	43.1%	8%	8%
Yellow Time (s)	3.3	3.3	3.3	3.3	2.0	2.0
All-Red Time (s)	2.1	2.1	2.1	2.1	0.0	0.0
Lost Time Adjust (s)		0.0	0.0	0.0		
Total Lost Time (s)		5.4	5.4	5.4		
Lead/Lag	Lag	Lag	Lag		Lead	Lead
Lead-Lag Optimize?	Yes	Yes	Yes		Yes	Yes
Act Effct Green (s)		26.6	26.6	22.6		
Actuated g/C Ratio		0.41	0.41	0.35		
v/c Ratio		0.48	0.32	0.28		
Control Delay		17.5	14.9	16.2		
Queue Delay		0.0	0.0	0.0		
Total Delay		17.5	14.9	16.2		
LOS		B	B	B		
Approach Delay		17.5	14.9	16.2		
Approach LOS		B	B	B		
Queue Length 50th (m)		23.9	15.6	12.8		
Queue Length 95th (m)		43.0	29.3	21.1		
Internal Link Dist (m)		53.7	62.8	73.7		
Turn Bay Length (m)						
Base Capacity (vph)		588	613	1031		
Starvation Cap Reductn		0	0	0		
Spillback Cap Reductn		0	0	0		
Storage Cap Reductn		0	0	0		
Reduced v/c Ratio		0.48	0.32	0.28		

#### Intersection Summary

Cycle Length: 65

Actuated Cycle Length: 65

Offset: 7 (11%), Referenced to phase 2:EBTL and 6:WBT, Start of Green

Natural Cycle: 50

Control Type: Pretimed

Maximum v/c Ratio: 0.48

Intersection Signal Delay: 16.4


Intersection LOS: B

Intersection Capacity Utilization 51.8%

ICU Level of Service A

Analysis Period (min) 15

Splits and Phases: 8: Bay & Laurier



	→	↑
Lane Group	EBT	NBT
Lane Configurations	↔↔	↔↔
Traffic Volume (vph)	440	400
Future Volume (vph)	440	400
Lane Group Flow (vph)	701	475
Turn Type	NA	NA
Protected Phases	2	8
Permitted Phases		
Minimum Split (s)	29.0	19.2
Total Split (s)	33.0	22.0
Total Split (%)	60.0%	40.0%
Yellow Time (s)	3.3	3.3
All-Red Time (s)	1.7	1.9
Lost Time Adjust (s)	0.0	0.0
Total Lost Time (s)	5.0	5.2
Lead/Lag		
Lead-Lag Optimize?		
Act Effect Green (s)	28.0	16.8
Actuated g/C Ratio	0.51	0.31
v/c Ratio	0.44	0.52
Control Delay	7.2	17.2
Queue Delay	0.0	0.0
Total Delay	7.2	17.2
LOS	A	B
Approach Delay	7.2	17.2
Approach LOS	A	B
Queue Length 50th (m)	14.8	19.0
Queue Length 95th (m)	24.6	30.7
Internal Link Dist (m)	103.1	73.0
Turn Bay Length (m)		
Base Capacity (vph)	1595	921
Starvation Cap Reductn	0	0
Spillback Cap Reductn	0	0
Storage Cap Reductn	0	0
Reduced v/c Ratio	0.44	0.52

#### Intersection Summary

Cycle Length: 55	
Actuated Cycle Length: 55	
Offset: 39 (71%), Referenced to phase 2:EBTL, Start of Green	
Natural Cycle: 50	
Control Type: Pretimed	
Maximum v/c Ratio: 0.52	
Intersection Signal Delay: 11.2	Intersection LOS: B
Intersection Capacity Utilization 46.0%	ICU Level of Service A
Analysis Period (min) 15	

Splits and Phases: 1: Bay & Slater








Lane Group	WBT	WBR	NBT
Lane Configurations	↑↑	↑	↑↑
Traffic Volume (vph)	458	161	550
Future Volume (vph)	458	161	550
Lane Group Flow (vph)	482	169	612
Turn Type	NA	Perm	NA
Protected Phases	8		2
Permitted Phases		8	
Minimum Split (s)	20.2	20.2	23.2
Total Split (s)	28.0	28.0	27.0
Total Split (%)	50.9%	50.9%	49.1%
Yellow Time (s)	3.3	3.3	3.3
All-Red Time (s)	1.9	1.9	1.9
Lost Time Adjust (s)	0.0	0.0	0.0
Total Lost Time (s)	5.2	5.2	5.2
Lead/Lag			
Lead-Lag Optimize?			
Act Effect Green (s)	22.8	22.8	21.8
Actuated g/C Ratio	0.41	0.41	0.40
v/c Ratio	0.38	0.29	0.50
Control Delay	12.3	4.0	9.7
Queue Delay	0.0	0.0	0.4
Total Delay	12.3	4.0	10.1
LOS	B	A	B
Approach Delay	10.2		10.1
Approach LOS	B		B
Queue Length 50th (m)	16.6	0.5	8.1
Queue Length 95th (m)	26.3	9.4	27.3
Internal Link Dist (m)	122.0		55.8
Turn Bay Length (m)		75.0	
Base Capacity (vph)	1264	581	1232
Starvation Cap Reductn	0	0	237
Spillback Cap Reductn	0	0	0
Storage Cap Reductn	0	0	0
Reduced v/c Ratio	0.38	0.29	0.62

#### Intersection Summary

Cycle Length: 55  
 Actuated Cycle Length: 55  
 Offset: 26 (47%), Referenced to phase 2:NBT, Start of Green  
 Natural Cycle: 45  
 Control Type: Pretimed  
 Maximum v/c Ratio: 0.50  
 Intersection Signal Delay: 10.1  
 Intersection Capacity Utilization 45.7%  
 Analysis Period (min) 15

Intersection LOS: B  
 ICU Level of Service A

Splits and Phases: 2: Bay & Albert



	→	↓
Lane Group	EBT	SBT
Lane Configurations	↕↕	↕↕↕
Traffic Volume (vph)	323	863
Future Volume (vph)	323	863
Lane Group Flow (vph)	517	1113
Turn Type	NA	NA
Protected Phases	4	6
Permitted Phases		
Minimum Split (s)	21.2	24.3
Total Split (s)	35.0	40.0
Total Split (%)	46.7%	53.3%
Yellow Time (s)	3.3	3.3
All-Red Time (s)	1.9	2.0
Lost Time Adjust (s)	0.0	0.0
Total Lost Time (s)	5.2	5.3
Lead/Lag		
Lead-Lag Optimize?		
Act Effect Green (s)	29.8	34.7
Actuated g/C Ratio	0.40	0.46
v/c Ratio	0.43	0.54
Control Delay	15.0	3.3
Queue Delay	0.0	0.4
Total Delay	15.0	3.6
LOS	B	A
Approach Delay	15.0	3.6
Approach LOS	B	A
Queue Length 50th (m)	22.5	5.7
Queue Length 95th (m)	34.7	7.3
Internal Link Dist (m)	123.5	56.3
Turn Bay Length (m)		
Base Capacity (vph)	1198	2058
Starvation Cap Reductn	0	399
Spillback Cap Reductn	0	0
Storage Cap Reductn	0	0
Reduced v/c Ratio	0.43	0.67

#### Intersection Summary

Cycle Length: 75

Actuated Cycle Length: 75

Offset: 4 (5%), Referenced to phase 6:SBTL, Start of Green

Natural Cycle: 50

Control Type: Pretimed

Maximum v/c Ratio: 0.54

Intersection Signal Delay: 7.2


Intersection LOS: A


Intersection Capacity Utilization 49.7%

ICU Level of Service A

Analysis Period (min) 15

Splits and Phases: 3: Lyon & Slater





Lane Group	WBT	SBT
Lane Configurations	↔↔	↔↔
Traffic Volume (vph)	466	973
Future Volume (vph)	466	973
Lane Group Flow (vph)	645	1024
Turn Type	NA	NA
Protected Phases	6	4
Permitted Phases		
Minimum Split (s)	23.4	21.5
Total Split (s)	38.0	37.0
Total Split (%)	50.7%	49.3%
Yellow Time (s)	3.3	3.3
All-Red Time (s)	2.1	2.2
Lost Time Adjust (s)	0.0	0.0
Total Lost Time (s)	5.4	5.5
Lead/Lag		
Lead-Lag Optimize?		
Act Effect Green (s)	32.6	31.5
Actuated g/C Ratio	0.43	0.42
v/c Ratio	0.48	0.80
Control Delay	15.6	24.9
Queue Delay	0.0	0.0
Total Delay	15.6	24.9
LOS	B	C
Approach Delay	15.6	24.9
Approach LOS	B	C
Queue Length 50th (m)	30.7	64.2
Queue Length 95th (m)	44.5	88.2
Internal Link Dist (m)	53.7	61.6
Turn Bay Length (m)		
Base Capacity (vph)	1333	1281
Starvation Cap Reductn	0	0
Spillback Cap Reductn	0	0
Storage Cap Reductn	0	0
Reduced v/c Ratio	0.48	0.80

#### Intersection Summary

Cycle Length: 75

Actuated Cycle Length: 75

Offset: 37 (49%), Referenced to phase 6:WBTL, Start of Green

Natural Cycle: 55

Control Type: Pretimed

Maximum v/c Ratio: 0.80

Intersection Signal Delay: 21.3


Intersection LOS: C










Intersection Capacity Utilization 60.7%

ICU Level of Service B

Analysis Period (min) 15

Splits and Phases: 4: Lyon & Albert











					
Lane Group	EBL	EBT	WBT	WBR	NBT
Lane Configurations					
Traffic Volume (vph)	109	57	212	172	611
Future Volume (vph)	109	57	212	172	611
Lane Group Flow (vph)	0	175	223	181	717
Turn Type	Perm	NA	NA	Perm	NA
Protected Phases		2	6		8
Permitted Phases	2			6	
Minimum Split (s)	21.1	21.1	21.1	21.1	29.1
Total Split (s)	22.0	22.0	22.0	22.0	33.0
Total Split (%)	40.0%	40.0%	40.0%	40.0%	60.0%
Yellow Time (s)	3.3	3.3	3.3	3.3	3.3
All-Red Time (s)	1.8	1.8	1.8	1.8	1.8
Lost Time Adjust (s)		-1.1	-1.1	-1.1	-1.1
Total Lost Time (s)		4.0	4.0	4.0	4.0
Lead/Lag					
Lead-Lag Optimize?					
Act Effect Green (s)		18.0	18.0	18.0	29.0
Actuated g/C Ratio		0.33	0.33	0.33	0.53
v/c Ratio		0.49	0.42	0.32	0.45
Control Delay		20.5	17.6	4.5	3.0
Queue Delay		0.0	0.0	0.0	0.0
Total Delay		20.5	17.6	4.5	3.0
LOS		C	B	A	A
Approach Delay		20.5	11.7		3.0
Approach LOS		C	B		A
Queue Length 50th (m)		13.7	17.0	0.0	4.4
Queue Length 95th (m)		29.1	32.6	10.5	9.0
Internal Link Dist (m)		52.1	53.3		60.9
Turn Bay Length (m)					
Base Capacity (vph)		357	525	568	1598
Starvation Cap Reductn		0	0	0	42
Spillback Cap Reductn		0	0	0	0
Storage Cap Reductn		0	0	0	0
Reduced v/c Ratio		0.49	0.42	0.32	0.46

#### Intersection Summary

Cycle Length: 55	
Actuated Cycle Length: 55	
Offset: 3 (5%), Referenced to phase 2:EBTL and 6:WBT, Start of Green	
Natural Cycle: 55	
Control Type: Pretimed	
Maximum v/c Ratio: 0.49	
Intersection Signal Delay: 8.1	Intersection LOS: A
Intersection Capacity Utilization 56.0%	ICU Level of Service B
Analysis Period (min) 15	

Splits and Phases: 7: Bay & Queen




						
Lane Group	EBL	EBT	WBT	NBT	Ø1	Ø5
Lane Configurations						
Traffic Volume (vph)	37	109	222	278		
Future Volume (vph)	37	109	222	278		
Lane Group Flow (vph)	0	154	441	335		
Turn Type	Perm	NA	NA	NA		
Protected Phases		2	6	8	1	5
Permitted Phases	2					
Minimum Split (s)	20.4	20.4	20.4	23.4	5.0	5.0
Total Split (s)	31.0	31.0	31.0	24.0	5.0	5.0
Total Split (%)	51.7%	51.7%	51.7%	40.0%	8%	8%
Yellow Time (s)	3.3	3.3	3.3	3.3	2.0	2.0
All-Red Time (s)	2.1	2.1	2.1	2.1	0.0	0.0
Lost Time Adjust (s)		-1.4	-1.4	-1.4		
Total Lost Time (s)		4.0	4.0	4.0		
Lead/Lag	Lag	Lag	Lag		Lead	Lead
Lead-Lag Optimize?	Yes	Yes	Yes		Yes	Yes
Act Effect Green (s)		27.0	27.0	20.0		
Actuated g/C Ratio		0.45	0.45	0.33		
v/c Ratio		0.25	0.65	0.34		
Control Delay		11.6	18.5	16.2		
Queue Delay		0.0	0.0	0.0		
Total Delay		11.6	18.5	16.2		
LOS		B	B	B		
Approach Delay		11.6	18.5	16.2		
Approach LOS		B	B	B		
Queue Length 50th (m)		9.9	35.6	14.2		
Queue Length 95th (m)		20.2	63.1	23.3		
Internal Link Dist (m)		53.7	52.3	65.9		
Turn Bay Length (m)						
Base Capacity (vph)		614	677	1000		
Starvation Cap Reductn		0	0	0		
Spillback Cap Reductn		0	0	0		
Storage Cap Reductn		0	0	0		
Reduced v/c Ratio		0.25	0.65	0.34		

#### Intersection Summary

Cycle Length: 60  
 Actuated Cycle Length: 60  
 Offset: 23 (38%), Referenced to phase 2:EBTL and 6:WBT, Start of Green  
 Natural Cycle: 60  
 Control Type: Pretimed  
 Maximum v/c Ratio: 0.65  
 Intersection Signal Delay: 16.5  
 Intersection LOS: B  
 Intersection Capacity Utilization 57.4%  
 ICU Level of Service B  
 Analysis Period (min) 15

Splits and Phases: 8: Bay & Laurier





# Appendix I

Truck Turning Templates

---









**PARSONS**

NOTE: The location of utilities is approximate only, the exact location should be determined by consulting the municipal authorities and utility companies concerned. The contractor shall prove the location of utilities and shall be responsible for adequate protection from damage.



Legend



MSU

10.00


0.50 8.50


Wash : 2.80  
Track : 2.80  
Look to Lock Time : 6.0  
Steering Angle : 40.2

Not to Scale

Drawing Description			
Garbage Truck Maneuvering			
Client	Main and Main	Date	April 27, 2020
Project Number	477196	Figure Number	001
Project Description		400 Albert Street	








NOTE: The location of utilities is approximate only, the exact location should be determined by consulting the municipal authorities and utility companies concerned. The contractor shall prove the location of utilities and shall be responsible for adequate protection from damage.

Legend




WB12

Tractor Width	2.80	Lock to Lock Time	6.0
Tractor Track	2.80	Steering Angle	21.3
Tractor Track	2.80	Articulating Angle	70.0

Not to Scale

Drawing Description					
Transport (WB-12) Truck Maneuvering					
Client	Main and Main	Date	April 27, 2020	Figure Number	003
Project Number	477196	Project Description	400 Albert Street		






NOTE: The location of utilities is approximate only, the exact location should be determined by consulting the municipal authorities and utility companies concerned. The contractor shall prove the location of utilities and shall be responsible for adequate protection from damage.



Legend



WB-20

Tractor Width	: 2.80	Lock to Lock Time	: 6.0
Tractor Wheel	: 2.80	Swiveling Angle	: 28.2
Tractor Track	: 2.80	Articulating Angle	: 70.0
Tractor Track	: 2.80		

Not to Scale

Drawing Description

Transport (WB-20) Truck Maneuvering

Client

Main and Main

Date

April 27, 2020

Figure Number

002

Project Number

477196

Project Description

400 Albert Street

# Appendix J

MMLoS and SYNCHRO Analysis – Projected Conditions

---

Multi-Modal Level of Service - Intersections Form

Consultant  
Scenario  
Comments

Parsons

Future Proposed Bay Street

Project  
Date

Bay Street Cycling

May-20

INTERSECTIONS		Laurier/Bay				Slater/Bay				Albert/Bay				Queen/Bay				Albert/Lyon				Slater/Lyon			
Crossing Side		NORTH	SOUTH	EAST	WEST	NORTH	SOUTH	EAST	WEST	NORTH	SOUTH	EAST	WEST	NORTH	SOUTH	EAST	WEST	NORTH	SOUTH	EAST	WEST	NORTH	SOUTH	EAST	WEST
Pedestrian	Lanes	0 - 2	0 - 2	0 - 2	0 - 2	0 - 2	0 - 2	0 - 2	0 - 2	0 - 2	0 - 2	3	0 - 2	0 - 2	0 - 2	3	0 - 2	3	3	0 - 2	0 - 2	3	3	0 - 2	0 - 2
	Median	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m	No Median - 2.4 m
	Conflicting Left Turns	Protected/ Permissive	No left turn / Prohib.	No left turn / Prohib.	Permissive	Permissive	No left turn / Prohib.	No left turn / Prohib.	No left turn / Prohib.	No left turn / Prohib.	No left turn / Prohib.	No left turn / Prohib.	No left turn / Prohib.	Permissive	Permissive	No left turn / Prohib.	No left turn / Prohib.	Permissive	No left turn / Prohib.	Permissive	No left turn / Prohib.	No left turn / Prohib.	No left turn / Prohib.	Permissive	No left turn / Prohib.
	Conflicting Right Turns	Permissive or yield control	No right turn	Permissive or yield control	No right turn	No right turn	No right turn	Permissive or yield control	No right turn	Permissive or yield control	No right turn	No right turn	No right turn	Permissive or yield control	No right turn	Permissive or yield control	No right turn	No right turn	No right turn	No right turn	Permissive or yield control	No right turn	No right turn	Permissive or yield control	No right turn
	Right Turns on Red (RTor) ?	RTOR prohibited	RTOR prohibited	RTOR prohibited	RTOR prohibited	RTOR prohibited	RTOR prohibited	RTOR prohibited	RTOR prohibited	RTOR prohibited	RTOR prohibited	RTOR prohibited	RTOR prohibited	RTOR prohibited	RTOR prohibited	RTOR prohibited	RTOR prohibited	RTOR prohibited	RTOR prohibited	RTOR prohibited	RTOR prohibited	RTOR prohibited	RTOR prohibited	RTOR prohibited	RTOR prohibited
	Ped Signal Leading Interval?	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	No	No	No	No	Yes	Yes	No	No	Yes	Yes
	Right Turn Channel	No Channel	No Channel	No Channel	No Channel	No Channel	No Channel	No Channel	No Channel	No Channel	No Channel	No Channel	No Channel	No Channel	No Channel	No Channel	No Channel	No Channel	No Channel	No Channel	No Channel	No Channel	No Channel	No Channel	No Channel
	Corner Radius	3-5m	3-5m	3-5m	3-5m	3-5m	3-5m	3-5m	3-5m	3-5m	3-5m	3-5m	3-5m	3-5m	3-5m	3-5m	3-5m	3-5m	3-5m	3-5m	3-5m	3-5m	3-5m	3-5m	3-5m
	Crosswalk Type	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings	Std transverse markings
	PETSI Score	92	105	100	97	97	105	100	105	100	105	90	97	92	105	83	95	88	80	105	100	88	83	97	105
	Ped. Exposure to Traffic LoS	A	A	A	A	A	A	A	A	A	A	A	A	A	A	B	A	B	B	A	A	B	B	A	A
	Cycle Length	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60
	Effective Walk Time	19	19	11	11	31	31	7	7	22	22	9	9	16	16	18	18	14	14	19	19	20	20	18	18
	Average Pedestrian Delay	14	14	20	20	7	7	23	23	12	12	22	22	16	16	15	15	18	18	14	14	13	13	15	15
	Pedestrian Delay LoS	B	B	C	C	A	A	C	C	B	B	C	C	B	B	B	B	B	B	B	B	B	B	B	B
	Level of Service	B	B	C	C	A	A	C	C	B	B	C	C	B	B	B	B	B	B	B	B	B	B	B	B
Approach From		C				C				C				B				B				B			
Bicycle	Bicycle Lane Arrangement on Approach	Curb Bike Lane, Cycletrack or MUP	Curb Bike Lane, Cycletrack or MUP	Curb Bike Lane, Cycletrack or MUP	Curb Bike Lane, Cycletrack or MUP	Curb Bike Lane, Cycletrack or MUP	Curb Bike Lane, Cycletrack or MUP		Curb Bike Lane, Cycletrack or MUP	Curb Bike Lane, Cycletrack or MUP	Curb Bike Lane, Cycletrack or MUP	Curb Bike Lane, Cycletrack or MUP	Curb Bike Lane, Cycletrack or MUP	Curb Bike Lane, Cycletrack or MUP	Curb Bike Lane, Cycletrack or MUP			Mixed Traffic		Curb Bike Lane, Cycletrack or MUP		Curb Bike Lane, Cycletrack or MUP		Curb Bike Lane, Cycletrack or MUP	
	Right Turn Lane Configuration																	≤ 50 m							
	Right Turning Speed																	≤ 25 km/h							
	Cyclist relative to RT motorists	Not Applicable	Not Applicable	Not Applicable	Not Applicable	Not Applicable	Not Applicable	-	Not Applicable	Not Applicable	Not Applicable	-	Not Applicable	Not Applicable	-	-	-	D	-	Not Applicable	-	Not Applicable	-	Not Applicable	
	Separated or Mixed Traffic	Separated	Separated	Separated	Separated	Separated	Separated	-	Separated	Separated	Separated	-	Separated	Separated	-	-	-	Mixed Traffic	-	Separated	-	Separated	-	Separated	
	Left Turn Approach	2-stage, LT box	2-stage, LT box	2-stage, LT box		2-stage, LT box	2-stage, LT box		2-stage, LT box		2-stage, LT box	2-stage, LT box		2-stage, LT box	2-stage, LT box	No lane crossed	No lane crossed	No lane crossed		2-stage, LT box		2-stage, LT box		2-stage, LT box	
	Operating Speed	> 40 to ≤ 50 km/h	> 40 to ≤ 50 km/h	> 40 to ≤ 50 km/h		> 40 to ≤ 50 km/h	> 40 to ≤ 50 km/h		> 40 to ≤ 50 km/h		> 40 to ≤ 50 km/h	> 40 to ≤ 50 km/h		> 40 to ≤ 50 km/h	> 40 to ≤ 50 km/h	> 40 to ≤ 50 km/h	> 40 to ≤ 50 km/h	≤ 40 km/h		> 40 to ≤ 50 km/h		> 40 to ≤ 50 km/h		> 40 to ≤ 50 km/h	
Left Turning Cyclist	A	A	A	-	A	A	-	A	-	A	A	-	A	A	B	B	B	-	A	-	A	-	-		
Level of Service	A	A	A	-	A	A	-	A	-	A	A	-	A	A	B	B	D	-	A	-	A	-	-		
Approach From		A				A				A				B				D				A			
Transit	Average Signal Delay							≤ 10 sec				≤ 20 sec	≤ 20 sec			≤ 10 sec		≤ 20 sec						≤ 10 sec	
	Level of Service	-	-	-	-	-	-	B	-	-	-	C	C	-	-	B	-	-	-	-	-	B	-	-	
		-				B				C				B				C				B			
Truck	Effective Corner Radius		10 - 15 m	10 - 15 m				< 10 m				< 10 m			10 - 15 m	< 10 m		< 10 m			< 10 m			< 10 m	
	Number of Receiving Lanes on Departure from Intersection		1	≥ 2			≥ 2					≥ 2			1	≥ 2		≥ 2			≥ 2			≥ 2	
	Level of Service	-	E	B	-	D	-	-	-	-	-	D	-	-	E	D	-	D	-	-	-	-	-	D	
		E				D				D				E				D				D			
Auto	Volume to Capacity Ratio		0.71 - 0.80				0.61 - 0.70					0.0 - 0.60				0.71 - 0.80				0.81 - 0.90				0.71 - 0.80	
	Level of Service	C				B				A				C				D				C			

Future AM  
1: Bay & Slater

04/23/2020

	→	↑		
Lane Group	EBT	NBT	Ø1	Ø7
Lane Configurations	↔↔	↔↔		
Traffic Volume (vph)	736	244		
Future Volume (vph)	736	244		
Lane Group Flow (vph)	932	320		
Turn Type	NA	NA		
Protected Phases	2	8	1	7
Permitted Phases				
Minimum Split (s)	29.0	19.2	5.0	5.0
Total Split (s)	41.0	19.0	5.0	5.0
Total Split (%)	58.6%	27.1%	7%	7%
Yellow Time (s)	3.3	3.3	2.0	2.0
All-Red Time (s)	1.7	1.9	0.0	0.0
Lost Time Adjust (s)	0.0	0.0		
Total Lost Time (s)	5.0	5.2		
Lead/Lag	Lag	Lag	Lead	Lead
Lead-Lag Optimize?	Yes	Yes	Yes	Yes
Act Effct Green (s)	36.0	13.8		
Actuated g/C Ratio	0.51	0.20		
v/c Ratio	0.59	0.54		
Control Delay	12.3	15.4		
Queue Delay	0.0	0.0		
Total Delay	12.3	15.4		
LOS	B	B		
Approach Delay	12.3	15.4		
Approach LOS	B	B		
Queue Length 50th (m)	36.7	8.5		
Queue Length 95th (m)	53.2	14.2		
Internal Link Dist (m)	111.5	72.8		
Turn Bay Length (m)				
Base Capacity (vph)	1587	588		
Starvation Cap Reductn	0	0		
Spillback Cap Reductn	0	0		
Storage Cap Reductn	0	0		
Reduced v/c Ratio	0.59	0.54		

Intersection Summary

Cycle Length: 70

Actuated Cycle Length: 70

Offset: 3 (4%), Referenced to phase 2:EBTL, Start of Green

Natural Cycle: 60

Control Type: Pretimed

Maximum v/c Ratio: 0.59

Intersection Signal Delay: 13.1


Intersection LOS: B

Intersection Capacity Utilization 51.5%

ICU Level of Service A

Analysis Period (min) 15

Splits and Phases: 1: Bay & Slater



Future AM  
2: Bay & Albert

04/23/2020



Lane Group	WBT	WBR	NBT	Ø1	Ø7
Lane Configurations	↑↑	↑	↑↑		
Traffic Volume (vph)	279	119	416		
Future Volume (vph)	279	119	416		
Lane Group Flow (vph)	279	119	476		
Turn Type	NA	Perm	NA		
Protected Phases	8		2	1	7
Permitted Phases		8			
Minimum Split (s)	20.2	20.2	23.2	5.0	5.0
Total Split (s)	35.0	35.0	25.0	5.0	5.0
Total Split (%)	50.0%	50.0%	35.7%	7%	7%
Yellow Time (s)	3.3	3.3	3.3	2.0	2.0
All-Red Time (s)	1.9	1.9	1.9	0.0	0.0
Lost Time Adjust (s)	0.0	0.0	0.0		
Total Lost Time (s)	5.2	5.2	5.2		
Lead/Lag	Lag	Lag	Lag	Lead	Lead
Lead-Lag Optimize?	Yes	Yes	Yes	Yes	Yes
Act Effct Green (s)	29.8	29.8	19.8		
Actuated g/C Ratio	0.43	0.43	0.28		
v/c Ratio	0.21	0.18	0.52		
Control Delay	13.3	3.6	19.0		
Queue Delay	0.0	0.0	0.4		
Total Delay	13.3	3.6	19.3		
LOS	B	A	B		
Approach Delay	10.4		19.3		
Approach LOS	B		B		
Queue Length 50th (m)	11.6	0.0	23.9		
Queue Length 95th (m)	18.8	8.2	42.1		
Internal Link Dist (m)	123.5		54.5		
Turn Bay Length (m)		75.0			
Base Capacity (vph)	1298	649	911		
Starvation Cap Reductn	0	0	118		
Spillback Cap Reductn	0	0	0		
Storage Cap Reductn	0	0	0		
Reduced v/c Ratio	0.21	0.18	0.60		

Intersection Summary

Cycle Length: 70

Actuated Cycle Length: 70

Offset: 58 (83%), Referenced to phase 2:NBTL, Start of Green

Natural Cycle: 55

Control Type: Pretimed

Maximum v/c Ratio: 0.52

Intersection Signal Delay: 15.3


Intersection LOS: B

Intersection Capacity Utilization 33.2%

ICU Level of Service A

Analysis Period (min) 15

Splits and Phases: 2: Bay & Albert





	→	↓	
Lane Group	EBT	SBT	Ø3
Lane Configurations	↕↕	↕↕↕	
Traffic Volume (vph)	637	818	
Future Volume (vph)	637	818	
Lane Group Flow (vph)	812	1073	
Turn Type	NA	NA	
Protected Phases	4	6	3
Permitted Phases			
Minimum Split (s)	21.2	24.3	5.0
Total Split (s)	29.0	31.0	5.0
Total Split (%)	44.6%	47.7%	8%
Yellow Time (s)	3.3	3.3	2.0
All-Red Time (s)	1.9	2.0	0.0
Lost Time Adjust (s)	0.0	0.0	
Total Lost Time (s)	5.2	5.3	
Lead/Lag	Lag		Lead
Lead-Lag Optimize?	Yes		Yes
Act Effct Green (s)	23.8	25.7	
Actuated g/C Ratio	0.37	0.40	
v/c Ratio	0.72	0.60	
Control Delay	20.9	8.0	
Queue Delay	0.0	0.2	
Total Delay	20.9	8.2	
LOS	C	A	
Approach Delay	20.9	8.2	
Approach LOS	C	A	
Queue Length 50th (m)	40.0	2.1	
Queue Length 95th (m)	59.0	21.6	
Internal Link Dist (m)	124.5	56.5	
Turn Bay Length (m)			
Base Capacity (vph)	1120	1798	
Starvation Cap Reductn	0	197	
Spillback Cap Reductn	0	0	
Storage Cap Reductn	0	0	
Reduced v/c Ratio	0.72	0.67	

#### Intersection Summary

Cycle Length: 65

Actuated Cycle Length: 65

Offset: 14 (22%), Referenced to phase 6:SBTL, Start of Green

Natural Cycle: 55

Control Type: Pretimed

Maximum v/c Ratio: 0.72

Intersection Signal Delay: 13.7


Intersection LOS: B


Intersection Capacity Utilization 60.6%

ICU Level of Service B

Analysis Period (min) 15

Splits and Phases: 3: Lyon & Slater






Lane Group	WBT	SBT	Ø3
Lane Configurations	↔↔	↔↔	
Traffic Volume (vph)	266	1005	
Future Volume (vph)	266	1005	
Lane Group Flow (vph)	404	1005	
Turn Type	NA	NA	
Protected Phases	6	4	3
Permitted Phases			
Minimum Split (s)	20.4	21.5	5.0
Total Split (s)	27.0	33.0	5.0
Total Split (%)	41.5%	50.8%	8%
Yellow Time (s)	3.3	3.3	2.0
All-Red Time (s)	2.1	2.2	0.0
Lost Time Adjust (s)	0.0	0.0	
Total Lost Time (s)	5.4	5.5	
Lead/Lag		Lag	Lead
Lead-Lag Optimize?		Yes	Yes
Act Effct Green (s)	21.6	27.5	
Actuated g/C Ratio	0.33	0.42	
v/c Ratio	0.37	0.78	
Control Delay	11.8	21.4	
Queue Delay	0.0	0.0	
Total Delay	11.8	21.4	
LOS	B	C	
Approach Delay	11.8	21.4	
Approach LOS	B	C	
Queue Length 50th (m)	12.1	52.5	
Queue Length 95th (m)	22.0	74.6	
Internal Link Dist (m)	117.5	50.0	
Turn Bay Length (m)			
Base Capacity (vph)	1088	1290	
Starvation Cap Reductn	0	0	
Spillback Cap Reductn	0	0	
Storage Cap Reductn	0	0	
Reduced v/c Ratio	0.37	0.78	










#### Intersection Summary

Cycle Length: 65  
 Actuated Cycle Length: 65  
 Offset: 48 (74%), Referenced to phase 6:WBTL, Start of Green  
 Natural Cycle: 55  
 Control Type: Pretimed  
 Maximum v/c Ratio: 0.78  
 Intersection Signal Delay: 18.7  
 Intersection Capacity Utilization 55.0%  
 Analysis Period (min) 15

Intersection LOS: B  
 ICU Level of Service A

Splits and Phases: 4: Lyon & Albert




						
Lane Group	EBL	EBT	WBT	WBR	NBT	Ø7
Lane Configurations						
Traffic Volume (vph)	233	184	187	105	400	
Future Volume (vph)	233	184	187	105	400	
Lane Group Flow (vph)	0	417	187	105	492	
Turn Type	Perm	NA	NA	Perm	NA	
Protected Phases		2	6		8	7
Permitted Phases	2			6		
Minimum Split (s)	21.1	21.1	21.1	21.1	29.1	5.0
Total Split (s)	30.0	30.0	30.0	30.0	30.0	5.0
Total Split (%)	46.2%	46.2%	46.2%	46.2%	46.2%	8%
Yellow Time (s)	3.3	3.3	3.3	3.3	3.3	2.0
All-Red Time (s)	1.8	1.8	1.8	1.8	1.8	0.0
Lost Time Adjust (s)		0.0	0.0	0.0	0.0	
Total Lost Time (s)		5.1	5.1	5.1	5.1	
Lead/Lag					Lag	Lead
Lead-Lag Optimize?					Yes	Yes
Act Effct Green (s)		24.9	24.9	24.9	24.9	
Actuated g/C Ratio		0.38	0.38	0.38	0.38	
v/c Ratio		0.93	0.30	0.18	0.42	
Control Delay		52.2	15.7	4.1	15.0	
Queue Delay		0.0	0.0	0.0	0.5	
Total Delay		52.2	15.7	4.1	15.4	
LOS		D	B	A	B	
Approach Delay		52.2	11.6		15.4	
Approach LOS		D	B		B	
Queue Length 50th (m)		46.8	15.2	0.0	20.3	
Queue Length 95th (m)		#97.1	28.7	7.9	31.7	
Internal Link Dist (m)		51.6	57.9		57.5	
Turn Bay Length (m)						
Base Capacity (vph)		446	615	587	1162	
Starvation Cap Reductn		0	0	0	296	
Spillback Cap Reductn		0	0	0	0	
Storage Cap Reductn		0	0	0	0	
Reduced v/c Ratio		0.93	0.30	0.18	0.57	

#### Intersection Summary

Cycle Length: 65	
Actuated Cycle Length: 65	
Offset: 31 (48%), Referenced to phase 2:EBTL and 6:WBT, Start of Green	
Natural Cycle: 70	
Control Type: Pretimed	
Maximum v/c Ratio: 0.93	
Intersection Signal Delay: 27.3	Intersection LOS: C
Intersection Capacity Utilization 67.1%	ICU Level of Service C
Analysis Period (min) 15	
# 95th percentile volume exceeds capacity, queue may be longer.	
Queue shown is maximum after two cycles.	

#### Splits and Phases: 7: Bay & Queen





					Ø1	Ø5	Ø7
Lane Group	EBL	EBT	WBT	NBT	Ø1	Ø5	Ø7
Lane Configurations							
Traffic Volume (vph)	58	209	96	262			
Future Volume (vph)	58	209	96	262			
Lane Group Flow (vph)	0	267	189	321			
Turn Type	Perm	NA	NA	NA			
Protected Phases		2	6	8	1	5	7
Permitted Phases	2						
Minimum Split (s)	20.4	20.4	20.4	23.4	5.0	5.0	5.0
Total Split (s)	32.0	32.0	32.0	28.0	5.0	5.0	5.0
Total Split (%)	45.7%	45.7%	45.7%	40.0%	7%	7%	7%
Yellow Time (s)	3.3	3.3	3.3	3.3	2.0	2.0	2.0
All-Red Time (s)	2.1	2.1	2.1	2.1	0.0	0.0	0.0
Lost Time Adjust (s)		0.0	0.0	0.0			
Total Lost Time (s)		5.4	5.4	5.4			
Lead/Lag	Lag	Lag	Lag	Lag	Lead	Lead	Lead
Lead-Lag Optimize?	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Act Effect Green (s)		26.6	26.6	22.6			
Actuated g/C Ratio		0.38	0.38	0.32			
v/c Ratio		0.49	0.33	0.33			
Control Delay		20.3	17.5	19.2			
Queue Delay		0.0	0.0	0.0			
Total Delay		20.3	17.5	19.2			
LOS		C	B	B			
Approach Delay		20.3	17.5	19.2			
Approach LOS		C	B	B			
Queue Length 50th (m)		25.9	17.1	16.5			
Queue Length 95th (m)		45.9	31.6	26.2			
Internal Link Dist (m)		53.7	62.8	73.7			
Turn Bay Length (m)							
Base Capacity (vph)		546	570	962			
Starvation Cap Reductn		0	0	0			
Spillback Cap Reductn		0	0	0			
Storage Cap Reductn		0	0	0			
Reduced v/c Ratio		0.49	0.33	0.33			

#### Intersection Summary

Cycle Length: 70

Actuated Cycle Length: 70

Offset: 7 (10%), Referenced to phase 2:EBTL and 6:WBT, Start of Green

Natural Cycle: 55

Control Type: Pretimed

Maximum v/c Ratio: 0.49

Intersection Signal Delay: 19.2


Intersection LOS: B

Intersection Capacity Utilization 53.4%

ICU Level of Service A

Analysis Period (min) 15

Splits and Phases: 8: Bay & Laurier



	→	↑		
Lane Group	EBT	NBT	Ø1	Ø7
Lane Configurations	↔↔	↔↔		
Traffic Volume (vph)	440	453		
Future Volume (vph)	440	453		
Lane Group Flow (vph)	698	504		
Turn Type	NA	NA		
Protected Phases	2	8	1	7
Permitted Phases				
Minimum Split (s)	29.0	19.2	5.0	5.0
Total Split (s)	33.0	22.0	5.0	5.0
Total Split (%)	50.8%	33.8%	8%	8%
Yellow Time (s)	3.3	3.3	2.0	2.0
All-Red Time (s)	1.7	1.9	0.0	0.0
Lost Time Adjust (s)	0.0	0.0		
Total Lost Time (s)	5.0	5.2		
Lead/Lag	Lag	Lag	Lead	Lead
Lead-Lag Optimize?	Yes	Yes	Yes	Yes
Act Effct Green (s)	28.0	16.8		
Actuated g/C Ratio	0.43	0.26		
v/c Ratio	0.50	0.65		
Control Delay	10.1	27.5		
Queue Delay	0.0	0.0		
Total Delay	10.1	27.5		
LOS	B	C		
Approach Delay	10.1	27.5		
Approach LOS	B	C		
Queue Length 50th (m)	19.1	34.0		
Queue Length 95th (m)	32.2	49.7		
Internal Link Dist (m)	103.1	73.0		
Turn Bay Length (m)				
Base Capacity (vph)	1400	779		
Starvation Cap Reductn	0	0		
Spillback Cap Reductn	0	0		
Storage Cap Reductn	0	0		
Reduced v/c Ratio	0.50	0.65		

#### Intersection Summary

Cycle Length: 65  
 Actuated Cycle Length: 65  
 Offset: 39 (60%), Referenced to phase 2:EBTL, Start of Green  
 Natural Cycle: 60  
 Control Type: Pretimed  
 Maximum v/c Ratio: 0.65  
 Intersection Signal Delay: 17.4  
 Intersection Capacity Utilization 48.7%  
 Analysis Period (min) 15

Intersection LOS: B  
 ICU Level of Service A

Splits and Phases: 1: Bay & Slater





Lane Group	WBT	WBR	NBT	Ø1	Ø7
Lane Configurations	↑↑	↑	↑↑		
Traffic Volume (vph)	520	222	594		
Future Volume (vph)	520	222	594		
Lane Group Flow (vph)	520	222	644		
Turn Type	NA	Perm	NA		
Protected Phases	8		2	1	7
Permitted Phases		8			
Minimum Split (s)	20.2	20.2	23.2	5.0	5.0
Total Split (s)	28.0	28.0	27.0	5.0	5.0
Total Split (%)	43.1%	43.1%	41.5%	8%	8%
Yellow Time (s)	3.3	3.3	3.3	2.0	2.0
All-Red Time (s)	1.9	1.9	1.9	0.0	0.0
Lost Time Adjust (s)	0.0	0.0	0.0		
Total Lost Time (s)	5.2	5.2	5.2		
Lead/Lag	Lag	Lag	Lag	Lead	Lead
Lead-Lag Optimize?	Yes	Yes	Yes	Yes	Yes
Act Effct Green (s)	22.8	22.8	21.8		
Actuated g/C Ratio	0.35	0.35	0.34		
v/c Ratio	0.49	0.41	0.59		
Control Delay	18.4	5.1	14.1		
Queue Delay	0.0	0.0	0.8		
Total Delay	18.4	5.1	14.9		
LOS	B	A	B		
Approach Delay	14.4		14.9		
Approach LOS	B		B		
Queue Length 50th (m)	25.2	0.0	36.7		
Queue Length 95th (m)	37.8	12.4	52.8		
Internal Link Dist (m)	122.0		55.8		
Turn Bay Length (m)		75.0			
Base Capacity (vph)	1070	545	1088		
Starvation Cap Reductn	0	0	194		
Spillback Cap Reductn	0	0	0		
Storage Cap Reductn	0	0	0		
Reduced v/c Ratio	0.49	0.41	0.72		

#### Intersection Summary

Cycle Length: 65

Actuated Cycle Length: 65

Offset: 26 (40%), Referenced to phase 2:NBT, Start of Green

Natural Cycle: 55

Control Type: Pretimed

Maximum v/c Ratio: 0.59

Intersection Signal Delay: 14.7


Intersection LOS: B

Intersection Capacity Utilization 52.2%

ICU Level of Service A

Analysis Period (min) 15

Splits and Phases: 2: Bay & Albert



	→	↓		
Lane Group	EBT	SBT	Ø3	Ø5
Lane Configurations	↕↕	↕↕↕		
Traffic Volume (vph)	323	875		
Future Volume (vph)	323	875		
Lane Group Flow (vph)	491	1070		
Turn Type	NA	NA		
Protected Phases	4	6	3	5
Permitted Phases				
Minimum Split (s)	21.2	24.3	5.0	5.0
Total Split (s)	35.0	40.0	5.0	5.0
Total Split (%)	41.2%	47.1%	6%	6%
Yellow Time (s)	3.3	3.3	2.0	2.0
All-Red Time (s)	1.9	2.0	0.0	0.0
Lost Time Adjust (s)	0.0	0.0		
Total Lost Time (s)	5.2	5.3		
Lead/Lag	Lag	Lag	Lead	Lead
Lead-Lag Optimize?	Yes	Yes	Yes	Yes
Act Effct Green (s)	29.8	34.7		
Actuated g/C Ratio	0.35	0.41		
v/c Ratio	0.45	0.59		
Control Delay	17.2	5.3		
Queue Delay	0.0	1.5		
Total Delay	17.2	6.8		
LOS	B	A		
Approach Delay	17.2	6.8		
Approach LOS	B	A		
Queue Length 50th (m)	23.3	6.2		
Queue Length 95th (m)	36.6	m7.6		
Internal Link Dist (m)	123.5	56.3		
Turn Bay Length (m)				
Base Capacity (vph)	1094	1821		
Starvation Cap Reductn	0	523		
Spillback Cap Reductn	0	0		
Storage Cap Reductn	0	0		
Reduced v/c Ratio	0.45	0.82		

#### Intersection Summary

Cycle Length: 85

Actuated Cycle Length: 85

Offset: 4 (5%), Referenced to phase 6:SBTL, Start of Green

Natural Cycle: 60

Control Type: Pretimed

Maximum v/c Ratio: 0.59

Intersection Signal Delay: 10.1

Intersection LOS: B


Intersection Capacity Utilization 50.0%


ICU Level of Service A

Analysis Period (min) 15

m Volume for 95th percentile queue is metered by upstream signal.

Splits and Phases: 3: Lyon & Slater





Lane Group	WBT	SBT	Ø3	Ø5
Lane Configurations	↔↔	↔↔		
Traffic Volume (vph)	558	985		
Future Volume (vph)	558	985		
Lane Group Flow (vph)	704	985		
Turn Type	NA	NA		
Protected Phases	6	4	3	5
Permitted Phases				
Minimum Split (s)	23.4	21.5	5.0	5.0
Total Split (s)	38.0	37.0	5.0	5.0
Total Split (%)	44.7%	43.5%	6%	6%
Yellow Time (s)	3.3	3.3	2.0	2.0
All-Red Time (s)	2.1	2.2	0.0	0.0
Lost Time Adjust (s)	0.0	0.0		
Total Lost Time (s)	5.4	5.5		
Lead/Lag	Lag	Lag	Lead	Lead
Lead-Lag Optimize?	Yes	Yes	Yes	Yes
Act Effct Green (s)	32.6	31.5		
Actuated g/C Ratio	0.38	0.37		
v/c Ratio	0.58	0.87		
Control Delay	20.5	35.1		
Queue Delay	0.0	0.0		
Total Delay	20.5	35.1		
LOS	C	D		
Approach Delay	20.5	35.1		
Approach LOS	C	D		
Queue Length 50th (m)	41.0	76.8		
Queue Length 95th (m)	58.1	#112.3		
Internal Link Dist (m)	53.7	61.6		
Turn Bay Length (m)				
Base Capacity (vph)	1209	1130		
Starvation Cap Reductn	0	0		
Spillback Cap Reductn	0	1		
Storage Cap Reductn	0	0		
Reduced v/c Ratio	0.58	0.87		

#### Intersection Summary

Cycle Length: 85

Actuated Cycle Length: 85

Offset: 37 (44%), Referenced to phase 6:WBTL, Start of Green

Natural Cycle: 60

Control Type: Pretimed

Maximum v/c Ratio: 0.87

Intersection Signal Delay: 29.0

Intersection LOS: C

Intersection Capacity Utilization 64.1%


ICU Level of Service C










Analysis Period (min) 15

# 95th percentile volume exceeds capacity, queue may be longer.

Queue shown is maximum after two cycles.

Splits and Phases: 4: Lyon & Albert





						
Lane Group	EBL	EBT	WBT	WBR	NBT	Ø7
Lane Configurations						
Traffic Volume (vph)	134	67	237	197	708	
Future Volume (vph)	134	67	237	197	708	
Lane Group Flow (vph)	0	201	237	197	796	
Turn Type	Perm	NA	NA	Perm	NA	
Protected Phases		2	6		8	7
Permitted Phases	2			6		
Minimum Split (s)	21.1	21.1	21.1	21.1	29.1	5.0
Total Split (s)	22.0	22.0	22.0	22.0	33.0	5.0
Total Split (%)	36.7%	36.7%	36.7%	36.7%	55.0%	8%
Yellow Time (s)	3.3	3.3	3.3	3.3	3.3	2.0
All-Red Time (s)	1.8	1.8	1.8	1.8	1.8	0.0
Lost Time Adjust (s)		-1.1	-1.1	-1.1	-1.1	
Total Lost Time (s)		4.0	4.0	4.0	4.0	
Lead/Lag					Lag	Lead
Lead-Lag Optimize?					Yes	Yes
Act Effct Green (s)		18.0	18.0	18.0	29.0	
Actuated g/C Ratio		0.30	0.30	0.30	0.48	
v/c Ratio		0.72	0.49	0.36	0.54	
Control Delay		36.9	21.5	5.1	12.3	
Queue Delay		0.0	0.0	0.0	0.8	
Total Delay		36.9	21.5	5.1	13.0	
LOS		D	C	A	B	
Approach Delay		36.9	14.0		13.0	
Approach LOS		D	B		B	
Queue Length 50th (m)		19.5	21.2	0.0	29.1	
Queue Length 95th (m)		#48.4	39.2	12.0	43.1	
Internal Link Dist (m)		52.1	53.3		60.9	
Turn Bay Length (m)						
Base Capacity (vph)		279	481	547	1465	
Starvation Cap Reductn		0	0	0	349	
Spillback Cap Reductn		0	0	0	0	
Storage Cap Reductn		0	0	0	0	
Reduced v/c Ratio		0.72	0.49	0.36	0.71	

#### Intersection Summary

Cycle Length: 60	
Actuated Cycle Length: 60	
Offset: 3 (5%), Referenced to phase 2:EBTL and 6:WBT, Start of Green	
Natural Cycle: 60	
Control Type: Pretimed	
Maximum v/c Ratio: 0.72	
Intersection Signal Delay: 16.7	Intersection LOS: B
Intersection Capacity Utilization 63.6%	ICU Level of Service B
Analysis Period (min) 15	
# 95th percentile volume exceeds capacity, queue may be longer.	
Queue shown is maximum after two cycles.	

#### Splits and Phases: 7: Bay & Queen




							
Lane Group	EBL	EBT	WBT	NBT	Ø1	Ø5	Ø7
Lane Configurations							
Traffic Volume (vph)	37	109	222	326			
Future Volume (vph)	37	109	222	326			
Lane Group Flow (vph)	0	146	424	365			
Turn Type	Perm	NA	NA	NA			
Protected Phases		2	6	8	1	5	7
Permitted Phases	2						
Minimum Split (s)	20.4	20.4	20.4	23.4	5.0	5.0	5.0
Total Split (s)	31.0	31.0	31.0	24.0	5.0	5.0	5.0
Total Split (%)	47.7%	47.7%	47.7%	36.9%	8%	8%	8%
Yellow Time (s)	3.3	3.3	3.3	3.3	2.0	2.0	2.0
All-Red Time (s)	2.1	2.1	2.1	2.1	0.0	0.0	0.0
Lost Time Adjust (s)		-1.4	-1.4	-1.4			
Total Lost Time (s)		4.0	4.0	4.0			
Lead/Lag	Lag	Lag	Lag	Lag	Lead	Lead	Lead
Lead-Lag Optimize?	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Act Effect Green (s)		27.0	27.0	20.0			
Actuated g/C Ratio		0.42	0.42	0.31			
v/c Ratio		0.26	0.68	0.39			
Control Delay		14.0	22.2	19.3			
Queue Delay		0.0	0.0	0.0			
Total Delay		14.0	22.2	19.3			
LOS		B	C	B			
Approach Delay		14.0	22.2	19.3			
Approach LOS		B	C	B			
Queue Length 50th (m)		11.1	40.0	18.0			
Queue Length 95th (m)		22.3	69.1	28.4			
Internal Link Dist (m)		53.7	52.3	65.9			
Turn Bay Length (m)							
Base Capacity (vph)		569	624	926			
Starvation Cap Reductn		0	0	0			
Spillback Cap Reductn		0	0	0			
Storage Cap Reductn		0	0	0			
Reduced v/c Ratio		0.26	0.68	0.39			

#### Intersection Summary

Cycle Length: 65  
 Actuated Cycle Length: 65  
 Offset: 23 (35%), Referenced to phase 2:EBTL and 6:WBT, Start of Green  
 Natural Cycle: 60  
 Control Type: Pretimed  
 Maximum v/c Ratio: 0.68  
 Intersection Signal Delay: 19.8  
 Intersection Capacity Utilization 59.3%  
 Analysis Period (min) 15

Intersection LOS: B  
 ICU Level of Service B

Splits and Phases: 8: Bay & Laurier



# Appendix K

Comment and Response Letter, Fall 2019

---



4 May 2020

OUR REF: 477196-01000

Albert and Main Development Inc.  
c/o Main and Main  
109 Atlantic Avenue  
Toronto, ON M6K 1X4

**Attention: Daniel Byrne**

Dear Daniel:

**Re: 400 Albert Street Transportation Impact Study  
City Comments and Responses**

The 400 Albert Street Transportation Impact Assessment (TIA) was submitted to the City of Ottawa in Fall 2019. City comments were received and are provided herein with corresponding responses provided by Parsons. The TIA report was updated as per these comments and this comment/response letter is provided within the TIA final submission as Appendix J.

**Comment 1:** *Albert Street is designated as an Arterial road within the City's Official Plan with a ROW protection. Maximum land requirement from property abutting existing ROW is 1.25 metres subject to widening/easement policy. The ROW limits are to be shown on all the drawings.*

**Response 1:** Noted and the proponent has been advised.

**Comment 2:** *Slater Street is designated as an Arterial road within the City's Official Plan with a ROW protection. Maximum land requirement from property abutting existing ROW is 1.25 metres subject to widening/easement policy. The ROW limits are to be shown on all the drawings.*

**Response 2:** Noted and the proponent has been advised.

**Comment 3:** *Lyon Street is designated as an Arterial road within the City's Official Plan with a ROW protection. Maximum land requirement from property abutting existing ROW is 0.9 metres subject to widening/easement policy. The ROW limits are to be shown on all the drawings.*

**Response 3:** Noted and the proponent has been advised.

**Comment 4:** *Confirm that the existing zoning allows for development that would generate 800 person trips during the peak hour. The report exempts Module 4.8 based on the zoning not allowing a development that would increase the person trips in the new zoning by more than 200 person trips during the peak hour.*

**Response 4:** Updated TIA (see section 4.7).

**Comment 5:** *Screening: Include Figure 2 (Proposed Site Plan). Ensure the submitted site plan includes base mapping of surrounding boundary streets and highlights accesses of neighbouring properties both adjacent to the site and across the road from the site. Include the proposed new accesses to the development at 383 Albert Street.*

**Response 5:** Updated TIA (see Appendix A) and the architect has been advised.

**Comment 6:** 2.1.2 Existing Conditions: Area Road Network: For Slater Street, clarify that off-peak parking (3pm-9am) is permitted in the north curb lane. For Albert Street, clarify that off-peak parking (3pm-9am) is permitted in the south curb lane. For Bay Street and Lyon Street, replace "cross-section" with "vehicular lane arrangement", otherwise the existing bike lane should be included in the cross-section description. Clarify why Queen Street is described but Laurier Avenue is not (Laurier/Bay intersection included in the study area).

**Response 6:** Updated TIA (see section 2.1.2).

**Comment 7:** Pedestrian / Cycling Network: Albert Street, Lyon Street, and Laurier Avenue are also classified as "spine" cycling routes. Queen Street is classified as a local cycling network.

**Response 7:** Updated TIA (see section 2.1.2).

**Comment 8:** Transit Network: Update Figure 4 with the latest OC Transpo service map and change descriptions of existing conditions throughout the report to include an in-service Confederation Line. Describe in more detail the layout of Lyon Station, the location of local and STO bus stops at this station, and the location of the closest station entrance to the proposed development.

**Response 8:** Updated TIA (see section 2.1.2).

**Comment 9:** Existing Study Area Intersections: At Bay/Queen, the westbound approach was recently reconstructed to include 1 westbound through lane and 1 westbound right turn lane. Describe the Bay/Laurier intersection as this intersection is included in the study area per Section 2.2.1. Note within the TIA that existing volumes are from Pre-LRT service conditions, and explain steps taken to remove/reallocate bus volumes and account for the recent southbound right turn prohibition at Lyon/Albert.

**Response 9:** Updated TIA (see section 2.1.2).

**Comment 10:** Existing Driveways: Provide a description of existing driveways to adjacent developments (both sides of all roads bordering the site) within 200m of a proposed site driveway, indicating the land use associated with the driveway.

**Response 10:** Updated TIA (see section 2.1.2).

**Comment 11:** Existing Road Safety Conditions: Provide number of collisions by intersection and by segment. provide further breakdown of the Slater/Bay intersection (highest collision rate). Clarify whether collisions involving active modes were concentrated at one location. This section claims, "related analysis is provided as Appendix C", however no analysis is provided in Appendix C.

**Response 11:** Updated TIA (see section 2.1.2).

**Comment 12:** 2.1.3 Planned Conditions: As previously noted, assume Stage 1 is operational under existing conditions. Describe how Stage 2 extends the LRT network to various destinations (Airport, etc.). Include the estimated completion date of the various legs (south, east, west) of Stage 2 and replace Figure 6 with the latest map showing Moodie Station on Line 1 and Limebank Station on Line 2.

**Response 12:** Updated TIA (see section 2.1.3).

**Comment 13:** Bay Street Cycling Facility - Revise estimated time of completion.

**Response 13:** Updated TIA (see section 2.1.3).

**Comment 14:** Albert Street and Slater Street - replace "the resulting cross-section" with "the resulting vehicular lane arrangement".

**Response 14:** Updated TIA (see section 2.1.3).

**Comment 15:** Other Area Developments: 900 Albert Street far enough away from the site that it does not need to be included. However, include a description of 343 Gloucester Street. The rationale for not including vehicle volumes for the other area developments is not acceptable. Please revise the TIA study to include these volumes. Also note that the last sentence of Section 2.1.3 refers to four (4) study area intersections whereas Section 2.2.1 lists six (6).

**Response 15:** Updated TIA (see section 2.1.3).

**Comment 16:** Section 2.2.1 Study Area: Revise Figure 9 to show the exact location of Lyon Station entrances.

**Response 16:** Updated TIA (see Figure 9).

**Comment 17:** Section 4.1.1 Design for Sustainable Modes: Provide the number and location of bicycle parking spaces. If located in the parking garage, giving priority to the convenient location of bicycle parking is preferred. Also note that if bicycle parking is located in the parking garage this may impact the number of vehicle parking spaces that can be provided.

**Response 17:** The revised Site Plan allows for 465 bicycle parking spaces within the parking garage. The TIA has been updated to reflect this.

**Comment 18:** Assess the opportunity to implement development facilities that are supportive of sustainable modes. Refer to TDM checklists in Appendix E.

**Response 18:** Some TDM measures will be refined during the Site Plan Application stage of approval. The proponent has been advised of the checklists and is aware of the importance of TDM measures.

**Comment 19:** Identify the actual walking distance from all exterior access doors in the proposed development to reach the nearest Lyon Station entrance.

**Response 19:** Updated TIA (see section 4.9.1).

**Comment 20:** Section 4.1.2 Circulation and Access: Suggest consolidating specific access design parameters (width, grade, location) to Section 4.4.1 for easier review.

**Response 20:** Updated TIA (see section 4.3.1).

**Comment 21:** Provide turning movements demonstrating how delivery and/or municipal service vehicles will enter and exit loading areas.

**Response 21:** Truck turning movement templates are provided within the updated TIA as Appendix I.

**Comment 22:** Clarify the functionality of mid-block connection (woonerf) - is the connection to Albert Street (reduced width compared to the Slater Street connection) 1-way or 2-way?

**Response 22:** Updated TIA (see section 4.9.2).

**Comment 23:** Clarify that the statement "Truck loading is proposed mid-block along Albert Street" does not refer to an on-street loading zone on Albert Street.

**Response 23:** Updated TIA (see section 4.9.2).

**Comment 24:** Section 4.3 Boundary Street Design: Assess the future background segment MMLOS of Bay Street, Albert Street, Lyon Street, and Slater Street adjacent to the development to identify any gaps in walking, cycling, transit, or truck LOS in the City's proposed plans.

**Response 24:** Updated TIA (see section 4.2).

**Comment 25:** Identify if there is an opportunity to coordinate with the City to modify the proposed interim measures on Albert Street and Slater Street to a permanent ultimate condition adjacent to the development.

**Response 25:** As this application is for Zoning only, this can be further discussed during the Site Plan Application phase of development.

**Comment 26:** Provide a review of boundary street road safety (may refer to Section 2.1.2).

**Response 26:** Updated TIA (see section 4.2).

**Comment 27:** Section 4.4.1 Location and Design of Access: Ensure internal mid-block connection (woonerf) meets building code and accessibility guidelines.

**Response 27:** Noted and the architect has been advised.

**Comment 28:** For all driveways, the concrete sidewalks should be continuous and depressed through the proposed accesses (refer to the City's sidewalk and curb standard drawing SC7.1 for unsignalized entrances).

**Response 28:** Noted and the architect has been advised.

**Comment 29:** Bay Street Driveway: Note that while the garage to 414 Albert Street is offset approximately 7m north of the proposed access, the alleyway that is offset approximately 1m north of the proposed access leads to the garage for 408 Albert Street. Clarify why the proposed driveway violates Section 25 (m) of the City's Private Approach By-law and explain why the driveway should be approved per 25 (n). Clarify why the driveway violates 25 (p) and explain why the minimum driveway to property line offset should be reduced for this access. Clarify why the driveway violates 25 (u) and why the approach should be approved per 25 (v). Note that a 12% grade may be an impediment to cyclists if bicycle parking is located within the parking garage.

**Response 29:** Updated TIA (see section 4.3.1).

**Comment 30:** Albert Driveways: Clarify why the woonerf entrance violates 25 (p) and explain why the minimum driveway to property line offset should be reduced for this driveway. Explain why the Albert driveways violate 25 (g). Please reduce the width of the truck loading entrance to 9.0m or less per 25 (c).

**Response 30:** Updated TIA (see section 4.3.1). The truck access has been revised.

**Comment 31:** Section 4.5 Transportation Demand Management: Identify any residential, institutional, recreational or natural land uses that would be impacted if traffic volumes generated by the proposed development are higher than expected.

**Response 31:** Updated TIA (see section 4.5).

**Comment 32:** Provide additional context for TDM measures by identifying the development's eventual owner, property manager and tenant(s), if known.

**Response 32:** Unknown at this stage of development.

**Comment 33:** Item 3.2.1 in the 'TDM Measures: Residential Developments' Checklist (page 13, Appendix E) should be "checked" to promote transit ridership considering the location's close proximity to Lyon Station.

**Response 33:** TDM measures will be further refined during the Site Plan Application.

**Comment 34:** While the proposed mid-block woonerf is appreciated, the claim that it will decrease walking distance to Lyon Station is not correct. If the development wishes to reduce walking distance to Lyon Station, consider permitting pedestrian through traffic diagonally from Tower C (southwest corner of site) to the proposed urban park (northeast corner of site). This could be provided through the retail space on the first floor, or via a pedestrian bridge over the woonerf and through the 2nd floor retail space in the Tower A/B podium.

**Response 34:** Updated TIA. The woonerf provides space for pedestrian access mid-block, as oppose to access only to the boundary street, as such, some pedestrian travel distance is reduced.

**Comment 35:** Disagree that LRT underneath Queen Street means TLOS on Albert Street and Slater Street is 'A'. Assess TLOS on Albert Street and Slater Street based on transit delay, while mentioning the nearby LRT as a consideration.

**Response 35:** Updated TIA (see section 4.9.3).

**Comment 36:** Recommend a future PHF of 1.0 per Appendix C of the City's TIA Guidelines.

**Response 36:** Updated TIA and SYNCHRO analysis (see section 4.9.3).

**Comment 37:** Existing Study Area Intersections: At Lyon/Albert the southbound approach now consists of two through lanes and a transit only lane for OC and STO buses to service Lyon Station. The southbound right turn at Lyon/Albert is prohibited (buses excepted) and a transit priority signal is in place to serve future OC and STO buses".

**Response 37:** Updated TIA and SYNCHRO analysis (see section 4.9).

**Comment 38:** All signalized intersections along Albert will have a Westbound cycling facility and signal displays when Albert is reconstructed in the near future.

**Response 38:** Noted.

**Comment 39:** At Bay/Queen the westbound approach was recently reconstructed to include 1 westbound through lane and 1 westbound right turn lane.

**Response 39:** Updated TIA (see section 4.9 and 2.1.2)

**Comment 40:** Note in future conditions that the southbound bike lane not provided on Lyon Street is provided on Bay Street one block to the west.

**Response 40:** Noted.

**Comment 41:** Bay Street Project and Albert/Slater Project have been designed as far as Traffic Signals Design Layouts are concerned. Please coordinate your design with project managers:

Truong, Lee-Anne 613-580-2424 x27805 - Bay Street

Murphy, Elizabeth 613-580-2424 x15397 - Albert/Slater East of Bay

No protective hording is to encroach on existing or new traffic signals above ground or underground infrastructure. It is to be fully accessible 24/7/365.

**Response 41:** Noted and the proponent has been advised.

**Comment 42:** Please check box 3.2.1 in the 'TDM Measures: Residential Developments' Checklist (page 13, Appendix E). Please consider the same for the non-residential portion of the development. Comments will be shared with the planner in charge regarding the inclusion of a draft condition for the purchase of transit passes in the form of loaded Presto cards to benefit future condo owners and promote transit ridership due to the development's close proximity to Lyon Station.

**Response 42:** Noted and the proponent has been advised. At this stage of development the proponent has not been able to commit to this TDM measure.

**Comment 43:** Please update 'Transit Network' map to reflect current routing and route numbers. Although the new LRT is considered in the TIA analysis, please update information throughout the TIA regarding Transitway and LRT/ Lyon Station.

**Response 43:** Updated TIA (throughout).


Based on the foregoing and the updated TIA document, the proposed development at 400 Albert Street continues to be recommended from a transportation perspective.

Prepared By:



André Sponder, P.Eng.  
Transportation Engineer

Reviewed by:



Ronald Jack, P.Eng.  
Senior Transportation Engineer

