

MEMORANDUM

DATE: AUGUST 31, 2020

TO: MIKE GIAMPA, CITY OF OTTAWA

FROM: ROCHELLE FORTIER / JENNIFER LUONG

- RE: 200 BARIBEAU STREET TRIP GENERATION
- CC: MARK BISSETT, NOVATECH

1.0 Introduction

This trip generation memo has been prepared in support of a Site Plan Control Application for a redevelopment at 200 Baribeau Street. The subject site is located in the Vanier neighborhood, at the southwest corner of the Baribeau Street and Landry Street intersection. An aerial view of the subject site is provided as **Figure 1**.



Figure 1: Aerial of the Subject Site

M:\2019\119068\DATA\CORRESPONDENCE\MEMOS\202008XX-TRIPGENERATION.DOCX



Currently, the subject property is occupied by a one-storey building which was originally constructed as an elementary school and contains 18 classrooms, as well as a general purpose room (gym/stage, change rooms, etc.) and administrative offices. The property was acquired by Ahlul Bayt Center Ottawa (ABCO), and continues to function as an elementary school, serving kindergarten to grade six students. Additionally, the general purpose room is now also used as a mosque for worship services and classrooms, in addition to serving as such, also serve for community centre purposes during non-school hours, on weekends and during the summer periods. The growth in ABCO's student population and community is not adequately accommodated by the existing building. Rather than pursuing the enlargement of the existing building, ABCO is now in the process of moving to a new, larger premises that will better accommodate its growing needs for additional floor space.

The proposed redevelopment at 200 Baribeau will include the demolishment of the existing building on-site and the construction of 92 townhouses. The development will be served by one access connection to Baribeau Street and one access connection to Landry Street. A copy of the proposed Site Plan is included in **Appendix A**.

Following discussions with City staff, a memo describing the trip generation for the existing and proposed uses on-site was requested in order to estimate the net site traffic generated by the redevelopment.

2.0 Trip Generation

2.1 Existing Trip Generation

The Ahlul Bayt Center Ottawa (ABCO) currently operates a private school, mosque, and community/recreational center out of the existing building. The ABCO is proposed to relocate to 3025 Albion Road, and a Transportation Impact Study (TIS) was prepared by Novatech in 2016 and revised in 2018 in support of this relocation. As such, peak hour trips for the proposed relocation were estimated using existing data at the ABCO. The trip generation section from the 2018 TIS is included as **Appendix B** for reference. The following summarizes the weekday peak hour trip generation for the existing uses on-site.

Elementary School

The elementary school serves approximately 170 students and employs 17 teachers and administrative staff. It is expected that all students and staff arrive within a single one-hour period during the AM peak hour, and that approximately 35% of staff/students remain on-site for after-school programs in the PM peak hour. It is expected that most students carpool and are dropped off/picked up from school. A vehicle occupancy of 3 students per vehicle was assumed. Peak hour person trips are estimated at 187 people per hour (pph) in the AM peak, and 122 pph in the PM peak hour. Peak hour vehicle trips are estimated at 119 vehicles per hour (vph) during the AM peak hour, and 78 vph during the PM peak hour.

Mosque

Currently, prayer services are not held during a school day. As such, no weekday peak hour vehicle trips are associated with the mosque use.

Community/Recreational Center

A variety of different programs (youth groups, scouts, religious education) are run out of the community/recreational center throughout the week. These programs are generally held outside of peak hours.



2.2 Proposed Trip Generation

In the absence of local data, the use of the *TRANS Trip Generation Manual* is preferred by the City of Ottawa to estimate the trip generation of residential development. As such, trips generated by the proposed residential use have been estimated using the relevant recommended rates outlined in the *TRANS Trip Generation Manual*. The vehicle trip generation rates, taken from Table 6.3 of the TRANS report, correspond to townhouses in the Urban Area (inside the greenbelt). The directional split between inbound and outbound trips are based on the blended splits presented in Table 3.17 of the report. Estimates of the trips generated by the proposed development are summarized in the following table.

| Land Use | TRANS | Units | AM Peak (VPH) | | | PM Peak (VPH) | | | | | |
|-----------|----------------------|----------|---------------|-----|-----|---------------|-----|-----|--|--|--|
| | Rate | | IN | OUT | тот | IN | OUT | тот | | | |
| Townhouse | AM: 0.51 PM: 0.51 | 92 units | 17 | 30 | 47 | 25 | 22 | 47 | | | |

Table 1: Proposed Residential Vehicle Trip Generation

The vehicle trips have been converted to person trips using auto modal shares for townhouses in the urban area presented in Table 3.13 of the TRANS report. Person trips generated by the proposed development are summarized in the following table.

| Table 2. Proposed Residential Person Trip Generation | | | | | | | | | | |
|--|--------------------|----|---------|-----|---------------|-----|-----|--|--|--|
| Land Use | TRANS Auto Share | АМ | Peak (P | PH) | PM Peak (PPH) | | | | | |
| | | IN | OUT | тот | IN | OUT | тот | | | |
| Townhouse | AM: 45% PM: 53% | 38 | 67 | 105 | 47 | 42 | 89 | | | |

Table 2: Proposed Residential Person Trip Generation

Based on the foregoing table, the proposed development will generate 105 person trips in the AM peak hour and 89 person trips in the PM peak hour.

The modal shares for the proposed development are anticipated to be consistent with the modal shares outlined in the 2011 TRANS O-D Survey Report, specific to the Ottawa East region. The modal share values applied to the proposed dwellings are based on the typical commuter pattern, represented by all observed trips from/within Ottawa East in the AM peak hour, and all observed trips to/within Ottawa East in the PM peak hour. A full breakdown of the projected person trips generated by modal share is shown in the following table.

| Travel Mode | Modal | | AM Peal | ¢ (| PM Peak | | | | | | |
|----------------|-----------------|----|---------|-----|---------|-----|-----|--|--|--|--|
| | Share | IN | OUT | TOT | IN | OUT | TOT | | | | |
| Per | Person Trips | | 67 | 105 | 47 | 42 | 89 | | | | |
| Auto Driver | Auto Driver 45% | | 30 | 47 | 21 | 19 | 40 | | | | |
| Auto Passenger | 15% | 6 | 10 | 16 | 7 | 6 | 13 | | | | |
| Transit | 25% | 9 | 17 | 26 | 12 | 11 | 23 | | | | |
| Non-Auto | 15% | 6 | 10 | 16 | 7 | 6 | 13 | | | | |

Table 3: Person Trips by Modal Share



From the previous table, the proposed development is projected to generate 47 vehicle trips during the AM peak hour and 40 vehicle trips during the PM peak hour.

2.3 Net Site Trip Generation

The following table summarizes the net site trip generation due to the proposed redevelopment at 200 Baribeau Street. Note that negative numbers indicate an overall reduction in site trips.

| Land Use | AM Peak | | | PM Peak | | | |
|-------------------------|---------|-----|-----|---------|-----|-----|--|
| | IN | OUT | ТОТ | IN | OUT | тот | |
| Vehicle Trip Generation | | | | | | | |
| Existing Vehicle Trips | 65 | 54 | 119 | 35 | 43 | 78 | |
| Proposed Vehicle Trips | 17 | 30 | 47 | 21 | 19 | 40 | |
| Net Site Vehicle Trips | -48 | -24 | -72 | -14 | -24 | -38 | |

Table 4: Net Site Trip Generation


Based on the foregoing, the proposed redevelopment will result in an overall net decrease in vehicle trips in the AM and PM peak hours.

3.0 Conclusions

Ahlul Bayt Center Ottawa (ABCO) currently operates a private school, mosque, and community/recreational center out of the existing building at 200 Baribeau Street. The proposed redevelopment, consisting of 92 townhouse units, will result in an overall net decrease in person and vehicle trips to/from the site.



Appendix A Proposed Site Plan



| | BLOCK 3 5 UNITS 720m ² BLOCK 4 5 UNITS 720m ² BLOCK 5 6 UNITS 884m ² BLOCK 6 8 UNITS 1,169M ² BLOCK 7 9 UNITS 1,311M ² | | | | | | | |
|--|--|-----------------------------------|---------------------------------------|---------|---|--|---|--|
| | BLOCK 10 14 UNITS 1,812M ² BLOCK 11 14 UNITS 1,812M ² | | | | | | | |
| | LOT COVERAGE | | | | | | | |
| | TOTAL GROSS BUILDING AREA:4,540TOTAL LOT COVERAGE35.3 | <u>0m</u> ² 7% | | | | | | |
| | TOTAL LOT COVERAGE319TOTAL LANDSCAPE AREA:5,281m² | % | | | | | | |
| | PARK AREA .09Ha | | | | | | | |
| | SURVEY INFORMATION | | | | | | | |
| HI-RENE - 2010 HE-RENE | JD BARNES LTD. 2430 DON REID DRIVE SUITE 204 OTTAWA, ON K1H 1E1, CANADA CONTACT: SHAWN LEROUX TEL. 613-731-7244 | PART 1 – PL PART (REGISTER | lan showing OF BLOCI RED PLAN M | | | | | |
| 259. No. 259. No. 8702, 572 M-CRONDEL 001.118/01 (1976) 4.401 OF DEVCAY 0.507 0.507 0.507 001.118/01 (1976) 4.402 NOTATE DEVCAY 0.507 0.507 0.507 011.118/01 (1976) 4.508 200 SECION 1000 0.507 0.507 0.507 011.118/01 (1976) 4.508 200 SECION 1000 0.507 0.507 0.507 0.507 011.118/01 (1976) 4.508 200 SECION 1000 0.507 0.507 0.507 0.507 011.118/01 (1976) 4.508 200 SECION 1000 0.507 0.508 0.508 0.508 0.508 0.508 | SITE STATISTICS | | | | | | | |
| APPROVAL SIGNATURE APPROVAL SIGNATURE APPROVAL SIGNATURE COASTING MANAGER, DEVELOPMENT EXTERNATE COASTING MANAGER, DEVELOPMENT EXTERNATION COASTING MANAGER COASTING C | PLANNED UNIT DEVELOPMENT ZONING N ZONING: | MECHANISM | | | | | | |
| | DWELLING TYPE: PUD – 92 UNITS | | | | | | | |
| SETRACKS Image: Dig to the set of the set | | DINGS | | | | | | |
| MRL 201 900H MRL 201 900H MRL 201 940A MR | SETBACKS | | | | | | | |
| MIN LOT AREA ANNA SHURLAN CALCHICAN MARKER, DEVELOPMENT EXPROVAL SIGNATURE APPROVAL SIGNATURE APPROVAL SIGNATURE APPROVAL SIGNATURE APPROVED CONTACT: CONTACT: APPROVED CONTACT: APPROVED CONTACT: CONTACT: CONTACT: APPROVED | | | | | | | | |
| | MIN. LOT WIDTH MIN. LOT AREA MAX BUILDING HEIGHT | | | | | | | |
| All DESIDENT STATES [32. (32-12).0.3] 22. (32-12 | | - RESIDE | NTS | | | | | |
| 40 RESIDENT SPACES 92. VESTORS 92. RESIDENT SPACES 92. VESTORS 92. VESTORS 92. VESTORS 92. MENT SPACES 0. NET SCHALL 1. Content Content Content Space 0. NET SCHALL STORET 1. Content Content Content Content Space 0. State Content Co | | · | | | | | | |
| 2 UNITORS (0.1.83) 2 DRIVEWAYS © 3ms5.2m contractor to check and verify all all arrows of or orisolons to and report all arrows of or orisolons to the such less. All contractors must compy with all perinent codes and by-lows. Do not such arrains arrows of the such less. Do not such arrains arrows of the such less. Do not such arrains arrows of the such less. Do not such arrains arrows of the such less. Do not such arrains arrows of the such less. Do not such arrains arrows of the such less. Do not such arrains arrows of the such less. Do not such arrains arrows of the such less. Do not such arrains arrows of the such less. Do not such arrains arrows of the such less. Do not such arrains arrows of the such less. Do not such arrains arrows of the such less. Do not such arrains arrows of the such less. Do not such arrains arrows of the such less. Do not such arrains arrows of the such less. Do not such arrains arrows of the such less. Do not such arrains arrows of the such less. Do not such arrays arrows of the such less. Do not such arrows of the such less. Do not such arrows of the such less. Do not such | 40 RESIDENT SPACES 92 [92. (92-12)x0.5] 92 | RESIDENT SI | PACES | | | | | |
| AB PRACES | , | | | | | ntractor to | check and v | /erify all di |
| CONSULTANTS ARCHITECT OBIN ARCHITECT OBIN ARCHITECT ODITACE STANL AS STREET, ODITACE GRAPHIC SCALE 1:250 CONTACT: APPROVAL SIGNATURE APPROVAL SIGNATURE APPROVED REFUSED DATE DECRRICK MOODIE, ACTING MANAGER, DEVELOPMENT REVIEW, SUBURBAN SERVICES CONTACT DECRRICK MOODIE, ACTING MANAGER, DEVELOPMENT REVIEW, SUBURBAN SERVICES CONTACT OTHER AND THE ADDITION CONTACT | <u>92</u> <u>8</u> VISITORS (0.1x80) | JZ DRIVEWA | ars e smxs.zm | | sic or All | ons on site omissions contractor | and report to the archi s must comp | tect. bly with all |
| Hobin Architecture RUC. SO PARLLA STREET. COTTAMA, ON KIS 3K7 SONTACT: BUL NTCC: MUL NTCC: SONTACT: BEREAT. SONTACT: BEREAT. SONTACT: BEREAT. SONTACT: BODIE ACCHIECTURE APPROVED ON TS: DEFRICK MOODIE, ACTING MANAGER, DEVELOPMENT REVIEW, SUBURBAN SERVICES DOCATION MAP N.T.S. DOCATION MAP N.T.S. NOBINITY STATE PLAN AND ASSOCIATION MARCHIECTURE SITE PLAN ACHIECTURE SITE PLAN COTATION MAP N.T.S. | <u>8</u> VISITORS (0.1×80) | | ars e smxs.zm | | sic or All pe | ons on site omissions contractor rtinent code | and report to the archi s must comp es and by-lo | tect. bly with all |
| BALL RITERY TAX. 813-285-2005 | <u>8</u> VISITORS (0.1×80) | | ans e amxa.zm | | All pe Do Thi co | ons on site omissions contractor rtinent code not scale is drawing nstruction o | and report to the archi s must comp es and by-lo drawings. may not be until signed. | tect. bly with all ws. |
| GRAPHIC SCALE 1:250 | 8 VISITORS (0.1×80) 48 SPACES CONSULTANTS ARCHITECT HOBIN ARCHITECTURE INC. 63 PAMILLA STREET, OTTAWA, ON K1S 3K7 | | | | All pe Do Thi co | ons on site omissions contractor rtinent code not scale is drawing nstruction o | and report to the archi s must comp es and by-lo drawings. may not be until signed. | tect. bly with all ws. |
| Om 5m 10m 15m 20m APPROVAL SIGNATURE 63 Partilla Street 0taway, Ontario 0taway, Ontario APPROVAL SIGNATURE F. 619 235 2005 E. mailghobinarc.com HOBSI DATE | 8 VISITORS (0.1×80) 48 SPACES CONSULTANTS ARCHITECT HOBIN ARCHITECTURE INC. 63 PAMILLA STREET, | | | | All pe Do Thi co | ons on site omissions contractor rtinent code not scale is drawing nstruction to opyright rese | and report to the archi s must comp es and by-lo drawings. may not be until signed. erved. | tect. bly with all ws. used for E T |
| APPROVED REFUSED APPROVED REFUSED APPROVED REFUSED ARCHITECTURE ACTING MANAGER, DEVELOPMENT REVIEW, SUBURBAN SERVICES BLOCK XX STYLE X BEDECK STYLE X STYLE X STYLE X STYLE X STYLE X BEDECK STYLE X STYLE X BEDECK STYLE X STYLE X BEDECK STYLE X STY | 8 VISITORS (0.1×80) 48 SPACES ECONSULTANTS ARCHITECT HOBIN ARCHITECTURE INC. 63 PAMILLA STREET, OTTAWA, ON K1S 3K7 CONTACT: BILL RITCEY TEL. 613-236-7200 | | | 1 : 250 | All pe Do Thi co | ons on site omissions contractor rtinent code not scale is drawing nstruction to opyright rese | and report to the archi s must comp es and by-lo drawings. may not be until signed. erved. | tect. bly with all ws. used for Used for |
| APPROVED REFUSED ARCHITECTU | 8 VISITORS (0.1×80) 48 SPACES CONSULTANTS ARCHITECT HOBIN ARCHITECTURE INC. 63 PAMILLA STREET, OTTAWA, ON K1S 3K7 CONTACT: BILL RITCEY TEL. 613–236–7200 FAX. 613–265–2005 GRAPHIC SCALE | | | | Sic or All pe Do Thi co | hons on site omissions contractor rtinent code not scale is drawing nstruction of pyright rese Hobin Archite Incorporated 63 Pamilla Stree Ottawa, Ontario | and report to the archi s must comp es and by-lo drawings. may not be until signed. erved. B OULI construction eture | tect. by with all ws. used for ET |
| DATE DERRICK MOODIE, ACTING MANAGER, DEVELOPMENT REVIEW, SUBURBAN SERVICES LOCATION MAP N.T.S. | 8 VISITORS (0.1×80) 48 SPACES CONSULTANTS ARCHITECT HOBIN ARCHITECTURE INC. 63 PAMILLA STREET, OTTAWA, ON K1S 3K7 CONTACT: BILL RITCEY TEL. 613–236–7200 FAX. 613–265–2005 GRAPHIC SCALE | | | | Sic or All pe Do Thi co | bons on site omissions contractor rtinent code o not scale is drawing nstruction of pyright rese B B B B B B B B B B B B B B B B B B | and report to the archi s must comp es and by-lo drawings. may not be until signed. erved. B OULI CONSTRUCTION cture et 7 | ET |
| 200 BARIBEAU BLOCK XX STYLE X DARBEAU ST. OTTAWA.ONTARIO INCATION MAP N.T.S. | 8 VISITORS (0.1×80) 48 SPACES CONSULTANTS ARCHITECT HOBIN ARCHITECTURE INC. 63 PAMILLA STREET, OTTAWA, ON K1S 3K7 CONTACT: BILL RITCEY TEL. 613–236–7200 FAX. 613–265–2005 GRAPHIC SCALE Om 5m APPROVAL SIGNATURE | | | Om I | Sic or All pe Do Thi co Co | bins on site omissions contractor rtinent code o not scale is drawing nstruction of opyright rese Hobin Archite Incorporated 63 Pamilla Stree Ottawa, Ontario Canada K1S 3K T: 613-238-7200 F: 613-235-2005 E: mail@hobinarc | and report to the archives s must complex drawings. may not be until signed. erved. CONSTRUCTION cture et 7 | tect. by with all used for CN |
| LOCATION MAP N.T.S. | 8 VISITORS (0.1x80) 48 SPACES CONSULTANTS ARCHITECT HOBIN ARCHITECTURE INC. 63 PAMILLA STREET, OTTAWA, ON KIS 3K7 CONTACT: BILL RITCEY TEL. 613-236-7200 FAX. 613-265-2005 GRAPHIC SCALE Om 5m APPROVAL SIGNATURE APPROVED | | 15m 2 | Om I | Sic or All pe Do Thi co | bons on site omissions contractor rtinent code o not scale is drawing nstruction of pyright rese by Hobin Archite Incorporated 63 Pamilla Stree Ottawa, Ontario Canada K1S 3K T: 613-238-7200 F: 613-235-2005 E: mail@hobinarc.col | and report to the archives s must complex drawings. may not be until signed. erved. CONSTRUCTION cture et 7 | tect. by with all used for CN |
| NORTH SITE LOCATION VANJERPKY NORTH LOCATION VANJERPKY NORTH LOCATION VANJERPKY NORTH LOCATION VANJERPKY NORTH LOCATION VANJERPKY NORTH LOCATION VANJERPKY NORTH LOCATION VANJERPKY NORTH LOCATION VANJERPKY NORTH LOCATION VANJERPKY NORTH LOCATION VANJERPKY NORTH LOCATION VANJERPKY NORTH NORTH LOCATION VANJERPKY NORTH NORTH LOCATION VANJERPKY NORTH NOR | 8 VISITORS (0.1x80) 48 SPACES CONSULTANTS ARCHITECT HOBIN ARCHITECTURE INC. 63 PAMILLA STREET, OTTAWA, ON KIS 3K7 CONTACT: BILL RITCEY TEL. 613-236-7200 FAX. 613-265-2005 GRAPHIC SCALE Om 5m APPROVAL SIGNATURE APPROVED | | 15m 2 | Om I | Sic or All pe Do Thi co | bins on site omissions contractor rtinent code o not scale is drawing nstruction of pyright rese Hobin Archite Incorporated 63 Pamilla Stree Ottawa, Ontario Canada K1S 3K T: 613-238-7200 F: 613-238-7200 F: 613-235-2005 E: mail@hobinarc.col oject title | and report to the archi s must comp es and by-lo drawings. may not be until signed. erved. | ET N S C S C S C S C S C S C S S S S S S S |
| NORTH SITE LOCATION VANIERPKY | 8 VISITORS (0.1x80) 48 SPACES ARCHITECT HOBIN ARCHITECTURE INC. 63 PAMILLA STREET, OTTAWA, ON KIS 3K7 CONTACT: BILL RITCEY TEL. 613-236-7200 FAX. 613-265-2005 GRAPHIC SCALE Om 5m APPROVAL SIGNATURE DATE DERRICK MOODIE, ACTING MAN REVIEW, SUBURBAN SERVICES | | 15m 2 | Om I | sic or All pe Do Thi co Co | Arring title | and report to the archi s must comp es and by-lo drawings. may not be until signed. erved. | ECHITECTUR |
| SITE LOCATION VANIER-PKV | 8 VISITORS (0.1x80) 48 SPACES ARCHITECT HOBIN ARCHITECTURE INC. 63 PAMILLA STREET, OTTAWA, ON KIS 3K7 CONTACT: BILL RITCEY TEL. 613-236-7200 FAX. 613-265-2005 GRAPHIC SCALE Om 5m APPROVAL SIGNATURE DATE DERRICK MOODIE, ACTING MAN REVIEW, SUBURBAN SERVICES | | 15m 2 | Om I | | bons on site omissions contractor rtinent code o not scale is drawing nstruction of opyright rese Hobin Archite Incorporated 63 Pamilla Stree Ottawa, Ontario Canada K1S 3K T: 613-238-7200 F: 613-238-7200 F: 613-238-7200 F: 613-238-7200 E: mail@hobinarc hobinarc.com oject title 2 awing title | and report to the archi s must comp drawings. may not be until signed. erved. | |
| VANIER PKY. | 8 VISITORS (0.1x80) 48 SPACES CONSULTANTS ARCHITECT HOBIN ARCHITECTURE INC. 63 PAMILLA STREET, OTTAWA, ON KIS 3K7 CONTACT: BILL RITCEY TEL. 613-236-7200 FAX. 613-265-2005 GRAPHIC SCALE Om 5m APPROVAL SIGNATURE APPROVED DATE DERRICK MOODIE, ACTING MAN REVIEW, SUBURBAN SERVICES | | 15m 2 | Om I | sic or All pe Do Thi co Co Co Co Co Co Co Co | awn da awn da | and report to the archi s must comp es and by-lo drawings. may not be until signed. erved. | tect. by with all used for ET ET ET EAU RCHITECTUE EAU X NTARIO |
| | & VISITORS (0.1x80) 42 SPACES CONSULTANTS ARCHITECT HOBIN ARCHITECTURE INC. 63 PAMILLA STREET, OTTAWA, ON KIS 3K7 CONTACT: BILL RITCEY TEL. 613–236–7200 FAX. 613–265–2005 GRAPHIC SCALE Om 5m APPROVAL SIGNATURE APPROVED DATE DERRICK MOODIE, ACTING MAN REVIEW, SUBURBAN SERVICES LOCATION MAP Image: Contemported state of the state of | | | Om | sic or All pe Do Thi co Co Co Co Co Co Co Co | awn da awn da | and report to the archi s must comp es and by-lo drawings. may not be until signed. erved. | tect. by with all used for CT CN CON CON CON CON CON CON CON |



Appendix B

Excerpt from 3025 Albion Road TIS

Albion Road and Bank Street in the vicinity of the subject site, as shown in the TRANS model (2011 to 2031), identified either no growth or negative growth over the 20-year planning horizon. Based on this information, no background growth has been applied to the road network. As no growth is anticipated, the 2019 and 2024 background traffic volumes remain consistent with the existing condition.

3.3 Trip Generation

The ABCO is a Lebanese Muslim Canadian registered charitable organization which offers the community ongoing social, cultural, educational, and religious services. The ABCO is relocating from their existing site in Vanier to 3025 Albion Road. The site is currently occupied by Hydro Ottawa offices. The proposed development will use the existing building to include a mix of several uses including a school, community centre, recreational facility, mosque, banquet hall, as well as leased office and warehouse spaces. The uses and programs for day-to-day operations have been reviewed independently from the banquet hall which will be used for occasional events, as described further in Section 3.3.6.

The approximate time periods associated with each program or facility are identified in **Table 2**, which includes the existing office use. During the weekday time period, the school remains the major trip generator with occasional evening programming at the community centre. The exercise facilities and mosque will continue to generate trips throughout the day and evening time periods. The proposed leased office and warehouse spaces will generate trips during the AM, midday, and PM peak hours. On weekends, Saturday mornings reflect the worst-case scenario with overlapping heritage language school and the use of the mosque and exercise facilities.

For the existing development and the proposed office and warehouse, the vehicle trips have been estimated using trip generation rates from ITE's *Trip Generation Manual, 9th Edition*. For the proposed development, the vehicle trips associated with each program or facility have been identified based on the existing staff experience at the facility in Vanier. The estimated vehicle trips have been compared to ITE rates (where available) to validate the assumptions. Given the limited access to transit and the city-wide catchment area, it has been assumed that few people will travel by non-auto modes. Higher proportions of carpooling are anticipated and estimated vehicle occupancies are identified for each trip generator.

| | | | kday | | | | rday | | S | unda | у |
|--------------------------|----|--------|-------------|---------|----------|------|--------|----------|----|------|--------|
| Use/Program | AM | Midday | Μd | Evening | AM | Noon | Mid-PM | Evening | AM | Noon | Mid-PM |
| Existing Development | | | | | | - | - | | | | |
| Industrial | ~ | ~ | ~ | | | | | | | | |
| Warehouse | ~ | ~ | > | | | | | | | | |
| Offices | > | > | > | | | | | | | | |
| Proposed Development | | | | | | | | | | | |
| School | > | > | > | | | | | | | | |
| Heritage Language School | | | | | ~ | ~ | ~ | | | | |
| Religious Education | | | | > | | | | | | | |
| Girls' Youth Group | | | | > | | | | | | | |
| Boys' Youth Group | | | | | | | | > | | | |
| Scouts | | | | | | | | | > | > | ✓ |
| Exercise Facility | > | > | > | • | ~ | ~ | ~ | ~ | | | |
| Prayers | > | > | > | < | > | > | > | < | | | |
| Leased Office | > | > | > | | | | | | | | |
| Leased Warehouse | > | > | > | | | | | | | | |

Table 2: Typical Facility Programs by Day and Time Period

3.3.1 Existing Development

The existing building is occupied by Hydro Ottawa, and currently contains 42,510 ft² GFA of industrial space, 25,324 ft² GFA of warehousing spaces, and 80,125 ft² GFA of office space. A section of the first floor is also used as garage space, which has been assumed to generate no trips.

Trips generated by the existing development during the weekday AM and PM peak periods have been estimated using relevant land uses in the ITE *Trip Generation Manual, 9th Edition*. Trips generated during the midday peak period has been estimated as half of the average between the AM and PM peaks. These trips represent employees or clients who arrive and/or depart the subject site for lunch, meetings, etc. A split of 50% entering/50% exiting during this period has also been assumed.

Trips generated using the ITE trip generation rates were converted to person trips using a factor of 1.28, consistent with the City's 2017 TIA Guidelines. The person trip generation by the existing site is summarized in **Table 3**.

| Land Use | ITE | ITE GFA | AM | AM Peak (pph) | | | Mid Peak (pph) | | | PM Peak (pph) | | |
|--------------------------|------|---------------------------|-----|---------------|-----|----|----------------|-----|----|---------------|-----|--|
| Lanu USe | Code | GFA | IN | OUT | ΤΟΤ | IN | OUT | ΤΟΤ | IN | OUT | тот | |
| Gen. Light Industrial | 110 | 42,510 ft ² | 44 | 6 | 50 | 13 | 13 | 26 | 6 | 46 | 52 | |
| Warehousing | 150 | 15,324 ft ² | 5 | 1 | 6 | 2 | 2 | 4 | 1 | 5 | 6 | |
| Single Tenant Office | 715 | 80,125 ft ² | 164 | 20 | 184 | 45 | 45 | 90 | 27 | 151 | 178 | |
| | | Total | 213 | 27 | 240 | 60 | 60 | 120 | 34 | 202 | 236 | |

Table 3: Existing Person Trips

The modal shares for the existing development are anticipated to be consistent with the modal shares outlined in the 2011 *TRANS O-D Survey Report*, specific to the Alta Vista district. A full breakdown of the person trips by modal share are shown in **Table 4**.

| Travel Modal | | AM Peak | | | Midday Peak | | | PM Peak | | | |
|--------------|-----------|---------|-----|-----|-------------|-----|-----|---------|-----|-----|--|
| Mode Share | IN | OUT | тот | IN | OUT | тот | IN | OUT | тот | | |
| Total Per | son Trips | 213 | 27 | 240 | 60 | 60 | 120 | 34 | 202 | 236 | |
| Auto Driver | 65% | 138 | 18 | 156 | 39 | 39 | 78 | 22 | 132 | 154 | |
| Auto Pass | 15% | 32 | 4 | 36 | 9 | 9 | 18 | 5 | 30 | 35 | |
| Transit | 15% | 32 | 4 | 36 | 9 | 9 | 18 | 5 | 30 | 35 | |
| Non-Auto | 5% | 11 | 1 | 12 | 3 | 3 | 6 | 2 | 10 | 12 | |

Table 4: Existing Person Trips by Modal Share

3.3.2 School

The elementary and middle school will include approximately 16 classrooms and serve approximately 170 students. The school will have 17 teachers and administrative staff and will be in session from Monday to Friday between 8:15am and 3:15pm.

Based on the 2011 OD Data for work trips to the Alta Vista area, it has been assumed that 65% of the teachers drive to the site; amounting to 11 vehicles. Based on current operations at the ABCO school in the Vanier area, it is expected that most students will carpool to/from school with an average of 3 students per vehicle; amounting to approximately 54 vehicles. It has been conservatively assumed that all students and teachers arrive within a single one-hour period during the AM peak hour, as summarized in **Table 5**. During the PM peak hour, 65% of teachers and students are expected to depart during the peak hour while the remaining 35% remain on-site for after-school programs. By comparison, the ITE rates for a private school (LU534) identify approximately 30% more vehicle trips in both the morning and afternoon peak periods; likely reflective of lower carpooling rates amongst students.

| Teachers | Students |
|----------|------------------------------|
| 17 | 170 |
| 5 | 9 |
| 1.1 | 3 |
| 11 | 54 |
| | |
| 11/0 | 54/54* |
| 0/8 | 35/35* |
| | 17 5 1.1 11 11/0 |

Table 5: School Trips

Note: * All drivers assumed to drop-off/pick-up only. Some linked vehicle trips may exist which is not accounted for.

3.3.3 Recreation/Community Centre

The recreation and community centre will include sports facilities and community programs. The centre will employ 9 full-time or part-time staff and up to 30 occasional volunteers to lead youth programs and serve on the Executive and Trustee boards. A total of ten vehicle trips have been included to account for these staff and volunteers.

Exercise Facility

The exercise facility is proposed to be open from 7:00am to 10:00pm but access will be limited to some facilities during school hours. The facility may include a swimming pool, gymnasium, and squash court. Peak use of the facility is expected to be approximately 50 persons and occur in the evening period from 7:00pm to 10:00pm. If on average users stay on-site for 1.5 hours, two-way vehicle trip rates are anticipated to be approximately 58vph, as shown in **Table 6**. By comparison, the ITE Trip Generation Manual Recreational Community Centre rates suggest two-way peak hour trips of up to 45vph; suggesting the estimate of 58vph is likely conservative.

| | Users |
|----------------------------------|-----------|
| Persons | 50 |
| Non-Auto Modes (5%) | 3 |
| Vehicle Occupancy | 1.1 |
| Vehicles | 43 |
| Average Length of Stay | 1.5 hours |
| Peak Hour Vehicle Trips (In/Out) | |
| -Evening and Weekends | 29/29 |
| -Weekday (33% reduction assumed | 19/19 |
| during school hours) | |

Table 6: Exercise Facility Trips

Religious Education

A religious education session will be hosted every Thursday evening at approximately 7:00pm and will serve 200 persons including both children and adults. It has been assumed that 95% will arrive by vehicle with an average of 3 students per vehicle, or 64 vehicles, as shown in **Table 7**. As some students are adults, it has been assumed that only 25% of drivers will be exclusively

dropping-off/picking-up while the remainder of drivers will remain on site to either attend the education session or use on-site facilities.

| | Leaders | Students |
|--|---------|----------|
| Persons | 7 | 200 |
| Non-Auto Modes (5%) | 0 | 10 |
| Vehicle Occupancy | 1.1 | 3 |
| Vehicles | 6 | 64 |
| Peak Hour Vehicle Trips (In/Out) 7:00PM Arrival | 6/0 | 64/16 |

Table 7: Religious Education Trips

Youth Groups

The centre will host a girls' youth group for ages 9 to 16 years on Friday evenings beginning at approximately 7:00pm. A boys' youth group for ages 15 to 18 years will be hosted on Saturday evenings beginning at approximately 7:00pm. The youth groups will be run by a team of 8 to 10 councillors. Most youth will carpool to the site with an average of 3 youths per vehicle, as summarized in **Table 8**. Half of the vehicles are expected to remain on-site while drivers attend the youth group or use the recreational facility while the other half return at the end of each session to pick-up the youth.

| Table | 8: | Youth | Group | Trips | |
|-------|----|-------|-------|-------|--|
| | - | | | | |

| | Girls' Youth | n Group | Boys' Youth Group | | |
|----------------------------------|--------------|---------|-------------------|-------|--|
| | Councilor | Youth | Councilor | Youth | |
| Persons | 10 | 120 | 8 | 100 | |
| Non-Auto Modes (5%) | 1 | 6 | 0 | 5 | |
| Vehicle Occupancy | 1.1 | 3 | 1.1 | 3 | |
| Vehicles | 8 | 38 | 7 | 32 | |
| Peak Hour Vehicle Trips (In/Out) | 8/0 | 38/19 | 7/0 | 32/16 | |

Scouts

A Scouts program will be hosted at the site on Sunday mornings from approximately 10:00am to 12:00pm. The Scouts will include both boys and girls from ages 6 to 14 years and will be run by a team of 15 Scout Leaders. Consistent with the travel assumptions for the youth groups, it is expected that only 5% arrive by non-auto modes and on average 3 scouts arrive in each vehicle, as shown in **Table 9**. Half of the vehicle drivers are assumed to remain on-site to make use of the available facilities while the second half are assumed to return to pick-up Scouts at the end of the program.

| | Leaders | Scouts |
|----------------------------------|---------|--------|
| Persons | 15 | 150 |
| Non-Auto Modes (5%) | 1 | 8 |
| Vehicle Occupancy | 1.1 | 3 |
| Vehicles | 13 | 48 |
| Peak Hour Vehicle Trips (In/Out) | | |
| -Arrival (AM Peak) | 13/0 | 48/24 |
| -Departure (Midday) | 0/13 | 24/48 |

Table 9: Scouts Trips

Heritage Language Program

A Heritage Language Program will be hosted on Saturdays from approximately 10:00am to 2:00pm. This program will include approximately 160 students and 15 teachers. Consistent with previous assumptions, students are expected to carpool with an average of 3 students per vehicle, as shown in **Table 10**. Half of the drivers are assumed to remain on-site to make use of the available facilities.

| | Teachers | Students |
|----------------------------------|----------|----------|
| Persons | 15 | 160 |
| Non-Auto Modes (5%) | 1 | 8 |
| Vehicle Occupancy | 1.1 | 3 |
| Vehicles | 13 | 51 |
| Peak Hour Vehicle Trips (In/Out) | | |
| -Arrival (AM Peak) | 13/0 | 51/26 |
| -Departure (Mid-Afternoon) | 0/13 | 26/51 |

Table 10: Heritage Language Program Trips

3.3.4 Mosque

Prayer services will occur approximately 5 times per day with the exact times shifting throughout the year. Peak attendance for weekly prayers will occur on Friday afternoon (approximately 1:00pm). Attendance at the mosque for prayers is not highly prioritized within the community and therefore attendance is expected to be less than what is observed at other mosques in Ottawa. At the existing site in Vanier, prayers are not held during the school day and therefore none of the community members currently attend Friday afternoon. It has been conservatively assumed that as many as 200 persons would be in attendance at midday on Friday (not including school children and staff already on-site).

In addition to the Friday afternoon service, typical weekday attendance at prayers has been estimated at approximately 70 persons (not including school children and staff). On weekends, typical attendance at prayers is expected to increase to approximately 90 persons to account for some school-aged children attending with their parents.

The time periods have been conservatively assumed to align with the peak travel demand for other on-site programs. The estimated people and vehicle trips are summarized in **Table 11**. It has been conservatively assumed that all persons attending prayers arrive and depart within a single hour as most prayer sessions are limited to approximately 30 minutes. By comparison, the ITE Trip Generation Manual land use for mosques (which is limited to a single observation) identifies 67% or 96% of trips occurring during the peak hour of generator as inbound trips; suggesting most remain on-site for more than a 1-hour period.

| | Typical Weekday | Friday Midday Peak Hour | Saturday | | | |
|----------------------------------|-----------------|----------------------------|----------|--|--|--|
| Persons | 70 | 200 | 90 | | | |
| Non-Auto Modes (5%) | 4 | 10 | 5 | | | |
| Vehicle Occupancy | 1.65 | 1.65 | 2.1 | | | |
| Vehicles | 40 | 115 | 40 | | | |
| Peak Hour Vehicle Trips (In/Out) | 40/40 | 115/115 | 40 /40 | | | |

3.3.5 Leased Office and Warehouse Space

The proposed redevelopment includes office and warehouse space that operates independently of the previous programs, with the office occupying approximately $3,000 \text{ ft}^2$ of the gross floor area and the warehouse occupying approximately $70,000 \text{ ft}^2$ of the gross floor area.

Trips generated by the proposed office and warehouse developments during the weekday AM and PM peak periods have been estimated using relevant land uses in the ITE *Trip Generation Manual, 9th Edition*. Consistent with the existing development, the trip generation for the midday peak period has been estimated as half of the average between the AM and PM peaks.

Trips generated using the ITE trip generation rates were converted to person trips using a factor of 1.28, consistent with the City's 2017 TIA Guidelines. The person trip generation by the existing site is summarized in **Table 12**.

| Land Use | AM Peak (pph) | | Mid Peak (pph) | | | PM Peak (pph) | | | | | |
|-------------------------|---------------|---------------------------|----------------|-----|-----|---------------|-----|-----|----|-----|-----|
| Lanu USe | Code | GFA | N | OUT | тот | IN | OUT | тот | IN | OUT | тот |
| Warehousing | 150 | 69,943 ft ² | 22 | 5 | 27 | 7 | 7 | 14 | 8 | 21 | 29 |
| Single Tenant Office | 715 | 2,940 ft ² | 5 | 1 | 6 | 1 | 1 | 2 | 1 | 5 | 6 |
| | | Total | 27 | 6 | 33 | 8 | 8 | 16 | 9 | 26 | 35 |

Table 12: Leased Office and Warehouse – Person Trips

As with the existing development, the modal shares are anticipated to be consistent with the modal shares outlined in the *2011 TRANS O-D Survey Report*, specific to the Alta Vista district. A full breakdown of the person trips by modal share are shown in **Table 13**.

| Travel | Modal | AM Peak | | Mi | Midday Peak | | | PM Peak | | |
|-------------|-----------|---------|-----|-----|-------------|-----|-----|---------|-----|-----|
| Mode | Share | IN | OUT | тот | IN | OUT | тот | IN | OUT | тот |
| Total Per | son Trips | 27 | 6 | 33 | 8 | 8 | 16 | 9 | 26 | 35 |
| Auto Driver | 65% | 17 | 4 | 21 | 6 | 6 | 12 | 6 | 17 | 23 |
| Auto Pass | 15% | 4 | 1 | 5 | 1 | 1 | 2 | 1 | 4 | 5 |
| Transit | 15% | 4 | 1 | 5 | 1 | 1 | 2 | 1 | 4 | 5 |
| Non-Auto | 5% | 2 | 0 | 2 | 0 | 0 | 0 | 1 | 1 | 2 |

Table 13: Leased Office and Warehouse – Person Trips by Modal Share

The net increase in trip generation, as identified in **Table 3** through **Table 13** above, is summarized in **Table 14** and identifies additional midday and PM peak hour trips of 87vph to 213vph for typical day-to-day scenarios. There are approximately eight annual events identified separately in Section 3.3.6, for which a detailed traffic assessment has not been carried out. As previously identified in Section 1.1, the weekday midday (Friday) and PM peak hours were selected for further analysis to reflect the worst-case combination of background and site generated traffic.

| WEEKDAYS | | | | |
|-----------------------------|---------------|--------------|---------------|---------------|
| Use or Program | АМ | Midday (Fri) | PM | Evening |
| Existing Development | | | | |
| Industrial | 29/4 | 8/8 | 4/30 | - |
| Warehouse | 3/1 | 1/1 | 1/3 | - |
| Office | 106/13 | 30/30 | 17/99 | - |
| Sub Total | 138/18 | 39/39 | 22/132 | - |
| Sub-Total | 156 | 78 | 154 | - |
| Proposed Development | | | | |
| School | 65/54 | - | 35/43 | - |
| Recreational Centre Staff | 10/0 | 5 /5 | 3/7 | 0/10 |
| Religious Education (Thurs) | _ | - | - | 70/16 |
| Girls' Youth Group (Fri) | - | - | - | 46/19* |
| Exercise Facility | 19/19 | 19/19 | 29/19 | 29/29 |
| Prayers | 40/40 | 115/115 | 40/40 | 40/40 |
| Leased Warehouse | 14/3 | 5/5 | 5/14 | - |
| Leased Office | 3/1 | 1/1 | 1/3 | - |
| Sub Total | 151/117 | 145/145 | 113/126 | 185/114* |
| Sub-Total | 268 | 290 | 239 | 299* |
| Net Difference | 13/99 | 106/106 | 91/-6 | 185/114* |
| | 112 | 212 | 85 | 299 |
| SATURDAY** | | | | |
| Use/Program | АМ | Noon | Midday | Evening |
| Recreational Centre Staff | 10/0 | 5 /5 | 3/7 | 0/10 |
| Heritage Language School | 64/26 | - | 26/64 | - |
| Boys' Youth Group | - | - | - | 39/16 |
| Exercise Facility | 29/29 | 29/29 | 29/29 | 29/29 |
| Prayers | 40/40 | 40/40 | 40/40 | 40/40 |
| Sub-Total/Net Difference | 143/95 238 | 74/74 148 | 98/140 238 | 108/95 203 |
| SUNDAY** | | | | |
| Use/Program | AM | Noon | Midday | Evening |
| Scouts | 61/24 | 24/61 | - | - |
| Sub-Total/Net Difference | 61/24 85 | 24/61 85 | - | - |

| Table 14: Summary of | of Peak Hour Vehicle Trip | os (Inbound and Outbound) |
|----------------------|---------------------------|---------------------------|
|----------------------|---------------------------|---------------------------|

Note: *Weekday evening sub-total reflective of Thursday evening as the worst-case scenario. **Existing development is assumed to generate no trips on weekends.

3.3.6 Banquet Hall and Annual Events

Up to eight annual events are anticipated at the ABCO facility with attendance as high as 600 persons. Five (5) of the events are typically held on a Saturday evening while the remaining three (3) events may occur during the AM peak period. During these events, families typically travel