JLR No.: 21967-100 September 8, 2021

Revision: 0

Prepared for:

MINTO COMMUNITIES INC.

200-180 Kent Street Ottawa, ON K1P 0B6 Prepared by:

J.L. RICHARDS & ASSOCIATES LIMITED

864 Lady Ellen Place Ottawa, ON K1Z 5M2

Tel: 613-728-3571 Fax: 613-728-6012

# Noise Control Feasibility Study KENNEDY LANDS



### **Table of Contents**

1.0 2.0 3.0	INTRODUCTION	11222
4.0	CONCLUSION AND RECOMMENDATIONS	6
List	of Tables	
Table	1: Outdoor Noise Control Measures for Surface Transportation Noise	2
Table	2: Indoor Noise Control Measures for Surface Transportation Noise	2
Table	3: Outdoor Living Area (OLA) Noise Limit for Surface Transportation	3
Table	4: Indoor Noise Limit for Surface Transportation	3
	5: Road Traffic Data to Predict Noise Levels	
	6: Bus Rapid Transit Corridor Data to Predict Noise Levels	
Table	7: Predicted Freefield Noise Levels and Distances from Noise Sources	5
List	of Figures	

FIGURE 1 - Location Plan

### **List of Appendices**

Appendix 'A' Concept Plan

Freefield Daytime Noise Contours – N1

Appendix 'B' City of Ottawa Surface Transportation Sample Warning Clauses

Appendix 'C' <u>Transportation Noise Source Predictions</u>

- Detailed Predicted Freefield Noise Level Calculations (Transportation

Noise Sources)

### 1.0 INTRODUCTION

J.L. Richards & Associates Limited (JLR) was retained by Minto Communities Inc. (Minto) to prepare a Noise Control Feasibility Study for their residential development known as Kennedy Lands, located at 3432 Greenbank Road, within the City of Ottawa. The purpose of this study is to assess the potential environmental noise impact on the Development, due to vehicular traffic from Realigned Greenbank Road and Bus Rapid Transit (BRT). This Noise Control Feasibility Study develops a strategy for site plan and subdivision development that minimizes the reliance upon noise barriers, ventilation requirements and air conditioning as a means of addressing roadway noise and instead examines land use, roadway layout and building orientation as a principal means to mitigate roadway noise. Land use and building orientation identified in this study will then be examined in detail as part of the Noise Control Detailed Design Study prepared for the site plan and subdivision applications.

This report is prepared to satisfy the Ministry of the Environment (MOE) Environmental Noise Guidelines NPC-300 and the City of Ottawa Environmental Noise Control Guidelines (approved by City Council January 2016) and in particular Part 4 Section 3.1 Noise Control Feasibility Study Requirements.

### 2.0 PROJECT DESCRIPTION

The proposed residential development is situated on a ±23.4 ha parcel of land that is bounded by vacant land and future park to the north, realigned Greenbank Road to the east and south and existing/future residential to the west and south, as shown on Figure 1 - Location Plan.


The proposed development will consist of 53 Single homes, 385 Executive Towns and 160 Avenue Towns for a total of 598 units as shown on the Concept Plan (dated August 19, 2021) provided in Appendix 'A'.

### 3.0 TRANSPORTATION NOISE SOURCE

The transportation noise sources are Realigned Greenbank Road and BRT. Drawing N1 shows the location of the noise sources and existing roadways in relation to the proposed development. Existing Greenbank Road is not considered a transportation noise source for this study because it is more than 200m away from the proposed noise sensitive land use, as shown on Drawing N1.

### 3.1 Transportation Sound Level Criteria

For the purpose of determining the predicted noise levels, and based on the sound level criteria established by the City of Ottawa Environmental Noise Control Guidelines (ENCG), the following will be used as the maximum acceptable sound levels (Leq) for residential development and other land uses, such as nursing homes, schools and daycare centres:



Plot Date: Tuesday, August 24, 2021 1:39:23 PM

<u>Criteria</u>	<u>Time Period</u>
55 dBA	Daytime (0700 - 2300 hrs.)
45 dBA	Daytime (0700 - 2300 hrs.)
50 dBA	Daytime (0700 - 2300 hrs.)
40 dBA	Nighttime (2300 - 0700 hrs.)
	45 dBA 50 dBA

Outdoor Living Areas (OLA) are defined as that portion of the outdoor amenity area of a dwelling for the quiet enjoyment of the outdoor environment during the daytime period. Typically, the point of assessment in an OLA is 3.0 m from the building façade mid-point and 1.5 m above the ground within the designated OLA for each individual unit. OLAs commonly include backyards, balconies (with a minimum depth of 4 m as per NPC-300), common outdoor living areas, and passive recreational areas.

### 3.2 Transportation Noise Attenuation Requirements

When the sound levels are equal to or less than the specified criteria, per the City of Ottawa ENCG and/or MOE NPC-300, no noise attenuation (control) measures are required.

The following tables outline noise attenuation measures to achieve required dBA Leq for surface transportation noise, per the City of Ottawa ENCG.

Table 1: Outdoor Noise Control Measures for Surface Transportation Noise

	Secondary Mitigation Measures		
Primary Mitigation Measure (in order of preference)	Landscape Plantings and/or Non-acoustic Fence to Obscure Noise Source	Warning Clauses	
Distance setback with soft ground Insertion of Noise insensitive land uses between the source and receiver receptor	Recommended		
Orientation of buildings to provide sheltered zones in rear yards Shared outdoor amenity areas Earth berms (sound barriers) Acoustic barriers (acoustic barriers)	Required	Warning Clauses necessary and to include:  Reference to specific noise mitigation measures in the development.  Whether noise is expected to increase in the future.  That there is a need to maintain mitigation.	

**Table 2: Indoor Noise Control Measures for Surface Transportation Noise** 

	Secondary Mitigation Measures		
Primary Mitigation Measure (in order of preference)	Landscape Plantings and/or Non-acoustic Fence to Obscure Noise Source	Warning Clauses	
Distance setback with soft ground	Recommended	Not necessary	

J.L. Richards & Associates Limited

JLR No.: 21967-100

September 8, 2021

Revision: 0

Insertion of Noise insensitive land uses between the source and receiver receptor		
Orientation of buildings to provide sheltered zones or modified interior spaces and amenity areas  Enhanced construction techniques and construction quality	Required	Warning Clauses necessary and to include: - Reference to specific noise mitigation measures in the development.
Earth berms (sound barriers)		- Whether noise is expected
Indoor isolation – air conditioning and ventilation, enhanced dampening materials (indoor isolation)		to increase in the future.  That there is a need to maintain mitigation.

The following tables outline the noise level limits per the MOE NPC-300 and City of Ottawa ENCG.

Table 3: Outdoor Living Area (OLA) Noise Limit for Surface Transportation

Time Period	Leq (16 hr) (dBA)
16 hr., 07:00 am - 23:00	55

**Table 4: Indoor Noise Limit for Surface Transportation** 

Type of Space	Time Period	Leq (dBA)	
Type of Space	Time Period	Road	Rail
Living/dining, den areas of residences, hospitals, nursing homes, schools, daycare centres, etc.	07:00-23:00	45	40
Living/dining, den areas of residences, hospitals, nursing homes, etc. (except schools or daycare centres)	23:00-07:00	45	40
Slooping quarters	07:00-23:00	45	40
Sleeping quarters	23:00-07:00	40	35

In addition to the implementation of noise attenuation features, if required, and depending on the severity of the noise problem, warning clauses may be recommended to advise the prospective purchasers/tenants of affected units of the potential environmental noise. These warning clauses should be included in the Site Plan and Subdivision Agreements, in the Offers of Purchase and Sale, and should be registered on Title. Warning clauses may be included for any development, irrespective of whether it is considered a noise sensitive land use.

Where site measures are required to mitigate noise levels, the City of Ottawa requires that notices be placed on Title informing potential buyers and/or tenants of the site conditions. Sample templates of the notices that could be registered on Title are included in Appendix 'B' as presented in the City of Ottawa ENCG.

Detailed wording for clauses should be provided as part of a detailed Noise Impact Study to be completed in support of the Subdivision Application. Clauses are to be worded to describe the

mitigation measures and noise conditions applicable where MOE and City of Ottawa noise criteria are exceeded.

#### 3.3 Prediction of Noise Levels

#### 3.3.1 Road Traffic Data

The following traffic data was used to predict noise levels:

Table 5: Road Traffic Data to Predict Noise Levels

	Realigned Greenbank Road
Total Traffic Volume (AADT)	35,000
Day/Night Split (%)	92/8
Medium Trucks (%)	7
Heavy Trucks (%)	5
Posted Speed (km/hr.)	80
Road Gradient (%)	1
Road Classification	4-Lane Urban Arterial-Divided (4-UAD)

Schedule 'E' and Annex 1 of the City of Ottawa Official Plan (May 2003) were utilized to determine the road classification and protected right-of-way. These road classifications were compared to Map 6 of the City of Ottawa Transportation Master Plan (Road Network – Urban). All findings were then compared to Table B1 (Part 4, Appendix 'B') of the City of Ottawa Environmental Noise Control Guidelines in order to determine an appropriate AADT value.

### 3.3.2 Bus Rapid Transit Corridor Data

Drawing N1 shows the location of the Bus Rapid Transit (BRT) Corridor in relation to the proposed residential development. The following data was used to predict BRT noise levels:

Table 6: Bus Rapid Transit Corridor Data to Predict Noise Levels

	Bus Rapid Transit Corridor
Total Traffic Volume (AADT)	270
Day/Night Split (%)	74/26
Medium Trucks (%)	100
Heavy Trucks (%)	0
Posted Speed (km/hr)	80
Road Gradient (%)	1

Appendix 'C' includes confirmation from the City specific to the Bus Rapid Transit Corridor, including the speed limit, AADT value and the day/night split.

The computer program Stamson is used to predict noise levels associated with the bus rapid transit corridor.

### 3.3.3 Noise Level Calculations (Transportation)

Noise contours for the daytime periods were developed using the MOE Road Traffic Noise Computer program STAMSON, Version 5.03.

Distances were calculated from the centre of the roadway to even 5 dBA freefield noise levels ranging from 50 dBA to 70 dBA for each of the roadways. Table 7 below presents this information. Computer printouts are included in Appendix 'C'. Drawing N1 identifies the receiver locations as contours for the calculations of the roadway freefield noise levels.

Table 7: Predicted Freefield Noise Levels and Distances from Noise Sources

Roads	Contour	(Freefi	OLA eld) Distar	nce (m)
	(dBA)	Daytime		
		South Lanes	BRT	North Lanes
4-UAD	50	455.00	467.25	479.50
	55	222.00	234.25	246.50
(Realigned Greenbank Road) 80 km/hr.	60	106.00	118.25	130.50
+ BRT 80km/hr.	65	49.00	61.25	73.50
	70	22.50	34.75	47.00

J.L. Richards & Associates Limited JLR No.: 21967-100

### 3.4 Summary of Findings (Transportation)

Kennedy Lands will result in multiple blocks of residential units that will be impacted by roadway traffic noise.

Due to their proximity to the Kennedy Lands residential development, Realigned Greenbank Road has the highest noise impact on the development. To help mitigate the noise impact of these transportation noise sources, the building orientation of the condo blocks has been carefully placed to mitigate the noise for the development and reduce the need for noise barriers. Despite best efforts to passively mitigate the transportation noise, barriers may still be required.

The predicted noise contours shown on Drawing N1 are freefield and considered a conservative analysis. Existing development will also help mitigate noise levels. Where possible, non-sensitive land uses have been placed adjacent to the transportation noise sources (i.e. SWM Blocks, and Parks). Freefield noise levels at the property lines adjacent to Realigned Greenbank Road are estimated to be approximately 70 dBA as presented on Drawing N1. Noise barriers and berms are projected to be required to mitigate outdoor living area noise levels. As a minimum, a 2.2 m high noise barrier will be required along the rear and side lot lines. In some locations the noise barriers will be 2.5 m high. Other locations will require a berm in addition to a 2.5 m high noise barrier. The approximate location of potential noise barriers, based on freefield noise calculations, are presented on Drawing N2. It is recommended that a Noise Control Detailed Study be completed to review and confirm the height and location of required noise barriers and/or berms.

As an alternative to noise barrier, setback buffers could be considered to reduce or eliminate noise barriers. However, in some locations, units flanking arterial roads may have to be eliminated. This is not a financially practical solution.

As part of the recommended Noise Control Detailed Study, a preliminary building component analysis should be included.

Warning clauses similar to those presented in Appendix 'B' will be required to highlight the exceedance of MOE and City of Ottawa noise criteria and to identify mitigation measures integrated into the subdivision design. Warning clauses could be required until it can be demonstrated that the noise guideline criteria is not exceeded. It is recommended that specific wording be developed for each unit and/or block in the Noise Control Detailed Study prepared to support the subdivision application.

At the time this study was completed, a detailed grading plan was not available.

### 4.0 CONCLUSION AND RECOMMENDATIONS

Predicted noise levels are expected to exceed the City of Ottawa ENCG and MOE criteria for the proposed units adjacent to Realigned Greenbank Road. To address these exceedances, the developer has revised the draft plan of subdivision to reduce the reliance of noise barriers as the primary noise mitigation tool. Building orientation and increased separation to the transportation noise source have been used to reduce noise levels for residential units in close proximity to the transportation noise sources. Noise barriers may still be required to protect outdoor living areas.

It is recommended that the City of Ottawa accept the draft plan of subdivision submitted and include the condition for the proponent to complete a Noise Control Detailed Study as per the City of Ottawa ENCG 2016.

It is further recommended that the following be addressed as part of the Noise Control Detailed Study:

- Noise barrier details, such as height and location.
- Noise levels should be assessed at the building façade of units nearest the transportation noise sources.
- If it is determined that the noise level at the façade of a building exceeds 64.49 dBA, then the Acoustical Insulation Factor (AIF) method should be utilized to review building acoustic measures to be incorporated into the building construction. This method is described in the Ministry of the Environment of Ontario document, *Environmental Noise Assessment in Land Use Planning*, 1987 and 1999.

This report has been prepared for the exclusive use of Minto Communities Inc., for the stated purpose, for the named facility. Its discussions and conclusions are summary in nature and cannot be properly used, interpreted or extended to other purposes without a detailed understanding and discussions with the client as to its mandated purpose, scope and limitations. This report was prepared for the sole benefit and use of Minto Communities Inc. and may not be used or relied on by any other party without the express written consent of J.L. Richards & Associates Limited.

This report is copyright protected and may not be reproduced or used, other than by Minto Communities Inc. for the stated purpose, without the express written consent of J.L. Richards & Associates Limited.


#### J.L. RICHARDS & ASSOCIATES LIMITED


Prepared by:	Reviewed by:
Momas Place	
Thomas Blais, A.Sc.T. Senior GIS Technologist	Lee Jablonski, P.Eng. Associate Senior Civil Engineer


### Appendix A

Concept Plan

Freefield Daytime Noise Contours – N1







### Appendix B

City of Ottawa Surface Transportation Sample Warning Clauses

### City of Ottawa Environmental Noise Control Guidelines Sample Warning Clauses

#### Generic

Purchasers/tenants are advised that sound levels due to increasing road/rail/Light Rail/transitway traffic may occasionally interfere with some outdoor activities as the sound levels may exceed the sound level limits of the City and the Ministry of the Environment.

To help address the need for sound attenuation this development has been designed so as to provide an outdoor amenity area that is within provincial guidelines. Measures for sound attenuation could include:

- A setback of buildings from the noise source and/or
- An acoustic barrier.

To ensure that provincial sound level limits are not exceeded it is important to maintain sound attenuation features.

The acoustic barrier shall be maintained and kept in good repair by the property owner. Any maintenance, repair or replacement is the responsibility of the owner and shall be with the same material or to the same standards, having the same colour, appearance and function of the original.

Additionally this development includes trees and shrubs to screen the source of noise from occupants.

### Extensive mitigation of indoor and outdoor amenity area

Purchasers/tenants are advised that despite the inclusion of noise control features in the development and within the building units, sound levels due to increasing road/rail/Light Rail/transitway traffic may, on occasion, interfere with some activities of the dwelling occupants as the sound levels exceed the sound level limits of the City and the Ministry of the Environment.

To help address the need for sound attenuation this development includes:

- multi-pane glass;
- double brick veneer;
- an earth berm; and
- an acoustic barrier.

To ensure that provincial sound level limits are not exceeded it is important to maintain these sound attenuation features.

The acoustic barrier shall be maintained and kept in good repair by the property owner. Any maintenance, repair or replacement is the responsibility of the owner and shall be with the same material or to the same standards, having the same colour, appearance and function of the original.

This dwelling unit has also been designed with the provision for adding central air conditioning at the occupant's discretion. Installation of central air conditioning will allow windows and exterior doors to remain closed, thereby ensuring that the indoor sound levels are within the sound level limits of the City and the Ministry of the Environment. Additionally this development includes trees and shrubs to screen the source of noise from occupants.

### No Outdoor amenity area

Purchasers/tenants are advised that sound levels due to increasing road/rail/Light Rail/transitway traffic will interfere with outdoor activities as the sound levels exceed the sound level limits of the City and the Ministry of the Environment.

To help address the need for sound attenuation this development includes:

- multi-pane glass;
- double brick veneer;
- high sound transmission class walls.

To ensure that provincial sound level limits are not exceeded it is important to maintain these sound attenuation features.

This dwelling unit has been supplied with a central air conditioning system and other measures which will allow windows and exterior doors to remain closed, thereby ensuring that the indoor sound levels are within the sound level limits of the City and the Ministry of the Environment

### **Appendix C**

<u>Transportation Noise Source</u> <u>Predictions</u>

 Detailed Predicted Freefield Noise Level Calculations (Transportation Noise Sources) STAMSON 5.0 NORMAL REPORT Date: 26-08-2021 09:17:12

MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: KL\_50.te Time Period: Day/Night 16/8 hours

Description: Kennedy Lands 50 dBA contour

Road data, segment # 1: ReGrnBnk\_N (day/night)

-----

Car traffic volume : 14168/1232 veh/TimePeriod \*
Medium truck volume : 1127/98 veh/TimePeriod \*
Heavy truck volume : 805/70 veh/TimePeriod \*

Posted speed limit : 80 km/h Road gradient : 1 %

Road pavement : 1 (Typical asphalt or concrete)

\* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 17500
Percentage of Annual Growth : 0.00
Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 1: ReGrnBnk\_N (day/night)

-----

Angle1 Angle2 : -90.00 deg 90.00 deg Wood depth : 0 (No woods.)

No of house rows : 0 / 0

Surface : 1 (Absorptive ground surface)

Receiver source distance : 479.50 / 479.50 m Receiver height : 1.50 / 4.50 m

Topography : 1 (Flat/gentle slope; no barrier)

Reference angle : 0.00

lack

Road data, segment # 2: ReGrnBnk S (day/night)

\_\_\_\_\_

Car traffic volume : 14168/1232 veh/TimePeriod \*
Medium truck volume : 1127/98 veh/TimePeriod \*
Heavy truck volume : 805/70 veh/TimePeriod \*

Posted speed limit : 80 km/h Road gradient : 1 %

Road pavement : 1 (Typical asphalt or concrete)

\* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 17500 Percentage of Annual Growth : 0.00

Number of Years of Growth : 0.00 Medium Truck % of Total Volume : 7.00 Heavy Truck % of Total Volume : 5.00 Day (16 hrs) % of Total Volume : 92.00 Data for Segment # 2: ReGrnBnk\_S (day/night) -----: -90.00 deg 90.00 deg : 0 (No woods Angle1 Angle2 Wood depth (No woods.) No of house rows : 0 / 0 1 (Absorptive ground surface) Surface Receiver source distance : 455.00 / 455.00 m Receiver height : 1.50 / 4.50 : 1 (Flat/gentle slope; no barrier) Topography : 0.00 Reference angle Results segment # 1: ReGrnBnk\_N (day) \_\_\_\_\_ Source height = 1.50 m ROAD (0.00 + 46.72 + 0.00) = 46.72 dBAAngle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq \_\_\_\_\_\_ -90 90 0.66 73.16 0.00 -24.98 -1.46 0.00 0.00 0.00 46.72 \_\_\_\_\_\_ Segment Leq: 46.72 dBA Results segment # 2: ReGrnBnk\_S (day) \_\_\_\_\_ Source height = 1.50 m ROAD (0.00 + 47.10 + 0.00) = 47.10 dBAAngle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq \_\_\_\_\_\_ -90 90 0.66 73.16 0.00 -24.60 -1.46 0.00 0.00 0.00 47.10 \_\_\_\_\_\_ Segment Leq: 47.10 dBA Total Leq All Segments: 49.92 dBA Results segment # 1: ReGrnBnk\_N (night)

```
ROAD (0.00 + 40.63 + 0.00) = 40.63 \text{ dBA}
Angle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq
______
  -90 90 0.57 65.56 0.00 -23.63 -1.30 0.00 0.00 0.00 40.63
Segment Leq: 40.63 dBA
Results segment # 2: ReGrnBnk_S (night)
-----
Source height = 1.50 m
ROAD (0.00 + 40.99 + 0.00) = 40.99 dBA
Angle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq
  -90 90 0.57 65.56 0.00 -23.27 -1.30 0.00 0.00 0.00 40.99
Segment Leq: 40.99 dBA
Total Leq All Segments: 43.82 dBA
RT/Custom data, segment # 1: BRT (day/night)
-----
Traffic volume : 200/70
                       veh/TimePeriod
Speed
            : 80 km/h
Data for Segment # 1: BRT (day/night)
-----
Angle1 Angle2 : -90.00 deg 90.00 deg Wood depth : 0 (No woods
                              (No woods.)
No of house rows :
                        0 / 0
Surface
                       1
                              (Absorptive ground surface)
Receiver source distance : 467.25 / 467.25 m
Receiver height : 1.50 / 4.50
Topography
                  : 1
                              (Flat/gentle slope; no barrier)
Reference angle : 0.00
Results segment # 1: BRT (day)
______
```

Source height = 1.50 m

Source height = 0.50 m

```
RT/Custom (0.00 + 33.37 + 0.00) = 33.37 dBA
Angle1 Angle2 Alpha RefLeq D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq
______
  -90 90 0.66 59.61 -24.79 -1.46 0.00 0.00 0.00 33.37
______
Segment Leq: 33.37 dBA
Total Leq All Segments: 33.37 dBA
Results segment # 1: BRT (night)
-----
Source height = 0.50 m
RT/Custom (0.00 + 32.81 + 0.00) = 32.81 dBA
Angle1 Angle2 Alpha RefLeq D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq
     90 0.60 58.06 -23.90 -1.35 0.00 0.00 0.00 32.81
Segment Leq: 32.81 dBA
Total Leq All Segments: 32.81 dBA
TOTAL Leg FROM ALL SOURCES (DAY): 50.02
                    (NIGHT): 44.15
STAMSON 5.0
               NORMAL REPORT
                                Date: 26-08-2021 09:03:11
MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT
Filename: KL 55.te
                        Time Period: Day/Night 16/8 hours
Description: Kennedy Lands 55 dBA contour
Road data, segment # 1: ReGrnBnk_N (day/night)
-----
Car traffic volume : 14168/1232 veh/TimePeriod
Medium truck volume : 1127/98 veh/TimePeriod
Heavy truck volume : 805/70 veh/TimePeriod *
Posted speed limit : 80 km/h
Road gradient : 1 %
Road pavement : 1 (Typical asphalt or concrete)
```

\* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 17500 Percentage of Annual Growth : 0.00 Number of Years of Growth : 0.00 Medium Truck % of Total Volume : 7.00 Heavy Truck % of Total Volume : 5.00 Day (16 hrs) % of Total Volume : 92.00

### Data for Segment # 1: ReGrnBnk N (day/night)

-----

Angle1 Angle2 : -90.00 deg 90.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)

Receiver source distance : 246.50 / 246.50 m

Receiver height : 1.50 / 4.50 m
Topography : 1 (Flat/gentle slope; no barrier)

Reference angle : 0.00

Road data, segment # 2: ReGrnBnk S (day/night)

-----

Car traffic volume : 14168/1232 veh/TimePeriod \* Medium truck volume : 1127/98 veh/TimePeriod \* Heavy truck volume : 805/70 veh/TimePeriod \*

Posted speed limit : 80 km/h

Road gradient : 1 %
Road pavement : 1 (Typical asphalt or concrete)

\* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 17500 Percentage of Annual Growth : 0.00 Number of Years of Growth : 0.00 Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

### Data for Segment # 2: ReGrnBnk\_S (day/night)

-----

Angle1 Angle2 : -90.00 deg 90.00 deg Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive

(Absorptive ground surface)

Receiver source distance : 222.00 / 222.00 m

Receiver height : 1.50 / 4.50 m
Topography : 1 (Flat/gentle slope; no barrier)

Reference angle : 0.00

```
Results segment # 1: ReGrnBnk N (day)
-----
Source height = 1.50 m
ROAD (0.00 + 51.52 + 0.00) = 51.52 \text{ dBA}
Angle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq
  -90 90 0.66 73.16 0.00 -20.18 -1.46 0.00 0.00 0.00 51.52
Segment Leq: 51.52 dBA
Results segment # 2: ReGrnBnk S (day)
_____
Source height = 1.50 m
ROAD (0.00 + 52.27 + 0.00) = 52.27 \text{ dBA}
Angle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq
______
  -90 90 0.66 73.16 0.00 -19.43 -1.46 0.00 0.00 0.00 52.27
______
Segment Leq: 52.27 dBA
Total Leq All Segments: 54.92 dBA
Results segment # 1: ReGrnBnk_N (night)
_____
Source height = 1.50 m
ROAD (0.00 + 45.17 + 0.00) = 45.17 \text{ dBA}
Angle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq
-----
      90 0.57 65.56 0.00 -19.09 -1.30 0.00 0.00 0.00 45.17
______
Segment Leq: 45.17 dBA
Results segment # 2: ReGrnBnk S (night)
______
Source height = 1.50 m
```

```
ROAD (0.00 + 45.88 + 0.00) = 45.88 dBA
Angle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq
  -90 90 0.57 65.56 0.00 -18.37 -1.30 0.00 0.00 0.00 45.88
Segment Leq: 45.88 dBA
Total Leq All Segments: 48.55 dBA
RT/Custom data, segment # 1: BRT (day/night)
_____
Traffic volume : 200/70 veh/TimePeriod
Speed
              : 80 km/h
Data for Segment # 1: BRT (day/night)
Angle1 Angle2 : -90.00 deg 90.00 deg
No of house rows : 0 / 0
Surface
                                 (No woods.)
                           0 / 0
                           1
                                  (Absorptive ground surface)
Receiver source distance : 234.25 / 234.25 m
Receiver height : 1.50 / 4.50
                                  (Flat/gentle slope; no barrier)
Topography
                         1
                : 0.00
Reference angle
Results segment # 1: BRT (day)
_____
Source height = 0.50 \text{ m}
RT/Custom (0.00 + 38.34 + 0.00) = 38.34 dBA
Angle1 Angle2 Alpha RefLeq D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq
  -90 90 0.66 59.61 -19.81 -1.46 0.00 0.00 0.00 38.34
Segment Leq: 38.34 dBA
Total Leq All Segments: 38.34 dBA
Results segment # 1: BRT (night)
_____
Source height = 0.50 m
```

```
RT/Custom (0.00 + 37.61 + 0.00) = 37.61 dBA
Angle1 Angle2 Alpha RefLeq D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq
______
  -90 90 0.60 58.06 -19.10 -1.35 0.00 0.00 0.00 37.61
______
Segment Leq: 37.61 dBA
Total Leq All Segments: 37.61 dBA
TOTAL Leg FROM ALL SOURCES (DAY): 55.02
                      (NIGHT): 48.89
STAMSON 5.0 NORMAL REPORT
                                   Date: 26-08-2021 08:50:35
MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT
Filename: KL 60.te
                           Time Period: Day/Night 16/8 hours
Description: Kennedy Lands 60 dBA contour
Road data, segment # 1: ReGrnBnk_N (day/night)
_____
Car traffic volume : 14168/1232 veh/TimePeriod *
Medium truck volume : 1127/98 veh/TimePeriod * Heavy truck volume : 805/70 veh/TimePeriod *
Posted speed limit : 80 km/h
Road gradient :
                     1 %
Road pavement : 1 (Typical asphalt or concrete)
* Refers to calculated road volumes based on the following input:
   24 hr Traffic Volume (AADT or SADT): 17500
   Percentage of Annual Growth : 0.00
   Number of Years of Growth
                                 : 0.00
   Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00
Data for Segment # 1: ReGrnBnk N (day/night)
-----
Angle1 Angle2 : -90.00 deg
                                    90.00 deg
Anglei Anglei
Wood depth : 0
No of house rows : 0 / 0
: 1
                                    (No woods.)
```

(Absorptive ground surface) Receiver source distance : 130.50 / 130.50 m

```
Receiver height : 1.50 / 4.50 m
Topography
                    : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00
Road data, segment # 2: ReGrnBnk_S (day/night)
-----
Car traffic volume : 14168/1232 veh/TimePeriod *
Medium truck volume : 1127/98 veh/TimePeriod *
Heavy truck volume : 805/70 veh/TimePeriod *
Posted speed limit : 80 km/h
Road gradient : 1 %
Road pavement : 1 (Typical asphalt or concrete)
* Refers to calculated road volumes based on the following input:
   24 hr Traffic Volume (AADT or SADT): 17500
   Percentage of Annual Growth : 0.00
   Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
   Day (16 hrs) % of Total Volume : 92.00
Data for Segment # 2: ReGrnBnk_S (day/night)
-----
Angle1 Angle2 : -90.00 deg 90.00 deg Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive
                        1 (Absorptive ground surface)
Receiver source distance : 106.00 / 106.00 m
Receiver height : 1.50 / 4.50 m
Topography
                     : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00
Results segment # 1: ReGrnBnk_N (day)
-----
Source height = 1.50 m
ROAD (0.00 + 56.10 + 0.00) = 56.10 \text{ dBA}
Angle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq
______
  -90 90 0.66 73.16 0.00 -15.60 -1.46 0.00 0.00 0.00 56.10
______
Segment Leq: 56.10 dBA
```

Results segment # 2: ReGrnBnk\_S (day)

Source height = 1.50 m

ROAD (0.00 + 57.60 + 0.00) = 57.60 dBAAngle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq -------90 90 0.66 73.16 0.00 -14.10 -1.46 0.00 0.00 0.00 57.60 -----

Segment Leq: 57.60 dBA

Total Leg All Segments: 59.92 dBA

Results segment # 1: ReGrnBnk N (night) \_\_\_\_\_

Source height = 1.50 m

ROAD (0.00 + 49.51 + 0.00) = 49.51 dBAAngle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq \_\_\_\_\_\_ -90 90 0.57 65.56 0.00 -14.75 -1.30 0.00 0.00 0.00 49.51 \_\_\_\_\_\_

Segment Leq: 49.51 dBA

Results segment # 2: ReGrnBnk\_S (night) -----

Source height = 1.50 m

ROAD (0.00 + 50.92 + 0.00) = 50.92 dBAAngle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq 90 0.57 65.56 0.00 -13.33 -1.30 0.00 0.00 0.00 50.92

Segment Leq: 50.92 dBA

Total Leq All Segments: 53.28 dBA

RT/Custom data, segment # 1: BRT (day/night)

-----

1 - Bus:

veh/TimePeriod

Traffic volume : 200/70 Speed : 80 km/ 80 km/h

```
Data for Segment # 1: BRT (day/night)
-----
Angle1 Angle2 : -90.00 deg 90.00 deg Wood depth : 0 (No woods
                             (No woods.)
No of house rows :
                        0 / 0
Surface
                              (Absorptive ground surface)
                       1
Receiver source distance : 118.25 / 118.25 m
Receiver height : 1.50 / 4.50
                  : 1 (Flat/gentle slope; no barrier)
Topography
Reference angle : 0.00
Results segment # 1: BRT (day)
______
Source height = 0.50 m
RT/Custom (0.00 + 43.27 + 0.00) = 43.27 dBA
Angle1 Angle2 Alpha RefLeq D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq
______
  -90 90 0.66 59.61 -14.89 -1.46 0.00 0.00 0.00 43.27
______
Segment Leq: 43.27 dBA
Total Leq All Segments: 43.27 dBA
Results segment # 1: BRT (night)
_____
Source height = 0.50 \text{ m}
RT/Custom (0.00 + 42.36 + 0.00) = 42.36 dBA
Angle1 Angle2 Alpha RefLeq D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq
  -90 90 0.60 58.06 -14.35 -1.35 0.00 0.00 0.00 42.36
______
Segment Leq: 42.36 dBA
Total Leq All Segments: 42.36 dBA
TOTAL Leg FROM ALL SOURCES (DAY): 60.02
```

(NIGHT): 53.62

1

STAMSON 5.0 NORMAL REPORT Date: 26-08-2021 09:45:39

MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: kl\_65.te Time Period: Day/Night 16/8 hours

Description: Kennedy Lands 65 dBA contour

Road data, segment # 1: ReGrnBnk\_N (day/night)

Car traffic volume : 14168/1232 veh/TimePeriod \*
Medium truck volume : 1127/98 veh/TimePeriod \*
Heavy truck volume : 805/70 veh/TimePeriod \*

Posted speed limit : 80 km/h Road gradient : 1 %

Road pavement : 1 (Typical asphalt or concrete)

\* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 17500
Percentage of Annual Growth : 0.00
Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 1: ReGrnBnk\_N (day/night)

-----

Angle1 Angle2 : -90.00 deg 90.00 deg Wood depth : 0 (No woods.)

No of house rows : 0 / 0

Surface : 1 (Absorptive ground surface)

Receiver source distance : 73.50 / 73.50 m Receiver height : 1.50 / 4.50 m

Topography : 1 (Flat/gentle slope; no barrier)

Reference angle : 0.00

♠

Road data, segment # 2: ReGrnBnk S (day/night)

-----

Car traffic volume : 14168/1232 veh/TimePeriod \*
Medium truck volume : 1127/98 veh/TimePeriod \*
Heavy truck volume : 805/70 veh/TimePeriod \*

Posted speed limit : 80 km/h
Road gradient : 1 %

Road pavement : 1 (Typical asphalt or concrete)

\* Refers to calculated road volumes based on the following input:

```
24 hr Traffic Volume (AADT or SADT): 17500
   Percentage of Annual Growth : 0.00
   Number of Years of Growth
                             : 0.00
   Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00
Data for Segment # 2: ReGrnBnk_S (day/night)
Angle1 Angle2 : -90.00 deg 90.00 deg
Wood depth : 0
No of house rows : 0 / 0
                               (No woods.)
                        1
Surface
                                (Absorptive ground surface)
Receiver source distance : 49.00 / 49.00 m
Receiver height : 1.50 / 4.50 m
                                (Flat/gentle slope; no barrier)
Topography
                       1
              : 0.00
Reference angle
Results segment # 1: ReGrnBnk_N (day)
-----
Source height = 1.50 m
ROAD (0.00 + 60.24 + 0.00) = 60.24 dBA
Angle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq
  -90 90 0.66 73.16 0.00 -11.46 -1.46 0.00 0.00 0.00 60.24
______
Segment Leq: 60.24 dBA
Results segment # 2: ReGrnBnk S (day)
______
Source height = 1.50 m
ROAD (0.00 + 63.17 + 0.00) = 63.17 \text{ dBA}
Angle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq
______
  -90 90 0.66 73.16 0.00 -8.53 -1.46 0.00 0.00 0.00 63.17
______
Segment Leq: 63.17 dBA
Total Leq All Segments: 64.96 dBA
```

Results segment # 1: ReGrnBnk\_N (night)

Source height = 1.50 m ROAD (0.00 + 53.42 + 0.00) = 53.42 dBAAngle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq ------90 90 0.57 65.56 0.00 -10.84 -1.30 0.00 0.00 0.00 53.42 -----Segment Leq: 53.42 dBA Results segment # 2: ReGrnBnk\_S (night) \_\_\_\_\_ Source height = 1.50 m ROAD (0.00 + 56.18 + 0.00) = 56.18 dBAAngle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq \_\_\_\_\_\_ -90 90 0.57 65.56 0.00 -8.07 -1.30 0.00 0.00 0.00 56.18 \_\_\_\_\_\_ Segment Leq: 56.18 dBA Total Leq All Segments: 58.03 dBA RT/Custom data, segment # 1: BRT (day/night) -----1 - Bus: Traffic volume : 200/70 veh/TimePeriod Speed : 80 km/h Data for Segment # 1: BRT (day/night) : -90.00 deg Angle1 Angle2 90.00 deg Wood depth : 0 (No woods.) No of house rows : 0 / 0 Surface 1 (Absorptive ground surface) Receiver source distance : 61.25 / 61.25 m Receiver height : 1.50 / 4.50 Topography (Flat/gentle slope; no barrier) : 1 : 0.00 Reference angle

Results segment # 1: BRT (day)

```
Source height = 0.50 m
RT/Custom (0.00 + 48.01 + 0.00) = 48.01 dBA
Angle1 Angle2 Alpha RefLeq D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq
______
  -90 90 0.66 59.61 -10.14 -1.46 0.00 0.00 0.00 48.01
______
Segment Leq: 48.01 dBA
Total Leq All Segments: 48.01 dBA
Results segment # 1: BRT (night)
-----
Source height = 0.50 m
RT/Custom (0.00 + 46.93 + 0.00) = 46.93 dBA
Angle1 Angle2 Alpha RefLeq D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq
______
  -90 90 0.60 58.06 -9.78 -1.35 0.00 0.00 0.00 46.93
______
Segment Leq: 46.93 dBA
Total Leq All Segments: 46.93 dBA
TOTAL Leq FROM ALL SOURCES (DAY): 65.04
                   (NIGHT): 58.35
STAMSON 5.0
              NORMAL REPORT
                               Date: 26-08-2021 09:21:04
MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT
Filename: kl 70.te
                        Time Period: Day/Night 16/8 hours
Description: Kennedy Lands 70 dBA contour
Road data, segment # 1: ReGrnBnk_N (day/night)
-----
Car traffic volume : 14168/1232 veh/TimePeriod *
Medium truck volume : 1127/98 veh/TimePeriod * Heavy truck volume : 805/70 veh/TimePeriod *
Posted speed limit : 80 km/h Road gradient : 1 %
```

Road pavement : 1 (Typical asphalt or concrete) \* Refers to calculated road volumes based on the following input: 24 hr Traffic Volume (AADT or SADT): 17500 Percentage of Annual Growth : 0.00 Number of Years of Growth : 0.00 Medium Truck % of Total Volume : 7.00 Heavy Truck % of Total Volume : 5.00 Day (16 hrs) % of Total Volume : 92.00 Data for Segment # 1: ReGrnBnk\_N (day/night) -----Angle1 Angle2 : -90.00 deg 90.00 deg Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive Surface : 1 (Absorber source distance : 47.00 / 47.00 m (Absorptive ground surface) Receiver height : 1.50 / 4.50 m
Topography : 1 (Flat/gentle slope; no barrier) Reference angle : 0.00 Road data, segment # 2: ReGrnBnk\_S (day/night) -----Car traffic volume : 14168/1232 veh/TimePeriod \* Medium truck volume : 1127/98 veh/TimePeriod \* Heavy truck volume : 805/70 veh/TimePeriod \* Posted speed limit : 80 km/h Road gradient : 1 %
Road pavement : 1 (Typical asphalt or concrete) \* Refers to calculated road volumes based on the following input: 24 hr Traffic Volume (AADT or SADT): 17500 Percentage of Annual Growth : 0.00 Number of Years of Growth : 0.00 Medium Truck % of Total Volume : 7.00 Heavy Truck % of Total Volume : 5.00 Day (16 hrs) % of Total Volume : 92.00 Data for Segment # 2: ReGrnBnk\_S (day/night) -----Angle1 Angle2 : -90.00 deg 90.00 deg Wood depth : 0 (No woods No of house rows : 0 / 0 Surface : 1 (Absorptive (No woods.)

Receiver height : 1.50 / 4.50 m
Topography : 1 (Flat/gentle slope; no barrier)

Receiver source distance : 22.50 / 22.50 m

1 (Absorptive ground surface)

```
Reference angle
              : 0.00
Results segment # 1: ReGrnBnk_N (day)
Source height = 1.50 m
ROAD (0.00 + 63.47 + 0.00) = 63.47 dBA
Angle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq
_____
       90 0.66 73.16 0.00 -8.23 -1.46 0.00 0.00 0.00 63.47
Segment Leq: 63.47 dBA
Results segment # 2: ReGrnBnk_S (day)
Source height = 1.50 m
ROAD (0.00 + 68.78 + 0.00) = 68.78 dBA
Angle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq
------
  -90
       90 0.66 73.16 0.00 -2.92 -1.46 0.00 0.00 0.00 68.78
Segment Leq: 68.78 dBA
Total Leg All Segments: 69.90 dBA
Results segment # 1: ReGrnBnk_N (night)
Source height = 1.50 m
ROAD (0.00 + 56.47 + 0.00) = 56.47 \text{ dBA}
Angle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq
______
  -90 90 0.57 65.56 0.00 -7.79 -1.30 0.00 0.00 0.00 56.47
Segment Leq: 56.47 dBA
Results segment # 2: ReGrnBnk_S (night)
```

```
Source height = 1.50 m
ROAD (0.00 + 61.49 + 0.00) = 61.49 dBA
Angle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq
______
  -90 90 0.57 65.56 0.00 -2.76 -1.30 0.00 0.00 0.00 61.49
______
Segment Leq: 61.49 dBA
Total Leq All Segments: 62.68 dBA
RT/Custom data, segment # 1: BRT (day/night)
-----
1 - Bus:
Traffic volume : 200/70
Speed : 80 km/h
                      veh/TimePeriod
Data for Segment # 1: BRT (day/night)
-----
Angle1 Angle2 : -90.00 deg 90.00 deg Wood depth : 0 (No woods
                             (No woods.)
No of house rows :
                      0 / 0
Surface
                      1
                             (Absorptive ground surface)
Receiver source distance : 34.75 / 34.75 m
Receiver height : 1.50 / 4.50 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00
Results segment # 1: BRT (day)
_____
Source height = 0.50 m
RT/Custom (0.00 + 52.10 + 0.00) = 52.10 dBA
Angle1 Angle2 Alpha RefLeq D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq
______
  -90 90 0.66 59.61 -6.06 -1.46 0.00 0.00 0.00 52.10
______
Segment Leq: 52.10 dBA
Total Leq All Segments: 52.10 dBA
Results segment # 1: BRT (night)
```

-----

Source height = 0.50 m

RT/Custom (0.00 + 50.87 + 0.00) = 50.87 dBA

Angle1 Angle2 Alpha RefLeq D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq

-90 90 0.60 58.06 -5.84 -1.35 0.00 0.00 0.00 50.87

Segment Leq: 50.87 dBA

Total Leq All Segments: 50.87 dBA

**^** 

TOTAL Leq FROM ALL SOURCES (DAY): 69.97 (NIGHT): 62.96

^ ^ [



### www.jlrichards.ca

### Ottawa

864 Lady Ellen Place Ottawa ON Canada K1Z 5M2 Tel: 613 728-3571

ottawa@jlrichards.ca

### **Kingston**

203-863 Princess Street Kingston ON Canada K7L 5N4 Tel: 613 544-1424

kingston@jlrichards.ca

### Sudbury

314 Countryside Drive Sudbury ON Canada P3E 6G2 Tel: 705 522-8174

sudbury@jlrichards.ca

### **Timmins**

834 Mountjoy Street S Timmins ON Canada P4N 7C5 Tel: 705 360-1899

timmins@jlrichards.ca

### **North Bay**

501-555 Oak Street E North Bay ON Canada P1B 8L3 Tel: 705 495-7597

northbay@jlrichards.ca

### Hawkesbury

326 Bertha Street Hawkesbury ON Canada K6A 2A8 Tel: 613 632-0287

hawkesbury@jlrichards.ca

### Guelph

107-450 Speedvale Ave. West Guelph ON Canada N1H 7Y6

Tel: 519 763-0713

guelph@jlrichards.ca



JLR Logo is a Registered Trademark ® 2009, all rights are reserved