

SCALE 1:150

GENERAL NOTES:

- 1. ACER RUBRUM, CELTIS OCCIDENTALIS, AND QUERCUS RUBRA TO BE SPRING DUG SPECIMENS AND PLANTED IN THE
- 2. THE LOCATION OF THE TREES SHOWN ON THIS PLAN IS APPROXIMATE AND SHALL NOT BE SCALED FROM THIS DRAWING. THIS PLAN MUST BE READ IN CONJUNCTION WITH THE APPROVED CUP AND CITY CROSS SECTIONS.
- 3. CONTRACTOR SHALL ENSURE THAT ALL UTILITY LOCATIONS ARE OBTAINED PRIOR TO ANY EXCAVATION FOR LANDSCAPING.
- 4. LOCATION OF ALL PLANT MATERIALS TO BE STAKED BY THE CONTRACTOR AND VERIFIED IN THE FIELD BY
- 5. ALL PLANT MATERIAL SHALL BE NURSERY GROWN STOCK UNLESS OTHERWISE NOTED.
- 6. TREES TO HAVE A MINIMUM 1800 CLEAR STEM ABOVE GRADE.
- 7. PLACE SOD ON A MINIMUM 150mm TOPSOIL.
- 8. CONTRACTOR TO MAKE GOOD ALL EXISTING AREAS DAMAGED BY HIS WORK TO THE SATISFACTION OF THE CITY OF
- 9. THE CITY WILL BE NOTIFIED IF ANY TREES CANNOT BE LOCATED OR PLANTED DUE TO CONFLICTS WITH UTILITIES OR DRIVEWAYS. THE REQUIRED TREES NOT PLANTED ARE SUBJECT TO TREE BANKING. THE FINAL NUMBER OF TREES TO BE BANKED WILL BE PROVIDED TO THE CITY FOLLOWING ALL PLANTINGS.
- 10. ALL PLANT MATERIAL SHALL BE WARRANTIED FOR TWO YEARS FROM THE DATE OF PERFORMANCE ACCEPTANCE AS DETERMINED BY THE CITY OF OTTAWA.
- 11. PERIODIC REVIEWS OF PLANTING SHALL BE CARRIED OUT BY THE LANDSCAPE ARCHITECT.
- 12. PLANTINGS TO BE STAKED FOR APPROVAL PRIOR TO CONSTRUCTION

PLANTING NOTES:

- 1. CONTRACTOR TO VERIFY LOCATION OF ALL SERVICES PRIOR TO ANY EXCAVATION.
- 2. LOCATIONS OF ALL PLANT MATERIALS TO BE STAKED BY THE CONTRACTOR AND VERIFIED IN THE FIELD BY LANDSCAPE ARCHITECT PRIOR TO THE EXCAVATION OF PITS.
- 3. ALL PLANT MATERIAL SHALL BE NURSERY GROWN STOCK UNLESS OTHERWISE NOTED.
- 4. DECIDUOUS TREES TO HAVE A MINIMUM 1800 CLEAR STEM ABOVE GRADE.
- 5. ALL PLANT MATERIAL SHALL BE WARRANTIED FOR TWO YEARS FROM THE DATE OF SUBSTANTIAL COMPLETION AS DETERMINED BY THE LANDSCAPE ARCHITECT.
- 6. ALL STEEL T-BARS TO BE REMOVED AT THE ONE YEAR INTERIM INSPECTION UNLESS OTHERWISE DIRECTED BY THE LANDSCAPE ARCHITECT.
- 7. CONTRACTOR TO REINSTATE ALL EXISTING AREAS DAMAGED BY HIS WORK TO THE SATISFACTION OF THE
- 8. PERIODIC REVIEWS OF PLANTING SHALL BE CARRIED OUT BY THE LANDSCAPE ARCHITECT.
- 9. ACER RUBRUM, QUERCUS RUBRA AND CELTIS OCCIDENTALIS TO BE SPRING DUG SPECIMENS AND PLANTING IN THE SPRING ONLY.
- 10. ANY PROPOSED SUBSTITUTIONS OF PLANT SPECIES SHALL BE MADE WITH PLANTS OF EQUIVALENT OVERALL FORM, HEIGHT, BRANCHING HABIT, FLOWER, LEAF, COLOR, FRUIT AND CULTURE AND ONLY AFTER APPROVAL OF THE LANDSCAPE ARCHITECT.
- 11. TREE STAKING IS NOT RECOMMENDED WITHIN A 10m RADIUS OF THE PLAY EQUIPMENT.


SOD & SEED NOTES:

- 1. SODDED AND SEEDED AREAS SHALL HAVE A MINIMUM 150mm TOPSOIL
- 2. ALL SEED MUST BE FROM A RECOGNIZED SEED FIRM, MEETING THE REQUIREMENTS FOR THE SEEDS ACT FOR CANADA NO. 1 SEED. SEED SHALL BE CERTIFIED NO. 1 GRADE. A GERMINATION TEST MAY BE REQUESTED AND ALL LAWN SEED MUST COMPLY WITH FEDERAL AND PROVINCIAL SEED LAWS.
- 3. INSTALL STANDARD MIXTURE BY MECHANICAL SEEDING. USE BIODEGRADABLE EROSION CONTROL MAT AS DIRECTED BY LANDSCAPE ARCHITECT TO RETAIN SEED ON STEEP SLOPES (OVER 3:1 UNTIL ESTABLISHED).
- 4. PLANT SEED AT A DEPTH EQUAL TO THE WIDEST THICKNESS OF THE SEED. GENERALLY THIS IS 6mm (1/4") OR AS PER SUPPLIERS RECOMMENDATIONS.
- 5. GENTLY TAMP OR ROLL THE SEEDBED AND DO NOT COMPACT THE SOIL. EXCESSIVE FORCE WILL DESTROY THE SOIL STRUCTURE AND INHIBIT GERMINATION.
- 6. CUT THE GRASS TO 50mm WHENEVER IT REACHES THE HEIGHT OF 70mm. REMOVE CLIPPINGS THAT WILL
- 8. SODDED AND SEEDED AREAS WILL BE ACCEPTED BY THE LANDSCAPE ARCHITECT FOLLOWING
 - PERFORMANCE ACCEPTANCE, PROVIDED:
 - SEEDED AREAS ARE PROPERLY ESTABLISHED. - TURF IS FREE OF DEAD SPOTS AND WEEDS.
 - NO SURFACE SOIL IS VISIBLE WHEN GRASS HAS BEEN CUT TO A HEIGHT OF 50mm
 - TURF AREAS HAVE BEEN CUT NO LESS THAN TWICE (MINIMUM), THE LAST CUT BEING CARRIED OUT WITHIN 24 HOURS PRIOR TO THE ACCEPTANCE INSPECTION.

PLANT LIST

KEY	QTY.	BOTANICAL NAME	COMMON NAME	CAL/HT.	ROOT		
DECIE	DUOUS TE	REES					
AR	4	ACER RUBRUM	RED MAPLE	60	B&B		
GD	4	GYMNOCLADUS DIOICUS	KENTUCKY COFFEE TREE	70	B&B		
QM	3	QUERCUS MACROCARPA	BUR OAK	70	B&B		
NS	2	NYSSA SYLVATICA	SOURGUM	70	B&B		
TA	3	TILIA AMERICANA	BASSWOOD	60	B&B		
SMAL AC	L MULTI- 4	STEM TREES AMELANCHIER CANADENSIS	SERVICEBERRY	70	B&B		
	CONIFEROUS STREET TREES						
PS	4	PINUS STROBUS	WHITE PINE	200cm	B&B		
DECIE Sj	OOUS SHF 26	RUBS SPIRAEA JAPONICA 'GOLDFLAME'	GOLDFLAME SPIREA		3 GAL.		
GRAS ca hms	SES/PERE 20 101	NNIALS CALAMAGROSTIS X ACUTIFLORA 'KARL FOERSTER' HEMEROCALLIS 'MINI STELLA'	KARL FOERSTER REED GRASS DAYLILY		1 GAL. 1 GAL.		

Contractor shall check all dimensions on the work and report any discrepancy to the Landscape Architect before proceeding. All drawings and specifications are the property of the Landscape Architect and must be returned at the completion of the work. This drawing is not to be used for construction until signed by the



LEGEND PROPERTY LINE

FENCING

PRIVACY FENCE

SURFACING

C.I.P CONCRETE

UNIT PAVING

PLANTING

DECIDUOUS TREE

SMALL MULTI-STEM TREE

CONIFEROUS TREE

DECIDUOUS SHRUB

GRASSES/PERENNIALS

2 Issued for First Submission 2023/06/09 1 Issued for Client Review 2023/05/19 No. Description Date

City Approval Stamp

Revision





1285 WELLINGTON STREET, OTTAWA, ON K1Y 3A8 CANADA T 613.237.2345 NAKDESIGNSTRATEGIES.COM


Manotick Main Development 5646 Manotick Main Street


Date 2023-05-16 Scale 1:150 Drawn EL Checked MK


Job No. 23-088

L01

SITE PLAN







REMOVE DAMAGED OR

NOT PRUNE LEADER.

AROUND TREE BASE.

OBJECTIONABLE BRANCHES,

FOLLOW THE MOST RECENT

CANADIAN NURSARY & TRADES

ASSOCIATION PRACTICE. DO

CONSTRUCT 100mm SAUCER

CUT AND REMOVE BURLAP

DISTURBING ROOTS.


AND WIRE BASKET FROM TOP

CONIFEROUS TREE PLANTING

TITLE:

2/3 OF ROOT BALL WITHOUT







MINIMUM 1 STAKE 2400mm LONG ON WINDWARD SIDE. SECURE

WITH No. 12 GALVANIZED WIRE ENCASED IN 12mm DIAMETER

STAKES AFTER ONE YEAR. STAKE BEYOND EDGE OF ROOT BALL

ROOT COLLAR TO BE SET 100mm ABOVE FINISHED GRADE

TOPSOIL MIXTURE AS PER SPECIFICATION

COMPACTED SUBGRADE

PLANTING TRENCH

WELL DRAINED SOILS (LOTS)

CONIFEROUS TREE PLANTING

RUBBER HOSE, ALLOWING SLACK IN GALVANIZED WIRE. REMOVE

1. ALL MEASUREMENTS ARE IN MILLIMETRES

DATE: MAY 2001


REV: JAN 2017

DWG No: L2


UNLESS OTHERWISE NOTED


2. LOCATION AS SPECIFIED ON THE

CONTRACT DRAWINGS



PERENNIAL/GRASS PLANTING








Contractor shall check all dimensions on the work and report any discrepancy to the Landscape Architect before proceeding. All drawings and specifications are the property of the Landscape Architect and must be returned at the completion of the work. This drawing is not to be used for construction until signed by the Landscape Architect.

2 Issued for First Submission 2023/06/09 2023/05/19 1 Issued for Client Review Date No. Description Revision City Approval Stamp






design strategies 1285 WELLINGTON STREET, OTTAWA, ON K1Y 3A8 CANADA T 613.237.2345 NAKDESIGNSTRATEGIES.COM

Manotick Main Development 5646 Manotick Main Street

DETAILS

Date 2023-05-16 Scale 1:150 Drawn EL Checked MK Job No. 23-088

L02



1.8m PRIVACY FENCE

Contractor shall check all dimensions on the work and report any discrepancy to the Landscape Architect before proceeding. All drawings and specifications are the property of the Landscape Architect and must be returned at the completion of the work. This drawing is not to be used for construction until signed by the Landscape Architect.

-		
-		
-		
-		
-		
2	Issued for First Submission	2023/06/09
1	Issued for Client Review	2023/05/19
No.	Description	Date

City Approval Stamp





1285 WELLINGTON STREET, OTTAWA, ON K1Y 3A8 CANADA T 613.237.2345 NAKDESIGNSTRATEGIES.COM

Manotick Main Development
5646 Manotick Main Street

DETAILS

Date 2023-05-16 Scale 1:150 Drawn EL Checked MK

Job No. 23-088

L03