CURVE SCHEDULE

NUM.	LOCATION	RADIUS	ARC	CHORD	BEARING
C1	promenade Dealership Drive	28.47	44.74	40.28	N22°26'50"E
C2	promenade Dealership Drive	165.42	61.70	61.35	N57°27'30"E
C3	promenade Dealership Drive	361.96	35.61	35.59	N56°09'40"E
C4	promenade Dealership Drive	704.87	21.20	21.20	N56°22'50"E





APPROVED UNDER SECTION 51 OF THE PLANNING ACT BY THE CITY OF OTTAWA.

THIS 7 DAY OF May 15

MICHAEL MCGE, MCIP, RPP, ACTING GENERAL MANAGER
PLANNING AND GROWTH MANAGEMENT DEPARTMENT
PLANNING AND INFRASTRUCTURE PORTFOLIO
CITY OF OTTAWA

PLAN 4M- 1538

I CERTIFY THAT THIS PLAN IS REGISTERED IN THE LAND REGISTRY OFFICE FOR THE LAND TITLES DIVISION OF OTTAWA-CARLETON NO. 4 AT 11:38 O'CLOCK ON THE 13 DAY OF May 2015 AND ENTERED IN THE PARCEL REGISTER FOR PROPERTY IDENTIFIERS 04467-1324 & 04467-1547

AND THE REQUIRED CONSENTS ARE REGISTERED AS PLAN DOCUMENT NO. OC1856170

F. Larocque, representative for

LAND REGISTRAR

This plan comprises part of the land identified by PIN 04467-1324 and all of the land identified by PIN 04467-1547.

PIN 04467-1324: Part of Blocks 31, 37, 38 and part of promenade Nortel Drive.

PIN 04467-1547: Part of Blocks 31, 37, 38 and part of promenade Nortel Drive.
All of Blocks 1 to 30 (both inclusive) and all of Blocks 32, 33, 34, 35 and 36.
All of the Streets, namely, place Crossley Place, promenade Dealership Drive, rue Systemhouse Street, rue Philsar Street.

PLAN OF SUBDIVISION OF

PART OF LOTS 17, 18, 19 And 20 CONCESSION 4 (RIDEAU FRONT)

Geographic Township of Nepean

CITY OF OTTAWA

Surveyed by Annis , O'Sullivan , Vollebekk Ltd.

Scale 1 : 2000

0 10 20 30 40 80 Metres

Metric

DISTANCES AND COORDINATES SHOWN ON THIS PLAN ARE IN METRES AND CAN BE CONVERTED TO FEET BY DIVIDING BY 0.3048.

SURVEYOR'S CERTIFICATE

I CERTIFY THAT :

1. This survey and plan are correct and in accordance with the Surveys Act, the Surveyors Act and the Land Titles Act and the regulations made under them.
2. The Survey was completed on the 5th day of February, 2015.

March 27/2015 — Edward M. Lancaster, Ontario Land Surveyor

OWNER'S CERTIFICATE

THIS IS TO CERTIFY THAT :

1. Blocks 1 to 14, both inclusive, Blocks 16, 17, 18, 19, 30 and 34, the Streets, namely, place Crossley Place, promenade Dealership Drive, rue Systemhouse Street, rue Philsar Street and part of promenade Nortel Drive, the Street Widenings, namely, Blocks 22, 28, and 29 and the Reserves, namely, Blocks 15, 20, 21, 23, 24, 26, 27, 28, 32, 33, 35, 36 and part of Blocks 31, 37 and 38 have been laid out in accordance with our instructions.
2. The Streets and Street Widenings are dedicated as public highways.

Dated this 4 day of May 2015

David Kamboj — Assistant Secretary
Stranderd Road Inc.
I have the authority to bind the corporation

OWNER'S CERTIFICATE

THIS IS TO CERTIFY THAT :

1. The Street, namely, part of promenade Nortel Drive and the Reserves, namely, part of Blocks 31, 37 and 38, have been laid out in accordance with our instructions.
2. The Street is dedicated as public highway.

Dated the 4th day of March 2015 — McKenna, Daniel Joseph

Dated the 4 day of March 2015 — Kilpatrick, Thomas John

Dated the 4 day of March 2015 — Hyland-Mc Kenna, Mary Jane

Dated the 4 day of March 2015 — McKenna, Ann Elizabeth

Dated the 4th day of March 2015 — McKenna, Rosalie Margaret

Dated the 4th day of March 2015 — McKenna, Michael James

NOTES AND LEGEND

—O—	denotes	Survey Monument Planted.
■	-	Survey Monument Found
SIB	-	Standard Iron Bar.
SSIB	-	Short Standard Iron Bar.
CC	-	Cut Cross.
IB	-	Iron Bar.
CP	-	Concrete Pin
CLF	-	Chain Link Fence
BF	-	Board Fence
C/L	-	Centreline
(AOG)	-	Annis, O'Sullivan, Vollebekk Ltd.
(P1)	-	Plan 4R-25244
(P2)	-	Plan 4R-8857
(P3)	-	Plan 4R-10821
(P4)	-	Plan 4R-22422
(P5)	-	Plan 4R-16142
(P6)	-	Plan 5R-13502
(P7)	-	Plan 4R-8623
(P8)	-	Plan 4R-27905
(P9)	-	Plan 4R-28239
(P10)	-	Plan 4R-8966

All planted survey monuments are SSIB's unless otherwise noted.

Distances shown on curved limits are Arc distances unless otherwise noted.

Distances shown on this plan are ground distances and can be converted to grid distances by multiplying by the combined scale factor of 0.99992.

Bearings are grid bearings, derived from the southerly limit of Plan 4R-28239, shown to be N 59°20'00" E, thereon.

Coordinates are derived from Can-Net 3.0 Real Time Network GPS observations on monument A and B, shown hereon, and are referred to the Central Meridian of MTM Zone 9 (76°30' West Longitude) NAD-83 (original).

Coordinate values are to urban accuracy in accordance with O. Reg. 216/10.

. Point A Northing 5013643.93 Easting 361142.33
. Point B Northing 5013891.88 Easting 361560.49

Caution: Coordinates cannot, in themselves, be used to re-establish corners or boundaries shown on this plan.

ANNIS, O'SULLIVAN, VOLLEBEKK LTD.
14 Concourse Gate, Suite 500
Nepean, Ont. K2E 7S8
Phone: (613) 727-0850 / Fax: (613) 727-1079
Email: mail@aovltd.com
Ontario Land Surveyors Job No. 14655-14 Regional Pl Lts 17-20 C4 NF SUB 7

K:\REGIONAL GROUP\14655-14\PRAO\14655-14 Regional Pl Lts 17-20 C4 NF SUB 7.dwg, 4M-3604