

250 Besserer Street, Ste. 100 Ottawa, Ontario K1N 6B3 Tel: 613.237.2345

Fax: 613.237.6423 Email: info@nak-design.com

# **MEMORANDUM**

To: Jillian Normand, Mattamy Homes

From: Anne-Claude Schellenberg

Date: May 25, 2018

Subject: Street Tree Planting Assessment – Summerside West Phase 4 Project no: 17-188

This memo provides an assessment of the potential for street tree planting in the Summerside West Phase 4 community in terms of the geotechnical findings summarized in the Paterson Group Report PG4049-2 (May 14, 2018). Based on the Atterberg test results summarized in this report, a 4.5 m tree-to-foundation setback is recommended in areas with low-to-moderate plasticity clay soils, and a minimum 7.5m tree-to-foundation setback, for small trees only, is recommended in areas with high plasticity soils, in accordance with the City of Ottawa's *Tree Planting in Sensitive Marine Clay Soils – 2017 Guidelines*. Soil volume and local grading at the tree are also addressed in accordance with the 2017 Guideline document.

### Subdivision design criteria and assumptions

The site zoning permits a minimum front yard setback of 3.0m. The front yard setback shown on the ROW cross sections for this community is 3.25m for all conditions except the 18m-with-sidewalk, shown as 4.25m. Increased front yard setbacks of up to 1m are being contemplated to permit tree planting in high plasticity clay soil areas. The proposed minimum lot widths are 9.14m for singles and 6.5m for townhomes. Driveways should be paired where possible to permit canopy tree planting. Under the current zoning bylaw driveways may be installed up to 50% of the total lot width. These assumptions will be used to provide an assessment of tree planting in this community.

### Review of required tree-to-foundation distance

The tree-to-foundation setback, based on the Right-of-Way (ROW) cross-sections, is demonstrated below.


ROW Cross Section	Front Yard Setback per ROW Cross Section (m)	Tree-to- Foundation Distance (m)	Complies with Low-to-Mod. Plasticity, 4.5m distance	Complies with High Plasticity, min. 7.5m distance
14.75 m	3.25	5.75	yes	no
18.0 m – w. sidewalk	4.25	6.50	yes	no
18.0 m – w/o sidewalk	3.25	6.50	yes	no
24.0 m – w. sidewalk	3.25	7.25	yes	no
24.0 m – w/o sidewalk	3.25	7.25	yes	no

ROW Cross Section	Contemplated Increased Front Yard Setback (m)	Tree-to- Foundation Distance (m)	Complies with Low-to-Mod. Plasticity, 4.5m distance	Complies with High Plasticity, min. 7.5m distance
14.75 m	4.25	6.75	yes	no
18.0 m – w. sidewalk	5.25	7.50	yes	yes
18.0 m – w/o sidewalk	4.25	7.50	yes	yes
24.0 m – w. sidewalk	3.50	7.50	yes	yes
24.0 m – w/o sidewalk	3.50	7.50	yes	yes

In all cases, the front yard setbacks above comply with the City's required tree-to-foundation setback in low-to-moderate clay soil areas. Small (up to 7.5m) and medium (7.5 - 15m) trees will be able to be planted in these areas.

The contemplated front yard setbacks are required to meet the City's setback guidelines for high plasticity clay soil areas, however the 14.75m ROW does not permit tree planting under the current scenario. Only small trees will be able to be planted in high plasticity clay soil areas.

## Standard detail for surface drainage toward the tree root zone



### Review of available soil volume

The City requires the provision of 25m³ of available soil volume for small trees (up to 7.5m mature height) and 30m³ for medium-sized trees (7.5-15m mature height) in areas with clay soils. Available soil volume is "based on a depth of 1.5m below finished grade.... It may include lands in the right-of-way and on private property, but it must subtract the volume of the shallow utility trenches." The following table summarizes soil volume calculations, based on the minimum lot frontages, for both singles and towns with both paired and non-paired driveways.

SOIL V	OLUME C	SOIL VOLUME CALCULATION	NOI																		
						GROSS	GROSS SOIL VOLUME	UME					S	BTRACT:	ититу 1	SUBTRACT: UTILITY TRENCH VOLUMES	SEMULC				
	LOTINFO		Law	Lawn Width (m)	m)	Lawi	Lawn Length (I	h (m)	Gross Sc	Gross Soil Volume (m3)	; (m3)	Main	Main Line Service Trench*	ice Trenc	h*	Late	ral Servic	Lateral Service Trench*	*	NET	
ROW	Dwelling	Driveway	Min. Frontage	Max. Driveway Width	Lawn Width	Building to curb	Sidewalk + median	Lawn Length	Area	Soil Depth	Soil Volume	Lot Width (m)	Trench Width (m)	Trench Depth (m)	Trench Volume (m3)	Lot Length (m)	Trench Width (m)	Trench T Depth V (m)	Trench Volume (m3)	VOLUME (m3)	Soil Volume Supports
14.75m	Single		9.14	4.57	4.57	8.25	0.00	8.25	37.70	1.50	56.55	4.57	1.20	1.50	8.23	8.25	09.0	1.00	4.95	43.38	1 medium tree / lot
	Single	Unpaired	9.14	4.57	4.57	8.25	00.0	8.25	37.70	1.50	56.55	4.57	1.20	1.50	8.23	8.25	09.0	1.00	4.95	43.38	1 medium tree / lot
	Town	Paired	6.50	3.25	3.25	8.25	00.00	8.25	26.81	1.50	40.22	3.25	1.20	1.50	5.85	8.25	09:0	1.00	4.95	29.42	1 small tree / lot, or 1 medium tree / 2 lots
	Town	Unpaired	6.50	3.25	3.25	8.25	00.00	8.25	26.81	1.50	40.22	3.25	1.20	1.50	5.85	8.25	09:0	1.00	4.95	29.42	1 small tree / lot, or 1 medium tree / 2 lots
18.0m	Single	Paired	9.14	4.57	4.57	10.00	1.80	8.20	37.47	1.50	56.21	4.57	1.20	1.50	8.23	8.20	09.0	1.00	4.92	43.07	1 medium tree / lot
with	Single	Unpaired	9.14	4.57	4.57	10.00	1.80	8.20	37.47	1.50	56.21	4.57	1.20	1.50	8.23	8.20	0.60	1.00	4.92	43.07	1 medium tree / lot
sidewalk	Town	Paired	6.50	3.25	3.25	10.00	1.80	8.20	26.65	1.50	39.98	3.25	1.20	1.50	5.85	8.20	09:0	1.00	4.92	29.21	1 small tree / lot, or 1 medium tree / 2 lots
	Town	Unpaired	6.50	3.25	3.25	10.00	1.80	8.20	26.65	1.50	39.98	3.25	1.20	1.50	5.85	8.20	0.60	1.00	4.92	29.21	1 small tree / lot, or 1 medium tree / 2 lots
18.0m	Single	Paired	9.14	4.57	4.57	10.00	00.0	10.00	45.70	1.50	68.55	4.57	1.20	1.50	8.23	10.00	09.0	1.00	00.9	54.32	1 medium tree / lot
without	Single	Unpaired	9.14	4.57	4.57	10.00	00.0	10.00	45.70	1.50	68.55	4.57	1.20	1.50	8.23	10.00	09.0	1.00	00.9	54.32	1 medium tree / lot
sidewalk	Town	Paired	6.50	3.25	3.25	10.00	0.00	10.00	32.50	1.50	48.75	3.25	1.20	1.50	5.85	10.00	09.0	1.00	9.00	36.90	1 medium tree / lot
	Town	Unpaired	6.50	3.25	3.25	10.00	00.00	10.00	32.50	1.50	48.75	3.25	1.20	1.50	5.85	10.00	0.60	1.00	00.9	36.90	1 medium tree / lot
24.0m	Single	Paired	9.14	4.57	4.57	10.75	1.80	8.95	40.90	1.50	61.35	4.57	1.20	1.50	8.23	8.95	09.0	1.00	5.37	47.76	1 medium tree / lot
with	Single	Unpaired	9.14	4.57	4.57	10.75	1.80	8.95	40.90	1.50	61.35	4.57	1.20	1.50	8.23	8.95	0.60	1.00	5.37	47.76	1 medium tree / lot
sidewalk	Town	Paired	6.50	3.25	3.25	10.75	1.80	8.95	29.09	1.50	43.63	3.25	1.20	1.50	5.85	8.95	09.0	1.00	5.37	32.41	1 medium tree / lot
	Town	Unpaired	6.50	3.25	3.25	10.75	1.80	8.95	29.09	1.50	43.63	3.25	1.20	1.50	5.85	8.95	09.0	1.00	5.37	32.41	1 medium tree / lot
24.0m	Single	Paired	9.14	4.57	4.57	10.75	0.00	10.75	49.13	1.50	73.69	4.57	1.20	1.50	8.23	10.75	09.0	1.00	6.45	59.02	1 medium tree / lot
without	Single	Unpaired	9.14	4.57	4.57	10.75	0.00	10.75	49.13	1.50	73.69	4.57	1.20	1.50	8.23	10.75	09.0	1.00	6.45	59.02	1 medium tree / lot
sidewalk	Town	Paired	6.50	3.25	3.25	10.75	0.00	10.75	34.94	1.50	52.41	3.25	1.20	1.50	5.85	10.75	09.0	1.00	6.45	40.11	1 medium tree / lot
	Town	Unpaired	6.50	3.25	3.25	10.75	0.00	10.75	34.94	1.50	52.41	3.25	1.20	1.50	5.85	10.75	09.0	1.00	6.45	40.11	1 medium tree / lot
Notes																					
1. Trench	width and	1. Trench width and depth estimated by Civil Eng.	ated by Ci	vil Eng.																	
2. Buildin	g to curb di	2. Building to curb distance is based on the closest portion of the building foundation to the curb.	sed on the	closest p	ontion or	the build	ling found	lation to	the curb.												
3. A med	ium tree (ap	3. A medium tree (approx 7.5-15m mature height) requires 30m3 of continuous soil volume (City of Ottawa).	im mature	height) r	equires 3	Om3 of co	ntinuous	soil volu	me (City c	of Ottawa	<u>.</u>										
4. A smal	Il tree (appro	4. A small tree (approx 7.5m mature height) requires 25m3 of continuous soil	ture heigh:	t) require:	s 25m3 o	f continu	ous soil vo	Jume (Ci	volume (City of Ottawa)	wa).											
5. Refert	5. Refer to City of Ottawa "Tree Planting in Sensitive Marine Clay Soils – 2017 Guidelines" for other tree planting conditions.	ttawa "Tree	Planting ir	Sensitive	e Marine	Clay Soils	2017 G	uidelines	" for othe	r tree pla	Inting cor	ditions.									

### Conclusions

The contemplated design permits tree planting in both low-to-medium and high plasticity clay soil areas except for the 14.75m ROW in high plasticity clay soil areas. It is anticipated that the municipal requirements for street tree planting will be met in this community. The available soil volumes do not present any constraints to tree planting. It is recommended that driveways be paired where possible, to permit canopy tree planting.

I trust this is satisfactory, please don't hesitate to contact the undersigned should you require additional information.

Anne-Claude Schellenberg, OALA, CSLA

Associate

List of attachments:

 Summerside West Phases 4, 5 and 6: Geotechnical Overlay – Tree Planting Setback Recommendations

