Geotechnical Engineering

Environmental Engineering

Hydrogeology

Geological Engineering

Materials Testing

Building Science

Archaeological Services

patersongroup

Phase I-Environmental Site Assessment

760 River Road Ottawa, Ontario

Prepared For

Claridge Homes

Paterson Group Inc.

Consulting Engineers 154 Colonnade Road South Ottawa (Nepean), Ontario Canada K2E 7J5

Tel: (613) 226-7381 Fax: (613) 226-6344 www.patersongroup.ca October 22, 2018

Report: PE4467-1

TABLE OF CONTENTS

EXEC	CUTIVE SUMMARY	ii
1.0	INTRODUCTION	1
2.0	PHASE I PROPERTY INFORMATION	2
3.0	SCOPE OF INVESTIGATION	3
4.0	RECORDS REVIEW	4
	4.1 General	4
	4.2 Environmental Source Information	5
	4.3 Physical Setting Sources	7
5.0	INTERVIEWS	9
6.0	SITE RECONNAISSANCE	
	6.1 General Requirements	9
	6.2 Specific Observations at Phase I Property	9
7.0	REVIEW AND EVALUATION OF INFORMATION	11
	7.1 Land Use History	
	7.2 Conceptual Site Model	11
8.0	CONCLUSIONS	
9.0	STATEMENT OF LIMITATIONS	
10.0	REFERENCES	15

List of Figures

Figure 1 - Key Plan Figure 2 - Topographic Map Drawing PE4467-1 - Site Plan Drawing PE4467-2 - Surrounding Land Use Plan

List of Appendices

- Appendix 1 Survey Plan Aerial Photographs Site Photograph
- Appendix 2 MECP Freedom of Information Response TSSA Correspondence MECP Well Records HLUI Response
- Appendix 3 Qualifications of Assessors

EXECUTIVE SUMMARY

Assessment

Paterson Group was retained by Claridge Homes to conduct a Phase I-Environmental Site Assessment (ESA) of the property addressed 760 River Road, in the City of Ottawa, Ontario. The purpose of this Phase I-ESA was to research the past and current use of the subject site and Phase I study area and to identify any environmental concerns with the potential to have impacted the Phase I property.

According to the historical research, the subject site was occupied by a residential dwelling/farmstead prior to 1946 until 2016 and has since been vacant land. Neighbouring land use has been residential and agricultural. No potentially contaminating activities were identified with the historical use of the subject site or surrounding lands.

Following the historical research, a site visit was conducted. The site was observed to be undergoing the initial stages of site development with some grading taking place and the construction of a sales centre. At the time of the visit, neighbouring properties within the Phase I study area were observed from publicly accessible roadways. Potentially contaminating activities were not identified on the subject site or in the Phase I study area. Therefore, no areas of potential environmental concern with respect to the Phase I property were identified.

Conclusion

Based on the results of the assessment, in our opinion, a Phase II- Environmental Site Assessment is not required for the subject property.

1.0 INTRODUCTION

At the request of Claridge Homes, Paterson Group (Paterson) conducted a Phase I-Environmental Site Assessment (Phase I-ESA) of the property addressed 760 River Road, in the City of Ottawa, Ontario. The purpose of this Phase I-ESA was to research the past and current use of the site and study area and to identify any environmental concerns with the potential to have impacted the subject property.

Paterson was engaged to conduct this Phase I-ESA by Mr. Vincent Denomme with Claridge Homes. The head office is located at 210 Gladstone Avenue, Ottawa, Ontario. Mr. Denomme can be reached by telephone at (613) 233-6030.

This report has been prepared specifically and solely for the above noted project which is described herein. It contains all of our findings and results of the environmental conditions at this site.

This Phase I-ESA report has been prepared in general accordance with the requirements of Ontario Regulation (O.Reg.) 153/04 as amended under the Environmental Protection Act, and also complies with the requirements of CSA Z768-01. The conclusions presented herein are based on information gathered from a limited historical review and field inspection program. The findings of the Phase I-ESA are based on a review of readily available geological, historical and regulatory information and a cursory review made at the time of the field assessment. The historical research relies on information supplied by others, such as, local, provincial and federal agencies and was limited within the scope-of-work, time and budget of the project herein.

2.0 PHASE I PROPERTY INFORMATION

Address:	760 River Road, Ottawa, Ontario.			
Legal Description:	Part of Lots 22 and 23, Broken Front Concession Rideau Front, Township of Gloucester, in the City of Ottawa			
Property Identification				
Numbers:	04589-1857			
Location:	The site is located on the west side of River Road, 620 meters north of the intersection with Nicolls Island Road, in the City of Ottawa (formerly Gloucester), Ontario. Refer to Figure 1 - Key Plan in the Figures section following the text.			
Latitude and Longitude:	45° 15' 30.14" N, 75° 15' 30.14" W			
Site Description:				
Configuration:	Irregular.			
Zoning:	DR – Development Reserve Zone			
Current Use:	The subject site is currently undergoing preliminary grading for the proposed residential development.			
Services:	The subject site and adjacent lands are currently serviced by private wells and sewage systems.			

3.0 SCOPE OF INVESTIGATION

The scope of work for this Phase I – Environmental Site Assessment was as follows:

- Determine the historical activities on the subject site and study area by conducting a review of readily available records, reports, photographs, plans, mapping, databases, and regulatory agencies;
- Investigate the existing conditions present at the subject site and study area by conducting site reconnaissance;
- □ Conduct interviews with persons knowledgeable of current and historic operations on the subject property, and if warranted, neighbouring properties;
- Present the results of our findings in a comprehensive report in general accordance with the requirements of O.Reg. 269/11 amending O.Reg. 153/04 made under the Environmental Protection Act and in compliance with the requirements of CSA Z768-01;
- Provide a preliminary environmental site evaluation based on our findings;
- □ Provide preliminary remediation recommendations and further investigative work if contamination is suspected or encountered.

4.0 RECORDS REVIEW

4.1 General

Phase I-ESA Study Area Determination

A radius of approximately 250 m was determined to be appropriate as a Phase I study area for this assignment. Properties outside the 250 m radius are not considered to have impacted the subject land, based on their significant distance from the site.

First Developed Use Determination

An aerial photograph from 1946 indicated that the subject site was occupied by a farmstead. It is unknown when the subject site was first developed, but it was first used for agricultural /residential purposes.

Fire Insurance Plans

Fire Insurance Plans (FIPs) are not available for the subject area.

City of Ottawa Street Directories

City directories are not available for the area of the subject site.

Chain of Title

Paterson did not request a Chain of Title for the subject site as it was determined that sufficient information was gathered from other sources, such as personal interviews, aerials photographs and previous engineering reports.

Environmental Reports

Paterson Group has conducted an environmental and geotechnical investigations in the immediate vicinity of the subject site. Based on a review of our files, no potential environmental concerns were identified on the subject site or neighbouring lands.

Plan of Survey

A draft plan of subdivision prepared by Annis, O'Sullivan, Vollebekk Ltd. was reviewed as part of this assessment. The plan depicts the Phase I property in its current configuration as well as part of the proposed residential. A copy of the survey plan is included in Appendix 1.

4.2 Environmental Source Information

Environment Canada

A search of the National Pollutant Release Inventory (NPRI) was conducted electronically on October 18, 2018. The subject site and adjacent properties were not listed in the NPRI database. No records of pollutant release were listed in the database for properties located within the Phase I study area.

PCB Inventory

A search of national PCB waste storage sites was conducted. No PCB waste storage sites are located within the Phase I study area.

Ministry of the Environment, Conservation and Parks (MECP) Instruments

A request was submitted to the MECP Freedom of Information (FOI) office for information with respect to certificates of approval, permits to take water, certificates of property use or any other similar MECP issued instruments for the site. At the time of issuing this report, a response had not been received from the MECP. A copy of the response will be forwarded to the client if it contains any pertinent information.

MECP Incident Reports

A request was submitted to the MECP FOI office for information with respect to records concerning environmental incidents, orders, offences, spills, discharges of contaminants or inspections maintained by the MECP for the site or adjacent properties. At the time of issuing this report, a response had not been received from the MECP. A copy of the response will be forwarded to the client if it contains any pertinent information.

MECP Waste Management Records

A request was submitted to the MECP FOI office for information with respect to waste management records. At the time of issuing this report, a response had not been received from the MECP. A copy of the response will be forwarded to the client if it contains any pertinent information.

MECP Coal Gasification Plant Inventory

The Ontario Ministry of Environment document titled "Municipal Coal Gasification Plant Site Inventory, 1991" was reviewed to reference the locations of former plants with respect to the site. No Municipal Coal Gasification Plant Sites are located within the Phase I study area.

MECP Submissions

A request was submitted to the MECP FOI office for information with respect to reports related to environmental conditions for the property. At the time of issuing this report, a response had not been received from the MECP. A copy of the response will be forwarded to the client if it contains any pertinent information.

MECP Brownfields Environmental Site Registry

A search of the MECP Brownfields Environmental Site Registry was conducted as part of this assessment for the site, neighbouring properties and the general area of the site. No Records of Site Condition (RSCs) were filed for the subject property or properties within the Phase I ESA study area.

MECP Waste Disposal Site Inventory

The Ontario Ministry of Environment document titled "Waste Disposal Site Inventory in Ontario, 1991" was reviewed as part of the historical research. This document includes all recorded active and closed waste disposal sites, industrial manufactured gas plants and coal tar distillation plants in the Province of Ontario. There are no former waste disposal sites located within 1 km of the Phase I study area.

Areas of Natural Significance

A search for areas of natural significance and features within the Phase I study area was conducted on the website of the Ontario Ministry of Natural Resources (MNR) on October 18, 2018. The search did not reveal areas of natural significance within the Phase I study area.

Technical Standards and Safety Authority (TSSA)

The TSSA, Fuels Safety Branch in Toronto was contacted electronically on October 18, 2018, to inquire about current and former underground storage tanks, spills and incidents for the site and neighbouring properties. No records are listed in the TSSA registry for the subject site or the adjacent properties. A copy of the TSSA correspondence is included in Appendix 2.

City of Ottawa Landfill Document

The document entitled "Old Landfill Management Strategy, Phase I – Identification of Sites, City of Ottawa", was reviewed. There are no closed landfill sites within the vicinity of the Phase I study area.

City of Ottawa Historical Land Use Inventory (HLUI)

A search of the City of Ottawa's Historical Land Use Inventory (HLUI) database was conducted as part of this assessment. At the time of issuance of this report, the HLUI search results had not been received. A copy of the HLUI request form is provided in Appendix 2.

4.3 Physical Setting Sources

Aerial Photographs

Historical air photos from the National Air Photo Library were reviewed in approximate ten (10) year intervals. Based on the review, the following observations have been made:

- 1946 The subject site appears to be occupied by a couple of large barnlike structures, a private garage and residential dwelling. The majority of the subject land is agricultural fields. The surrounding lands appear as vacant agricultural land with occasional residential dwellings. The Rideau River is present to the west and River Road is present to the east.
- 1956 No significant changes are apparent on the subject site or adjacent properties.
- 1968 No significant changes are apparent to the subject site. The adjacent property to the north appears to be occupied by a farmstead as well. No significant changes have been made to the surrounding lands.
- 1976 No apparent changes have been made to the subject site or surrounding area.
- 1991 No significant changes are apparent to the subject site or surrounding area, with the exception of more tree coverage on the subject property.

- 2002 No significant changes have been made to the subject site or surrounding properties. Residential development is beginning to occur further to the north.
- All of the previous structures on the subject site have been demolished and no longer exist at this time. The subject site and adjacent properties to the north, east, and south appear as vacant lands. The surrounding lands appear unchanged from the previous photograph, with the exception of further to the north, where there has been an increase in residential development.

Laser copies of selected aerial photographs reviewed are included in Appendix 1.

Topographic Maps

Topographic maps were obtained from Natural Resources Canada – The Atlas of Canada website and from the City of Ottawa website. The topographic maps indicate that the regional topography in the general area of the site slopes significantly down to the west in the direction of the Rideau River. The Rideau River is located to the immediate west of the subject site. A couple of its tributaries are located on the south and east portions of the subject site. An illustration of the referenced topographic map is presented on Figure 2 – Topographic Map, appended to this report.

Physiographic Maps

The Ontario Geological Survey publication 'The Physiography of Southern Ontario, Third Edition' was reviewed as a part of this assessment. According to the publication, the site is situated within the Ottawa Clay Plain physiographic region.

Geological Maps

The Geological Survey of Canada website on the Urban Geology of the National Capital Area was consulted as part of this assessment. Based on this information, bedrock in the southern area of the site consists of dolomite of the Oxford Formation, while the northern area consists of sandstone and dolomite of the March Formation. The site is located in an area where both offshore marine sediments and marine sediments of clay and silt are present, respectively, beneath the western and eastern areas of the subject site. The drift thickness in the area ranges from 10 to 25 m.

Water Well Records

A Well Record search was conducted on October 18, 2018 for all drilled wells within 250 m of the subject site. The well record search returned thirteen (13) domestic well records, six (6) of which were located on-site, while three (3) were identified north and four (4) identified south of the subject site. No potential environmental concern has been identified with respect to the subject site. A copy of the well records has been included in Appendix 2.

Water Bodies and Areas of Natural Significance

A couple of small tributaries exist on the subject site and flow southwest and west in the direction of the Rideau River, which is located immediately west of the site. No areas of natural significance are known to exist in the Phase I study area.

5.0 INTERVIEWS

Property Owner Representative

Mr. Vincent Denomme with Claridge Homes was interviewed via email as part of this assessment. Claridge Homes purchased the subject property in 2013 and demolished the residential home and associated buildings located on the northeast corner of the property in 2016. The subject site has since been vacant. Mr. Denomme is not aware of any potential environmental concerns with respect to the subject or adjacent properties.

6.0 SITE RECONNAISSANCE

6.1 General Requirements

The site visit was conducted on October 18, 2018. Weather conditions were sunny and windy with a temperature of approximately 4°C. Ms. Mandy Witteman from the Environmental Department of Paterson conducted the site assessment. In addition to the site, the uses of neighbouring properties within the Phase I study area were also assessed at the time of the site visit.

6.2 Specific Observations at Phase I Property

Buildings and Structures

There is one structure currently under construction on the southeast corner of the subject site; a sales centre for the future residential development. No

aboveground storage tanks (ASTs) or evidence of underground storage tanks (USTs) or other chemical storage were observed at the subject site.

Site Features

The site is vacant and in the initial grading stages for the proposed residential development. The site is covered by soil and some gravel along the eastern edge of the property, while the majority of the remaining land along the western and northern edges is grass, brush and tree covered.

The site topography is relatively at grade with River Road, and slopes down towards the west. The regional topography slopes down towards the west as well, in the direction of the Rideau River. Site drainage consists primarily of infiltration.

No underground structures, drains, or private sewage systems were observed or suspected at the subject land at the time of the site visit. No evidence of current or former railway or spur lines on the subject property was observed at the time of the site visit. No areas of stained soil or unidentified substances were observed on-site at this time.

Fill Material

Evidence of some fill placement was observed on-site. The fill consisted of native soil that most likely originated from the subject site. Some gravel was also observed on site to create an access lane. The fill was not considered to be deleterious and does not pose an environmental issue.

Neighbouring Properties

An inspection of the neighbouring properties was conducted from publicly accessible roadways at the time of the site inspection. Land use adjacent to the subject site was as follows:

- □ North Vacant land, followed by Residential dwellings;
- □ South Residential dwellings and vacant land;
- □ East River Road, followed by vacant, undeveloped land;
- U West The Rideau River, followed by Beryl Gaffney Park.

The current use of the immediately adjacent properties is not considered to pose an environmental concern to the subject site. No properties within the Phase I study area are occupied by potentially contaminating activities. Current land use in the Phase I Study area is illustrated on Drawing PE4467-2 – Surrounding Land Use Plan in the Figures section of this report.

7.0 REVIEW AND EVALUATION OF INFORMATION

7.1 Land Use History

The following table indicates the current and past uses of the site as well as associated potentially contaminating activities dating back to the first developed use of the site.

Table 1 - Land Use History – 760 River Road				
Time Period Land Use		Potentially Contaminating Activities (PCAs)	Areas of Potential Environmental Concern (APECs)	
1946 – 2016	Farmstead/residential	None	None	
2016 - present Vacant land		None	None	

Potentially Contaminating Activities and Areas of Potential Environmental Concern

No potentially contaminating activities (PCAs) were identified at the Phase I property or within the Phase I study area. Therefore, no Areas of Potential Environmental Concern (APECs) were identified on the subject site.

Contaminants of Potential Concern

No Contaminants of Potential Concern (CPCs) were identified on the subject site.

7.2 Conceptual Site Model

Geological and Hydrogeological Setting

Based on information from the Geological Survey of Canada, drift thickness in the area of the subject site is estimated to be on the order of 10 to 15 m on the southern edge and up to 25 m on the northern edge of the subject site. The overburden on the eastern part is comprised of offshore marine deposits of clay and silt and offshore marine sediments of erosional terraces on the western part of the subject site. Bedrock in the area is comprised of dolomite, and dolomite

with some sandstone of the Oxford Formation and March Formation, respectively.

Fill Material

Based on the site inspection, some fill material was observed to have been placed along the eastern edge of the property. The fill material consisted of some gravel as well as native reworked soil, consistent with typical construction sites. The fill material is not considered to pose a risk to the Phase I property.

Contaminants of Potential Concern

As per Section 7.1 of this report, no Contaminants of Potential Concern (CPCs) were identified on the subject site.

Existing Buildings and Structures

The subject site is currently an active construction site with one partially completed structure (sales centre).

Water Bodies and Areas of Natural Significance

A small tributary on the subject site flows west into the Rideau River. No areas of natural significance were identified on the site or in the Phase I study area.

Drinking Water Wells

Six (6) potable water wells were located on the subject site. All wells on-site were drilled to fresh water at depths ranging from 13 to 30.5 m. No potential environmental concern has been identified with respect to the Phase I property.

Neighbouring Land Use

Neighbouring land use in the Phase I study area consists of vacant, undeveloped land and/or residential dwellings.

Potentially Contaminating Activities and Areas of Potential Environmental Concern

As per Section 7.1 of this report, PCAs were not identified on the subject property or within the Phase I study area. Therefore, no APECs are present on the Phase I property.

Assessment of Uncertainty and/or Absence of Information

The information available for review as part of the preparation of this Phase I-ESA is considered to be sufficient to conclude that there are no APECs on the subject site. A variety of independent sources were consulted as part of this assessment, and as such, the conclusions of this report are not affected by uncertainty which may be present with respect to the individual sources.

8.0 CONCLUSIONS

Assessment

Paterson Group was retained by Claridge Homes to conduct a Phase I-Environmental Site Assessment (ESA) of the property addressed 760 River Road, in the City of Ottawa, Ontario. The purpose of this Phase I-ESA was to research the past and current use of the subject site and Phase I study area and to identify any environmental concerns with the potential to have impacted the Phase I property.

According to the historical research, the subject site was occupied by a residential dwelling/farmstead prior to 1946 until 2016 and has since been vacant land. Neighbouring land use has been residential and agricultural. No potentially contaminating activities were identified with the historical use of the subject site or surrounding lands.

Following the historical research, a site visit was conducted. The site was observed to be undergoing the initial stages of site development with some grading taking place and the construction of a sales centre. At the time of the visit, neighbouring properties within the Phase I study area were observed from publicly accessible roadways. Potentially contaminating activities were not identified on the subject site or in the Phase I study area. Therefore, no areas of potential environmental concern with respect to the Phase I property were identified.

Based on the results of the assessment, in our opinion, a Phase II-Environmental Site Assessment is not required for the subject property.

9.0 STATEMENT OF LIMITATIONS

This Phase I - Environmental Site Assessment report has been prepared in general accordance with O.Reg. 153/04 as amended and meets the requirements of CSA Z768-01. The conclusions presented herein are based on information gathered from a limited historical review and field inspection program. The findings of the Phase I - ESA are based on a review of readily available geological, historical and regulatory information and a cursory review made at the time of the field assessment. The historical research relies on information supplied by others, such as, local, provincial and federal agencies and was limited within the scope-of-work, time and budget of the project herein.

Should any conditions be encountered at the subject site and/or historical information that differ from our findings, we request that we be notified immediately in order to allow for a reassessment.

This report was prepared for the sole use of Claridge Homes. Permission and notification from Claridge Homes and Paterson will be required to release this report to any other party.

Paterson Group Inc.

Mandy Witteman, M.A.Sc.



Mark S. D'Arcy, P.Eng.

Report Distribution:

- Claridge Homes
- Paterson Group



10.0 REFERENCES

Federal Records

Air photos at the Energy Mines and Resources Air Photo Library. National Archives. Maps and photographs (Geological Survey of Canada surficial and subsurface mapping). Natural Resources Canada – The Atlas of Canada. Environment Canada, National Pollutant Release Inventory. PCB Waste Storage Site Inventory.

Provincial Records

MECP Freedom of Information and Privacy Office.
MECP Municipal Coal Gasification Plant Site Inventory, 1991.
MECP document titled "Waste Disposal Site Inventory in Ontario".
MECP Brownfields Environmental Site Registry.
Office of Technical Standards and Safety Authority, Fuels Safety Branch.
MNR Areas of Natural Significance.
MECP Water Well Record Inventory.
Chapman, L.J., and Putnam, D.F., 1984: 'The Physiography of Southern

Ontario, Third Edition', Ontario Geological Survey Special Volume 2.

Municipal Records

City of Ottawa Document "Old Landfill Management Strategy, Phase I -Identification of Sites.", prepared by Golder Associates, 2004. Intera Technologies Limited Report "Mapping and Assessment of Former Industrial Sites, City of Ottawa", 1988.

geoOttawa: City of Ottawa electronic mapping website.

City of Ottawa Historical Land Use Inventory (HLUI) Database

Local Information Sources

Personal Interviews.

Public Information Sources

Google Earth. Google Maps/Street View.

FIGURES

FIGURE 1 – KEY PLAN

FIGURE 2 – TOPOGRAPHIC MAP

DRAWING PE4467-1 – SITE PLAN

DRAWING PE4467-2 – SURROUNDING LAND USE PLAN




FIGURE 1 KEY PLAN





FIGURE 2 TOPOGRAPHIC MAP



\autocad drawings\environmenta\\pe44xx\pe4467\pe4467-1 site plan.d

	I O O O O O O O O O O O O O O O O O O O		SITE #760 RIVER ROAD VACANT LAND	VACANT VACANT VACANT VACANT VACANT VACANT VACANT
patersongroup consulting engineers 154 Colonnade Road South Ottawa, Ontario K2E 7J5		OTTA Title:	VACAN WA,	CLARIGE HOMES IRONMENTAL SITE ASSESSMENT IT LAND - 760 RIVER ROAD
Tel: (613) 226-7381 Fax: (613) 226-6344	0 NO. REVISIONS	DATE INITIAL	JUKKUUN	DING LAND USE PLAN

PHASE I ENVIRONMENTAL SITE ASSESSMENT STUDY AREA

	Scale:		Date:
		1:6000	10/2018
	Drawn by:		Report No.:
		MPG	PE4467-1
ONTARIO	Checked by:		Dwg. No.:
		MW	PE4467-2
	Approved by:		FE4407-2
		MSD	Revision No.: 0


. autocad drawings/environmental/pe44xx/pe4467/pe4467-2 slup.dw


APPENDIX 1


SURVEY PLAN


AERIAL PHOTOGRAPHS


SITE PHOTOGRAPHS

















Site Photographs

PE4467

760 River Road, Ottawa, ON

October 26, 2018



Photograph 1: View of the southeast end of the subject property, looking onto a future sales office.



Photograph 2: View of the central portion of the subject site, taken from River Road.

Site Photographs

PE4467

760 River Road, Ottawa, ON


October 26, 2018



Photograph 3: View of the northeast side of the subject site, along River Road, looking north.




Photograph 4: View of the central portion of the subject site, looking west.



SUBJECT TO THE CONDITIONS, IF ANY, SET FORTH IN OUR LETTER DATED

THIS DRAFT PLAN IS APPROVED BY THE CITY OF OTTAWA UNDER SECTION 51 OF THE PLANNING ACT. THIS _ _ _ DAY OF _ _ _ _ , 20__.

DON HERWEYER, MCIP RPP, MANAGER DEVELOPMENT REVIEW-SOUTH PLANNING, INFRASTRUCTURE AND ECONOMIC DEVELOPMENT DEPARTMENT, CITY OF OTTAWA



DRAFT PLAN OF SUBDIVISION OF PART OF LOTS 22 And 23 BROKEN FRONT CONCESSION RIDEAU FRONT Geographic Township of Gloucester CITY OF OTTAWA

Prepared by Annis, O'Sullivan, Vollebekk Ltd.

Scale 1:1000

40 30 20 10 0 20 40 Metre

DISTANCES SHOWN ON THIS PLAN ARE IN METRES AND CAN BE CONVERTED TO FEET BY DIVIDING BY 0.3048

SURVEYOR'S CERTIFICATE

I CERTIFY THAT: The boundaries of the lands to be subdivided and their relationship to adjoining lands have been accurately and correctly shown.

Date

Andre Roy ONTARIO LAND SURVEYOR

OWNER'S CERTIFICATE

This is to certify that we are the owners of the lands to be subdivided and that this plan was prepared in accordance with our instructions.

Date

Jim Burghout Authorized Signing Officer Claridge Homes Corporation I have the authority to bind the corporation.

ADDITIONAL INFORMATION REQUIRED UNDER SECTION 51-17 OF THE PLANNING ACT

- (a) see plan (b) see plan
- (c) see plan
- (d) single family residential housing and storm water
- management lands
- (e) see plan(f) see plan
- (g) see plan
- (h) City of Ottawa
- (i) see soils report
- (j) see plan(k) sanitary, storm sewers, municipal water, bell, hydro, cable and
- gas to be available
- (l) see plan



ANNIS, O'SULLIVAN, VOLLEBEKK LTD. 14 Concourse Gate, Suite 500 Nepean, Ont. K2E 7S6 Phone: (613) 727-0850 / Fax: (613) 727-1079

 Email: Nepean@aovltd.com

 Job No. 18590-17 Claridge Pt Lts 22 23 BF GL DPS D2
 N

APPENDIX 2

MECP FREEDOM OF INFORMATION

TSSA CORRESPONDENCE

MECP WELL RECORDS

HLUI RESPONSE

Ministry of the Environment, Conservation and Parks

Freedom of Information and Protection of Privacy Office

12th Floor 40 St. Clair Avenue West Toronto ON M4V 1M2 Tel: (416) 314-4075 Ministère de l'Environnement, de la Protection de la nature et des Parcs

Bureau de l'accès à l'information et de la protection de la vie privée



12^e étage 40, avenue St. Clair ouest Toronto ON M4V 1M2 Tél. : (416) 314-4075

October 29, 2018

Mandy Witteman Paterson Group Inc. 154 Colonnade Road Ottawa, ON K2E 7J5

Dear Mandy Witteman:

RE: Freedom of Information and Protection of Privacy Act Request Our File # A-2018-06989, Your Reference PE4467

This letter is in response to your request made pursuant to the *Freedom of Information and Protection of Privacy Act* relating to 760 River Road, Ottawa.

After a thorough search through the files of the Ministry's Ottawa District Office, Investigations and Enforcement Branch, Environmental Assessment and Permissions Branch, Environmental Monitoring and Reporting Branch, Sector Compliance Branch and Safe Drinking Water Branch, no records were located responsive to your request. To provide you with this response and in accordance with Section 57 of the *Freedom of Information and Protection of Privacy Act*, the fee owed is \$30.00 for 1 hour of search time @ \$30.00 per hour. We have applied the \$30.00 for this request from your initial payment. This file is now closed.

You may request a review of my decision by contacting the Information and Privacy Commissioner/Ontario, 2 Bloor Street East, Suite 1400, Toronto, ON M4W 1A8 (800-387-0073 or 416-326-3333). Please note that there is a \$25.00 fee and you only have 30 days from receipt of this letter to request a review.

If you have any questions regarding this matter, please contact Rebeka Bogdan at the **Freedom of Information Office at 416-314-4075**.

Yours truly,

FOR

Janet Dadufalza FOI Manager

Mandy Witteman

From:	Public Information Services < publicinformationservices@tssa.org>
Sent:	October-18-18 5:12 PM
То:	Mandy Witteman
Subject:	RE: Search records request (PE4467)

Hello Mandy,

Thank you for your request for confirmation of public information.

We confirm that there are no records in our database of any fuel storage tanks at the subject addresses.

For a further search in our archives please complete our release of public information form found at <u>https://www.tssa.org/en/about-tssa/release-of-public-information.aspx? mid =392</u> and email the completed form to <u>publicinformationservices@tssa.org</u> or through mail along with a fee of \$56.50 (including HST) per location. The fee is payable with credit card (Visa or MasterCard) or with a Cheque made payable to TSSA.

Although TSSA believes the information provided pursuant to your request is accurate, please note that TSSA does not warrant this information in any way whatsoever.

Kind regards,

Yalini



Yalini Kanagendran | Public Information Agent Facilities 345 Carlingview Drive Toronto, Ontario M9W 6N9 Tel: +1-416-734-3449 | Fax: +1-416-231-6183 | E-Mail: <u>publicinformationservices@tssa.org</u> www.tssa.org

From: Mandy Witteman <MWitteman@Patersongroup.ca> Sent: October 18, 2018 1:25 PM To: Public Information Services <publicinformationservices@tssa.org> Subject: Search records request (PE4467)

Good Afternoon,

Could you please complete a search of your records for **underground/aboveground storage tanks**, historical spills or **other incidents/infractions** for the following addresses in Ottawa, ON:

River Road: 760, 782, 788, 792, 798, 879, 750, 746 Spratt Rd: 4650 Nicolls Island Rd: 415,

Thank you

Well ID

Well ID Number: 1509609 Well Audit Number: Well Tag Number:

This table contains information from the original well record and any subsequent updates.

Well Location

Address of Well Location	
Township	GLOUCESTER TOWNSHIP
Lot	022
Concession	BF
County/District/Municipality	OTTAWA-CARLETON
City/Town/Village	
Province	ON
Postal Code	n/a
UTM Coordinates	NAD83 — Zone 18 Easting: 444750.70 Northing: 5011772.00
Municipal Plan and Sublot Number	
Other	

Overburden and Bedrock Materials Interval

General Colour	Most Common Material	Other Materials	General Description	Depth From	Depth To
GREY	CLAY	BLDR		0 ft	40 ft
	SNDS			40 ft	57 ft

Annular Space/Abandonment Sealing Record

Depth	Depth	Type of Sealant Used	Volume
From	То	(Material and Type)	Placed

Method of Construction & Well Use

Method of Construction Well Use Cable Tool

Domestic

Status of Well

Water Supply

Construction Record - Casing

Inside Diameter	Open Hole or material	Depth From	Depth To
5 inch	STEEL		40 ft
2 inch	STEEL		50 ft

2 inch

Construction Record - Screen

OPEN HOLE

Outside Diameter Material Depth Depth From To

Well Contractor and Well Technician Information

Well Contractor's Licence Number: 1301

Results of Well Yield Testing

After test of well yield, water was	CLEAR
If pumping discontinued, give reason	
Pump intake set at	
Pumping Rate	10 GPM
Duration of Pumping	1 h:0 m
Final water level	8 ft
If flowing give rate	
Recommended pump depth	25 ft
Recommended pump rate	10 GPM
Well Production	PUMP
Disinfected?	

Draw Down & Recovery

Draw Down Time(min)	Draw Down Water level	Recovery Time(min)	Recovery Water level
SWL	6 ft		
1		1	
2		2	
3		3	
4		4	
5		5	
10		10	
15		15	
20		20	
25		25	
30		30	
40		40	
45		45	
50		50	
60		60	

Water Found at Depth	Kind
55 ft	Fresh

	31G/5b.		\V\		
UTM 118 Z 441504			Mea	ghers N	1º X6
5 R 501214	0 N				
Elev. $ \underline{4} ^{R}$ $ \underline{0} \underline{2} \underline{9} $		_	-	GROUND W	ATER BRANCH
Basin 12/31 Front			rillers Act, 1954 t of Mines		1 4 1957
Lor id	Vater	-We	ell Recor	d ONTAR RESOURCES	IO WATER COMMISSION
County or Territorial District	Parleton	Tow	nship, Village, Town or	City Sou	eeder
			n Village, Town or C	Sity)	•••••
			Address	wolldfred	
(day)	(month)	(year)			
Pipe and Casing	Record			Pumping Test	
Casing diameter(s)			Static level		
Length(s)			Pumping rate	O.J.P.Z	,
Length of screen			Duration of test		
Well Log				Water Record	
Overburden and Bedrock Record	From ft.	To ft.	Depth(s) at which water(s) found	No. of feet water rises	Kind of water (fresh, salty, or sulphur)
	<u><u></u></u>	46	-		
				-	
- Une stone LAFY	46'	3-1-	5.15	415'	Treal
				-	
					//_
For what purpose(s) is the water			Lo	cation of Well	(*
Is water clear or cloudy?	~	1	-	show distances of	
Is well on upland, in valley, or on	hillside?	1	road and lot line	e. Indicate north N	by arrow.
Drilling firm	ey		\sim	301	A ser instruct
Address	woodl	Tree	V		10 7 22
Cl.	Tues		B.F		6°
Name of Driller	a fall in the second			N.	
Address	•••••••••••••••••••••••••••••••••••••••			NA V.	queester
Licence Number.			×	12.2	la concentration an
I certify that the statements of fact				$\gamma \gamma$	
				V	
Date Jally & Van Jak	nature of License	e	\times	Bdy O	gy flor
			/		()
Form 5			1		

9

Form 5

	316/56.				
UTM 118 2 4141510151	<u>د</u>			GROUND WAT 15 N AUG 1	0 32/
5R 50112110	<i>⊙</i> N	ONT	ARIO A		
BKY. A A R BY 24912	The Wat	er-well Dı	rillers Act, 1954	ONTARIO RESOURCES	
Basin 2732	D	epartment	of Mines		
V	Vater-	We	ll Record	b	
0V					7
County or Territorial District	Carlelon	Towr	nship, Village, Town or C	Sity	ueuster
			n Village, Town or Ci Address	ty)	
(day)	(month)	(year)			
Pipe and Casing	Record			Pumping Test	
Casing diameter(s)			Static level		·····
Length(s)	1 <i>1 K</i>		Pumping rate		
			Pumping level		
Length of screen	•••••••		Duration of test	~~~.	·····
Well Log				Water Record	
Overburden and Bedrock Record	From ft.	To ft.	Depth (s) at which water (s) found	No. of feet water rises	Kind of water (fresh, salty, or sulphur)
- Clay		416'			
Line son EREY	46.	3.10	51-	40'	heel
					¥
	·	·			
	- <u></u>				
·					
					_
			**]	
For what purpose(s) is the water	to be used?	I	Te	ation of Well	<i>N</i> ₁ .
the and		••••••	In diagram below		f well from
Is water clear or cloudy?			road and lot line		by arrow,
Is well on upland, in valley, or on				<u>N/</u>	It
Drilling firm VII C	a chen	•••••	/	**	, A ²⁰⁰
Address		Ree		N.	ATHLOTLINE
	lawa	••••••	BF	72	•
Name of Driller			192	N	2822
Address	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~				್ರಜ್ಞಾ ನಿರ್ದೇಶ ಕ್ಷೇತೆ ಕಾರ್ ಕರಿಂ ಕ್ಷೇವಿಷ್ಟು ನಿರ್ದೇಶ ಕ್ಷೇತೆ
Licence Number	•		Y	1.2.50	
I certify that the				2 200	
statements of fact			14		
Date July 18 70 3	machin		11 F		
Si	gnature of License			Bity 249	Junio de Co
				6 6	
Form 5					

5

10+23 (04/	ان N The Wa I	Townsh	ers Act, 1954 Mines I Recor ip, Village, Town or	City_ Glorie	1957 Narea Lanseron
		,	Village, Town or C ddress	ng Bridge	<u>2</u>
(day) Pipe and Casing	(month)	(year)	<u> </u>	Pumping Test	
Casing diameter(s)	<u>{</u> †	P	tatic level Pumping rate Pumping level Duration of test	23 ft 300 M-A 30 ft	H
Well Log				Water Record	
Overburden and Bedrock Record	From ft.	To ft.	Depth (s) at which water (s) found	No. of feet water rises	Kind of water (fresh, salty, or sulphur)
Hand elay	D	80	100	77	sulphur
Sand stone	80	100			_
Address	Hour Clear hillside? Hellsid sette Ling h iew nette	te te	In diagram below	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	
Form 5		Maple	++		

A Q E. RISU		-		
JTM 1/18-1444720 4422	1150	9609-1	AND RESOURCES	B
14 ISP /1/IST STOCODED			orvient.	
Hev. St. 01216101 The Ontario Water Reso		The second se	UG 2 7 1968	1
Sain 2011 WATER WEL	L REC	DRD	ONTA GO WATER	
County or District Carloten		1	CLORES COMMISSION	transfer tran
Con B.F. R.F. Lot 24 22 D	ate completed	20 Angr	nst 1968	year)
	ress 64 Delaw		ottawa, ont.	
		Pumpin	a Test	·····
Casing and Screen RecordInside diameter of casing40 * of 5* & 10 * of 2*	Static level		/	
	Test-numping r	ate	10	G.P.M.
Total length of casing	Pumping level	5	7	
Type of screen nil			1 Hour	
Length of screen	Water clear or cl	oudy at end of	f test clear	
Depth to top of screen n/a	Recommended	oumping rate	10-	G.P.M.
Diameter of finished hole			25 feet belo	
Well Log				Record
Overburden and Bedrock Record	From ft.	To ft.	Depth(s) at which water(s) found	Kind of water (fresh, salty, sulphur)
1-pey Chay - Boulders.	C	40		
GREY CLAY - Boulders. SANDSTONE	40	57	55 AT.	FRESH
JANDSTENE	70			
For what purpose(s) is the water to be used?		Location	of Well	1
Winterised cottage	In di a gra	um below show	a distances of we	11 from
Is well on upland, in valley, or on hillside? valley	road and	l lot line. It	dicate toth by	arrow.
Drilling or Boring Firm		ŝ		\backslash
Bleir Fhillips Drilling Co. Ltd.,		i h	A. T	\setminus
Address 1119 Falaise Rd.,		1		$\backslash $
Ottawa 5, Ontario.		1-		
Licence Number 2779			S mini	
Name of Driller or Borer Ron. Phillips		/ 23		4
Address 1440 Mayvies Apt. #207 Sttawa, Ont.	A T	`פֿ /	1 705	
Date 20 Ingust 1968			13	
PIL A. Muss		50	74	
(Signiture of Licensed Drilling or Poring Contractor)	NORTH	30		
Form 7 15M-60-4138		i	فتر ب	A
OWRC COPY				<u>.</u>

Well ID

Well ID Number: 1500334 Well Audit Number: Well Tag Number:

This table contains information from the original well record and any subsequent updates.

Well Location

Address of Well Location	
Township	GLOUCESTER TOWNSHIP
Lot	023
Concession	BF
County/District/Municipality	OTTAWA-CARLETON
City/Town/Village	
Province	ON
Postal Code	n/a
UTM Coordinates	NAD83 — Zone 18 Easting: 445100.80 Northing: 5011702.00
Municipal Plan and Sublot Number	
Other	

Overburden and Bedrock Materials Interval

General Colour	Most Common Material	Other Materials	General Description	Depth From	Depth To
	CLAY			0 ft	80 ft
	SNDS			80 ft	100 ft

Annular Space/Abandonment Sealing Record

Depth	Depth	Type of Sealant Used	Volume
From	То	(Material and Type)	Placed

Method of Construction & Well Use

Method of Construction Well Use Cable Tool

Domestic

Status of Well

Water Supply

Construction Record - Casing

Inside Diameter	Open Hole or material	Depth From	Depth To
3 inch	STEEL		80 ft
3 inch	OPEN HOLE		100 ft

Construction Record - Screen

Outside Diameter Material Depth Depth From To

Well Contractor and Well Technician Information

Well Contractor's Licence Number: 1603

Results of Well Yield Testing

After test of well yield, water was	CLEAR
If pumping discontinued, give reason	
Pump intake set at	
Pumping Rate	5 GPM
Duration of Pumping	3 h:0 m
Final water level	30 ft
If flowing give rate	
Recommended pump depth	
Recommended pump rate	
Well Production	PUMP
Disinfected?	

Draw Down & Recovery

Draw Down Time(min)	Draw Down Water level	Recovery Time(min)	Recovery Water level
SWL	23 ft		
1		1	
2		2	
3		3	
4		4	
5		5	
10		10	
15		15	
20		20	
25		25	
30		30	
40		40	
45		45	
50		50	
60		60	

Water Found at Depth	Kind
100 ft	Sulphur

Well ID

Well ID Number: 1500334 Well Audit Number: Well Tag Number:

This table contains information from the original well record and any subsequent updates.

Well Location

Address of Well Location	
Township	GLOUCESTER TOWNSHIP
Lot	023
Concession	BF
County/District/Municipality	OTTAWA-CARLETON
City/Town/Village	
Province	ON
Postal Code	n/a
UTM Coordinates	NAD83 — Zone 18 Easting: 445100.80 Northing: 5011702.00
Municipal Plan and Sublot Number	
Other	

Overburden and Bedrock Materials Interval

General Colour	Most Common Material	Other Materials	General Description	Depth From	Depth To
	CLAY			0 ft	80 ft
	SNDS			80 ft	100 ft

Annular Space/Abandonment Sealing Record

Depth	Depth	Type of Sealant Used	Volume
From	То	(Material and Type)	Placed

Method of Construction & Well Use

Method of Construction Well Use Cable Tool

Domestic

Status of Well

Water Supply

Construction Record - Casing

Inside Diameter	Open Hele or meterial		Depth To
3 inch	STEEL		80 ft
3 inch	OPEN HOLE		100 ft

Construction Record - Screen

Outside Diameter Material Depth Depth From To

Well Contractor and Well Technician Information

Well Contractor's Licence Number: 1603

Results of Well Yield Testing

After test of well yield, water was	CLEAR
If pumping discontinued, give reason	
Pump intake set at	
Pumping Rate	5 GPM
Duration of Pumping	3 h:0 m
Final water level	30 ft
If flowing give rate	
Recommended pump depth	
Recommended pump rate	
Well Production	PUMP
Disinfected?	

Draw Down & Recovery

Draw Down Time(min)	Draw Down Water level	Recovery Time(min)	Recovery Water level
SWL	23 ft		
1		1	
2		2	
3		3	
4		4	
5		5	
10		10	
15		15	
20		20	
25		25	
30		30	
40		40	
45		45	
50		50	
60		60	

Water Found at Depth	Kind
100 ft	Sulphur

Well ID

Well ID Number: 1500338 Well Audit Number: Well Tag Number:

This table contains information from the original well record and any subsequent updates.

Well Location

Address of Well Location	
Township	GLOUCESTER TOWNSHIP
Lot	023
Concession	BF
County/District/Municipality	OTTAWA-CARLETON
City/Town/Village	
Province	ON
Postal Code	n/a
UTM Coordinates	NAD83 — Zone 18 Easting: 444790.80 Northing: 5011632.00
Municipal Plan and Sublot Number	
Other	

Overburden and Bedrock Materials Interval

General Colour	Most Common Material	Other Materials	General Description	Depth From	Depth To
	CLAY	BLDR		0 ft	25 ft
	GRVL			25 ft	44 ft
	LMSN			44 ft	55 ft
	SNDS			55 ft	59 ft
	LMSN			59 ft	64 ft

Annular Space/Abandonment Sealing Record

Depth	Depth	Type of Sealant Used	Volume
From	То	(Material and Type)	Placed

Method of Construction & Well Use

Method of Construction	Well Use
-------------------------------	----------

Cable Tool

Public

Status of Well

Water Supply

Construction Record - Casing

Inside Open Hole or material Depth Depth

10/26/2018

Map: Well records	Ontario.ca
-------------------	------------

Diameter		From	То
5 inch	STEEL		47 ft
5 inch	OPEN HOLE		64 ft

Construction Record - Screen

Outside Diameter Material Depth Depth From To

Well Contractor and Well Technician Information

Well Contractor's Licence Number: 1503

Results of Well Yield Testing

After test of well yield, water was	CLEAR
If pumping discontinued, give reason	
Pump intake set at	-
Pumping Rate	10 GPM
Duration of Pumping	0 h:30 m
Final water level	2 ft
If flowing give rate	2 GPM
Recommended pump depth	50 ft
Recommended pump rate	10 GPM
Well Production	PUMP
Disinfected?	

Draw Down & Recovery

Draw Down Time(min)	Draw Down Water level	Recovery Time(min)	Recovery Water level
SWL	FLW		
1		1	
2		2	
3		3	
4		4	
5		5	
10		10	
15		15	
20		20	
25		25	
30		30	
40		40	
45		45	
50		50	
60		60	

Well ID

Well ID Number: 1500337 Well Audit Number: Well Tag Number:

This table contains information from the original well record and any subsequent updates.

Well Location

TownshipGLOUCESTER TOWNSHIPLot023ConcessionBFCounty/District/MunicipalityOTTAWA-CARLETONCity/Town/VillageONProvinceONPostal Coden/aUTM CoordinatesEasting: 444840.80 Northing: 5011582.00Municipal Plan and Sublot NumberOthor	Address of Well Location	
DotConcessionBFCounty/District/MunicipalityOTTAWA-CARLETONCity/Town/VillageONProvinceONPostal Coden/aUTM CoordinatesEasting: 444840.80 Northing: 5011582.00Municipal Plan and Sublot Number	Township	GLOUCESTER TOWNSHIP
CountessionDiamatrixCounty/District/MunicipalityOTTAWA-CARLETONCity/Town/VillageONProvinceONPostal Coden/aUTM CoordinatesEasting: 444840.80 Northing: 5011582.00Municipal Plan and Sublot Number	Lot	023
City/Town/VillageONProvinceONPostal Coden/aUTM CoordinatesEasting: 444840.80 Northing: 5011582.00Municipal Plan and Sublot Number	Concession	BF
ProvinceONPostal Coden/aUTM CoordinatesNAD83 — Zone 18Easting: 444840.80Northing: 5011582.00Municipal Plan and Sublot Number	County/District/Municipality	OTTAWA-CARLETON
Postal Coden/aPostal Coden/aUTM CoordinatesNAD83 — Zone 18Easting: 444840.80Northing: 5011582.00Municipal Plan and Sublot Number	City/Town/Village	-
UTM CoordinatesNAD83 — Zone 18UTM CoordinatesEasting: 444840.80Northing: 5011582.00Municipal Plan and Sublot Number	Province	ON
UTM Coordinates Easting: 444840.80 Northing: 5011582.00 Municipal Plan and Sublot Number	Postal Code	n/a
	UTM Coordinates	Easting: 444840.80
Other	Municipal Plan and Sublot Number	
Other	Other	

Overburden and Bedrock Materials Interval

General Colour	Most Common Material	Other Materials	General Description	Depth From	Depth To
	CLAY			0 ft	15 ft
	BLDR	MSND		15 ft	28 ft
	GRVL	MSND		28 ft	52 ft

Annular Space/Abandonment Sealing Record

Depth	Depth	Type of Sealant Used	Volume
From	То	(Material and Type)	Placed

Method of Construction & Well Use

Method of Construction Well Use Cable Tool

Public

Status of Well

Water Supply

Construction Record - Casing

Inside	Open Hole or material	Depth	Depth
Diameter		From	To
5 inch	STEEL		45 ft

5 inch

Construction Record - Screen

Outside Diameter Material Depth Depth From To

Well Contractor and Well Technician Information

52 ft

Well Contractor's Licence Number: 1503

Results of Well Yield Testing

After test of well yield, water was	CLEAR
If pumping discontinued, give reason	
Pump intake set at	
Pumping Rate	10 GPM
Duration of Pumping	1 h:0 m
Final water level	2 ft
If flowing give rate	-
Recommended pump depth	40 ft
Recommended pump rate	5 GPM
Well Production	PUMP
Disinfected?	

Draw Down & Recovery

Draw Down Time(min)	Draw Down Water level	Recovery Time(min)	Recovery Water level
SWL	2 ft		
1		1	
2		2	
3		3	
4		4	
5		5	
10		10	
15		15	
20		20	
25		25	
30		30	
40		40	
45		45	
50		50	
50		60	

Water Found at Depth	Kind
51 ft	Fresh

Well ID

Well ID Number: 1500335 Well Audit Number: Well Tag Number:

This table contains information from the original well record and any subsequent updates.

Well Location

Address of Well Location	
Township	GLOUCESTER TOWNSHIP
Lot	023
Concession	BF
County/District/Municipality	OTTAWA-CARLETON
City/Town/Village	
Province	ON
Postal Code	n/a
UTM Coordinates	NAD83 — Zone 18 Easting: 445090.80 Northing: 5011912.00
Municipal Plan and Sublot Number	
Other	

Overburden and Bedrock Materials Interval

General Colour	Most Common Material	Other Materials	General Description	Depth From	Depth To
BLUE	CLAY MSND SNDS	BLDR	GRVL	0 ft 21 ft 49 ft	21 ft 49 ft 85 ft

Annular Space/Abandonment Sealing Record

Depth	Depth	Type of Sealant Used	Volume
From	То	(Material and Type)	Placed

Method of Construction & Well Use

Method of Construction Well Use Cable Tool

Domestic

Status of Well

Water Supply

Construction Record - Casing

Inside	Open Hole or material	Depth	Depth
Diameter		From	To
2 inch	STEEL		51 ft

2 inch

Construction Record - Screen

OPEN HOLE

Outside Diameter Material Depth Depth From To

Well Contractor and Well Technician Information

Well Contractor's Licence Number: 1802

Results of Well Yield Testing

After test of well yield, water was	CLEAR
If pumping discontinued, give reason	
Pump intake set at	
Pumping Rate	5 GPM
Duration of Pumping	1 h:0 m
Final water level	35 ft
If flowing give rate	
Recommended pump depth	35 ft
Recommended pump rate	5 GPM
Well Production	PUMP
Disinfected?	_

Draw Down & Recovery

Draw Down Time(min)	Draw Down Water level	Recovery Time(min)	Recovery Water level
SWL	23 ft		
1		1	
2		2	
3		3	
4		4	
5		5	
10		10	
15		15	
20		20	
25		25	
30		30	
40		40	
45		45	
50		50	
60		60	

Water Found at Depth	Kind
82 ft	Fresh

چ . ر		A CHA	0	GROUND W	ATER BRANCH	25
U	TFM 118 2 41415101610 E		38	FEB	15 Nº 20 1952	X000
	5 5 B 5101/1/61910 The Ontario Water Resou				NO WATER	
	Elev. 4 R 021910 WATER WEL			Land the second s	and the second	
E	Basin 215 1 0arleton 77 To	ownshij	p, Village, T	own or City 1	Gloucest 12	1961
	County or District $BF - RF_{Lot} 23$					
		dress	R.R. 1,	Manotick Ontario	Station,	
	Casing and Screen Record			Pumping		
	Inside diameter of casing 2"	Stati	c level	23 : F		C D M
	Total length of casing 51 ^t	Test	-pumping ra	ite <u>2</u> , 2		G.P.M.
	Type of screen	Pum	ping level	ر ر	Un	
	Length of screen	Dura	ation of test j	oumping	Hr.	Clear
	Depth to top of screen Nil	Wat	er clear or cl	oudy at end of	test	CPM
	Diameter of finished hole 2"	Rec	ommended]	oumping rate	5 faat haloo	G.P.M. w ground surface
		with	n pump settir	ng ot		
	Well Log				Depth(s) at	Kind of water
	Overburden and Bedrock Record		From ft.	To ft.	which water(s) found	(fresh, salty, sulphur)
	Blue Clay		0	21	82	Fresh
	Sand, Bolders & Gravel		<u>21</u> 49	49 85		
	Sand Stone					
	House			Location	of Well	
	For what purpose(s) is the water to be used? HOUSE		In diagra		distances of we	ll from
	Holands		road and	l lot line. In	dicate north by	arrow.
	Is well on upland, in valley, or on hillside? Uplands Drilling or Boring Firm J.B. Dufresne & Co. Ltd.		70		6+23	
	Drilling or Boring Firm		RCMP		20723	
	Address 1014 Maitland Ave.				•	
	Address Ottawa, Ont.		3,		3 3	$\neg N$
	Licence Number 194				-	
	Name of Driller or Borer F. Laramée			River	road	
	Address Hull, Que.					
	Date December 1, 195]					
	(Signature of Licensed Frilling or Boring Contractor)					
	Form 7 15M Sets 60-5930					C 9
	OWRC COPY				CSS	

Well ID Number: 7287853 Well Audit Number: *Z237339* Well Tag Number:

This table contains information from the original well record and any subsequent updates.

Well Location

Address of Well Location	793 RIVER RD
Township	GLOUCESTER TOWNSHIP
Lot	
Concession	
County/District/Municipality	OTTAWA-CARLETON
City/Town/Village	
Province	ON
Postal Code	n/a
	NAD83 — Zone 18
UTM Coordinates	Easting: 445196.00
	Northing: 5011539.00
Municipal Plan and Sublot Number	
Other	

Overburden and Bedrock Materials Interval

General Colour Most Common Material Other Materials General Description Depth Depth From To	General Colour	Most Common Material	Other Materials	General Description	Depth From	Depth To
--	----------------	----------------------	-----------------	---------------------	---------------	-------------

Annular Space/Abandonment Sealing Record

Depth From	Depth To	Type of Sealant Used (Material and Type)	Volume Placed
6 ft	0 ft	BACKFILL	
72 ft	6 ft	3/8 HOLEPLUG 2BAGS	
0 ft	72 ft	2" DRILLED WELL ABANDONMENT	Γ

Method of Construction & Well Use

Method of Construction Well Use

Status of Well

Abandoned-Other

Construction Record - Casing

Construction Record - Screen

Outside Material Depth Depth Diameter Material From To

Well Contractor and Well Technician Information

Results of Well Yield Testing

After test of well yield, water was	
If pumping discontinued, give reason	1
Pump intake set at	
Pumping Rate	
Duration of Pumping	
Final water level	
If flowing give rate	
Recommended pump depth	
Recommended pump rate	
Well Production	
Disinfected?	Ŋ

Draw Down & Recovery

Draw Down Time(min)	Draw Down Water level	Recovery Time(min)	Recovery Water level
SWL			
1		1	
2		2	
3		3	
4		4	
5		5	
10		10	
15		15	
20		20	
25		25	
30		30	
40		40	
45		45	
50		50	
60		60	

Water Details

Water Found at Depth Kind

Hole Diameter

Depth Depth From To Diameter

Audit Number: Z237339

Date Well Completed: April 28, 2017

Date Well Record Received by MOE: June 07, 2017

https://www.ontario.ca/environment-and-energy/map-well-records

Updated: June 28, 2018 Rate <u>Rate</u> Share <u>facebook twitter Print</u> Well ID Number: 7287916 Well Audit Number: *Z237345* Well Tag Number: *A207611*

This table contains information from the original well record and any subsequent updates.

Well Location

Address of Well Location	793 RIVER ROAD
Township	GLOUCESTER TOWNSHIP
Lot	
Concession	
County/District/Municipality	OTTAWA-CARLETON
City/Town/Village	MANOTICK
Province	ON
Postal Code	n/a
UTM Coordinates	NAD83 — Zone 18 Easting: 445201.00 Northing: 5011532.00
Municipal Plan and Sublot Number	
Other	

Overburden and Bedrock Materials Interval

General Colour	Most Common Material	Other Materials	General Description	Depth From	Depth To
GREY	CLAY			0 ft	36 ft
WHIT	SNDS	LMSN		36 ft	53 ft
WHIT	SNDS	LMSN		53 ft	72 ft
WHIT	SNDS	LMSN		72 ft	74 ft
WHIT	SNDS	LMSN		74 ft	81 ft

Annular Space/Abandonment Sealing Record

Depth	Depth	Type of Sealant Used	Volume
From	To	(Material and Type)	Placed
42 ft	0 ft	NEAT CEMENT	

Method of Construction & Well Use

Method of Construction	Well Use
Air Percussion	
	Domestic

Status of Well

Water Supply

Construction Record - Casing

Inside Diameter	Open Hole or material	Depth From	Depth To
6.25 inch	STEEL	-2 ft	42 ft
6 inch	OPEN HOLE	42 ft	81 ft

Construction Record - Screen

Outside Diameter Material Depth Depth From To

Well Contractor and Well Technician Information

Well Contractor's Licence Number: 1119

Results of Well Yield Testing

After test of well yield, water was	OTHER
If pumping discontinued, give reason	_
Pump intake set at	70 ft
Pumping Rate	20 GPM
Duration of Pumping	1 h:0 m
Final water level	24.25 ft
If flowing give rate	_
Recommended pump depth	70 ft
Recommended pump rate	20 GPM
Well Production	_
Disinfected?	Y

Draw Down & Recovery

Draw Down Time(min)	Draw Down Water level	Recovery Time(min)	Recovery Water level
SWL	19.75 ft		
1	22 ft	1	22.5 ft
2	22.333 ft	2	19.75 ft
3	22.5 ft	3	19.75 ft
4	22.667 ft	4	19.75 ft
5	22.75 ft	5	19.75 ft
10	23.5 ft	10	19.75 ft
15	24.083 ft	15	19.75 ft
20	24.083 ft	20	19.75 ft
25	24.167 ft	25	19.75 ft
30	24.25 ft	30	19.75 ft
40	24.25 ft	40	19.75 ft
45		45	
50	24.25 ft	50	19.75 ft
60	24.25 ft	60	19.75 ft

Water Details

Water Found at Depth	Kind
53 ft	Untested
72 ft	Untested
74 ft	Untested

Hole Diameter

Depth From	Depth To	Diameter
0 ft	42 ft	9.75 inch
42 ft	81 ft	6 inch

Audit Number: Z237345

Date Well Completed: April 26, 2017

Date Well Record Received by MOE: June 07, 2017

Updated: June 28, 2018 Rate <u>Rate</u>

patersongroup

Consulting Engineers

154 Colorinado Real South Oltaval, Onland Canatta, K2E 735 Tel: (613) 226-7381 Fax: (613) 226-6344

Geotechnical Engineering En aroamental Engineering Hydrogeology Geological Engineering Mateorals Testory Building Science Archaeological Services

www.patersongroup.ca

October 17, 2018 File: PE4467-HLUJ

City of Ottawa 110 Laurier Avenue W Ottawa, Ontario K1P 1J1

Subject:

Authorization Letter, HLUI Search Phase I-Environmental Site Assessment 760 River Road Ottawa, Ontario

Dear Sir or Madame,

Please consider this letter as confirmation that Paterson Group has been retained to conduct a Phase I-Environmental Site Assessment at the aforementioned property.

With this letter, the property owner authorizes the City of Ottawa and other regulatory bodies to release, to Paterson Group, information requested for the purpose of completing an environmental assessment of the property.

Name of Company/Property Owner:

Name of Representative

Authorization of Representative

Date

River Road Inc. n lo M-

2018-10-17

APPENDIX 3

QUALIFICATIONS OF ASSESSORS

Mandy Witteman, E.I.T.

patersongroup

Geotechnical Engineering

Environmental Engineering

Hydrogeology

Geological Engineering

Materials Testing

Building Science

Archaeological Services

POSITION

Environmental Engineer

EDUCATION

Carleton University, M.A.Sc., 2013 Carleton University, B.Eng., 2008 Environmental Engineering

MEMBERSHIPS & AWARDS

Alberta Professional Engineers and Geoscience Association NSERC Industry R&D Scholarship

EXPERIENCE

2018 – Present **Paterson Group Inc.** Consulting Engineers Geotechnical and Environmental Division Environmental Engineer

2014 – 2015 **Thurber Engineering Limited** Oil Sand Tailings Group Tailings Engineer

2014 – 2013 **Carleton University** Department of Civil & Environmental Engineering Division Research Engineer

2013 - 2009 Carleton University Department of Civil & Environmental Engineering Division Research Assistant and Teachers Assistant

2008 – 2009 SLR Consulting Limited Contaminated Sites Junior Environmental Engineer

Mark S. D'Arcy, P. Eng.

patersongroup

Geotechnical Engineering

Environmental Engineering

Hydrogeology

Geological Engineering

Materials Testing

Building Science

Archaeological Services

POSITION

Associate and Supervisor of the Environmental Division Senior Environmental/Geotechnical Engineer

EDUCATION

Queen's University, B.A.Sc.Eng, 1991 Geotechnical / Geological Engineering

MEMBERSHIPS

Ottawa Geotechnical Group Professional Engineers of Ontario

EXPERIENCE

1991 to Present **Paterson Group Inc.** Associate and Senior Environmental/Geotechnical Engineer Environmental and Geotechnical Division Supervisor of the Environmental Division

SELECT LIST OF PROJECTS

Mary River Exploration Mine Site - Northern Baffin Island Agricultural Supply Facilities - Eastern Ontario Laboratory Facility - Edmonton (Alberta) Ottawa International Airport - Contaminant Migration Study - Ottawa **Richmond Road Reconstruction - Ottawa** Billings Hurdman Interconnect - Ottawa Bank Street Reconstruction - Ottawa Environmental Review - Various Laboratories across Canada - CFIA Dwyer Hill Training Centre - Ottawa Nortel Networks Environmental Monitoring - Carling Campus - Ottawa Remediation Program - Block D Lands - Kingston Investigation of former landfill sites - City of Ottawa Record of Site Condition for Railway Lands - North Bay Commercial Properties - Guelph and Brampton Brownfields Remediation - Alcan Site - Kingston Montreal Road Reconstruction - Ottawa Appleford Street Residential Development - Ottawa Remediation Program - Ottawa Train Yards Remediation Program - Bayshore and Heron Gate Gladstone Avenue Reconstruction - Ottawa Somerset Avenue West Reconstruction - Ottawa