

Geotechnical  
Engineering

Environmental  
Engineering

Hydrogeology

Geological  
Engineering

Materials Testing

Building Science

Archaeological Services

## **Environmental Noise Control Study**

Proposed 6-Storey Apartment Building  
322 Waverley Street West, Ottawa

Prepared For

Serco Realty Group

### **Paterson Group Inc.**

Consulting Engineers  
154 Colonnade Road South  
Ottawa (Nepean), Ontario  
Canada K2E 7J5

Tel: (613) 226-7381

Fax: (613) 226-6344

[www.patersongroup.ca](http://www.patersongroup.ca)

January 19, 2021

Report: PG5667-1

<b>Table of Contents</b>		<b>Page</b>
<b>1.0</b>	<b>Introduction</b> .....	<b>1</b>
<b>2.0</b>	<b>Background</b> .....	<b>1</b>
<b>3.0</b>	<b>Methodology and Noise Assessment Criteria</b> .....	<b>2</b>
<b>4.0</b>	<b>Analysis</b> .....	<b>5</b>
<b>5.0</b>	<b>Results</b> .....	<b>7</b>
<b>6.0</b>	<b>Discussion and Recommendations</b>	
	6.1 Outdoor Living Areas .....	8
	6.2 Indoor Living Areas and Ventilation .....	8
<b>7.0</b>	<b>Summary of Findings</b> .....	<b>9</b>
<b>8.0</b>	<b>Statement of Limitations</b> .....	<b>10</b>

## Appendices

- Appendix 1    Table 7 - Summary of Reception Points and Geometry  
                  Drawing PG5667-2 - Receptor Location Plan  
                  Drawing PG5667-3 - Site Geometry  
                  Drawing PG5667-3A - Site Geometry (REC 1-1 and REC 1-6)  
                  Drawing PG5667-3B - Site Geometry (REC 2-1 and REC 2-6)  
                  Drawing PG5667-3C - Site Geometry (REC 3-1 and REC 3-6)  
                  Drawing PG5667-3D - Site Geometry (REC 4-1 and REC 4-6)  
                  Drawing PG5667-3E - Site Geometry (REC 5)
- Appendix 2    STAMSON Results

## 1.0 Introduction

Paterson Group (Paterson) was commissioned by Serco Realty Group to conduct an environmental noise control study for the proposed 6-storey apartment building to be located at 322 Waverley Street West, in the City of Ottawa.

The objective of the current study is to:

- ❑ Determine the primary noise sources impacting the site and compare the projected sound levels to guidelines set out by the Ministry of Environment and Climate Change (MOECC) and the City of Ottawa.
- ❑ Review the projected noise levels and offer recommendations regarding warning classes, construction materials or alternative sound barriers.

The following report has been prepared specifically and solely for the aforementioned project which is described herein. It contains our findings and includes acoustical recommendations pertaining to the design and construction of the subject development as they are understood at the time of writing this report.

This study has been conducted according to City of Ottawa document - Engineering Noise Control Guidelines (ENCG), dated January 2016, and the Ontario Ministry of the Environment Guideline NPC-300.

## 2.0 Background

It is understood that the proposed project will consist of a six storey apartment building with one (1) underground level. Associated at-grade landscaped areas are further anticipated. A rooftop patio amenity area is identified on the proposed site plan.

### 3.0 Methodology and Noise Assessment Criteria

The City of Ottawa outlines three (3) sources of environmental noise that must be analyzed separately:

- Surface Transportation Noise
- Stationary Noise
  - new noise-sensitive development applications (noise receptors) in proximity to existing or approved stationary sources of noise, and
  - new stationary sources of noise (noise generating) in proximity to existing or approved noise-sensitive developments
- Aircraft noise

#### Surface Transportation Noise

The City of Ottawa’s Official Plan, in addition to the ENCG, dictate that the influence area must contain any of following conditions to classify as a surface transportation noise source for a subject site:

- Within 100 m of the right-of-way of an existing or proposed arterial, collector or major collector road; a light rail transit corridor; bus rapid transit, or transit priority corridor
- Within 250 m of the right-of-way for an existing or proposed highway or secondary rail line
- Within 300 m from the right of way of a proposed or existing rail corridor or a secondary main railway line
- Within 500 m of an existing 400 series provincial highway, freeway or principle main railway line.

The NPC-300 outlines the limitations of the stationary and environmental noise levels in relation to the location of the receptors. These can be found in the following tables:

<b>Table 1 - Sound Level Limits for Outdoor Living Areas</b>	
<b>Time Period</b>	<b>Required <math>L_{eq(16)}</math> (dBA)</b>
16-hour, 7:00-23:00	55
<input type="checkbox"/> Standards taken from Table 2.2a; Sound Level Limit for Outdoor Living Areas - Road and Rail	

<b>Table 2 - Sound Level Limits for Indoor Living Area</b>			
<b>Type of Space</b>	<b>Time Period</b>	<b>Required L<sub>eq</sub> (dBA)</b>	
		<b>Road</b>	<b>Rail</b>
Living/Dining, den areas of residences, hospitals, nursing homes, schools, daycare centres, etc	7:00-23:00	45	40
Theaters, place of worship, libraries, individual or semi-private offices, conference rooms, reading rooms	23:00-7:00	45	40
Sleeping quarters	7:00-23:00	45	40
	23:00-7:00	40	35
<input type="checkbox"/> Standards taken from Table 2.2b; Sound Level Limit for Indoor Living Areas - Road and Rail			

It is noted in the ENCG that the limits outlined in Table 2 are for the sound levels on the interior of the glass pane. The ENCG further goes on to state that the limit for the exterior of the pane of glass will be 55 dBA.

If the sound level limits are exceeded at the window panes for the indoor living areas, the following Warning Clauses may be referenced:

<b>Table 3 - Warning Clauses for Sound Level Exceedances</b>	
<b>Warning Clause</b>	<b>Description</b>
Warning Clause Type A	"Purchasers/tenants are advised that sound levels due to increasing road traffic (rail traffic) (air traffic) may occasionally interfere with some activities of the dwelling occupants as the sound levels exceed the sound level limits of the Municipality and the Ministry of the Environment."
Warning Clause Type B	"Purchasers/tenants are advised that despite the inclusion of noise control features in the development and within the building units, sound levels due to increasing road traffic (rail traffic) (air traffic) may on occasions interfere with some activities of the dwelling occupants as the sound levels exceed the sound level limits of the Municipality and the Ministry of the Environment."
Warning Clause Type C	"This dwelling unit has been designed with the provision for adding central air conditioning at the occupant's discretion. Installation of central air conditioning by the occupant in low and medium density developments will allow windows and exterior doors to remain closed, thereby ensuring that the indoor sound levels are within the sound level limits of the Municipality and the Ministry of the Environment."
Warning Clause Type D	"This dwelling unit has been supplied with a central air conditioning system which will allow windows and exterior doors to remain closed, thereby ensuring that the indoor sound levels are within the sound level limits of the Municipality and the Ministry of the Environment."
<input type="checkbox"/> Clauses taken from section C8 Warning Clauses; Environmental Noise Guidelines - NPC-300	

## Stationary Noise

Stationary noise sources include sources or facilities that are fixed or mobile and can cause a combination of sound and vibration levels emitted beyond the property line. These sources may include commercial air conditioner units, generators and fans. Facilities that may contribute to stationary noise may include car washes, snow disposal sites, transit stations and manufacturing facilities.

The subject site is not in proximity to existing or approved stationary sources of noise. Therefore, a stationary noise analysis will not be required.

## Aircraft/Airport Noise

The subject site is not located within the Airport Vicinity Development Zone. Therefore this project will not require an aircraft/airport noise analysis. No warning clauses regarding aircraft or airport noise will be required.

## 4.0 Analysis

### Surface Transportation Noise

The subject building is bordered to the north by Waverley Street West, followed by residential dwellings and Lewis Street, to the east by residential dwellings, to the west by a commercial building followed by O'Connor Street, and to the south by residential dwellings and commercial buildings, Frank Street, and Gladstone Avenue. Waverley Street West, Lewis Street, O'Connor Street, Frank Street and Gladstone Avenue are identified within the 100 m radius of proposed development.

Based on the City of Ottawa Official Plan, Schedule F, O'Connor Street is considered a 2 lane urban arterial road (2-UAU). Gladstone Avenue is considered a 2 lane major collector road (2-UMCU). Other roads within the 100 m radius of the development are not classified as either arterial, collector or major collector roads, and therefore are not included in this study. Additionally, the 3 lane Highway 417 westbound and the 3 lane Highway 417 eastbound are within the 500 m radius from the proposed building.

All noise sources are presented in Drawing PG5667-3 - Site Geometry located in Appendix 1.

The noise levels from road traffic are provided by the City of Ottawa, taking into consideration the right-of-way width and the implied roadway class. It is understood that these values represent the maximum allowable capacity of the proposed roadways. The parameters to be used for sound level predictions can be found below:

<b>Table 4 - Traffic and Road Parameters</b>						
<b>Road</b>	<b>Implied Roadway</b>	<b>AADT (Veh/day)</b>	<b>Posted Speed (km/h)</b>	<b>Day/Night Split %</b>	<b>Medium Truck %</b>	<b>Heavy Truck %</b>
Highway 417 Eastbound	3-Queensway	54999	100	92/8	7	5
Highway 417 Westbound	3-Queensway	54999	100	92/8	7	5
O'Connor Street	2-UAU	15000	50	92/8	7	5
Gladstone Avenue	2-UMCU	12000	50	92/8	7	5
<input type="checkbox"/> Data obtained from the City of Ottawa document ENCG						



Three (3) levels of reception points were selected for this analysis. The following elevations were selected from the heights provided on the survey plan for the subject building.

<b>Table 5 - Elevation of Reception Points</b>			
<b>Floor Number</b>	<b>Elevation at Centre of Window (m)</b>	<b>Floor Use</b>	<b>Daytime/Nighttime Analysis</b>
Ground Floor	1.5	Living Area/Bedroom	daytime/nighttime
Sixth Floor	16.5	Living Area/Bedroom	daytime/nighttime
Rooftop Patio	19.5	--	Outdoor Living Area

For this analysis, a reception point was taken at the centre of each floor, at the ground floor and sixth floor. An outdoor living area - rooftop patio was identified on the proposed site plan. A reception point in the centre of rooftop, 19.5 m high, was selected for the analysis of this area. Reception points are detailed on Drawing PG5667-2 - Receptor Locations presented in Appendix 1.

All horizontal distances have been measured from the reception point to the edge of the right-of-way. The highway was analyzed where it intersected the 500 m buffer zone, and the roadways were analyzed where they intersected the 100 m buffer zone, which is reflected in the local angles described in Paterson Drawings PG5667-3A to 3E - Site Geometry in Appendix 1.

Table 7 - Summary of Reception Points and Geometry, located in Appendix 1, provides a summary of the points of reception and their geometry with respect to the noise sources. The analysis is completed so that no effects of sound reflection off of the building facade are considered, as stipulated by the ENCG.

The subject site is relatively flat and at grade with the neighbouring roads within the 500 m radius.

The analysis was completed using STAMSON version 5.04, a computer program which uses the road and rail traffic noise prediction methods using ORNAMENT (Ontario Road Noise Analysis Method for Environment and Transportation) and STEAM (Sound from Trains Environment Analysis Method), publications from the Ontario Ministry of Environment and Energy.

## 5.0 Results

### Surface Transportation

The primary descriptors are the 16-hour daytime and the 8-hour night time equivalent sound levels,  $L_{eq(16)}$  and the  $L_{eq(8)}$  for City roads.

The proposed traffic noise levels were analyzed at all reception points. The results of the STAMSON software can be located in Appendix 2, and the summary of the results can be noted in Table 6.

<b>Table 6 - Proposed Noise Levels</b>				
<b>Reception Point</b>	<b>Description</b>	<b>OLA (dBA)</b>	<b>Daytime at Facade <math>L_{EQ(16)}</math> (dBA)</b>	<b>Nighttime at Facade <math>L_{eq(8)}</math> (dBA)</b>
REC 1-1	Eastern Elevation, 1st Floor	--	36.37	28.77
REC 1-6	Eastern Elevation, 6th Floor	--	47.97	40.38
REC 2-1	Southern Elevation, 1st Floor	--	42.80	35.20
REC 2-6	Southern Elevation, 6th Floor	--	53.22	45.62
REC 3-1	Western Elevation, 1st Floor	--	60.95	53.36
REC 3-6	Western Elevation, 6th Floor	--	63.12	55.52
REC 4-1	Northern Elevation, 1st Floor	--	54.87	47.28
REC 4-6	Northern Elevation, 6th Floor	--	57.59	49.99
REC 5	Rooftop Patio	61.78	--	--

## 6.0 Discussion and Recommendations

### 6.1 Outdoor Living Areas

A roof top patio was identified in the centre of the proposed building. One (1) receptor point was selected for the analysis at outdoor living area (REC 5). It is assumed that the roof top patio will only be utilized as an outdoor living area provided that the proposed building is constructed. The proposed  $L_{eq(16)}$  at the roof top patio will be 61.78 dBA, which exceeds the 55 dBA threshold value specified by the MOECC.

The outdoor living area was designed as a roof top patio, which will increase the total distance between the noise and receptor points. It is also noted that the exterior cladding of the building will act as a noise barrier, providing noise relief to the roof top patio. Utilizing the exterior of the building as a barrier, including the 1 m solid railing that will extend around the perimeter of the roof top patio, the proposed  $L_{eq(16)}$  at the roof top patio will now be 51.72 dBA, which is below the 55 dBA threshold value specified by the ENCG. Therefore, with the recommended noise mitigation measures, the anticipated noise level is acceptable.

### 6.2 Indoor Living Areas and Ventilation

The results of the STAMSON modelling indicates that the  $L_{eq(16)}$  ranges between 36.37 dBA and 63.12 dBA. The ENCG states that the limits for the exterior of the pane of glass is 55 dBA. This value was exceeded at the western and northern receptor points of the building. Therefore, the building should be designed with a central air conditioning unit. Additionally, warning clause Type D, as outlined in Table 3, is also recommended for all units on the western and northern elevations of the building.

## 7.0 Summary of Findings

The subject site is located at 322 Waverley Street West. It is understood that the proposed development will consist of a 6 storey residential apartment building. The associated analysis identified four surface transportation noise sources: Highway 417 Westbound, Highway 417 Eastbound, O'Connor Street, and Gladstone Avenue.

A roof top patio was identified on the proposed site plan. The preliminary analysis indicated that there was an exceedance at this reception point. After utilizing the mitigation measures, including maximizing the distance setback, the anticipated noise levels at the outdoor living area would be lower than the 55 dBA guideline specified by the ENCG.

Several reception points were selected for the analysis, consisting of pane of glass reception points on both the first and top level. The western and northern elevations of the proposed building exceeded the 55 dBA guideline specified by the ENCG. Therefore, a warning clause Type D will be required for this building in addition to the installation of a central air conditioning unit.

The following warning clause is to be included on all Offers of Purchase and Sale and/or lease agreements:

"This dwelling unit has been supplied with a central air conditioning system which will allow windows and exterior doors to remain closed, thereby ensuring that the indoor sound levels are within the sound level limits of the Municipality and the Ministry of the Environment."

## 8.0 Statement of Limitations

The recommendations made in this report are in accordance with our present understanding of the project. Our recommendations should be reviewed when the project drawings and specifications are complete.

The present report applies only to the project described in this document. Use of this report for purposes other than those described herein or by person(s) other than Serco Realty Group or their agent(s) is not authorized without review by this firm for the applicability of our recommendations to the altered use of the report.

### Paterson Group Inc.



Stephanie A. Boisvenue, P.Eng.



Scott S. Dennis, P.Eng.



### Report Distribution:

- Serco Realty Group (3 copies)
- Paterson Group (1 copy)

# **APPENDIX 1**

**TABLE 7 - SUMMARY OF RECEPTION POINTS AND GEOMETRY**

**DRAWING PG5667-2 - RECEPTOR LOCATION PLAN**

**DRAWING PG5667-3 - SITE GEOMETRY**

**DRAWING PG5667-3A - SITE GEOMETRY (REC 1-1 and REC 1-6)**

**DRAWING PG5667-3B - SITE GEOMETRY (REC 2-1 and REC 2-6)**

**DRAWING PG5667-3C - SITE GEOMETRY (REC 3-1 and REC 3-6)**



**DRAWING PG5667-3D - SITE GEOMETRY (REC 4-1 and REC 4-6)**

**DRAWING PG5667-3E - SITE GEOMETRY (REC 5)**

**Table 7 - Summary of Reception Points and Geometry  
322 Waverley Street West**

Point of Reception	Location	Leq Day (dBA)	O'Connor Street								Gladstone Avenue							
			Horizontal (m)	Vertical (m)	Total (m)	Local Angle (degree)	Number of Rows of Houses	Density (%)	Barrier Height (m)	Barrier Distance (m)	Horizontal (m)	Vertical (m)	Total (m)	Local Angle (degree)	Number of Rows of Houses	Density (%)	Barrier Height (m)	Barrier Distance (m)
REC 1-1	Eastern Elevation, 1st Floor	36.37	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	95	1.5	95.01	-23, 0	1	40	9	40
REC 1-6	Eastern Elevation, 6th Floor	47.97	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	95	16.5	96.42	-23, 0	1	40	9	40
REC 2-1	Southern Elevation, 1st Floor	42.80	45	1.5	45.02	-69, 0	n/a	n/a	9	35	85	1.5	85.01	-30, 32	1	40	9	30
REC 2-6	Southern Elevation, 6th Floor	53.22	45	16.5	47.93	-69, 0	n/a	n/a	9	35	85	16.5	86.6	-30, 32	1	40	9	30
REC 3-1	Western Elevation, 1st Floor	60.95	30	1.5	30.04	-75, 80	1	20	n/a	n/a	95	1.5	95.01	0, 32	1	40	9	40
REC 3-6	Western Elevation, 6th Floor	63.12	30	16.5	34.24	-75, 80	1	20	n/a	n/a	95	16.5	96.42	0, 32	1	40	9	40
REC 4-1	Northern Elevation, 1st Floor	54.87	45	1.5	45.02	0, 73	1	20	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
REC 4-6	Northern Elevation, 6th Floor	57.59	45	16.5	47.93	0, 73	1	20	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
REC 5	Rooftop Patio	61.78	45	19.5	49.0	-71, 76	1	20	n/a	n/a	95	19.5	97.0	-26, 34	1	40	9	40

Point of Reception	Location	Leq Day (dBA)	Highway 417 Westbound								Highway 417 Eastbound							
			Horizontal (m)	Vertical (m)	Total (m)	Local Angle (degree)	Number of Rows of Houses	Density (%)	Barrier Height (m)	Barrier Distance (m)	Horizontal (m)	Vertical (m)	Total (m)	Local Angle (degree)	Number of Rows of Houses	Density (%)	Barrier Height (m)	Barrier Distance (m)
REC 1-1	Eastern Elevation, 1st Floor	36.37	470	1.5	470.0	-19, 0	7	80	n/a	n/a	485	1.5	485.0	-13, 0	7	80	n/a	n/a
REC 1-6	Eastern Elevation, 6th Floor	47.97	470	16.5	470.29	-19, 0	7	80	n/a	n/a	485	16.5	485.3	-13, 0	7	80	n/a	n/a
REC 2-1	Southern Elevation, 1st Floor	42.80	455	1.5	455.0	-21, 24	7	80	n/a	n/a	470	1.5	470.0	-15, 19	7	80	n/a	n/a
REC 2-6	Southern Elevation, 6th Floor	53.22	455	16.5	455.3	-21, 24	7	80	n/a	n/a	470	16.5	470.3	-15, 19	7	80	n/a	n/a
REC 3-1	Western Elevation, 1st Floor	60.95	475	1.5	475.0	0, 22	7	80	n/a	n/a	485	1.5	485.0	0, 17	7	80	n/a	n/a
REC 3-6	Western Elevation, 6th Floor	63.12	475	16.5	475.3	0, 22	7	80	n/a	n/a	485	16.5	485.3	0, 17	7	80	n/a	n/a
REC 4-1	Northern Elevation, 1st Floor	54.87	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
REC 4-6	Northern Elevation, 6th Floor	57.59	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
REC 5	Rooftop Patio	61.78	460	19.5	460.4	-20, 22	7	80	n/a	n/a	475	19.5	475.4	-15, 17	7	80	n/a	n/a



**LEGEND:**  
 RECEPTOR LOCATION

**patersongroup**  
 consulting engineers

154 Colonnade Road South  
 Ottawa, Ontario K2E 7J5  
 Tel: (613) 226-7381 Fax: (613) 226-6344

NO.	REVISIONS	DATE	INITIAL


OTTAWA, ONTARIO  
 Title: **SERCO REALTY GROUP  
 NOISE ATTENUATION STUDY  
 PROPOSED 6-STORY APARTMENT BUILDING  
 322 WAVERLEY STREET WEST**

Scale: 1:150  
 Drawn by: YA  
 Checked by: SB  
 Approved by: DJG

Date: 01/2021  
 Report No.: PG5667-1  
 Dwg. No.: **PG5667-2**  
 Revision No.:

p:\autocad\drawings\geotechnical\pg5667\pg5667-2-receptor location plan.dwg





**patersongroup**  
consulting engineers

154 Colonnade Road South  
Ottawa, Ontario K2E 7J5  
Tel: (613) 226-7381 Fax: (613) 226-6344

NO.	REVISIONS	DATE	INITIAL

OTTAWA,  
Title:

SERCO REALTY GROUP  
NOISE ATTENUATION STUDY  
PROPOSED 6-STORY APARTMENT BUILDING  
322 WAVERLEY STREET WEST


ONTARIO

**SITE GEOMETRY**

Scale: 1:5000  
Drawn by: YA  
Checked by: SB  
Approved by: DJG

Date: 01/2021  
Report No.: PG5667-1  
Dwg. No.: **PG5667-3**  
Revision No.:





**patersongroup**  
consulting engineers

154 Colonnade Road South  
Ottawa, Ontario K2E 7J5  
Tel: (613) 226-7381 Fax: (613) 226-6344

NO.	REVISIONS	DATE	INITIAL


**SERCO REALTY GROUP**  
**NOISE ATTENUATION STUDY**  
**PROPOSED 6-STORY APARTMENT BUILDING**  
**322 WAVERLEY STREET WEST**  
**ONTARIO**


OTTAWA,  
 Title: **SITE GEOMETRY - REC 1-1 AND REC 1-6**

Scale:	1:5000	Date:	01/2021
Drawn by:	YA	Report No.:	PG5667-1
Checked by:	SB	Dwg. No.:	<b>PG5667-3A</b>
Approved by:	DJG	Revision No.:	

p:\autocad\drawings\geotechnical\pg5667\pg5667-3-site\_geometry.dwg





**LEGEND:**  
 RECEPTOR LOCATION

**patersongroup**  
 consulting engineers

154 Colonnade Road South  
 Ottawa, Ontario K2E 7J5  
 Tel: (613) 226-7381 Fax: (613) 226-6344


NO.	REVISIONS	DATE	INITIAL

**SERCO REALTY GROUP**  
**NOISE ATTENUATION STUDY**  
**PROPOSED 6-STORY APARTMENT BUILDING**  
**322 WAVERLEY STREET WEST**  
 OTTAWA, ONTARIO  
 Title: **SITE GEOMETRY - REC 2-1 AND REC 2-6**

Scale:	1:5000	Date:	01/2021
Drawn by:	YA	Report No.:	PG5667-1
Checked by:	SB	Dwg. No.:	<b>PG5667-3B</b>
Approved by:	DJG	Revision No.:	

p:\autocad\drawings\geotechnical\pg5667\pg5667-3-site\_geometry.dwg





**patersongroup**  
consulting engineers

154 Colonnade Road South  
Ottawa, Ontario K2E 7J5  
Tel: (613) 226-7381 Fax: (613) 226-6344


NO.	REVISIONS	DATE	INITIAL

SERCO REALTY GROUP  
NOISE ATTENUATION STUDY  
PROPOSED 6-STOREY APARTMENT BUILDING  
322 WAVERLEY STREET WEST  
ONTARIO

OTTAWA,  
Title: **SITE GEOMETRY - REC 3-1 AND REC 3-6**

Scale:	1:5000	Date:	01/2021
Drawn by:	YA	Report No.:	PG5667-1
Checked by:	SB	Dwg. No.:	<b>PG5667-3C</b>
Approved by:	DJG	Revision No.:	





**patersongroup**  
consulting engineers

154 Colonnade Road South  
Ottawa, Ontario K2E 7J5  
Tel: (613) 226-7381 Fax: (613) 226-6344

NO.	REVISIONS	DATE	INITIAL


SERCO REALTY GROUP  
NOISE ATTENUATION STUDY  
PROPOSED 6-STOREY APARTMENT BUILDING  
322 WAVERLEY STREET WEST  
ONTARIO

OTTAWA,  
Title: **SITE GEOMETRY - REC 4-1 AND REC 4-6**

Scale:	1:5000	Date:	01/2021
Drawn by:	YA	Report No.:	PG5667-1
Checked by:	SB	Dwg. No.:	<b>PG5667-3D</b>
Approved by:	DJG	Revision No.:	

p:\autocad\drawings\geotechnical\pg5667\pg5667-3-site\_geometry.dwg





**patersongroup**  
consulting engineers

154 Colonnade Road South  
Ottawa, Ontario K2E 7J5  
Tel: (613) 226-7381 Fax: (613) 226-6344

NO.	REVISIONS	DATE	INITIAL

OTTAWA,  
Title:

SERCO REALTY GROUP  
NOISE ATTENUATION STUDY  
PROPOSED 6-STORY APARTMENT BUILDING  
322 WAVERLEY STREET WEST

ONTARIO

**SITE GEOMETRY - REC 5**

Scale: 1:5000  
Drawn by: YA  
Checked by: SB  
Approved by: DJG

Date: 01/2021  
Report No.: PG5667-1  
Dwg. No.: **PG5667-3E**  
Revision No.:



# **APPENDIX 2**

**STAMSON RESULTS**

Filename: rec11.te                            Time Period: Day/Night 16/8 hours  
Description: Reception Point 1-1

Road data, segment # 1: GladstoneAve (day/night)

-----  
Car traffic volume : 9715/845    veh/TimePeriod    \*  
Medium truck volume : 773/67    veh/TimePeriod    \*  
Heavy truck volume : 552/48    veh/TimePeriod    \*  
Posted speed limit : 50 km/h  
Road gradient : 0 %  
Road pavement : 1 (Typical asphalt or concrete)

\* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 12000  
Percentage of Annual Growth : 0.00  
Number of Years of Growth : 0.00  
Medium Truck % of Total Volume : 7.00  
Heavy Truck % of Total Volume : 5.00  
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 1: GladstoneAve (day/night)

-----  
Angle1    Angle2            : -23.00 deg    0.00 deg  
Wood depth                : 0            (No woods.)  
No of house rows         : 1 / 1  
House density             : 40 %  
Surface                    : 1            (Absorptive ground surface)  
Receiver source distance : 95.00 / 95.00 m  
Receiver height            : 1.50 / 1.50 m  
Topography                : 2            (Flat/gentle slope; with barrier)  
Barrier angle1            : -23.00 deg    Angle2 : 0.00 deg  
Barrier height             : 9.00 m  
Barrier receiver distance : 40.00 / 40.00 m  
Source elevation          : 70.00 m  
Receiver elevation        : 70.00 m  
Barrier elevation         : 70.00 m  
Reference angle            : 0.00

↑  
Road data, segment # 2: Hwy 417 West (day/night)

-----  
Car traffic volume : 44527/3872    veh/TimePeriod    \*  
Medium truck volume : 3542/308    veh/TimePeriod    \*  
Heavy truck volume : 2530/220    veh/TimePeriod    \*  
Posted speed limit : 100 km/h



Road gradient : 0 %  
Road pavement : 1 (Typical asphalt or concrete)

\* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 54999  
Percentage of Annual Growth : 0.00  
Number of Years of Growth : 0.00  
Medium Truck % of Total Volume : 7.00  
Heavy Truck % of Total Volume : 5.00  
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 2: Hwy 417 West (day/night)

-----  
Angle1 Angle2 : -19.00 deg 0.00 deg  
Wood depth : 0 (No woods.)  
No of house rows : 7 / 7  
House density : 80 %  
Surface : 1 (Absorptive ground surface)  
Receiver source distance : 470.00 / 470.00 m  
Receiver height : 1.50 / 1.50 m  
Topography : 3 (Elevated; no barrier)  
Elevation : 2.00 m  
Reference angle : 0.00

↑

Road data, segment # 3: Hwy 417 East (day/night)

-----  
Car traffic volume : 44527/3872 veh/TimePeriod \*  
Medium truck volume : 3542/308 veh/TimePeriod \*  
Heavy truck volume : 2530/220 veh/TimePeriod \*  
Posted speed limit : 100 km/h  
Road gradient : 0 %  
Road pavement : 1 (Typical asphalt or concrete)

\* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 54999  
Percentage of Annual Growth : 0.00  
Number of Years of Growth : 0.00  
Medium Truck % of Total Volume : 7.00  
Heavy Truck % of Total Volume : 5.00  
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 3: Hwy 417 East (day/night)

-----  
Angle1 Angle2 : -13.00 deg 0.00 deg  
Wood depth : 0 (No woods.)  
No of house rows : 7 / 7  
House density : 80 %

Surface : 1 (Absorptive ground surface)  
 Receiver source distance : 485.00 / 485.00 m  
 Receiver height : 1.50 / 1.50 m  
 Topography : 3 (Elevated; no barrier)  
 Elevation : 2.00 m  
 Reference angle : 0.00

↑  
 Results segment # 1: GladstoneAve (day)

-----  
 Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	1.50	1.50	71.50

ROAD (0.00 + 31.26 + 0.00) = 31.26 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-23	0	0.66	67.51	0.00	-13.31	-9.01	0.00	-2.00	0.00	43.19
-23	0	0.12	67.51	0.00	-8.98	-8.95	0.00	0.00	-18.33	31.26

-----  
 Segment Leq : 31.26 dBA

↑  
 Results segment # 2: Hwy 417 West (day)

-----  
 Source height = 1.50 m

ROAD (0.00 + 32.58 + 0.00) = 32.58 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-19	0	0.60	80.15	0.00	-23.94	-9.81	0.00	-13.82	0.00	32.58

-----  
 Segment Leq : 32.58 dBA

↑  
 Results segment # 3: Hwy 417 East (day)

-----  
 Source height = 1.50 m

ROAD (0.00 + 30.76 + 0.00) = 30.76 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-13	0	0.60	80.15	0.00	-24.16	-11.44	0.00	-13.80	0.00	30.76

Segment Leq : 30.76 dBA

Total Leq All Segments: 36.37 dBA

↑  
Results segment # 1: GladstoneAve (night)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	1.50	1.50	71.50

ROAD (0.00 + 23.66 + 0.00) = 23.66 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-23	0	0.66	59.91	0.00	-13.31	-9.01	0.00	-2.00	0.00	35.59
-23	0	0.12	59.91	0.00	-8.98	-8.95	0.00	0.00	-18.33	23.66

Segment Leq : 23.66 dBA

↑  
Results segment # 2: Hwy 417 West (night)

Source height = 1.50 m

ROAD (0.00 + 24.98 + 0.00) = 24.98 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-19	0	0.60	72.55	0.00	-23.94	-9.81	0.00	-13.82	0.00	24.98

Segment Leq : 24.98 dBA

↑  
Results segment # 3: Hwy 417 East (night)

Source height = 1.50 m

ROAD (0.00 + 23.16 + 0.00) = 23.16 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-13	0	0.60	72.55	0.00	-24.16	-11.44	0.00	-13.80	0.00	23.16

Segment Leq : 23.16 dBA

Total Leq All Segments: 28.77 dBA

↑

TOTAL Leq FROM ALL SOURCES (DAY): 36.37  
(NIGHT): 28.77

↑

↑

Filename: rec16.te                            Time Period: Day/Night 16/8 hours  
Description: Reception Point 1-6

Road data, segment # 1: GladstoneAve (day/night)

-----  
Car traffic volume : 9715/845    veh/TimePeriod    \*  
Medium truck volume : 773/67    veh/TimePeriod    \*  
Heavy truck volume : 552/48    veh/TimePeriod    \*  
Posted speed limit : 50 km/h  
Road gradient : 0 %  
Road pavement : 1 (Typical asphalt or concrete)

\* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 12000  
Percentage of Annual Growth : 0.00  
Number of Years of Growth : 0.00  
Medium Truck % of Total Volume : 7.00  
Heavy Truck % of Total Volume : 5.00  
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 1: GladstoneAve (day/night)

-----  
Angle1    Angle2            : -23.00 deg    0.00 deg  
Wood depth                : 0            (No woods.)  
No of house rows         : 1 / 1  
House density             : 40 %  
Surface                   : 1            (Absorptive ground surface)  
Receiver source distance : 95.00 / 95.00 m  
Receiver height           : 16.50 / 16.50 m  
Topography                : 2            (Flat/gentle slope; with barrier)  
Barrier angle1            : -23.00 deg    Angle2 : 0.00 deg  
Barrier height            : 9.00 m  
Barrier receiver distance : 40.00 / 40.00 m  
Source elevation         : 70.00 m  
Receiver elevation        : 70.00 m  
Barrier elevation         : 70.00 m  
Reference angle           : 0.00

↑

Road data, segment # 2: Hwy 417 West (day/night)

-----  
Car traffic volume : 44527/3872    veh/TimePeriod    \*  
Medium truck volume : 3542/308    veh/TimePeriod    \*  
Heavy truck volume : 2530/220    veh/TimePeriod    \*  
Posted speed limit : 100 km/h

Road gradient : 0 %  
Road pavement : 1 (Typical asphalt or concrete)

\* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 54999  
Percentage of Annual Growth : 0.00  
Number of Years of Growth : 0.00  
Medium Truck % of Total Volume : 7.00  
Heavy Truck % of Total Volume : 5.00  
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 2: Hwy 417 West (day/night)

-----  
Angle1 Angle2 : -19.00 deg 0.00 deg  
Wood depth : 0 (No woods.)  
No of house rows : 7 / 7  
House density : 80 %  
Surface : 1 (Absorptive ground surface)  
Receiver source distance : 470.00 / 470.00 m  
Receiver height : 16.50 / 16.50 m  
Topography : 3 (Elevated; no barrier)  
Elevation : 2.00 m  
Reference angle : 0.00

↑

Road data, segment # 3: Hwy 417 East (day/night)

-----  
Car traffic volume : 44527/3872 veh/TimePeriod \*  
Medium truck volume : 3542/308 veh/TimePeriod \*  
Heavy truck volume : 2530/220 veh/TimePeriod \*  
Posted speed limit : 100 km/h  
Road gradient : 0 %  
Road pavement : 1 (Typical asphalt or concrete)

\* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 54999  
Percentage of Annual Growth : 0.00  
Number of Years of Growth : 0.00  
Medium Truck % of Total Volume : 7.00  
Heavy Truck % of Total Volume : 5.00  
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 3: Hwy 417 East (day/night)

-----  
Angle1 Angle2 : -13.00 deg 0.00 deg  
Wood depth : 0 (No woods.)  
No of house rows : 7 / 7  
House density : 80 %

Surface : 1 (Absorptive ground surface)  
 Receiver source distance : 485.00 / 485.00 m  
 Receiver height : 16.50 / 16.50 m  
 Topography : 3 (Elevated; no barrier)  
 Elevation : 2.00 m  
 Reference angle : 0.00

↑  
 Results segment # 1: GladstoneAve (day)

-----  
 Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	16.50	10.18	80.18

ROAD (0.00 + 46.85 + 0.00) = 46.85 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-23	0	0.21	67.51	0.00	-9.70	-8.96	0.00	-2.00	0.00	46.85
-23	0	0.00	67.51	0.00	-8.02	-8.94	0.00	0.00	-3.29	47.27*
-23	0	0.21	67.51	0.00	-9.70	-8.96	0.00	0.00	0.00	48.85

-----  
 \* Bright Zone !

Segment Leq : 46.85 dBA

↑  
 Results segment # 2: Hwy 417 West (day)

-----  
 Source height = 1.50 m

ROAD (0.00 + 39.34 + 0.00) = 39.34 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-19	0	0.15	80.15	0.00	-17.21	-9.78	0.00	-13.82	0.00	39.34

-----  
 Segment Leq : 39.34 dBA

↑  
 Results segment # 3: Hwy 417 East (day)

-----

Source height = 1.50 m

ROAD (0.00 + 37.57 + 0.00) = 37.57 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-13	0	0.15	80.15	0.00	-17.36	-11.42	0.00	-13.80	0.00	37.57

Segment Leq : 37.57 dBA

Total Leq All Segments: 47.97 dBA

↑

Results segment # 1: GladstoneAve (night)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	16.50	10.18	80.18

ROAD (0.00 + 39.25 + 0.00) = 39.25 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-23	0	0.21	59.91	0.00	-9.70	-8.96	0.00	-2.00	0.00	39.25
-23	0	0.00	59.91	0.00	-8.02	-8.94	0.00	0.00	-3.29	39.67*
-23	0	0.21	59.91	0.00	-9.70	-8.96	0.00	0.00	0.00	41.25

\* Bright Zone !

Segment Leq : 39.25 dBA

↑

Results segment # 2: Hwy 417 West (night)

Source height = 1.50 m

ROAD (0.00 + 31.75 + 0.00) = 31.75 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-19	0	0.15	72.55	0.00	-17.21	-9.78	0.00	-13.82	0.00	31.75

Segment Leq : 31.75 dBA



↑  
Results segment # 3: Hwy 417 East (night)  
-----

Source height = 1.50 m

ROAD (0.00 + 29.97 + 0.00) = 29.97 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-13	0	0.15	72.55	0.00	-17.36	-11.42	0.00	-13.80	0.00	29.97

-----

Segment Leq : 29.97 dBA

Total Leq All Segments: 40.38 dBA

↑

TOTAL Leq FROM ALL SOURCES (DAY): 47.97  
(NIGHT): 40.38

↑  
↑

Filename: rec21.te                            Time Period: Day/Night 16/8 hours  
Description: Reception Point 2-1

Road data, segment # 1: O'Connor St (day/night)

-----  
Car traffic volume : 12144/1056 veh/TimePeriod \*  
Medium truck volume : 966/84 veh/TimePeriod \*  
Heavy truck volume : 690/60 veh/TimePeriod \*  
Posted speed limit : 50 km/h  
Road gradient : 0 %  
Road pavement : 1 (Typical asphalt or concrete)

\* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 15000  
Percentage of Annual Growth : 0.00  
Number of Years of Growth : 0.00  
Medium Truck % of Total Volume : 7.00  
Heavy Truck % of Total Volume : 5.00  
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 1: O'Connor St (day/night)

-----  
Angle1 Angle2 : -69.00 deg 0.00 deg  
Wood depth : 0 (No woods.)  
No of house rows : 0 / 0  
Surface : 1 (Absorptive ground surface)  
Receiver source distance : 45.00 / 45.00 m  
Receiver height : 1.50 / 1.50 m  
Topography : 2 (Flat/gentle slope; with barrier)  
Barrier angle1 : -69.00 deg Angle2 : 0.00 deg  
Barrier height : 9.00 m  
Barrier receiver distance : 35.00 / 35.00 m  
Source elevation : 70.00 m  
Receiver elevation : 70.00 m  
Barrier elevation : 70.00 m  
Reference angle : 0.00

↑

Road data, segment # 2: GladstoneAve (day/night)

-----  
Car traffic volume : 9715/845 veh/TimePeriod \*  
Medium truck volume : 773/67 veh/TimePeriod \*  
Heavy truck volume : 552/48 veh/TimePeriod \*  
Posted speed limit : 50 km/h  
Road gradient : 0 %

Road pavement : 1 (Typical asphalt or concrete)

\* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 12000  
Percentage of Annual Growth : 0.00  
Number of Years of Growth : 0.00  
Medium Truck % of Total Volume : 7.00  
Heavy Truck % of Total Volume : 5.00  
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 2: GladstoneAve (day/night)

-----  
Angle1 Angle2 : -30.00 deg 32.00 deg  
Wood depth : 0 (No woods.)  
No of house rows : 1 / 1  
House density : 40 %  
Surface : 1 (Absorptive ground surface)  
Receiver source distance : 85.00 / 85.00 m  
Receiver height : 1.50 / 1.50 m  
Topography : 2 (Flat/gentle slope; with barrier)  
Barrier angle1 : -30.00 deg Angle2 : 32.00 deg  
Barrier height : 9.00 m  
Barrier receiver distance : 30.00 / 30.00 m  
Source elevation : 70.00 m  
Receiver elevation : 70.00 m  
Barrier elevation : 70.00 m  
Reference angle : 0.00

↑

Road data, segment # 3: Hwy 417 West (day/night)

-----  
Car traffic volume : 44527/3872 veh/TimePeriod \*  
Medium truck volume : 3542/308 veh/TimePeriod \*  
Heavy truck volume : 2530/220 veh/TimePeriod \*  
Posted speed limit : 100 km/h  
Road gradient : 0 %  
Road pavement : 1 (Typical asphalt or concrete)

\* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 54999  
Percentage of Annual Growth : 0.00  
Number of Years of Growth : 0.00  
Medium Truck % of Total Volume : 7.00  
Heavy Truck % of Total Volume : 5.00  
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 3: Hwy 417 West (day/night)

-----

Angle1 Angle2 : -21.00 deg 24.00 deg  
 Wood depth : 0 (No woods.)  
 No of house rows : 7 / 7  
 House density : 80 %  
 Surface : 1 (Absorptive ground surface)  
 Receiver source distance : 455.00 / 455.00 m  
 Receiver height : 1.50 / 1.50 m  
 Topography : 3 (Elevated; no barrier)  
 Elevation : 2.00 m  
 Reference angle : 0.00

↑

Road data, segment # 4: Hwy 417 East (day/night)

-----  
 Car traffic volume : 44527/3872 veh/TimePeriod \*  
 Medium truck volume : 3542/308 veh/TimePeriod \*  
 Heavy truck volume : 2530/220 veh/TimePeriod \*  
 Posted speed limit : 100 km/h  
 Road gradient : 0 %  
 Road pavement : 1 (Typical asphalt or concrete)

\* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 54999  
 Percentage of Annual Growth : 0.00  
 Number of Years of Growth : 0.00  
 Medium Truck % of Total Volume : 7.00  
 Heavy Truck % of Total Volume : 5.00  
 Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 4: Hwy 417 East (day/night)

-----  
 Angle1 Angle2 : -15.00 deg 19.00 deg  
 Wood depth : 0 (No woods.)  
 No of house rows : 7 / 7  
 House density : 80 %  
 Surface : 1 (Absorptive ground surface)  
 Receiver source distance : 470.00 / 470.00 m  
 Receiver height : 1.50 / 1.50 m  
 Topography : 3 (Elevated; no barrier)  
 Elevation : 2.00 m  
 Reference angle : 0.00

↑

Results segment # 1: O'Connor St (day)

-----  
 Source height = 1.50 m

Barrier height for grazing incidence

```

-----
Source      ! Receiver      ! Barrier      ! Elevation of
Height (m) ! Height (m) ! Height (m) ! Barrier Top (m)
-----+-----+-----+-----
          1.50 !          1.50 !          1.50 !          71.50

```

ROAD (0.00 + 38.95 + 0.00) = 38.95 dBA

```

Angle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq
-----+-----+-----+-----+-----+-----+-----+-----+-----+-----+-----
   -69     0   0.12  68.48   0.00  -5.34  -4.31   0.00   0.00 -19.87  38.95
-----+-----+-----+-----+-----+-----+-----+-----+-----+-----+-----

```

Segment Leq : 38.95 dBA

↑  
Results segment # 2: GladstoneAve (day)

Source height = 1.50 m

Barrier height for grazing incidence

```

-----
Source      ! Receiver      ! Barrier      ! Elevation of
Height (m) ! Height (m) ! Height (m) ! Barrier Top (m)
-----+-----+-----+-----
          1.50 !          1.50 !          1.50 !          71.50

```

ROAD (0.00 + 35.45 + 0.00) = 35.45 dBA

```

Angle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq
-----+-----+-----+-----+-----+-----+-----+-----+-----+-----+-----
  -30    32   0.66  67.51   0.00 -12.51  -4.77   0.00  -2.00   0.00  48.23
  -30    32   0.12  67.51   0.00  -8.44  -4.66   0.00   0.00 -18.97  35.45
-----+-----+-----+-----+-----+-----+-----+-----+-----+-----+-----

```

Segment Leq : 35.45 dBA

↑  
Results segment # 3: Hwy 417 West (day)

Source height = 1.50 m

ROAD (0.00 + 36.49 + 0.00) = 36.49 dBA

```

Angle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq
-----+-----+-----+-----+-----+-----+-----+-----+-----+-----+-----
  -21    24   0.60  80.15   0.00 -23.71  -6.09   0.00 -13.85   0.00  36.49
-----+-----+-----+-----+-----+-----+-----+-----+-----+-----+-----

```

Segment Leq : 36.49 dBA

↑  
Results segment # 4: Hwy 417 East (day)

-----  
Source height = 1.50 m

ROAD (0.00 + 35.11 + 0.00) = 35.11 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-15	19	0.60	80.15	0.00	-23.94	-7.28	0.00	-13.82	0.00	35.11

-----

Segment Leq : 35.11 dBA

Total Leq All Segments: 42.80 dBA

↑  
Results segment # 1: O'Connor St (night)

-----  
Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	1.50	1.50	71.50

ROAD (0.00 + 31.35 + 0.00) = 31.35 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-69	0	0.12	60.88	0.00	-5.34	-4.31	0.00	0.00	-19.87	31.35

-----

Segment Leq : 31.35 dBA

↑  
Results segment # 2: GladstoneAve (night)

-----  
Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	1.50	1.50	71.50

ROAD (0.00 + 27.85 + 0.00) = 27.85 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-30	32	0.66	59.91	0.00	-12.51	-4.77	0.00	-2.00	0.00	40.64
-30	32	0.12	59.91	0.00	-8.44	-4.66	0.00	0.00	-18.97	27.85

Segment Leq : 27.85 dBA

↑

Results segment # 3: Hwy 417 West (night)

Source height = 1.50 m

ROAD (0.00 + 28.90 + 0.00) = 28.90 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-21	24	0.60	72.55	0.00	-23.71	-6.09	0.00	-13.85	0.00	28.90

Segment Leq : 28.90 dBA

↑

Results segment # 4: Hwy 417 East (night)

Source height = 1.50 m

ROAD (0.00 + 27.51 + 0.00) = 27.51 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-15	19	0.60	72.55	0.00	-23.94	-7.28	0.00	-13.82	0.00	27.51

Segment Leq : 27.51 dBA

Total Leq All Segments: 35.20 dBA

↑

TOTAL Leq FROM ALL SOURCES (DAY): 42.80  
(NIGHT): 35.20

↑

↑

Filename: rec26.te                            Time Period: Day/Night 16/8 hours  
Description: Reception Point 2-6

Road data, segment # 1: O'Connor St (day/night)

-----  
Car traffic volume : 12144/1056 veh/TimePeriod \*  
Medium truck volume : 966/84 veh/TimePeriod \*  
Heavy truck volume : 690/60 veh/TimePeriod \*  
Posted speed limit : 50 km/h  
Road gradient : 0 %  
Road pavement : 1 (Typical asphalt or concrete)

\* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 15000  
Percentage of Annual Growth : 0.00  
Number of Years of Growth : 0.00  
Medium Truck % of Total Volume : 7.00  
Heavy Truck % of Total Volume : 5.00  
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 1: O'Connor St (day/night)

-----  
Angle1 Angle2 : -69.00 deg 0.00 deg  
Wood depth : 0 (No woods.)  
No of house rows : 0 / 0  
Surface : 1 (Absorptive ground surface)  
Receiver source distance : 45.00 / 45.00 m  
Receiver height : 16.50 / 16.50 m  
Topography : 2 (Flat/gentle slope; with barrier)  
Barrier angle1 : -69.00 deg Angle2 : 0.00 deg  
Barrier height : 9.00 m  
Barrier receiver distance : 35.00 / 35.00 m  
Source elevation : 70.00 m  
Receiver elevation : 70.00 m  
Barrier elevation : 70.00 m  
Reference angle : 0.00

↑

Road data, segment # 2: GladstoneAve (day/night)

-----  
Car traffic volume : 9715/845 veh/TimePeriod \*  
Medium truck volume : 773/67 veh/TimePeriod \*  
Heavy truck volume : 552/48 veh/TimePeriod \*  
Posted speed limit : 50 km/h  
Road gradient : 0 %



Road pavement : 1 (Typical asphalt or concrete)

\* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 12000  
Percentage of Annual Growth : 0.00  
Number of Years of Growth : 0.00  
Medium Truck % of Total Volume : 7.00  
Heavy Truck % of Total Volume : 5.00  
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 2: GladstoneAve (day/night)

-----  
Angle1 Angle2 : -30.00 deg 32.00 deg  
Wood depth : 0 (No woods.)  
No of house rows : 1 / 1  
House density : 40 %  
Surface : 1 (Absorptive ground surface)  
Receiver source distance : 85.00 / 85.00 m  
Receiver height : 16.50 / 16.50 m  
Topography : 2 (Flat/gentle slope; with barrier)  
Barrier angle1 : -30.00 deg Angle2 : 32.00 deg  
Barrier height : 9.00 m  
Barrier receiver distance : 30.00 / 30.00 m  
Source elevation : 70.00 m  
Receiver elevation : 70.00 m  
Barrier elevation : 70.00 m  
Reference angle : 0.00

↑

Road data, segment # 3: Hwy 417 West (day/night)

-----  
Car traffic volume : 44527/3872 veh/TimePeriod \*  
Medium truck volume : 3542/308 veh/TimePeriod \*  
Heavy truck volume : 2530/220 veh/TimePeriod \*  
Posted speed limit : 100 km/h  
Road gradient : 0 %  
Road pavement : 1 (Typical asphalt or concrete)

\* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 54999  
Percentage of Annual Growth : 0.00  
Number of Years of Growth : 0.00  
Medium Truck % of Total Volume : 7.00  
Heavy Truck % of Total Volume : 5.00  
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 3: Hwy 417 West (day/night)

-----

Angle1 Angle2 : -21.00 deg 24.00 deg  
 Wood depth : 0 (No woods.)  
 No of house rows : 7 / 7  
 House density : 80 %  
 Surface : 1 (Absorptive ground surface)  
 Receiver source distance : 455.00 / 455.00 m  
 Receiver height : 16.50 / 16.50 m  
 Topography : 3 (Elevated; no barrier)  
 Elevation : 2.00 m  
 Reference angle : 0.00

↑

Road data, segment # 4: Hwy 417 East (day/night)

-----  
 Car traffic volume : 44527/3872 veh/TimePeriod \*  
 Medium truck volume : 3542/308 veh/TimePeriod \*  
 Heavy truck volume : 2530/220 veh/TimePeriod \*  
 Posted speed limit : 100 km/h  
 Road gradient : 0 %  
 Road pavement : 1 (Typical asphalt or concrete)

\* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 54999  
 Percentage of Annual Growth : 0.00  
 Number of Years of Growth : 0.00  
 Medium Truck % of Total Volume : 7.00  
 Heavy Truck % of Total Volume : 5.00  
 Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 4: Hwy 417 East (day/night)

-----  
 Angle1 Angle2 : -15.00 deg 19.00 deg  
 Wood depth : 0 (No woods.)  
 No of house rows : 7 / 7  
 House density : 80 %  
 Surface : 1 (Absorptive ground surface)  
 Receiver source distance : 470.00 / 470.00 m  
 Receiver height : 16.50 / 16.50 m  
 Topography : 3 (Elevated; no barrier)  
 Elevation : 2.00 m  
 Reference angle : 0.00

↑

Results segment # 1: O'Connor St (day)

-----  
 Source height = 1.50 m

Barrier height for grazing incidence

```

-----
Source      ! Receiver      ! Barrier      ! Elevation of
Height (m) ! Height (m) ! Height (m) ! Barrier Top (m)
-----+-----+-----+-----
          1.50 !         16.50 !         4.83 !         74.83

```

```

ROAD (0.00 + 43.99 + 0.00) = 43.99 dBA
Angle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq
-----+-----+-----+-----+-----+-----+-----+-----+-----+-----+-----
   -69     0   0.00  68.48   0.00  -4.77  -4.16   0.00   0.00 -15.56  43.99
-----+-----+-----+-----+-----+-----+-----+-----+-----+-----+-----

```

Segment Leq : 43.99 dBA

↑  
Results segment # 2: GladstoneAve (day)

Source height = 1.50 m

Barrier height for grazing incidence

```

-----
Source      ! Receiver      ! Barrier      ! Elevation of
Height (m) ! Height (m) ! Height (m) ! Barrier Top (m)
-----+-----+-----+-----
          1.50 !         16.50 !         11.20 !         81.20

```

```

ROAD (0.00 + 51.72 + 0.00) = 51.72 dBA
Angle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq
-----+-----+-----+-----+-----+-----+-----+-----+-----+-----+-----
  -30    32   0.21  67.51   0.00  -9.12  -4.67   0.00  -2.00   0.00  51.72
  -30    32   0.00  67.51   0.00  -7.53  -4.63   0.00   0.00   0.00  55.35*
  -30    32   0.21  67.51   0.00  -9.12  -4.67   0.00   0.00   0.00  53.72
-----+-----+-----+-----+-----+-----+-----+-----+-----+-----+-----

```

\* Bright Zone !

Segment Leq : 51.72 dBA

↑  
Results segment # 3: Hwy 417 West (day)

Source height = 1.50 m

```

ROAD (0.00 + 43.21 + 0.00) = 43.21 dBA
Angle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq
-----+-----+-----+-----+-----+-----+-----+-----+-----+-----+-----
  -21    24   0.15  80.15   0.00 -17.04  -6.04   0.00 -13.85   0.00  43.21
-----+-----+-----+-----+-----+-----+-----+-----+-----+-----+-----

```

Segment Leq : 43.21 dBA

↑  
Results segment # 4: Hwy 417 East (day)  
-----

Source height = 1.50 m

ROAD (0.00 + 41.87 + 0.00) = 41.87 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-15	19	0.15	80.15	0.00	-17.21	-7.25	0.00	-13.82	0.00	41.87

-----

Segment Leq : 41.87 dBA

Total Leq All Segments: 53.22 dBA

↑  
Results segment # 1: O'Connor St (night)  
-----

Source height = 1.50 m

Barrier height for grazing incidence  
-----

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50 !	16.50 !	4.83 !	74.83

ROAD (0.00 + 36.39 + 0.00) = 36.39 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-69	0	0.00	60.88	0.00	-4.77	-4.16	0.00	0.00	-15.56	36.39

-----

Segment Leq : 36.39 dBA

↑  
Results segment # 2: GladstoneAve (night)  
-----

Source height = 1.50 m

Barrier height for grazing incidence  
-----

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
-------------------	---------------------	--------------------	------------------------------

-----+-----+-----+-----  
 1.50 !            16.50 !            11.20 !            81.20

ROAD (0.00 + 44.12 + 0.00) = 44.12 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-30	32	0.21	59.91	0.00	-9.12	-4.67	0.00	-2.00	0.00	44.12
-30	32	0.00	59.91	0.00	-7.53	-4.63	0.00	0.00	0.00	47.75*
-30	32	0.21	59.91	0.00	-9.12	-4.67	0.00	0.00	0.00	46.12

\* Bright Zone !

Segment Leq : 44.12 dBA

↑  
 Results segment # 3: Hwy 417 West (night)

Source height = 1.50 m

ROAD (0.00 + 35.62 + 0.00) = 35.62 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-21	24	0.15	72.55	0.00	-17.04	-6.04	0.00	-13.85	0.00	35.62

Segment Leq : 35.62 dBA

↑  
 Results segment # 4: Hwy 417 East (night)

Source height = 1.50 m

ROAD (0.00 + 34.28 + 0.00) = 34.28 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-15	19	0.15	72.55	0.00	-17.21	-7.25	0.00	-13.82	0.00	34.28

Segment Leq : 34.28 dBA

Total Leq All Segments: 45.62 dBA

↑  
 TOTAL Leq FROM ALL SOURCES (DAY): 53.22

(NIGHT): 45.62



Filename: rec31.te                            Time Period: Day/Night 16/8 hours  
Description: Reception Point 3-1

Road data, segment # 1: O'Connor St (day/night)

-----  
Car traffic volume : 12144/1056 veh/TimePeriod \*  
Medium truck volume : 966/84 veh/TimePeriod \*  
Heavy truck volume : 690/60 veh/TimePeriod \*  
Posted speed limit : 50 km/h  
Road gradient : 0 %  
Road pavement : 1 (Typical asphalt or concrete)

\* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 15000  
Percentage of Annual Growth : 0.00  
Number of Years of Growth : 0.00  
Medium Truck % of Total Volume : 7.00  
Heavy Truck % of Total Volume : 5.00  
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 1: O'Connor St (day/night)

-----  
Angle1 Angle2 : -75.00 deg 80.00 deg  
Wood depth : 0 (No woods.)  
No of house rows : 1 / 1  
House density : 20 %  
Surface : 1 (Absorptive ground surface)  
Receiver source distance : 30.00 / 30.00 m  
Receiver height : 1.50 / 1.50 m  
Topography : 1 (Flat/gentle slope; no barrier)  
Reference angle : 0.00

↑

Road data, segment # 2: GladstoneAve (day/night)

-----  
Car traffic volume : 9715/845 veh/TimePeriod \*  
Medium truck volume : 773/67 veh/TimePeriod \*  
Heavy truck volume : 552/48 veh/TimePeriod \*  
Posted speed limit : 50 km/h  
Road gradient : 0 %  
Road pavement : 1 (Typical asphalt or concrete)

\* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 12000

Percentage of Annual Growth : 0.00  
 Number of Years of Growth : 0.00  
 Medium Truck % of Total Volume : 7.00  
 Heavy Truck % of Total Volume : 5.00  
 Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 2: GladstoneAve (day/night)

-----

Angle1 Angle2 : 0.00 deg 32.00 deg  
 Wood depth : 0 (No woods.)  
 No of house rows : 1 / 1  
 House density : 40 %  
 Surface : 1 (Absorptive ground surface)  
 Receiver source distance : 95.00 / 95.00 m  
 Receiver height : 1.50 / 1.50 m  
 Topography : 2 (Flat/gentle slope; with barrier)  
 Barrier angle1 : 0.00 deg Angle2 : 32.00 deg  
 Barrier height : 9.00 m  
 Barrier receiver distance : 40.00 / 40.00 m  
 Source elevation : 70.00 m  
 Receiver elevation : 70.00 m  
 Barrier elevation : 70.00 m  
 Reference angle : 0.00

↑

Road data, segment # 3: Hwy 417 West (day/night)

-----

Car traffic volume : 44527/3872 veh/TimePeriod \*  
 Medium truck volume : 3542/308 veh/TimePeriod \*  
 Heavy truck volume : 2530/220 veh/TimePeriod \*  
 Posted speed limit : 100 km/h  
 Road gradient : 0 %  
 Road pavement : 1 (Typical asphalt or concrete)

\* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 54999  
 Percentage of Annual Growth : 0.00  
 Number of Years of Growth : 0.00  
 Medium Truck % of Total Volume : 7.00  
 Heavy Truck % of Total Volume : 5.00  
 Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 3: Hwy 417 West (day/night)

-----

Angle1 Angle2 : 0.00 deg 22.00 deg  
 Wood depth : 0 (No woods.)  
 No of house rows : 7 / 7  
 House density : 80 %  
 Surface : 1 (Absorptive ground surface)



Receiver source distance : 475.00 / 475.00 m  
 Receiver height : 1.50 / 1.50 m  
 Topography : 3 (Elevated; no barrier)  
 Elevation : 2.00 m  
 Reference angle : 0.00

↑  
 Road data, segment # 4: Hwy 417 East (day/night)

-----  
 Car traffic volume : 44527/3872 veh/TimePeriod \*  
 Medium truck volume : 3542/308 veh/TimePeriod \*  
 Heavy truck volume : 2530/220 veh/TimePeriod \*  
 Posted speed limit : 100 km/h  
 Road gradient : 0 %  
 Road pavement : 1 (Typical asphalt or concrete)

\* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 54999  
 Percentage of Annual Growth : 0.00  
 Number of Years of Growth : 0.00  
 Medium Truck % of Total Volume : 7.00  
 Heavy Truck % of Total Volume : 5.00  
 Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 4: Hwy 417 East (day/night)

-----  
 Angle1 Angle2 : 0.00 deg 17.00 deg  
 Wood depth : 0 (No woods.)  
 No of house rows : 7 / 7  
 House density : 80 %  
 Surface : 1 (Absorptive ground surface)  
 Receiver source distance : 485.00 / 485.00 m  
 Receiver height : 1.50 / 1.50 m  
 Topography : 3 (Elevated; no barrier)  
 Elevation : 2.00 m  
 Reference angle : 0.00

↑  
 Results segment # 1: O'Connor St (day)

-----  
 Source height = 1.50 m

ROAD (0.00 + 60.93 + 0.00) = 60.93 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-75	80	0.66	68.48	0.00	-5.00	-1.65	0.00	-0.90	0.00	60.93

-----

Segment Leq : 60.93 dBA

↑

Results segment # 2: GladstoneAve (day)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	1.50	1.50	71.50

ROAD (0.00 + 32.80 + 0.00) = 32.80 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
0	32	0.66	67.51	0.00	-13.31	-7.65	0.00	-2.00	0.00	44.55
0	32	0.12	67.51	0.00	-8.98	-7.53	0.00	0.00	-18.21	32.80

Segment Leq : 32.80 dBA

↑

Results segment # 3: Hwy 417 West (day)

Source height = 1.50 m

ROAD (0.00 + 33.13 + 0.00) = 33.13 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
0	22	0.60	80.15	0.00	-24.01	-9.19	0.00	-13.81	0.00	33.13

Segment Leq : 33.13 dBA

↑

Results segment # 4: Hwy 417 East (day)

Source height = 1.50 m

ROAD (0.00 + 31.90 + 0.00) = 31.90 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
0	17	0.60	80.15	0.00	-24.16	-10.29	0.00	-13.80	0.00	31.90

Segment Leq : 31.90 dBA

Total Leq All Segments: 60.95 dBA

↑

Results segment # 1: O'Connor St (night)

Source height = 1.50 m

ROAD (0.00 + 53.34 + 0.00) = 53.34 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-75	80	0.66	60.88	0.00	-5.00	-1.65	0.00	-0.90	0.00	53.34

Segment Leq : 53.34 dBA

↑

Results segment # 2: GladstoneAve (night)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	1.50	1.50	71.50

ROAD (0.00 + 25.20 + 0.00) = 25.20 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
0	32	0.66	59.91	0.00	-13.31	-7.65	0.00	-2.00	0.00	36.95
0	32	0.12	59.91	0.00	-8.98	-7.53	0.00	0.00	-18.21	25.20

Segment Leq : 25.20 dBA

↑

Results segment # 3: Hwy 417 West (night)

Source height = 1.50 m

ROAD (0.00 + 25.54 + 0.00) = 25.54 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
0	22	0.60	72.55	0.00	-24.01	-9.19	0.00	-13.81	0.00	25.54

-----  
Segment Leq : 25.54 dBA

↑  
Results segment # 4: Hwy 417 East (night)  
-----

Source height = 1.50 m

ROAD (0.00 + 24.31 + 0.00) = 24.31 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
0	17	0.60	72.55	0.00	-24.16	-10.29	0.00	-13.80	0.00	24.31

-----

Segment Leq : 24.31 dBA

Total Leq All Segments: 53.36 dBA

↑

TOTAL Leq FROM ALL SOURCES (DAY): 60.95  
(NIGHT): 53.36

↑  
↑

Filename: rec36.te                            Time Period: Day/Night 16/8 hours  
Description: Reception Point 3-6

Road data, segment # 1: O'Connor St (day/night)

-----  
Car traffic volume : 12144/1056 veh/TimePeriod \*  
Medium truck volume : 966/84 veh/TimePeriod \*  
Heavy truck volume : 690/60 veh/TimePeriod \*  
Posted speed limit : 50 km/h  
Road gradient : 0 %  
Road pavement : 1 (Typical asphalt or concrete)

\* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 15000  
Percentage of Annual Growth : 0.00  
Number of Years of Growth : 0.00  
Medium Truck % of Total Volume : 7.00  
Heavy Truck % of Total Volume : 5.00  
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 1: O'Connor St (day/night)

-----  
Angle1 Angle2 : -75.00 deg 80.00 deg  
Wood depth : 0 (No woods.)  
No of house rows : 1 / 1  
House density : 20 %  
Surface : 1 (Absorptive ground surface)  
Receiver source distance : 30.00 / 30.00 m  
Receiver height : 16.50 / 16.50 m  
Topography : 1 (Flat/gentle slope; no barrier)  
Reference angle : 0.00

↑

Road data, segment # 2: GladstoneAve (day/night)

-----  
Car traffic volume : 9715/845 veh/TimePeriod \*  
Medium truck volume : 773/67 veh/TimePeriod \*  
Heavy truck volume : 552/48 veh/TimePeriod \*  
Posted speed limit : 50 km/h  
Road gradient : 0 %  
Road pavement : 1 (Typical asphalt or concrete)

\* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 12000

Percentage of Annual Growth : 0.00  
 Number of Years of Growth : 0.00  
 Medium Truck % of Total Volume : 7.00  
 Heavy Truck % of Total Volume : 5.00  
 Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 2: GladstoneAve (day/night)

-----

Angle1 Angle2 : 0.00 deg 32.00 deg  
 Wood depth : 0 (No woods.)  
 No of house rows : 1 / 1  
 House density : 40 %  
 Surface : 1 (Absorptive ground surface)  
 Receiver source distance : 95.00 / 95.00 m  
 Receiver height : 16.50 / 16.50 m  
 Topography : 2 (Flat/gentle slope; with barrier)  
 Barrier angle1 : 0.00 deg Angle2 : 32.00 deg  
 Barrier height : 9.00 m  
 Barrier receiver distance : 40.00 / 40.00 m  
 Source elevation : 70.00 m  
 Receiver elevation : 70.00 m  
 Barrier elevation : 70.00 m  
 Reference angle : 0.00

↑

Road data, segment # 3: Hwy 417 West (day/night)

-----

Car traffic volume : 44527/3872 veh/TimePeriod \*  
 Medium truck volume : 3542/308 veh/TimePeriod \*  
 Heavy truck volume : 2530/220 veh/TimePeriod \*  
 Posted speed limit : 100 km/h  
 Road gradient : 0 %  
 Road pavement : 1 (Typical asphalt or concrete)

\* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 54999  
 Percentage of Annual Growth : 0.00  
 Number of Years of Growth : 0.00  
 Medium Truck % of Total Volume : 7.00  
 Heavy Truck % of Total Volume : 5.00  
 Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 3: Hwy 417 West (day/night)

-----

Angle1 Angle2 : 0.00 deg 22.00 deg  
 Wood depth : 0 (No woods.)  
 No of house rows : 7 / 7  
 House density : 80 %  
 Surface : 1 (Absorptive ground surface)

Receiver source distance : 475.00 / 475.00 m  
 Receiver height : 16.50 / 16.50 m  
 Topography : 3 (Elevated; no barrier)  
 Elevation : 2.00 m  
 Reference angle : 0.00

↑  
 Road data, segment # 4: Hwy 417 East (day/night)

-----  
 Car traffic volume : 44527/3872 veh/TimePeriod \*  
 Medium truck volume : 3542/308 veh/TimePeriod \*  
 Heavy truck volume : 2530/220 veh/TimePeriod \*  
 Posted speed limit : 100 km/h  
 Road gradient : 0 %  
 Road pavement : 1 (Typical asphalt or concrete)

\* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 54999  
 Percentage of Annual Growth : 0.00  
 Number of Years of Growth : 0.00  
 Medium Truck % of Total Volume : 7.00  
 Heavy Truck % of Total Volume : 5.00  
 Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 4: Hwy 417 East (day/night)

-----  
 Angle1 Angle2 : 0.00 deg 17.00 deg  
 Wood depth : 0 (No woods.)  
 No of house rows : 7 / 7  
 House density : 80 %  
 Surface : 1 (Absorptive ground surface)  
 Receiver source distance : 485.00 / 485.00 m  
 Receiver height : 16.50 / 16.50 m  
 Topography : 3 (Elevated; no barrier)  
 Elevation : 2.00 m  
 Reference angle : 0.00

↑  
 Results segment # 1: O'Connor St (day)

-----  
 Source height = 1.50 m

ROAD (0.00 + 62.94 + 0.00) = 62.94 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-75	80	0.21	68.48	0.00	-3.64	-1.00	0.00	-0.90	0.00	62.94

-----

Segment Leq : 62.94 dBA

↑

Results segment # 2: GladstoneAve (day)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	16.50	10.18	80.18

ROAD (0.00 + 48.26 + 0.00) = 48.26 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
0	32	0.21	67.51	0.00	-9.70	-7.55	0.00	-2.00	0.00	48.26
0	32	0.00	67.51	0.00	-8.02	-7.50	0.00	0.00	-3.34	48.66*
0	32	0.21	67.51	0.00	-9.70	-7.55	0.00	0.00	0.00	50.26

\* Bright Zone !

Segment Leq : 48.26 dBA

↑

Results segment # 3: Hwy 417 West (day)

Source height = 1.50 m

ROAD (0.00 + 39.93 + 0.00) = 39.93 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
0	22	0.15	80.15	0.00	-17.26	-9.14	0.00	-13.81	0.00	39.93

Segment Leq : 39.93 dBA

↑

Results segment # 4: Hwy 417 East (day)

Source height = 1.50 m

ROAD (0.00 + 38.73 + 0.00) = 38.73 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
--------	--------	-------	--------	-------	-------	-------	-------	-------	-------	--------



0 17 0.15 80.15 0.00 -17.36 -10.26 0.00 -13.80 0.00 38.73

-----  
Segment Leq : 38.73 dBA

Total Leq All Segments: 63.12 dBA

↑  
Results segment # 1: O'Connor St (night)

-----  
Source height = 1.50 m

ROAD (0.00 + 55.34 + 0.00) = 55.34 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-75	80	0.21	60.88	0.00	-3.64	-1.00	0.00	-0.90	0.00	55.34

-----  
Segment Leq : 55.34 dBA

↑  
Results segment # 2: GladstoneAve (night)

-----  
Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	16.50	10.18	80.18

ROAD (0.00 + 40.66 + 0.00) = 40.66 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
0	32	0.21	59.91	0.00	-9.70	-7.55	0.00	-2.00	0.00	40.66
0	32	0.00	59.91	0.00	-8.02	-7.50	0.00	0.00	-3.34	41.06*
0	32	0.21	59.91	0.00	-9.70	-7.55	0.00	0.00	0.00	42.66

-----  
\* Bright Zone !

Segment Leq : 40.66 dBA

↑  
Results segment # 3: Hwy 417 West (night)

Source height = 1.50 m

ROAD (0.00 + 32.34 + 0.00) = 32.34 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
0	22	0.15	72.55	0.00	-17.26	-9.14	0.00	-13.81	0.00	32.34

Segment Leq : 32.34 dBA

↑  
Results segment # 4: Hwy 417 East (night)

Source height = 1.50 m

ROAD (0.00 + 31.13 + 0.00) = 31.13 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
0	17	0.15	72.55	0.00	-17.36	-10.26	0.00	-13.80	0.00	31.13

Segment Leq : 31.13 dBA

Total Leq All Segments: 55.52 dBA

↑  
TOTAL Leq FROM ALL SOURCES (DAY): 63.12  
(NIGHT): 55.52

↑  
↑

Filename: rec41.te                            Time Period: Day/Night 16/8 hours  
 Description: Reception Point 4-1

Road data, segment # 1: O'Connor St (day/night)

-----  
 Car traffic volume : 12144/1056 veh/TimePeriod \*  
 Medium truck volume : 966/84 veh/TimePeriod \*  
 Heavy truck volume : 690/60 veh/TimePeriod \*  
 Posted speed limit : 50 km/h  
 Road gradient : 0 %  
 Road pavement : 1 (Typical asphalt or concrete)

\* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 15000  
 Percentage of Annual Growth : 0.00  
 Number of Years of Growth : 0.00  
 Medium Truck % of Total Volume : 7.00  
 Heavy Truck % of Total Volume : 5.00  
 Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 1: O'Connor St (day/night)

-----  
 Angle1 Angle2 : 0.00 deg 73.00 deg  
 Wood depth : 0 (No woods.)  
 No of house rows : 1 / 1  
 House density : 20 %  
 Surface : 1 (Absorptive ground surface)  
 Receiver source distance : 45.00 / 45.00 m  
 Receiver height : 1.50 / 1.50 m  
 Topography : 1 (Flat/gentle slope; no barrier)  
 Reference angle : 0.00

↑  
 Results segment # 1: O'Connor St (day)

-----  
 Source height = 1.50 m

ROAD (0.00 + 54.87 + 0.00) = 54.87 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
0	73	0.66	68.48	0.00	-7.92	-4.79	0.00	-0.90	0.00	54.87

-----  
 Segment Leq : 54.87 dBA

Total Leq All Segments: 54.87 dBA

↑

Results segment # 1: O'Connor St (night)

-----

Source height = 1.50 m

ROAD (0.00 + 47.28 + 0.00) = 47.28 dBA

Angle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq

-----

0	73	0.66	60.88	0.00	-7.92	-4.79	0.00	-0.90	0.00	47.28
---	----	------	-------	------	-------	-------	------	-------	------	-------

-----

Segment Leq : 47.28 dBA

Total Leq All Segments: 47.28 dBA

↑

TOTAL Leq FROM ALL SOURCES (DAY): 54.87

(NIGHT): 47.28

↑

↑

Filename: rec46.te                            Time Period: Day/Night 16/8 hours  
 Description: Reception Point 4-6

Road data, segment # 1: O'Connor St (day/night)

```
-----
Car traffic volume   : 12144/1056  veh/TimePeriod  *
Medium truck volume :   966/84    veh/TimePeriod  *
Heavy truck volume  :   690/60    veh/TimePeriod  *
Posted speed limit  :    50 km/h
Road gradient       :     0 %
Road pavement      :     1 (Typical asphalt or concrete)
```

\* Refers to calculated road volumes based on the following input:

```
24 hr Traffic Volume (AADT or SADT): 15000
Percentage of Annual Growth         :   0.00
Number of Years of Growth           :   0.00
Medium Truck % of Total Volume      :   7.00
Heavy Truck % of Total Volume       :   5.00
Day (16 hrs) % of Total Volume      :  92.00
```

Data for Segment # 1: O'Connor St (day/night)

```
-----
Angle1  Angle2      :   0.00 deg   73.00 deg
Wood depth          :     0      (No woods.)
No of house rows    :     1 / 1
House density       :    20 %
Surface             :     1      (Absorptive ground surface)
Receiver source distance : 45.00 / 45.00 m
Receiver height     :  16.50 / 16.50 m
Topography          :     1      (Flat/gentle slope; no barrier)
Reference angle     :     0.00
```

↑  
 Results segment # 1: O'Connor St (day)

Source height = 1.50 m

ROAD (0.00 + 57.59 + 0.00) = 57.59 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
0	73	0.21	68.48	0.00	-5.77	-4.22	0.00	-0.90	0.00	57.59

Segment Leq : 57.59 dBA

Total Leq All Segments: 57.59 dBA

↑

Results segment # 1: O'Connor St (night)

-----

Source height = 1.50 m

ROAD (0.00 + 49.99 + 0.00) = 49.99 dBA

Angle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq

-----

0	73	0.21	60.88	0.00	-5.77	-4.22	0.00	-0.90	0.00	49.99
---	----	------	-------	------	-------	-------	------	-------	------	-------

-----

Segment Leq : 49.99 dBA

Total Leq All Segments: 49.99 dBA

↑

TOTAL Leq FROM ALL SOURCES (DAY): 57.59

(NIGHT): 49.99

↑

↑

Filename: rec5.te                            Time Period: Day/Night 16/8 hours  
Description: Reception Point 5

Road data, segment # 1: O'Connor St (day/night)

-----  
Car traffic volume : 12144/1056 veh/TimePeriod \*  
Medium truck volume : 966/84 veh/TimePeriod \*  
Heavy truck volume : 690/60 veh/TimePeriod \*  
Posted speed limit : 50 km/h  
Road gradient : 0 %  
Road pavement : 1 (Typical asphalt or concrete)

\* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 15000  
Percentage of Annual Growth : 0.00  
Number of Years of Growth : 0.00  
Medium Truck % of Total Volume : 7.00  
Heavy Truck % of Total Volume : 5.00  
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 1: O'Connor St (day/night)

-----  
Angle1 Angle2 : -71.00 deg 76.00 deg  
Wood depth : 0 (No woods.)  
No of house rows : 1 / 1  
House density : 20 %  
Surface : 1 (Absorptive ground surface)  
Receiver source distance : 45.00 / 45.00 m  
Receiver height : 19.50 / 19.50 m  
Topography : 1 (Flat/gentle slope; no barrier)  
Reference angle : 0.00

↑

Road data, segment # 2: GladstoneAve (day/night)

-----  
Car traffic volume : 9715/845 veh/TimePeriod \*  
Medium truck volume : 773/67 veh/TimePeriod \*  
Heavy truck volume : 552/48 veh/TimePeriod \*  
Posted speed limit : 50 km/h  
Road gradient : 0 %  
Road pavement : 1 (Typical asphalt or concrete)

\* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 12000

Percentage of Annual Growth : 0.00  
 Number of Years of Growth : 0.00  
 Medium Truck % of Total Volume : 7.00  
 Heavy Truck % of Total Volume : 5.00  
 Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 2: GladstoneAve (day/night)

-----

Angle1 Angle2 : -26.00 deg 34.00 deg  
 Wood depth : 0 (No woods.)  
 No of house rows : 1 / 1  
 House density : 40 %  
 Surface : 1 (Absorptive ground surface)  
 Receiver source distance : 95.00 / 95.00 m  
 Receiver height : 19.50 / 19.50 m  
 Topography : 2 (Flat/gentle slope; with barrier)  
 Barrier angle1 : -26.00 deg Angle2 : 34.00 deg  
 Barrier height : 9.00 m  
 Barrier receiver distance : 40.00 / 40.00 m  
 Source elevation : 70.00 m  
 Receiver elevation : 70.00 m  
 Barrier elevation : 70.00 m  
 Reference angle : 0.00

↑

Road data, segment # 3: Hwy 417 West (day/night)

-----

Car traffic volume : 44527/3872 veh/TimePeriod \*  
 Medium truck volume : 3542/308 veh/TimePeriod \*  
 Heavy truck volume : 2530/220 veh/TimePeriod \*  
 Posted speed limit : 100 km/h  
 Road gradient : 0 %  
 Road pavement : 1 (Typical asphalt or concrete)

\* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 54999  
 Percentage of Annual Growth : 0.00  
 Number of Years of Growth : 0.00  
 Medium Truck % of Total Volume : 7.00  
 Heavy Truck % of Total Volume : 5.00  
 Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 3: Hwy 417 West (day/night)

-----

Angle1 Angle2 : -20.00 deg 22.00 deg  
 Wood depth : 0 (No woods.)  
 No of house rows : 7 / 7  
 House density : 80 %  
 Surface : 1 (Absorptive ground surface)



Receiver source distance : 460.00 / 460.00 m  
 Receiver height : 19.50 / 19.50 m  
 Topography : 3 (Elevated; no barrier)  
 Elevation : 2.00 m  
 Reference angle : 0.00

↑  
 Road data, segment # 4: Hwy 417 East (day/night)

-----  
 Car traffic volume : 44527/3872 veh/TimePeriod \*  
 Medium truck volume : 3542/308 veh/TimePeriod \*  
 Heavy truck volume : 2530/220 veh/TimePeriod \*  
 Posted speed limit : 100 km/h  
 Road gradient : 0 %  
 Road pavement : 1 (Typical asphalt or concrete)

\* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 54999  
 Percentage of Annual Growth : 0.00  
 Number of Years of Growth : 0.00  
 Medium Truck % of Total Volume : 7.00  
 Heavy Truck % of Total Volume : 5.00  
 Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 4: Hwy 417 East (day/night)

-----  
 Angle1 Angle2 : -15.00 deg 17.00 deg  
 Wood depth : 0 (No woods.)  
 No of house rows : 7 / 7  
 House density : 80 %  
 Surface : 1 (Absorptive ground surface)  
 Receiver source distance : 475.00 / 475.00 m  
 Receiver height : 19.50 / 19.50 m  
 Topography : 3 (Elevated; no barrier)  
 Elevation : 2.00 m  
 Reference angle : 0.00

↑  
 Results segment # 1: O'Connor St (day)

-----  
 Source height = 1.50 m

ROAD (0.00 + 61.18 + 0.00) = 61.18 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-71	76	0.12	68.48	0.00	-5.34	-1.06	0.00	-0.90	0.00	61.18

-----

Segment Leq : 61.18 dBA

↑

Results segment # 2: GladstoneAve (day)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	19.50	11.92	81.92

ROAD (0.00 + 51.73 + 0.00) = 51.73 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-26	34	0.12	67.51	0.00	-8.98	-4.80	0.00	-2.00	0.00	51.73
-26	34	0.00	67.51	0.00	-8.02	-4.77	0.00	0.00	0.00	54.72*
-26	34	0.12	67.51	0.00	-8.98	-4.80	0.00	0.00	0.00	53.73

\* Bright Zone !

Segment Leq : 51.73 dBA

↑

Results segment # 3: Hwy 417 West (day)

Source height = 1.50 m

ROAD (0.00 + 44.22 + 0.00) = 44.22 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-20	22	0.06	80.15	0.00	-15.76	-6.33	0.00	-13.84	0.00	44.22

Segment Leq : 44.22 dBA

↑

Results segment # 4: Hwy 417 East (day)

Source height = 1.50 m

ROAD (0.00 + 42.92 + 0.00) = 42.92 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
--------	--------	-------	--------	-------	-------	-------	-------	-------	-------	--------

-15 17 0.06 80.15 0.00 -15.91 -7.50 0.00 -13.81 0.00 42.92

-----  
Segment Leq : 42.92 dBA

Total Leq All Segments: 61.78 dBA

↑  
Results segment # 1: O'Connor St (night)

-----  
Source height = 1.50 m

ROAD (0.00 + 53.58 + 0.00) = 53.58 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-71	76	0.12	60.88	0.00	-5.34	-1.06	0.00	-0.90	0.00	53.58

-----  
Segment Leq : 53.58 dBA

↑  
Results segment # 2: GladstoneAve (night)

-----  
Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	19.50	11.92	81.92

ROAD (0.00 + 44.14 + 0.00) = 44.14 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-26	34	0.12	59.91	0.00	-8.98	-4.80	0.00	-2.00	0.00	44.14
-26	34	0.00	59.91	0.00	-8.02	-4.77	0.00	0.00	0.00	47.12*
-26	34	0.12	59.91	0.00	-8.98	-4.80	0.00	0.00	0.00	46.14

-----  
\* Bright Zone !

Segment Leq : 44.14 dBA

↑  
Results segment # 3: Hwy 417 West (night)

Source height = 1.50 m

ROAD (0.00 + 36.62 + 0.00) = 36.62 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-20	22	0.06	72.55	0.00	-15.76	-6.33	0.00	-13.84	0.00	36.62

Segment Leq : 36.62 dBA

↑

Results segment # 4: Hwy 417 East (night)

Source height = 1.50 m

ROAD (0.00 + 35.33 + 0.00) = 35.33 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-15	17	0.06	72.55	0.00	-15.91	-7.50	0.00	-13.81	0.00	35.33

Segment Leq : 35.33 dBA

Total Leq All Segments: 54.18 dBA

↑

TOTAL Leq FROM ALL SOURCES (DAY): 61.78  
(NIGHT): 54.18

↑

↑

Filename: rec5tr.te                    Time Period: Day/Night 16/8 hours  
Description: Reception Point 5 - with building effects

Road data, segment # 1: O'Connor St (day/night)

-----  
Car traffic volume : 12144/1056 veh/TimePeriod \*  
Medium truck volume : 966/84 veh/TimePeriod \*  
Heavy truck volume : 690/60 veh/TimePeriod \*  
Posted speed limit : 50 km/h  
Road gradient : 0 %  
Road pavement : 1 (Typical asphalt or concrete)

\* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 15000  
Percentage of Annual Growth : 0.00  
Number of Years of Growth : 0.00  
Medium Truck % of Total Volume : 7.00  
Heavy Truck % of Total Volume : 5.00  
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 1: O'Connor St (day/night)

-----  
Angle1 Angle2 : -71.00 deg 76.00 deg  
Wood depth : 0 (No woods.)  
No of house rows : 1 / 1  
House density : 20 %  
Surface : 1 (Absorptive ground surface)  
Receiver source distance : 45.00 / 45.00 m  
Receiver height : 19.50 / 19.50 m  
Topography : 2 (Flat/gentle slope; with barrier)  
Barrier angle1 : -71.00 deg Angle2 : 76.00 deg  
Barrier height : 19.00 m  
Barrier receiver distance : 10.00 / 10.00 m  
Source elevation : 70.00 m  
Receiver elevation : 70.00 m  
Barrier elevation : 70.00 m  
Reference angle : 0.00

↑

Road data, segment # 2: GladstoneAve (day/night)

-----  
Car traffic volume : 9715/845 veh/TimePeriod \*  
Medium truck volume : 773/67 veh/TimePeriod \*  
Heavy truck volume : 552/48 veh/TimePeriod \*  
Posted speed limit : 50 km/h

Road gradient : 0 %  
Road pavement : 1 (Typical asphalt or concrete)

\* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 12000  
Percentage of Annual Growth : 0.00  
Number of Years of Growth : 0.00  
Medium Truck % of Total Volume : 7.00  
Heavy Truck % of Total Volume : 5.00  
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 2: GladstoneAve (day/night)

-----  
Angle1 Angle2 : -26.00 deg 34.00 deg  
Wood depth : 0 (No woods.)  
No of house rows : 1 / 1  
House density : 40 %  
Surface : 1 (Absorptive ground surface)  
Receiver source distance : 95.00 / 95.00 m  
Receiver height : 19.50 / 19.50 m  
Topography : 2 (Flat/gentle slope; with barrier)  
Barrier angle1 : -26.00 deg Angle2 : 34.00 deg  
Barrier height : 19.00 m  
Barrier receiver distance : 10.00 / 10.00 m  
Source elevation : 70.00 m  
Receiver elevation : 70.00 m  
Barrier elevation : 70.00 m  
Reference angle : 0.00

↑

Road data, segment # 3: Hwy 417 West (day/night)

-----  
Car traffic volume : 44527/3872 veh/TimePeriod \*  
Medium truck volume : 3542/308 veh/TimePeriod \*  
Heavy truck volume : 2530/220 veh/TimePeriod \*  
Posted speed limit : 100 km/h  
Road gradient : 0 %  
Road pavement : 1 (Typical asphalt or concrete)

\* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 54999  
Percentage of Annual Growth : 0.00  
Number of Years of Growth : 0.00  
Medium Truck % of Total Volume : 7.00  
Heavy Truck % of Total Volume : 5.00  
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 3: Hwy 417 West (day/night)

```

-----
Angle1   Angle2       : -20.00 deg   22.00 deg
Wood depth      :      0      (No woods.)
No of house rows :      7 / 7
House density   :      80 %
Surface        :      1      (Absorptive ground surface)
Receiver source distance : 460.00 / 460.00 m
Receiver height : 19.50 / 19.50 m
Topography     :      2      (Flat/gentle slope; with barrier)
Barrier angle1 : -20.00 deg   Angle2 : 22.00 deg
Barrier height  : 19.00 m
Barrier receiver distance : 10.00 / 10.00 m
Source elevation : 72.00 m
Receiver elevation : 70.00 m
Barrier elevation : 70.00 m
Reference angle : 0.00

```

↑

Road data, segment # 4: Hwy 417 East (day/night)

```

-----
Car traffic volume : 44527/3872 veh/TimePeriod *
Medium truck volume : 3542/308 veh/TimePeriod *
Heavy truck volume : 2530/220 veh/TimePeriod *
Posted speed limit : 100 km/h
Road gradient      : 0 %
Road pavement     : 1 (Typical asphalt or concrete)

```

\* Refers to calculated road volumes based on the following input:

```

24 hr Traffic Volume (AADT or SADT): 54999
Percentage of Annual Growth      : 0.00
Number of Years of Growth       : 0.00
Medium Truck % of Total Volume   : 7.00
Heavy Truck % of Total Volume    : 5.00
Day (16 hrs) % of Total Volume   : 92.00

```

Data for Segment # 4: Hwy 417 East (day/night)

```

-----
Angle1   Angle2       : -15.00 deg   17.00 deg
Wood depth      :      0      (No woods.)
No of house rows :      7 / 7
House density   :      80 %
Surface        :      1      (Absorptive ground surface)
Receiver source distance : 475.00 / 475.00 m
Receiver height : 19.50 / 19.50 m
Topography     :      2      (Flat/gentle slope; with barrier)
Barrier angle1 : -15.00 deg   Angle2 : 17.00 deg
Barrier height  : 19.00 m
Barrier receiver distance : 10.00 / 10.00 m
Source elevation : 72.00 m

```

Receiver elevation : 70.00 m  
 Barrier elevation : 70.00 m  
 Reference angle : 0.00

↑  
 Results segment # 1: O'Connor St (day)

-----  
 Source height = 1.50 m

Barrier height for grazing incidence

-----  
 Source ! Receiver ! Barrier ! Elevation of  
 Height (m) ! Height (m) ! Height (m) ! Barrier Top (m)  
 -----+-----+-----+-----  
 1.50 ! 19.50 ! 15.50 ! 85.50

ROAD (0.00 + 48.58 + 0.00) = 48.58 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-71	76	0.12	68.48	0.00	-5.34	-1.06	0.00	-0.90	0.00	61.18
-71	76	0.00	68.48	0.00	-4.77	-0.88	0.00	0.00	-14.24	48.58

-----

Segment Leq : 48.58 dBA

↑  
 Results segment # 2: GladstoneAve (day)

-----  
 Source height = 1.50 m

Barrier height for grazing incidence

-----  
 Source ! Receiver ! Barrier ! Elevation of  
 Height (m) ! Height (m) ! Height (m) ! Barrier Top (m)  
 -----+-----+-----+-----  
 1.50 ! 19.50 ! 17.60 ! 87.60

ROAD (0.00 + 45.93 + 0.00) = 45.93 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-26	34	0.12	67.51	0.00	-8.98	-4.80	0.00	-2.00	0.00	51.73
-26	34	0.00	67.51	0.00	-8.02	-4.77	0.00	0.00	-8.79	45.93

-----

Segment Leq : 45.93 dBA

↑  
 Results segment # 3: Hwy 417 West (day)



-----  
Source height = 1.50 m

Barrier height for grazing incidence  
-----

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	19.50	19.15	89.15

ROAD (0.00 + 43.32 + 0.00) = 43.32 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-20	22	0.12	80.15	0.00	-16.65	-6.33	0.00	-13.84	0.00	43.32
-20	22	0.00	80.15	0.00	-14.87	-6.32	0.00	0.00	-4.94	54.02*
-20	22	0.12	80.15	0.00	-16.65	-6.33	0.00	0.00	0.00	57.16

-----  
\* Bright Zone !

Segment Leq : 43.32 dBA

↑

Results segment # 4: Hwy 417 East (day)  
-----

Source height = 1.50 m

Barrier height for grazing incidence  
-----

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	19.50	19.16	89.16

ROAD (0.00 + 42.02 + 0.00) = 42.02 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-15	17	0.12	80.15	0.00	-16.81	-7.51	0.00	-13.81	0.00	42.02
-15	17	0.00	80.15	0.00	-15.01	-7.50	0.00	0.00	-4.93	52.71*
-15	17	0.12	80.15	0.00	-16.81	-7.51	0.00	0.00	0.00	55.83

-----  
\* Bright Zone !

Segment Leq : 42.02 dBA

Total Leq All Segments: 51.72 dBA

↑  
Results segment # 1: O'Connor St (night)

-----  
Source height = 1.50 m

Barrier height for grazing incidence

-----  
Source           ! Receiver       ! Barrier       ! Elevation of  
Height (m) ! Height (m) ! Height (m) ! Barrier Top (m)  
-----+-----+-----+-----  
          1.50 !       19.50 !       15.50 !       85.50

ROAD (0.00 + 40.99 + 0.00) = 40.99 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-71	76	0.12	60.88	0.00	-5.34	-1.06	0.00	-0.90	0.00	53.58
-71	76	0.00	60.88	0.00	-4.77	-0.88	0.00	0.00	-14.24	40.99

-----

Segment Leq : 40.99 dBA

↑  
Results segment # 2: GladstoneAve (night)

-----  
Source height = 1.50 m

Barrier height for grazing incidence

-----  
Source           ! Receiver       ! Barrier       ! Elevation of  
Height (m) ! Height (m) ! Height (m) ! Barrier Top (m)  
-----+-----+-----+-----  
          1.50 !       19.50 !       17.60 !       87.60

ROAD (0.00 + 38.33 + 0.00) = 38.33 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-26	34	0.12	59.91	0.00	-8.98	-4.80	0.00	-2.00	0.00	44.14
-26	34	0.00	59.91	0.00	-8.02	-4.77	0.00	0.00	-8.79	38.33

-----

Segment Leq : 38.33 dBA

↑  
Results segment # 3: Hwy 417 West (night)

-----  
Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	19.50	19.15	89.15

ROAD (0.00 + 35.72 + 0.00) = 35.72 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-20	22	0.12	72.55	0.00	-16.65	-6.33	0.00	-13.84	0.00	35.72
-20	22	0.00	72.55	0.00	-14.87	-6.32	0.00	0.00	-4.94	46.42*
-20	22	0.12	72.55	0.00	-16.65	-6.33	0.00	0.00	0.00	49.57

\* Bright Zone !

Segment Leq : 35.72 dBA

↑

Results segment # 4: Hwy 417 East (night)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	19.50	19.16	89.16

ROAD (0.00 + 34.42 + 0.00) = 34.42 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-15	17	0.12	72.55	0.00	-16.81	-7.51	0.00	-13.81	0.00	34.42
-15	17	0.00	72.55	0.00	-15.01	-7.50	0.00	0.00	-4.93	45.11*
-15	17	0.12	72.55	0.00	-16.81	-7.51	0.00	0.00	0.00	48.23

\* Bright Zone !

Segment Leq : 34.42 dBA

Total Leq All Segments: 44.13 dBA

↑

TOTAL Leq FROM ALL SOURCES (DAY): 51.72  
(NIGHT): 44.13

