Proposed Residential Use Building			
Required	Proposed		
450 m2	611.6		
15 metres.	30.43		
14.5 metres.	22.11		
4.5 metres or			
Section 144 1			
	4.76		
corresponding yard setback abutting the street(s).			
the Residential subzone in which the lot is located.			
- Varies1			
- 1.5m for the first 18 metres back from the street 7.5	0.685		
metres for the remainder, to a maximum 7.5 metres,			
- Varies4			
	5.92		
need not exceed 7.5 m.			
- 6 m2/unit with minimum of 50% communal			
- Total = 6 * 150 = 900 m2	462.89		
- Communal = 450 m2			
200/ of total lat are a	000.00		
	222.80		
	N1/A		
required rear yard.	N/A		
- Any part of the rear yard not occupied by accessory			
buildings and structures, permitted projections, bicycle			
and permitted driveways, parking aisles and parking			
spaces, must be sorily landscaped.			
- At least 50 per cent of the rear yard must be landscaped	21.8		
and,			
- in all cases, must comprise at least one aggregated			
longer dimension is not more than twice its shorter			
dimension, for the purposes of tree planting.			
- Any part of any yard other than the rear yard not occupied			
by accessory buildings and structures, permitted			
	99.54		
walkways, permitted driveways and parking exclusion			
	72.2		
with a width of 12 metres or more.	12.2		
- Minimum 40% soft landscaped area.	2.21		
- The front yard and corner side yard must be equipped with			
solid, permanent fixtures sufficient to prevent motor vehicle	N/A		
parking in contravention of this By-law.			
- At least one principal entrance to a ground-floor unit or to a			
facade and provide direct access to the street.			
- In the case of a lot of 24 metres width or greater, one	1		
principal entrance is required for every 12 metres of lot			
width or part thereof.			
- The front facade must comprise at least 25 per cent	138.14		
windows.	130.14		
- At least 20 per cent of the area of the front facade must be			
7 7	64.6%		
- at least 25 per cent of dwelling units must have at least	Providing 0 2-bedrom units.		
two bedrooms.	dilito.		
- Minimum 1.2 metres in width;	2		
- Where a walkway extends from the right-of-way it must be			
separated from any driveway by at least 0.6m of soft			
landscaping.			
- The width of a walkway may not exceed: 1.8 m.	4.7		
- A walkway giving access to a storage area for			
containerized waste may not exceed 2.2m in width.			
	Required  450 m2  15 metres.  14.5 metres.  4.5 metres.  5. Section 144.1:  - In the case of an interior lot or through lot, the yard setback must align with the average of the abutting lots' corresponding yard setback abutting the street(s).  - Despite the foregoing, the minimum front and/or corner side yard setback need not exceed the minimum required in the Residential subzone in which the lot is located.  - Varies1  - 1.5m for the first 18 metres back from the street 7.5 metres for the remainder, to a maximum 7.5 metres,  - Varies4  - Minimum rear yard setback is 25% of the lot depth which must comprise at least 25% of the area of the lot, however it need not exceed 7.5 m.  - 6 m2/unit with minimum of 50% communal  - Total = 6 * 150 = 900 m2  - Communal = 450 m2  - 30% of total lot area.  - Exit stairs providing required egress under the Building Code may project a maximum of 2.2 metres into the required reary avard.  - Any part of the rear yard not occupied by accessory buildings and structures, permitted projections, bicycle parking and alsies, hardscaped paths of travel for waste and recycling management, pedestrian walkways, patios, and permitted driveways, parking aisles and parking spaces, must be softly landscaped.  - At least 50 per cent of the rear yard must be landscaped and;  - in all cases, must comprise at least one aggregated rectangular area of at least 25 square metres and whose longer dimension is not more than twice its shorter dimension, for the purposes of tree planting.  - Any part of any yard other than the rear yard not occupied by accessory buildings and structures, permitted projections, bicycle parking and aisles, hardscaped paths of travel for waste and recycling management, pedestrian wallways, permitted driveways and parking exclusion fixtures per (e) must be softly landscaped.  - Any part of any yard other than the rear yard not occupied by accessory buildings and structures, permitted projections, bicycle parking and aisles, hardscaped paths of travel for waste and recycling m		

1 SITE PLAN.
1:100

Zoning in	formation :Residential Fourth Density, Subzone UD			
Parking Requirements				
Provision	Required	Proposed		
Min. Residential Vehicle Parking (Area Y)	Low-rise Apartment: - No spaces for the first 12 units; then 0.5 spaces per dwelling unit= 9.5	0		
Min. Visitor Parking	Low-rise Apartment: - No spaces for the first 12 units on a lot; then 0.1 spaces per dwelling unit (no more than 30 spaces per building required = 2.0	0		
Min. Residential Bicycle Parking	- 0.5 spaces/unit = 14	17		
Bicycle Parking Access Route (m)	- Minimum of 1.5 metres.	1.70 to 1.6		
Bicycle Parking Orientation	- 50% vertical or stacked and the remainder horizontal.	100% Horizontal		
Bicycle Space Dimensions (Vertical)	- Min Width: 0.5 metres. - Min Length: 1.5 metres.	N/A		
Aisle and Driveway Width	<ul> <li>m minimum for a double traffic lane leading to a parking garage or lot.</li> <li>6.7 m minimum aisle for parking garage or lot serving non-residential uses.</li> </ul>	N/A		
Driveway Width (Table 139.3)	<ul> <li>Maximum width of a shared driveway is 3m.</li> <li>Maximum width of a double-wise driveway is 5.5 metres to 6 metres.</li> </ul>	N/P		
Loading Space	- No loading space required for residential uses.			
Parking Lot Landscaping	<ul> <li>A minimum of 15% of the area must be provided as perimeter or interior landscaped area.</li> <li>In addition to the landscaped buffer, interior landscaping may be provided including various landscaped islands, landscaped medians, pedestrian pathways, or public plazas to meet the minimum 15% requirement.</li> </ul>	N/A		
Parking Lot Landscape Buffer	- Abutting a street: 3 metres All other areas: 1.5 metres.	N/A		

END

LEGAL DESCRIPTION:

LOT 9 (South Side of Waverly Street)
REGISTERED PLAN No. 12
CITY OF OTTAWA

NOTE: THIS DRAWING IS THE PROPERTY OF THE ARCHITECT AND MAY NOT BE REPRODUCED OR USED WITHOUT THE EXPRESSED CONSENT OF THE ARCHITECT. THE CONTRACTOR SHALL CHECK AND VERIFY ALL DIMENSIONS AND REPORT ANY OMISSIONS OR DISCREPANCIES TO THE ARCHITECT BEFORE PROCEEDING WITH THE WORK.

DO NOT SCALE THE DRAWINGS

RE	RELEASE / REVISION RECORD		
No.	Description	Date	
1	ISSUED FOR PRECONSULATION	19-10-21	
2	ISSUED FOR COORDINATION	20-07-23	
3	ISSUED FOR COORDINATION	20-10-22	
4	ISSUED FOR COORDINATION	21-04-29	
5	ISSUED FOR FOTENN REVIEW	21-08-31	
6	ISSUED FOR FOTENN/SUBMISSION	21-09-09	

PROJECT NORTH

MAY NOT BE USED FOR CONSTRUCTION UNTIL SIGNED BY THE ARCHITECT

chmiel architects
200 - 109 Bank Street
Ottawa ON K1P 5N5
t (613) 234-3585
f (613) 234-6224

WAVERLEY APARTMENTS

322 WAVERLEY STREET

PROJECT NO. DRAWN

19-1805 JA

1:100 RC
WINGTITLE
SITE PLAN

SHE PLAN

SP-01

