

Honeywell Works Inc.

2966 Stagecoach Road

Osgoode, ON K0A 2W0

Office: (613) 821-9500

Mobile: (613) 298-7331

SEPTIC INSPECTION

SITE ADDRESS: 1353 Coker Street
Greely, ON K4P 1A1

TANK:


- Septic tanks lids were exposed and opened
- Inlet and Outlet Baffles are in good condition
- Tank and lids are in good condition
- Tank appears to be a 2700L concrete tank
- The effluent level was at the proper height in tank

TILE BED:

- The tile bed was probed and consists of a filter media bed of 6 runs, 6 meters each
- Test holes was dug and exposed the stone layer and the 3" PVC pipe
- No effluent was found in the stone or pipe area indication that the effluent is seeping into the sand filter as it is designed to
- There was no biomat found in the sand or stone area

FINDINGS:

- The tank and septic system appear to be in good working order, although level of usage is undetermined in the months prior to inspection
- The septic bed was found to be covered with 2 ½ feet of fill, whereas the maximum depth of cover should fall between 1 and 2 feet over pipes.



Paul Honeywell

Paul Honeywell

Chief Inspector

Honeywell Works Inc.

NOV 23 2017